This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

+ *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.

+ *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.

+ *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.

+ *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at `http://books.google.com/`

S 6552.98.6

GIFT OF

WENDELL TABER

HARVARD COLLEGE LIBRARY

PRINCIPLES

OF

GEOLOGY.



VIEW OF THE TEMPLE OF SERAPIS AT PUZZUOLI, IN 1836

PRINCIPLES

OF

GEOLOGY;

OR,

THE MODERN CHANGES OF THE EARTH AND ITS INHABITANTS

CONSIDERED AS ILLUSTRATIVE OF GEOLOGY.

BY SIR CHARLES LYELL, M.A. F.R.S.

VICE-PRESIDENT OF THE GEOLOGICAL SOCIETY OF LONDON;
AUTHOR OF "A MANUAL OF ELEMENTARY GEOLOGY," "TRAVELS IN NORTH AMERICA," "A SECOND VISIT TO THE UNITED STATES,"
ETC. ETC.

NINTH AND ENTIRELY REVISED EDITION.

Illustrated with Maps, Plates, and Woodcuts.

BOSTON:
LITTLE, BROWN, AND COMPANY.
1853.

~~Geol 388.53~~

S 6552.98.5

HARVARD COLLEGE
JUN 24 1926
LIBRARY

[illegible]

"Verè scire est per causas scire." — BACON.

"The stony rocks are not primeval, but the daughters of Time." — *Syst. Nat.* ed. 5. *Stockholm*, 1748, p. 219.

"Amid all the revolutions of the globe the economy of Nature has be and her laws are the only things that have resisted the general move rivers and the rocks, the seas and the continents have been changed parts; but the laws which direct those changes, and the rules to whi ubject, have remained invariably the same." — PLAYFAIR, *Illustrations tonian Theory*, § 374.

"The inhabitants of the globe, like all the other parts of it, are subject It is not only the individual that perishes but whole species.

"A change in the animal kingdom seems to be a part of the order of is visible in instances to which human power cannot have extended." — *Illustrations of the Huttonian Theory*, § 413.

PREFACE TO THE NINTH EDITION.

THE Principles of Geology in the first five editions embraced not only a view of the *modern changes* of the earth and its inhabitants, as set forth in the present work, but also some account of those monuments of analogous changes of *ancient* date, both in the organic and inorganic world, which it is the business of the geologist to interpret. The subject last mentioned, or "geology proper," constituted originally a fourth book, now omitted, the same having been enlarged into a separate treatise, first published in 1838, in one volume 12mo., and called "The Elements of Geology," afterwards recast in two volumes 12mo. in 1842, and again re-edited under the title of "Manual of Elementary Geology," in one volume 8vo. in 1851. The "Principles" and "Manual" thus divided, occupy, with one exception, to which I shall presently allude, very different ground. The "Principles" treat of such portions of the economy of existing nature, animate and inanimate, as are illustrative of Geology, so as to comprise an investigation of the permanent effects of causes now in action, which may serve as records to after ages of the present condition of the globe and its inhabitants. Such effects are the enduring monuments of the ever-varying state of the physical geography of the globe, the lasting signs of its destruction and renovation, and the memorials of the equally fluctuating condition of the organic world. They may be regarded, in short, as a symbolical language, in which the earth's autobiography is written.

In the "Manual of Elementary Geology," on the other hand, I have treated *briefly of the component* materials of the earth's crust, their arrangement and relative position, and their contents, which, when deciphered by aid of the key s by the study of the modern changes above alluded to, re us the annals of a grand succession of past events — a se revolutions which the solid exterior of the globe, and its inhabitants, have experienced in times antecedent to the c of man.

In thus separating the two works, however, I have re in the "Principles" (book i.) the discussion of some n which might fairly be regarded as common to both tre as for example, an historical sketch of the early progr geology, followed by a series of preliminary essays to e the facts and arguments which lead me to believe tha forces now operating upon and beneath the earth's surfac be the same, both in kind and degree, as those which at r epochs have worked out geological changes. (See Analy Contents of this work, p. ix.)

If I am asked whether the "Principles" or the "Ma should be studied first, I feel much the same difficult answering the question as if a student should inquire wh he ought to take up first a treatise on Chemistry, or on Natural Philosophy, subjects sufficiently distinct, yet inse bly connected. On the whole, while I have endeavour make each of the two treatises, in their present form, independent of the other, I would recommend the read study first the modern changes of the earth and its inhabi as they are discussed in the present volume, proceeding a wards to the classification and interpretation of the monum of more remote ages.

CHARLES LYEL

11. *Harley Street, London*, May 24. 1853.

Dates of the successive Editions of the "Principles" and "Elements" (or Manual) of Geology, by the Author.

◆

Principles, 1st vol. in octavo, published in	Jan. 1830.
———, 2d vol. do.	Jan. 1832.
———, 1st vol. 2d edition in octavo	1832.
———, 2d vol. 2d edition do.	Jan. 1833.
———, 3d vol. 1st edition do.	May 1833.
———, New edition (called the 3d) of the whole work in 4 vols. 12mo.	May 1834.
———, 4th edition, 4 vols. 12mo.	June 1835.
———, 5th do. do. do.	Mar. 1837.
Elements, 1st edition in one vol.	July 1838.
Principles, 6th do. 3 vols. 12mo.	June 1840.
Elements, 2d edition in 2 vols. 2 12mo.	July 1841.
Principles, 7th edition in one vol. 8vo.	Feb. 1847.
———, 8th edition in one vol. 8vo.	May 1850.
Manual of Elementary Geology (or "Elements," 3d edition) in one vol. 8vo.	Jan. 1851.
Manual, 4th edition, one vol. 8vo.	Jan. 1852.
Principles, 9th edition, now published in one vol. 8vo.	June 1853.

Works by Sir Charles Lyell.

I.

TRAVELS IN NORTH AMERICA,—1841-2. With Ge
Observations on the United States, Canada, and Nova Scotia. Wi
coloured geological Map and Plates. 2 vols. post 8vo. 21*s*.

II.

A SECOND VISIT TO THE UNITED STATES,— 1
Second Edition. 2 vols. post 8vo. 18*s*.

III.

PRINCIPLES OF GEOLOGY; or the Modern Changes
Earth and its Inhabitants considered, as illustrative of Geology. 9th
thoroughly revised. With Maps, Plates, and Woodcuts. 8vo. 18*s*.

IV.

A MANUAL OF ELEMENTARY GEOLOGY; o
Monuments of the ANCIENT CHANGES of the Earth and its Inh
4th Edition, *thoroughly revised.* With numerous Wood-cuts and Plate
12*s*.

ANALYSIS OF THE CONTENTS

OF

THE PRINCIPLES OF GEOLOGY.

BOOK I. (CHAPTERS I. to XIII.)

HISTORICAL SKETCH OF THE PROGRESS OF GEOLOGY, WITH A SERIES OF ESSAYS TO SHOW THAT THE MONUMENTS OF THE ANCIENT STATE OF THE EARTH AND ITS INHABITANTS, WHICH THIS SCIENCE INTERPRETS, CAN ONLY BE UNDERSTOOD BY A PREVIOUS ACQUAINTANCE WITH TERRESTRIAL CHANGES NOW IN PROGRESS, BOTH IN THE ORGANIC AND INORGANIC WORLDS.

CHAPTER I.

Geology defined — Its relation to other Sciences - - - - Page 1

CHAPTER II.

Oriental and Egyptian Cosmogonies — Doctrines of the Greeks and Romans bearing on Geology - - - - - - - - - - - 4

CHAPTER III.

Historical progress of Geology — Arabian writers — Italian, French, German, and English geologists before the nineteenth century — Physico-theological school. 17

CHAPTER IV.

Werner and Hutton — Modern progress of the science - - - - 46

CHAPTER V.

Prepossessions in regard to the duration of past time, and other causes which have retarded the progress of Geology - - - - - - - 61

CHAPTER VI.

Agreement of the ancient and modern course of nature considered — Changes of climate. 73

CHAPTERS VII. VIII.

Causes of vicissitudes in climate, and their connection with changes in physical geography - - - - - - - - - 92. 114

CHAPTER IX.

Theory of the progressive development of organic life at successive periods considered — Modern origin of Man - - - - - - - - 130

CHAPTER X.

Supposed intensity of aqueous forces at remote periods — Erratic blocks — D

CHAPTER XI.

Supposed former intensity of the igneous forces — Upheaval of land — Volc

CHAPTER XII.

Causes of the difference in texture of older and newer rocks—Plutonic and M action - - - - - - - - - -

CHAPTER XIII.

Supposed alternate periods of repose and disorder —Opposite doctrine, which logical phenomena to an uninterrupted series of changes in the organic and world, unattended with general catastrophes, or the development of p forces - - - - - - - - - -

---

BOOK II. (Chapters XIV. to XXXII.)

OBSERVED CHANGES IN THE INORGANIC WORLD NOW IN PROGRESS: FI EFFECTS OF AQUEOUS CAUSES, SUCH AS RIVERS, SPRINGS, GLACIERS, TIDES, AND CURRENTS; SECONDLY, OF IGNEOUS CAUSES, OR SUBTE HEAT, AS EXHIBITED IN THE VOLCANO AND THE EARTHQUAKE.

CHAPTER XIV.

Aqueous causes — Excavating and transporting power of rivers - -

CHAPTER XV.

Carrying power of river-ice — Glaciers and Icebergs - - -

CHAPTER XVI.

Phenomena of springs - - - - - - -

CHAPTER XVII.

Reproductive effects of rivers — Deltas of lakes and inland seas - -

CHAPTER XVIII.

Deltas of the Mississippi, Ganges, and other rivers exposed to tidal action -

CHAPTERS XIX. XX. XXI.

Denuding, transporting, and depositing agency of the waves, tides, and currents of sea-cliffs on the coast of England — Delta of the Rhine — Deposition of under the influence of marine currents - - - - 290.

CHAPTER XXII.

Observed effects of igneous causes — Regions of active volcanos - -

CHAPTERS XXIII. XXIV.

History of the volcanic eruptions of the district round Naples — Structure of — Herculaneum and Pompeii - - - - - -

CHAPTER XXV.

Etna—Its eruptions—Structure and antiquity of the cone - - Page 396

CHAPTER XXVI.

Volcanos of Iceland, Mexico, the Canaries, and Grecian archipelago—Mud volcanos. 424

CHAPTER XXVII.

Earthquakes and the permanent changes attending them - - - - 451

CHAPTER XXVIII.

Earthquake of 1783 in Calabria - - - - - - - 471

CHAPTER XXIX.

Elevation and subsidence of dry land, and of the bed of the sea during earthquakes—Evidence of the same afforded by the Temple of Serapis near Naples - - 493

CHAPTER XXX.

Elevation and subsidence of land in regions free from volcanos and earthquakes—Rising of land in Sweden - - - - - - - - 519

CHAPTERS XXXI. XXXII.

Causes of earthquakes and volcanos—Theory of central fluidity of the earth—Chemical theory of volcanos—Causes of permanent upheaval and depression of land 533. 545

BOOK III. (Chapters XXXIII. to L.)

OBSERVED CHANGES OF THE ORGANIC WORLD NOW IN PROGRESS: FIRST, NATURE AND GEOGRAPHICAL DISTRIBUTION OF SPECIES, AND THEORIES RESPECTING THEIR CREATION AND EXTINCTION; SECONDLY, THE INFLUENCE OF ORGANIC BEINGS IN MODIFYING PHYSICAL GEOGRAPHY; THIRDLY, THE LAWS ACCORDING TO WHICH THEY ARE IMBEDDED IN VOLCANIC, FRESHWATER, AND MARINE DEPOSITS.

CHAPTERS XXXIII. XXXIV. XXXV. XXXVI.

Whether species have a real existence in nature—Theory of transmutation of species—Variability of species—Phenomena of hybrids in animals and plants 566. 578. 591. 600

CHAPTER XXXVII.

Laws which regulate the geographical distribution of species—Distinct provinces of peculiar species of plants—Their mode of diffusion - - - - 612

CHAPTER XXXVIII.

Distinct provinces of peculiar species of animals—Distribution and despersion of quadrupeds, birds, and reptiles - - - - - - - 629

CHAPTER XXXIX.

Geographical distribution and migrations of fish—Of testacea—Of zoophytes—Of insects—Geographical distribution and diffusion of the human race - - - 646

CHAPTER XL.

Theories respecting the original introduction of species—Reciprocal influence of species on each other - - - - - - - - - 665

CHAPTERS XLI. XLII.

Extinction of species—How every extension of the range of a species alters
tion of many others—Effect of changes of climate - - Pag

CHAPTER XLIII.

Creation of species—Whether the loss of certain animals and plants is compa
the introduction of new species - - - - - -

CHAPTER XLIV.

Modifications in physical geography caused by organic beings - -

CHAPTER XLV.

Imbedding of organic remains in peat, blown sand, and volcanic ejections -

CHAPTER XLVI.

Imbedding of the same in alluvial deposits and in caves - - -

CHAPTER XLVII.

Imbedding of organic remains in aqueous deposits—Terrestrial plants—Insects
birds, quadrupeds - - - - - - -

CHAPTER XLVIII.

Imbedding of the remains of man and his works - - - -

CHAPTER XLIX.

Imbedding of aquatic animals and plants, both freshwater and marine, in aqueous

CHAPTER L.

Formation of coral reefs - - - - - - -

LIST OF PLATES.

DIRECTIONS TO THE BINDER.

Frontispiece, View of the Temple of Serapis at Puzzuoli in 1836,
titlepage.
Plate 1. Map showing the Area in Europe which has been covered by Wa
since the beginning of the Eocene Period - *to face*
2. Boulders drifted by Ice on the Shores of the St. Lawrence —
3. View looking up the Val del Bove, Etna - - —
4. View of the Val del Bove, Etna, as seen from above - —

PRINCIPLES OF GEOLOGY.

BOOK I.

CHAPTER I.

Geology defined — Compared to History — Its relation to other Physical Sciences — Not to be confounded with Cosmogony.

Geology is the science which investigates the successive changes that have taken place in the organic and inorganic kingdoms of nature; it inquires into the causes of these changes, and the influence which they have exerted in modifying the surface and external structure of our planet.

By these researches into the state of the earth and its inhabitants at former periods, we acquire a more perfect knowledge of its present condition, and more comprehensive views concerning the laws now governing its animate and inanimate productions. When we study *history*, we obtain a more profound insight into human nature, by instituting a comparison between the present and former states of society. We trace the long series of events which have gradually led to the actual posture of affairs; and by connecting effects with their causes, we are enabled to classify and retain in the memory a multitude of complicated relations—the various peculiarities of national character — the different degrees of moral and intellectual refinement, and numerous other circumstances, which, without historical associations, would be uninteresting or imperfectly understood. As the present condition of nations is the result of many antecedent changes, some extremely remote, and others recent, some gradual, others sudden and violent; so the state of the natural world is the result of a long succession of events; and if we would enlarge our experience of the present economy of nature, we must investigate the effects of her operations in former epochs.

We often discover with surprise, on looking back into the chronicles of nations, how the fortune of some battle has influenced the fate of millions of our contemporaries, when it has long been forgotten by the mass of the population. With this remote event we may find inseparably connected the geographical boundaries of a great state, the language now spoken by the inhabitants, their peculiar manners laws, and religious opinions. But far more astonishing expected are the connections brought to light, when we c our researches into the history of nature. The form of a configuration of the interior of a country, the existence and lakes, valleys, and mountains, can often be traced to the for valence of earthquakes and volcanos in regions which have undisturbed. To these remote convulsions the present f some districts, the sterile character of others, the elevatio above the sea, the climate, and various peculiarities, may be referred. On the other hand, many distinguishing featur surface may often be ascribed to the operation, at a re of slow and tranquil causes—to the gradual deposition of in a lake or in the ocean, or to the prolific increase of test corals.

To select another example, we find in certain localities sub deposits of coal, consisting of vegetable matter, formerly dri seas and lakes. These seas and lakes have since been fille lands whereon the forests grew have disappeared or chan form, the rivers and currents which floated the vegetable m no longer be traced, and the plants belonged to species which have passed away from the surface of our planet. Yet the co prosperity, and numerical strength of a nation, may now b dependent on the local distribution of fuel determined by tha state of things.

Geology is intimately related to almost all the physical sci history is to the moral. An historian should, if possible, b profoundly acquainted with ethics, politics, jurisprudence, the art, theology; in a word, with all branches of knowledge any insight into human affairs, or into the moral and int nature of man, can be obtained. It would be no less desirab geologist should be well versed in chemistry, natural phi mineralogy, zoology, comparative anatomy, botany; in s every science relating to organic and inorganic nature. W accomplishments, the historian and geologist would rarel draw correct and philosophical conclusions from the variou ments transmitted to them of former occurrences. They wou to what combination of causes analogous effects were refera they would often be enabled to supply, by inference, inf concerning many events unrecorded in the defective arc former ages. But as such extensive acquisitions are scarcel the reach of any individual, it is necessary that men who have their lives to different departments should unite their efforts; the historian receives assistance from the antiquary, and fro who have cultivated different branches of moral and political so the geologist should avail himself of the aid of many nat and particularly of those who have studied the fossil remain species of animals and plants.

The analogy, however, of the monuments consulted in and those available in history, extends no farther than to one historical monuments,—those which may be said to be *undesignedly* commemorative of former events. The canoes, for example, and stone hatchets found in our peat bogs, afford an insight into the rude arts and manners of the earliest inhabitants of our island; the buried coin fixes the date of the reign of some Roman emperor; the ancient encampment indicates the districts once occupied by invading armies, and the former method of constructing military defences: the Egyptian mummies throw light on the art of embalming, the rites of sepulture, or the average stature of the human race in ancient Egypt. This class of memorials yields to no other in authenticity, but it constitutes a small part only of the resources on which the historian relies, whereas in geology it forms the only kind of evidence which is at our command. For this reason we must not expect to obtain a full and connected account of any series of events beyond the reach of history. But the testimony of geological monuments, if frequently imperfect, possesses at least the advantage of being free from all intentional misrepresentation. We may be deceived in the inferences which we draw, in the same manner as we often mistake the nature and import of phenomena observed in the daily course of nature; but our liability to err is confined to the interpretation, and, if this be correct, our information is certain.

It was long before the distinct nature and legitimate objects of geology were fully recognized, and it was at first confounded with many other branches of inquiry, just as the limits of history, poetry, and mythology were ill-defined in the infancy of civilization. Even in Werner's time, or at the close of the eighteenth century, geology appears to have been regarded as little other than a subordinate department of mineralogy; and Desmarest included it under the head of Physical Geography. But the most common and serious source of confusion arose from the notion, that it was the business of geology to discover the mode in which the earth originated, or, as some imagined, to study the effects of those cosmological causes which were employed by the Author of Nature to bring this planet out of a nascent and chaotic state into a more perfect and habitable condition. Hutton was the first who endeavoured to draw a strong line of demarcation between his favourite science and cosmogony, for he declared that geology was in nowise concerned "with questions as to the origin of things."

An attempt will be made in the sequel of this work to demonstrate that geology differs as widely from cosmogony, as speculations concerning the mode of the first creation of man differ from history. But, before entering more at large on this controverted question, it will be desirable to trace the progress of opinion on this topic, from the earliest ages to the commencement of the present century.

CHAPTER II.

HISTORICAL SKETCH OF THE PROGRESS OF GEOLOGY

Oriental Cosmogony—Hymns of the Vedas—Institutes of Menù—I
the successive destruction and renovation of the world—Origin of th
—Common to the Egyptians—Adopted by the Greeks—System of
—of Aristotle—Dogmas concerning the extinction and reproduction
and species—Strabo's theory of elevation by earthquakes—Pliny—
Remarks on the knowledge of the Ancients.

Oriental Cosmogony.—THE earliest doctrines of the In
Egyptian schools of philosophy agreed in ascribing the first
of the world to an omnipotent and infinite Being. They c
also in representing this Being, who had existed from all ete
having repeatedly destroyed and reproduced the world an
inhabitants. In the sacred volume of the Hindoos, called t
nances of Menù, comprising the Indian system of duties relig
civil, we find a preliminary chapter treating of the Creation,
the cosmogony is known to have been derived from earlier
and traditions; and principally from certain hymns of high a
called the Vedas. These hymns were first put together acc
Mr. Colebrooke[*], in a connected series, about thirteen centuri
the Christian era, but they appear from internal evidence
been written at various antecedent periods. In them, as
from the researches of Professor Wilson, the eminent Sanscrit
two distinct philosophical systems are discoverable. Acco
one of them, all things were originally brought into existenc
sole will of a single First Cause, which existed from etern
cording to the other, there have always existed two principles
material, but without form, the other spiritual and capable
pelling "inert matter to develope its sensible properties.'
development of matter into "individual and visible existe
called creation, and is assigned to a subordinate agent, or the
faculty of the Supreme Being embodied in the person of Brah

In the first chapter of the Ordinances of Menù above allud
meet with the following passages relating to former destructi
renovations of the world:—

"The Being, whose powers are incomprehensible, having
me (Menù) and this universe, again became absorbed in the
spirit, changing the time of energy for the hour of repose.

"When that Power awakes, then has this world its full exp
but when he slumbers with a tranquil spirit, then the whole

---

[*] Essays on the Philosophy of the Hindoos.

fades away. . . . . For while he reposes, as it were, embodied spirits endowed with principles of action depart from their several acts, and the mind itself becomes inert."

The absorption of all beings into the Supreme essence is then described, and the Divine soul itself is said to slumber, and to remain for a time immersed in "the first idea, or in darkness." After which the text thus proceeds (verse fifty-seven), "Thus that immutable power by waking and reposing alternately, revivifies and destroys, in eternal succession, this whole assemblage of locomotive and immovable creatures.

It is then declared that there has been a long succession of *manwantaras*, or periods, each of the duration of many thousand ages, and—

"There are creations also, and destructions of worlds innumerable: the Being, supremely exalted, performs all this with as much ease as if in sport, again and again, for the sake of conferring happiness."*

No part of the Eastern cosmogony, from which these extracts are made, is more interesting to the geologist than the doctrine, so frequently alluded to, of the reiterated submersion of the land beneath the waters of an universal ocean. In the beginning of things, we are told, the First Sole Cause "with a thought created the waters," and then moved upon their surface in the form of Brahma the creator, by whose agency the emergence of the dry land was effected, and the peopling of the earth with plants, animals, celestial creatures, and man. Afterwards, as often as a general conflagration at the close of each manwantara had annihilated every visible and existing thing, Brahma, on awaking from his sleep, finds the whole world a shapeless ocean. Accordingly, in the legendary poems called the Puranas, composed at a later date than the Vedas, the three first Avatars or descents of the Deity upon earth have for their object to recover the land from the waters. For this purpose Vishnu is made successively to assume the form of a fish, a tortoise, and a boar.

Extravagant as may be some of the conceits and fictions which disfigure these pretended revelations, we can by no means look upon them as a pure effort of the unassisted imagination, or believe them to have been composed without regard to opinions and theories founded on the observation of Nature. In astronomy, for instance, it is declared that, at the North Pole, the year was divided into a long day and night, and that their long day was the northern, and their night the southern course of the sun; and to the inhabitants of the moon, it is said one day is equal in length to one month of mortals.† If such statements cannot be resolved into mere conjectures, we have no right to refer to mere chance the prevailing notion that the earth and its inhabitants had formerly undergone a succe revolutions and aqueous catastrophes interrupted by long i of tranquillity.

---

* Institutes of Hindoo Law, or the Ordinances of Menù, from the Sanscrit, translated by Sir William Jones, 1796.

† Menù, Inst. c. i. 66, and 67.

Now there are two sources in which such a theory m originated. The marks of former convulsions on every par surface of our planet are obvious and striking. The rer marine animals imbedded in the solid strata are so abunda they may be expected to force themselves on the attention c people who have made some progress in refinement; and es where one class of men are expressly set apart from the rest, ancient priesthoods of India and Egypt, for study and contem If these appearances are once recognized, it seems natural t mind should conclude in favour, not only of mighty changes ages, but of alternate periods of repose and disorder;—of when the animals now fossil lived, grew and multiplied—of d when the strata in which they were buried became transferr the sea to the interior of continents, and were uplifted so as part of high mountain-chains. Those modern writers, who posed to disparage the former intellectual advancement and civi of Eastern nations, may concede some foundation of observed f the curious theories now under consideration, without indul exaggerated opinions of the progress of science; especially as u catastrophes of the world, and exterminations of organic bei the sense in which they were understood by the Brahmins, tenable doctrines.

We know that the Egyptian priests were aware, not on the soil beneath the plains of the Nile, but that also the hills b the great valley, contained marine shells; and Herodotus i from these facts, that all lower Egypt, and even the high land Memphis had once been covered by the sea.* As simila remains occur in all parts of Asia hitherto explored, far interior of the continent as well as near the sea, they could have escaped detection by some Eastern sages not less than the Greek historian of reasoning philosophically on phenomena.

We also know that the rulers of Asia were engaged in very eras in executing great national works, such as tanks and requiring extensive excavations. In the fourteenth century era, (in the year 1360,) the removal of soil necessary for such takings brought to light geological facts, which attracted the at of a people less civilized than were many of the older nations East. The historian Ferishta relates that fifty thousand lab were employed in cutting through a mound, so as to form a ju between the rivers Selima and Sutlej; and in this mound were the bones of elephants and men, some of them petrified, and a them resembling bone. The gigantic dimensions attributed human bones show them to have belonged to some of the larger pachydermata.*

---

* Herodot. Euterpe, 12.

But although the Brahmins, like the priests of Egypt, may have been acquainted with the existence of fossil remains in the strata, it is possible that the doctrine of successive destructions and renovations of the world, merely received corroboration from such proofs; and that it may have been originally handed down, like the religious traditions of most nations, from a ruder state of society. The system may have had its source, in part at least, in exaggerated accounts of those dreadful catastrophes, which are occasioned by particular combinations of natural causes. Floods and volcanic eruptions, the agency of water and fire, are the chief instruments of devastation on our globe. We shall point out in the sequel the extent of many of these calamities, recurring at distant intervals of time, in the present course of nature; and shall only observe here, that they are so peculiarly calculated to inspire a lasting terror, and are so often fatal in their consequences to great multitudes of people, that it scarcely requires the passion for the marvellous, so characteristic of rude and half-civilized nations, still less the exuberant imagination of Eastern writers, to augment them into general cataclysms and conflagrations.

The great flood of the Chinese, which their traditions carry back to the period of Yaou, something more than 2000 years before our era, has been identified by some persons with the universal deluge described in the Old Testament; but according to Mr. Davis, who accompanied two of our embassies to China, and who has carefully examined their written accounts, the Chinese cataclysm is therein described as interrupting the business of agriculture, rather than as involving a general destruction of the human race. The great Yu was celebrated for having "opened nine channels to draw off the waters," which "covered the low hills and bathed the foot of the highest mountains." Mr. Davis suggests that a great derangement of waters of the Yellow River, one of the largest in the world, might even now cause the flood of Yaou to be repeated, and lay the most fertile and populous plains of China under water. In modern times the bursting of the banks of an artificial canal, into which a portion of the Yellow River has been turned, has repeatedly given rise to the most dreadful accidents, and is a source of perpetual anxiety to the government. It is easy, therefore, to imagine how much greater may have been the inundation, if this valley was ever convulsed by a violent earthquake.†

Humboldt relates the interesting fact that, after the annihilation of a large part of the inhabitants of Cumana, by an earthquake in 1766, a season of extraordinary fertility ensued, in consequence of the great rains which accompanied the subterranean convulsions. Indians," he says, "celebrated, after the ideas of an antiqu stition, by festivals and dancing, the destruction of the world approaching epoch of its regeneration."*

---

* A Persian MS. copy of the historian Ferishta, in the library of the East India Company, relating to the rise and progress of the Mahomedan empire in India, was procured by Colonel Briggs from the library of Tippoo Sultan in 1799; which has been referred to at some length by Dr. Buckland. (Geol. Trans. 2d Series, vol. ii. part iii. p. 389.)

† See Davis on "The Chinese," published by the Soc. for the Diffus. of Use. Know. vol. i. pp. 137. 147.

The existence of such rites among the rude nations o America is most important, as showing what effects may be p by local catastrophes, recurring at distant intervals of time minds of a barbarous and uncultivated race. I shall point ou sequel how the tradition of a deluge among the Araucanian may be explained, by reference to great earthquake-waves have repeatedly rolled over part of Chili since the first r flood of 1590. (See chap. 29. Book II.). The legend also of the Peruvians of an inundation many years before the reign of th in which only six persons were saved on a float, relates to which has more than once been overwhelmed by inroads of th since the days of Pizarro (Chap. 29. Book II.). I might refer th to my account of the submergence of a wide area in Cutch s as the year 1819, when a single tower only of the fort of appeared above the waste of waters (see Chap. 28. Book II.), if necessary, to prove how easily the catastrophes of moder might give rise to traditionary narratives, among a rude pe floods of boundless extent. Nations without written recor who are indebted for all their knowledge of past events excl to oral tradition, are in the habit of confounding in one legend of incidents which have happened at various epochs; nor m forget that the superstitions of a savage tribe are transmitted t all the progressive stages of society, till they exert a powerful ence on the mind of the philosopher. He may find, in the mon of former changes on the earth's surface, an apparent confirma tenets handed down through successive generations, from th hunter, whose terrified imagination drew a false picture of those visitations of floods and earthquakes, whereby the whole ea known to him was simultaneously devastated.

Egyptian Cosmogony.—Respecting the cosmogony of the Eg priests, we gather much information from writers of the Grecian who borrowed almost all their tenets from Egypt, and amongst that of the former successive destruction and renovation o world.† We learn from Plutarch, that this was the theme of the hymns of Orpheus, so celebrated in the fabulous ages of G It was brought by him from the banks of the Nile; and we eve in his verses, as in the Indian systems, a definite period assign the duration of each successive world.‡ The returns of great trophes were determined by the period of the Annus Magn great year,—a cycle composed of the revolutions of the sun, and planets, and terminating when these return together to the sign whence they were supposed at some remote epoch to have set out. The duration of this great cycle was variously estimated. According to Orpheus, it was 120,000 years; according to others, 300,000; and by Cassander it was taken to be 360,000 years.*

---

* Humboldt et Bonpland, Voy. Relat. Hist. vol. i. p. 30.

† Prichard's Egypt. Mythol. p. 177.

‡ Plut. de Defectu Oraculoru 12. Censorinus de Die Natali also Prichard's Egypt. Mythol. p.

We learn particularly from the Timæus of Plato, that the Egyptians believed the world to be subject to occasional conflagrations and deluges, whereby the gods arrested the career of human wickedness, and purified the earth from guilt. After each regeneration, mankind were in a state of virtue and happiness, from which they gradually degenerated again into vice and immorality. From this Egyptian doctrine, the poets derived the fable of the decline from the golden to the iron age. The sect of Stoics adopted most fully the system of catastrophes destined at certain intervals to destroy the world. Those they taught were of two kinds;—the Cataclysm or destruction by water, which sweeps away the whole human race, and annihilates all the animal and vegetable productions of nature; and the Ecpyrosis, or destruction by fire, which dissolves the globe itself. From the Egyptians also they derived the doctrine of the gradual debasement of man from a state of innocence. Towards the termination of each era the gods could no longer bear with the wickedness of men, and a shock of the elements or a deluge overwhelmed them; after which calamity, Astrea again descended on the earth, to renew the golden age.†

The connection between the doctrine of successive catastrophes and repeated deteriorations in the moral character of the human race is more intimate and natural than might at first be imagined. For, in a rude state of society, all great calamities are regarded by the people as judgments of God on the wickedness of man. Thus in our own time, the priests persuaded a large part of the population of Chili, and perhaps believed themselves, that the fatal earthquake of 1822 was a sign of the wrath of Heaven for the great political revolution just then consummated in South America. In like manner, in the account given to Solon by the Egyptian priests, of the submersion of the island of Atlantis under the waters of the ocean, after repeated shocks of an earthquake, we find that the event happened when Jupiter had seen the moral depravity of the inhabitants.‡ Now, when the notion had once gained ground, whether from causes before suggested or not, that the earth had been destroyed by several general catastrophes, it would next be inferred that the human race had been as often destroyed and renovated. And since every extermination was assumed to be penal, it could only be reconciled with divine justice, by the supposition that man, at each successive creation, was regenerated in a state of purity and innocence.

A very large portion of Asia, inhabited by the earliest nations whose traditions have come down to us, has been always subject to tremendous earthquakes. Of the geographical boundaries of these, and their effects, I shall speak in the proper place. Egypt has, for the most part, been exempt from this scourge, and the Egypti trine of great catastrophes was probably derived in part, as hinted, from early geological observations, and in part from : nations.

---

* Prichard's Egypt. Mythol. p. 182.

† Ibid. p. 193.

‡ Plato's Timæus.

Pythagorean Doctrines.—Pythagoras, who resided for mo twenty years in Egypt, and according to Cicero, had visited th and conversed with the Persian philosophers, introduced into l country, on his return, the doctrine of the gradual deteriora the human race from an original state of virtue and happine if we are to judge of his theory concerning the destructi renovation of the earth from the sketch given by Ovid, w concede it to have been far more philosophical than any version of the cosmogonies of Oriental or Egyptian sects.

Although Pythagoras is introduced by the poet as deliver doctrine in person, some of the illustrations are derived from events which happened after the death of the philosophe notwithstanding these anachronisms, we may regard the acco a true picture of the tenets of the Pythagorean school in the Au age; and although perhaps partially modified, it must have co the substance of the original scheme. Thus considered, it tremely curious and instructive; for we here find a compreh summary of almost all the great causes of change now in acti the globe, and these adduced in confirmation of a principle of petual and gradual revolution inherent in the nature of our ter system. These doctrines, it is true, are not directly applied explanation of geological phenomena; or, in other words, no a is made to estimate what may have been in past ages, or wh hereafter be, the aggregate amount of change brought about b never-ending fluctuations. Had this been the case, we migh been called upon to admire so extraordinary an anticipation w less interest than astronomers, when they endeavour to det what means the Samian philosopher came to the knowledge Copernican system.

Let us now examine the celebrated passages to which we hav adverting *: —

"Nothing perishes in this world; but things merely var change their form. To be born, means simply that a thing beg be something different from what it was before; and dyi ceasing to be the same thing. Yet, although nothing retains lo same image, the sum of the whole remains constant." These g propositions are then confirmed by a series of examples, all d from natural appearances, except the first, which refers to the g age giving place to the age of iron. The illustrations are consecutively adduced.

1. Solid land has been converted into sea.
2. Sea has been changed into land. Marine shells lie far d from the deep, and the anchor has been found on the summit of

---

* Ovid's Metamor. lib. 15.

3. Valleys have been excavated by running water, and floods have washed down hills into the sea.[*]

4. Marshes have become dry ground.

5. Dry lands have been changed into stagnant pools.

6. During earthquakes some springs have been closed up, and new ones have broken out. Rivers have deserted their channels, and have been re-born elsewhere; as the Erasinus in Greece, and Mysus in Asia.

7. The waters of some rivers, formerly sweet, have become bitter; as those of the Anigris in Greece, &c.[†]

8. Islands have become connected with the main land by the growth of deltas and new deposits; as in the case of Antissa joined to Lesbos, Pharos to Egypt, &c.

9. Peninsulas have been divided from the main land, and have become islands, as Leucadia; and according to tradition Sicily, the sea having carried away the isthmus.

10. Land has been submerged by earthquakes; the Grecian cities of Helice and Buris, for example, are to be seen under the sea, with their walls inclined.

11. Plains have been upheaved into hills by the confined air seeking vent, as at Trœzene in the Peloponnesus.

12. The temperature of some springs varies at different periods. The waters of others are inflammable.[‡]

13. There are streams which have a petrifying power, and convert the substances which they touch into marble.

14. Extraordinary medicinal and deleterious effects are produced by the water of different lakes and springs.[§]

15. Some rocks and islands, after floating and having been subject to violent movements, have at length become stationary and immoveable, as Delos, and the Cyanean Isles.[‖]

16. Volcanic vents shift their position; there was a time when Etna was not a burning mountain, and the time will come when it will cease to burn. Whether it be that some caverns become closed up by the movements of the earth, and others opened, or whether the fuel is finally exhausted, &c. &c.

---

[*] Eluvie mons est deductus in æquor, v. 267. The meaning of this last verse is somewhat obscure; but taken with the context, may be supposed to allude to the abrading power of floods, torrents, and rivers.

[†] The impregnation from new mineral springs, caused by earthquakes in volcanic countries, is perhaps here alluded to.

[‡] That is probably an allusion to the escape of inflammable gas, like that in the district of Baku, west of the Caspian; at Pietramala, in the Tuscan Apennines; and several other places.

[§] Many of those described seem fanciful fictions, like the virtue still so commonly attributed to mineral waters.

[‖] Raspe, in a learned and judicious essay (De Novis Insulis, cap. 19), has made it appear extremely probable that all the traditions of certain islands in the Mediterranean having at some former time frequently shifted their positions, and at length become stationary, originated in the great change produced in their form by earthquakes and submarine eruptions, of which there have been modern examples in the new islands raised in the time of history. When the series of convulsions ended, the island was said to become fixed.

The various causes of change in the inanimate world having
thus enumerated, the doctrine of equivocal generation is nex
pounded, as illustrating a corresponding perpetual flux in the an
creation.*

In the Egyptian and Eastern cosmogonies, and in the Greek ve
of them, no very definite meaning can, in general, be attached t
term "destruction of the world;" for sometimes it would seem a
to imply the annihilation of our planetary system, and at others a
revolution of the surface of the earth.

Opinions of Aristotle.—From the works now extant of Ari
and from the system of Pythagoras, as above exposed, we
certainly infer that these philosophers considered the agents of c
now operating in nature, as capable of bringing about in the la
ages a complete revolution; and the Stagyrite even considers
sional catastrophes, happening at distant intervals of time, as p
the regular and ordinary course of nature. The deluge of Deuc
he says, affected Greece only, and principally the part called H
and it arose from great inundations of rivers during a rainy w
But such extraordinary winters, he says, though after a certain p
they return, do not always revisit the same places.†

Censorinus quotes it as Aristotle's opinion, that there were g
inundations of the globe, and that they alternated with conflagra
and that the flood constituted the winter of the great year, or
nomical cycle, while the conflagration, or destruction by fire,
summer or period of greatest heat.‡ If this passage, as Lipsiu
poses, be an amplification, by Censorinus, of what is written in
Meteorics," it is a gross misrepresentation of the doctrine o
Stagyrite, for the general bearing of his reasoning in that tr
tends clearly in an opposite direction. He refers to many exa
of changes now constantly going on, and insists emphatically o
great results which they must produce in the lapse of ages. H
stances particular cases of lakes that had dried up, and desert
had at length become watered by rivers and fertilized. He poi
the growth of the Nilotic Delta since the time of Homer, to the
shoaling of the Palus Mæotis within sixty years from his own
and although, in the same chapter, he says nothing of earthqu
yet in others of the same treatise he shows himself not unacqu

---

* It is not inconsistent with the Hindoo mythology to suppose that Pythagoras might have found in the East not only the system of universal and violent catastrophes and periods of repose in endless succession, but also that of periodical revolutions, effected by the continual agency of ordinary causes. For Brahma, Vishnu, and Siva, the first, second, and third persons of the Hindoo triad, severally represented the Creative, the Preserving, and the Destroying powers of the Deity. The coexistence of these three attributes, all in
simultaneous operation, might well acco
the notion of perpetual but parti
revolutions finally bringing about a c
change. But the fiction expres
verses before quoted from M
eternal vicissitudes in the vig
slumbers of Brahma seems accom
to the system of great general cata
followed by new creations and p
repose.

† Meteor. lib. i. cap. 12.

‡ De Die Nat.

with their effects.* He alludes, for example, to the upheaving of one of the Eolian islands previous to a volcanic eruption. "The changes of the earth," he says, "are so slow in comparison to the duration of our lives, that they are overlooked (λανθανει); and the migrations of people after great catastrophes and their removal to other regions, cause the event to be forgotten."†

When we consider the acquaintance displayed by Aristotle, in his various works, with the destroying and renovating powers of Nature, the introductory and concluding passages of the twelfth chapter of his "Meteorics" are certainly very remarkable. In the first sentence he says, "The distribution of land and sea in particular regions does not endure throughout all time, but it becomes sea in those parts where it was land, and again it becomes land where it was sea: and there is reason for thinking that these changes take place according to a certain system, and within a certain period." The concluding observation is as follows:—"As time never fails, and the universe is eternal, neither the Tànais, nor the Nile, can have flowed for ever. The places where they rise were once dry, and there is a limit to their operations; but there is none to time. So also of all other rivers; they spring up, and they perish; and the sea also continually deserts some lands and invades others. The same tracts, therefore, of the earth are not, some always sea, and others always continents, but every thing changes in the course of time."

It seems, then, that the Greeks had not only derived from preceding nations, but had also, in some slight degree, deduced from their own observations, the theory of periodical revolutions in the inorganic world: there is, however, no ground for imagining that they contemplated former changes in the races of animals and plants. Even the fact that marine remains were enclosed in solid rocks, although observed by some, and even made the groundwork of geological speculation, never stimulated the industry or guided the inquiries of naturalists. It is not impossible that the theory of equivocal generation might have engendered some indifference on this subject, and that a belief in the spontaneous production of living beings from the earth or corrupt matter, might have caused the organic world to appear so unstable and fluctuating, that phenomena indicative of former changes would not awaken intense curiosity. The Egyptians, it is true, had taught, and the Stoics had repeated, that the earth had once given birth to some monstrous animals, which existed no longer; but the prevailing opinion seems to have been, that after each great catastrophe the same species of animals were created over again. This tenet is implied in a passage of Seneca, where, speaking of a future deluge, he says, "Every animal shall be generated anew, and man free from guilt shall be given to the earth."‡

An old Arabian version of the doctrine of the successive revolutions of the globe, translated by Abraham Ecchellensis[*], seer form a singular exception to the general rule, for here we fi idea of different genera and species having been created. The banites, a sect of astronomers who flourished some centuries l the Christian era, taught as follows:—"That after every per thirty-six thousand four hundred and twenty-five years, there produced a pair of *every* species of animal, both male and fe from whom animals might be propagated and inhabit this lower v But when a circulation of the heavenly orbs was completed, wh finished in that space of years, *other genera and species* of an are propagated, as also of plants and other things, and the first is destroyed, and so it goes on for ever and ever."[†]

---

* Lib. ii. cap. 14, 15, and 16.

† Lib. ii. cap. 14, 15, and 16.

‡ Omne ex integro animal generabitur, dabiturque terris homo inscius scelerum. —Quæst. Nat. iii. c. 29.

Theory of Strabo.—As we learn much of the tenets of the l tian and Oriental schools in the writings of the Greeks, so, speculations of the early Greek authors are made known to the works of the Augustan and later ages. Strabo, in parti enters largely, in the second book of his Geography, into the opi of Eratosthenes and other Greeks on one of the most difficult blems in geology, viz. by what causes marine shells came to be tifully buried in the earth at such great elevations and dist from the sea.

He notices, amongst others, the explanation of Xanthus the Ly who said that the seas had once been more extensive, and that had afterwards been partially dried up, as in his own time many rivers, and wells in Asia had failed during a season of drc Treating this conjecture with merited disregard, Strabo passes the hypothesis of Strato, the natural philosopher, who had obs that the quantity of mud brought down by rivers into the E was so great, that its bed must be gradually raised, while the r still continue to pour in an undiminished quantity of water. therefore, conceived that, originally, when the Euxine was an i sea, its level had by this means become so much elevated tl burst its barrier near Byzantium, and formed a communication the Propontis; and this partial drainage, he supposed, had al converted the left side into marshy ground, and thus, at last whole would be choked up with soil. So, it was argued, the Mediterranean had once opened a passage for itself by the Columns of Hercules into the Atlantic; and perhaps the abundance of sea-shells in Africa, near the Temple of Jupiter Ammon, might also be the deposit of some former inland sea, which had at length forced a passage and escaped.

---

[*] This author was Regius Professor of Syriac and Arabic at Paris, where, in 1685, he published a Latin translation of many Arabian MSS. on different departments of philosophy. This work has always been considered of high authority.

[†] Gerbanitæ docebant singulos triginta sex mille annos quadringentos, viginti quinque bina ex singulis animalium speciebus produci, marem scilicet ac feminam ex quibus animalia propagantur, huncque inferiorem incolunt orbem. Absolutâ autem cœlestium orbium circulatione, quæ illo annorum conficitur spatio, iterum alia producuntur animalium genera et species, quemadmodum et plantarum aliarumque rerum, et primus destruitur ordo, sicque in infinitun ducitur. — Histor. Orient. Supp Abrahamum Ecchellensem, Syrur ronitam, cap. 7. et 8. ad calcem Cl Orientali. Parisiis, e Typ. Regia. fol.

I have given the punctuation as Paris edition, there being no c after quinque; but, at the sugges M. de Schlegel, I have referre number twenty-five to the period of and not to the number of pairs o species created at one time, as I ha in the two first editions. Fortis ir that twenty-five new *species* onl created at a time; a construction the passage will not admit. Mé l'Hist. Nat. de l'Italie, vol. i. p. 20

But Strabo rejects this theory, as insufficient to account for all the phenomena, and he proposes one of his own, the profoundness of which modern geologists are only beginning to appreciate. "It is not," he says, "because the lands covered by seas were originally at different altitudes, that the waters have risen, or subsided, or receded from some parts and inundated others. But the reason is, that the same land is sometimes raised up and sometimes depressed, and the sea also is simultaneously raised and depressed, so that it either overflows or returns into its own place again. We must, therefore, ascribe the cause to the ground, either to that ground which is under the sea, or to that which becomes flooded by it, but rather to that which lies beneath the sea, for this is more moveable and, on account of its humidity, can be altered with greater celerity.* *It is proper,*" he observes in continuation, "*to derive our explanations from things which are obvious, and in some measure of daily occurrence, such as deluges, earthquakes, and volcanic eruptions*†, *and sudden swellings of the land beneath the sea;* for the last raise up the sea also; and when the same lands subside again, they occasion the sea to be let down. And it is not merely the small, but the large islands also, and not merely the islands, but the continents which can be lifted up together with the sea; and both large and small tracts may subside, for habitations and cities, like Bure, Bizona, and many others, have been engulphed by earthquakes."

In another place, this learned geographer, in alluding to the tradition that Sicily had been separated by a convulsion from Italy, remarks, that at present the land near the sea in those parts was rarely shaken by earthquakes, since there were now open orifices whereby fire and ignited matters, and waters escape; but formerly, when the volcanos of Etna, the Lipari Islands, Ischia, and others, were closed up, the imprisoned fire and wind might have produced far more vehement movements.‡ The doctrine, therefore, that volcanos are safety-valves, and that the subterranean convulsions are probably most violent when first the volcanic energy shifts itself to a new quarter, is not modern.

---

* "Quod enim hoc attollitur aut subsidit, et vel inundat quædam loca, vel ab iis recedit, ejus rei causa non est, quod alia aliis sola humiliora sint aut altiora; sed quod idem solum modò attollitur modò deprimitur, simulque etiam modò attollitur modò deprimitur, mare: itaque vel exundat vel in suum redit locum."

Postea, p. 88. "Restat, ut causam adscribamus solo, sive quod mari subest sive quod inundatur; potiùs tamen ei quod mari subest. Hoc enim multò est mobilius, et quod ob humiditatem celeriùs multari possit." — Strabo, Geog. Edit. Almelov. Amst. 1707. lib. i.

† *Volcanic eruptions*, eruptiones flatuum, in the Latin translations, and in the original Greek, αναφυσηματα, gaseous eruptions? or *inflations* of land? — Ibid. p. 93.

‡ Strabo, lib. vi. p. 396.

[illegible]

[illegible] of man.

[illegible] made for the [illegible] examples [illegible] But they had nev[illegible] and [illegible] living species of anim[illegible] conditions of the [illegible] elements and positions of [illegible] and made some prop[illegible] and mineral kingdoms: [illegible] sealed book, and [illegible] striking and imposing ki[illegible]

CHAPTER III.

HISTORY OF THE PROGRESS OF GEOLOGY—*continued.*

Arabian writers of the tenth century—Avicenna—Omar—Cosmogony of the Koran—Kazwini—Early Italian writers—Leonardo da Vinci—Fracastoro—Controversy as to the real nature of fossils—Attributed to the Mosaic deluge—Palissy—Steno—Scilla—Quirini—Boyle—Lister—Leibnitz—Hooke's Theory of Elevation by Earthquakes—Of lost species of animals—Ray—Physico-theological writers—Woodward's Diluvial Theory—Burnet—Whiston—Vallisneri—Lazzaro Moro—Generelli—Buffon—His theory condemned by the Sorbonne as unorthodox—His declaration—Targioni—Arduino—Michell—Catcott—Raspe—Fuchsel—Fortis—Testa—Whitehurst—Pallas—Saussure.

Arabian writers.—After the decline of the Roman empire, the cultivation of physical science was first revived with some success by the Saracens, about the middle of the eighth century of our era. The works of the most eminent classic writers were purchased at great xpense from the Christians, and translated into Arabic; and Al amûn, son of the famous Harûn-al-Rashid, the contemporary of harlemagne, received with marks of distinction, at his court at agdad, astronomers and men of learning from different countries. his caliph, and some of his successors, encountered much opposition d jealousy from the doctors of the Mahometan law, who wished the oslems to confine their studies to the Koran, dreading the effects of e diffusion of a taste for the physical sciences.[*]

Avicenna.—Almost all the works of the early Arabian writers are st. Amongst those of the tenth century, of which fragments are w extant, is a short treatise, "On the Formation and Classification Minerals," by Avicenna, a physician, in whose arrangement there is nsiderable merit. The second chapter, "On the Cause of Mountains," remarkable; for mountains, he says, are formed, some by essential, hers by accidental causes. In illustration of the essential, he instances "a violent earthquake, by which land is elevated, and becomes mountain;" of the accidental, the principal, he says, is excavation y water, whereby cavities are produced, and adjoining lands made to and out and form eminences.[†]

Omar—Cosmogony of the Koran.—In the same century also, mar, surnamed "El Aalem," or "The Learned," wrote a work on The Retreat of the Sea." It appears that on comparing the charts

---

[*] Mod. Univ. Hist. vol. ii. chap. iv. ction iii.

[†] Montes quandóque fiunt ex causa sentiali, quandóque ex causa accidentali. Ex essentiali causa, ut ex vehementi motu terræ elevatur terra, et fit mons. Accidentali, &c.—De Congelatione Lapidum, ed. Gedani, 1682.

of his own time with those made by the Indian and Persian as
mers two thousand years before, he had satisfied himself that i
ant changes had taken place since the times of history in th
of the coasts of Asia, and that the extension of the sea had
greater at some former periods. He was confirmed in this opin
the numerous salt springs and marshes in the interior of As
phenomenon from which Pallas, in more recent times, has draw
same inference.

Von Hoff has suggested, with great probability, that the ch
in the level of the Caspian (some of which there is reason to b
have happened within the historical era), and the geologic
pearances in that district, indicating the desertion by that sea
ancient bed, had probably led Omar to his theory of a genera
sidence. But whatever may have been the proofs relied on, his t
was declared contradictory to certain passages in the Koran, a
was called upon publicly to recant his errors; to avoid whic
secution he went into voluntary banishment from Samarkand.*

The cosmological opinions expressed in the Koran are few
merely introduced incidentally: so that it is not easy to unde
how they could have interfered so seriously with free discuss
the former changes of the globe. The Prophet declares that the
was created in two days, and the mountains were then placed
and during these, and two additional days, the inhabitants of the
were formed; and in two more the seven heavens.† There
more detail of circumstances; and the deluge, which is also ment
is discussed with equal brevity. The waters are represented t
poured out of an oven; a strange fable, said to be borrowed fr
Persian Magi, who represented them as issuing from the oven
old woman.‡ All men were drowned, save Noah and his famil
then God said, "O earth, swallow up thy waters; and thou, O h
withhold thy rain;" and immediately the waters abated.§

We may suppose Omar to have represented the desertion
land by the sea to have been gradual, and that his hypothesis re
a greater lapse of ages than was consistent with Moslem ortho
for it is to be inferred from the Koran, that man and this plane
created at the same time; and although Mahomet did not lin
pressly the antiquity of the human race, yet he gave an i

---

* Von Hoff, Geschichte der Veränderungen der Erdoberfläche, vol. i. p. 406., who cites Delisle, bey Hismann Welt-und Völkergeschichte. Alte Geschichte 1ter theil, s. 234.—The Arabian persecutions for heretical dogmas in theology were often very sanguinary. In the same ages wherein learning was most in esteem, the Mahometans were divided into two sects, one of whom maintained that the Koran was increate, and had subsisted in the very essence of God from all eternity; and the other, the Motazalites, who, admitting that the Koran was instituted by God, conceived it to have been first ma
revealed to the Prophet at Mec
accused their opponents of belie
two eternal beings. The opinions
of these sects were taken up by c
caliphs in succession, and the foll
each sometimes submitted to be be
or flogged till at the point of deat
than renounce their creed.—Mo
Hist. vol. ii. ch. iv.

† Koran, chap. xli.

‡ Sale's Koran, chap. xi. see n

§ Ibid.

sanction to the Mosaic chronology, by the veneration expressed by him for the Hebrew Patriarchs.*

A manuscript work, entitled the "Wonders of Nature," is preserved in the Royal Library at Paris, by an Arabian writer, Mohammed Kazwini, who flourished in the seventh century of the Hegira, or at the close of the thirteenth century of our era.† Besides several curious remarks on aerolites, earthquakes, and the successive changes of position which the land and sea have undergone, we meet with the following beautiful passage which is given as the narrative of Kidhz, an allegorical personage:—"I passed one day by a very ancient and wonderfully populous city, and asked one of its inhabitants how long it had been founded. 'It is indeed a mighty city,' replied he; 'we know not how long it has existed, and our ancestors were on this subject as ignorant as ourselves.' Five centuries afterwards, as I passed by the same place, I could not perceive the slightest vestige of the city. I demanded of a peasant, who was gathering herbs upon its former site, how long it had been destroyed. 'In sooth a strange question!' replied he. 'The ground here has never been different from what you now behold it.'—'Was there not of old,' said I, 'a splendid city here?'—'Never,' answered he, 'so far as we have seen, and never did our fathers speak to us of any such.' On my return there 500 years afterwards, *I found the sea in the same place*, and on its shores were a party of fishermen, of whom I inquired how long the land had been covered by the waters? 'Is this a question,' said they, 'for a man like you? this spot has always been what it is now.' I again returned, 500 years afterwards, and the sea had disappeared; I inquired of a man who stood alone upon the spot, how long ago this change had taken place, and he gave me the same answer as I had received before. Lastly, on coming back again after an equal lapse of time, I found there a flourishing city, more populous and more rich in beautiful buildings, than the city I had seen the first time, and when I would fain have informed myself concerning its origin, the inhabitants answered me, 'Its rise is lost in remote antiquity: we are ignorant how long it has existed, and our fathers were on this subject as ignorant as ourselves.'"

Early Italian writers.—It was not till the earlier part of the sixteenth century that geological phenomena began to attract the attention of the Christian nations. At that period a very animated controversy sprang up in Italy, concerning the true nature and origin of marine shells, and other organized fossils, found abundantly in the strata of the peninsula. The celebrated painter Leonardo da Vinci, who in his youth had planned and executed some navigable canals in the north of Italy, was one of the first who applied sound reasoning to these subjects. The mud of rivers, he said, had covered and penetrated into the in-

---

* Kossa, appointed master to the Caliph Al Mamûd, was author of a book entitled "The history of the Patriarchs and Prophets, *from the Creation of the World*."—Mod. Univ. Hist. vol. ii. ch. iv.

† Translated by MM. Chezy and De Sacy, and cited by M. Elie de Beaumont, Ann. des Sci. Nat. 1832.

terior of fossil shells at a time when these were still at the bot
the sea near the coast. "They tell us that these shells were
in the hills by the influence of the stars; but I ask where in t
are the stars now forming shells of distinct ages and species? a
can the stars explain the origin of gravel, occurring at different
and composed of pebbles rounded as if by the motion of r
water; or in what manner can such a cause account for the
faction in the same places of various leaves, sea-weeds, and
crabs?" *

The excavations made in 1517, for repairing the city of
brought to light a multitude of curious petrifactions, and fu
matter for speculation to different authors, and among the
Fracastoro †, who declared his opinion, that fossil shells
belonged to living animals, which had formerly lived and mu
where their exuviæ are now found. He exposed the absur
having recourse to a certain "plastic force," which it was s
power to fashion stones into organic forms; and with no less
arguments, demonstrated the futility of attributing the situatio
shells in question to the Mosaic deluge, a theory obstinately d
by some. That inundation, he observed, was too transient;
sisted principally of fluviatile waters; and if it had transporte
to great distances, must have strewed them over the surfa
buried them at vast depths in the interior of mountains. H
exposition of the evidence would have terminated the discus
ever, if the passions of mankind had not been enlisted in the d
and even though doubts should for a time have remained i
minds, they would speedily have been removed by the fresh i
tion obtained almost immediately afterwards, respecting the st
of fossil remains, and of their living analogues.

But the clear and philosophical views of Fracastoro we
regarded, and the talent and argumentative powers of the
were doomed for three centuries to be wasted in the discu
these two simple and preliminary questions; first, whethe
remains had ever belonged to living creatures; and, secondly, w
if this be admitted, all the phenomena could not be explained
deluge of Noah. It had been the general belief of the C
world down to the period now under consideration, that the o
this planet was not more remote than a few thousand years; a
since the creation the deluge was the only great catastrophe b
considerable change had been wrought on the earth's surfac
the other hand, the opinion was scarcely less general, that t
dissolution of our system was an event to be looked for at no
period. The era, it is true, of the expected millennium had

---

* See Venturi's extracts from Da Vinci's MSS. now in Library of Institute of France. They are not mentioned by Brocchi, and my attention was first called to them by Mr. Hallam. L. da Vinci died A.D. 1519.

† Museum Calceol. — See
Discourse on the Progress of the
Fossil Conchology in Italy, wher
the following notices on Italia
will be found more at large.

away; and for five hundred years after the fatal hour when the annihilation of the planet had been looked for, the monks remained in undisturbed enjoyment of rich grants of land bequeathed to them by pious donors, who, in the preamble of deeds beginning "appropinquante mundi termino"——"appropinquante magno judicii die," left lasting monuments of the popular delusion.*

But although in the sixteenth century it had become necessary to interpret certain prophecies respecting the millennium more liberally, and to assign a more distant date to the future conflagration of the world, we find, in the speculations of the early geologists, perpetual allusion to such an approaching catastrophe; while in all that regarded the antiquity of the earth, no modification whatever of the opinions of the dark ages had been effected. Considerable alarm was at first excited when the attempt was made to invalidate, by physical proofs, an article of faith so generally received; but there was sufficient spirit of toleration and candour amongst the Italian ecclesiastics, to allow the subject to be canvassed with much freedom. They even entered warmly into the controversy themselves, often favouring different sides of the question; and however much we may deplore the loss of time and labour devoted to the defence of untenable positions, it must be conceded that they displayed far less polemic bitterness than certain writers who followed them "beyond the Alps," two centuries and a half later.

CONTROVERSY AS TO THE REAL NATURE OF FOSSIL ORGANIC REMAINS.

Mattioli—Falloppio.—The system of scholastic disputations, encouraged in the universities of the middle ages, had unfortunately trained men to habits of indefinite argumentation; and they often preferred absurd and extravagant propositions, because greater skill was required to maintain them; the end and object of these intellectual combats being victory, and not truth. No theory could be so far-fetched or fantastical as not to attract some followers, provided it fell in with popular notions; and as cosmogonists were not at all restricted, in building their systems, to the agency of known causes, the opponents of Fracastoro met his arguments by feigning imaginary causes, which differed from each other rather in name than in substance. Andrea Mattioli, for instance, an eminent botanist, the illustrator of Dioscorides, embraced the notion of Agricola, a skilful German miner, that a certain "materia pinguis," or "fatty matter," set into fermentation by heat, gave birth to fossil organic shapes. Yet Mattioli had come to the conclusion, from his own observations, that porous bodies, such as bones and shells, might be converted into stone, as being permeable to what he termed the "lapidifying juice." In like manner, Falloppio of Padua conceived that petrified shells were generated by fermentation in the spots where they are found, (they had in some cases acquired their form from "the tumu movements of terrestrial exhalations." Although celebrated professor of anatomy, he taught that certain tusks of elephant up in his time in Apulia, were mere earthy concretions; and sistently with these principles, he even went so far as to co it probable, that the vases of Monte Testaceo at Rome were r impressions stamped in the soil.* In the same spirit, Mercat published, in 1574, faithful figures of the fossil shells preserv Pope Sixtus V. in the Museum of the Vatican, expressed an o that they were mere stones, which had assumed their p configuration from the influence of the heavenly bodies: and C Cremona, who described the fossil remains of a rich muse Verona, was satisfied with considering them as mere "sp nature."

---

* In Sicily, in particular, the title-deeds of many valuable grants of land to the monasteries are headed by such preambles, composed by the testators about the period when the good King Roger was expelling the Saracens from that island.

Some of the fanciful notions of those times were deeme unreasonable, as being somewhat in harmony with the Arist theory of spontaneous generation, then taught in all the sch For men who had been taught in early youth, that a large prop of living animals and plants was formed from the fortuitou course of atoms, or had sprung from the corruption of organic m might easily persuade themselves, that organic shapes, often fectly preserved in the interior of solid rocks, owed their exist causes equally obscure and mysterious.

Cardano, 1552.—But there were not wanting some who, the progress of this century, expressed more sound and sober op The title of a work of Cardano's, published in 1552, "De Subti (corresponding to what would now be called Transcendental sophy), would lead us to expect, in the chapter on minerals, far-fetched theories characteristic of that age; but when trea petrified shells, he decided that they clearly indicated the sojourn of the sea upon the mountains.‡

Cesalpino—Majoli, 1597.—Cesalpino, a celebrated botani ceived that fossil shells had been left on the land by the retiri and had concreted into stone during the consolidation of the and in the following year (1597), Simeone Majoli ‖ went still f and, coinciding for the most part with the views of Ces suggested that the shells and submarine matter of the Verone other districts, might have been cast up upon the land by v explosions, like those which gave rise, in 1538, to Monte near Puzzuoli. This hint seems to have been the first im attempt to connect the position of fossil shells with the ag volcanos, a system afterwards more fully developed by Lazzaro Moro, Hutton, and other writers.

---

* De Fossilib. pp. 109. and 176.

† Aristotle, On Animals, chapters 1. and 15.

‡ Brocchi, Con. Fos. Subap. : Progressi. vol. i. p. 57.

§ De Metallicis.

‖ Dies Caniculares.

Two years afterwards, Imperati advocated the animal origin of fossilized shells, yet admitted that stones could vegetate by force of "an internal principle;" and, as evidence of this, he referred to the teeth of fish and spines of echini found petrified.[*]

Palissy, 1580.—Palissy, a French writer on "The Origin of Springs from Rain-water," and of other scientific works, undertook, in 1580, to combat the notions of many of his contemporaries in Italy, that petrified shells had all been deposited by the universal deluge. "He was the first," said Fontenelle, when, in the French Academy, he pronounced his eulogy, nearly a century and a half later, "who dared assert," in Paris, that fossil remains of testacea and fish had once belonged to marine animals.

Fabio Colonna.—To enumerate the multitude of Italian writers, who advanced various hypotheses, all equally fantastical, in the early part of the seventeenth century, would be unprofitably tedious; but Fabio Colonna deserves to be distinguished; for, although he gave way to the dogma, that all fossil remains were to be referred to the deluge of Noah, he resisted the absurd theory of Stelluti, who taught that fossil wood and ammonites were mere clay, altered into such forms by sulphureous waters and subterranean heat; and he pointed out the different states of shells buried in the strata, distinguishing between, first, the mere mould or impression; secondly, the cast or nucleus; and, thirdly, the remains of the shell itself. He had also the merit of being the first to point out, that some of the fossils had belonged to marine and some to terrestrial testacea.[†]

Steno, 1669.—But the most remarkable work of that period was published by Steno, a Dane, once professor of anatomy at Padua, and who afterwards resided many years at the court of the Grand Duke of Tuscany. His treatise bears the quaint title of "De Solido intra Solidum naturaliter contento (1669)," by which the author intended to express, "On Gems, Crystals, and organic Petrifactions inclosed within solid Rocks." This work attests the priority of the Italian school in geological research; exemplifying at the same time the powerful obstacles opposed, in that age, to the general reception of enlarged views in the science. It was still a favourite dogma, that the fossil remains of shells and marine creatures were not of animal origin; an opinion adhered to by many from their extreme reluctance to believe, that the earth could have been inhabited by living beings before a great part of the existing mountains were formed. In reference to this controversy, Steno had dissected a shark recently taken from the Mediterranean, and had demonstrated that its teeth and bones were identical with many fossils found in Tuscany. He had also compared the shells discovered in the Italian strata with living species, pointed out their resemblance, and traced the various gradations from shells merely calcined, or which had only lost their animal gluten, to those petrifactions in which there was a perfect substitution of stony matter. In his division of mineral masses, he insisted on the secondary origin of those deposits in which th of animals or fragments of older rocks were inclosed. He guished between marine formations and those of a fluviatile cha the last containing reeds, grasses, or the trunks and branches o He argued in favour of the original horizontality of sediment posits, attributing their present inclined and vertical positio times to the escape of subterranean vapours heaving the crust earth from below upwards, and sometimes to the falling in of overlying subterranean cavities.

---

[*] Storia Naturale.

[†] Osserv. sugli Animali aquat. e terrest. 1626.

He declared that he had obtained proof that Tuscany must sively have acquired six distinct configurations, having bee covered by water, twice laid dry with a level, and twice with gular and uneven surface.* He displayed great anxiety to re his new views with Scripture, for which purpose he pointed tain rocks as having been formed before the existence of anim plants: selecting unfortunately as examples certain formati limestone and sandstone in his own country, now known to c though sparingly, the remains of animals and plants,—strata do not even rank as the oldest part of our secondary series. suggested that Moses, when speaking of the loftiest mount having been covered by the deluge, meant merely the loftiest hills then existing, which may not have been very high. diluvian waters, he supposed, may have issued from the int the earth into which they had retired, when in the beginni land was separated from the sea. These, and other hypoth the same subject, are not calculated to enhance the value treatise, and could scarcely fail to detract from the authority o opinions which were sound and legitimate deductions from fa observation. They have served, nevertheless, as the germs of popular theories of later times, and in an expanded form hav put forth as original inventions by some of our contemporaries

Scilla, 1670.—Scilla, a Sicilian painter, published, in 1 treatise, in Latin, on the fossils of Calabria, illustrated b engravings. This work proves the continued ascendancy of often refuted; for we find the wit and eloquence of the author directed against the obstinate incredulity of naturalists as organic nature of fossil shells.† Like many eminent natural his day, Scilla gave way to the popular persuasion, that all shells were the effects and proofs of the Mosaic deluge. It doubted whether he was perfectly sincere, and some of his c poraries who took the same course were certainly not so. eager were they to root out what they justly considered an prejudice respecting the nature of organized fossils, that they s have been ready to make any concessions, in order to establish this preliminary point. Such a compromising policy was short-sighted, since it was to little purpose that the nature of the documents should at length be correctly understood, if men were to be prevented from deducing fair conclusions from them.

---

* Sex itaque distinctas Etruriæ facies agnoscimus, dum bis fluida, bis plana, et sicca, bis aspera fuerit, &c.

† Scilla quotes the remark of Cicero on the story that a stone in Chios had been cleft open, and presented the head of Paniscus in relief:—"I believe the orator, "that the figure bor resemblance to Paniscus, but n that you would have deemed it scu by Scopas; for chance never p ites the truth."

Diluvial Theory.—The theologians who now entered the field in Italy, Germany, France, and England, were innumerable; and henceforward, they who refused to subscribe to the position, that all marine organic remains were proofs of the Mosaic deluge, were exposed to the imputation of disbelieving the whole of the sacred writings. Scarcely any step had been made in approximating to sound theories since the time of Fracastoro, more than a hundred years having been lost, in writing down the dogma that organized fossils were mere sports of nature. An additional period of a century and a half was now destined to be consumed in exploding the hypothesis, that organized fossils had all been buried in the solid strata by Noah's flood. Never did a theoretical fallacy, in any branch of science, interfere more seriously with accurate observation and the systematic classification of facts. In recent times, we may attribute our rapid progress chiefly to the careful determination of the order of succession in mineral masses, by means of their different organic contents, and their regular superposition. But the old diluvialists were induced by their system to confound all the groups of strata together instead of discriminating,—to refer all appearances to one cause and to one brief period, not to a variety of causes acting throughout a long succession of epochs. They saw the phenomena only as they desired to see them, sometimes misrepresenting facts, and at other times deducing false conclusions from correct data. Under the influence of such prejudices, three centuries were of as little avail as a few years in our own times, when we are no longer required to propel the vessel against the force of an adverse current.

It may be well, therefore, to forewarn the reader, that in tracing the history of geology from the close of the seventeenth to the end of the eighteenth century, he must expect to be occupied with accounts of the retardation, as well as of the advance, of the science. It will be necessary to point out the frequent revival of exploded errors, and the relapse from sound to the most absurd opinions; and to dwell on futile reasoning and visionary hypothesis, because some of the most extravagant systems were invented or controverted by men of acknowledged talent. In short, a sketch of the progress of geology is the history of a constant and violent struggle of new opinions against doctrines sanctioned by the implicit faith of many generations, and supposed to rest on scriptural authority. The inquiry, therefore, although highly interesting to one who studies the philosophy of the human mind, is too often barren of instruction to him who searches for truths in physical science.

Quirini, 1676.—Quirini, in 1676*, contended, in opposition to Scilla, that the diluvian waters could not have conveyed heavy bodies to the summit of mountains, since the agitation of the sea neve Boyle had demonstrated) extended to great depths*; and still could the testacea, as some pretended, have lived in these dilu waters; for "the duration of the flood was brief, and *the heavy* *must have destroyed the saltness of the sea!*" He was the writer who ventured to maintain that the universality of Mosaic cataclysm ought not to be insisted upon. As to the n of petrified shells, he conceived that as earthy particles united i sea to form the shells of mollusca, the same crystallizing pr might be effected on the land; and that, in the latter case, the g of the animals might have been disseminated through the subs of the rocks, and afterwards developed by virtue of humi Visionary as was this doctrine, it gained many proselytes amongst the more sober reasoners of Italy and Germany; f conceded that the position of fossil bodies could not be accounte by the diluvial theory.

---

* De Testaceis fossilibus Mus. Septaliani.

Plot—Lister, 1678.—In the mean time, the doctrine that shells had never belonged to real animals maintained its grou England, where the agitation of the question began at a much period. Dr. Plot, in his "Natural History of Oxfordshire" (1 attributed to a "plastic virtue latent in the earth" the orig fossil shells and fishes; and Lister, to his accurate account of B shells, in 1678, added the fossil species, under the appellati *turbinated and bivalve stones.* "Either," said he, "these were ginous, or, if otherwise, the animals they so exactly represent *become extinct.*" This writer appears to have been the first wh aware of the continuity over large districts of the principal gro strata in the British series, and who proposed the constructi regular geological maps.†

Leibnitz, 1680.—The great mathematician Leibnitz publishe "Protogæa" in 1680. He imagined this planet to have been orig a burning luminous mass, which ever since its creation has undergoing refrigeration. When the outer crust had cooled sufficiently to allow the vapours to be condensed, they fell formed a universal ocean, covering the loftiest mountains, and i ing the whole globe. The crust, as it consolidated from a st fusion, assumed a vesicular and cavernous structure; and bein in some places, allowed the water to rush into the subterr hollows, whereby the level of the primeval ocean was lowered. breaking in of these vast caverns is supposed to have given the dislocated and deranged position of the strata "which Steno had described," and the same disruptions communicated violent movements to the incumbent waters, whence great inundations ensued. The waters, after they had been thus agitated, deposited their sedimentary matter during intervals of quiescence, and hence the various stony and earthy strata. "We may recognise, therefore," says Leibnitz, "a double origin of primitive masses, the one by refrigeration from igneous fusion, the other by concretion from aqueous solution."* By the repetition of similar causes (the disruption of the crust and consequent floods), alternations of new strata were produced until at length these causes were reduced to a condition of quiescent equilibrium, and a more permanent state of things was established.†

---

* The opinion of Boyle, alluded to in the [illegible] [illegible] [illegible] of the Sea.' [illegible] [illegible] [illegible] [illegible] not high above the surface of the water, [illegible] [illegible] even during heavy gales of wind, the motion of the water was exce diminished at the depth of tw [illegible] He had also learn [illegible] that the [illegible] di [illegible]—Boyle's Wo [illegible] London, 1744.

† See Conybeare and Phillips' [illegible] the Geology of Englan Wales,' p. [illegible]

Hooke, 1688. — The "Posthumous Works of Robert Hooke, M.D.," well known as a great mathematician and natural philosopher, appeared in 1705, containing "A Discourse of Earthquakes," which, we are informed by his editor, was written in 1668, but revised at subsequent periods.‡ Hooke frequently refers to the best Italian and English authors who wrote before his time on geological subjects; but there are no passages in his works implying that he participated in the enlarged views of Steno and Lister, or of his contemporary, Woodward, in regard to the geographical extent of certain groups of strata. His treatise, however, is the most philosophical production of that age, in regard to the causes of former changes in the organic and inorganic kingdoms of nature.

"However trivial a thing," he says, "a rotten shell may appear to some, yet these monuments of nature are more certain tokens of antiquity than coins or medals, since the best of those may be counterfeited or made by art and design, as may also books, manuscripts, and inscriptions, as all the learned are now sufficiently satisfied has often been actually practised," &c.; "and though it must be granted that it is very difficult to read them (the records of nature) and *to raise a chronology out of them*, and to state the intervals of the time wherein such or such catastrophes and mutations have happened, yet it is not impossible." §

Respecting the extinction of species, Hooke was aware that the fossil ammonites, nautili, and many other shells and fossil skeletons found in England, were of different species from any then known; but he doubted whether the species had become extinct, observing that the knowledge of naturalists of all the marine species, especially those

---

* Unde jam duplex origo intelligitur primorum corporum, una, cum ab ignis fusione refrigescerent, altera, cum reconcrescerent ex solutione aquarum.

† Redeunte mox simili causâ strata subinde alia aliis imponerentur, et facies teneri adhuc orbis sæpius novata est. Donec quiescentibus causis, atque æquilibratis, consistentior emergeret rerum status. — For an able analysis of the views of Leibnitz, in his Protogæa, see Mr. Conybeare's Report to the Brit. Assoc. on the Progress of Geological Science, 1832.

‡ Between the year 1688 and his death, in 1703, he read several memoirs to the Royal Society, and delivered lectures on various subjects, relating to fossil remains and the effects of earthquakes.

§ Posth. Works, Lecture, Feb. 29. 1688.

inhabiting the deep sea, was very deficient. In some parts o
writings, however, he leans to the opinion that species had been l
and in speculating on this subject, he even suggests that there m
be some connection between the disappearance of certain kin
animals and plants, and the changes wrought by earthquakes in fo
ages. Some species, he observes, with great sagacity, are "*pec*
to certain places, and not to be found elsewhere. If, then, su
place had been swallowed up, it is not improbable but that t
animate beings may have been destroyed with it; and this ma
true both of aërial and aquatic animals: for those animated bo
whether vegetables or animals, which were naturally nourished o
freshed by the air, would be destroyed by the water," &c.* Tu
he adds, and such large ammonites as are found in Portland, see
have been the productions of hotter countries; and it is necessa
suppose that England once lay under the sea within the torrid
To explain this and similar phenomena, he indulges in a varie
speculations concerning changes in the position of the axis o
earth's rotation, "a shifting of the earth's centre of gravity, anal
to the revolutions of the magnetic pole," &c. None of these co
tures, however, are proposed dogmatically, but rather in the ho
promoting fresh inquiries and experiments.

In opposition to the prejudices of his age, we find him ar
against the idea that nature had formed fossil bodies "for no othe
than to play the mimic in the mineral kingdom;"—maintaining
figured stones were "really the several bodies they represent, o
mouldings of them petrified," and "not as some have imagine
lusus naturæ,' sporting herself in the needless formation of u
beings."†

It was objected to Hooke, that his doctrine of the extincti
species derogated from the wisdom and power of the Omnip
Creator; but he answered, that, as individuals die, there may be
termination to the duration of a species; and his opinions, he dec
were not repugnant to Holy Writ: for the Scriptures taught
our system was degenerating, and tending to its final dissolu
"and as, when that shall happen, all the species will be lost, wh
some at one time and some at another?"‡

---

* Posth. Works, p. 327.

† Posth. Works, Lecture, Feb. 15. 1688. Hooke explained with considerable clearness, the different modes wherein organic substances may become lapidified; and, among other illustrations, he mentions some silicified palm-wood brought from Africa, on which M. de la Hire had read a memoir to the Royal Academy of France (June, 1692), wherein he had pointed out, not only the tubes running the length of the trunk, but the roots at one extremity. De la Hire, says Hooke, also treated of certain trees found petrified in the "river that passes by Bakan, in the kingdom of *Ava*, and
which has for the space of ten l
the virtue of petrifying wood." I
interesting fact that the silicified
of the Irawadi should have attrac
tention more than one hundred yea
Remarkable discoveries have been
there in later times of fossil anim
vegetables, by Mr. Crawfurd a
Wallich.—See Geol. Trans. vol.
iii. p. 377. second series. De l
cites Father Duchatz, in the
volume of "Observations made
Indies by the Jesuits."

‡ Posth. Works, Lecture, M
1689.

But his principal object was to account for the manner in which shells had been conveyed into the higher parts of "the Alps, Apennines, and Pyrenean hills, and the interior of continents in general." These and other appearances, he said, might have been brought about by earthquakes, "which have turned plains into mountains, and mountains into plains, seas into land, and land into seas, made rivers where there were none before, and swallowed up others that formerly were, &c. &c.; and which, since the creation of the world, have wrought many great changes on the superficial parts of the earth, and have been the instruments of placing shells, bones, plants, fishes, and the like, in those places where, with much astonishment, we find them."[*] This doctrine, it is true, had been laid down in terms almost equally explicit by Strabo, to explain the occurrence of fossil shells in the interior of continents, and to that geographer, and other writers of antiquity, Hooke frequently refers; but the revival and development of the system was an important step in the progress of modern science.

Hooke enumerated all the examples known to him of subterranean disturbance, from "the sad catastrophe of Sodom and Gomorrah," down to the Chilian earthquake of 1646. The elevating of the bottom of the sea, the sinking and submersion of the land, and most of the inequalities of the earth's surface, might, he said, be accounted for by the agency of these subterranean causes. He mentions that the coast near Naples *was raised during the eruption of Monte Nuovo;* and that, in 1591, land rose in the island of St. Michael, during an eruption: and although it would be more difficult, he says, to prove, he does not doubt but that there had been as many earthquakes in the parts of the earth under the ocean, as in the parts of the dry land; in confirmation of which, he mentions the immeasurable depth of the sea near some volcanos. To attest the extent of simultaneous subterranean movements, he refers to an earthquake in the West Indies, in the year 1690, where the space of earth raised, or "struck upwards," by the shock, exceeded, he affirms, the length of the Alps and Pyrenees.

Hooke's diluvial theory.—As Hooke declared the favorite hypothesis of the day, "that marine fossil bodies were to be referred to Noah's flood," to be wholly untenable, he appears to have felt himself called upon to substitute a diluvial theory of his own, and thus he became involved in countless difficulties and contradictions. "During the great catastrophe," he said, "there might have been a changing of that part which was before dry land into sea by sinking, and of that which was sea into dry land by raising, and marine bodies might have been buried in sediment beneath the ocean, in the interval between the creation and the deluge."[†] Then follows a disquisition on the separation of the land from the waters, mentioned in Genesis; during which operation some places of the shell of the earth were forced outwards, and others pressed downwards or inwards, &c. His diluvial hypothesis very much resembled that of Steno, and was entirely opposed to the fundamental principles professed by him, that he explain the former changes of the earth *in a more natural* than others had done. When, in despite of this declaratio required a former "crisis of nature," and taught that earthq had become debilitated, and that the Alps, Andes, and other c had been lifted up in a few months, he was compelled to a so rapid a rate of change, that his machinery appeared scarce extravagant than that of his most fanciful predecessors. Fo reason, perhaps, his whole theory of earthquakes met with served neglect.

---

[*] Posth. Works, p. 312.

[†] Posth. Works, p. 410.

Ray, 1692.—One of his contemporaries, the celebrated natu Ray, participated in the same desire to explain geological phen by reference to causes less hypothetical than those usually re to.* In his essay on "Chaos and Creation," he proposed a s agreeing in its outline, and in many of its details, with that of H but his knowledge of natural history enabled him to elucida subject with various original observations. Earthquakes, he gested, might have been the second causes employed at the creati separating the land from the waters, and in gathering the together into one place. He mentions, like Hooke, the earth of 1646, which had violently shaken the Andes for some hundr leagues, and made many alterations therein. In assigning a for the general deluge, he preferred a change in the earth's ce gravity to the introduction of earthquakes. Some unknown he said, might have forced the subterranean waters outwards, a perhaps, indicated by "the breaking up of the fountains of the deep."

Ray was one of the first of our writers who enlarged up effects of running water upon the land, and of the encroachm the sea upon the shores. So important did he consider the age these causes, that he saw in them an indication of the tendency system to its final dissolution; and he wondered why the ear not proceed more rapidly towards a general submersion bene sea, when so much matter was carried down by rivers, or unde in the sea-cliffs. We perceive clearly from his writings, th gradual decline of our system, and its future consummation was held to be as necessary an article of faith by the ortho was the recent origin of our planet. His discourses, like t Hooke, are highly interesting, as attesting the familiar associa the minds of philosophers, in the age of Newton, of questi physics and divinity. Ray gave an unequivocal proof of the si of his mind, by sacrificing his preferment in the church, rathe take an oath against the Covenanters, which he could not re with his conscience. His reputation, moreover, in the sc world placed him high above the temptation of courting popu by pandering to the physico-theological taste of his age. It is, therefore, curious to meet with so many citations from the Christian fathers and prophets in his essays on physical science—to find him in one page proceeding, by the strict rules of induction, to explain the former changes of the globe, and in the next gravely entertaining the question, whether the sun and stars, and the whole heavens, shall be annihilated, together with the earth, at the era of the grand conflagration.

---

* Ray's Physico-theological Discourses were of somewhat later date than Hooke's great work on earthquakes. He speaks of Hooke as one "whom for his learning and deep insight into the mys nature he deservedly honoured *the Deluge*, chap. iv.

Woodward, 1695.—Among the contemporaries of Hooke and Ray, Woodward, a professor of medicine, had acquired the most extensive information respecting the geological structure of the crust of the earth. He had examined many parts of the British strata with minute attention; and his systematic collection of specimens, bequeathed to the University of Cambridge, and still preserved there as arranged by him, shows how far he had advanced in ascertaining the order of superposition. From the great number of facts collected by him, we might have expected his theoretical views to be more sound and enlarged than those of his contemporaries; but in his anxiety to accommodate all observed phenomena to the scriptural account of the Creation and Deluge, he arrived at most erroneous results. He conceived "the whole terrestrial globe to have been taken to pieces and dissolved at the flood, and the strata to have settled down from this promiscuous mass as any earthy sediment from a fluid."* In corroboration of these views he insisted upon the fact, that "marine bodies are lodged in the strata according to the order of their gravity, the heavier shells in stone, the lighter in chalk, and so of the rest."† Ray immediately exposed the unfounded nature of this assertion, remarking truly that fossil bodies "are often mingled, heavy with light, in the same stratum;" and he even went so far as to say, that Woodward "must have invented the phenomena for the sake of confirming his bold and strange hypothesis"‡—a strong expression from the pen of a contemporary.

Burnet, 1690.—At the same time Burnet published his "Theory of the Earth."§ The title is most characteristic of the age,—"The Sacred Theory of the Earth; containing an Account of the Original of the Earth, and of all the general Changes which it hath already undergone, or is to undergo, till the Consummation of all Things." Even Milton had scarcely ventured in his poem to indulge his imagination so freely in painting scenes of the Creation and Deluge, Paradise and Chaos. He explained why the primeval earth enjoyed a perpetual spring before the flood! showed how the crust of the globe was fissured by "the sun's rays," so that it burst, and thus the diluvial waters were let loose from a supposed central abyss. Not satisfied with these themes, he derived from the books of the inspired writers, and even from heathen authorities, prophetic views of the future revolutions of the globe, gave a most terrific descriptio general conflagration, and proved that a new heaven and a ne will rise out of a *second chaos*—after which will follow the millennium.

---

* Essay towards a Natural History of the Earth, 1695. Preface.

† Ibid.

‡ Consequences of the Deluge, p. 165.

§ First published in Latin between the years 1680 and 1690.

The reader should be informed, that, according to the opi many respectable writers of that age, there was good scri ground for presuming that the garden bestowed upon our first p was not on the earth itself, but above the clouds, in the middle between our planet and the moon. Burnet approaches with bec gravity the discussion of so important a topic. He was willi concede that the geographical position of Paradise was not in potamia, yet he maintained that it was upon the earth, and southern hemisphere, near the equinoctial line. Butler select conceit as a fair mark for his satire, when, amongst the nu accomplishments of Hudibras, he says,—

> "He knew the seat of Paradise,
> Could tell in what degree it lies;
> And, as he was disposed, could prove it
> Below the moon, or else above it."

Yet the same monarch, who is said never to have slept Butler's poem under his pillow, was so great an admirer and of Burnet's book, that he ordered it to be translated from the into English. The style of the "Sacred Theory" was eloque the book displayed powers of invention of no ordinary stan was, in fact, a fine historical romance, as Buffon afterwar clared: but it was treated as a work of profound science time of its author, and was panegyrized by Addison in a Lat while Steele praised it in the "Spectator."

Whiston, 1696.—Another production of the same scho equally characteristic of the time, was that of Whiston, entitl New Theory of the Earth; wherein the Creation of the W Six Days, the Universal Deluge, and the General Conflagra laid down in the Holy Scriptures, are shown to be perfectly able to Reason and Philosophy." He was at first a follo Burnet; but his faith in the infallibility of that writer was by the declared opinion of Newton, that there was every presu in astronomy against any former change in the inclination earth's axis. This was a leading dogma in Burnet's system, not original, for it was borrowed from an Italian, Alessandr Alessandri, who had suggested it in the beginning of the fi century, to account for the former occupation of the presen nents by the sea. La Place has since strengthened the argun Newton, against the probability of any former revolution kind.

The remarkable comet of 1680 was fresh in the memory o one when Whiston first began his cosmological studies; principal novelty of his speculations consisted in attributi deluge to the near approach to the earth of one of these erratic

Having ascribed an increase of the waters to this source, he adopted Woodward's theory, supposing all stratified deposits to have resulted from the "chaotic sediment of the flood." Whiston was one of the first who ventured to propose that the text of Genesis should be interpreted differently from its ordinary acceptation, so that the doctrine of the earth having existed long previous to the creation of man might no longer be regarded as unorthodox. He had the art to throw an air of plausibility over the most improbable parts of his theory, and seemed to be proceeding in the most sober manner, and, by the aid of mathematical demonstration, to the establishment of his various propositions. Locke pronounced a panegyric on his theory, commending him for having explained so many wonderful and before inexplicable things. His book, as well as Burnet's, was attacked and refuted by Keill.* Like all who introduced purely hypothetical causes to account for natural phenomena, Whiston retarded the progress of truth, diverting men from the investigation of the laws of sublunary nature, and inducing them to waste time in speculations on the power of comets to drag the waters of the ocean over the land —on the condensation of the vapours of their tails into water, and other matters equally edifying.

Hutchinson, 1724.—John Hutchinson, who had been employed by Woodward in making his collection of fossils, published afterwards, in 1724, the first part of his "Moses's Principia," wherein he ridiculed Woodward's hypothesis. He and his numerous followers were accustomed to declaim loudly against human learning; and they maintained that the Hebrew Scriptures, when rightly translated, comprised a perfect system of natural philosophy, for which reason they objected to the Newtonian theory of gravitation.

Celsius.—Andrea Celsius, the Swedish astronomer, published about this time his remarks on the gradual diminution and sinking of the waters in the Baltic, to which I shall have occasion to advert more particularly in the sequel (ch. 29.).

Scheuchzer, 1708.—In Germany, in the mean time, Scheuchzer published his "Complaint and Vindication of the Fishes" (1708), "Piscium Querelæ et Vindiciæ," a work of zoological merit, in which he gave some good plates and descriptions of fossil fish. Among other conclusions he laboured to prove that the earth had been remodelled at the deluge. Pluche, also, in 1732, wrote to the same effect; while Holbach, in 1753, after considering the various attempts to refer all the ancient formations to the flood of Noah, exposed the inadequacy of this cause.

Italian Geologists—Vallisneri.—I return with pleasure to the geologists of Italy, who preceded, as has been already shown, the naturalists of other countries in their investigations into the ancient history of the earth, and who still maintained a decided pre-eminence. They refuted and ridiculed the physico-theological systems of Burnet,

---

* An Examination of Dr. Burnet's Theory, &c. 2d ed. 1734.

Whiston, and Woodward [*]; while Vallisneri [†], in his comme the Woodwardian theory, remarked how much the interests of rel as well as those of sound philosophy, had suffered by perp mixing up the sacred writings with questions in physical sc The works of this author were rich in original observations. I tempted the first general sketch of the marine deposits of Italy, geographical extent, and most characteristic organic remain his treatise "On the Origin of Springs," he explained their de ence on the order, and often on the dislocations, of the strat reasoned philosophically against the opinions of those who reg the disordered state of the earth's crust as exhibiting signs wrath of God for the sins of man. He found himself und necessity of contending, in his preliminary chapter, again Jerome, and four other principal interpreters of Scripture, b several professors of divinity, "that springs did not flow by s ranean siphons and cavities from the sea upwards, losing thei ness in the passage," for this theory had been made to rest infallible testimony of Holy Writ.

Although reluctant to generalize on the rich materials accum in his travels, Vallisneri had been so much struck with the re able continuity of the more recent marine strata, from one Italy to the other, that he came to the conclusion that the formerly extended over the whole earth, and after abiding the a long time, had gradually subsided. This opinion, however able, was a great step beyond Woodward's diluvian hypo against which Vallisneri, and after him all the Tuscan geol uniformly contended, while it was warmly supported by the me of the Institute of Bologna. [‡]

Among others of that day, Spada, a priest of Grezzana, in wrote to prove that the petrified marine bodies near Verona we diluvian. [§] Mattani drew a similar inference from the sh Volterra and other places: while Costantini, on the other whose observations on the valley of the Brenta and other di were not without value, undertook to vindicate the truth deluge, as also to prove that Italy had been peopled by the de ants of Japhet. [‖]

Moro, 1740.—Lazzaro Moro, in his work (published in "On the Marine Bodies which are found in the Mountai attempted to apply the theory of earthquakes, as expound Strabo, Pliny, and other ancient authors, with whom he was fa to the geological phenomena described by Vallisneri. [**] His att was awakened to the elevating power of subterranean forces by a remarkable phenomenon which happened in his own time, and which had also been noticed by Vallisneri in his letters. A new island rose in 1707 from deep water in the Gulf of Santorin in the Mediterranean, during continued shocks of an earthquake, and, increasing rapidly in size, grew in less than a month to be half a mile in circumference, and about twenty-five feet above high-water mark. It was soon afterwards covered by volcanic ejections, but, when first examined, it was found to be a white rock, bearing on its surface living oysters and crustacea. In order to ridicule the various theories then in vogue, Moro ingeniously supposes the arrival on this new island of a party of naturalists ignorant of its recent origin. One immediately points to the marine shells, as proofs of the universal deluge; another argues that they demonstrate the former residence of the sea upon the mountains; a third dismisses them as mere *sports of nature;* while a fourth affirms, that they were born and nourished within the rock in ancient caverns, into which salt water had been raised in the shape of vapour by the action of subterranean heat.

---

[*] Ramazzini even asserted, that the ideas of Burnet were mainly borrowed from a dialogue of one Patrizio; but Brocchi, after reading that dialogue, assures us, that there was scarcely any other correspondence between these systems, except that both were equally whimsical.

[†] Dei Corpi Marini, Lettere critiche, &c. 1721.

[‡] Brocchi, p. 28.

[§] Ibid. p. 33.

[‖] Ibid.

[¶] Sui Crostacei ed altri Corpi che si trovano sui Monti.

[**] Moro does not cite the w Hooke and Ray; and although so of his views were in accordanc theirs, he was probably ignorant c

Moro pointed with great judgment to the *faults* and dislocations of the strata described by Vallisneri, in the Alps and other chains, in confirmation of his doctrine, that the continents had been heaved up by subterranean movements. He objected, on solid grounds, to the hypothesis of Burnet and of Woodward; yet he ventured so far to disregard the protest of Vallisneri, as to undertake the adaptation of every part of his own system to the Mosaic account of the creation. On the third day, he said, the globe was every where covered to the same depth by fresh water; and when it pleased the Supreme Being that the dry land should appear, volcanic explosions broke up the smooth and regular surface of the earth composed of primary rocks. These rose in mountain masses above the waves, and allowed melted metals and salts to ascend through fissures. The sea gradually acquired its saltness from volcanic exhalations, and, while it became more circumscribed in area, increased in depth. Sand and ashes ejected by volcanos were regularly disposed along the bottom of the ocean, and formed the secondary strata, which in their turn were lifted up by earthquakes. We need not follow this author in tracing the progress of the creation of vegetables and animals on the other days of creation; but, upon the whole, it may be remarked, that few of the old cosmological theories had been conceived with so little violation of known analogies.

Generelli's illustrations of Moro, 1749.—The style of Moro was extremely prolix, and, like Hutton, who, at a later period, advanced many of the same views, he stood in need of an illustrator. The Scotch geologist was hardly more fortunate in the advocacy of Playfair, than was Moro in numbering amongst his admirers Cirillo

---

writings, for they had not been translated. As he always refers to the Latin edition of Burnet, and a French translation of Woodward, we may presume that he did not read English.

Generelli, who, nine years afterwards, delivered at a sitti
Academicians at Cremona a spirited exposition of his theory.
learned Carmelitan friar does not pretend to have been an o
observer, but he had studied sufficiently to enable him to confi
opinions of Moro by arguments from other writers; and his sel
of the doctrines then best established is so judicious, that a
abstract of them cannot fail to be acceptable, as illustrating th
of geology in Europe, and in Italy in particular, before the mid
the last century.

The bowels of the earth, says he, have carefully preserv
memorials of past events, and this truth the marine producti
frequent in the hills attest. From the reflections of Lazzaro
we may assure ourselves that these are the effects of earthqu
past times, which have changed vast spaces of sea into terra
and inhabited lands into seas. In this, more than in any
department of physics, are observations and experiments
pensable, and we must diligently consider facts. The land is l
wherever we make excavations, to be composed of different st
soils placed one above the other, some of sand, some of rock, s
chalk, others of marl, coal, pummice, gypsum, lime, and th
These ingredients are sometimes pure, and sometimes confuse
termixed. Within are often imprisoned different marine fish
dried mummies, and more frequently shells, crustacea, corals,
&c., not only in Italy, but in France, Germany, England, Africa
and America; — sometimes in the lowest, sometimes in the
beds of the earth, some upon the mountains, some in deep
others near the sea, and others hundreds of miles distant fi
Woodward conjectured that these marine bodies might be
every where; but there are rocks in which none of them occu
sufficiently attested by Vallisneri and Marsilli. The rem
fossil animals consist chiefly of their more solid parts, and th
rocky strata must have been soft when such exuviæ were incl
them. Vegetable productions are found in different states of
rity, indicating that they were imbedded in different seasons
phants, elks, and other terrestrial quadrupeds, have been fo
England and elsewhere, in superficial strata, never covered
sea. Alternations are rare, yet not without example, of marine
with those which contain marshy and terrestrial productions.
animals are arranged in the subterraneous beds with admirabl
in distinct groups, oysters here, dentalia or corals there, &c.,
according to Marsilli[*], on the shores of the Adriatic. W
abandon the doctrine, once so popular, which denies that or
fossils were derived from living beings, and we cannot acc
their present position by the ancient theory of Strabo, nor by
Leibnitz, nor by the universal deluge, as explained by Wo
and others; "nor is it reasonable to call the Deity capriciousl
the stage, and to make him work miracles for the sake of con

---

[*] Saggio fisico intorno alla Storia del Mare, part i. p. 24.

our preconceived hypothesis."—"I hold in utter abomination, most learned Academicians! those systems which are built with their foundations in the air, and cannot be propped up without a miracle; and I undertake, with the assistance of Moro, to explain to you how these marine animals were transported into the mountains by natural causes."*

A brief abstract then follows of Moro's theory, by which, says Generelli, we may explain all the phenomena, as Vallisneri so ardently desired, "*without violence, without fictions, without hypothesis, without miracles.*"† The Carmelitan then proceeds to struggle against an obvious objection to Moro's system, considered as a method of explaining the revolutions of the earth, *naturally*. If earthquakes have been the agents of such mighty changes, how does it happen that their effects since the times of history have been so inconsiderable? This same difficulty had, as we have seen, presented itself to Hooke, half a century before, and forced him to resort to a former "crisis of nature:" but Generelli defended his position by showing how numerous were the accounts of eruptions and earthquakes, of new islands, and of elevations and subsidences of land, and yet how much greater a number of like events must have been unattested and unrecorded during the last six thousand years. He also appealed to Vallisneri as an authority to prove that the mineral masses containing shells bore, upon the whole, but a small proportion to those rocks, which were destitute of organic remains; and the latter, says the learned monk, might have been created as they now exist, *in the beginning*.

Generelli then describes the continual waste of mountains and continents, by the action of rivers and torrents, and concludes with these eloquent and original observations:—"Is it possible that this waste should have continued for six thousand, and *perhaps* a greater number of years, and that the mountains should remain so great, unless their ruins have been repaired? Is it credible that the Author of Nature should have founded the world upon such laws, as that the dry land should for ever be growing smaller, and at last become wholly submerged beneath the waters? Is it credible that, amid so many created things, the mountains alone should daily diminish in number and bulk, without there being any repair of their losses? This would be contrary to that order of Providence which is seen to reign in all other things in the universe. Wherefore I deem it just to conclude, that the same cause which, in the beginning of time, raised mountains from the abyss, has down to the present day continued to produce others, in order to restore from time to time the losses of all such as sink down in different places, or are rent asunder, or in other way suffer disintegration. If this be admitted, we can easily understand why there should now be found upon many mountains so g number of crustacea and other marine animals."

---

* "Abbomino al sommo qualsivoglia sistema, che sia di pianta fabbricato in aria; massime quando è tale, che non possa sostenersi senza un miracolo," &c. —De' Crostacei e di altre Produz. del Mare, &c. 1749.

† "Senza violenze, senza finzioni, senza supposti, senza miracoli." De' Crostacei e di altre Produz. del Mare, &c. 1749.

In the above extract, I have not merely enumerated the o and facts which are confirmed by recent observation, suppress that has since proved to be erroneous, but have given a f abridgment of the entire treatise, with the omission only of hypothesis, which Generelli adopted, with all its faults and lences. The reader will therefore remark, that although this able essay embraces so large a portion of the principal obj geological research, it makes no allusion to the extinction of classes of animals; and it is evident that no opinions on this he at that time, gained a firm footing in Italy. That Lister and English naturalists should long before have declared in favour loss of species, while Scilla and most of his countrymen hesitate perhaps natural, since the Italian museums were filled with fossil belonging to species of which a great portion did actually exist Mediterranean; whereas the English collectors could obtain no species from such of their own strata as were then explored.

The weakest point in Moro's system consisted in deriving stratified rocks from volcanic ejections; an absurdity which h ponents took care to expose, especially Vito Amici.* Moro se have been misled by his anxious desire to represent the format secondary rocks as having occupied an extremely short period, at the same time he wished to employ known agents in natur imagine torrents, rivers, currents, partial floods, and all the ope of moving water, to have gone on exerting an energy many th times greater than at present, would have appeared prepostero incredible, and would have required a hundred violent hypo but we are so unacquainted with the true sources of subterrane turbances, that their former violence may in theory be multipli definitely, without its being possible to prove the same manife tradiction or absurdity in the conjecture. For this reason, p Moro preferred to derive the materials of the strata from v ejections, rather than from transportation by running water.

Marsilli.—Marsilli, whose work is alluded to by Generelli, ha prompted to institute inquiries into the bed of the Adriatic, covering, in the territory of Parma, (what Spada had observe Verona, and Schiavo in Sicily,) that fossil shells were not sc through the rocks at random, but disposed in regular order, acc to certain genera and species.

Vitaliano Donati, 1750.—But with a view of throwing light upon these questions Donati, in 1750, undertook a mo tensive investigation of the Adriatic, and discovered, by nu soundings, that deposits of sand, marl, and tufaceous incrust most strictly analogous to those of the Subapennine hills, were act of accumulating there. He ascertained that there were no in some of the submarine tracts, while in other places they gether in families, particularly the genera Arca, Pecten, Venus, urex, and some others. He also states that in divers localities he und a mass composed of corals, shells, and crustaceous bodies of fferent species, confusedly blended with earth, sand, and gravel. At e depth of a foot or more, the organic substances were entirely trified and reduced to marble; at less than a foot from the surface, ey approached nearer to their natural state; while at the surface ey were alive, or, if dead, in a good state of preservation.

---

* Sui Testacei della Sicilia.

Baldassari.—A contemporary naturalist, Baldassari, had shown at the organic remains in the tertiary marls of the Siennese ter- ory were grouped in families, in a manner precisely similar to that ove alluded to by Donati.

Buffon, 1749.—Buffon first made known his theoretical views ncerning the former changes of the earth, in his Natural History, blished in 1749. He adopted the theory of an original volcanic cleus, together with the universal ocean of Leibnitz. By this ueous envelope the highest mountains were once covered. Marine rrents then acted violently, and formed horizontal strata, by wash- g away solid matter in some parts, and depositing it in others; they o excavated deep submarine valleys. The level of the ocean was en depressed by the entrance of a part of its waters into subter- nean caverns, and thus some land was left dry. Buffon seems not have profited, like Leibnitz and Moro, by the observations of eno, or he could not have imagined that the strata were generally rizontal, and that those which contain organic remains had never en disturbed since the era of their formation. He was conscious the great power annually exerted by rivers and marine currents transporting earthy materials to lower levels, and he even con- nplated the period when they would destroy all the present con- ents. Although in geology he was not an original observer, his nius enabled him to render his hypothesis attractive; and by the quence of his style, and the boldness of his speculations, he akened curiosity, and provoked a spirit of inquiry amongst his untrymen.

Soon after the publication of his "Natural History," in which was luded his "Theory of the Earth," he received an official letter ated January, 1751) from the Sorbonne, or Faculty of Theology in ris, informing him that fourteen propositions in his works "were prehensible, and contrary to the creed of the church." The first of se obnoxious passages, and the only one relating to geology, was follows:—"The waters of the sea have produced the mountains d valleys of the land—the waters of the heavens, reducing all to a el, will at last deliver the whole land over to the sea, and the sea ccessively prevailing over the land, will leave dry new continents e those which we inhabit." Buffon was invited by the College, in ry courteous terms, to send in an explanation, or rather a recantation his unorthodox opinions. To this he submitted; and a general sembly of the Faculty having approved of his "Declaration," he s required to publish it in his next work. The document begins with these words:—"I declare that I had no intention to cont the text of Scripture; that I believe most firmly all therein about the creation, both as to order of time and matter of fact *I abandon everything in my book respecting the foundation earth*, and, generally, all which may be contrary to the narrat Moses."*

The grand principle which Buffon was called upon to ren was simply this,—"that the present mountains and valleys earth are due to secondary causes, and that the same causes time destroy all the continents, hills, and valleys, and rep others like them." Now, whatever may be the defects of m his views, it is no longer controverted that the present contine of secondary origin. The doctrine is as firmly established earth's rotation on its axis; and that the land now elevated the level of the sea will not endure for ever, is an opinion gains ground daily, in proportion as we enlarge our experience changes now in progress.

Targioni, 1751.—Targioni, in his voluminous "Travels in Tu 1751 and 1754," laboured to fill up the sketch of the geology region left by Steno sixty years before. Notwithstanding a w arrangement and condensation in his memoirs, they contained store of faithful observations. He has not indulged in many views, but in regard to the origin of valleys, he was opposed theory of Buffon, who attributed them principally to sub currents. The Tuscan naturalist laboured to show that bo larger and smaller valleys of the Apennines were excavated by and floods, caused by the bursting of the barriers of lakes, af retreat of the ocean. He also maintained that the elephan other quadrupeds, so frequent in the lacustrine and alluvial d of Italy, had inhabited that peninsula; and had not been tran thither, as some had conceived, by Hannibal or the Romans, what they were pleased to term "a catastrophe of nature."

Lehman, 1756.—In the year 1756 the treatise of Lehman, a G mineralogist, and director of the Prussian mines, appeared, w divided mountains into three classes: the first, those forme the world, and prior to the creation of animals, and which co no fragments of other rocks; the second class, those which r from the partial destruction of the primary rocks by a revolution; and a third class, resulting from local revolutions, part from the deluge of Noah.

A French translation of this work appeared in 1759, in the of which, the translator displays very enlightened views res the operations of earthquakes, as well as of the aqueous causes

Gesner, 1758.—In this year Gesner, the botanist, of published an excellent treatise on petrifactions, and the cha the earth which they testify.‡ After a detailed enumeration us classes of fossils of the animal and vegetable kingdoms, and rks on the different states in which they are found petrified, he ders the geological phenomena connected with them; observing, some, like those of Œningen, resembled the testacea, fish, and s indigenous in the neighbouring region*; while some, such mmonites, gryphites, belemnites, and other shells, are either ıknown species, or found only in the Indian and other distant

---

* Hist. Nat. tom. v. éd. de l'Imp. Royale, Paris, 1769.

† Essai d'une Hist. Nat. des Couches de la Terre, 1759.

‡ John Gesner published at in Latin.

In order to elucidate the structure of the earth, he gives ms, from Verenius, Buffon, and others, obtained in digging ; distinguishes between horizontal and inclined strata; and, in ılating on the causes of these appearances, mentions Donati's ination of the bed of the Adriatic; the filling up of lakes and by sediment; the imbedding of shells, now in progress; and known effects of earthquakes, such as the sinking down of icts, or the heaving up of the bed of the sea, so as to form new ds, and lay dry strata containing petrifactions. The ocean, he deserts its shores in many countries, as on the borders of the c; but the rate of recession has been so slow in the last 2000 , that to allow the Apennines, whose summits are filled with ne shells, to emerge to their present height, would have required t 80,000 years,—a lapse of time ten times greater, or more, the age of the universe. We must therefore refer the pheno- n to the command of the Deity, related by Moses, that "the rs should be gathered together in one place, and the dry land ar." Gesner adopted the views of Leibnitz, to account for the at of the primeval ocean: his essay displays much erudition; he opinions of preceding writers of Italy, Germany, and England, ommented upon with fairness and discrimination.

rduino, 1759.—In the year following, Arduino†, in his memoirs e mountains of Padua, Vicenza, and Verona, deduced, from ori- l observations, the distinction of rocks into primary, secondary, tertiary, and showed that in those districts there had been a suc- on of submarine volcanic eruptions.

ichell, 1760.—In the following year (1760) the Rev. John ell, Woodwardian Professor of Mineralogy at Cambridge, pub- d in the Philosophical Transactions, an Essay on the Cause and omena of Earthquakes.‡ His attention had been drawn to this subject by the great earthquake of Lisbon in 1755. He ad many original and philosophical views respecting the propaga subterranean movements, and the caverns and fissures wherein might be generated. In order to point out the application theory to the structure of the globe, he was led to descri arrangement and disturbance of the strata, their usual horizo in low countries, and their contortions and fractured state i neighbourhood of mountain chains. He also explained, wit prising accuracy, the relations of the central ridges of older ro the "long narrow slips of similar earth, stones, and minerals," are parallel to these ridges. In his generalizations, derived in part from his own observations on the geological structure of shire, he anticipated many of the views more fully developed b naturalists.

---

* art ii. chap. 9.

† iornale del Criselini, 1759.

‡ See a Sketch of the History of En- Geology, by Dr. Fitton, in Edinb. Feb. 1818, re-edited Lond. and . Phil. Mag. vol. i. and ii. 1832-33. of Michell's observations anticipate remarkable a manner the theories ished forty years afterwards, that itings would probably have formed in the science, if his researches had ninterrupted. He held, however, ofessorship only eight years, when reer was suddenly cut short by pre- nt to a benefice. From that time he appears to have been engaged in his clerical duties, and to have entirely discontinued his scientific pursuits, exemplifying the working of a system still in force at Oxford and Cambridge, where the chairs of mathematics, natural philosophy, chemistry, botany, astronomy, geology, mineralogy, and others, being frequently filled by clergymen, the reward of success disqualifies them, if they conscientiously discharge their new duties, from farther advancing the cause of science, and that, too, at the moment when their labours would naturally bear the richest fruits.

Catcott, 1761.—Michell's papers were entirely free fr physico-theological disquisitions, but some of his contemp were still earnestly engaged in defending or impugning the wardian hypothesis. We find many of these writings referred Catcott, an Hutchinsonian, who published a "Treatise on the D in 1761. He laboured particularly to refute an explanation by his contemporary, Bishop Clayton, of the Mosaic writings. prelate had declared that the deluge "could not be literally tru in respect to that part where Noah lived before the flood." C insisted on the universality of the deluge, and referred to tra of inundations mentioned by ancient writers, or by travellers, East Indies, China, South America, and other countries. Thi of his book is valuable, although it is not easy to see what b the traditions have, if admitted to be authentic, on the B argument, since no evidence is adduced to prove that the catast were contemporaneous events, while some of them are ex represented by ancient authors to have occurred in succession.

Fortis—*Odoardi*, 1761.—The doctrines of Arduino, abo verted to, were afterwards confirmed by Fortis and Desmarest, i travels in the same country; and they, as well as Baldassari, la to complete the history of the Subapennine strata. In the w Odoardi*, there was also a clear argument in favour of the d ages of the older Apennine strata, and the Subapennine form of more recent origin. He pointed out that the strata of the groups were *unconformable*, and must have been the depo different seas at distant periods of time.

Raspe, 1763.—A history of the new islands by Raspe, an verian, appeared in 1763, in Latin.† In this work, all the au accounts of earthquakes which had produced permanent chan the solid parts of the earth were collected together and examine judicious criticism. The best systems which had been pr ıg the ancient history of the globe, both by ancient and writers, are reviewed; and the merits and defects of the of Hooke, Ray, Moro, Buffon, and others, fairly estimated. miration is expressed for the hypothesis of Hooke, and his on of the origin of the strata is shown to have been more ıan Moro's, while their theory of the effects of earthquakes ame. Raspe had not seen Michell's memoirs, and his views ıg the geological structure of the earth were perhaps less ; yet he was able to add many additional arguments in Hooke's theory, and to render it, as he said, a nearer to what Hooke would have written had he lived in later ls to the periods wherein all the earthquakes happened, to owe the elevation of various parts of our continents and laspe says he pretends not to assign their duration, still less Hooke's suggestion, that the convulsions almost all took ring the deluge of Noah. He adverts to the apparent ıs of the former tropical heat of the climate of Europe, and es in the species of animals and plants, as among the most nd difficult problems in geology. In regard to the islands m the sea, within the times of history or tradition, he declares of them were composed of strata containing organic remains, they were not, as Buffon had asserted, made of mere volter. His work concludes with an eloquent exhortation* to s to examine the isles which rose, in 1707, in the Grecian go, and, in 1720, in the Azores, and not to neglect such pportunities of studying nature "in the act of parturition." ke's writings should have been neglected for more than half , was matter of astonishment to Raspe; but it is still more that his own luminous exposition of that theory should, han another half century, have excited so little interest.

---

* Sui Corpi Marini del Feltrino, 1761.

† De Novis e Mari Natis Insulis. Raspe was also the editor of the "Philosophical Works of Leibnitz. Amst. et Leipzig, 1765;" also author of " Gems," and "Baron Muncl Travels."

, 1762 and 1773.—Fuchsel, a German physician, published, ı geological description of the country between the Thul and the Hartz, and a memoir on the environs of Rudelnd afterwards, in 1773, a theoretical work on the ancient the earth and of man.† He had evidently advanced ıly beyond his predecessor Lehman, and was aware of the ıs, both as to position and fossil contents, of several groups f different ages, corresponding to the secondary formations gnized by geologists in various parts of Germany. He the European continents to have remained covered by the the formation of the marine strata called in Germany alk," at the same time that the terrestrial plants of many deposits, attested the existence of dry land which bordered t sea; land which, therefore, must have occupied the place ent ocean. This pre-existing continent had been *gradually*

---

adcmiæ Electoralis Magun- Erfurt.

ount of Fuchsel is derived from an excellent analysis of his memoirs by M. Keferstein. Journ. de Géologie, tom. ii. Oct. 1830.

swallowed up by the sea, different parts having subsided in succe into subterranean caverns. All the sedimentary strata were origi horizontal, and their present state of derangement must be ref to subsequent oscillations of the ground.

As there were plants and animals in the ancient periods, so there must have been men, but they did not all descend from pair, but were created at various points on the earth's surface; the number of these distinct birth-places was as great as ar original languages of nations.

In the writings of Fuchsel we see a strong desire manifest explain geological phenomena as far as possible by reference to agency of known causes; and although some of his speculations fanciful, his views coincide much more nearly with those now gene adopted, than the theories afterwards promulgated by Werner his followers.

Brander, 1766.—Gustavus Brander published, in 1766, his " silia Hantoniensia," containing excellent figures of fossil shells the more modern (or Eocene) marine strata of Hampshire. "Va opinions," he says in the preface, "had been entertained conce the time when and how these bodies became deposited. Some are who conceive that it might have been effected in a wond length of time by a gradual changing and shifting of the sea,' But the most common cause assigned is that of "the deluge." conjecture, he says, even if the universality of the flood be not in question, is purely hypothetical. In his opinion, fossil ani and testacea were, for the most part, of unknown species; a such as were known, the living analogues now belonged to sout latitudes.

Soldani, 1780.—Soldani applied successfully his knowled zoology to illustrate the history of stratified masses. He expl that microscopic testacea and zoophytes inhabited the depths o Mediterranean; and that the fossil species were, in like ma found in those deposits wherein the fineness of their particles the absence of pebbles, implied that they were accumulated in a sea, or far from shore. This author first remarked the alternati marine and freshwater strata in the Paris basin.*

Fortis—Testa, 1793.—A lively controversy arose between F and another Italian naturalist, Testa, concerning the fish of M Bolca, in 1793. Their letters†, written with great spirit elegance, show that they were aware that a large proportion o Subapennine shells were identical with living species, and son them with species now living in the torrid zone. Fortis propo somewhat fanciful conjecture, that when the volcanos of the Vic were burning, the waters of the Adriatic had a higher temperat and in this manner, he said, the shells of warmer regions may have peopled their own seas. But Testa was disposed to think pecies of testacea were still common to their own and to tial seas: for many, he said, once supposed to be confined to egions, had been afterwards discovered in the Mediterranean.*

---

* Saggio orittografico, &c. 1780, and other Works.

† Lett. sui Pesci Fossili di Milan, 1793.

esi — *Spallanzani* — *Wallerius* — *Whitehurst.* — While these naturalists, together with Cortesi and Spallanzani, were busily d in pointing out the analogy between the deposits of modern cient seas, and the habits and arrangement of their organic ants, and while some progress was making, in the same r, in investigating the ancient and modern volcanic rocks, f the most original observers among the English and German , Whitehurst† and Wallerius, were wasting their strength tending, according to the old Woodwardian hypothesis, that strata were formed by Noah's deluge. But Whitehurst's tion of the rocks of Derbyshire was most faithful; and he for false theoretical views, by providing data for their refu-

'as — *Saussure.* — Towards the close of the eighteenth century, ea of distinguishing the mineral masses on our globe into te groups, and studying their relations, began to be generally d. Pallas and Saussure were among the most celebrated labours contributed to this end. After an attentive examina- ' the two great mountain chains of Siberia, Pallas announced sult, that the granitic rocks were in the middle, the schistose r sides, and the limestones again on the outside of these; and conceived would prove a general law in the formation of all composed chiefly of primary rocks.‡

his "Travels in Russia," in 1793 and 1794, he made many ical observations on the recent strata near the Wolga and the n, and adduced proofs of the greater extent of the latter sea at tant era in the earth's history. His memoir on the fossil bones eria attracted attention to some of the most remarkable phe- a in geology. He stated that he had found a rhinoceros entire frozen soil, with its skin and flesh: an elephant, found after- in a mass of ice on the shore of the North Sea, removed all as to the accuracy of so wonderful a discovery.§

subjects relating to natural history which engaged the at- 1 of Pallas, were too multifarious to admit of his devoting a hare of his labours exclusively to geology. Saussure, on the hand, employed the chief portion of his time in studying the

---

is argument of Testa has been bened of late years by the dis- that dealers in shells had long the habit of selling Mediterranean as shells of more southern and latitudes, for the sake of enhan- eir price. It appears, moreover, veral hundred experiments made at distinguished hydrographer, n Smyth, on the water within fathoms of the surface, that the ature of the Mediterranean is on an average 3½° of Fahrenheit higher than the Western part of the Atlantic ocean; an important fact, which in some degree may help to explain why many species are common to tropical latitudes and to the Mediterranean.

† Inquiry into the Original State and Formation of the Earth, 1778.

‡ Observ. on the Formation of Mountains. Act Petrop. ann. 1778, part. i.

§ Nov. comm. Petr. XVII. Cuvier, Eloge de Pallas.

structure of the Alps and Jura, and he provided valuable da
those who followed him. He did not pretend to deduce any g
system from his numerous and interesting observations; and th
theoretical opinions which escaped from him, seem, like the
Pallas, to have been chiefly derived from the cosmological specula
of preceding writers.

CHAPTER IV.

HISTORY OF THE PROGRESS OF GEOLOGY—*continued.*

Werner's application of geology to the art of mining—Excursive character
lectures—Enthusiasm of his pupils—His authority—His theoretical er
Desmarest's Map and Description of Auvergne—Controversy between the
canists and Neptunists—Intemperance of the rival sects—Hutton's The
the earth—His discovery of granite veins—Originality of his views—
opposed—Playfair's illustrations—Influence of Voltaire's writings on g
—Imputations cast on the Huttonians by Williams, Kirwan, and De
Smith's Map of England—Geological Society of London—Progress of the s
in France—Growing importance of the study of organic remains.

Werner.—THE art of mining has long been taught in Fr
Germany, and Hungary, in scientific institutions established fo
purpose, where mineralogy has always been a principal bran
instruction.

Werner was named, in 1775, professor of that science in
"School of Mines," at Freyberg, in Saxony. He directed his
tion not merely to the composition and external characters of min
but also to what he termed "geognosy," or the natural positi
minerals in particular rocks, together with the grouping of
rocks, their geographical distribution, and various relations.
phenomena observed in the structure of the globe had hitherto s
for little else than to furnish interesting topics for philoso
discussion: but when Werner pointed out their application t
practical purposes of mining, they were instantly regarded by a
class of men as an essential part of their professional educatio
from that time the science was cultivated in Europe more ard
and systematically. Werner's mind was at once imaginative
richly stored with miscellaneous knowledge. He associated
thing with his favourite science, and in his excursive lecture
pointed out all the economical uses of minerals, and their appli
to medicine: the influence of the mineral composition of rocks
the soil, and of the soil upon the resources, wealth, and civili
of man. The vast sandy plains of Tartary and Africa, he woul
retained their inhabitants in the shape of wandering shepherds
granitic mountains and the low calcareous and alluvial plains
rise to different manners, degrees of v ntelligence.

history even of languages, and the migrations of tribes, had been determined by the direction of particular strata. The qualities of certain stones used in building would lead him to descant on the architecture of different ages and nations; and the physical geography of a country frequently invited him to treat of military tactics. The charm of his manners and his eloquence kindled enthusiasm in the minds of his pupils; and many, who had intended at first only to acquire a slight knowledge of mineralogy, when they had once heard him, devoted themselves to it as the business of their lives. In a few years, a small school of mines, before unheard of in Europe, was raised to the rank of a great university; and men already distinguished in science studied the German language, and came from the most distant countries to hear the great oracle of geology.*

Werner had a great antipathy to the mechanical labour of writing, and, with the exception of a valuable treatise on metalliferous veins, he could never be persuaded to pen more than a few brief memoirs, and those containing no development of his general views. Although the natural modesty of his disposition was excessive, approaching even to timidity, he indulged in the most bold and sweeping generalizations, and he inspired all his scholars with a most implicit faith in his doctrines. Their admiration of his genius, and the feelings of gratitude and friendship which they all felt for him, were not undeserved; but the supreme authority usurped by him over the opinions of his contemporaries, was eventually prejudicial to the progress of the science; so much so, as greatly to counterbalance the advantages which it derived from his exertions. If it be true that delivery be the first, second, and third requisite in a popular orator, it is no less certain, that to travel is of first, second, and third importance to those who desire to originate just and comprehensive views concerning the structure of our globe. Now Werner had not travelled to distant countries; he had merely explored a small portion of Germany, and conceived, and persuaded others to believe that the whole surface of our planet, and all the mountain chains in the world, were made after the model of his own province. It became a ruling object of ambition in the minds of his pupils to confirm the generalizations of their great master, and to discover in the most distant parts of the globe his "universal formations," which he supposed had been each in succession simultaneously precipitated over the whole earth from a common menstruum, or "chaotic fluid." It now appears that the Saxon professor had misinterpreted many of the most important appearances even in the immediate neighbourhood of Freyberg. Thus, for example, within a day's journey of his school, the porphyry, called by him primitive, has been found not only to send forth veins or dikes through strata of the coal formation, but to overlie them in mass. The granite of the Hartz mountains, on the other hand, which he supposed to be the nucleus of the chain, is now well known to traverse the other beds, as near Goslar; and still

---

* Cuvier, Eloge de Werner.

nearer Freyberg, in the Erzgebirge, the mica slate does not
round the granite as was supposed, but abuts abruptly agai
Fragments, also, of the greywacké slate, containing organic re
have recently been found entangled in the granite of the Har
M. de Seckendorf.*

The principal merit of Werner's system of instruction con
in steadily directing the attention of his scholars to the co
relations of superposition of certain mineral groups; but hi
been anticipated, as has been shown in the last chapter, in th
covery of this general law, by several geologists in Italy and
where; and his leading divisions of the secondary strata were
same time, and independently, made the basis of an arrangem
the British strata by our countryman, William Smith, to whose
I shall refer in the sequel.

Controversy between the Vulcanists and Neptunists.—In
to basalt and other igneous rocks, Werner's theory was origin
it was also extremely erroneous. The basalts of Saxony and
to which his observations were chiefly confined, consisted of t
masses capping the hills, and not connected with the levels of
ing valleys, like many in Auvergne and the Vivarais. These b
and all other rocks of the same family in other countries,
according to him, chemical precipitates from water. He
that they were the products of submarine volcanos; and even
that, in the primeval ages of the world, there were no vol
His theory was opposed, in a two-fold sense, to the doctrine
permanent agency of the same causes in nature; for not only
introduce, without scruple, many imaginary causes supposed t
once effected great revolutions in the earth, and then to have
extinct, but new ones also were feigned to have come into
modern times; and, above all, that most violent instrum
change, the agency of subterranean heat.

So early as 1768, before Werner had commenced his minera
studies, Raspe had truly characterized the basalts of Hesse
igneous origin. Arduino, we have seen, had pointed out nu
varieties of trap-rock in the Vicentin as analogous to volcani
ducts, and as distinctly referable to ancient submarine eru
Desmarest, as before stated, had, in company with Fortis, ex
the Vicentin in 1766, and confirmed Arduino's views. In
Banks, Solander, and Troil compared the columnar basalt of
with that of the Hebrides. Collini, in 1774, recognized th
nature of the igneous rocks on the Rhine, between Anderna
Bonn. In 1775, Guettard visited the Vivarais, and establis
relation of basaltic currents to lavas. Lastly, in 1779, Fauja
lished his description of the volcanos of the Vivarais and Vel
showed how the streams of basalt had poured out from crater
still remain in a perfect state.†

---

* I am indebted for this information partly to Messrs. Sedgwick and Murchison, who have investigated the country, and partly to Dr. Charles H
the translator of this work into

† Cuvier, Eloge de Desmares

Desmarest.—When sound opinions had thus for twenty years prevailed in Europe concerning the true nature of the ancient trap-rocks, Werner by his simple dictum caused a retrograde movement, and not only overturned the true theory, but substituted for it one of the most unphilosophical that can well be imagined. The continued ascendancy of his dogmas on this subject was the more astonishing, because a variety of new and striking facts were daily accumulated in favour of the correct opinions previously entertained. Desmarest, after a careful examination of Auvergne, pointed out, first, the most recent volcanos which had their craters still entire, and their streams of lava conforming to the level of the present river-courses. He then showed that there were others of an intermediate epoch, whose craters were nearly effaced, and whose lavas were less intimately connected with the present valleys; and, lastly, that there were volcanic rocks, still more ancient, without any discernible craters or scoriæ, and bearing the closest analogy to rocks in other parts of Europe, the igneous origin of which was denied by the school of Freyberg.*

Desmarest's map of Auvergne was a work of uncommon merit. He first made a trigonometrical survey of the district, and delineated its physical geography with minute accuracy and admirable graphic power. He contrived, at the same time, to express without the aid of colours, many geological details, including the different ages and sometimes even the structure, of the volcanic rocks, and distinguishing them from the fresh-water and the granitic. They alone who have carefully studied Auvergne, and traced the different lava streams from their craters to their termination,—the various isolated basaltic cappings,—the relation of some lavas to the present valleys,—the absence of such relations in others,—can appreciate the extraordinary fidelity of this elaborate work. No other district of equal dimensions in Europe exhibits, perhaps, so beautiful and varied a series of phenomena; and, fortunately, Desmarest possessed at once the mathematical knowledge required for the construction of a map, skill in mineralogy, and a power of original generalization.

Dolomieu—*Montlosier.*—Dolomieu, another of Werner's contemporaries, had found prismatic basalt among the ancient lavas of Etna; and, in 1784, had observed the alternations of submarine lavas and calcareous strata in the Val di Noto, in Sicily.† In 1790, also, he described similar phenomena in the Vicentin and in the Tyrol.‡ Montlosier published, in 1788, an essay on the theory of the volcanos of Auvergne, combining accurate local observations with comprehensive views. Notwithstanding this mass of evidence, the scholars of Werner were prepared to support his opinions to their utmost extent; maintaining, in the fulness of their faith, that even obsidian was an aqueous precipitate. As they were blinded by their veneration for the great teacher, they were impatient of opposition, and soon imbibed the spirit of a faction; and their opponents the Vul were not long in becoming contaminated with the same inte zeal. Ridicule and irony were weapons more frequently em than argument by the rival sects, till at last the controver carried on with a degree of bitterness almost unpreceden questions of physical science. Desmarest alone, who had long provided ample materials for refuting such a theory, kept aloof the strife; and whenever a zealous Neptunist wished to dra old man into an argument, he was satisfied with replying "G see."*

---

* Journ. de Phys. vol. xiii. p. 115.; and Mém. de l'Inst., Sciences Mathémat. et Phys. vol. vi. p. 219.

† Journ. de Phys. tom. xxv. p. 191

‡ Ib. tom. xxxvii. part ii. p. 200.

Hutton, 1788.—It would be contrary to all analogy, in matt graver import, that a war should rage with such fury on the Con and that the inhabitants of our island should not mingle in the Although in England the personal influence of Werner was w to stimulate men to the defence of the weaker side of the qu they contrived to find good reason for espousing the Wernerian with great enthusiasm. In order to explain the peculiar m which led many to enter, even with party feeling, into this con will be necessary to present the reader with a sketch of the unfolded by Hutton, a contemporary of the Saxon geologist. former naturalist had been educated as a physician, but declini practice of medicine, he resolved, when young, to remain conten the small independence inherited from his father, and thencef give his undivided attention to scientific pursuits. He resi Edinburgh, where he enjoyed the society of many men of hi tainments, who loved him for the simplicity of his manners a sincerity of his character. His application was unwearied; made frequent tours through different parts of England and Sc acquiring considerable skill as a mineralogist, and constantly a at grand and comprehensive views in geology. He communica results of his observations unreservedly, and with the fearless of one who was conscious that love of truth was the sole stim his exertions. When at length he had matured his views, h lished, in 1788, his "Theory of the Earth,"† and the same, afte more fully developed in a separate work, in 1795. This treati the first in which geology was declared to be in no way con about "questions as to the origin of things;" the first in wh attempt was made to dispense entirely with all hypothetical and to explain the former changes of the earth's crust by re exclusively to natural agents. Hutton laboured to give fixe ciples to geology, as Newton had succeeded in doing to astro but, in the former science, too little progress had been made t furnishing the necessary data, to enable any philosopher, howeve his genius, to realise so noble a project.

Huttonian theory.—"The ruins of an older world," said I "are visible in the present structure of our planet; and the which now compose our continents have been once beneath t and were formed out of the waste of pre-existing continents. The same forces are still destroying, by chemical decomposition or mechanical violence, even the hardest rocks, and transporting the materials to the sea, where they are spread out, and form strata analogous to those of more ancient date. Although loosely deposited along the bottom of the ocean, they become afterwards altered and consolidated by volcanic heat, and then heaved up, fractured, and contorted."

---

* Cuvier, Eloge de Desmarest.

† Ed. Phil. Trans. 1788.

Although Hutton had never explored any region of active volcanos, he had convinced himself that basalt and many other trap-rocks were of igneous origin, and that many of them had been injected in a melted state through fissures in the older strata. The compactness of these rocks, and their different aspect from that of ordinary lava, he attributed to their having cooled down under the pressure of the sea; and in order to remove the objections started against this theory, his friend, Sir James Hall, instituted a most curious and instructive series of chemical experiments, illustrating the crystalline arrangement and texture assumed by melted matter cooled under high pressure.

The absence of stratification in granite, and its analogy, in mineral character, to rocks which he deemed of igneous origin, led Hutton to conclude that granite also must have been formed from matter in fusion; and this inference he felt could not be fully confirmed, unless he discovered at the contact of granite and other strata a repetition of the phenomena exhibited so constantly by the trap-rocks. Resolved to try his theory by this test, he went to the Grampians, and surveyed the line of junction of the granite and superincumbent stratified masses, until he found in Glen Tilt, in 1785, the most clear and unequivocal proofs in support of his views. Veins of red granite are there seen branching out from the principal mass, and traversing the black micaceous schist and primary limestone. The intersected stratified rocks are so distinct in colour and appearance as to render the example in that locality most striking, and the alteration of the limestone in contact was very analogous to that produced by trap veins on calcareous strata. This verification of his system filled him with delight, and called forth such marks of joy and exultation, that the guides who accompanied him, says his biographer, were convinced that he must have discovered a vein of silver or gold.* He was aware that the same theory would not explain the origin of the primary schists, but these he called primary, rejecting the term primitive, and was disposed to consider them as sedimentary rocks altered by heat, and that they originated in some other form from the waste of previously existing rocks.

By this important discovery of granite veins, to which he had been led by fair induction from an independent class of facts, Hutton prepared the way for the greatest innovation on the systems of his predecessors. Vallisneri had pointed out the general fact were certain fundamental rocks which contained no organic and which he supposed to have been formed before the living beings. Moro, Generelli, and other Italian writers, the same doctrine; and Lehman regarded the mountains him primitive, as parts of the original nucleus of the glo same tenet was an article of faith in the school of Freyber any one ventured to doubt the possibility of our being carry back our researches to the creation of the present order the granitic rocks were triumphantly appealed to. On the written, in legible characters, the memorable inscription —

---

* Playfair's Works, vol. iv. p. 75.

> "Dinanzi a me non fur cose create
> Se non eterne;" *

and no small sensation was excited when Hutton seemed, hallowed hand, desirous to erase characters already regarded as sacred. "In the economy of the world," said the Scotch "I can find no traces of a beginning, no prospect of an declaration the more startling when coupled with the doctr all past ages on the globe had been brought about by the slo of existing causes. The imagination was first fatigued powered by endeavouring to conceive the immensity of time for the annihilation of whole continents by so insensible a and when the thoughts had wandered through these inter periods, no resting-place was assigned in the remotest distance oldest rocks were represented to be of a derivative nature, of an antecedent series, and that, perhaps, one of many pre- worlds. Such views of the immensity of past time, lik unfolded by the Newtonian philosophy in regard to space, vast to awaken ideas of sublimity unmixed with a painful our incapacity to conceive a plan of such infinite extent. Wo seen beyond worlds immeasurably distant from each othe beyond them all, innumerable other systems are faintly traced confines of the visible universe.

The characteristic features of the Huttonian theory was, hinted, [the exclusion of all causes not supposed to belong present order of nature.] But Hutton had made no step Hooke, Moro, and Raspe, in pointing out in what manner now governing subterranean movements might bring about ge changes, if sufficient time be allowed. On the contrary, he have fallen far short of some of their views, especially whe fused to attribute any part of the external configuration of the crust to subsidence. He imagined that the continents we gradually destroyed by aqueous degradation; and when the had furnished materials for new continents, they were uphe violent convulsions. He therefore required alternate pe

---

* "Before me things create were none, save things
Eternal."

Dante's *Inferno*, canto iii., Cary's Tran ral disturbance and repose: and such he believed had been, and d for ever be, the course of nature.

merelli, in his exposition of Moro's system, had made a far nearer oximation towards reconciling geological appearances with the of nature as known to us; for while he agreed with Hutton, the decay and reproduction of rocks were always in progress, eding with the utmost uniformity, the learned Carmelite repre- d the repairs of mountains by elevation from below to be effected a equally constant and synchronous operation. Neither of these ies, considered singly, satisfies all the conditions of the great lem, which a geologist, who rejects cosmological causes, is called to solve; but they probably contain together the germs of a ct system. There can be no doubt, that periods of disturbance repose have followed each other in succession in every region of globe; but it may be equally true, that the energy of the sub- nean movements has been always uniform as regards the *whole* . The force of earthquakes may for a cycle of years have been iably confined, as it is now, to large but determinate spaces, and then have gradually shifted its position, so that another region, h had for ages been at rest, became in its turn the grand theatre tion.

ayfair's illustrations of Hutton.—The explanation proposed by on, and by Playfair, the illustrator of his theory, respecting the a of valleys and of alluvial accumulations, was also very im- ct. They ascribed none of the inequalities of the earth's surface ovements which accompanied the upheaving of the land, ima- g that valleys in general were formed in the course of ages by ivers now flowing in them; while they seem not to have reflected e excavating and transporting power which the waves of the might exert on land during its emergence.

though Hutton's knowledge of mineralogy and chemistry was derable, he possessed but little information concerning organic ins; they merely served him, as they did Werner, to charac- certain strata, and to prove their marine origin. The theory rmer revolutions in organic life was not yet fully recognized; rithout this class of proofs in support of the antiquity of the , the indefinite periods demanded by the Huttonian hypothesis red visionary to many; and some, who deemed the doctrine sistent with revealed truths, indulged very uncharitable suspicions motives of its author. They accused him of a deliberate design viving the heathen dogma of an "eternal succession," and of ng that this world ever had a beginning. Playfair, in the aphy of his friend, has the following comment on this part of theory:—"In the planetary motions, where geometry has d the eye so far, both into the future and the past, we discover ark either of the commencement or termination of the present . It is unreasonable, indeed, to suppose that such marks should rhere exist. The Author of Nature has not given laws to the rse, which, like the institutions of men, carry in themselves the elements of their own destruction. He has not permitted i works any symptom of infancy or of old age, or any sign by we may estimate either their future or their past duration. H *put an end, as He no doubt gave a beginning,* to the present s at some determinate period of time; but we may rest assured this great catastrophe will not be brought about by the law existing, and that it is not indicated by any thing whic perceive."*

The party feeling excited against the Huttonian doctrines, a open disregard of candour and temper in the controversy, will be credited by the reader, unless he recalls to his recollectio the mind of the English public was at that time in a state of fe excitement. A class of writers in France had been labouri dustriously for many years, to diminish the influence of the c by sapping the foundations of the Christian faith; and their s and the consequences of the Revolution, had alarmed the most lute minds, while the imagination of the more timid was conti haunted by dread of innovation, as by the phantom of some dream.

Voltaire.—Voltaire had used the modern discoveries in p as one of the numerous weapons of attack and ridicule direct him against the Scriptures. He found that the most popular s of geology were accommodated to the sacred writings, and that ingenuity had been employed to make every fact coincide e with the Mosaic account of the creation and deluge. It was, fore, with no friendly feelings that he contemplated the cultiva geology in general, regarding the science as one which ha successfully enlisted by theologians as an ally in their cause. knew that the majority of those who were aware of the abund fossil shells in the interior of continents, were still persuade they were proofs of the universal deluge; and as the readiest shaking this article of faith, he endeavoured to inculcate sce as to the real nature of such shells, and to recall from conten exploded dogma of the sixteenth century, that they were sp nature. He also pretended that vegetable impressions we those of real plants.‡ Yet he was perfectly convinced that th had really belonged to living testacea, as may be seen in hi "On the formation of Mountains."§ He would sometimes, fiance of all consistency, shift his ground when addressing the vulgar; and, admitting the true nature of the shells collected in the Alps and other places, pretend that they were Eastern species, which had fallen from the hats of pilgrims coming from Syria. The numerous essays written by him on geological subjects were all calculated to strengthen prejudices, partly because he was ignorant of the real state of the science, and partly from his bad faith.[*] On the other hand, they who knew that his attacks were directed by a desire to invalidate Scripture, and who were unacquainted with the true merits of the question, might well deem the old diluvian hypothesis incontrovertible, if Voltaire could adduce no better argument against it than to deny the true nature of organic remains.

---

* Playfair's Works, vol. iv. p. 55.

† In allusion to the theories of Burnet, Woodward, and other physico-theological writers, he declared that they were as fond of changes of scene on the face of the globe, as were the populace at a play. "Every one of them destroys and renovates the earth after his own fashion, as Descartes framed it: for philosophers put themselves without ceremony in the place of God, and think to create a universe with a word."—Dissertation envoyée a l'Academie de Boulogne, sur les Changemens arrivés dans notre Globe. Unfortunately, this and similar directed against the cosmogon too well deserved.

‡ See the chapter on "Des figurés."

§ In that essay he lays it dow all naturalists are now agreed posits of shells in the midst of t nents are monuments of the c occupation of these districts by th In another place also, when spe the fossil shells of Touraine, h their true origin.

It is only by careful attention to impediments originating in extrinsic causes, that we can explain the slow and reluctant adoption of the simplest truths in geology. First, we find many able naturalists adducing the fossil remains of marine animals as proofs of an event related in Scripture. The evidence is deemed conclusive by the multitude for a century or more; for it favours opinions which they entertained before, and they are gratified by supposing them confirmed by fresh and unexpected proofs. Many, who see through the fallacy, have no wish to undeceive those who are influenced by it, approving the effect of the delusion, and conniving at it as a pious fraud; until, finally, an opposite party, who are hostile to the sacred writings, labour to explode the erroneous opinion, by substituting for it another dogma which they know to be equally unsound.

The heretical Vulcanists were soon after openly assailed in England, by imputations of the most illiberal kind. We cannot estimate the malevolence of such a persecution, by the pain which similar insinuations might now inflict; for although charges of infidelity and atheism must always be odious, they were injurious in the extreme at that moment of political excitement; and it was better, perhaps, for a man's good reception in society, that his moral character should have been traduced, than that he should become a mark for these poisoned weapons.

I shall pass over the works of numerous divines, who may be excused for sensitiveness on points which then excited so much uneasiness in the public mind; and shall say nothing of the amiable poet Cowper[†], who could hardly be expected to have inquired into the merit of doctrines in physics. But in the foremost ranks of the intolerant are found several laymen who had high claims to scientific reputation. Among these appears Williams, a mineral surveyor of Edinburgh, who published a "Natural History of the Mineral

---

[*] As an instance of his desire to throw doubt indiscriminately on all geological data, we may recall the passage where he says, that "the bones of a reindeer and hippopotamus discovered near Etampes did not prove, as some would have it, that Lapland and the Nile were once on a tour from Paris to Orleans, but merely that a lover of curiosities once preserved them in his cabinet."

[†] "Some drill and bore
The solid earth, and from the strata there
Extract a register, by which we learn,
That he who made it, and revealed its date
To Moses, was mistaken in its age."
The Task, book iii. "The Garden."

Kingdom," in 1789; a work of great merit for that day, a practical utility, as containing the best account of the coal In his preface he misrepresents Hutton's theory altogether, charges him with considering all rocks to be lavas of diff colours and structure; and also with "warping every thi support the eternity of the world."* He descants on the perni influence of such sceptical notions, as leading to downright inf and atheism, "and as being nothing less than to depose the Alm Creator of the universe from his office."†

Kirwan—De Luc.—Kirwan, president of the Royal Acade Dublin, a chemist and mineralogist of some merit, but who pos much greater authority in the scientific world than he was en by his talents to enjoy, said, in the introduction to his "Geol Essays, 1799," "that *sound* geology *graduated* into religion, an required to dispel certain systems of atheism or infidelity, of they had had recent experience."‡ He was an uncompro defender of the aqueous theory of all rocks, and was sc surpassed by Burnet and Whiston, in his desire to adduce the M writings in confirmation of his opinions.

De Luc, in the preliminary discourse to his Treatise on Geo says, "the weapons have been changed by which revealed relig attacked; it is now assailed by geology, and the knowledge o science has become essential to theologians." He imputes the f of former geological systems to their having been anti-Mosaica directed against a "sublime tradition." These and similar tations, reiterated in the works of De Luc, seem to have been for granted by some modern writers: it is therefore necess state, in justice to the numerous geologists of different nations, works have been considered, that none of them were gui endeavouring, by arguments drawn from physics, to inva scriptural tenets. On the contrary, the majority of those wh fortunate enough "to discover the true causes of things," deserved another part of the poet's panegyric, "*Atque metus subjecit pedibus.*" The caution, and even timid reserve, of eminent Italian authors of the earlier period is very apparent there can hardly be a doubt, that they subscribed to certain d and particularly to the first diluvian theory, out of defere popular prejudices, rather than from conviction. If they were of dissimulation, we may feel regret, but must not blame thei of moral courage, reserving rather our condemnation for the rance of the times, and that inquisitorial power which forced to abjure, and the two Jesuits to disclaim the theory of Newto

---

* P. 577.

† P. 59.

‡ Introd. p. 2.

§ London, 1809.

|| In a most able article, by Mr. Drinkwater, on the "Life of Galileo," published in the "Library of Useful Knowledge," it is stated that both Galileo's work, and *the book of* Copernicus "Nisi corrigatur" (for, with the omission of certa sages, it was sanctioned), were sti seen on the forbidden list of the I Rome in 1828. I was, however, in the same year, by Professor Sca at Rome, that Pius VII., a pont tinguished for his love of scien procured a repeal of the edicts Galileo and the Copernican syste

Hutton answered Kirwan's attacks with great warmth, and with the indignation justly excited by unmerited reproach. "He had always displayed," says Playfair, "the utmost disposition to admire the beneficent design manifested in the structure of the world; and he contemplated with delight those parts of his theory which made the greatest additions to our knowledge of final causes." We may say with equal truth, that in no scientific works in our language can more eloquent passages be found, concerning the fitness, harmony, and grandeur of all parts of the creation, than in those of Playfair. They are evidently the unaffected expressions of a mind, which contemplated the study of nature, as best calculated to elevate our conceptions of the attributes of the First Cause. At any other time the force and elegance of Playfair's style must have insured popularity to the Huttonian doctrines; but by a singular coincidence, Neptunianism and orthodoxy were now associated in the same creed; and the tide of prejudice ran so strong, that the majority were carried far away into the chaotic fluid, and other cosmological inventions of Werner. These fictions the Saxon professor had borrowed with little modification, and without any improvement, from his predecessors. They had not the smallest foundation either in Scripture or in common sense, and were probably approved of by many as being so ideal and unsubstantial, that they could never come into violent collision with any pre-conceived opinions.

According to De Luc, the first essential distinction to be made between the various phenomena exhibited on the surface of the earth was, to determine which were the results of causes still in action, and which had been produced by causes that had ceased to act. The form and composition of the mass of our continents, he said, and their existence above the level of the sea, must be ascribed to causes no longer in action. These continents emerged, at no very remote period, on the sudden retreat of the ocean, the waters of which made their way into subterranean caverns. The formation of the rocks which enter into the crust of the earth began with the precipitation of granite from a primordial liquid, after which other strata containing the remains of organized bodies were deposited, till at last the present sea remained as the residuum of the primordial liquid, and no longer continued to produce mineral strata.*

William Smith, 1790.—While the tenets of the rival schools of Freyberg and Edinburgh were warmly espoused by devoted partisans the labours of an individual, unassisted by the advantages of wealth or station in society were almost unheeded. Mr. William Smith, an

---

had assembled the Congregation; and the late Cardinal Toriozzi, assessor of the Sacred Office, proposed "that they should wipe off this scandal from the church." The repeal was carried, with the dissentient voice of one Dominican only. Long before that time the Newtonian theory had been taught in the Sapienza, and all Catholic universities in Europe (with the exception, I am told, of Salamanca); but it was always required of professors, in deference to the decrees of the church, to use the term *hypothesis*, instead of theory. They now speak of the Copernican *theory*.

* Elementary Treatise on Geology. London, 1809. Translated by De la Fite.

English surveyor, published his "Tabular View of the Bri Strata" in 1790, wherein he proposed a classification of the secon formations in the West of England. Although he had not com nicated with Werner, it appeared by this work that he had arriv the same views respecting the laws of superposition of stratified ro that he was aware that the order of succession of different gr was never inverted; and that they might be identified at very dis points by their peculiar organized fossils.

From the time of the appearance of the "Tabular View," author laboured to construct a geological map of the whole of Engl and with the greatest disinterestedness of mind, communicated results of his investigations to all who desired information, gi such publicity to his original views, as to enable his contempor almost to compete with him in the race. The execution of his was completed in 1815, and remains a lasting monument of ori talent and extraordinary perseverance; for he had explored whole country on foot without the guidance of previous observe the aid of fellow-labourers, and had succeeded in throwing natural divisions the whole complicated series of British r D'Aubuisson, a distinguished pupil of Werner, paid a just tribu praise to this remarkable performance, observing, that "what t celebrated mineralogists had only accomplished for a small pa Germany in the course of half a century, had been effected single individual for the whole of England."*

Werner invented a new language to express his divisions of r and some of his technical terms, such as grauwacke, gneiss, others, passed current in every country in Europe. Smith ad for the most part English provincial terms, often of barbarous so such as gault, cornbrash, clunch clay; and affixed them to s visions of the British series. Many of these still retain their pla our scientific classifications, and attest his priority of arrangeme

MODERN PROGRESS OF GEOLOGY.

The contention of the rival factions of the Vulcanists and Neptu had been carried to such a height, that these names had become of reproach; and the two parties had been less occupied in sear for truth, than for such arguments as might strengthen their own or serve to annoy their antagonists. A new school at last arose professed the strictest neutrality, and the utmost indifference t systems of Werner and Hutton, and who resolved diligently to c their labours to observation. The reaction, provoked by th temperance of the conflicting parties now produced a tenden extreme caution. Speculative views were discountenanced, through fear of exposing themselves to the suspicion of a bias to the dogmas of a party, some geologists became anxious to ent no opinion whatever on the causes of phenomena, and were in to scepticism even where the conclusions deducible from observed facts scarcely admitted of reasonable doubt.

---

* See Dr. Fitton's Memoir, before cited, p. 57.

Geological Society of London.—But although the reluctance to theorize was carried somewhat to excess, no measure could be more salutary at such a moment than a suspension of all attempts to form what were termed "theories of the earth." A great body of new data were required; and the Geological Society of London, founded in 1807, conduced greatly to the attainment of this desirable end. To multiply and record observations, and patiently to await the result at some future period, was the object proposed by them; and it was their favourite maxim that the time was not yet come for a general system of geology, but that all must be content for many years to be exclusively engaged in furnishing materials for future generalizations. By acting up to these principles with consistency, they in a few years disarmed all prejudice, and rescued the science from the imputation of being a dangerous, or at best but a visionary pursuit.

A distinguished modern writer has with truth remarked, that the advancement of three of the main divisions of geological inquiry have during the last half century, been promoted successively by three different nations of Europe,—the Germans, the English, and the French.* We have seen that the systematic study of what may be called mineralogical geology had its origin and chief point of activity in Germany, where Werner first described with precision the mineral characters of rocks. The classification of the secondary formations, each marked by their peculiar fossils, belongs, in a great measure, to England, where the labours before alluded to of Smith, and those of the most active members of the Geological Society of London, were steadily directed to these objects. The foundation of the third branch, that relating to the tertiary formations, was laid in France by the splendid work of Cuvier and Brongniart, published in 1808, "On the Mineral Geography and Organic Remains of the Neighbourhood of Paris."

We may still trace, in the language of the science and our present methods of arrangement, the various countries where the growth of these several departments of geology was at different times promoted. Many names of simple minerals and rocks remain to this day German; while the European divisions of the secondary strata are in great part English, and are, indeed, often founded too exclusively on English types. Lastly, the subdivisions first established of the succession of strata in the Paris basin have served as normal groups to which other tertiary deposits throughout Europe have been compared, even in cases where this standard was wholly inapplicable.

No period could have been more fortunate for the discovery, in the immediate neighbourhood of Paris, of a rich store of well-preserved fossils, than the commencement of the present century; for at no former era had Natural History been cultivated with such enthusiasm in the French metropolis. The labours of Cuvier in comparative

---

* Whewell, British Critic, No. xvii. p. 187. 1831.

recent and fossil shells, had raised th
rank of which they had never previo
Their investigations had eventuall
the illusion which had long prevailed c
analogy between the ancient and modern s
comparison of the recent and fossil spe
in regard to their habits, accustomed
the earth as having been at successive per
animals and plants of different races, s
aquatic—some fitted to live in seas, others in
By the consideration of these topics,
insensibly withdrawn from imaginary pict
chaotic confusion, such as haunted the imagina
Numerous proofs were discovered of
sedimentary matter, and the slow developm
writers, and Cuvier himself in the num
maintain, that "the thread of induction
reasoning by the strict rules of induction from re
in a great measure disclaimed the dogma w
The adoption of the same generic, an
same specific, names for the exuviæ of f
analogues, was an important step tow
the idea of the identity and unity o
It was an acknowledgment, as it were,
memorials of nature were written
importance, then, of the natural hi
out as the characteristic featu
during the present century. This br
an instrument of great utili
is continuing daily to unfold new
respecting the former changes o

observations in the last fifty
centuries, we cannot but look for
to the degree of excellen
even by the labours of the pr
any science, with the excepti
period, so many novel an
many preconceived opinions.
to be at rest, until the astron
space with inconceivable rap
of this planet regarded as h
until the geologist proved
change, and was still the su
The discovery of other sy
was the triumph of astronom
various transformations—to beh

&c.

at successive eras adorned with different hills and valleys, lakes and seas, and peopled with new inhabitants, was the delightful meed of geological research. By the geometer were measured the regions of space, and the relative distances of the heavenly bodies;—by the geologist myriads of ages were reckoned, not by arithmetical computation, but by a train of physical events — a succession of phenomena in the animate and inanimate worlds — signs which convey to our minds more definite ideas than figures can do of the immensity of time.

Whether our investigation of the earth's history and structure will eventually be productive of as great practical benefits to mankind as a knowledge of the distant heavens, must remain for the decision of posterity. It was not till astronomy had been enriched by the observations of many centuries, and had made its way against popular prejudices to the establishment of a sound theory, that its application to the useful arts was most conspicuous. The cultivation of geology began at a later period; and in every step which it has hitherto made towards sound theoretical principles, it has had to contend against more violent prepossessions. The practical advantages already derived from it have not been inconsiderable; but our generalizations are yet imperfect, and they who come after us may be expected to reap the most valuable fruits of our labour. Meanwhile the charm of first discovery is our own; and, as we explore this magnificent field of inquiry, the sentiment of a great historian of our times may continually be present to our minds, that "he who calls what has vanished back again into being, enjoys a bliss like that of creating."*

CHAPTER V.

PREJUDICES WHICH HAVE RETARDED THE PROGRESS OF GEOLOGY.

Prepossessions in regard to the duration of past time — Prejudices arising from our peculiar position as inhabitants of the land — Of those occasioned by our not seeing subterranean changes now in progress — All these causes combine to make the former course of Nature appear different from the present — Objections to the doctrine, that causes similar in kind and energy to those now acting, have produced the former changes of the earth's surface, considered.

If we reflect on the history of the progress of geology, as explained in the preceding chapters, we perceive that there have been great fluctuations of opinion respecting the nature of the causes to which all former changes of the earth's surface are referable. The first observers conceived the monuments which the geologist endeavours to decipher to relate to an original state of the earth, or to a period when there were causes in activity, distinct, in kind and degree, from those now constituting the economy of nature. These views w gradually modified, and some of them entirely abandoned in prop tion as observations were multiplied, and the signs of former mutati more skilfully interpreted. Many appearances, which had for a l time been regarded as indicating mysterious and extraordinary agen were finally recognized as the necessary result of the laws now gove ing the material world; and the discovery of this unlooked-for u formity has at length induced some philosophers to infer, that, duri the ages contemplated in geology, there has never been any int ruption to the agency of the same uniform laws of change. The sa assemblage of general causes, they conceive, may have been suffici to produce, by their various combinations, the endless diversity effects, of which the shell of the earth has preserved the memori and, consistently with these principles, the recurrence of analog changes is expected by them in time to come.

---

* Niebuhr's Hist. of Rome, vol. i. p. 5. Hare and Thirlwall's translation.

Whether we coincide or not in this doctrine, we must admit t the gradual progress of opinion concerning the succession of phe mena in very remote eras, resembles, in a singular manner, t which has accompanied the growing intelligence of every people regard to the economy of nature in their own times. In an ea state of advancement, when a great number of natural appeara are unintelligible, an eclipse, an earthquake, a flood, or the appro of a comet, with many other occurrences afterwards found to bel to the regular course of events, are regarded as prodigies. The sa delusion prevails as to moral phenomena, and many of these ascribed to the intervention of demons, ghosts, witches, and ot immaterial and supernatural agents. By degrees, many of enigmas of the moral and physical world are explained, and, inst of being due to extrinsic and irregular causes, they are found to pend on fixed and invariable laws. The philosopher at last beco convinced of the undeviating uniformity of secondary causes; guided by his faith in this principle, he determines the probabilit accounts transmitted to him of former occurrences, and often rej the fabulous tales of former times, on the ground of their being i concilable with the experience of more enlightened ages.

Prepossessions in regard to the duration of past time.—A belief in the want of conformity in the causes by which the ea crust has been modified in ancient and modern periods was, for a time, universally prevalent, and that, too, amongst men who were vinced that the order of nature had been uniform for the last sev thousand years, every circumstance which could have influenced t minds and given an undue bias to their opinions deserves partic attention. Now the reader may easily satisfy himself, that, how undeviating the course of nature may have been from the ear epochs, it was impossible for the first cultivators of geology to c [illegible] conclusion, so long as they were under a delusion a [illegible] the world, and the date of the first creation of ani beings. However fantastical some theories of the sixteenth cen [illegible] appear to us,—however unworthy of men of great t and sound judgment,—we may rest assured that, if the same misconception now prevailed in regard to the memorials of human transactions, it would give rise to a similar train of absurdities. Let us imagine, for example, that Champollion, and the French and Tuscan literati lately engaged in exploring the antiquities of Egypt, had visited that country with a firm belief that the banks of the Nile were never peopled by the human race before the beginning of the nineteenth century, and that their faith in this dogma was as difficult to shake as the opinion of our ancestors, that the earth was never the abode of living beings until the creation of the present continents, and of the species now existing,—it is easy to perceive what extravagant systems they would frame, while under the influence of this delusion, to account for the monuments discovered in Egypt. The sight of the pyramids, obelisks, colossal statues, and ruined temples, would fill them with such astonishment, that for a time they would be as men spell-bound—wholly incapable of reasoning with sobriety. They might incline at first to refer the construction of such stupendous works to some superhuman powers of a primeval world. A system might be invented resembling that so gravely advanced by Manetho, who relates that a dynasty of gods originally ruled in Egypt, of whom Vulcan, the first monarch, reigned nine thousand years; after whom came Hercules and other demigods, who were at last succeeded by human kings.

When some fanciful speculations of this kind had amused their imaginations for a time, some vast repository of mummies would be discovered, and would immediately undeceive those antiquaries who enjoyed an opportunity of personally examining them; but the prejudices of others at a distance, who were not eye-witnesses of the whole phenomena, would not be so easily overcome. The concurrent report of many travellers would, indeed, render it necessary for them to accommodate ancient theories to some of the new facts, and much wit and ingenuity would be required to modify and defend their old positions. Each new invention would violate a greater number of known analogies; for if a theory be required to embrace some false principle, it becomes more visionary in proportion as facts are multiplied, as would be the case if geometers were now required to form an astronomical system on the assumption of the immobility of the earth.

Amongst other fanciful conjectures concerning the history of Egypt, we may suppose some of the following to be started. "As the banks of the Nile have been so recently colonized for the first time, the curious substances called mummies could never in reality have belonged to men. They may have been generated by some *plastic virtue* residing in the interior of the earth, or they may be abortions of Nature produced by her incipient efforts in the work of creation. For if deformed beings are sometimes born even now, when the scheme of the universe is fully developed, many more may have been 'sent before their time, scarce half made up,' when the planet itself was in the embryo state. But if these notions appear to derogate from the perfection of the Divine attributes, and if these mummies be in all their parts true representations of the human form, may we not them to the future rather than the past?—May we not be lo into the womb of Nature, and not her grave? May not images be like the shades of the unborn in Virgil's Elysium—archetypes of men not yet called into existence?"

These speculations, if advocated by eloquent writers, would fail to attract many zealous votaries, for they would relieve men the painful necessity of renouncing preconceived opinions. credible as such scepticism may appear, it has been rivalled by systems of the sixteenth and seventeenth centuries, and among by that of the learned Falloppio, who regarded the tusks of fossil phants as earthy concretions, and the pottery or fragments of vas the Monte Testaceo, near Rome, as works of nature, and not of But when one generation had passed away, and another, not com mitted to the support of antiquated dogmas, had succeeded, would review the evidence afforded by mummies more imparti and would no longer controvert the preliminary question, human beings had lived in Egypt before the nineteenth centur that when a hundred years perhaps had been lost, the industr talents of the philosopher would be at last directed to the elucid of points of real historical importance.

But the above arguments are aimed against one only of prejudices with which the earlier geologists had to contend. when they conceded that the earth had been peopled with ani beings at an earlier period than was at first supposed, they h conception that the quantity of time bore so great a proporti the historical era as is now generally conceded. How fatal error as to the quantity of time must prove to the introducti rational views concerning the state of things in former ages, m conceived by supposing the annals of the civil and military tra tions of a great nation to be perused under the impression that occurred in a period of one hundred instead of two thousand Such a portion of history would immediately assume the air romance, the events would seem devoid of credibility, and i [illegible] with the present course of human affairs. A crow [illegible] would follow each other in thick succession. Armie [illegible] would appear to be assembled only to be destroyed, and [illegible] to fall in turns. There would be the most v [illegible] from foreign or intestine war to periods of pro [illegible] works effected during the years of disorder or [illegible] would appear alike superhuman in magnitude.

[illegible] study the monuments of the natural world [illegible] infatuation, must draw a no less exagg [illegible] and violence of causes, and must experien [illegible] difficulty in reconciling the former and p [illegible] If we could behold in one view all the vo [illegible] in Iceland, Italy, Sicily, and other parts of E [illegible] thousand years, and could see the lavas [illegible] period; the dislocations, subsidenc elevations caused during earthquakes; the lands added to various deltas, or devoured by the sea, together with the effects of devastation by floods, and imagine that all these events had happened in one year, we must form most exalted ideas of the activity of the agents, and the suddenness of the revolutions. Were an equal amount of change to pass before our eyes in the next year, could we avoid the conclusion that some great crisis of nature was at hand? If geologists, therefore, have misinterpreted the signs of a succession of events, so as to conclude that centuries were implied where the characters imported thousands of years, and thousands of years where the language of Nature signified millions, they could not, if they reasoned logically from such false premises, come to any other conclusion than that the system of the natural world had undergone a complete revolution.

(a

We should be warranted in ascribing the erection of the great pyramid to superhuman power, if we were convinced that it was raised in one day; and if we imagine, in the same manner, a continent or mountain-chain to have been elevated, during an equally small fraction of the time which was really occupied in upheaving it, we might then be justified in inferring, that the subterranean movements were once far more energetic than in our own times. We know that during one earthquake the coast of Chili may be raised for a hundred miles to the average height of about three feet. A repetition of two thousand shocks, of equal violence, might produce a mountain-chain one hundred miles long, and six thousand feet high. Now, should one or two only of these convulsions happen in a century, it would be consistent with the order of events experienced by the Chilians from the earliest times: but if the whole of them were to occur in the next hundred years, the entire district must be depopulated, scarcely any animals or plants could survive, and the surface would be one confused heap of ruin and desolation.

b)

One consequence of undervaluing greatly the quantity of past time, is the apparent coincidence which it occasions of events necessarily disconnected, or which are so unusual, that it would be inconsistent with all calculation of chances to suppose them to happen at one and the same time. When the unlooked-for association of such rare phenomena is witnessed in the present course of nature, it scarcely ever fails to excite a suspicion of the preternatural in those minds which are not firmly convinced of the uniform agency of secondary causes;—as if the death of some individual in whose fate they are interested happens to be accompanied by the appearance of a luminous meteor, or a comet, or the shock of an earthquake. It would be only necessary to multiply such coincidences indefinitely, and the mind of every philosopher would be disturbed. Now it would be difficult to exaggerate the number of physical events, many of them most rare and unconnected in their nature, which were imagined by the Woodwardian hypothesis to have happened in the course of a few months: and numerous other examples might be found of popular geological theories, which require us to imagine that a long suc of events happened in a brief and almost momentary period.

C Another liability to error, very nearly allied to the former, from the frequent contact of geological monuments referring t distant periods of time. We often behold, at one glance, the ef causes which have acted at times incalculably remote, and yet may be no striking circumstances to mark the occurrence of a chasm in the chronological series of Nature's archives. In th interval of time which may really have elapsed between the of operations thus compared, the physical condition of the eart by slow and insensible modifications, have become entirely al one or more races of organic beings may have passed away, a have left behind, in the particular region under contemplati trace of their existence.

To a mind unconscious of these intermediate events, the p from one state of things to another must appear so violent, th idea of revolutions in the system inevitably suggests itself. imagination is as much perplexed by the deception, as it might two distant points in space were suddenly brought into imm proximity. Let us suppose, for a moment, that a philosopher lie down to sleep in some arctic wilderness, and then be trans by a power, such as we read of in tales of enchantment, to a in a tropical country, where, on awaking, he might find himsel rounded by birds of brilliant plumage, and all the luxuria animal and vegetable forms of which Nature is so prodigal i regions. The most reasonable supposition, perhaps, which he make, if by the necromancer's art he were placed in such a sit would be, that he was dreaming; and if a geologist form t under a similar delusion, we cannot expect him to preserve consistency in his speculations than in the train of ideas in a nary dream.

It may afford, perhaps, a more lively illustration of the pr here insisted upon, if I recall to the reader's recollection the of the Seven Sleepers. The scene of that popular fable was in the two centuries which elapsed between the reign of the e Decius and the death of Theodosius the younger. In that i of time (between the years 249 and 450 of our era) the union Roman empire had been dissolved, and some of its fairest pr overrun by the barbarians of the north. The seat of gove had passed from Rome to Constantinople, and the throne pagan persecutor to a succession of Christian and orthodox The genius of the empire had been humbled in the dust, altars of Diana and Hercules were on the point of being tran to Catholic saints and martyrs. The legend relates, "tha Decius was still persecuting the Christians, seven noble yo Ephesus concealed themselves in a spacious cavern in the sid adjacent mountain, where they were doomed to perish by the who gave orders that the entrance should be firmly secured wit of huge stones. They immediately fell into a deep slumber ously prolonged, without injuring the powers of life, iod of 187 years. At the end of that time the slaves of rhom the inheritance of the mountain had descended, re- stones to supply materials for some rustic edifice: the : sun darted into the cavern, and the seven sleepers ted to awake. After a slumber, as they thought, of a few were pressed by the calls of hunger, and resolved that one of their number, should secretly return to the city to ead for the use of his companions. The youth could no nise the once familiar aspect of his native country, and was increased by the appearance of a large cross trium- cted over the principal gate of Ephesus. His singular solete language confounded the baker, to whom he offered nedal of Decius as the current coin of the empire; and on the suspicion of a secret treasure, was dragged before Their mutual inquiries produced the amazing discovery, enturies were almost elapsed since Jamblichus and his escaped from the rage of a pagan tyrant."*

end was received as authentic throughout the Christian re the end of the sixth century, and was afterwards by Mahomet as a divine revelation into the Koran, and was adopted and adorned by all the nations from Bengal ho professed the Mahometan faith. Some vestiges even r tradition have been discovered in Scandinavia. "This iversal belief," observes the philosophical historian of the l Fall, "so expressive of the sense of mankind, may be the genuine merit of the fable itself. We imperceptibly om youth to age, without observing the gradual, but hange of human affairs; and even, in our larger experience the imagination is accustomed, by a perpetual series of effects, to unite the most distant revolutions. But if the etween two memorable eras could be instantly annihilated; possible, after a momentary slumber of two hundred years, the new world to the eyes of a spectator who still retained id recent impression of the old, his surprise and his re rould furnish the pleasing subject of a philosophical ro-

ces arising from our peculiar position as inhabitants of the he sources of prejudice hitherto considered may be deemed or the most part to the infancy of the science, but others on to the first cultivators of geology and to ourselves, and igularly calculated to produce the same deception, and to our belief that the course of nature in the earlier ages idely from that now established. Although these circum- annot be fully explained without assuming some things as hich it will be the object of another part of this work to te, it may be well to allude to them briefly in this place.

---

* Gibbon, Decline and Fall, chap. xxxiii.

† Id. Ibid.

The first and greatest difficulty, then, consists in an consciousness that our position as observers is essenti able, when we endeavour to estimate the nature and mag changes now in progress. In consequence of our inatt subject, we are liable to serious mistakes in contrasting with former states of the globe. As dwellers on the land about a fourth part of the surface; and that portion is clusively a theatre of decay, and not of reproduction. indeed, that new deposits are annually formed in seas and that every year some new igneous rocks are produced in of the earth, but we cannot watch the progress of their and as they are only present to our minds by the aid of requires an effort both of the reason and the imagin preciate duly their importance. It is, therefore, not sur we estimate very imperfectly the result of operations th to us; and that, when analogous results of former epoc sented to our inspection, we cannot immediately re analogy. He who has observed the quarrying of stone fr and has seen it shipped for some distant port, and then to conceive what kind of edifice will be raised by the ma the same predicament as a geologist, who, while he is the land, sees the decomposition of rocks, and the trans matter by rivers to the sea, and then endeavours to pictur the new strata which Nature is building beneath the wat

Prejudices arising from our not seeing subterranean Nor is his position less unfavourable when, beholding eruption, he tries to conceive what changes the column produced, in its passage upwards, on the intersected stra form the melted matter may assume at great depths on what may be the extent of the subterranean rivers and liquid matter far beneath the surface. It should, there membered, that the task imposed on those who study history requires no ordinary share of discretion; for we are from collating the corresponding parts of the system of exists now, and as it existed at former periods. If we bitants of another element—if the great ocean were instead of the narrow limits of the land, our difficulties considerably lessened; while, on the other hand, there doubt, although the reader may, perhaps, smile at the bare of such an idea, that an amphibious being, who should faculties, would still more easily arrive at sound theoreti in geology, since he might behold, on the one hand, position of rocks in the atmosphere, or the transportatio by running water; and, on the other, examine the d sediment in the sea, and the imbedding of animal an remains in new strata. He might ascertain, by direct the action of a mountain torrent, as well as of a mar might compare the products of volcanos poured out with those ejected beneath the waters; and might mark hand, the growth of the forest, and, on the other, that of the coral reef. Yet, even with these advantages, he would be liable to fall into the greatest errors, when endeavouring to reason on rocks of subterranean origin. He would seek in vain, within the sphere of his observation, for any direct analogy to the process of their formation, and would therefore be in danger of attributing them, wherever they are upraised to view, to some "primeval state of nature."

But if we may be allowed so far to indulge the imagination, as to suppose a being entirely confined to the nether world—some "dusky melancholy sprite," like Umbriel, who could "flit on sooty pinions to the central earth," but who was never permitted to "sully the fair face of light," and emerge into the regions of water and of air; and if this being should busy himself in investigating the structure of the globe, he might frame theories the exact converse of those usually adopted by human philosophers. He might infer that the stratified rocks, containing shells and other organic remains, were the oldest of created things, belonging to some original and nascent state of the planet. "Of these masses," he might say, "whether they consist of loose incoherent sand, soft clay, or solid stone, none have been formed in modern times. Every year some part of them are broken and hattered by earthquakes, or melted by volcanic fire; and when they ool down slowly from a state of fusion, they assume a new and more rystalline form, no longer exhibiting that stratified disposition and hose curious impressions and fantastic markings, by which they ere previously characterized. This process cannot have been rried on for an indefinite time, for in that case all the stratified cks would long ere this have been fused and crystallized. It is erefore probable that the whole planet once consisted of these ysterious and curiously bedded formations at a time when the lcanic fire had not yet been brought into activity. Since that riod there seems to have been a gradual development of heat; and is augmentation we may expect to continue till the whole globe all be in a state of fluidity and incandescence."

Such might be the system of the Gnome at the very time that the llowers of Leibnitz, reasoning on what they saw on the outer surce, might be teaching the opposite doctrine of gradual refrigeram, and averring that the earth had begun its career as a fiery met, and might be destined hereafter to become a frozen mass. he tenets of the schools of the nether and of the upper world would directly opposed to each other, for both would partake of the ejudices inevitably resulting from the continual contemplation of e class of phenomena to the exclusion of another. Man observes e annual decomposition of crystalline and igneous rocks, and may metimes see their conversion into stratified deposits; but he cannot tness the reconversion of the sedimentary into the crystalline by bterranean fire. He is in the habit of regarding all the sedimentary cks as more recent than the unstratified, for the same reason that may suppose him to fall into the opposite error if he saw the igin of the igneous class only.

It was not an impossible contingency, that astronomers migh
been placed at some period in a situation much resembling t
which the geologist seems to stand at present. If the Italia
example, in the early part of the twelfth century, had discove
Amalfi, instead of the pandects of Justinian, some ancient
scripts filled with astronomical observations relating to a pe
three thousand years, and made by some ancient geometers wh
sessed optical instruments as perfect as any in modern Europe
would probably, on consulting these memorials, have come to
clusion that there had been a great revolution in the solar and s
systems. "Many primary and secondary planets," they migh
"are enumerated in these tables, which exist no longer.
positions are assigned with such precision that we may assu
selves that there is nothing in their place at present but the blu
Where one star is visible to us, these documents represent
thousands. Some of those which are now single consisted then
separate bodies, often distinguished by different colours, and rev
periodically round a common centre of gravity. There is
analogous to them in the universe at present; for they were
fixed stars nor planets, but seem to have stood in the mutual
of sun and planet to each other. We must conclude, therefo
there has occurred, at no distant period, a tremendous catas
whereby thousands of worlds have been annihilated at once, an
heavenly bodies absorbed into the substance of others."

When such doctrines had prevailed for ages, the discovery
of the worlds, supposed to have been lost (the satellites of Jupi
example), by aid of the first rude telescope invented after the
of science, would not dissipate the delusion, for the whole bu
proof would now be thrown on those who insisted on the sta
the system from a remote period, and these philosophers w
required to demonstrate the existence of *all* the worlds said
been annihilated.

Such popular prejudices would be most unfavourable to
vancement of astronomy; for, instead of persevering in the
to improve their instruments, and laboriously to make and
observations, the greater number would despair of verifying t
tinued existence of the heavenly bodies not visible to the na
Instead of confessing the extent of their ignorance, and stri
remove it by bringing to light new facts, they would indulg
more easy and indolent employment of framing imaginary
concerning catastrophes and mighty revolutions in the syste
universe.

For more than two centuries the shelly strata of the Suba
hills afforded matter of speculation to the early geologists of It
few of them had any suspicion that similar deposits were then
in the neighbouring sea. They were as unconscious of the co
action of causes still producing similar effects, as the astrono
the case above supposed, of the existence of certain heavenl
still giving and reflecting light, and performing their moven

l. Some imagined that the strata, so rich in organic remains,
d of being due to secondary agents, had been so created in the
ning of things by the fiat of the Almighty. Others, as we have
ascribed the imbedded fossil bodies to some plastic power which
d in the earth in the early ages of the world. In what manner
these dogmas at length exploded? The fossil relics were care-
compared with their living analogues, and all doubts as to their
ic origin were eventually dispelled. So, also, in regard to the
of the containing beds of mud, sand, and limestone: those
of the bottom of the sea were examined where shells are now
ing annually entombed in new deposits. Donati explored the
f the Adriatic, and found the closest resemblance between the
there forming, and those which constituted hills above a thou-
feet high in various parts of the Italian peninsula. He as-
ned by dredging that living testacea were there grouped together
cisely the same manner as were their fossil analogues in the
strata; and while some of the recent shells of the Adriatic
becoming incrusted with calcareous rock, he observed that others
een newly buried in sand and clay, precisely as fossil shells
in the Subapennine hills. This discovery of the identity of
n and ancient submarine operations was not made without the
artificial instruments, which, like the telescope, brought phe-
a into view not otherwise within the sphere of human obser-
l.

like manner, the volcanic rocks of the Vicentin had been studied (2)
beginning of the last century; but no geologist suspected,
the time of Arduino, that these were composed of ancient
rine lavas. During many years of controversy, the popular
n inclined to a belief that basalt and rocks of the same class
een precipitated from a chaotic fluid, or an ocean which rose at
sive periods over the continents, charged with the component
nts of the rocks in question. Few will now dispute that it would
been difficult to invent a theory more distant from the truth;
e must cease to wonder that it gained so many proselytes, when
member that its claims to probability arose partly from the very
nstance of its confirming the assumed want of analogy between
gical causes and those now in action. By what train of in-
ations were geologists induced at length to reject these views,
assent to the igneous origin of the trappean formations? By
amination of volcanos now active, and by comparing their
ure and the composition of their lavas with the ancient trap

e establishment, from time to time, of numerous points of iden-
ion, drew at length from geologists a reluctant admission, that
was more correspondence between the condition of the globe at
e eras and now, and more uniformity in the laws which have
ted the changes of its surface, than they at first imagined. If,
state of the science, they still despaired of reconciling every
f geological phenomena to the operations of ordinary causes,

even by straining analogy to the utmost limits of credibility, we have expected, at least, that the balance of probability would have been presumed to incline towards the close analogy of the a and modern causes. But, after repeated experience of the fail attempts to speculate on geological monuments, as belonging distinct order of things, new sects continued to persevere in the ciples adopted by their predecessors. They still began, as each problem presented itself, whether relating to the animate or inan world, to assume an original and dissimilar order of nature; and at length they approximated, or entirely came round to an op opinion, it was always with the feeling, that they were conceding they had been justified *à priori* in deeming improbable. In a the same men who, as natural philosophers, would have been incredulous respecting any extraordinary deviations from the k course of nature, if reported to have happened *in their own time* equally disposed, as geologists, to expect the proofs of such devi at every period of the past.

I shall proceed in the following chapters to enumerate some principal difficulties still opposed to the theory of the uniform and energy of the causes which have worked successive chan the crust of the earth, and in the condition of its living inhab The discussion of so important a question on the present oc may appear premature, but it is one which naturally arises on review of the former history of the science. It is, of cours possible to enter into such speculative topics, without occasi carrying the novice beyond his depth, and appealing to fac conclusions with which he will be unacquainted, until he has s some elementary work on geology, but it may be useful to exci curiosity, and lead him to study such works by calling his att at once to some of the principal points of controversy.*

---

* In the earlier editions of this work, a fourth book was added on Geology Proper, or Systematic Geology, containing an account of the former changes of the animate and inanimate creation, brought to light by an examination of the crust of the earth. This I afterwards (i expanded into a separate pub called the Elements or Manual logy, of which a fourth edition ap December, 1851.

CHAPTER VI.

DOCTRINE OF THE DISCORDANCE OF THE ANCIENT AND MODERN CAUSES OF CHANGE CONTROVERTED.

Climate of the Northern Hemisphere formerly different — Direct proofs from the organic remains of the Italian strata — Proofs from analogy derived from extinct quadrupeds — Imbedding of animals in icebergs — Siberian mammoths — Evidence in regard to temperature, from the fossils of tertiary and secondary rocks — From the plants of the coal formation — Northern limit of these fossils — Whether such plants could endure the long continuance of an arctic night.

Climate of the Northern hemisphere formerly different. — PROOFS of former revolutions in climate, as deduced from fossil remains, have afforded one of the most popular objections to the theory which endeavours to explain all geological changes by reference to those now in progress on the earth. The probable causes, therefore, of fluctuations in climate, may first be treated of.

That the climate of the Northern hemisphere has undergone an important change, and that its mean annual temperature must once have more nearly resembled that now experienced within the tropics, was the opinion of some of the first naturalists who investigated the contents of the ancient strata. Their conjecture became more probable when the shells and corals of the older tertiary and many secondary rocks were carefully examined; for the organic remains of these formations were found to be intimately connected by generic affinity with species now living in warmer latitudes. At a later period, many reptiles, such as turtles, tortoises, and large saurian animals, were discovered in European formations in great abundance; and they supplied new and powerful arguments, from analogy, in support of the doctrine, that the heat of the climate had been great when our secondary strata were deposited. Lastly, when the botanist turned his attention to the specific determination of fossil plants, the evidence acquired still fuller confirmation; for the flora of a country is peculiarly influenced by temperature: and the ancient vegetation of the earth might have been expected more readily than the forms of animals, to have afforded conflicting proofs, had the popular theory been without foundation. When the examination of fossil remains was extended to rocks in the most northern parts of Europe and North America, and even to the Arctic regions, indications of the same revolution in climate were discovered.

It cannot be said, that in this, as in many other departments of geology, we have investigated the phenomena of former eras, and neglected those of the present state of things. On the contrary,

[illegible] this interesting question, the accession
[illegible] animals and plants have been immense,
[illegible] the data previously obtained for gen
[illegible] certain types of organization to partic
[illegible] and temperate zones of South America
[illegible] explored: and, on close comparison, it
[illegible] any of the species of the animate creatio
[illegible] continents are identical with those inhabiting the
[illegible] and botanist, well acquainted with
[illegible] of organic beings in other parts of
[illegible] able, if distinct groups of species had
[illegible] from these regions, to recognize those which
[illegible] latitudes within, and those which were bro
[illegible]

[illegible] explain the probable causes of great vicissit
[illegible] earth's surface. I shall take a rapid vie
[illegible] data which appear to support the po
[illegible] on the subject. To insist on the soun
[illegible] the more necessary, because some zool
[illegible] the uniformity of the laws of na
[illegible] fluctuations in climate, but by der
[illegible] favour.*

[illegible] strata.—In Sicily, Cala
[illegible] Naples, the fossil testacea of the
[illegible] almost entirely to species
[illegible] as we proceed northwards i
[illegible] strata called Subapennin
[illegible] somewhat more widely fron
[illegible] proportion of species identi
[illegible] is still considerable
[illegible] South of Italy and part of S
[illegible] occurring in localities
[illegible] from the equator (as at Si
[illegible] clear indications of a w
[illegible] weight, and is not neutraliz
[illegible] such, for instance, as the as
[illegible] referable to species now co
[illegible] of the fossil shells are identified
[illegible] Mediterranean, it is not in the Nor
[illegible] that they must be sought: o
[illegible] species belong, for the most
[illegible] largely developed in equin
[illegible] genera Cancellaria, Cassidaria, P

[illegible] the tertiary deposits of Pari
[illegible] and these again with the

[illegible] Journ. No. xii. p. 277., April,
[illegible] and No. xv. p. 65., Jan. 1830.

modern strata of Sicily, we should at first expect that they would each indicate a higher temperature in proportion as they are situated farther to the south. But the contrary is true; of the shells belonging to these several groups, whether freshwater or marine, some are of extinct, others of living species. Those found in the older, or Eocene, deposits of Paris and London, although six or seven degrees to the north of the Miocene strata at Bordeaux, afford evidence of a warmer climate; while those of Bordeaux imply that the sea in which they lived was of a higher temperature than that of Sicily, where the shelly strata were formed six or seven degrees nearer to the equator. In these cases the greater antiquity of the several formations (the Parisian being the oldest and the Sicilian the newest) has more than counterbalanced the influence which latitude would otherwise exert, and this phenomenon clearly points to a gradual and successive refrigeration of climate.

Siberian Mammoths.—It will naturally be asked, whether some recent geological discoveries bringing evidence to light, of a colder, or as it has been termed "glacial epoch," towards the close of the tertiary periods throughout the northern hemisphere, does not conflict with the theory above alluded to, of a warmer temperature having prevailed in the eras of the Eocene, Miocene, and Pliocene formations. In answer to this enquiry, it may certainly be affirmed, that an oscillation of climate has occurred in times immediately antecedent to the peopling of the earth by man; but proof of the intercalation of a less genial climate at an era when nearly all the marine and terrestrial testacea had already become specifically the same as those now living, by no means rebuts the conclusion previously drawn, in favour of a warmer condition of the globe, during the ages which elapsed while the tertiary strata were deposited. In some of the most superficial patches of sand, gravel, and loam, scattered very generally over Europe, and containing recent shells, the remains of extinct species of land quadrupeds have been found, especially in places where the alluvial matter appears to have been washed into small lakes, or into depressions in the plains bordering ancient rivers. Similar deposits have also been lodged in rents and caverns of rocks, where they may have been swept in by land floods, or introduced by engulphed rivers during changes in the physical geography of these countries. The various circumstances under which the bones of animals have been thus preserved will be more fully considered hereafter *; I shall only state here, that among the extinct mammalia thus entombed, we find species of the elephant, rhinoceros, hippopotamus, bear, hyæna, lion, tiger, monkey (macacus †), and many others; consisting partly of genera now confined to warmer regions.

It is certainly probable that when some of these quadrupeds abounded in Europe, the climate was milder than that now ex enced. The hippopotamus, for example, is now only met with w the temperature of the water is warm and nearly uniform throug the year, and where the rivers are never frozen over. Yet whe great fossil species (*Hippopotamus major* Cuv.) inhabited England testacea of our country were nearly the same as those now existing, the climate cannot be supposed to have been very hot. The bon this animal have lately been found by Mr. Strickland, together w those of a bear and other mammalia, at Cropthorn, near Evesha Worcestershire, in alluvial sand, together with twenty-three speci terrestrial and freshwater shells, all, with two exceptions, of Bri species. The bed of sand, containing the shells and bones, repose lias, and is covered with alternating strata of gravel, sand, and lo

---

* Book iii. chaps. 46, 47, &c.

† Macacus pliocenus, Owen, Brit. Foss. Mam. Intr. p. 37., found with the extinct elephant, &c. in the modern freshwater beds at Grays Thurrock (Essex), in the valley of the Thames.

The mammoth also appears to have existed in England when temperature of our latitudes could not have been very different f that which now prevails; for remains of this animal have been fo at North Cliff, in the county of York, in a lacustrine formatio which all the land and freshwater shells, thirteen in number, ca identified with species and varieties now existing in that cou Bones of the bison also, an animal now inhabiting a cold or tempe climate, have been found in the same place. That these quadru and the indigenous species of testacea associated with them, wer contemporary inhabitants of Yorkshire, has been established unequivocal proof. The Rev. W. V. Vernon Harcourt caused to be sunk to the depth of twenty-two feet through undistu strata, in which the remains of the mammoth were found imbed together with the shells, in a deposit, which had evidently res from tranquil waters.†

In the valley of the Thames, as at Ilford and Grays, in E bones of the elephant and rhinoceros occur in strata aboundin freshwater shells of the genera Unio, Cyclas, Paludina, Val Ancylus, and others. These fossil shells belong for the most pa species now living in the same district, yet some few of them extinct, as, for example, a species of Cyrena, a genus no lo inhabiting Europe, and now entirely restricted to warmer latitud

When reasoning on such phenomena, the reader must always in mind that the fossil individuals belonged to *species* of elep rhinoceros, hippopotamus, bear, tiger, and hyæna, distinct those which now dwell within or near the tropics. Dr. Flemin a discussion on this subject, has well remarked that a near re blance in form and osteological structure is not always followe the existing creation, by a similarity of geographical distribu and we must therefore be on our guard against deciding too c dently, from mere analogy of anatomical structure, respecting habits and physiological peculiarities of *species* now no more. ' zebra delights to roam over the tropical plains; while the hors

---

[*] Geol. Proceedings, No. xxxvi. June, 1834.

[†] Phil. Mag., Sept. 1829, and 1830.

maintain its existence throughout an Iceland winter. The buffalo, like the zebra, prefers a high temperature, and cannot thrive even where the common ox prospers. The musk ox, on the other hand, though nearly resembling the buffalo, prefers the stinted herbage of the arctic regions, and is able, by its periodical migrations, to outlive a northern winter. The jackal (*Canis aureus*) inhabits Africa, the warmer parts of Asia, and Greece; while the isatis (*Canis lagopus*) resides in the arctic regions. The African hare and the polar hare have their geographical distribution expressed in their trivial names;"[*] and different species of bears thrive in tropical, temperate, and arctic latitudes.

Recent investigations have placed beyond all doubt the important fact that a species of tiger, identical with that of Bengal, is common in the neighbourhood of Lake Aral, near Sussac, in the forty-fifth degree of north latitude; and from time to time this animal is now seen in Siberia, in a latitude as far north as the parallel of Berlin and Hamburgh.[†] Humboldt remarks that the part of Southern Asia now inhabited by this Indian species of tiger is separated from the Himalaya by two great chains of mountains, each covered with perpetual snow,—the chain of Kuenlun, lat. 35° N., and that of Mouztagh, lat. 42°,—so that it is impossible that these animals should merely have made excursions from India, so as to have penetrated in summer to the forty-eighth and fifty-third degrees of north latitude. They must remain all the winter north of the Mouztagh, or Celestial Mountains. The last tiger killed, in 1828, on the Lena, in lat. 52¼°, was in a climate colder than that of Petersburg and Stockholm.[‡]

We learn from Mr. Hodgson's account of the mammalia of Nepal, that the tiger is sometimes found at the very edge of perpetual snow in the Himalaya[§]; and Pennant mentions that it is found among the snows of Mount Ararat in Armenia. The jaguar, also, has been seen in America, wandering from Mexico, as far north as Kentucky, lat. 37° N.[‖], and even as far as 42° S. in South America,—a latitude which corresponds to that of the Pyrenees in the northern hemisphere.[¶] The range of the puma is still wider, for it roams from the equator to the Straits of Magellan, being often seen at Port Famine, in lat. 53° 38′ S.

A new species of panther (*Felis irbis*), covered with long hair, has been discovered in Siberia, evidently inhabiting, like the tiger, a region north of the Celestial Mountains, which are in lat. 42°.[**]

The two-horned African rhinoceros occurs without the tropics at the Cape of Good Hope, in lat. 34° 29′ S., where it is accompanied by the elephant, hippopotamus, and hyæna. Here the migration of all these species towards the south is arrested by the ocean; but if continent had been prolonged still farther, and the land had bee moderate elevation, it is very probable that they might have exte their range to a greater distance from the tropics.

---

[*] Fleming, Ed. New Phil. Journ., No. xii. p. 282. 1829. The zebra, however, inhabits chiefly the extra-tropical parts of Africa.

[†] Humboldt, Fragmens de Géologie, &c., tome ii. p. 388. Ehrenberg, Ann. des Sci. Nat., tome xxi. p. 387.

[‡] Ehrenberg, ibid. p. 390.

[§] Journ. of Asiat. Soc., vol. i. p. 240.

[‖] Rafinesque, Atlantic Journ. p. 18.

[¶] Darwin's Journal of Travels in South America, &c. 1832 to 1836, in Voyage of H. M. S. Beagle, p. 159.

[**] Ehrenberg, ibid.

Now, if the Indian tiger can range in our own times to the south borders of Siberia, or skirt the snows of the Himalaya, and if puma can reach the fifty-third degree of latitude in South Ame we may easily understand how large species of the same *genera* once have inhabited our temperate climates. The mammoth *primigenius*), already alluded to, as occurring fossil in England, decidedly different from the two existing species of elephants, o which is limited to Asia, south of the 31° of N. lat., the oth Africa, where it extends, as before stated, as far south as the of Good Hope. The bones of the great fossil species are very w spread over Europe and North America; but are nowhere in profusion as in Siberia, particularly near the shores of the Fr Ocean. Are we, then, to conclude that this animal preferred a climate? If so, it may well be asked, by what food was it susta and why does it not still survive near the arctic circle?*

Pallas and other writers describe the bones of the mammo abounding throughout all the lowland of Siberia, stretching direction west and east, from the borders of Europe to the ext point nearest America, and south and north, from the base o mountains of Central Asia to the shores of the Arctic Sea. (See fig. 1.) Within this space, scarcely inferior in area to the wh Europe, fossil ivory has been collected almost everywhere, o banks of the Irtish, Obi, Yenesei, Lena, and other rivers. Th phantine remains do not occur in the marshes and low plain where the banks of the rivers present lofty precipices of sand and from which circumstance Pallas very justly inferred that, if se could be obtained, similar bones might be found in all the ele lands intervening between the great rivers. Strahlenberg, indeed stated, before the time of Pallas, that wherever any of the great overflowed and cut out fresh channels during floods, more remains of the same kind were invariably disclosed.

As to the position of the bones, Pallas found them in some imbedded together with marine remains; in others, simply fossil wood, or lignite, such, as he says, might have been de

---

* The speculations which follow, on the ancient physical geography of Siberia, and its former fitness as a residence for the mammoth, were first given in their present form in my 4th edition, June, 1835. Recently Sir R. Murchison and his companions in their great work on the Geology of Russia, 1845 (vol. i. p. 497.), have, in citing this chapter, declared that their investigations have led them to similar conclusions. Professor Owen, in his excellent History of British Fossil Mammalia, 1844, p. 261. *et seq.*, o that the teeth of the mammoth diff those of the living Asiatic or elephant in having a larger propo dense enamel, which may have en to subsist on the coarser ligneous of trees and shrubs. In short, h opinion, that the structure of its t well as the nature of its epiderm coverings, may have made it " companion for the reindeer."

Fig. 1.

MAP OF SIBERIA.



Map showing the course of the Siberian rivers from south to north, from temperate to arctic regions, in the country where the fossil bones of the Mammoth abound.

rom carbonized peat. On the banks of the Yenesei, below the city f Krasnojarsk, in lat. 56°, he observed grinders, and bones of elehants, in strata of yellow and red loam, alternating with coarse sand nd gravel, in which was also much petrified wood of the willow and her trees. Neither here nor in the neighbouring country were ere any marine shells, but merely layers of black coal.* But

---

* Pallas, Reise in Russ. Reiche, pp. 409, 410.

[illegible] of the mammoth were collected much farther down the river, near the sea, in lat. 70°, mixed with *marine* petrificatio Many other places in Siberia are cited by Pallas, where sea sh and fishes' teeth accompany the bones of the mammoth, rhinoce and Siberian buffalo, or bison (*Bos priscus*). But it is not on Obi nor the Yenesei, but on the Lena, farther to the east, where, the same parallels of latitude, the cold is far more intense, that fo remains have been found in the most wonderful state of preservati In 1772, Pallas obtained from Wiljuiskoi, in lat. 64°, from the ba of the Wiljui, a tributary of the Lena, the carcass of a rhinoce (*R. tichorhinus*), taken from the sand in which it must have remai congealed for ages, the soil of that region being always frozen within a slight depth of the surface. This carcass was compared a natural mummy, and emitted an odour like putrid flesh, part of skin being still covered with black and grey hairs. So great, ind was the quantity of hair on the foot and head conveyed to St. Pet burg, that Pallas asked whether the rhinoceros of the Lena mi not have been an inhabitant of the temperate regions of mi Asia, its clothing being so much warmer than that of the Afri rhinoceros.[†]

Professor Brandt, of St. Petersburg, in a letter to Baron A von Humboldt, dated 1846, adds the following particulars respect this wonderful fossil relic:—"I have been so fortunate as to ext from cavities in the molar teeth of the Wiljui rhinoceros a s quantity of its half-chewed food, among which fragments of leaves, one-half of the seed of a polygonaceous plant, and minute portions of wood with porous cells (or small fragment coniferous wood), were still recognisable. It was also remarkable, on investigation of the head, that the blood-vessels discovere the interior of the mass appeared filled, even to the capillary ves with a brown mass (coagulated blood), which in many places showed the red colour of blood."[‡]

After more than thirty years, the entire carcass of a mammot [illegible] species of elephant) was obtained in 1803, by Mr. Ad much farther to the north. It fell from a mass of ice, in whi had been encased, on the banks of the Lena, in lat. 70°; an perfectly had the soft parts of the carcass been preserved, that [illegible] lay, was devoured by wolves and bears. This skelet [illegible] the museum of St. Petersburg, the head retaining its int [illegible] many of the ligaments entire. The skin of the animal [illegible] with black bristles, thicker than horse hair, from tw [illegible] inches in length; secondly, with hair of a reddish br [illegible] four inches long; and thirdly, with wool of the [illegible] about an inch in length. Of the fur, upwar [illegible] weight were gathered from the wet sand-bank. [illegible] feet high and sixteen feet long, without recko

---

[*] [illegible] viii. p. 584.

[†] [illegible] viii. p. 591.

[‡] Quart. Journ. Geol. Soc. Lon iv. p. 10., Memoirs.

the large curved tusks : a size rarely surpassed by the largest living male elephants.*

It is evident, then, that the mammoth, instead of being naked, like the living Indian and African elephants, was enveloped in a thick shaggy covering of fur, probably as impenetrable to rain and cold as that of the musk ox.† The species may have been fitted by nature to withstand the vicissitudes of a northern climate ; and it is certain that, from the moment when the carcasses, both of the rhinoceros and elephant, above described, were buried in Siberia, in latitudes 64° and 70° N., the soil must have remained frozen, and the atmosphere nearly as cold as at this day.

The most recent discoveries made in 1843 by Mr. Middendorf, a distinguished Russian naturalist, and which he communicated to me in September 1846, afford more precise information as to the climate of the Siberian lowlands, at the period when the extinct quadrupeds were entombed. One elephant was found on the Tas, between the Obi and Yenesei, near the arctic circle, about lat. 66° 30′ N., with some parts of the flesh in so perfect a state that the bulb of the eye is now preserved in the Museum at Moscow. Another carcass, together with a young individual of the same species, was met with in the same year, 1843, in lat. 75° 15′ N., near the river Taimyr, with the flesh decayed. It was imbedded in strata of clay and sand, with erratic blocks, at about 15 feet above the level of the sea. In the same deposit Mr. Middendorf observed the trunk of a larch tree (*Pinus larix*), the same wood as that now carried down in abundance by the Taimyr, to the Arctic Sea. There were also associated fossil shells of *living northern* species, and which are moreover characteristic of the drift or *glacial* deposits of Europe. Among these *Nucula pygmæa*, *Tellina calcarea*, *Mya truncata*, and *Saxicava rugosa* were conspicuous.

So fresh is the ivory throughout northern Russia, that, according to Tilesius, thousands of fossil tusks have been collected and used in turning ; yet others are still procured and sold in great plenty declares his belief that the bones still left in northern Russi greatly exceed in number all the elephants now living on the

---

* Journal du Nord, St. Petersburg, 1807.

† Fleming, Ed. New Phil. Journ., No. xii., p. 285.

Bishop Heber informs us (Narr. of a Journey through the Upper Provinces of India, vol. ii. p. 166—219.), that in the lower range of the Himalaya mountains, in the north-eastern borders of the Delhi territory, between lat. 29° and 30°, he saw an Indian elephant of a small size, covered with shaggy hair. But this variety must be exceedingly rare ; for Mr. Royle (late superintendent of the East India Company's Botanic Garden at Saharunpore) has assured me, that being in India when Heber's Journal appeared, and having never seen or heard of such elephants, he made the strictest inquiries respecting the fact, and was never able to obtain any evidence in corroboration. Mr. Royle resided at Saharunpore, lat. 30° N., upon *the extreme northern limits* of the range of the elephant. Mr. Everest also declares that he has been equally unsuccessful in finding any one aware of the existence of such a variety or breed of the animal, though one solitary individual was mentioned to him as having been seen at Delhi, with a good deal of long hair upon it. The greatest elevation, says Mr. E., at which the wild elephant is found in the mountains to the north of Bengal, is at a place called Nahun, about 4000 feet above the level of the sea, and in the 31st degree of N. lat., where the mean yearly temperature may be about 64° Fahrenheit, and the difference between winter and summer very great, equal to about 36° F., the month of January averaging 45°, and June, the hottest month, 81° F. (Everest on climate of Foss. Eleph., Journ. of Asiat. Soc., No. 25. p. 21.)

We are as yet ignorant of the entire geographical range mammoth; but its remains have been recently collected fro cliffs of frozen mud and ice on the east side of Behring's Str Eschscholtz's Bay, in Russian America, lat. 66° N. As the waste away by the thawing of the ice, tusks and bones fall out, strong odour of animal matter is exhaled from the mud.*

On considering all the facts above enumerated, it seems reas to imagine that a large region in central Asia, including, perhap southern half of Siberia, enjoyed, at no very remote period i earth's history, a temperate climate, sufficiently mild to food for numerous herds of elephants and rhinoceroses, *of speci tinct from those now living.* It has usually been taken for gr that herbivorous animals, of large size, require a very lux vegetation for their support; but this opinion is, according t Darwin, completely erroneous:—"It has been derived," he "from our acquaintance with India and the Indian islands, whe mind has been accustomed to associate troops of elephants with forests and impenetrable jungles. But the southern parts of A from the tropic of Capricorn to the Cape of Good Hope, alth sterile and desert, are remarkable for the number and great b their indigenous quadrupeds. We there meet with an elephan species of rhinoceros, a hippopotamus, a giraffe, the bos caffe elan, two zebras, the quagga, two gnus, and several antelopes. must we suppose, that while the species are numerous, the indiv of each kind are few. Dr. Andrew Smith saw, in one day's ma lat. 24° S., without wandering to any great distance on either about 150 rhinoceroses, with several herds of giraffes, and his had killed, on the previous night, eight hippopotamuses. Y country which they inhabited was thinly covered with gra bushes about four feet high, and still more thinly with mimosa so that the waggons of the travellers were not prevented fron ceeding in a nearly direct line." †

In order to explain how so many animals can find support i region, it is suggested that the underwood, of which their food consists, may contain much nutriment in a small bulk, and al the vegetation has a rapid growth; for no sooner is a part con than its place, says Dr. Smith, is supplied by a fresh stock. theless, after making every allowance for this successive prod and consumption, it is clear, from the facts above cited, th quantity of food required by the larger herbivora is much les we have usually imagined. Mr. Darwin conceives that the of vegetation supported at any one time by Great Britain may in a ten-fold ratio, the quantity existing on an equal area

---

[*] See Dr. Buckland's description of these bones, Appen. to Beechy's Voy.

[†] Darwin, Journal of Travels in S. America, &c., 1832—1836, in of H.M.S. Beagle, p. 98. 2d E don, 1845, p. 86.

interior parts of Southern Africa.* It is remarked, moreover, in illustration of the small connexion discoverable between abundance of food and the magnitude of indigenous mammalia, that while in the desert part of Southern Africa there are so many huge animals; in Brazil, where the splendour and exuberance of the vegetation are unrivalled, there is not a single wild quadruped of large size.†

It would doubtless be impossible for herds of mammoths and rhinoceroses to subsist, at present, throughout the year, even in the southern part of Siberia, covered as it is with snow during winter; but there is no difficulty in supposing a vegetation capable of nourishing these great quadrupeds to have once flourished between the latitudes 40° and 60° N.

Dr. Fleming has hinted, that "the kind of food which the existing species of elephant prefers, will not enable us to determine, or even to offer a probable conjecture, concerning that of the extinct species. No one acquainted with the gramineous character of the food of our fallow-deer, stag, or roe, would have assigned a lichen to the reindeer."

Travellers mention that, even now, when the climate of eastern Asia is so much colder than the same parallels of latitude farther west, there are woods not only of fir, but of birch, poplar, and alder, on the banks of the Lena, as far north as latitude 60°.

It has, moreover, been suggested, that as, in our own times, the northern animals migrate, so the Siberian elephant and rhinoceros may have wandered towards the north in summer. The musk oxen annually desert their winter quarters in the south, and cross the sea upon the ice, to graze for four months, from May to September, on the rich pasturage of Melville Island, in lat. 75°. The mammoths, without passing so far beyond the arctic circle, may nevertheless have made excursions, during the heat of a brief northern summer, from the central or temperate parts of Asia to the sixtieth parallel of latitude.

Now, in this case, the preservation of their bones, or even occasionally of their entire carcasses, in ice or frozen soil, may be accounted for, without resorting to speculations concerning sudden revolutions in the former state and climate of the earth's surface. We are entitled to assume, that, in the time of the extinct elephant and rhinoceros, the Lowland of Siberia was less extensive towards the north than now; for we have seen (p. 80.) that the strata of this Lowland, in which the fossil bones lie buried, were originally deposited beneath the sea; and we know, from the facts brought to light in Wrangle's Voyage, in the years 1821, 1822, and 1823, that a slow upheaval of the land along the borders of the Icy Sea is now constantly taking place, similar to that experienced in part of Sweden. In the same manner, then, as the shores of the Gulf of Bothnia are extended, not only by the influx of sediment brought down by but also by the elevation and consequent drying up of the bed sea, so a like combination of causes may, in modern times, hav extending the low tract of land where marine shells and fossil occur in Siberia.[*] Such a change in the physical geography o region, implying a constant augmentation in the quantity of land, would, according to principles to be explained in the chapter, tend to increase the severity of the winters. We conclude, therefore, that, before the land reached so far to the the temperature of the Siberian winter and summer was more equalized; and a greater degree of winter's cold may, even than a general diminution of the mean annual temperature, finally contributed to the extermination of the mammoth and its temporaries.

---

* Darwin, Journal of Travels in S. America, &c., p. 99. 2d Ed. p. 85.

† Burchell, cited by Darwin, ibid., p. 101. 2d Ed. p. 87.

On referring to the map (p. 79.), the reader will see how al great rivers of Siberia flow at present from south to north, temperate to arctic regions, and they are all liable, like the Mack in North America, to remarkable floods, in consequence of flowi this direction. For they are filled with running water in their or southern course when completely frozen over for several hu miles near their mouths, where they remain blocked up by ic six months in every year. The descending waters, therefore, fi no open channel, rush over the ice, often changing their dire and sweeping along forests and prodigious quantities of soil gravel mixed with ice. Now the rivers of Siberia are amon largest in the world, the Yenesei having a course of 2500, the of 2000 miles; so that we may easily conceive that the bodi animals which fall into their waters may be transported to distances towards the Arctic Sea, and, before arriving there, m stranded upon and often frozen into thick ice. Afterwards, wh ice breaks up, they may be floated still farther towards the until at length they become buried in fluviatile and submarine de near the mouths of rivers.

Humboldt remarks that near the mouths of the Lena a consid thickness of frozen soil may be found at all seasons at the de a few feet; so that if a carcass be once imbedded in mud and such a region and in such a climate, its putrefaction may be ar for indefinite ages.[†] According to Prof. Von Baer of St. Peter the ground is now frozen permanently to the depth of 400 f the town of Yakutzt, on the western bank of the Lena, in lat. 6 600 miles distant from the polar sea. Mr. Hedenstrom te that, throughout a wide area in Siberia, the boundary cliffs lakes and rivers consist of alternate layers of earthy materials a in horizontal stratification*; and Mr. Middendorf informed us, in 1846, that, in his tour there three years before, he had bored in Siberia to the depth of seventy feet, and, after passing through much frozen soil mixed with ice, had come down upon a solid mass of pure transparent ice, the thickness of which, after penetrating two or three yards, they did not ascertain. We may conceive, therefore, that even at the period of the mammoth, when the Lowland of Siberia was less extensive towards the north, and consequently the climate more temperate than now, the cold may still have been sufficiently intense to cause the rivers flowing in their present direction to sweep down from south to north the bodies of drowned animals, and there bury them in drift ice and frozen mud.

---

[*] Since the above passage was first printed in a former edition, June 1835, it has been shown by the observations of Sir R. Murchison, M. de Verneuil, and Count Keyserling, and more recently by M. Middendorf (see above, p. 81.), that the Lowland of Siberia has actual extended, since the *existing sp* shells inhabited the northern seas.

[†] Humboldt, Fragmens Asi tom. ii. p 393.

If it be true that the carcass of the mammoth was imbedded in pure ice, there are two ways in which it may have been frozen in. We may suppose the animal to have been overwhelmed by drift snow; I have been informed by Dr. Richardson, that, in the northern parts of America, comprising regions now inhabited by many herbivorous quadrupeds, the drift snow is often converted into permanent glaciers. It is commonly blown over the edges of steep cliffs, so as to form an inclined talus hundreds of feet high; and when a thaw commences, torrents rush from the land, and throw down from the top of the cliff alluvial soil and gravel. This new soil soon becomes covered with vegetation, and protects the foundation of snow from the rays of the sun. Water occasionally penetrates into the crevices and pores of the snow; but, as it soon freezes again, it serves the more rapidly to consolidate the mass into a compact iceberg. It may sometimes happen hat cattle grazing in a valley at the base of such cliffs, on the borders f a sea or river, may be overwhelmed, and at length enclosed in solid ce, and then transported towards the polar regions. Or a herd of mammoths returning from their summer pastures in the north, may ave been surprised, while crossing a stream, by the sudden congeation of the waters. The missionary Huc relates, in his Travels in Thibet in 1846, that, after many of his party had been frozen to death, hey pitched their tents on the banks of the Mouroui-Ousson (which ower down becomes the famous Blue River), and saw from their ncampment "some black shapeless objects ranged in file across the tream. As they advanced nearer no change either in form or disinctness was apparent; nor was it till they were quite close, hat they recognized in them a troop of the wild oxen, called Yak by the Thibetans.† There were more than fifty of them ncrusted in the ice. No doubt they had tried to swim across at he moment of congelation, and had been unable to disengage themelves. Their beautiful heads, surmounted by huge horns, were still bove the surface, but their bodies were held fast in the ice, which as so transparent that the position of the imprudent beasts was easily distinguishable; they looked as if still swimming, but the ea and ravens had pecked out their eyes."*

---

* Reboul. Geol. de la Période Quaterire, who cites Observ. sur la Sibérie, ibl. Univ., Juillet, 1832.

† Conjectured to be the wild stock of Bos grunniens.

The foregoing investigations, therefore, lead us to infer that mammoth, and some other extinct quadrupeds fitted to live in h latitudes, were inhabitants of Northern Asia at a time when geographical conditions and climate of that continent were diffe from the present. But the age of this fauna was comparati modern in the earth's history. It appears that when the oldest eocene tertiary deposits were formed, a warm temperature pervaded European seas and lands. Shells of the genus Nautilus and ot forms characteristic of tropical latitudes; fossil reptiles, such as crocodile, turtle, and tortoise; plants, such as palms, some of th allied to the cocoa-nut, the screw-pine, the custard-apple, and acacia, all lead to this conclusion. This flora and fauna were follo by those of the miocene formation, in which indications of a south but less tropical climate are detected. Finally, the pliocene depo which come next in succession, exhibit in their organic remains a n nearer approach to the state of things now prevailing in correspon latitudes. It was towards the close of this period that the seas of northern hemisphere became more and more filled with floating bergs often charged with erratic blocks, so that the waters and atmosphere were chilled by the melting ice, and an arctic f enabled, for a time, to invade the temperate latitudes both o America and Europe. The extinction of a considerable numb land quadrupeds and aquatic mollusca was gradually brought a by the increasing severity of the cold; but many species survived revolution in climate, either by their capacity of living und variety of conditions, or by migrating for a time to more southern and seas. At length, by modifications in the physical geography o northern regions, and the cessation of floating ice on the eastern of the Atlantic, the cold was moderated, and a milder climate en such as we now enjoy in Europe.†

Proofs from fossils in secondary and still older strata.—A interval of time appears to have elapsed between the formation o secondary strata, which constitute the principal portion of the vated land in Europe, and the origin of the eocene deposits. examine the rocks from the chalk to the new red sandstone incl we find many distinct assemblages of fossils entombed in them, unknown species, and many of them referable to genera and fa now most abundant between the tropics. Among the mos markable are reptiles of gigantic size; some of them herbiv others carnivorous, and far exceeding in size any now known

---

[*] Recollections of a Journey through Tartary, Thibet, and China (ch. xv. p. 234.), by M. Huc. Longman, 1852.

[†] For an account of the more modern changes of the tertiary fauna and flora of the British Isles and adjoining countries, and particularly those facts which relate to the "glacial epoch," admirable essay by Prof. E. Memoirs of Geol. Survey of Gre vol. i. p. 336. London, 1846. important memoir I shall have occasion to refer in the sequel.

n the torrid zone. The genera are for the most part extinct, but ome of them, as the crocodile and monitor, have still representatives n the warmer parts of the earth. Coral reefs also were evidently numerous in the seas of the same periods, composed of species often belonging to genera now characteristic of a tropical climate. The number of large chambered shells also, including the nautilus, leads us to infer an elevated temperature; and the associated fossil plants, lthough imperfectly known, tend to the same conclusion, the Cycadeæ constituting the most numerous family.

But it is from the more ancient coal deposits, that the most extraordinary evidence has been supplied in proof of the former xistence of a very different climate, a climate which seems to have been moist, warm, and extremely uniform, in those very latitudes which are now the colder, and in regard to temperature the most variable regions of the globe. We learn from the researches of Adolphe Brongniart, Goeppert, and other botanists, that in the flora f the carboniferous era there was a great predominance of ferns, ome of which were arborescent; as, for example, Caulopteris, Propteris, and Psarronius; nor can this be accounted for, as some have pposed, by the greater power which ferns possess of resisting macetion in water.* This prevalence of ferns indicates a moist, equable, d temperate climate, and the absence of any severe cold; for such e the conditions which, at the present day, are found to be most vourable to that tribe of plants. It is only in the islands of the opical oceans, and of the southern temperate zone, such as Norfolk land, Otaheite, the Sandwich Islands, Tristan d'Acunha, and New aland, that we find any near approach to that remarkable preponrance of ferns, which is characteristic of the Carboniferous flora. has been observed that tree ferns and other forms of vegetation hich flourished most luxuriantly within the tropics, extend to a uch greater distance from the equator in the southern hemisphere an in the northern, being found even as far as 46° S. latitude in ew Zealand. There is little doubt that this is owing to the more iform and moist climate occasioned by the greater proportional ea of sea. Next to ferns and pines, the most abundant vegetable rms in the coal formation are the Calamites, Lepidodendra, Sigillariæ, d Stigmariæ. These were formerly considered to be so closely lied to tropical genera, and to be so much greater in size than the rresponding tribes now inhabiting equatorial latitudes, that they ere thought to imply an extremely hot, as well as humid and uable climate. But recent discoveries respecting the structure and lations of these fossil plants, have shown that they deviated so idely from all existing types in the vegetable world, that we have ore reason to infer from this evidence a widely different climate in e Carboniferous era, as compared to that now prevailing, than a temperature extremely elevated.[*] Palms, if not entirely wa when the strata of the carboniferous group were deposited, appe have been exceedingly rare.[†] The Coniferæ, on the other so abundantly met with in the coal, resemble Araucariæ in struc a family of the fir tribe characteristic at present of the milder re of the southern hemisphere, such as Chili, Brazil, New Holland, Norfolk Island.

---

* See a paper by Charles J. F. Bunbury, Esq. Journ. of Geol. Soc. London, . 6. p. 88. 1846.

"In regard to the geographical extent of the ancient vegetati was not confined," says M. Brongniart, "to a small space, Europe, for example; for the same forms are met with again at distances. Thus, the coal-plants of North America are, for the part, identical with those of Europe, and all belong to the genera. Some specimens, also, from Greenland, are referabl ferns, analogous to those of our European coal mines."[‡] The plants brought from Melville Island, although in a very impe state, have been supposed to warrant similar conclusions[§]; assuming that they agree with those of Baffin's Bay, mentione M. Brongniart, how shall we explain the manner in which su vegetation lived through an arctic night of several months' tion?[||]

It may seem premature to discuss this question, until the nature of the fossil flora of the arctic regions has been more accurately determined; yet, as the question has attracted some attention, let us assume for a moment, that the coal plants of Melville Island are strictly analogous to those of the strata of Northumberland—would such a fact present an inexplicable enigma to the vegetable physiologist?

---

[*] The Calamities were formerly regarded by Adolphe Brongniart as belonging to the tribe of Equisetaceæ; but he is now inclined to refer them to the class of gymnogens or gymnospermous exogens, which includes the Coniferæ and Cycadeæ. Lepidodendron appears to have been either a gigantic form of the lycopodium tribe, or, as Dr. Lindley thinks, intermediate between the lycopodia and the fir tribe. The Sigillariæ were formerly supposed by Ad. Brongniart, to be arborescent ferns; but the discovery of their internal structure, and of their leaves, has since proved that they have no real affinity to ferns. According to the view now taken of their structure, their nearest allies in the recent world are the genera Cycas and Zamia; while Corda, on the other hand, maintains that they were closely related to the succulent euphorbias. Stigmaria is now generally admitted to have been merely the root of sigillaria. The scalariform vessels of these two genera are not conclusive in proving them to have a real affinity with ferns, as Mr. Brown has discovered the same structure of vessels in Myzodendron, a genius allied to the mistletoe; and Corda has lately shown that in two species of Stigmaria, hardly distinguishable by external characters, the vessels of the one are scalariform, and of the other dotted.

[†] Mr. Lindley endeavoured formerly (1834), to show in the "Fossil that Trigonocarpum Noeggerathii, found in the coal measures, has t structure of a palm-fruit; but Ad. niart has since inclined to regar cycadeous; nor is the French b satisfied that some specimens of su palm-wood from the coal mines of B in Bohemia, described by Corda, belong to palms. On the other Corda has proved Flabellaria bora of Sternberg to be an exogenous and Brongniart contends that it wa to the Cycadeæ. See Tables Genres de Végétaux Fossiles. Paris

[‡] Prodrome d'une Hist. des Foss. p. 179. See also a late Quart. Journ. of Geol. Soc. L 1846, in which coal-plants of Al lat. 33° N., collected by the auth identified by Mr. Bunbury with fossil species, showing the great so extension of this flora.

[§] König, Journ. of Sci. vol. xv. Mr. König informs me, that he no believes any of these fossils to ferns, as he at first stated, but th agree generically with plants in o glish coal-beds. The Melville specimens, now in the British M are very obscure impressions.

[||] Fossil Flora of Great Brita John Lindley and William Esqrs. No. IV.

Plants, it is affirmed, cannot remain in darkness, even for a week, without serious injury, unless in a torpid state; and if exposed to heat and moisture they cannot remain torpid, but will grow, and must therefore perish. If, then, in the latitude of Melville Island, 75° N., a high temperature, and consequent humidity, prevailed at that period when we know the arctic seas were filled with corals and large multilocular shells, how could plants of tropical forms have flourished? Is not the bright light of equatorial regions as indispensable a condition of their well-being as the sultry heat of the same countries? and how could they annually endure a night prolonged for three months?*

Now, in reply to this objection, we must bear in mind, in the first place, that, so far as experiments have been made, there is every reason to conclude, that the range of intensity of light to which living plants can accommodate themselves is far wider than that of heat. No palms or tree ferns can live in our temperate latitudes without protection from the cold: but when placed in hot-houses they grow luxuriantly, even under a cloudy sky, and where much light is intercepted by the glass and frame-work. At St. Petersburg, in lat. 60° N., these plants have been successfully cultivated in hot-houses, although there they must exchange the perpetual equinox of their native regions, for days and nights which are alternately protracted to nineteen hours and shortened to five. How much farther towards the pole they might continue to live, provided a due quantity of heat and moisture were supplied, has not yet been determined; but St. Petersburg is probably not the utmost limit, and we should expect that in lat. 65° at least, where they would never remain twenty-four hours without enjoying the sun's light, they might still exist.

It should also be borne in mind, in regard to tree ferns, that they grow in the gloomiest and darkest parts of the forests of warm and temperate regions, even extending to nearly the 46th degree of south latitude in New Zealand. In equatorial countries, says Humboldt, they abound chiefly in the temperate, humid, and shady parts of *mountains*. As we know, therefore, that elevation often compensates for the effect of latitude in the geographical distribution of plants, we may easily understand that a class of vegetables, which grows at a certain height in the torrid zone, would flourish on the plains at greater distances from the equator, if the temperature, moisture, and other necessary conditions, were equally uniform throughout the year.

---

* Fossil Flora of Great Britain, by John Lindley and William Hutton, Esqrs. No. IV.

Nor must we forget that in all the examples above alluded to, w have been speaking of *living* species; but the coal-plants were of pe fectly distinct species, nay, few of them except the ferns and pines ca be referred to genera or even families of the existing vegetable kingdo Having a structure, therefore, and often a form which appears to th botanist so anomalous, they may also have been endowed with a di ferent constitution, enabling them to bear a greater variation of ci cumstances in regard to light. We find that particular species o plants and tree ferns require at present different degrees of heat; an that some species can thrive only in the immediate neighbourhood o the equator, others only a distance from it. In the same mann the *minimum* of *light*, sufficient for the now existing species, canno be taken as the standard for all analogous tribes that may ever hav flourished on the globe.

But granting that the extreme northern point to which a flora lik that of the Carboniferous era could ever reach, may be somewhe between the latitudes of 65° and 70°, we should still have to inqui whether the vegetable remains might not have been drifted fro thence, by rivers and currents, to the parallel of Melville Island, o still farther. In the northern hemisphere, at present, we see that th materials for future beds of lignite and coal are becoming amassed i high latitudes, far from the districts where the forests grew, and o shores where scarcely a stunted shrub can now exist. The Mackenzi and other rivers of North America, carry pines with their roots a tached for many hundred miles towards the north, into the Arctic Se where they are imbedded in deltas, and some of them drifted still farth by currents towards the pole.

Before we can decide on this question of transportation, we mu know whether the fossil coal-plants occurring in high latitudes be the marks of friction and of having decayed previously to fossilizatio Many appearances in our English coal-fields certainly prove that t plants were not floated from great distances; for the outline of t stems of succulent species preserve their sharp angles, and others ha their surfaces marked with the most delicate lines and streaks. Lo leaves, also, are attached in many instances to the trunks or branches and leaves we know, in general, are soon destroyed when steeped water, although ferns will retain their forms after an immersion many months.† It seems fair to presume, that most of the co plants grew upon the same land which supplied materials for t sandstones and conglomerates of the strata in which they are imbedde The coarseness of the particles of many of these rocks attests that th were not borne from very remote localities, and that there was la therefore in the vicinity wasting away by the action of moving wate The progress also of modern discovery has led to the very gene admission of the doctrine that beds of coal have for the most part be formed of the remains of trees and plants that grew on the spot whe the coal now exists; the land having been successively submerged, so that a covering of mud and sand was deposited upon accumulations of vegetable matter. That such has been the origin of some coal-seams is proved by the upright position of fossil trees, both in Europe and America, in which the roots terminate downwards in beds of coal.[*]

---

* Fossil Flora, No. X.

† This has been proved by Mr. Li ley's experiments, ibid., No. XVII.

To return, therefore, from this digression,—the flora of the coal appears to indicate a uniform and mild temperature in the air, while the fossils of the contemporaneous mountain-limestone, comprising abundance of lamelliferous corals, large chambered cephalopods, and crinoidea, naturally lead us to infer a considerable warmth in the waters of the northern sea of the Carboniferous period. So also in regard to strata older than the coal, they contain in high northern latitudes mountain masses of corals which must have lived and grown on the spot, and large chambered univalves, such as Orthocerata and Nautilus, all seeming to indicate, even in regions bordering on the arctic circle, the former prevalence of a temperature more elevated than that now prevailing.

The warmth and humidity of the air, and the uniformity of climate, both in the different seasons of the year, and in different latitudes, appears to have been most remarkable when some of the oldest of the fossiliferous strata were formed. The approximation to a climate similar to that now enjoyed in these latitudes does not commence till the era of the formations termed tertiary; and while the different tertiary rocks were deposited in succession, from the eocene to the pliocene, the temperature seems to have been lowered, and to have continued to diminish even after the appearance upon the earth of a considerable number of the existing species, the cold reaching its maximum of intensity in European latitudes during the glacial epoch, or the epoch immediately antecedent to that in which all the species now contemporary with man were in being.

---

[*] I have treated of this subject in my Manual of Geology, and still more fully in my Travels in N. America, vol. ii. p. 178. For a full account of the facts at present known, and the theories entertained by the most eminent geologists and botanists on this subject, see Mr. Horner's Anniversary Address to the Geological Society of London, February, 1846. Consult also Sir H. de la Beche, on the formation of rocks in South Wales, Memoirs of Geol. Survey of Great Brit. 1846, p. 1. to 296.

CHAPTER VII.

FARTHER EXAMINATION OF THE QUESTION AS TO THE ASSUMED DI CORDANCE OF THE ANCIENT AND MODERN CAUSES OF CHANGE.

On the causes of vicissitudes in climate—Remarks on the present diffusion of he over the globe—On the dependence of the mean temperature on the relati position of land and sea—Isothermal Lines—Currents from equatorial regions—Drifting of icebergs—Different temperature of Northern and Southern hem spheres—Combination of causes which might produce the extreme cold of whi the earth's surface is susceptible—Conditions necessary for the production the extreme of heat, and its probable effects on organic life.

Causes of vicissitudes in climate.[*]—As the proofs enumerated i the last chapter indicate that the earth's surface has experienced gre changes of climate since the deposition of the older sedimentary strat we have next to inquire how such vicissitudes can be reconciled wit the existing order of nature. The cosmogonist has availed himse of this, as of every obscure problem in geology, to confirm his view concerning a period when the planet was in a nascent or half-form state, or when the laws of the animate and inanimate world differe essentially from those now established; and he has in this, as i many other cases, succeeded so far, as to divert attention from th class of facts which, if fully understood, might probably lead to a explanation of the phenomena. At first it was imagined that th earth's axis had been for ages perpendicular to the plane of th ecliptic, so that there was a perpetual equinox, and uniformity seasons throughout the year;—that the planet enjoyed this "parad siacal" state until the era of the great flood; but in that catastroph whether by the shock of a comet, or some other convulsion, it lo its equal poise, and hence the obliquity of its axis, and with that th varied seasons of the temperate zone, and the long nights and days the polar circles.

When the progress of astronomical science had exploded this theor it was assumed, that the earth at its creation was in a state of fluidit and red hot, and that ever since that era, it had been cooling dow contracting its dimensions, and acquiring a solid crust,—an hyp thesis hardly less arbitrary, yet more calculated for lasting popularit because, by referring the mind directly to the beginning of things, requires no support from observation, nor from any ulterior hyp thesis. But if, instead of forming vague conjectures as to what mig have been the state of the planet at the era of its creation, we fix o thoughts on the connexion at present existing between climate and the distribution of land and sea; and then consider what influence former fluctuations in the physical geography of the earth must have had on superficial temperature, we may perhaps approximate to a true theory. If doubts and obscurities still remain, they should be ascribed to our limited acquaintance with the laws of Nature, not to revolutions in her economy;—they should stimulate us to farther research, not tempt us to indulge our fancies respecting the imaginary changes of internal temperature in an embryo world.

---

[*] The theory proposed in this and the following chapters, to account for former fluctuations of climate at successive geological periods, agrees in every essential particular, and has indeed been reprinted almost verbatim from that published by me twenty years ago in the first edition of my Principles, 1830. It was referred to by Sir John F. W. Herschel in Discourse on Natural Philosophy, pu lished in 1830. In preceding works gradual diminution of the earth's cent heat was almost the only cause assign for the acknowledged diminution of superficial temperature of our planet.

Diffusion of heat over the globe.—In considering the laws which regulate the diffusion of heat over the globe, we must be careful, as Humboldt well remarks, not to regard the climate of Europe as a type of the temperature which all countries placed under the same latitude enjoy. The physical sciences, observes this philosopher, always bear the impress of the places where they began to be cultivated; and as, in geology, an attempt was at first made to refer all the volcanic phenomena to those of the volcanos in Italy, so in meteorology, a small part of the old world, the centre of the primitive civilization of Europe, was for a long time considered a type to which the climate of all corresponding latitudes might be referred. But this region, constituting only one seventh of the whole globe, proved eventually to be the exception to the general rule. For the same reason, we may warn the geologist to be on his guard, and not hastily to assume that the temperature of the earth in the present era is a type of that which most usually obtains, since he contemplates far mightier alterations in the position of land and sea, at different epochs, than those which now cause the climate of Europe to differ from that of other countries in the same parallels.

It is now well ascertained that zones of equal warmth, both in the atmosphere and in the waters of the ocean, are neither parallel to the equator nor to each other.* It is also known that the *mean* annual temperature may be the same in two places which enjoy very different climates, for the seasons may be nearly uniform, or violently contrasted, so that the lines of equal winter temperature do not coincide with those of equal annual heat or isothermal lines. The deviations of all these lines from the same parallel of latitude are determined by a multitude of circumstances, among the principal of which are the position, direction, and elevation of the continents and islands, the position and depths of the sea, and the direction of currents and of winds.

---

* We are indebted to Baron Alex. von Humboldt for having first collected together the scattered data on which he founded an approximation to a true theory of the distribution of heat over the globe. Many of these data were derived from the author's own observations, and many from the works of M. Pierre Prevost, of Geneva, on the radiation of heat, and from other writers.—See Humboldt on Isothermal Lines, Mémoires d'Arcueil, tom. iii. translated in the Edin. Phil. Journ. vol. iii. July, 1820.

The map of Isothermal Lines, recently published by Humboldt and Dove (1848), supplies a large body of well-established data for such investigations, of which Mr. Hopkins has most ably availed himself in an essay "On the Causes which may have produced Changes in the Earth's Superficial Temperature."—Q. Journ. Geol. Soc. 1852, p. 56.

On comparing the two continents of Europe and America, i found that places in the same latitudes have sometimes a mean di ence of temperature amounting to 11°, or even in a few cases to Fahr.; and some places on the two continents, which have the s mean temperature, differ from 7° to 17° in latitude. Thus, Cumb land House, in North America, having the same latitude (54° N.) the city of York in England, stands on the isothermal line of which in Europe rises to the North Cape, in lat. 71°, but its sum heat exceeds that of Brussels or Paris.* The principal caus greater intensity of cold in corresponding latitudes of North Ame as contrasted with Europe, is the connexion of America with polar circle, by a large tract of land, some of which is from thre five thousand feet in height; and, on the other hand, the separatio Europe from the arctic circle by an ocean. The ocean has a tende to preserve every where a mean temperature, which it communic to the contiguous land, so that it tempers the climate, moderating al an excess of heat or cold. The elevated land, or the other ha rising to the colder regions of the atmosphere, becomes a great res voir of ice and snow, arrests, condenses, and congeals vapour, a communicates its cold to the adjoining country. For this rea Greenland, forming part of a continent which stretches northw to the 82d degree of latitude, experiences under the 60th paralle more rigorous climate than Lapland under the 72d parallel.

But if land be situated between the 40th parallel and the equat it produces, unless it be of extreme height, exactly the oppo effect; for it then warms the tracts of land or sea that interv between it and the polar circle. For the surface being in this c exposed to the vertical, or nearly vertical rays of the sun, absorb large quantity of heat, which it diffuses by radiation into the at sphere. For this reason, the western parts of the old continent der warmth from Africa, "which, like an immense furnace, distributes heat to Arabia, to Turkey in Asia, and to Europe."† On the c trary, the north-eastern extremity of Asia experiences in the sa latitude extreme cold; for it has land on the north between the 6 and 70th parallel, while to the south it is separated from the equa by the Pacific Ocean.

In consequence of the more equal temperature of the waters of ocean, the climate of islands and of coasts differs essentially from t of the interior of continents, the more maritime climates being c racterized by mild winters, and more temperate summers; for the breezes moderate the cold of winter, as well as the heat of sumn When, therefore, we trace round the globe those belts in which mean annual temperature is the same, we often find great difference climate; for there are *insular* climates in which the seasons are nea equalized, and *excessive* climates, as they have been termed, wh the temperature of winter and summer is strongly contrasted. ' whole of Europe, compared with the eastern parts of America

---

* Sir J. Richardson's Appendix to Sir G. Bach's Journal, 1843—1845, p. 478.

† Malte-Brun, Phys. Geol. book

Asia, has an insular climate. The northern part of China, and the Atlantic region of the United States, exhibit "excessive climates." We find at New York, says Humboldt, the summer of Rome and the winter of Copenhagen; at Quebec, the summer of Paris and the winter of Petersburg. At Pekin, in China, where the mean temperature of the year is that of the coasts of Brittany, the scorching heats of summer are greater than at Cairo, and the winters as rigorous as at Upsala.*

If lines be drawn round the globe through all those places which have the same winter temperature, they are found to deviate from the terrestrial parallels much farther than the lines of equal mean annual heat. The lines of equal winter in Europe, for example, are often curved so as to reach parallels of latitude 9° or 10° distant from each other, whereas the isothermal lines, or those passing through places having the same mean annual temperature, differ only from 4° to 5° in Europe.

Influence of currents and drift ice on temperature.—Among other influential causes, both of remarkable diversity in the mean annual heat, and of unequal division of heat in the different seasons, are the direction of currents and the accumulation and drifting of ice in high latitudes. The temperature of the Lagullas current is 10° or 12° Fahr. above that of the sea at the Cape of Good Hope; for it derives the greater part of its waters from the Mozambique channel, and south-east coast of Africa, and from regions in the Indian Ocean much nearer the line, and much hotter than the Cape.† An opposite effect is produced by the "equatorial" current, which crosses the Atlantic from Africa to Brazil, having a breadth varying from 160 to 450 nautical miles. Its waters are cooler by 3° or 4° Fahr. than those of the ocean under the line, so that it moderates the heat of the tropics.‡

But the effects of the Gulf stream on the climate of the North Atlantic Ocean are far more remarkable. This most powerful of known currents has its source in the Gulf or Sea of Mexico, which, like the Mediterranean and other close seas in temperate or low latitudes, is warmer than the open ocean in the same parallels. The temperature of the Mexican sea in summer is, according to Rennell, 86° Fahr., or at least 7° above that of the Atlantic in the same latitude.§ From this great reservoir or caldron of warm water, a constant current pours forth through the straits of Bahama at the rate of 3 or 4 miles an hour; it crosses the ocean in a north-easterly direction, skirting the great bank of Newfoundland, where it still retains a temperature of 8° above that of the surrounding sea. It reaches the Azores in about 78 days, after flowing nearly 3000 geographical miles, and from thence it sometimes extends its course a thousand miles farther, so as to reach the Bay of Biscay, still retaining an excess of 5° above the mean temperature of that sea. As it has been known to arrive there in the months of November and January, it may t greatly to moderate the cold of winter in countries on the wes Europe.

---

* On Isothermal Lines, &c.

† Rennell on Currents, p. 96. London, 1832.

‡ Ibid. p. 153.

§ Ibid. p. 25.

There is a large tract in the centre of the North Atlantic, betw the parallels of 33° and 45° N. lat. which Rennell calls the "recipi of the gulf water." A great part of it is covered by the weed cal sargasso (*Sargassum bacciferum*), which the current floats in abu dance from the Gulf of Mexico. This mass of water is nearly sta nant, is warmer by 7° or 10° than the waters of the Atlantic, a may be compared to the fresh water of a river overflowing the heavi salt water of the sea. Rennell estimates the area of the "recipien together with that covered by the main current, as being 2000 mil in length from E. to W., and 350 in breadth from N. to S., which, remarks, is a larger area than that of the Mediterranean. The he of this great body of water is kept up by the incessant and quick a rivals of fresh supplies of warm water from the south ; and there c be no doubt that the general climate of parts of Europe and Ameri is materially affected by this cause.

It is considered probable by Scoresby that the influence of the Gu stream extends even to the sea near Spitzbergen, where its waters m pass under those of melted ice ; for it has been found that in t neighbourhood of Spitzbergen, the water is warmer by 6° or 7° at t depth of one hundred and two hundred fathoms than at the surfa This might arise from the known law that fresh water passes the poi of greatest density when cooled down below 40°, and between th and the freezing point expands again. The water of melted ice mig be lighter, both as being fresh (having lost its salt in the decomposi process of freezing), and because its temperature is nearer the fre ing point than the inferior water of the Gulf stream.

The great glaciers generated in the valleys of Spitzbergen, in 79° of north latitude, are almost all cut off at the beach, being mel by the feeble remnant of heat still retained by the Gulf stream. Baffin's Bay, on the contrary, on the west coast of Old Greenla where the temperature of the sea is not mitigated by the same cau and where there is no warmer under-current, the glaciers stretch from the shore, and furnish repeated crops of mountainous masses ice which float off into the ocean.* The number and dimensions these bergs is prodigious. Capt. Sir John Ross saw several of th together in Baffin's Bay aground in water fifteen hundred feet de Many of them are driven down into Hudson's Bay and accumulat there, diffuse excessive cold over the neighbouring continent; so t Captain Franklin reports, that at the mouth of Hayes' River, wh lies in the same latitude as the north of Prussia or the south Scotland, ice is found every where in digging wells, in summer the depth of four feet! Other bergs have been occasionally with, at midsummer, in a state of rapid thaw, as far south as lat.

---

* Scoresby's Arctic Regions, vol. i. p. 208.—Dr. Latta's Observations on the Glaciers of Spitzbergen, &c. Edin. Phil. Journ. vol. iii. p. 97.

and longitude about 60° West, where they cool the water sensibly to the distance of forty or fifty miles around, the thermometer sinking sometimes 17°, or even 18°, Fahrenheit, in their neighbourhood.* It is a well-known fact that every four or five years a large number of icebergs, floating from Greenland, double Cape Langaness, and are stranded on the west coast of Iceland. The inhabitants are then aware that their crops of hay will fail, in consequence of fogs which are generated almost incessantly; and the dearth of food is not confined to the land, for the temperature of the water is so changed that the fish entirely desert the coast.

Difference of climate of the Northern and Southern hemispheres.—When we compare the climate of the northern and southern hemispheres, we obtain still more instruction in regard to the influence of the distribution of land and sea on climate. The dry land in the southern hemisphere is to that of the northern in the ratio only of one to three, excluding from our consideration that part which lies between the pole and the 78° of south latitude, which has hitherto proved inaccessible. And whereas in the northern hemisphere, between the pole and the thirtieth parallel of north latitude, the land and sea occupy nearly equal areas, the ocean in the southern hemisphere covers no less than fifteen parts in sixteen of the entire space included between the antarctic circle and the thirtieth parallel of south latitude.

This great extent of sea gives a particular character to climates south of the equator, the winters being mild and the summers cool. Thus, in Van Diemen's Land, corresponding nearly in latitude to Rome, the winters are more mild than at Naples, and the summers not warmer than those at Paris, which is 7° farther from the equator.† The effects on animal and vegetable life are remarkable. Capt. King observed large shrubs of Fuchsia and Veronica, which in England are treated as tender plants, thriving and in full flower in Tierra del Fuego with the temperature at 36°. He states also that humming birds were seen sipping the sweets of the flowers "after two or three days of constant rain, snow, and sleet, during which time the thermometer had been at the freezing point." Mr. Darwin also saw parrots feeding on the seeds of a tree called the winter's bark, south of lat. 55°, near Cape Horn.‡

So the orchideous plants which are parasitical on trees, and are generally characteristic of the tropics, advance to the 38th and 42nd degree of S. lat., and even beyond the 45th degree in New Zealand, where they were found by Forster. In South America also arborescent grasses abound in the dense forests of Chiloe, in lat. 42° S., where "they entwine the trees into one entangled mass to the height of thirty or forty feet above the ground. Palm trees in the same quarter of the globe grow in lat. 37°, an arborescent grass very like a bamboo in 40°, and another closely allied kind, of great le but not erect, even as far south as 45°."[*]

---

* Rennell on Currents, p. 95.

† Humboldt on Isothermal Lines.

‡ Journ. of Travels in S America, &c. p. 272.

It has long been supposed that the general temperature of southern hemisphere was considerably lower than that of the no ern, and that the difference amounted to at least 10° Fahren Baron Humboldt, after collecting and comparing a great numbe observations, came to the conclusion that even a much larger differe existed, but that none was to be observed within the tropics, only a small difference as far as the thirty-fifth and fortieth para Captain Cook was of opinion that the ice of the antarctic predo nated greatly over that of the arctic region, that encircling the sou ern pole coming nearer to the equator by 10° than the ice arou the north pole. All the recent voyages of discovery have tend to confirm this opinion, although Capt. Weddel penetrated, in 18 three degrees farther south than Capt. Cook, reaching lat. 74° South, long. 34° 17′ West, and Sir James Ross, in 1842, arrived lat. 78° 10′ S., as high a latitude, within three degrees, as the farth point attained by Captain Parry in the arctic circle, or lat. 81° North.

The description given by ancient as well as modern navigators the sea and land in high southern latitudes, clearly attests greater severity of the climate as compared to arctic regions. Sandwich Land, in lat. 59° S., or in nearly the same parallel as north of Scotland, Capt. Cook found the whole country, from summits of the mountains down to the very brink of the sea-cli "covered many fathoms thick with everlasting snow," and this the 1st of February, the hottest time of the year; and what is more astonishing, in the island of S. Georgia, which is in the 54° so latitude, or the same parallel as Yorkshire, the line of perpetual sn descends to the level of the ocean.[†] When we consider this fact, then recollect that the highest mountains in Scotland, which asce to an elevation of nearly 5000 feet, and are four degrees farther the north, do not attain the limit of perpetual snow on our side the equator, we learn that latitude is one only of many powe causes, which determine the climate of particular regions of the gl Capt. Sir James Ross, in his exploring expedition in 1841–3, fo that the temperature south of the 60th degree of latitude seldom r above 32° Fahr. During the two summer months of the year 18 (January and February) the range of the thermometer was betw 11° and 32° Fahr.; and scarcely once rose above the freezing point. permanence of snow in the southern hemisphere, is in this insta partly due to the floating ice, which chills the atmosphere and c denses the vapour, so that in summer the sun cannot pierce thro the foggy air. But besides the abundance of ice which covers the sea to the south of Georgia and Sandwich Land, we may also, as Humboldt suggests, ascribe the cold of those countries in part to the absence of land between them and the tropics.

---

[*] Darwin's Travels in S. America, p. 271.

[†] Mr. Hopkins raises the question whether, in South Georgia, the descent of glaciers to the margin of the sea might not have been mistaken by Capt. Cook for the descent of the snow-line to the level. Quart. Journ. Geol. Soc. p. 1852. The great navigator is gene very accurate, and there seem to b observations of more recent date ei to confirm or invalidate his stateme

If Africa and New Holland extended farther to the south, a diminution of ice would take place in consequence of the radiation of heat from these continents during summer, which would warm the contiguous sea and rarefy the air. The heated aërial currents would then ascend and flow more rapidly towards the south pole, and moderate the winter. In confirmation of these views, it is stated that the ice, which extends as far as the 68° and 71° of south latitude, advances more towards the equator whenever it meets an open sea; that is, where the extremities of the present continents are not opposite to it; and this circumstance seems explicable only on the principle above alluded to, of the radiation of heat from the lands so situated.

The cold of the antarctic regions was conjectured by Cook to be due to the existence of a large tract of land between the seventieth degree of south latitude and the pole. The justness of these and other speculations of that great navigator have since been singularly confirmed by the investigation made by Sir James Ross in 1841. He found Victoria Land, extending from 71° to 79° S. latitude, skirted by a great barrier of ice, the height of the land ranging from 4000 to 14,000 feet, the whole entirely covered with snow, except a narrow ring of black earth surrounding the huge crater of the active volcano of Mount Erebus, rising 12,400 feet above the level of the sea. The position of a mountainous territory of such altitude, so near the pole, and so obvious a source of intense cold, fully explains why Graham's and Enderby's Land, discovered by Captain Biscoe in 1831–2 (between lat. 64° 68° S.), presented a most wintry aspect, covered even in summer with ice and snow, and nearly destitute of animal life. In corresponding latitudes of the northern hemisphere we not only meet with herds of wild herbivorous animals, but with land which man himself inhabits, and where he has even built ports and inland villages.[*]

The distance to which icebergs float from the polar regions on the opposite sides of the line is, as might have been anticipated, very different. Their extreme limit in the northern hemisphere is lat. 40°, as before mentioned, and they are occasionally seen in lat. 42° N., near the termination of the great bank of Newfoundland, and at the Azores, lat. 42° N., to which they are sometimes drifted from Baffin's Bay. But in the other hemisphere they have been seen, within the last few years, at different points off the Cape of Good Hope, between lat. 36° and 39°.[†] One of these (see fig. 2.) was

---

[*] After all these modern discoveries, the area still unexplored, within the antarctic circle, is more than double the area of Europe. The surface of the latter contains about 2,793,000 square geographical miles. The unexplored antarctic region, as calculated for me by Mr. Gardner, in 1840, equalled about 7,620,000 square miles.

[†] On icebergs in low latitudes, by Capt. Horsburgh, by whom the sketch was made. Phil. Trans. 1830.

Fig. 2.

Iceberg seen [illegible] he Cape of Good Hope, April, 1829.
La[illegible] 13′ S. Long. 48° 46′ E.

two miles in circumference, and 150 feet high, appearing lik when the sun was obscured, and having the lustre of refined when the sun was shining on it. Others rose from 250 to 3 above the level of the sea, and were therefore of great volume since it is ascertained, by experiments on the buoyancy of ice in sea water, that for every cubic foot seen above, there m least be eight cubic feet below water.* If ice islands from the polar regions floated as far, they might reach Cape St. Vincen there, being drawn by the current that always sets in fro Atlantic through the Straits of Gibraltar, be drifted into the terranean, so that the serene sky of that delightful region migh be deformed by clouds and mists.

Before the amount of difference between the temperature two hemispheres was ascertained, it was referred by many as mers to the precession of the equinoxes, or the acceleration earth's motion in its perihelium; in consequence of which the and summer of the southern hemisphere are now shorter, by eight days, than those seasons north of the equator. But Herschel reminds us that the excess of eight days in the du of the sun's presence in the northern hemisphere is not produc an excess of annual light and heat; since, according to the l elliptic motion, it is demonstrable that whatever be the elli of the earth's orbit, the two hemispheres must receive *equal a* *quantities* of light and heat per annum, the proximity of the perigree exactly compensating the effect of its swifter m Humboldt, however, observes, that there must be a greater heat by radiation in the southern hemisphere during a winter by eight days than that on the other side of the equator.‡

Perhaps no very sensible effect may be produced by this so urbance; yet the geologist should bear in mind that to a certain ent it operates alternately on each of the two hemispheres for a od of upwards of 10,000 years, dividing unequally the times ng which the annual supply of solar light and heat is received. s cause may sometimes tend to counterbalance inequalities of perature resulting from other far more influential circumstances; on the other hand, it must sometimes tend to increase the exte of deviation arising from particular combinations of causes.

---

* Scoresby's Arctic Regions, vol. i. p. 234.

† This follows, observes Herschel, from a very simple theorem, which may be thus stated: — "The amount of heat received by the earth from the sun, while describing any part of its orbit, is proportional to the angle described round the sun's centre." So that if t be divided into two portions b drawn *in any direction* through t centre, the heat received in d the two unequal segments of th so produced will be equal. Geol vol. iii. part. ii. p. 298.; second

‡ On Isothermal Lines.

ut whatever may be at present the inferiority of heat in the erate and frigid zones south of the line, it is quite evident that cold would be far more intense if there happened, instead of open to be tracts of elevated land between the 55th and 70th parallel; on the other hand, the cold would be moderated if there were land between the line and the forty-fifth degree of south ide.

langes in the position of land and sea may give rise to vicis- les in climate.—Having offered these brief remarks on the sion of heat over the globe in the present state of the surface, I now proceed to speculate on the vicissitudes of climate, which attend those endless variations in the geographical features of planet which are contemplated in geology. That our speculations be confined within the strict limits of analogy, I shall assume, That the proportion of dry land to sea continues always the . 2dly, That the volume of the land rising above the level of ea is a constant quantity; and not only that its mean, but that ctreme height, is liable only to trifling variations. 3dly, That the mean and extreme depth of the sea are invariable; and , It may be consistent with due caution to assume that the ping together of the land in continents is a necessary part of the omy of nature; for it is possible that the laws which govern the rranean forces, and which act simultaneously along certain lines, ot but produce, at every epoch, continuous mountain-chains; at the subdivision of the whole land into innumerable islands be precluded.

it be objected, that the maximum of elevation of land and depth a are probably not constant, nor the gathering together of all and in certain parts, nor even perhaps the relative extent of land water, I reply, that the arguments about to be adduced will be gthened if, in these peculiarities of the surface, there be conable deviations from the present type. If, for example, all other mstances being the same, the land is at one time more divided islands than at another, a greater uniformity of climate might roduced, the mean temperature remaining unaltered; or if, at ter era, there were mountains higher than the Himalaya, these, placed in high latitudes, would cause a greater excess of cold. f we suppose that at certain periods no chain of hills in the l rose beyond the height of 10,000 feet, a greater heat might have prevailed than is compatible with the existence of mounthrice that elevation.

However constant may be the relative proportion of sea and la we know that there is annually some small variation in their resp tive geographical positions, and that in every century the land is some parts raised, and in others depressed in level, and so likew is the bed of the sea. By these and other ceaseless changes, the co figuration of the earth's surface has been remodelled again and aga since it was the habitation of organic beings, and the bed of the oce has been lifted up to the height of some of the loftiest mounta The imagination is apt to take alarm when called upon to admit formation of such irregularities in the crust of the earth, after it once become the habitation of living creatures; but, if time be lowed, the operation need not subvert the ordinary repose of natu and the result is in a general view insignificant, if we consider h slightly the highest mountain-chains cause our globe to differ fro perfect sphere. Chimborazo, though it rises to more than 21, feet above the sea, would be represented, on a globe of about six in diameter, by a grain of sand less than one-twentieth of an inc thickness.

The superficial inequalities of the earth, then, may be dee minute in quantity, and their distribution at any particular ep must be regarded in geology as temporary peculiarities, like height and outline of the cone of Vesuvius in the interval betw two eruptions. But although, in reference to the magnitude of globe, the unevenness of the surface is so unimportant, it is on position and direction of these small inequalities that the state of atmosphere, and both the local and general climate, are ma dependent.

Before considering the effect which a material change in the tribution of land and sea must occasion, it may be well to rem how greatly organic life may be affected by those minor variati which need not in the least degree alter the general tempera Thus, for example, if we suppose, by a series of convulsions, a ce part of Greenland to become sea, and, in compensation, a tra land to rise and connect Spitzbergen with Lapland,—an acce not greater in amount than one which the geologist can prov have occurred in certain districts bordering the Mediterranean, wi a comparatively modern period,—this altered form of the land m cause an interchange between the climate of certain parts of N America and of Europe, which lie in corresponding latitudes. M European species of plants and animals would probably peris consequence, because the mean temperature would be greatly ered; and others would fail in America, because it would the raised. On the other hand, in places where the mean annual remained unaltered, some species which flourish in Europe, w the seasons are more uniform, would be unable to resist the gr heat of the North American summer, or the intenser cold o winter; while others, now fitted by their habits for the great con of the American seasons, would not be fitted for the *insular* cli of Europe. The vine, for example, according to Humboldt, ca cultivated with advantage 10° farther north in Europe than in North America. Many plants endure severe frost, but cannot ripen their seeds without a certain intensity of summer heat and a certain quantity of light; others cannot endure a similar intensity either of heat or cold.

It is now established that many of the existing species of animals have survived great changes in the physical geography of the globe. If such species be termed modern, in comparison to races which preceded them, their remains, nevertheless, enter into submarine deposits many hundred miles in length, and which have since been raised from the deep to no inconsiderable altitude. When, therefore, it is shown that changes in the temperature of the atmosphere may be the consequence of such physical revolutions of the surface, we ought no longer to wonder that we find the distribution of existing species to be *local*, in regard to *longitude* as well as latitude. If all species were now, by an exertion of creative power, to be diffused uniformly throughout those zones where there is an equal degree of heat, and in all respects a similarity of climate, they would begin from this moment to depart more and more from their original distribution. Aquatic and terrestrial species would be displaced, as Hooke long ago observed, so often as land and water exchanged places; and there would also, by the formation of new mountains and other changes, be transpositions of climate, contributing, in the manner before alluded to, to the local extermination of species.*

If we now proceed to consider the circumstances required for a *general* change of temperature, it will appear, from the facts and principles already laid down, that whenever a greater extent of high land is collected in the polar regions, the cold will augment; and the same result will be produced when there is more sea between or ear the tropics; while, on the contrary, so often as the above conditions are reversed, the heat will be greater. (See figs. 5. and 6. p. 111.) If this be admitted, it will follow, that unless the superficial inequalities of the earth be fixed and permanent, there must be never-ending luctuations in the mean temperature of every zone; and that the limate of one era can no more be a type of every other, than is one f our four seasons of all the rest.

It has been well said, that the earth is covered by an ocean, in the nidst of which are two great islands, and many smaller ones; for the rhole of the continents and islands occupy an area scarcely exceeding ne-fourth of the whole superficies of the spheroid. Now, according o this analogy, we may fairly speculate on the probability that there rould not be usually, at any given epoch of the past, more than about ne-fourth dry land in a particular region; as, for example, near the oles, or between them and the 75th parallels of N. and S. latitude. f, therefore, at present there should happen to be, in both these uarters of the globe, much *more* than this average proportion of land,

---

* A full consideration of the effect of anges in physical geography on the distribution and extinction of species is given in book iii.

some of it in the arctic region being above five thousand feet in hei
and if in antarctic latitudes a mountainous country has been fo
varying from 4000 to 14,000 feet in height, this alone affords gro
for concluding that, in the present state of things, the mean hea
the climate is below that which the earth's surface, in its m
ordinary state, would enjoy. This presumption is heightened wh
we reflect on the results of the recent soundings made by
James Ross, in the Southern Ocean, and continued for four success
years, ending 1844, which seem to prove that the mean depth of
Atlantic and Pacific is as great as Laplace and other eminent astro
mers had imagined*; for then we might look not only for more th
two-thirds sea in the frigid zones, but for water of great depth, wh
could not readily be reduced to the freezing point. The same opin
is confirmed, when we compare the quantity of land lying betw
the poles and the 30th parallels of north and south latitude, with
quantity placed between those parallels and the equator; for, i
clear, that we have at present not only more than the usual de
of cold in the polar regions, but also less than the average quan
of heat within the tropics.

Position of land and sea which might produce the extreme of
of which the earth's surface is susceptible.—To simplify our vie
the various changes in climate, which different combination
geographical circumstances may produce, we shall first consider
conditions necessary for bringing about the extreme of cold, or w
would have been termed in the language of the old writers the wi
of the "great year," or geological cycle, and afterwards, the condit

---

* For calculations founded on astronomical data, see Young's Nat. Phil., Lect. xlvii.; Mrs. Somerville's Connex. of Phys. Sci., sect. 14. p. 110. Laplace, endeavouring to estimate the probable depth of the sea from some of the phenomena of the tides, says of the ocean generally, "que sa profondeur moyenne est du même ordre que la hauteur moyenne des continens et des isles au-dessus de son niveau, hauteur qui ne surpasse pas mille mètres (3280 ft.)." Mec. Céleste, tom. xi. et Syst. du Monde, p. 254. The expression "du même ordre" admits in mathematical language of considerable latitude of signification, and does not mean that the depth of the water below the level of the sea corresponds exactly to the height of the land above it.

It appeared from the observations of Sir James Ross, communicated to me in 1849, by himself and his fellow-voyager, Dr. Joseph Hooker, that in latitude 15° 3′ S., longitude 23° 14′ W. (the island of Trinidad, the nearest land, being 486 miles distant, and bearing S. 47 W.), they sounded with a weight of 76 lbs., and 4600 fathoms of line, which ran out to the very end, without finding bottom.
Here therefore in mid-ocean the
exceeded 27,600 feet. One of
shallowest soundings ever obtaine
the open sea during the same su
struck bottom with 2677 fathom
16,062 feet, latitude 33° 21′ S., long
9° 4′ E. The surveyors arrived
conclusion, that at a moderate dis
from the shore, the depth of the
ocean always exceeds 4000 feet.

During the American survey in
a much greater depth, or 5700 fa
(34,200 feet), was sounded in the At
by Lieut. Walsh, without reachin
bottom, in lat. 31° 59′ N., long. 5
W., or between the Bermudas an
Azores. But the deepest soundin
published were taken Oct. 30. 18
Capt. Henry M. Denham, R. N.,
reached bottom at 7706 fathoms (
feet), lat. 36° 49′ S., long. 37°
the nearest land being at the mo
the River Plate. A weight of 9 lb
attached to the line, which was $\frac{1}{16}$
inch in diameter; the day was cal
the line took 9 hours 24 minutes
out. When the bottom was stru
line was raised 50 fathoms, and
allowed to run out again. It str

requisite to produce the maximum of heat, or the summer of the same year.

To begin with the northern hemisphere. Let us suppose those hills of the Italian peninsula and of Sicily, which are of comparatively modern origin, and contain many fossil shells identical with living species, to subside again into the sea, from which they have been raised, and that an extent of land of equal area and height (varying from one to three thousand feet) should rise up in the Arctic Ocean between Siberia and the north pole. In speaking of such changes, I shall not allude to the manner in which I conceive it possible that they may be brought about, nor of the time required for their accomplishment — reserving for a future occasion, not only the proofs that revolutions of equal magnitude have taken place, but that analogous operations are still in gradual progress. The alteration now supposed in the physical geography of the northern regions would cause additional snow and ice to accumulate where now there is usually an open sea; and the temperature of the greater part of Europe would be somewhat lowered, so as to resemble more nearly that of corresponding latitudes of North America: or, in other words, it might be necessary to travel about 10° farther south in order to meet with the same climate which we now enjoy. No compensation would be derived from the disappearance of land in the Mediterranean countries; but the contrary, since the mean heat of the soil in those latitudes probably exceeds that which would belong to the sea, by which we imagine it to be replaced.

But let the configuration of the surface be still farther varied, and let some large district within or near the tropics, such as Brazil, with its plains and hills of moderate height, be converted into sea, while lands of equal elevation and extent rise up in the arctic circle. From this change there would, in the first place, result a sensible diminution of temperature near the tropic, for the Brazilian soil would no longer be heated by the sun; so that the atmosphere would be less warm, as also the neighbouring Atlantic. On the other hand, the whole of Europe, Northern Asia, and North America, would be chilled by the enormous quantity of ice and snow, thus generated on the new arctic continent. If, as we have already seen, there are now some points in the southern hemisphere where snow is perpetual down to the level of the sea, in latitudes as low as central England, such might assuredly be the case throughout a great part of Europe, under the change of circumstances above supposed: and if at present the extreme range of drifted icebergs is the Azores, they might easily reach the equator after the assumed alteration. But to pursue the subject still farther, let the Himalaya mountains, with the whole of Hindostan, sink down, and their place be occupied by the Indian

---

the same point as before, verifying the observations. Nevertheless some experienced surveyors have remarked that the experiment would have been more satisfactory had the weight been greater. The highest summits of the Himalaya are about 28,000 feet; the Pacific, according to this sounding, is probably at some points twice as deep as the Himalaya are high.

Ocean, while an equal extent of territory and mountains, of the sa vast height, rise up between North Greenland and the Ork Islands. It seems difficult to exaggerate the amount to which th climate of the northern hemisphere would then be cooled.*

But the refrigeration brought about at the same time in th southern hemisphere, would be nearly equal, and the difference i temperature between the arctic and equatorial latitudes would not b much greater than at present; for no important disturbance can occu in the climate of a particular region without its immediately affectin all other latitudes, however remote. The heat and cold whi surround the globe are in a state of constant and universal flux an reflux. The heated and rarefied air is always rising and flowin from the equator towards the poles in the higher regions of th atmosphere; while in the lower, the colder air is flowing back t restore the equilibrium. That this circulation is constantly going o in the aërial currents is not disputed; it is often proved by th opposite course of the clouds at different heights, and the fact ha been farther illustrated in a striking manner by two recent event The trade wind continually blows with great force from the island o Barbadoes to that of St. Vincent; notwithstanding which, durin the eruption of the volcano in the island of St. Vincent, in 181 ashes fell in profusion from a great height in the atmosphere upo Barbadoes.† In like manner, during the great eruption of Sumbaw in 1815, ashes were carried to the islands of Amboyna and Band which last is about 800 miles east from the site of the volcano. Y the south-east monsoon was then at its height.‡ This appare transposition of matter against the wind, confirmed the opinion the existence of a counter-current in the higher regions, which ha previously rested on theoretical conclusions only.

That a corresponding interchange takes place in the seas, demonstrated, according to Humboldt, by the cold which is found exist at great depths within the tropics; and, among other proo may be mentioned the mass of warmer water which the gulf strea is constantly bearing northwards, while a cooler current flows fro the north along the coast of Greenland and Labrador, and helps restore the equilibrium.§

---

* Mr. Hopkins, reasoning on data furnished by Dove's Isothermal maps, has arrived at the very interesting conclusion, that both on Snowdon and the lower mountains of the West of Ireland the snow-line would descend to within 1000 feet of the sea level, and glaciers reach the sea, if we could simply assume the three following geographical changes:—

1st, The diversion of the gulf stream from its present northerly course; 2dly, the depression of the existing land of Northern and Western Europe, to the amount of no more than 500 feet; and 3dly, A cold current from the North sweeping over the submerged ar Quart. Journ. Geol. Soc. 1852, p. 85.

† Daniell's Meteorological Ess p. 103.

‡ Observed by J. Crawfurd, Esq.

§ In speaking of the circulation of and water in this chapter, no allusio made to the trade winds, or to ir gularities in the direction of curre caused by the rotatory motion of the ea These causes prevent the moveme from being direct from north to sou or from south to north, but they do affect the theory of a constant cir lation.

Currents of colder and therefore specifically heavier water pass from the poles towards the equator, which cool the inferior parts of the ocean; so that the heat of the torrid zone and the cold of the polar circle balance each other. The refrigeration, therefore, of the polar regions, resulting from the supposed alteration in the distribution of land and sea, would be immediately communicated to the tropics, and from them its influence would extend to the antarctic circle, where the atmosphere and the ocean would be cooled, so that ice and snow would augment. Although the mean temperature of higher latitudes in the southern hemisphere is, as before stated, for the most part, lower than that of the same parallels in the northern, yet, for a considerable space on each side of the line, the mean annual heat of the waters is found to be the same in corresponding parallels. If, therefore, by the new position of the land, the formation of icebergs had become of common occurrence in the northern temperate zone, and if these were frequently drifted as far as the equator, the same degree of cold which they generated would immediately be communicated as far as the tropic of Capricorn, and from thence to the lands or ocean to the south.

The freedom, then, of the circulation of heat and cold from pole to pole being duly considered, it will be evident that the mean temperature which may prevail at the same point at two distinct periods, may differ far more widely than that of any two points in the same parallels of latitude, at one and the same period. For the range of temperature, or in other words, the curvature of the isothermal lines in a given zone, and at a given period, must always be circumscribed within narrow limits, the climate of each place in that zone being controlled by the combined influence of the geographical peculiarities of all other parts of the earth. Whereas, if we compare the state of things at two distinct and somewhat distant epochs, a particular zone may at one time be under the influence of one class of disturbing causes, and at another time may be affected by an opposite combination. The lands, for example, to the north of Greenland cause the present climate of North America to be colder than that of Europe in the same latitudes; but the excess of cold is not so great as it would have been if the western hemisphere had been entirely isolated, or separated from the eastern like a distinct planet. For not only does the refrigeration produced by Greenland chill to a certain extent the atmosphere of northern and western Europe, but the mild climate of Europe reacts also upon North America, and moderates the chilling influence of the adjoining polar lands.

To return to the state of the earth after the changes above supposed, we must not omit to dwell on the important effects to which a wide expanse of perpetual snow would give rise. It is probable that nearly the whole sea, from the poles to the parallels of 45°, would be frozen over; for it is well known that the immediate proximity of land is not essential to the formation and increase of field ice, provided there be in some part of the same zone a sufficient quantity of glaciers generated on or near the land, to cool down the sea. Captain Scores in his account of the arctic regions, observes, that when the sun's r "fall upon the snow-clad surface of the ice or land, they are i great measure reflected, without producing any material elevatio temperature; but when they impinge on the black exterior of a sh the pitch on one side occasionally becomes fluid while ice is rapid generated at the other." *

Now field ice is almost always covered with snow †; and thus n only land as extensive as our existing continents, but immense tra of sea in the frigid and temperate zones, might present a solid surfa covered with snow, and reflecting the sun's rays for the greater pa of the year. Within the tropics, moreover, where the ocean no predominates, the sky would no longer be serene and clear, as in t present era; but masses of floating ice would cause quick condensatio of vapour, so that fogs and clouds would deprive the vertical rays o the sun of half their power. The whole planet, therefore, wou receive annually a smaller proportion of the solar influence, and th external crust would part, by radiation, with some of the heat whic had been accumulated in it, during a different state of the surfa This heat would be dissipated in the spaces surrounding our atm sphere, which, according to the calculations of M. Fourier, have temperature much inferior to that of freezing water.

After the geographical revolution above assumed, the climate o equinoctial lands might be brought at last to resemble that of the prese temperate zone, or perhaps be far more wintry. They who shoul then inhabit such small isles and coral reefs as are now seen in th Indian Ocean and South Pacific, would wonder that zoophytes of lar dimensions had once been so prolific in their seas; or if, perchanc they found the wood and fruit of the cocoa-nut tree or the pal silicified by the waters of some ancient mineral spring, or incrust with calcareous matter, they would muse on the revolutions which ha annihilated such genera, and replaced them by the oak, the chestnu and the pine. With equal admiration would they compare th skeletons of their small lizards with the bones of fossil alligators an crocodiles more than twenty feet in length, which, at a former epoc had multiplied between the tropics: and when they saw a pi included in an iceberg, drifted from latitudes which we now ca temperate, they would be astonished at the proof thus afforded, th forests had once grown where nothing could be seen in their ow times but a wilderness of snow.

If the reader hesitate to suppose so extensive an alteration temperature as the probable consequence of geographical chang confined to one hemisphere, he should remember how great are t local anomalies in climate now resulting from the peculiar distributi of land and sea in certain regions. Thus, in the island of Sou Georgia, before mentioned (p. 98.), Captain Cook found the eve lasting snows descending to the level of the sea, between lat 54° a 55° S.; no trees or shrubs were to be seen, and in summer a f

---

* See Scoresby's Arctic Regions, vol. i. p. 378.

† Ibid. p. 320.

rocks only, after a partial melting of the ice and snow, were scantily covered with moss and turfs of grass. If such a climate can now exist at the level of the sea in a latitude corresponding to that of Yorkshire in spite of all those equalising causes before enumerated, by which the mixture of the temperatures of distant regions is facilitated throughout the globe, what rigours might we not anticipate in a winter generated by the transfer of the mountains of India to our arctic circle!

But we have still to contemplate the additional refrigeration which might be effected by changes in the relative position of land and sea in the southern hemisphere. If the remaining continents were transferred from the equatorial and contiguous latitudes to the south polar regions, the intensity of cold produced might, perhaps, render the globe uninhabitable. We are too ignorant of the laws governing the direction of subterranean forces, to determine whether such a crisis be within the limits of possibility. At the same time, it may be observed, that no distribution of land can well be imagined more irregular, or, as it were, capricious, than that which now prevails; for at present, the globe may be divided into two equal parts, in such a manner, that one hemisphere shall be almost entirely covered with water, while the other shall contain less water than land (see figs. 3 and 4.)*; and, what is still more extraordinary, on comparing the extratropical lands in the northern and southern hemispheres, the lands in the northern are found to be to those in the southern in the proportion of thirteen to one!† To imagine all the lands, therefore, in high, and all the sea in low latitudes, as delineated in fig. 6. p. 111., would scarcely be a more anomalous state of the surface.

Position of land and sea which might give rise to the extreme of heat.—Let us now turn from the contemplation of the winter of the "great year," and consider the opposite train of circumstances which would bring on the spring and summer. To imagine all the lands to be collected together in equatorial latitudes, and a few promontories only to project beyond the thirtieth parallel, as represented in the annexed maps (figs. 5 and 6.), would be undoubtedly to suppose an extreme result of geological change. But if we consider a mere approximation to such a state of things, it would be sufficient to cause a general elevation of temperature. Nor can it be regarded as a visionary idea, that amidst the revolutions of the earth's surface, the

---

[*] This is shown by projecting a map on the horizon of London, that is to say, by supposing the eye of the observer to be placed above that city, and to see from thence one half of the globe. For it so happens that from that point, and no other, we should behold the greatest possible quantity of land; and if we are then transferred to the opposite or antipodal point, we should see the greatest possible quantity of water. (See figs. 3 and 4.) A singular fact, first pointed out by Mr. James Gardner, namely, that only one twenty-seventh part of the dry land has any land opposite to it, is intimately connected with this excess of land in one of the two hemispheres above alluded to. Thus, in fig. 3., the land shaded black in part of China answers to that portion of the extremity of South America and Tierra del Fuego which is opposite or antipodal to it, whilst the dark spots in the northern and central parts of South America represent Borneo, Sumatra, and other antipodal islands in the Eastern Archipelago. See Gardner, Geol. Soc. Proceedings, 1833, vol. i. p. 488.

[†] Humboldt on Isothermal Lines.

Map showing the present unequal Distribution of Land and Water on the Surface of the Globe.

Fig. 3.



Fig. 4.



Fig. 3 Here London is taken as a centre, and we behold the greatest quantity of land existing in one hemisphere.

Fig. 4. Here the centre is the antipodal point to London, and we see the greatest quantity of water existing in one hemisphere.

The black shading expresses land having land opposite or antipodal to it.

ng the position of Land and Sea which might produce the Extremes of Heat and Cold in the Climates of the Globe.

Fig. 5.



Extreme of Heat.

Fig. 6.



Extreme of Cold.

ı. — These maps are intended to show that continents and islands having the same ve dimensions as those now existing, might be placed so as to occupy either the ar regions.

cely any of the land extends from the Equator towards the poles beyond the 30th de; and in fig. 6. a very small propo tion of it extends from the poles towards the the 40th parallel of latitude.

quantity of land should, at certain periods, have been simultaneou lessened in the vicinity of both the poles, and increased within tropics. We must recollect that even now it is necessary to asce to the height of fifteen thousand feet in the Andes under the line, in the Himalaya mountains, which are without the tropic, to sevente thousand feet, before we reach the limit of perpetual snow. On th northern slope, indeed, of the Himalaya range, where the heat radiat from a great continent moderates the cold, there are meadows a cultivated land at an elevation equal to the height of Mont Blanc. If then there were no arctic lands to chill the atmosphere, and free the sea, and if the loftiest chains were near the line, it seems reaso able to imagine that the highest mountains might be clothed with rich vegetation to their summits, and that nearly all signs of fro would disappear from the earth.

When the absorption of the solar rays was in no region impede even in winter, by a coat of snow, the mean heat of the earth's cr would augment to considerable depths, and springs, which we kn to be in general an index of the mean temperature of the clima would be warmer in all latitudes. The waters of lakes, therefore, a rivers, would be much hotter in winter, and would be never chilled summer by melted snow and ice. A remarkable uniformity of clim would prevail amid the archipelagos of the temperate and polar ocea where the tepid waters of equatorial currents would freely circula The general humidity of the atmosphere would far exceed that of t present period, for increased heat would promote evaporation in parts of the globe. The winds would be first heated in their passa over the tropical plains, and would then gather moisture from surface of the deep, till, charged with vapour, they arrived at extre northern and southern regions, and there encountering a co atmosphere, discharged their burden in warm rain. If, during long night of a polar winter, the snows should whiten the summit some arctic islands, they would be dissolved as rapidly by the retu ing sun, as are the snows of Etna by the blasts of the sirocco.

We learn from those who have studied the geographical distribut of plants, that in very low latitudes, at present, the vegetatio small islands remote from continents has a peculiar character; ferns and allied families, in particular, bearing a great proportio the total number of other plants. Other circumstances being same, the more remote the isles are from the continents, the gre does this proportion become. Thus, in the continent of India, the tropical parts of New Holland, the proportion of ferns to phænogamous plants is only as one to twenty-six; whereas, in South-Sea Islands, it is as one to four, or even as one to three.†

We might expect, therefore, in the summer of the "great y or cycle of climate, that there would be a predominance of tree

---

[*] Humboldt, Tableaux de la Nature, tom. i. p. 112.

[†] Ad. Brongniart, Consid. Générales sur la Nat de la Végét. &c., An Sciences Nat., Nov. 1828.

and plants allied to genera now called tropical, in the islands of the wide ocean, while many forms now confined to arctic and temperate regions, or only found near the equator on the summit of the loftiest mountains, would almost disappear from the earth. Then might those genera of animals return, of which the memorials are preserved in the ancient rocks of our continents. The pterodactyle might flit again through the air, the huge iguanodon reappear in the woods, and the ichthyosaurs swarm once more in the sea. Coral reefs might be prolonged again beyond the arctic circle, where the whale and the narwal now abound; and droves of turtles might begin again to wander through regions now tenanted by the walrus and the seal.

But not to indulge too far in these speculations, I may observe, in conclusion, that however great, during the lapse of ages, may be the vicissitudes of temperature in every zone, it accords with this theory that the general climate should not experience any sensible change in the course of a few thousand years; because that period is insufficient to affect the leading features of the physical geography of the globe.

Notwithstanding the apparent uncertainty of the seasons, it is found that the mean temperature of particular localities is very constant, when observations made for a sufficient series of years are compared.

Yet there must be exceptions to this rule; and even the labours of man have, by the drainage of lakes and marshes, and the felling of extensive forests, caused such changes in the atmosphere as greatly to raise our conception of the more important influence of those forces to which, in certain latitudes, even the existence of land or water, hill or valley, lake or sea, must be ascribed. If we possessed accurate information of the amount of *local* fluctuation in climate in the course of twenty centuries, it would often, undoubtedly, be considerable. Certain tracts, for example, on the coast of Holland and of England consisted of cultivated land in the time of the Romans, which the sea, by gradual encroachments, has at length occupied. Here, at least, a slight alteration has been effected; for neither the distribution of heat in the different seasons, nor the mean annual temperature of the atmosphere investing the sea, is precisely the same as that which rests upon the land.

In those countries, also, where earthquakes and volcanos are in full activity, a much shorter period may produce a sensible variation. The climate of the great table-land of Malpais in Mexico, must differ materially from that which prevailed before the middle of the last century; for, since that time, six mountains, the highest of them rising sixteen hundred feet above the plateau, have been thrown up by volcanic eruptions. It is by the repetition of an indefinite number of such local revolutions, and by slow movements extending simultaneously over wider areas, as will be afterwards shown, that a general change of climate may finally be brought about.

CHAPTER VIII.

ON FORMER CHANGES IN PHYSICAL GEOGRAPHY AND CLIMATE.

Geographical features of the northern hemisphere, at the period of the oldest liferous strata—State of the surface when the mountain limestone and were deposited—Changes in physical geography, between the carbonif period and the chalk—Abrupt transition from the secondary to the tertiary —Accession of land, and elevation of mountain chains, after the consolidati the secondary rocks—Explanation of Map, showing the area covered by since the commencement of the tertiary period—Astronomical theories of causes of variations in climate—Theory of the diminution of the supposed mitive heat of the globe.

In the sixth chapter, I stated the arguments derived from org remains for concluding that in the period when the carbonife strata were deposited, the temperature of the ocean and the air more uniform in the different seasons of the year, and in diffe latitudes, than at present, and that there was a remarkable absen cold as well as great moisture in the atmosphere. It was also sh that the climate had been modified more than once since that ep and that it had been reduced, by successive changes, more and m nearly to that now prevailing in the same latitudes. Farther, I deavoured, in the last chapter, to prove that vicissitudes in cli of no less importance may be expected to recur in future, if i admitted that causes now active in nature have power, in the lap ages, to produce considerable variations in the relative positio land and sea. It remains to inquire whether the alterations, w the geologist can prove to have *actually taken place* at former per in the geographical features of the northern hemisphere, coinci their nature, and in the time of their occurrence, with such r lutions in climate as might naturally have resulted, according t meteorological principles already explained.

Period of the primary fossiliferous rocks.—The oldest syste strata which afford by their organic remains any evidence climate, or the former position of land and sea, are those forn known as the *transition rocks*, or what have since been termed I Silurian or "primary fossiliferous" formations. These have been in England, France, Germany, Sweden, Russia, and other pa central and northern Europe, as also in the great Lake distr Canada and the United States. The multilocular or cham univalves, including the Nautilus, and the corals, obtained fro limestones of these ancient groups, have been compared to form most largely developed in tropical seas. The corals, however, been shown by M. Milne Edwards to differ generally from all zoophytes; so that conclusions as to a warmer climate drawn fro remote analogies must be received with caution. Hitherto, few, if any, contemporaneous vegetable remains have been noticed; but such as are mentioned agree more nearly with the plants of the carboniferous era than any other, and would therefore imply a warm and humid atmosphere entirely free from intense cold throughout the year.

This absence or great scarcity of plants as well as of freshwater shells and other indications of neighbouring land, coupled with the wide extent of marine strata of this age in Europe and North America, are facts which imply such a state of physical geography (so far at least as regards the northern hemisphere) as would, according to the principles before explained, give rise to such a moist and equable climate. (See p. 109. and fig. 5. p. 111.)

Carboniferous group.—This group comes next in the order of succession: and one of its principal members, the mountain limestone, was evidently a marine formation, as is shown by the shells and corals which it contains. That the ocean of that period was of considerable extent in our latitudes, we may infer from the continuity of these calcareous strata over large areas in Europe, Canada, and the United States. The same group has also been traced in North America, towards the borders of the arctic sea.*

There are also several regions in Scotland, and in the central and northern parts of England, as well as in the United States, where marine carboniferous limestones alternate with strata containing coal, in such a manner as to imply the drifting down of plants by rivers into the sea, and the alternate occupation of the same space by fresh and salt water.

Since the time of the earlier writers, no strata have been more extensively investigated, both in Europe and North America, than those of the ancient carboniferous group, and the progress of science has led to a general belief that a large portion of the purest coal has been formed, not, as was once imagined, by vegetable matter floated from a distance, but by plants which grew on the spot, and somewhat in the manner of peat on the spaces now covered by the beds of coal. The former existence of land in some of these spaces has been proved, as already stated, by the occurrence of numerous upright fossil trees, with their roots terminating downwards in seams of coal; and still more generally by the roots of trees (stigmariæ) remaining in their natural position in the clays which underlie almost every layer of coal.

As some nearly continuous beds of such coal have of late years been traced in North America, over areas 100 or 200 miles and upwards in diameter, it may be asked whether the large tracts of ancient land implied by this fact are not inconsistent with the hypothesis of the general prevalence of islands at the period under consideration? In reply, I may observe that the coal-fields must originally have been low alluvial grounds, resembling in situation the cypress-swamps of the Mississippi, or the sunderbunds of the Ganges, being liable them to be inundated at certain periods by a river or by the se the land should be depressed a few feet. All the phenomena, org and inorganic, imply conditions nowhere to be met with except in deltas of large rivers. We have to account for an abundant sup of fluviatile sediment, carried for ages towards one and the sa region, and capable of forming strata of mud and sand thousands feet, or even fathoms, in thickness, many of them consisting of la nated shale, inclosing the leaves of ferns and other terrestrial pla We have also to explain the frequent intercalations of root-beds, the interposition here and there of brackish and marine deposits, monstrating the occasional presence of the neighbouring sea. these forest-covered deltas could only have been formed at the ter nation of large hydrographical basins, each drained by a great riv and its tributaries; and the accumulation of sediment bears testimony contemporaneous denudation on a large scale, and, therefore, to a wi area of land, probably containing within it one or more mount chains.

---

* Sir J. Richardson, Proceedings of Geol. Soc. No. 7. p. 68. March, 1828.

In the case of the great Ohio or Appalachian coal-field, the larg in the world, it seems clear that the uplands drained by one or m great rivers were chiefly to the eastward, or they occupied a sp now filled by part of the Atlantic Ocean, for the mechanical depo of mud and sand increase greatly in thickness and coarseness material as we approach the eastern borders of the coal-field, or south-east flanks of the Alleghany mountains, near Philadelphia. that region numerous beds of pebbles, often of the size of a hen's e are seen to alternate with beds of pure coal.

But the American coal-fields are all comprised within the 30th 50th degrees of north latitude; and there is no reason to presume t the lands at the borders of which they originated ever penetrated so or in such masses into the colder and arctic regions, so as to gene a cold climate. In the southern hemisphere, where the predomina of sea over land is now the distinguishing geographical feature, nevertheless find a large part of the continent of Australia, as wel New Zealand, placed between the 30th and 50th degrees of S. latit The two islands of New Zealand taken together, are between 800 900 miles in length, with a breadth in some parts of ninety miles, they stretch as far south as the 46th degree of latitude. They aff therefore, a wide area for the growth of a terrestrial vegetation, the botany of this region is characterised by abundance of ferns, hundred and forty species of which are already known, some of t attaining the size of trees. In this respect the southern shore New Zealand in the 46th degree of latitude almost vie with trop islands. Another point of resemblance between the Flora of Zealand and that of the ancient carboniferous period is the preval of the fir tribe or of coniferous wood.

An argument of some weight in corroboration of the theory al explained respecting the geographical condition of the temperate arctic latitudes of the northern hemisphere in the carbonife period may also be derived from an examination of those groups of strata which immediately preceded the coal. The fossils of the Devonian and Silurian strata in Europe and North America have led to the conclusion, that they were formed for the most part in deep seas, far from land. In those older strata land plants are almost as rare as they are abundant or universal in the coal measures. Those ancient deposits, therefore, may be supposed to have belonged to an epoch when dry land had only just begun to be upraised from the deep; a theory which would imply the existence during the carboniferous epoch of islands, instead of an extensive continent, in the area where the coal was formed.

Such a state of things prevailing in the north, from the pole to the 30th parallel of latitude, if not neutralized by circumstances of a contrary tendency in corresponding regions south of the line, would give rise to a general warmth and uniformity of climate throughout the globe.

Changes in physical geography between the formation of the carboniferous strata and the chalk.—We have evidence in England that the strata of the ancient carboniferous group, already adverted to, were, in many instances, fractured and contorted, and often thrown into a vertical position, before the deposition of some even of the oldest known secondary rocks, such as the new red sandstone.

Fragments of the older formations are sometimes included in the conglomerates of the more modern; and some of these fragments still retain their fossil shells and corals, so as to enable us to determine the parent rocks from whence they were derived. There are other proofs of the disturbance at successive epochs of different secondary rocks before the deposition of others; and satisfactory evidence that, during these reiterated convulsions, the geographical features of the northern hemisphere were frequently modified, and that from time to time new lands emerged from the deep. The vegetation, during some parts of the period in question (from the lias to the chalk inclusive), when genera allied to Cycas and Zamia were abundant, appears to have approached to that of the larger islands of the equatorial zone; such, for example, as we now find in the West Indian archipelago.* These islands appear to have been drained by rivers of considerable size, which were inhabited by crocodiles and gigantic oviparous reptiles, both herbivorous and carnivorous, belonging for the most part to extinct genera. Of the contemporary inhabitants of the land we have as yet acquired but canty information, but we know that there were flying reptiles, inects, and small mammifers, allied to the marsupial tribes.

A freshwater deposit, called the Wealden, occurs in the upper part f the secondary series of the south of England, which, by its extent nd fossils, attests the existence in that region of a large river raining a continent or island of considerable dimensions. We know that this land was clothed with wood, and inhabited by hu terrestrial reptiles and birds. Its position so far to the north a the counties of Surrey and Sussex, at a time when the mean temperature of the climate is supposed to have been much hotter than a present, may at first sight appear inconsistent with the theory befor explained, that the heat was caused by the gathering together of al the great masses of land in low latitudes, while the northern regions were almost entirely sea. But it must not be taken for granted tha the geographical conditions already described (p. 109., and fig. 4 p. 111.) as capable of producing the extreme of heat were ever combined at any geological period of which we have as yet obtained information. It is more probable, from what has been stated in the preceding chapters, that a slight approximation to such an extrem state of things would be sufficient; in other words, if most of the dry land were tropical, and scarcely any of it arctic or antarctic, a prodigious elevation of temperature must ensue, even though a part o some continents should penetrate far into the temperate zones.

---

* Ad. Brongniart, Consid. Générales sur la Nat. de la Végét. &c., Ann. des Sci. lat., Nov. 1828.

Changes during the tertiary periods.—The secondary and tertiar formations of Europe, when considered separately, may be contraste as having very different characters; the secondary appearing to hav been deposited in open seas, the tertiary in regions where dr land, lakes, bays, and perhaps inland seas, abounded. The secondar series is almost exclusively marine; the tertiary, even the olde part, contains lacustrine strata, and not unfrequently freshwater an marine beds alternating. In fact, there is evidence of importa geographical changes having occurred between the deposition of th cretaceous system, or uppermost of the secondary series, and that the oldest tertiary group, and still more between the era of the latt and that of the newer tertiary formations. This change in t physical geography of Europe and North America was accompani by an alteration no less remarkable in organic life, scarcely any *spec* being common both to the secondary and tertiary rocks, and t fossils of the latter affording evidence of a different climate.

On the other hand, when we compare the tertiary formations successive ages, we trace a gradual approximation in the imbedd fossils, from an assemblage in which extinct species predominate, one where the species agree for the most part with those now exi ing. In other words, we find a gradual increase of animals a plants fitted for our present climates, in proportion as the str which we examine are more modern. Now, during all these s cessive tertiary periods, there are signs of a great increase of land European and North American latitudes. By reference to the m (Pl. 1.). and its description, p. 121., the reader will see that ab two thirds of the present European lands have emerged since earliest tertiary group originated. Nor is this the only revolut which the same region has undergone within the period alluded some tracts which were previously land having gained in altitu others, on the contrary, having sunk below their former level.

That the existing lands were not all upheaved at once into th present position is proved by the most striking evidence. Several Italian geologists, even before the time of Brocchi, had justly inferred that the Apennines were elevated several thousand feet above the level of the Mediterranean before the deposition of the modern Subapennine beds which flank them on either side. What now constitutes the central calcareous chain of the Apennines must for a long time have been a narrow ridgy peninsula, branching off, at its northern extremity, from the Alps near Savona. This peninsula has since been raised from one to two thousand feet, by which movement the ancient shores, and, for a certain extent, the bed of the contiguous sea, have been laid dry, both on the side of the Mediterranean and the Adriatic.

The nature of these vicissitudes will be explained by the accompanying diagram, which represents a transverse section across the Italian peninsula. The inclined strata A are the disturbed formations of the Apennines into which the ancient igneous rocks *a* are supposed to have intruded themselves. At a lower level on each flank of the chain are the more recent shelly beds *b b*, which often contain rounded pebbles derived from the waste of contiguous parts of the older Apennine limestone. These, it will be seen, are horizontal, and lie in what is termed "unconformable stratification" on the more ancient series. They now constitute a line of hills of moderate elevation between the sea and the Apennines, but never penetrate to the higher and more ancient valleys of that chain.

Fig. 7.



The same phenomena are exhibited in the Alps on a much grander scale; those mountains being composed in some even of their higher regions of the newer secondary and oldest tertiary formations, while they are encircled by a great zone of more modern tertiary rocks both on their southern flank towards the plains of the Po, and on the side of Switzerland and Austria, and at their eastern termination towards Styria and Hungary.* This newer tertiary zone marks the position of former seas or gulfs, like the Adriatic, wherein masses of strata accumulated, some single groups of which are not inferior in thickness to the most voluminous of our secondary formations in England. Some even of these newer groups have been raised to the height of three or four thousand feet, and in proportion to their antiquity, they generally rise to greater heights, the older of them forming interior zones nearest to the central ridges of the Alps. We

---

* See a Memoir on the Alps, by Professor Sedgwick and Sir Rod. Murchison, Trans. of Geol. Soc. second ser. vol. iii., accompanied by a map.

have already ascertained that the Alps gained accessions
height and width at several successive periods, and that the la
of movements occurred when the seas were inhabited by many
species of animals.

We may imagine some future series of convulsions once
heave up this stupendous chain, together with the adjoining
the sea, so that the mountains of Europe may rival the A
elevation; in which case the deltas of the Po, Adige, and
now encroaching upon the Adriatic, might be uplifted so as
another exterior belt of considerable height around the south-
flank of the Alps.

The Pyrenees, also, have acquired their present altitude, w
Mont Perdu exceeds eleven thousand feet, since the deposition
nummulitic or Eocene division of the tertiary series. Some
tertiary strata at the base of the chain are raised to the height
a few hundred feet above the sea, and retain a horizontal p
without partaking in general in the disturbances to which th
series has been subjected; so that the great barrier between
and Spain was almost entirely upheaved in the interval betw
deposition of certain groups of tertiary strata.

The remarkable break between the most modern of the
secondary rocks and the oldest tertiary, may be apparent onl
ascribable to the present deficiency of our information. Alre
marles and green sand of Heers near Tongres, in Belgium, obse
M. Dumont, and the "pisolitic limestone" of the neighbourl
Paris, both intermediate in age between the Maestricht chalk
lower Eocene strata, begin to afford us signs of a passage from o
of things to another. Nevertheless, it is far from impossible t
interval between the chalk and tertiary formations constituted
in the earth's history, when the transition from one class of
beings to another was, comparatively speaking, rapid. For
doctrines above explained in regard to vicissitudes of tempera
sound, it will follow that changes of equal magnitude in the
phical features of the globe may at different periods produ
unequal effects on climate; and, so far as the existence of
animals and plants depends on climate, the duration of specie
be shortened or protracted, according to the rate at which the
of temperature proceeded.

For even if we assume that the intensity of the subterran
turbing forces is uniform and capable of producing nearl
amounts of alteration on the surface of the planet, during
periods of time, still the rate of alteration in climate would b
means uniform. Let us imagine the quantity of land betw
equator and the tropic in one hemisphere to be to that in the
thirteen to one, which, as before stated, represents the unequ
portion of the extra-tropical lands in the two hemispheres at
(See figs. 3 and 4. p. 110.) Then let the first geographical change
in the shifting of this preponderance of land from one side of th
the other; from the southern hemisphere, for example, to the n


50
45
40
35
50
45
40
35
Belfast
Dublin
inburgh
Berwick
Newcastle
Chester
London
Bristol
Portsmouth
Brest
Quimper
St Lo
Alencon
Paris
Laval
Angers
Orleans
Nantes
Blois
R. Garonne
Limoges
Clermont
Bordeaux
Cantal
Rodez
Bayonne
Toulouse
Montpellier
R. Rhone
Pampeluna
Oporto
R. Mondego
R. Zezere
Lisbon
R. Tagus
Madrid
R. Guadiana
Villa Nova
Valencia
Gulf of Lyons
Barcelona
Tarragona
Minorca
Majorca
Iviza
Cadiz
Seville
Murcia
Carthagena
Gibraltar
C. Gata
Tangier
El Araish
Sallee
Rabat
Mequinez
Fez
Melilla
Oran
Algiers
R. Mulujah
Azamore
Tedla
A F R I C
5
0
5

r this need not affect the *general* temperature of the earth. But if,
.nother epoch, we suppose a continuance of the same agency to
sfer an equal volume of land from the torrid zone to the tem-
.te and arctic regions of the northern and southern hemispheres,
ıto one of them, there might be so great a refrigeration of the
n temperature *in all latitudes*, that scarcely any of the pre-
ting races of animals would survive; and, unless it pleased the
hor of Nature that the planet should be uninhabited, new species,
probably of widely different forms, would then be substituted in
room of the extinct. We ought not, therefore, to infer that equal
ods of time are always attended by an equal amount of change in
nic life, since a great fluctuation in the mean temperature of the
h, the most influential cause which can be conceived in exter-
ting whole races of animals and plants, must, in different epochs,
ire unequal portions of time for its completion.

I. *Map showing the extent of surface in Europe which has at one period*
another been covered by the sea since the commencement of the deposition of the
er or Eocene Tertiary strata.

map will enable the reader to perceive at a glance the great
nt of change in the physical geography of Europe, which can be
ed to have taken place since some of the older tertiary strata
n to be deposited. The proofs of submergence, during some part
her of this period, in all the districts distinguished by ruled lines,
of a most unequivocal character; for the area thus described is
covered by deposits containing the fossil remains of animals
h could only have lived in salt water. The most ancient part of
period referred to cannot be deemed very remote, considered
gically; because the deposits of the Paris and London basins,
many other districts belonging to the older tertiary epoch, are
r than the greater part of the sedimentary rocks (those com-
ly called secondary and primary fossiliferous or paleozoic) of
h the crust of the globe is composed. The species, moreover,
arine testacea, of which the remains are found in these older
ary formations, are not entirely distinct from such as now live.
notwithstanding the comparatively recent epoch to which this
spect is carried, the variations in the distribution of land and
lepicted on the map form only a part of those which must have
n place during the period under consideration. Some approxi-
on has merely been made to an estimate of the amount of *sea*
erted into land in parts of Europe best known to geologists; but
annot determine how much land has become sea during the same
d; and there may have been repeated interchanges of land and
r in the same places, changes of which no account is taken in the
and respecting the amount of which little accurate information
ver be obtained.

have extended the sea in some instances beyond the limits of
and now covered by tertiary formations, and marine drift, because

other geological data have been obtained for inferring the submergence of these tracts after the deposition of the Eocene strata had begun. Thus, for example, there are good reasons for concluding that part of the chalk of England (the North and South Downs, for example, together with the intervening secondary tracts) continued beneath the sea until the oldest tertiary beds had begun to accumulate.

A strait of the sea separating England and Wales has also been introduced, on the evidence afforded by shells of existing species found in a deposit of gravel, sand, loam, and clay, called the northern drift, by Sir R. Murchison.* And Mr. Trimmer has discovered similar recent marine shells on the northern coast of North Wales, and on Moel Tryfane, near the Menai Straits, at the height of 1392 feet above the level of the sea!

Some raised sea-beaches, and drift containing marine shells, which I examined in 1843, between Limerick and Dublin, and which have been traced over other parts of Ireland by different geologists, have required an extension of the dark lines so as to divide that island into several. In improving this part of my map I have been especially indebted to the assistance of Mr. Oldham, who in 1843 announced to the British Association at Cork the fact that at the period when the drift or glacial beds were deposited, Ireland must have formed an archipelago such as is here depicted. A considerable part of Scotland might also have been represented in a similar manner as under water when the drift originated.

A portion of Brittany is divided into islands, because it is known to be covered with patches of marine tertiary strata chiefly miocene. When I examined these in 1830 and 1843, I convinced myself that the sea must have covered much larger areas than are now occupied by these small and detached deposits. The former connection of the White Sea and the Gulf of Finland is proved by the fact that a multitude of huge erratic blocks extend over the intervening space, and a large portion of Norway, Sweden, and Denmark, as well as Germany and Russia, are represented as sea, on the same evidence, strengthened by the actual occurrence of fossil sea-shells, of recent species, in the drift of various portions of those countries. The submergence of considerable areas under large bodies of fresh water, during the tertiary period, of which there are many striking geological proofs in Auvergne, and elsewhere, has not been expressed by ruled lines. They bear testimony to the former existence of neighbouring lands, and a certain elevation of the areas where they occur above the level of the ocean; they are therefore left blank, together with all the space that cannot be demonstrated to have been part of the sea at some time or other, since the commencement of the Eocene epoch.

In compiling this map, which has been entirely recast since the first edition, I have availed myself of the latest geological maps of the

---

* See Proceedings of Geol. Soc. vol. ii. p. 334.

British isles, and north of Europe; also of those published by the government surveyors of France, MM. de Beaumont and Dufresnoy; the map of Germany and part of Europe, by Von Dechen, and that of Italy by M. Tchihatchoff (Berlin, 1842). Lastly, Sir R. Murchison's important map of Russia, and the adjoining countries, has enabled me to mark out not only a considerable area, previously little known, in which tertiary formations occur; but also a still wider expanse, over which the northern drift, and erratic blocks with occasional marine shells, are traceable. The southern limits of these glacial deposits in Russia and Germany indicate the boundary, so far as we can now determine it, of the northern ocean, at a period immediately antecedent to that of the human race.

I was anxious, even in the title of this map, to guard the reader against the supposition that it was intended to represent the state of the physical geography of part of Europe at any *one point of time.* The difficulty, or rather the impossibility, of restoring the geography of the globe as it may have existed at any former period, especially a remote one, consists in this, that we can only point out where part of the sea has been turned into land, and are almost always unable to determine what land may have become sea. All maps, therefore, pretending to represent the geography of remote geological epochs must be ideal. The map under consideration is not a restoration of a former state of things, at any particular moment of time, but a synoptical view of a certain amount of one kind of change (the conversion of sea into land) known to have been brought about within a given period.

It may be proper to remark that the vertical movements to which the land is subject in certain regions, occasion alternately the subsidence and the uprising of the surface; and that, by such oscillations at successive periods, a great area may have been entirely covered with marine deposits, although the whole may never have been beneath the waters at one time; nay, even though the relative proportion of land and sea may have continued unaltered throughout the whole period. I believe, however, that since the commencement of the tertiary period, the dry land in the northern hemisphere has been continually on the increase, both because it is now greatly in excess beyond the average proportion which land generally bears to water on the globe, and because a comparison of the secondary and tertiary strata affords indications, as I have already shown, of a passage from the condition of an ocean interspersed with islands to that of a large continent.

But supposing it were possible to represent all the vicissitudes in the distribution of land and sea that have occurred during the tertiary period, and to exhibit not only the actual existence of land where there was once sea, but also the extent of surface now submerged which may once have been land, the map would still fail to express all the important revolutions in physical geography which have taken place within the epoch under consideration. For the oscillations of level, as was before stated, have not merely been such as to lift up the land from below the water, but in some cases to occasion a rise of many thousand feet above the sea. Thus the Alps have acquired an additional altitude of 4000, and even in some places 10,000 feet; and the Apennines owe a considerable part of their present height to subterranean convulsions which have happened within the tertiary epoch.

On the other hand, some mountain chains may have been lowered during the same series of ages, in an equal degree, and shoals may have been converted into deep abysses.* Since this map was recast in 1847, geologists have very generally come to the conclusion that the nummulitic limestone, together with the overlying fucoidal grit and shale, called "Flysch," in the Alps, belongs to the older tertiary or Eocene group. As these nummulitic rocks enter into the structure of some of the most lofty and disturbed parts of the Alps, Apennines, Carpathians, Pyrenees, and other mountain chains, and form many of the elevated lands of Africa and Asia, their position almost implies the ubiquity of the post-Eocene ocean, not, indeed, by the simultaneous, but by the successive, occupancy of the whole ground by its waters.†

Concluding remarks on changes in physical geography.—The foregoing observations, it may be said, are confined chiefly to Europe, and therefore merely establish the increase of dry land in a space which constitutes but a small portion of the northern hemisphere; but it was stated in the preceding chapter, that the great Lowland of Siberia, lying chiefly between the latitudes 55° and 75° N. (an area nearly equal to all Europe), is covered for the most part by marine strata, which, from the account given by Pallas, and more recently by Sir R. Murchison, belongs to a period when all or nearly all the shells were of a species still living in the north. The emergence, therefore, of this area from the deep is, comparatively speaking, a very modern event, and must, as before remarked, have caused a great increase of cold throughout the globe.

Upon a review, then, of all the facts above enumerated, respecting the ancient geography of the globe as attested by geological monuments, there appear good grounds for inferring that changes of climate coincided with remarkable revolutions in the former position of sea and land. A wide expanse of ocean, interspersed with islands, seems to have pervaded the northern hemisphere at the periods when the Silurian and carboniferous rocks were formed, and a warm and very uniform temperature then prevailed. Subsequent modifications in climate accompanied the deposition of the secondary formations, when repeated changes were effected in the physical geography of our northern latitudes. Lastly, the refrigeration became most decided, and the climate most nearly assimilated to that now enjoyed, when the lands in Europe and northern Asia had attained their full extension, and the mountain chains their actual height.

---

* It may be observed, that the facts and inferences exhibited in this map bear not merely on the theory of climate above proposed, but serve also to illustrate the views explained in the third book respecting the migrations of animals and plants and the gradual extinction of species.

† See Sir R. Murchison's Paper on the Alps, Quart. Journ. Geol. Soc. vol. v.; and my Anniversary Address for 1850, ibid. vol. vi.

Soon after the first publication of this theory of climate, an objection was made by an anonymous German critic in 1833 that there are no geological proofs of the prevalence at any former period of a temperature *lower* than that now enjoyed; whereas, if the causes above assigned were the true ones, it might reasonably have been expected that fossil remains would sometimes indicate colder as well as hotter climates than those now established.* In answer to this objection, I may suggest, that our present climates are probably far more distant from the extreme of possible heat than from its opposite extreme of cold. A glance at the map (fig. 6. p. 111.) will show that all the existing lands might be placed between the 30th parallels of latitude on each side of the equator, and that even then they would by no means fill that space. In no other position would they give rise to so high a temperature. But the present geographical condition of the earth is so far removed from such a state of things, that the land lying between the poles and the parallels of 30, is in great excess; so much so that, instead of being to the sea in the proportion of 1 to 3, which is as near as possible the average general ratio throughout the globe, it is 9 to 23.† Hence it ought not to surprise us if, in our geological retrospect, embracing perhaps a small part only of a complete cycle of change in the terrestrial climates, we should happen to discover every where the signs of a higher temperature. The strata hitherto examined may have originated when the quantity of equatorial land was always decreasing and the land in regions nearer the poles augmenting in height and area, until at length it attained its present excess in high latitudes. There is nothing improbable in supposing that the geographical revolutions of which we have hitherto obtained proofs had this general tendency; and in that case the refrigeration must have been constant, although, for reasons before explained, the rate of cooling may not have been uniform.

It may, however, be as well to recall the reader's attention to what was before said of the indication brought to light of late years, of a considerable oscillation of temperature, in the period immediately preceding the human era. We have seen that on examining some of the most northern deposits, those commonly called the northern drift

---

* Allgemeine Literatur Zeitung, No. cxxxix. July, 1833.

† In this estimate, the space within the antarctic circle is not taken into account: if included, it would probably add to the excess of dry land: for the late discoveries of Capt. Sir James Ross, who penetrated to lat. 78° 10′ S., confirm the conjecture of Captain Cook that the accumulation of antarctic ice implies the presence of a certain quantity of terra firma. The number of square miles on the surface of the globe are 148,522,000, the part occupied by the sea being 110,849,000, and that by land, 37,673,000; so that the land is very nearly to the sea as 1 part in 4. I am informed by Mr. Gardner that, according to a rough approximation, the land between the 30° N. lat. and the pole occupies a space *about equal to that of the sea*, and the land between the 30° S. lat. and the antarctic circle about $\frac{1}{16}$ of that zone

in Scotland, Ireland, and Canada, in which nearly all, in some ca
perhaps all, the fossil shells are of recent species, we discover
signs of a climate colder than that now prevailing in correspon
latitudes on both sides the Atlantic. It appears that an arctic fa
specifically resembling that of the present seas, extended farthe
the south than now. This opinion is derived partly from the kn
habitations of the corresponding living species, and partly from
abundance of certain genera of shells and the absence of oth
The date of the refrigeration thus inferred appears to coincide
nearly with the era of the dispersion of erratic blocks over Eu
and North America, a phenomenon which will be ascribed in
sequel (ch. 16.), to the cold then prevailing in the northern h
sphere. The force, moreover, of the German critic's objection
been since in a great measure destroyed, by the larger and m
profound knowledge acquired in the last few years of the anc
carboniferous flora, which has led the ablest botanists to adopt
opinion, that the climate of the coal period was remarkable fo
warmth, moisture, equability, and freedom from cold, rather than
intensity of its *tropical heat.* We are therefore no longer entitle
assume that there has been a constant and gradual decline in
absolute amount of heat formerly contained in the atmosphere
waters of the ocean, such as it was conjectured might have eman
from the incandescent central nucleus of a new and nearly
planet, before the interior had lost, by radiation into surroun
space, a great part of its original high temperature.

Astronomical causes of fluctuations in climate.—Sir John Her
has lately inquired, whether there are any astronomical causes w
may offer a possible explanation of the difference between the ac
climate of the earth's surface, and those which formerly appea
have prevailed. He has entered upon this subject, he says, "
pressed with the magnificence of that view of geological revoluti
which regards them rather as regular and necessary effects of g
and general causes, than as resulting from a series of convulsions
catastrophes, regulated by no laws, and reducible to no fixed p
ciples." Geometers, he adds, have demonstrated the absolute in
riability of the mean distance of the earth from the sun; when
would at first seem to follow, that the mean annual supply of l
and heat derived from that luminary would be alike invariable:
a closer consideration of the subject will show, that this would no
a legitimate conclusion; but that on the contrary, the *mean* am
of solar radiation is dependent on the excentricity of the earth's o
and therefore liable to variation.†

---

* See papers by Mr. Smith of Jordanhill, F.G.S., and the author, Proceedings Geol. Soc. No. 63., 1839, also that of Prof. E. Forbes, before cited, p. 86. note.

† The theorem is thus stated:—"The excentricity of the orbit varying, the total quantity of heat received by the earth from the sun in one revolution is inversely proportional to the minor
of the orbit. The major axis i
variable, and therefore, of course,
absolute length of the year: hen
follows that the mean annual avera
heat will also be in the same in
ratio of the minor axis."—Geol. T
second series, vol. iii. p. 295.

Now the eccentricity of the orbit, he continues, is actually diminishing, and has been so for ages beyond the records of history. In consequence, the ellipse is in a state of approach to a circle, and the annual average of solar heat radiated to the earth is actually on the *decrease*. So far this is in accordance with geological evidence, which indicates a general refrigeration of climate; but the question remains, whether the amount of diminution which the eccentricity may have ever undergone can be supposed sufficient to account for any sensible refrigeration. The calculations necessary to determine this point, though practicable, have never yet been made, and would be extremely laborious; for they must embrace all the perturbations which the most influential planets, Venus, Mars, Jupiter, and Saturn, would cause in the earth's orbit, and in each other's movements round the sun.

The problem is also very complicated, inasmuch as it depends not merely on the ellipticity of the earth's orbit, but on the assumed temperature of the celestial spaces beyond the earth's atmosphere; a matter still open to discussion, and on which M. Fourier and Sir J. Herschel have arrived at very different opinions. But if, says Herschel, we suppose an extreme case, as if the earth's orbit should ever become as excentric as that of the planet Juno or Pallas, a great change of climate might be conceived to result, the winter and summer temperatures being sometimes mitigated, and at others exaggerated, in the same latitudes.

It is much to be desired that the calculations alluded to were executed, as even if they should demonstrate, as M. Arago thinks highly probable*, that the mean amount of solar radiation can never be materially affected by irregularities in the earth's motion, it would still be satisfactory to ascertain the point. Such inquiries, however, can never supersede the necessity of investigating the consequences of the varying position of continents, shifted as we know them to have been during successive epochs, from one part of the globe to the other.

Another astronomical hypothesis respecting the possible cause of secular variations in climate, has been proposed by a distinguished mathematician and philosopher, M. Poisson. He begins by assuming 1st, that the sun and our planetary system are not stationary, but carried onward by a common movement through space; 2dly, that every point in space receives heat as well as light from innumerable stars surrounding it on all sides, so that if a right line of indefinite length be produced in any direction from such point, it must encounter a star either visible or invisible to us. 3dly, He then goes on to assume, that the different regions of space, which in the course of millions of years are traversed by our system, must be of very unequal temperature, inasmuch as some of them must receive a greater, others a less, quantity of radiant heat from the great stellary inclosure. If the earth, he continues, or any other large body, pass

* Ann. du Bur. des Long. 1834.

from a hotter to a colder region, it would not readily lose in the second all the heat which it has imbibed in the first region, but retain a temperature increasing downwards from the surface, as in the actual condition of our planet.[*]

Now the opinion originally suggested by Sir W. Herschel, that our sun and its attendant planets were all moving onward through space, in the direction of the constellation Hercules, is very generally thought by eminent astronomers to be confirmed. But even if its reality be no longer matter of doubt, conjectures as to its amount are still vague and uncertain; and great, indeed, must be the extent of the movement before this cause alone can work any material alteration in the terrestrial climates. Mr. Hopkins, when treating of this theory, remarked, that so far as we are acquainted with the position of stars not very remote from the sun, they seem to be so distant from each other, that there are no points in space among them, where the intensity of radiating heat would be comparable to that which the earth derives from the sun, except at points very near to each star. Thus, in order that the earth should derive a degree of heat from stellar radiation comparable to that now derived from the sun, she must be in close proximity to some particular star, leaving the aggregate effect of radiation from the other stars nearly the same as at present. This approximation, however, to a single star could not take place consistently with the preservation of the motion of the earth about the sun, according to its present laws.

Suppose our sun should approach a star within the present distance of Neptune. That planet could no longer remain a member of the solar system, and the motions of the other planets would be disturbed in a degree which no one has ever contemplated as probable since the existence of the solar system. But such a star, supposing it to be no larger than the sun, and to emit the same quantity of heat, would not send to the earth much more than one-thousandth part of the heat which she derives from the sun, and would therefore produce only a very small change in terrestrial temperature.[†]

Variable splendour of stars.—There is still another astronomical suggestion respecting the possible causes of secular variations in the terrestrial climates which deserves notice. It has long been known that certain stars are liable to great and periodical fluctuations in splendour, and Sir J. Herschel has lately ascertained (Jan. 1840), that a large and brilliant star, called *alpha* Orionis, sustained, in the course of six weeks, a loss of nearly half its light. "This phenomenon," he remarks, "cannot fail to awaken attention, and revive those speculations which were first put forth by my father Sir W. Herschel, respecting the possibility of a change in the lustre of *our sun itself*. If there really be a community of nature between the sun and fixed stars, every proof that we obtain of the extensive prevalence of such periodical changes in those remote bodies, adds to the pro-ability of finding something of the kind nearer home." Referring hen to the possible bearing of such facts on ancient revolutions, in errestrial climates, he says, that, "it is a matter of observed fact, hat many stars *have* undergone, in past ages, within the records of stronomical history, very extensive changes in apparent lustre, vithout a change of distance adequate to producing such an effect. f our sun were even *intrinsically* much brighter than at present, the nean temperature of the surface of our globe would, of course, be roportionally greater. I speak now not of periodical, but of secular hanges. But the argument is complicated with the consideration of he possibly imperfect transparency of the celestial spaces, and with he cause of that imperfect transparency, which may be due to mateial non-luminous particles diffused irregularly in patches analogous o nebulæ, but of greater extent—to *cosmical clouds*, in short—of vhose existence we have, I think, some indication in the singular and pparently capricious phenomena of temporary stars, and perhaps in he recent extraordinary sudden increase and hardly less sudden liminution of η *Argus*."*

---

[*] Poisson, Théorie Mathémat. de la Chaleur, Comptes Rendus de l'Acad. des Sci., Jan. 30. 1837.

[†] Quart. Journ. Geol. Soc. 1852. p. 62.

More recently (1852) Schwabe has observed that the spots on the un alternately increase and decrease in the course of every ten ears, and Captain Sabine has pointed out that this variable obscuation coincides in time both as to its maximum and minimum with hanges in all those terrestrial magnetic variations which are caused y the sun. Hence he infers that the period of alteration in the pots is a *solar magnetic period.* Assuming such to be the case, the ariable light of some stars may indicate a similar phenomenon, or they nay be stellar magnetic periods, differing only in the degree of bscuration and its duration. And as hitherto we have perceived no luctuation in the heat received by the earth from the sun coincident rith the solar magnetic period, so the fluctuations in the brilliancy of he stars may not perhaps be attended with any perceptible alteration n their power of radiating heat. But before we can speculate with dvantage in this new and interesting field of inquiry, we require nore facts and observations.

Supposed gradual diminution of the earth's primitive heat.—The radual diminution of the supposed primitive heat of the globe has een resorted to by many geologists as the principal cause of alteraions of climate. The matter of our planet is imagined, in accordance rith the conjectures of Leibnitz, to have been originally in an ntensely heated state, and to have been parting ever since with ortions of its heat, and at the same time contracting its dimensions. There are, undoubtedly, good grounds for inferring from recent bservation and experiment, that the temperature of the earth ncreases as we descend from the surface to that slight depth to which nan can penetrate: but there are no positive proofs of a secular ecrease of internal heat accompanied by contraction. On the contrary, La Place has shown, by reference to astronomical observations made in the time of Hipparchus, that in the last two thousa years at least there has been no sensible contraction of the glo by cooling; for had this been the case, even to an extremely sma amount, the day would have been shortened, whereas its length ha certainly not diminished during that period by $\frac{1}{300}$th of a second.

---

* Proceedings Roy. Astronom. Soc. No. iii. Jan. 1840.

Baron Fourier, after making a curious series of experiments on th cooling of incandescent bodies, considers it to be proved mathematically, that the actual distribution of heat in the earth's envelope i precisely that which would have taken place if the globe had bee formed in a medium of a very high temperature, and had afterward been constantly cooled.* He contends, that although no contractio can be demonstrated to have taken place within the historical perio (the operation being slow and the time of observation limited), yet i is no less certain that heat is annually passing out by radiation fro the interior of the globe into the planetary spaces. He even undertook to demonstrate that the quantity of heat thus transmitted in space in the course of every century, through every square metre o the earth's surface, would suffice to melt a column of ice having square metre for its base, and being three metres (or 9 feet 10 inche high.

It is at the same time denied, that there is any assignable mode i which the heat thus lost by radiation can be again restored to t earth, and consequently the interior of our planet must, from t moment of its creation, have been subject to refrigeration, and destined together with the sun and stars for ever to grow colde But I shall point out in the sequel (chapter 31.) many objections these views and to the theory of the intense heat of the earth's centr nucleus, and shall then inquire how far the observed augmentation temperature, as we descend below the surface, may be referable other causes unconnected with the supposed pristine fluidity of t entire globe.

CHAPTER IX.

THEORY OF THE PROGRESSIVE DEVELOPMENT OF ORGANIC LIFE SUCCESSIVE GEOLOGICAL PERIODS.

Theory of the progressive development of organic life — Evidence in its sup inconclusive — Vertebrated animals, and plants of the most perfect organizat in strata of very high antiquity — Differences between the organic remain successive formations — Comparative modern origin of the human race — popular doctrine of successive development not established by the admis that man is of modern origin — Introduction of man, to what extent a chang the system.

Progressive development of organic life. — In the preceding chapte have considered whether revolutions in the general climate of obe afford any just ground of opposition to the doctrine that the rmer changes of the earth which are treated of in geology belong one uninterrupted series of physical events governed by ordinary uses. Against this doctrine some popular arguments have been rived from the great vicissitudes of the organic creation in times st; I shall therefore proceed to the discussion of such objections, hich have been thus formally advanced by the late Sir Humphrey avy. "It is impossible," he affirms, "to defend the proposition, at the present order of things is the ancient and constant order of ture, only modified by existing laws: in those strata which are epest, and which must, consequently, be supposed to be the earliest posited, forms even of vegetable life are rare; shells and vegetable mains are found in the next order; the bones of fishes and oviparous ptiles exist in the following class; the remains of birds, with those the same genera mentioned before, in the next order; those of adrupeds of extinct species in a still more recent class; and it is ly in the loose and slightly consolidated strata of gravel and sand, d which are usually called diluvian formations, that the remains of imals such as now people the globe are found, with others belonging extinct species. But, in none of these formations, whether called condary, tertiary, or diluvial, have the remains of man, or any of s works, been discovered; and whoever dwells upon this subject ust be convinced, that the present order of things, and the comparavely recent existence of man as the master of the globe, is as certain the destruction of a former and a different order, and the extinction a number of living forms which have no types in being. In the dest secondary strata there are no remains of such animals as now long to the surface; and in the rocks, which may be regarded as ore recently deposited, these remains occur but rarely, and with undance of extinct species;—there seems, as it were, a gradual proach to the present system of things, and a succession of deructions and creations preparatory to the existence of man."*

---

* See a Memoir on the Temperature of the Terrestrial Globe, and the Planetary Spaces, Ann. de Chimi Phys. tom. xxvii. p. 136. Oct. 182

In the above passages, the author deduces two important conclusions om geological data: first, that in the successive groups of strata, om the oldest to the most recent, there is a progressive development organic life, from the simplest to the most complicated forms;—condly, that man is of comparatively recent origin, and these nclusions he regards as inconsistent with the doctrine, "that the resent order of things is the ancient and constant order of nature ly modified by existing laws."

With respect, then, to the first of these propositions, we may ask hether the theory of the progressive development of animal and getable life, and their successive advancement from a simple to a ore perfect state, has any secure foundation in fact? No geologists ho are in possession of all the data now established respecting fossil mains, will for a moment contend for the doctrine in all its detail, laid down by the distinguished philosopher to whose opinions we have referred: but naturalists, who are not unacquainted with rec discoveries, continue to defend it in a modified form. They say t in the first period of the world (by which they mean the earlies which we have yet brought to light any memorials), the vegeta was characterized by a predominance of cryptogamic plants, while animals which co-existed were almost entirely confined to zoophy testacea, and a few fish. Plants of a less simple structure, conif and cycadeæ, flourished largely in the next epoch, when ovipar reptiles began also to abound. Lastly, the terrestrial flora bec most diversified and most perfect when the highest orders of anim the mammalia and birds, were called into existence.

---

* Sir H. Davy, Consolations in Travel: Dialogue III. "The Unknown."

Now in the first place, it may be observed, that many natura are guilty of no small inconsistency in endeavouring to connect phenomena of the earliest vegetation with a nascent conditio organic life, and at the same time to deduce from the numeri predominance of certain forms, the greater heat or uniformity of ancient climate. The arguments in favour of the latter conclu are without any force, unless we can assume that the rules follow by the Author of Nature in the creation and distribution of orga beings were the same formerly as now; and that, as certain familie animals and plants are now most abundant in, or exclusively confi to regions where there is a certain temperature, a certain degre humidity, a certain intensity of light, and other conditions, so analogous phenomena were exhibited at every former era.

If this postulate be denied, and the prevalence of particular fami be declared to depend on a certain order of precedence in introduction of different classes into the earth, and if it be maintai that the standard of organization was raised successively, we m then ascribe the numerical preponderance, in the earlier ages plants of simpler structure, *not to the heat*, or other climatal c ditions, but to those different laws which regulate organic lif newly created worlds.

Before we can infer a warm and uniform temperature in h latitudes, from the presence of 250 species of ferns, some of t arborescent, accompanied by lycopodiaceæ of large size, and arauca we must be permitted to assume, that at all times, past, present, future, a heated and moist atmosphere pervading the northern he phere has a tendency to produce in the vegetation a predominanc analogous forms.

It should moreover be borne in mind, when we are considering question of development from a botanical point of view, that n ralists are by no means agreed as to the existence of an ascen scale of organization in the vegetable world corresponding to which is very generally recognized in animals. "From the sp to man," in the language of De Blainville, there may be a prog sive chain of being, although often broken and imperfect; b we seek to classify plants according to a linear arrangement, asc ing gradually from the lichen to the lily or the rose, we enco incomparably greater difficulties. Yet the doctrine of a more h developed organization in the plants created at successive periods presupposes the admission of such a graduated scale.

We have as yet obtained but scanty information respecting the state of the terrestrial flora at periods antecedent to the coal. In the carboniferous epoch, about 500 species of fossil plants are enumerated by Adolphe Brongniart, which we may safely regard as a mere fragment of an ancient flora; since, in Europe alone, there are now no less than 11,000 living species. I have already hinted that the plants which produced coal were not drifted from a distance, but that nearly all of them grew on the spots where they became fossil. They appear to have belonged, as before explained (p. 115.), to a peculiar class of *stations*, — to low level and swampy regions, in the deltas of large rivers, slightly elevated above the level of the sea. From the study, therefore, of such a vegetation we can derive but little insight into the nature of the contemporaneous upland flora, still less of the plants of the mountainous or Alpine country; and if so, we are enabled to account for the apparent monotony of the vegetation, although its uniform character was doubtless in part owing to a greater uniformity of climate then prevailing throughout the globe. Some of the commonest trees of this period, such as the sigillariæ, which united the structure of ferns and of cycadeæ, departed very widely from all known living types. The coniferæ and ferns, on the contrary, were very closely allied to living genera. It is remarkable that none of the exogens of Lindley (dicotyledonous angiosperms of Brongniart), which comprise four-fifths of the living flora of the globe, and include all the forest trees of Europe except the fir-tribe, have yet been discovered in the coal measures, and a very small number — fifteen species only — of monocotyledons. If several of these last are true palms, an opinion to which Messrs. Lindley, Unger, Corda, and other botanists of note incline, the question whether any of the most highly organized plants are to be met with in ancient strata is at once answered in the affirmative. But the determination of these palms being doubtful, we have as yet in the coal no positive proofs either of the existence of the most perfect, or of the most simple forms of flowering or flowerless vegetation. We have no fungi, lichens, hepatici or mosses: yet this latter class may have been as fully represented then as now.

In the flora of the secondary eras, all botanists agree that palms existed, although in Europe plants of the family of zamia and cycas together with coniferæ predominated, and must have given a peculiar aspect to the flora. As only 200 or 300 species of plants are known in all the rocks ranging from the Trias to the Oolite inclusive, our data are too scanty as yet to affirm whether the vegetation of this second epoch was or was not on the whole of a simpler organization than that of our own times.

In the Lower Cretaceous formation, near Aix-la-Chapelle, the leaves of a great many dicotyledonous trees have lately been discovered by Dr. Debey, establishing the important fact of the co-existence of a large number of angiosperms with cycadeæ, and with that rich reptilian fauna comprising the icthyosaur, plesiosaur, and pterodactyl, which some had supposed to indicate a state of the atmosphere un favourable to a dicotyledonous vegetation.

The number of plants hitherto obtained from *tertiary* strata of di ferent ages is very limited, but is rapidly increasing. They are re ferable to a much greater variety of families and classes than a equal number of fossil species taken from secondary or primary rock the angiosperms bearing the same proportion to the gymnosperms an acrogens as in the present flora of the globe. This greater variet may, doubtless, be partly ascribed to the greater diversity of station in which the plants grew, as we have in this case an opportunit rarely enjoyed in studying the secondary fossils, of investigating inlan or lacustrine deposits accumulated at different heights above the se and containing the memorials of plants washed down from adjoinin mountains.

In regard, then, to the strata from the cretaceous to the upperm tertiary inclusive, we may affirm that we find in them all the princip classes of living plants, and during this vast lapse of time four or f complete changes in the vegetation occurred, yet no step whatev was made in advance at any of these periods by the addition of mo highly organized species.

If we next turn to the fossils of the animal kingdom, we may i quire whether, when they are arranged by the geologist in a chro logical series, they imply that beings of a more highly develop structure and greater intelligence entered upon the earth at success epochs, those of the simplest organization being the first creat and those more highly organized being the last.

Our knowledge of the Silurian fauna is at present derived entir from rocks of marine origin, no fresh-water strata of such high a quity having yet been met with. The fossils, however, of these anci rocks at once reduce the theory of progressive development to wit very narrow limits, for already they comprise a very full represen tion of the radiata, mollusca, and articulata proper to the sea. Th in the great division of radiata, we find asteroid and helianthoid phytes, besides crinoid and cystidean echinoderms. In the mollu between 200 and 300 species of cephalopoda are enumerated. In articulata we have the crustaceans represented by more than 200 spe of trilobites, besides other genera of the same class. The remain fish are as yet confined to the upper part of the Silurian series; some of these belong to placoid fish, which occupy a high grad the scale of organization. Some naturalists have assumed that earliest fauna was exclusively marine, because we have not yet fo a single Silurian helix, insect, bird, terrestrial reptile or mammi but when we carry back our investigations to a period so remote f the present, we ought not to be surprised if the only accessible st should be limited to deposits formed far from land, because the o probably occupied then, as now, the greater part of the ea surface. After so many entire geographical revolutions, the cha are nearly three to one in favour of our finding that such small port of the existing continents and islands as expose Silurian strat view, should coincide in position with the ancient ocean rather than the land. We must not, therefore, too hastily infer, from the absence of fossil bones of mammalia in the older rocks, that the highest class of vertebrated animals did not exist in remoter ages. There are regions at present, in the Indian and Pacific Oceans, co-extensive in area with the continents of Europe and North America, where we might dredge the bottom and draw up thousands of shells and corals, without obtaining one bone of a land quadruped. Suppose our mariners were to report, that, on sounding in the Indian Ocean near some coral reefs, and at some distance from the land, they drew up on hooks attached to their line portions of a leopard, elephant, or tapir, should we not be sceptical as to the accuracy of their statements? and if we had no doubt of their veracity, might we not suspect them to be unskilful naturalists? or, if the fact were unquestioned, should we not be disposed to believe that some vessel had been wrecked on the spot?

The casualties must always be rare by which land quadrupeds are swept by rivers far out into the open sea, and still rarer the contingency of such a floating body not being devoured by sharks or other predacious fish, such as were those of which we find the teeth preserved in some of the carboniferous strata. But if the carcass should escape, and should happen to sink where sediment was in the act of accumulating, and if the numerous causes of subsequent disintegration should not efface all traces of the body, included for countless ages in solid rock, is it not contrary to all calculation of chances that we should hit upon the exact spot—that mere point in the bed of an ancient ocean, where the precious relic was entombed? Can we expect for a moment, when we have only succeeded, amidst several thousand fragments of corals and shells, in finding a few bones of *aquatic* or *amphibious* animals, that we should meet with a single skeleton of an inhabitant of the land?

Clarence, in his dream, saw, "in the slimy bottom of the deep,"

> —— a thousand fearful wrecks;
> A thousand men, that fishes gnaw'd upon;
> Wedges of gold, great anchors, heaps of pearl.

Had he also beheld, amid "the dead bones that lay scattered by," the carcasses of lions, deer, and the other wild tenants of the forest and the plain, the fiction would have been deemed unworthy of the genius of Shakspeare. So daring a disregard of probability and violation of analogy would have been condemned as unpardonable, even where the poet was painting those incongruous images which present themselves to a disturbed imagination during the visions of the night.

Until lately it was supposed that the old red sandstone, or Devonian rocks, contained no vertebrate remains except those of fish, but in 1850 the footprints of a chelonian, and in 1851 the skeleton of a reptile, allied both to the batrachians and lizards, were found in a sandstone of that age near Elgin in Scotland.* Up to the year 1844 it was laid down as a received dogma in many works of high authorit in geology, that reptiles were not created until after the close of th carboniferous epoch. In the course of that year, however, Herma Von Meyer announced the discovery, in the coal measures of Rhen Bavaria, of a reptile, called by him Apateon, related to the salam ders; and in 1847 three species of another genus, called archegosa rus by Goldfuss, were obtained from the coal of Saarbrück, betwe Treves and Strasburg. The footprints of a large quadruped, pr bably batrachian, had also been observed by Dr. King in the ca boniferous rocks of Pennsylvania in 1844. The first example of t *bones* of a reptile in the Coal of North America was detected lately as September, 1852, by Mr. G. W. Dawson and myself Nova Scotia. These remains, referred by Messrs. Wyman and Ow to a perennibranchiate batrachian, were met with in the interior an erect fossil tree, apparently a sigillaria. They seem clearly to ha been introduced together with sediment into the tree, during i submergence and after it had decayed and was standing as a hollo cylinder of bark, this bark being now converted into coal.

---

* Quart. Journ. Geol. Soc. 1852.

When Agassiz, in his great work on fossil fish, described 1 species of ichthyolites from the Coal, he found them to consist of placoids, belonging to the families of shark and ray, and 58 ganoid One family of the latter he called "sauroid fish," including t megalichthys and holoptychius, often of great size, and all pred ceous. Although true fish, and not intermediate between that cla and reptiles, they seem to have been more highly organized than a living fish, reminding us of the skeletons of saurians by the clo suture of their cranial bones, their large conical teeth, striated lo gitudinally, and the articulation of the spinous processes with t vertebræ. Among living species they are most nearly allied to t lepidosteus, or bony pike of the North American rivers. Before t recent progress of discovery above alluded to had shown the falla of such ideas, it was imagined by some geologists that this ichthy type was the more highly developed, because it took the lead at t head of nature before the class of reptiles had been created. T confident assumption indulged in till the year 1844, that reptiles we first introduced into the earth in the Permian period, shows t danger of taking for granted that the date of the creation of a family of animals or plants in past time coincides with the age of t oldest stratified rock in which the geologist has detected its remai Nevertheless, after repeated disappointments, we find some naturali as much disposed as ever to rely on such negative evidence, and to f now as sure that reptiles were not introduced into the earth after the Silurian epoch, as they were in 1844, that they appeared the first time at an era subsequent to the carboniferous.

Scanty as is the information hitherto obtained in regard to the ar culata of the coal formation, we have at least ascertained that so insects winged their way through the ancient forests. In the ir stone of Coalbrook Dale, two species of coleoptera of the Linna genus curculio have been met with: and a neuropterous insect sembling a corydalis, together with another of the same order rela to the phasmidæ. As an example of the insectivorous arachnidæ, I may mention the scorpion of the Bohemian coal, figured by Count Sternberg, in which even the eyes, skin, and minute hairs were preserved.* We need not despair, therefore, of obtaining eventually fossil representatives of all the principal orders of hexapods and arachnidæ in carboniferous strata.

Next in chronological order above the Coal comes the allied Magnesian Limestone, or Permian group, and the secondary formations from the Trias to the Chalk inclusive. These rocks comprise the monuments of a long series of ages in which reptiles of every variety of size, form, and structure peopled the earth; so that the whole period, and especially that of the Lias and Oolite, has been sometimes called "the age of reptiles." As there are now mammalia entirely confined to the land; others which, like the bat and vampire, fly in the air; others, again, of amphibious habits, frequenting rivers, like the hippopotamus, otter, and beaver; others exclusively aquatic and marine, like the seal, whale, and narwal; so in the early ages under consideration, there were terrestrial, winged, and aquatic reptiles. There were iguanodons walking on the land, pterodactyls winging their way through the air, monitors and crocodiles in the rivers, and ichthyosaurs and plesiosaurs in the ocean. It appears also that some of these ancient saurians approximated more nearly in their organization to the type of living mammalia than do any of the reptiles now existing.†

In the vast range of strata above alluded to, comprising the Permian, the Upper New Red Sandstone and Muschelkalk, the Lias, Oolite, Wealden, Green-sand, and Chalk, scarcely any well-authenticated instances of the occurrence of fossil birds in Europe are on record, and only two or three of fossil mammalia.

In regard to the absence of birds, they are usually wanting, for reasons afterwards to be explained (see chap. 47.), in deposits of all ages, even in the tertiary periods, where we know that birds as well as land quadrupeds abounded. Some at least of the fossil remains formerly referred to this class in the Wealden (a great freshwater deposit below the chalk), have been recently shown by Mr. Owen to belong to pterodactyls.‡ But in North America still more ancient indications of the existence of the feathered tribe have been detected, the fossil foot-marks of a great variety of species, of various sizes, some larger than the ostrich, others smaller than the plover, having been observed. These bipeds have left marks of their footsteps on strata of an age decidedly intermediate between the Lias and the Coal.§

The examples of mammalia, above alluded to, are confined to the Trias and the Oolite. In the former, the evidence is as yet limited to two small molar teeth, described by Professor Plieninger in 1847, under the generic name of Microlestes. They were found near Stutt-

---

* Buckland's Bridgewater Treatise, p. 409.

† Owen's Report on "British Fossil Reptiles, to Brit. Soc." 1841, p. 200.

‡ Quart. Journ. Geol. Soc. No. 6. p. 96.

§ See Hitchcock's Report on Geol. of Massachusetts, and Lyell's Travels in North America, chap. 12.

gart, and possess the double fangs so characteristic of mamm
The other fossil remains of the same class were derived from o
the inferior members of the oolitic series in Oxfordshire, and afford
full and satisfactory evidence, consisting of the lower jaws of t
species of small quadrupeds about the size of a mole. Cuvier, w
he saw one of them (during a visit to Oxford in 1818), referred i

Fig. 8.



Thylacotherium Prevostii (*Valenciennes*). Amphitherium (*Owen*). Lower jaw, from the slate of Stonesfield, near Oxford.†

the marsupial order, stating, however, that it differed from all kno
carnivora in having ten molar teeth in a row. Professor Ow
afterwards pointed out that the jaw belonged to an extinct ge
having considerable affinity to a newly discovered Australian m
mifer, the *Myrmecobius* of Waterhouse, which has nine molar teet
the lower jaw. (Fig. 9.) A more perfect specimen enabled Mr. O
in 1846 to prove that the inf
tion of the angular process of
lower jaw was not suffici
marked to entitle the osteolo
to infer that this quadruped
marsupial, as the process is
bent inwards in a greater de
than in the mole or hedge
Hence the genus amphitherium, of which there are two species f
Stonesfield, must be referred to the ordinary or placental typ
insectivorous mammals, although it approximates in some point

Fig. 9.



Myrmecobius fasciatus (*Waterhouse*). Recent from Swan River. Lower jaw of the natural size.‡

---

* See Manual of Geol. by the Author, index *Microlestes.*

† This figure (No. 8.) is from a drawing by Professor C. Prevost, published Ann. des Sci. Nat. Avril, 1825. The fossil is a lower jaw, adhering by its inner side to the slab of oolite, in which it is sunk. The form of the condyle, or posterior process of the jaw, is convex, agreeing with the mammiferous type, and is distinctly seen, an impression of it being left on the stone, although in this specimen the bone is wanting. The anterior part of the jaw has been partially broken away, so that the double fangs of the molar teeth are seen fixed in their sockets, the form of the fangs being characteristic of the mammalia. Ten molars are preserved, and the place of an eleventh is believed to be app
The enamel of some of the teeth is
preserved.

‡ A coloured figure of this small
elegant quadruped is given in the T
Zool. Soc. vol. ii. pl. 28. It is i
tivorous, and was taken in a hollow
in a country abounding in ant
ninety miles to the south-east o
mouth of Swan River in Australia.
is the first living marsupial species k
to have nine molar teeth in the l
jaw, and some of the teeth are w
separated from others, one of the
liarities in the thylacotherium of St
field, which at first induced M. Blai
to refer that creature to the cla
reptiles.

structure to the myrmecobius and allied marsupials of Australia. The other contemporary genus, called phascolotherium, agrees much more nearly in osteological character and precisely in the number of the teeth with the opossums; and is believed to have been truly marsupial. (Fig. 10.)

Fig. 10.



Natural size.

Phascolotherium Bucklandi, *Owen*. (*Syn*. Didelphis Bucklandi, *Brod.*)
Lower jaw, from Stonesfield.[†]

1. The jaw magnified twice in length. 2. The second molar tooth magnified six times.

The occurrence of these most ancient memorials of the mammiferous type, in so low a member of the oolitic series, while no other representatives of the same class (if we except the microlestes) have yet been found in any other of the inferior or superior secondary strata, is a striking fact, and should serve as a warning to us against hasty generalizations, founded solely on negative evidence. So important an exception to a general rule may be perfectly consistent with the conclusion, that a small number only of mammalia inhabited European latitudes when our secondary rocks were formed; but it seems fatal to the theory of progressive development, or to the notion that the order of precedence in the creation of animals, considered chronologically, has precisely coincided with the order in which they would be ranked according to perfection or complexity of structure.

It was for many years suggested that the marsupial order to which the fossil animals of Stonesfield were supposed exclusively to belong

---

[*] This figure (No. 10.) was taken from the original, formerly in Mr. Broderip's collection, and now in the British Museum. It consists of the right half of a lower jaw, of which the inner side is seen. The jaw contains seven molar teeth, one canine, and three incisors; but the end of the jaw is fractured, and traces of the alveolus of a fourth incisor are seen. With this addition, the number of teeth would agree exactly with those of a lower jaw of a didelphis. The fossil is well preserved in a slab of oolitic structure containing shells of trigoniæ and other marine remains. Two or three other similar jaws, besides those above represented, have been procured from the quarries of Stonesfield.—See Broderip, Zool. Journ. vol. iii. p. 408. Owen, Proceedings Geol. Soc., November, 1838.

constitutes the lowest grade in the class Mammalia, and that this order, of which the brain is of more simple form, evinces an inferior degree of intelligence. If, therefore, in the oolitic period the marsupial tribes were the only warm-blooded quadrupeds which had as yet appeared upon our planet, the fact, it was said, confirmed the theory which teaches that the creation of the more simple forms in each division of the animal kingdom preceded that of the more complex. But on how slender a support, even if the facts had continued to hold true, did such important conclusions hang! The Australian continent, so far as it has been hitherto explored, contains no indigenous quadrupeds save those of the marsupial order, with the exception of a few small rodents, while some neighbouring islands to the north, and even southern Africa, in the same latitude as Australia, abound in mammalia of every tribe except the marsupial. We are entirely unable to explain on what physiological or other laws this singular diversity in the habitations of living mammalia depends; but nothing is more clear than that the causes which stamp so peculiar a character on two different provinces of wide extent are wholly independent of time, or of the age or maturity of the planet.

The strata of the Wealden, although of a later date than the oolite of Stonesfield, and although filled with the remains of large reptiles, both terrestrial and aquatic, have not yielded as yet a single marsupial bone. Were we to assume on such scanty data that no warm-blooded quadrupeds were then to be found throughout the northern hemisphere, there would still remain a curious subject of speculation, whether the entire suppression of one important class of vertebrata, such as the mammiferous, and the great development of another, such as the reptilian, implies a departure from fixed and uniform rules governing the fluctuations of the animal world; such rules, for example, as appear from one century to another to determine the growth of certain tribes of plants and animals in arctic, and of other tribes in tropical regions.

In Australia, New Zealand, and many other parts of the southern hemisphere, where the indigenous land quadrupeds are comparatively few, and of small dimensions, the reptiles do not predominate in number or size. The deposits formed at the mouth of an Australian river, within the tropics, might contain the bones of only a few small marsupial animals, which, like those of Stonesfield, might hereafter be discovered with difficulty by geologists; but there would, at the same time, be no megalosauri and other fossil remains, showing that large saurians were plentiful on the land and in the waters at a time when mammalia were scarce. This example, therefore, would afford a very imperfect parallel to the state of the animal kingdom, supposed to have prevailed during the secondary periods, when a high temperature pervaded European latitudes.

It may nevertheless be advantageous to point to some existing anomalies in the geographical development of distinct classes of vertebrata which may be comparable to former conditions of the animal creation brought to light by geology. Thus in the arctic regions, a present, reptiles are small, and sometimes wholly wanting, where birds, large land quadrupeds, and cetacea abound. We meet with bears, wolves, foxes, musk oxen, and deer, walrusses, seals, whales, and narwals, in regions of ice and snow, where the smallest snakes, efts, and frogs are rarely, if ever, seen.

A still more anomalous state of things presents itself in the southern hemisphere. Even in the temperate zone, between the latitudes 52° and 56° S., as, for example, in Tierra del Fuego, as well as in the woody region immediately north of the Straits of Magellan, and in the Falkland Islands, no reptiles of any kind are met with, not even a snake, lizard, or frog; but in these same countries we find the guanaco (a kind of llama), a deer, the puma, a large species of fox, many small rodentia, besides the seal and otter, together with the porpoise, whale, and other cetacea.

On what grand laws in the animal physiology these remarkable phenomena depend, cannot in the present state of science be conjectured; nor could we predict whether any opposite condition of the atmosphere, in respect to heat, moisture, and other circumstances, would bring about a state of animal life which might be called the converse of that above described, namely, a state in which reptiles of every size and order might abound, and mammalia disappear.

The nearest approximation to such a fauna is found in the Galapagos Archipelago. These islands, situated under the equator, and nearly 600 miles west of the coast of Peru, have been called "the land of reptiles," so great is the number of snakes, large tortoises, and lizards, which they support. Among the lizards, the first living species proper to the ocean has been discovered. Yet, although some of these islands are from 3000 to 4000 feet high, and one of them 75 miles long, they contain, with the exception of one small mouse, no indigenous mammifer. Even here, however, it is true that in the neighbouring sea there are seals, and several kinds of cetacea.*

It may be unreasonable to look for a nearer analogy between the fauna now existing in any part of the globe, and that which we can show to have prevailed when our secondary strata were deposited, because we must always recollect that a climate like that now experienced at the equator, co-existing with the unequal days and nights of European latitudes, was a state of things to which there is now no counterpart on the globe. Consequently, the type of animal and vegetable existence required for such a climate might be expected to deviate almost as widely from that now established, as do the flora and fauna of our tropical differ from those of our arctic regions.

In the Tertiary strata.—The tertiary formations were deposited when the physical geography of the northern hemisphere had been entirely altered. Large inland lakes had become numerous, as in central France and other countries. There were gulfs of the sea, into which considerable rivers emptied themselves, and where strata like those of the Paris basin were accumulated. There were also formations in progress, in shallow seas not far from shore, such as are indicated by portions of the *Faluns* of the Loire, and the English *Crag*.

---

* Darwin's Journal, chap. 19. Lyell's Manual of Geol. ch. 21. p. 279.

The proximity, therefore, of large tracts of dry land to the seas and lakes then existing, may, in a great measure, explain why the remains of land animals, so rare in the older strata, are not uncommon in these more modern deposits. Yet even these have sometimes proved entirely destitute of mammiferous relics, for years after they had become celebrated for the abundance of their fossil testacea, fish, and reptiles. Thus the calcaire grossier, a marine limestone of the district round Paris, had afforded to collectors more than 1100 species of shells, besides many zoophytes, echinodermata, and the teeth of fish, before the bones of one or two land quadrupeds were met with in the same rock. The strata called London and Plastic clay in England have been studied for more than half a century, and about 400 species of shells, 50 or more of fish, besides several kinds of chelonian and saurian reptiles, were known before a single mammifer was detected. At length, in the year 1839, there were found in this formation the remains of a monkey, an opossum, a bat*, and a species of the extinct genus Hyracotherium, allied to the Peccary or hog tribe.

If we examine the strata above the London clay in England, we first meet with mammiferous remains in the Isle of Wight, in beds also belonging to the Eocene epoch, such as the remains of the Palæotherium, Anoplotherium, and other extinct quadrupeds, agreeing very closely with those first found by Cuvier, near Paris, in strata of the same age, and of similar freshwater origin.

In France we meet with another fauna, both conchological and mammalian in the Miocene "faluns" of the Loire; above which in the ascending series in Great Britain we arrive at the coralline crag of Suffolk, a marine formation which has yielded three or four hundred species of shells, very different from the Eocene testacea, and of which a large proportion, although a minority of the whole number, are recent, besides many corals, echini, foraminifera, and fish, but as yet no relic decidedly mammalian except the ear-bone of a whale.

In the shelly sand, provincially termed "Red Crag," in Suffolk, which immediately succeeds the coralline, constituting a newer member of the same tertiary group, about 250 species of shells have been recognised, of which a still larger proportion are recent. They are associated with numerous teeth of fish; but no signs of a warm-blooded quadruped had been detected until 1839, when the teeth of a leopard, a bear, a hog, and a species of ruminant, were found at Newbourn, in Suffolk, and since that time, several other genera of mammalia have been met with in the same formation, or in the Red Crag.†

---

* Taylor's Annals of Nat. Hist. Nov. 1839.

† See notice by the Author, and Professor Owen, Taylor's Annals of Nat. Hist. Nov. 1839.

Of a still newer date is the Norwich Crag, a fluviomarine deposit of the Pleiocene epoch, containing a mixture of marine, fluviatile, and land shells, of which 90 per cent. or more are recent. These beds, since the time of their first investigation, have yielded a supply of mammalian bones of the genera mastodon, elephant, rhinoceros, pig, horse, deer, ox, and others, the bodies of which may have been washed down into the sea by rivers draining land, of which the contiguity is indicated by the occasional presence of terrestrial and freshwater shells.

Our acquaintance with the newer Pleiocene mammalia in Europe, South America, and Australia, is derived chiefly from cavern deposits, a fact which we ought never to forget if we desire to appreciate the superior facilities we enjoy for studying the more modern as compared to the more ancient terrestrial faunas. We know nothing of the fossil bones which must have been enclosed in the stalagmite of caverns in the older Pleiocene, or in the Miocene or Eocene epochs, much less can we derive any information respecting the inhabitants of the land from a similar source, when we carry back our inquiries to the Wealden or carboniferous epochs. We are as well assured that land and rivers then existed, as that they exist now; but it is evident that even a slight geographical revolution, accompanied by the submergence and denudation of land, would reduce to an extreme improbability the chance of our hitting on those minute points of space where caves may once have occurred in limestone rocks.

Fossil quadrumana.—Until within a few years (1836, 1837), not a single bone of any quadrumanous animal, such as the orang, ape, baboon, and monkey, had been discovered in a fossil state, although so much progress had been made in bringing to light the extinct mammalia of successive tertiary eras, both carnivorous and herbivorous. The total absence of these anthropomorphous tribes among the records of a former world, had led some to believe that the type of organization most nearly resembling the human, came so late in the order of creation, as to be scarcely, if it all, anterior to that of man. That such generalisations were premature, I endeavoured to point out in the first edition of this work*, in which I stated that the bones of quadrupeds hitherto met with in tertiary deposits were chiefly those which frequent marshes, rivers, or the borders of lakes, as the elephant, rhinoceros, hippopotamus, tapir, hog, deer, and ox, while species which live in trees are extremely rare in a fossil state. I also hinted, that we had as yet no data for determining how great a number of the one kind we ought to find, before we have a right to expect a single individual of the other. Lastly, I observed that the climate of the more modern (or Post-Eocene) tertiary periods in England was not tropical, and that in regard to the London clay, of which the crocodiles, turtles, and fossil fruits implied a climate hot enough for the quadrumana, we had as yet made too little progress in ascertaining what were the Eocene pachydermata of

---

* See Principles of Geology, 1st ed. 1830, vol. i. p. 152.

England, to entitle us to expect to have discovered any quadrumana of the same date.

Since those remarks were first written, in 1829, a great number of extinct species have been added to our collections of tertiary mammalia from Great Britain and other parts of the world. At length, between the years 1836 and 1839, a few remains of quadrumana were found in France and England, India and Brazil. Those of India, belonging to more than one extinct species of monkey, were first discovered near the Sutlej, in lat. 30° N., in tertiary strata, of which the age is not yet determined; the Brazilian fossil, brought from the basin of the Rio das Velhas, about lat. 18° S., is referable to a form now peculiar to America, allied to the genus Callithrix, the species being extinct. The skull and other bones met with in the South of France belong to a gibbon, or one of the tailless apes, which stand next in the scale of organization to the orang. It occurred at Sansan, about forty miles west of Toulouse, in lat. 43° 40′ N., in freshwater strata, probably of the Miocene or middle tertiary period. Lastly, the English quadrumane first met with, occurred in a more ancient stratum than the rest, and at a point more remote from the equator. It belongs to the genus Macacus, is an extinct species, and was found in Suffolk, in lat. 52°[*], in the London clay, the fossils of which, such as crocodiles, turtles, shells of the genus Nautilus, and many curious fruits, had already led geologists to the conclusion that the climate of that era (the Eocene) was warm and nearly tropical.

Some years later (in 1846) the jaw of another British species of fossil monkey, Macacus pliocenus, was announced by Mr. Owen as having been met with in the newer Pleiocene strata, on the banks of the Thames, at Grays, in Essex, accompanying the remains of hippopotamus, elephant, and other quadrupeds, and associated with freshwater and land shells, most of which are now inhabitants of the British Isles.[†]

---

[*] The first quadrumanous fossils discovered in India were observed in 1836 in the Sewalik Hills, a lower range of the Himalayan Mountains, by Lieutenants Baker and Durond, by whom their osteological characters were determined (Journ. of Asiat. Soc. of Bengal, vol. v. p. 739.), and in the year following, other fossils of the same class were brought to light and described by Capt. Cautley and Dr. Falconer. These were imbedded, like the former, in tertiary strata of conglomerate, sand, marl, and clay, in the Sub-Himalayan Mountains. (Ibid. vol. v. p. 379. Nov. 1836; and vol. vi. p. 354. May, 1837.)

The Brazilian quadrumane was found, with a great many other extinct species of animals, by a Danish naturalist, Dr. Lund, between the rivers Francisco and Velhas, in 1837.

The gibbon of the South of France was found by M. Lartet in the beginning of 1837, and determined by M. de Blainville. It occurred near Auch, in the department of Gers, about forty miles west of Toulouse, in freshwater marl, limestone, and sand. They were accompanied by the remains of the mastodon, dinotherium, palæotherium, rhinoceros, gigantic sloth, and other extinct quadrupeds. (Bulletin de la Soc. Geol. de France, tom. viii. p. 92.)

The British quadrumane was discovered in 1839, by Messrs. William Colchester and Searles Wood, at Kyson, near Woodbridge, in Suffolk, and was referred by Professor Owen to the genus Macacus. (Mag. of Nat. Hist. Sept. 1839. Taylor, Annals of Nat. Hist., No. xxiii. Nov. 1839.)

[†] Owen's Introduction to British Fossil Mammals, p. 46.

When we consider the small area of the earth's surface hitherto explored geologically, and the new discoveries brought to light daily, even in the environs of great European capitals, we must feel that it would be rash to assume that the Lower Eocene deposits mark the era of the first creation of quadrumana. It would, however, be still more unphilosophical to infer, as some writers have done, from a single extinct species of this family obtained in a latitude far from the tropics, that the Eocene quadrumana did not attain as high a grade of organization as they do in our own times. What would the naturalist know of the apes and orangs now contemporary with man, if our investigations were restricted to such northern latitudes as those where alone the geologist has hitherto found all the fossil quadrumana of Europe?

Cetacea.—The absence of Cetacea from rocks older than the Eocene has been frequently adduced as lending countenance to the theory of the very late appearance of the highest class of Vertebrata on the earth. Professor Sedgwick possesses in the Cambridge Museum a mass of anchylosed cervical vertebræ of a whale, which he found in drift clay near Ely, and which he has no doubt was washed out of the Kimmeridge clay, an upper member of the Oolite. According to Professor Owen, it exhibits well-marked specific characters, distinguishing it from all other known recent or fossil cetacea. Dr. Leidy, of Philadelphia, has lately described (1851) two species of cetacea of a new genus, which he has called Priscodelphinus from the green sand of New Jersey, which corresponds in age with the English Chalk or the cretaceous strata above the gault. The specimens consist of dorsal and cervical vertebræ.* Even in the Eocene strata of Europe, the discovery of cetaceans has never kept pace with that of land quadrupeds. The only instance cited in Great Britain is a species of Monodon, from the London clay, of doubtful authenticity as to its geological position. On the other hand, the gigantic Zeuglodon of North America occurs abundantly in the Middle Eocene strata of Georgia and Alabama, from which as yet no bones of land quadrupeds have been obtained.

In the present imperfect state then of our information, we can scarcely say more than that the cetacea seem to have been scarce in the secondary and primary periods. It is quite conceivable that when aquatic saurians, some of them carnivorous, like the Ichthyosaurus, were swarming in the sea, and when there were large herbivorous reptiles, like the Iguanodon, on the land, the class of reptiles may, to a certain extent, have superseded the cetacea, and discharged their functions in the animal economy.

That mammalia had been created long before the epoch of the Kimmeridge clay, is shown by the Microlestes of the Trias before alluded to, and by the Stonesfield quadrupeds from the Inferior Oolite. And we are bound to remember, whenever we infer the poverty of the flora or fauna of any given period of the past, from the small number of fossils occurring in ancient rocks, that it has been evidently no part of th plan of Nature to hand down to us a complete or systematic reco of the former history of the animate world. We may have failed t discover a single shell, marine or freshwater, or a single coral or bo in certain sandstones, such as that of the valley of the Connectic where the footprints of bipeds and quadrupeds abound; but su failure may have arisen, not because the population of the land o sea was scanty at that era, but because in general the preservati of any relics of the animals or plants of former times is the exceptio to a general rule. Time so enormous as that contemplated by th geologist may multiply exceptional cases till they seem to constitu the rule, and so impose on the imagination as to lead us to infer th non-existence of creatures of which no monuments happen to remai Professor Forbes has remarked, that few geologists are aware ho large a proportion of all known species of fossils are founded on singl specimens, while a still greater number are founded on a few individuals discovered in one spot. This holds true not only in regard t animals and plants inhabiting the land, the lake, and the river, bu even to a surprising number of the marine mollusca, articulata, an radiata. Our knowledge, therefore, of the living creation of an given period of the past may be said to depend in a great degree o what we commonly call chance, and the casual discovery of som new localities rich in peculiar fossils may modify or entirely overthrow all our previous generalizations.

---

* Proceedings of Acad. Nat. Sci. Philad. Dec. 9. 1851.

Upon the whole then we derive this result from a general review of the fossils of the successive tertiary strata, namely, that sinc the Eocene period, there have been several great changes in th land quadrupeds inhabiting Europe, probably not less than fiv complete revolutions, during which there has been no step what ever made in advance, no elevation in the scale of being; so tha had man been created at the commencement of the Eocene era, h would not have constituted a greater innovation on the state of th animate creation previously established than now, when we believ him to have begun to exist at the close of the Pleiocene. Th views, therefore, which I proposed in the first edition of this wor January, 1830, in opposition to the theory of progressive developmen do not seem to me to require material modification, notwithstandin the large additions since made to our knowledge of fossil remains.

These views may be thus briefly stated. From the earlie period at which plants and animals can be proved to have e isted, there has been a continual change going on in the positio of land and sea, accompanied by great fluctuations of climate. T these ever-varying geographical and climatal conditions the state the animate world has been unceasingly adapted. No satisfacto proof has yet been discovered of the gradual passage of the ear from a chaotic to a more habitable state, nor of any law of progressi development governing the extinction and renovation of specie and causing the fauna and flora to pass from an embryonic to a mo perfect condition, from a simple to a more complex organization.

The principle of adaptation to which I have alluded, appears to have een analogous to that which now peoples the arctic, temperate, and troical regions contemporaneously with distinct assemblages of species nd genera, or which, independently of mere temperature, gives rise a predominance of the marsupial or didelphous tribe of quadrupeds n Australia, of the placental or monodelphous tribe in Asia and urope, or which causes a profusion of reptiles without mammalia in he Galapagos Archipelago, and of mammalia without reptiles in reenland.

Recent origin of man.—If, then, the popular theory of the sucessive development of the animal and vegetable world, from the implest to the most perfect forms, rests on a very insecure foundaion; it may be asked, whether the recent origin of man lends any upport to the same doctrine, or how far the influence of man may e considered as such a deviation from the analogy of the order of hings previously established, as to weaken our confidence in the niformity of the course of nature.

Antecedently to investigation, we might reasonably have anticiated that the vestiges of man would have been traced back at least s far as those modern strata in which all the testacea and a certain umber of the mammalia are of existing species, for of all the mammalia the human species is the most cosmopolite, and perhaps more apable than any other of surviving considerable vicissitudes in limate, and in the physical geography of the globe.

No inhabitant of the land exposes himself to so many dangers on he waters as man, whether in a savage or a civilized state*; and here is no animal, therefore, whose skeleton is so liable to become mbedded in lacustrine or submarine deposits: nor can it be said hat his remains are more perishable than those of other animals; or in ancient fields of battle, as Cuvier has observed, the bones of nen have suffered as little decomposition as those of horses which vere buried in the same grave.† But even if the more solid parts f our species had disappeared, the impression of their form would ave remained engraven on the rocks, as have the traces of the nderest leaves of plants, and the soft integuments of many animals. Vorks of art, moreover, composed of the most indestructible materials, ould have outlasted almost all the organic contents of sedimentary cks. Edifices, and even entire cities, have, within the times of istory, been buried under volcanic ejections, submerged beneath the a, or engulphed by earthquakes; and had these catastrophes been peated throughout an indefinite lapse of ages, the high antiquity of an would have been inscribed in far more legible characters on the amework of the globe than are the forms of the ancient vegetation hich once covered the islands of the northern ocean, or of those gantic reptiles which at still later periods peopled the seas and vers of the northern hemisphere.‡

---

* See ch. 48.

† Ibid.

‡ Ibid.

Dr. Prichard has argued that the human race have not alw existed on the surface of the earth, because "the strata of which continents are composed were once a part of the ocean's bed" "mankind had a beginning, since we can look back to the pe when the surface on which they lived began to exist." * This pr however, is insufficient, for many thousands of human beings dwell in various quarters of the globe where marine species li within the times of history, and, on the other hand, the sea prevails permanently over large districts once inhabited by thou of human beings. Nor can this interchange of sea and land cease while the present causes are in existence. Terrestrial spec therefore, might be older than the continents which they inhabit, aquatic species of higher antiquity than the lakes and seas which th now people.

But so far as our interpretation of physical movements has gone, we have every reason to infer that the human race is extrem modern, even when compared to the larger number of species now contemporaries on the earth, and we may, therefore, ask whether creation can be considered as one step in a supposed progres system, by which the organic world has advanced slowly from more simple to a more complex and perfect state? If we conce for a moment, the truth of the proposition, that the sponge, cephalopod, the fish, the reptile, the bird, and the mammifer ha followed each other in regular chronological order, the creati of each class being separated from the other by vast intervals time, should we be able to recognize, in man's entrance upon earth, the last term of one and the same series of progressive velopments?

In reply to this question it should first be observed, that superiority of man depends not on those faculties and attribu which he shares in common with the inferior animals, but on reason, by which he is distinguished from them. When it is that the human race is of far higher dignity than were any existing beings on the earth, it is the intellectual and moral attrib of our race, rather than the physical, which are considered; and i by no means clear that the organization of man is such as wo confer a decided pre-eminence upon him, if, in place of his reason powers, he was merely provided with such instincts as are posses by the lower animals.

If this be admitted, it would not follow, even if there were s cient geological evidence in favour of the theory of progressive de lopment, that the creation of man was the last link in the same ch For the sudden passage from an irrational to a rational animal, phenomenon of a distinct kind from the passage from the more sin to the more perfect forms of animal organization and instinct. pretend that such a step, or rather leap, can be part of a regular se

---

* Phys. Hist. of Mankind, vol. ii. p. 594.

of changes in the animal world, is to strain analogy beyond all reasonable bounds.

Introduction of man, to what extent a change in the system. — But setting aside the question of progressive development, another and a far more difficult one may arise out of the admission that man is comparatively of modern origin. Is not the interference of the human species, it may be asked, such a deviation from the antecedent course of physical events, that the knowledge of such a fact tends to destroy all our confidence in the uniformity of the order of nature, both in regard to time past and future? If such an innovation could take place after the earth had been exclusively inhabited for thousands of ages by inferior animals, why should not other changes as extraordinary and unprecedented happen from time to time? If one new cause was permitted to supervene, differing in kind and energy from any before in operation, why may not others have come into action at different epochs? Or what security have we that they may not arise hereafter? And if such be the case, how can the experience of one period, even though we are acquainted with all the possible effects of the then existing causes, be a standard to which we can refer all natural phenomena of other periods?

Now these objections would be unanswerable, if adduced against one who was contending for the absolute uniformity throughout all time of the succession of sublunary events—if, for example, he was disposed to indulge in the philosophical reveries of some Egyptian and Greek sects, who represented all the changes both of the moral and material world as repeated at distant intervals, so as to follow each other in their former connection of place and time. For they compared the course of events on our globe to astronomical cycles; and not only did they consider all sublunary affairs to be under the influence of the celestial bodies, but they taught that on the earth, as well as in the heavens, the same identical phenomena recurred again and again in a perpetual vicissitude. The same individual men were doomed to be re-born, and to perform the same actions as before; the same arts were to be invented, and the same cities built and destroyed. The Argonautic expedition was destined to sail again with the same heroes, and Achilles with his Myrmidons to renew the combat before the walls of Troy.

> Alter erit tum Tiphys, et altera quæ vehat Argo
> Dilectos heroas; erunt etiam altera bella,
> Atque iterum ad Trojam magnus mittetur Achilles.[*]

The geologist, however, may condemn these tenets as absurd, without running into the opposite extreme, and denying that the order of nature has, from the earliest periods, been uniform in the same sense in which we believe it to be uniform at present, and

---

[*] Virgil, Eclog. iv. For an account f these doctrines, see Dugald Stewart's lements of the Philosophy of the Human Mind, vol. ii. chap. ii. sect. 4., and Prichard's Egypt. Mythol. p. 177.

expect it to remain so in future. We have no reason to suppo
that when man first became master of a small part of the globe,
greater change took place in its physical condition than is
experienced when districts, never before inhabited, become succ
sively occupied by new settlers. When a powerful European colo
lands on the shores of Australia, and introduces at once those a
which it has required many centuries to mature; when it imports
multitude of plants and large animals from the opposite extremity
the earth, and begins rapidly to extirpate many of the indigen
species, a mightier revolution is effected in a brief period than
first entrance of a savage horde, or their continued occupation of
country for many centuries, can possibly be imagined to have p
duced. If there be no impropriety in assuming that the system
uniform when disturbances so unprecedented occur in certain lo
ities, we can with much greater confidence apply the same langu
to those primeval ages when the aggregate number and power of
human race, or the rate of their advancement in civilization, must
supposed to have been far inferior. In reasoning on the state of
globe immediately before our species was called into existence,
must be guided by the same rules of induction as when we specul
on the state of America in the interval that elapsed between
introduction of man into Asia, the supposed cradle of our race,
the arrival of the first adventurers on the shores of the New Wo
In that interval, we imagine the state of things to have gone
according to the order now observed in regions unoccupied by
Even now, the waters of lakes, seas, and the great ocean, which te
with life, may be said to have no immediate relation to the hu
race — to be portions of the terrestrial system of which man
never taken, nor ever can take possession; so that the greater part
the inhabited surface of the planet may still remain as insensible
our presence as before any isle or continent was appointed to be
residence.

If the barren soil around Sydney had at once become fertile u
the landing of our first settlers; if, like the happy isles whereof
poets have given us such glowing descriptions, those sandy tr
had begun to yield spontaneously an annual supply of grain,
might then, indeed, have fancied alterations still more remarka
in the economy of nature to have attended the first coming of
species into the planet. Or if, when a volcanic island like Is
was, for the first time, brought under cultivation by the enterp
and industry of a Greek colony, the internal fire had become
mant, and the earthquake had remitted its destructive violence, th
would then have been some ground for speculating on the debilita
of the subterranean forces, when the earth was first placed un
the dominion of man. But after a long interval of rest, the volc
bursts forth again with renewed energy, annihilates one half of th
habitants, and compels the remainder to emigrate. The course of na
remains evidently unchanged; and, in like manner, we may sup
the general condition of the globe, immediately before and after

period when our species first began to exist, to have been the same, with the exception only of man's presence.

The modifications in the system of which man is the instrument do not, perhaps, constitute so great a deviation from previous analogy as we usually imagine; we often, for example, form an exaggerated estimate of the extent of our power in extirpating some of the inferior animals, and causing others to multiply; a power which is circumscribed within certain limits, and which, in all likelihood, is by no means exclusively exerted by our species.* The growth of human population cannot take place without diminishing the numbers, or causing the entire destruction, of many animals. The larger beasts of prey in particular give way before us; but other quadrupeds of smaller size, and innumerable birds, insects, and plants, which are inimical to our interests, increase in spite of us, some attacking our food, others our raiment and persons, and others interfering with our agricultural and horticultural labours. We behold the rich harvest which we have raised by the sweat of our brow, devoured by myriads of insects, and are often as incapable of arresting their depredations, as of staying the shock of an earthquake, or the course of a stream of lava.

A great philosopher has observed, that we can command nature only by obeying her laws; and this principle is true even in regard to the astonishing changes which are superinduced in the qualities of certain animals and plants by domestication and garden culture. I shall point out in the third book that we can only effect such surprising alterations by assisting the development of certain instincts, or by availing ourselves of that mysterious law of their organization, by which individual peculiarities are transmissible from one generation to another.†

It is probable from these and many other considerations, that as we enlarge our knowledge of the system, we shall become more and more convinced, that the alterations caused by the interference of man deviate far less from the analogy of those effected by other animals than is usually supposed.‡ We are often misled, when we institute such comparisons, by our knowledge of the wide distinction between the instincts of animals and the reasoning power of man; and we are apt hastily to infer, that the effects of a rational and irrational species, considered merely *as physical agents*, will differ almost as much as the faculties by which their actions are directed.

It is not, however, intended that a real departure from the antecedent course of physical events cannot be traced in the introduction of man. If that latitude of action which enables the brutes to accommodate themselves in some measure to accidental circumstances could be imagined to have been at any former period so great, that the operations of instinct were as much diversified as are those of human reason, it might, perhaps, be contended, that the agency of man did not constitute an anomalous deviation from the previous established order of things. It might then have been said, that the earth's becoming at a particular period the residence of human beings, was an era in the moral, not in the physical world—that our study and contemplation of the earth, and the laws which govern its animate productions, ought no more to be considered in the light of a disturbance or deviation from the system, than the discovery of the satellites of Jupiter should be regarded as a physical event affect ing those heavenly bodies. Their influence in advancing the progress of science among men, and in aiding navigation and commerce, was accompanied by no reciprocal action of the human mind upon the economy of nature in those distant planets; and so the earth might be conceived to have become, at a certain period, a place of moral discipline and intellectual improvement to man, without the slightest derangement of a previously existing order of change in its animate and inanimate productions.

---

* See ch. 41.

† See ch. 35.

‡ See ch. 37, 38, 39. 41.

The distinctness, however, of the human from all other species, considered merely as an efficient cause in the physical world, is real; for we stand in a relation to contemporary species of animals and plants widely different from that which other irrational animals can ever be supposed to have held to each other. We modify their instincts, relative numbers, and geographical distribution, in a manner superior in degree, and in some respects very different in kind from that in which any other species can affect the rest. Besides, the progressive movement of each successive generation of men causes the human species to differ more from itself in power at two distant periods, than any one species of the higher order of animals differs from another. The establishment, therefore, by geological evidence of the first intervention of such a peculiar and unprecedented agency long after other parts of the animate and inanimate world existed affords ground for concluding that the experience during thousand of ages of all the events which may happen on this globe, would no enable a philosopher to speculate with confidence concerning futur contingencies.

If, then, an intelligent being, after observing the order of event for an indefinite series of ages, had witnessed at last so wonderful a innovation as this, to what extent would his belief in the regularit of the system be weakened?—would he cease to assume that ther was permanency in the laws of nature? — would he no longer b guided in his speculations by the strictest rules of induction? T these questions it may be answered, that, had he previously pr sumed to dogmatise respecting the absolute uniformity of the ord of nature, he would undoubtedly be checked by witnessing this ne and unexpected event, and would form a more just estimate of th limited range of his own knowledge, and the unbounded extent the scheme of the universe. But he would soon perceive that n one of the fixed and constant laws of the animate or inanimate wor was subverted by human agency, and that the modifications no introduced for the first time were the accompaniments of new and extraordinary circumstances, and those not of a *physical* but a *moral* nature. The deviation permitted would also appear to be as slight as was consistent with the accomplishment of the new *moral* ends proposed, and to be in a great degree temporary in its nature, so that, whenever the power of the new agent was withheld, even for a brief period, a relapse would take place to the ancient state of things; the domesticated animal, for example, recovering in a few generations its wild instinct, and the garden-flower and fruit-tree reverting to the likeness of the parent stock.

Now, if it would be reasonable to draw such inferences with respect to the future, we cannot but apply the same rules of induction to the past. We have no right to anticipate any modifications in the results of existing causes in time to come, which are not conformable to analogy, unless they be produced by the progressive development of human power, or perhaps by some other new relations which may hereafter spring up between the moral and material worlds. In the same manner, when we speculate on the vicissitudes of the animate and inanimate creation in former ages, we ought not to look for any anomalous results, unless where man has interfered, or unless clear indications appear of some other *moral* source of temporary derangement.

CHAPTER X.

SUPPOSED INTENSITY OF AQUEOUS FORCES AT REMOTE PERIODS.

Intensity of aqueous causes — Slow accumulation of strata proved by fossils — Rate of denudation can only keep pace with deposition — Erratics, and effects of ice — Deluges, and the causes to which they are referred — Supposed universality of ancient deposits.

Intensity of aqueous causes. — The great problem considered in the preceding chapters, namely, whether the former changes of the earth made known to us by geology, resemble in kind and degree those now in daily progress, may still be contemplated from several other points of view. We may inquire, for example, whether there are any grounds for the belief entertained by many, that the intensity both of aqueous and of igneous forces, in remote ages, far exceeded that which we witness in our own times.

First, then, as to aqueous causes: it has been shown in our history of the science, that Woodward did not hesitate, in 1695, to teach that the entire mass of fossiliferous strata contained in the earth's crust had been deposited in a few months; and, consequently, as their mechanical and derivative origin was already admitted, the reduction of rocky masses into mud, sand, and pebbles, the transportation of the same to a distance, and their accumulation elsewhere in regular strata, were all assumed to have taken place with a rapidity unparalleled in modern times. This doctrine was modified by degrees, in proportion as different classes of organic remains, such as shells, corals, and fossil plants, had been studied with attention. Analogy led every naturalist to assume, that each full-grown individual of the animal or vegetable kingdom, had required a certain number of months or years for the attainment of maturity, and the perpetuation of its species by generation; and thus the first approach was made to the conception of a common standard of time, without which there are no means whatever of measuring the comparative rate at which any succession of events has taken place at two distinct periods. This standard consisted of the average duration of the lives of individuals of the same genera or families in the animal and vegetable kingdoms; and the multitude of fossils dispersed through successive strata implied the continuance of the same species for many generations. At length the idea that species themselves had had a limited duration, arose out of the observed fact that sets of strata of different ages contained fossils of distinct species. Finally, the opinion became general, that in the course of ages, one assemblage of animals and plants had disappeared after another again and again, and new tribes had started into life to replace them.

Denudation. — In addition to the proofs derived from organic remains, the forms of stratification led also, on a fuller investigation, to the belief that sedimentary rocks had been slowly deposited; but it was still supposed that *denudation*, or the power of running water, and the waves and currents of the ocean, to strip off superior strata, and lay bare the rocks below, had formerly operated with an energy wholly unequalled in our times. These opinions were both illogical and inconsistent, because deposition and denudation are parts of the same process, and what is true of the one must be true of the other. Their speed must be always limited by the same causes, and the conveyance of solid matter to a particular region can only keep pac with its removal from another, so that the aggregate of sedimentar strata in the earth's crust can never exceed in volume the amount o solid matter which has been ground down and washed away b running water. How vast then must be the spaces which thi abstraction of matter has left vacant! how far exceeding in dimensions all the valleys, however numerous, and the hollows, howeve vast, which we can prove to have been cleared out by aqueou erosion! The evidences of the work of denudation are defective because it is the nature of every destroying cause to obliterate th signs of its own agency; but the amount of reproduction in the forn of sedimentary strata must always afford a true measure of the minimum of denudation which the earth's surface has undergone.

Erratics. — The next phenomenon to which the advocates of th excessive power of running water in times past have appealed, is th enormous size of the blocks called *erratic*, which lie scattered over the northern parts of Europe and North America. Unquestionably a large proportion of these blocks have been transported far from their original position, for between them and the parent rocks we now find, not unfrequently, deep seas and valleys intervening, or hills more than a thousand feet high. To explain the present situation of such travelled fragments, a deluge of mud has been imagined by some to have come from the north, bearing along with it sand, gravel, and stony fragments, some of them hundreds of tons in weight. This flood, in its transient passage over the continents, dispersed the boulders irregularly over hill, valley, and plain; or forced them along over a surface of hard rock, so as to polish it and leave it indented with parallel scratches and grooves, — such markings as are still visible in the rocks of Scandinavia, Scotland, Canada, and many other countries.

There can be no doubt that the myriads of angular and rounded blocks above alluded to, cannot have been borne along by ordinary rivers or marine currents, so great is their volume and weight, and so clear are the signs, in many places, of time having been occupied in their successive deposition; for they are often distributed at various depths through heaps of regularly stratified sand and gravel. No waves of the sea raised by earthquakes, nor the bursting of lakes dammed up for a time by landslips or by avalanches of snow, can account for the observed facts; but I shall endeavour to show, in the next book, chap. 15.*, that a combination of existing causes may have conveyed erratics into their present situations.

The causes which will be referred to are, first, the carrying power of ice, combined with that of running water; and second, the upward movement of the bed of the sea, converting it gradually into land. Without entering at present into any details respecting these causes, I may mention that the transportation of blocks by ice is now simultaneously in progress in the cold and temperate latitudes, both of the northern and southern hemisphere, as, for example, on the coasts of Canada and Gulf of St. Lawrence, and also in Chili, Patagonia, and the island of South Georgia. In those regions the uneven bed of the ocean is becoming strewed over with ice-drifted fragments, which have either stranded on shoals, or been dropped in deep water by melting bergs. The entanglement of boulders in drift ice will also be shown to occur annually in North America, and these stones, when firmly frozen into ice, wander year after year from Labrador to the St. Lawrence, and reach points of the western hemisphere farther south than any part of Great Britain.

The general absence of erratics in the warmer parts of the equatorial regions of Asia, Africa, and America, confirms the same views. As to the polishing and grooving of hard rocks, it has lately been ascertained that glaciers give rise to these effects when pushing forward sand, pebbles, and rocky fragments, and causing them to grate along the bottom. Nor can there be any reasonable doubt that icebergs, when they run aground on the floor of the ocean, must imprint similar marks upon it.

---

* See also Manual of Geology, ch. 11, 12.

It is unnecessary, therefore, to refer to deluges, or even to speculate on the former existence of a climate more severe than that now prevailing in the western hemisphere, to explain the geographical distribution of most of the European erratics.

Deluges.—As deluges have been often alluded to, I shall say something of the causes which may be supposed to give rise to these grand movements of water in addition to those already alluded to (p. 9.). Geologists who believe that mountain-chains have been thrown up suddenly at many successive epochs, imagine that the waters of the ocean may be raised by these convulsions, and then break in terrific waves upon the land, sweeping over whole continents, hollowing out valleys, and transporting sand, gravel, and erratics, to great distances. The sudden rise of the Alps or Andes, it is said, may have produced a flood even subsequently to the time when the earth became the residence of man. But it seems strange that none of the writers who have indulged their imaginations in conjectures of this kind, should have ascribed a deluge to the sudden conversion of part of the unfathomable ocean into a shoal rather than to the rise of mountain-chains. In the latter case, the mountains themselves could do no more than displace a certain quantity of atmospheric air, whereas, the instantaneous formation of the shoal would displace a vast body of water, which being heaved up to a great height might roll over and permanently submerge a large portion of a continent.

If we restrict ourselves to combinations of causes at present known, it would seem that the two principal sources of extraordinary inundations are, first, the escape of the waters of a large lake raised far above the sea; and, secondly, the pouring down of a marine current into lands depressed below the mean level of the ocean.

As an example of the first of these cases, we may take Lake Superior, which is more than 400 geographical miles in length and about 150 in breadth, having an average depth of from 500 to 900 feet. The surface of this vast body of fresh water is no less than 600 feet above the level of the ocean; the lowest part of the barrier which separates the lake on its south-west side from those streams which flow into the head waters of the Mississippi being about 600 feet high. If, therefore, a series of subsidences should lower any part of this barrier 600 feet, any subsequent rending or depression, even of a few yards at a time, would allow the sudden escape of vast floods of water into a hydrographical basin of enormous extent. If the event happened in the dry season, when the ordinary channels of the Mississippi and its tributaries are in a great degree empty, the inundation might not be considerable; but if in the flood-season, a region capable of supporting a population of many millions might be suddenly submerged. But even this event would be insufficient to cause a violent rush of water, and to produce those effects usually called diluvial; for the difference of level of 600 feet between Lake Superior and the

Gulf of Mexico, when distributed over a distance of 1800 miles, would give an average fall of only four inches per mile.

The second case before adverted to is where there are large tracts of dry land beneath the mean level of the ocean. It seems, after much controversy, to be at length a settled point, that the Caspian is really 83 feet 6 inches lower than the Black Sea. As the Caspian covers an area about equal to that of Spain, and as its shores are in general low and flat, there must be many thousand square miles of country less than 83 feet above the level of that inland sea, and consequently depressed below the Black Sea and Mediterranean. This area includes the site of the populous city of Astrakhan and other towns. Into this region the ocean would pour its waters if, the land now intervening between the Sea of Azof and the Caspian should subside. Yet, even if this event should occur, it is most probable that the submergence of the whole region would not be accomplished simultaneously, but by a series of minor floods, the sinking of the barrier being gradual.*

Supposed universality of ancient deposits.—The next fallacy which has helped to perpetuate the doctrine that the operations of water were on a different and grander scale in ancient times, is founded on the indefinite areas over which homogeneous deposits were supposed to extent. No modern sedimentary strata, it is said, equally identical in mineral character and fossil contents, can be traced continuously from one quarter of the globe to another. But the first propagators of these opinions were very slightly acquainted with the inconstancy in mineral composition of the ancient formations, and equally so of the wide spaces over which the same kind of sediment is now actually distributed by rivers and currents in the course of centuries. The persistency of character in the older series was exaggerated, its extreme variability in the newer was assumed without proof. In the chapter which treats of river-deltas and the dispersion of sediment by currents, and in the description of reefs of coral now growing over areas many hundred miles in length, I shall have opportunities of convincing the reader of the danger of hasty generalizations on this head.

---

* It has been suspected ever since the middle of the last century, that the Caspian was lower than the ocean, it being known that in Astrakhan the mercury in the barometer generally stands above thirty inches. In 1811, MM. Engelhardt and Parrot attempted to determine the exact amount of difference by a series of levellings and barometrical measurements across the isthmus at two different places near the foot of Mount Caucasus. The result of their operations led them to the opinion that the Caspian was more than 300 feet below the Black Sea. But the correctness of the observations having afterwards been called in question, M. Parrot revisited the ground in 1829 and 1830, and inferred from new levellings, that the mouth of the Don was between three and four feet lower than that of the Wolga; in other words, that the sea of Azof, which communicates with the Black Sea, was actually lower than the Caspian! Other statements, no less contradictory, having been made by other observers, the Russian government at length directed the Academy of St. Petersburg to send an expedition, in 1836, to decide the point by a trigonometrical survey, from which it appeared that the Caspian is 101 Russian, or 108 English, feet lower than the Black Sea. (For authorities, see Journ. Roy. Geograph. Soc. vol. viii. p. 135.) Sir R. Murchison, however, concludes, in 1845, from the best Russian authorities, that the depression of the Caspian is only 83 feet 6 inches.

The measurements of Major Anthony Symonds, since confirmed by French authorities, make the Dead Sea to be 1200 feet below the Mediterranean.

In regard to the imagined universality of particular rocks of ancient date, it was almost unavoidable that this notion, when once embraced, should be perpetuated; for the same kinds of rock have occasionally been reproduced at successive epochs: and when once the agreement or disagreement in mineral character alone was relied on as the test of age, it followed that similar rocks, if found even at the antipodes, were referred to the same era, until the contrary could be shown.

Now it is usually impossible to combat such an assumption on geological grounds, so long as we are imperfectly acquainted with the order of superposition and the organic remains of these same formations. Thus, for example, a group of red marl and red sandstone, containing salt and gypsum, being interposed in England between the Lias and the Coal, all other red marls and sandstones, associated some of them with salt, and others with gypsum, and occurring not only in different parts of Europe, but in North America, Peru, India, the salt deserts of Asia, those of Africa—in a word, in every quarter of the globe, were referred to one and the same period. The burden of proof was not supposed to rest with those who insisted on the identity in age of all these groups—their identity in mineral composition was thought sufficient. It was in vain to urge as an objection the improbability of the hypothesis which implies that all the moving waters on the globe were once simultaneously charged with sediment of a red colour.

But the rashness of pretending to identify, in age, all the red sandstones and marls in question, has at length been sufficiently exposed, by the discovery that, even in Europe, they belong decidedly to many different epochs. It is already ascertained, that the red sandstone and red marl containing the rock-salt of Cardona in Catalonia is newer than the Oolitic, if not more modern than the Cretaceous period It is also known that certain red marls and variegated sandstones in Auvergne which are undistinguishable in mineral composition from the New Red Sandstone of English geologists, belong, nevertheless, to the Eocene period: and, lastly, the gypseous red marl of Aix, in Provence, formerly supposed to be a marine secondary group, is now acknowledged to be a tertiary freshwater formation. In Nova Scotia one great deposit of red marl, sandstone, and gypsum, precisely resembling in mineral character the "New Red" of England, occurs as a member of the Carboniferous group, and in the United States near the Falls of Niagara, a similar formation constitutes a subdivision of the Silurian series. *

Nor was the nomenclature commonly adopted in geology without its influence in perpetuating the erroneous doctrine of universal formations. Such names, for example, as Chalk, Green Sand, Oolite,

---

* See Lyell's Travels in N. America, ch. 2. and 25.

Red Marl, Coal, and others, were given to some of the principal fossiliferous groups in consequence of mineral peculiarities which happened to characterize them in the countries where they were first studied. When geologists had at length shown, by means of fossils and the order of superposition, that other strata, entirely dissimilar in colour, texture, and composition, were of contemporaneous date, it was thought convenient still to retain the old names. That these were often inappropriate was admitted; but the student was taught to understand them in no other than a chronological sense; so that the Chalk might not be a white cretaceous rock, but a hard dolomitic limestone, as in the Alps, or a brown sandstone or green marl, as in New Jersey, U. S. In like manner, the Green Sand, it was said, might in some places be represented by red sandstone, red marl, salt, and gypsum, as in the north of Spain. So the oolitic texture was declared to be rather an exception than otherwise to the general rule in rocks of the Oolitic period; and it often became necessary to affirm that no particle of carbonaceous matter could be detected in districts where the true Coal series abounded. In spite of every precaution the habitual use of this language could scarcely fail to instil into the mind of the pupil an idea that chalk, coal, salt, red marl, or the Oolitic structure were far more widely characteristic of the rocks of a given age than was really the case.

There is still another cause of deception, disposing us to ascribe a more limited range to the newer sedimentary formations as compared to the older, namely, the very general concealment of the newer strata beneath the waters of lakes and seas, and the wide exposure above waters of the more ancient. The Chalk, for example, now seen stretching for thousands of miles over different parts of Europe, has become visible to us by the effect, not of one, but of many distinct series of subterranean movements. Time has been required, and a succession of geological periods, to raise it above the waves in so many regions; and if calcareous rocks of the middle and upper tertiary periods have been formed, as homogeneous in mineral composition throughout equally extensive regions, it may require convulsions as numerous as all those which have occurred since the origin of the Chalk to bring them up within the sphere of human observation. Hence the rocks of more modern periods may appear partial, as compared to those of remoter eras, not because of any original inferiority in their extent, but because there has not been sufficient time since their origin for the development of a great series of elevatory movements.

In regard, however, to one of the most important characteristics of sedimentary rocks, their organic remains, many naturalists of high authority have maintained that the same species of fossils are more uniformly distributed through formations of high antiquity than in those of more modern date, and that distinct zoological and botanical provinces, as they are called, which form so striking a feature in the living creation, were not established at remote eras. Thus the plants of the Coal, the shells, and trilobites of the Silurian rocks, and t [illegible] monites of the Oolite, have been supposed to have a wider geographical range than any living species of plants, crustaceans, or mollusks. This opinion seems in certain cases to be well founded, especially in relation to the plants of the carboniferous epoch, owing probably to the more uniform temperature of the globe, at a time when the position of sea and land was less favourable to variations in climate, according to principles already explained in the seventh and eighth chapters. But a recent comparison of the fossils of North American rocks with those of corresponding ages in the European series, has proved that the terrestrial vegetation of the Carboniferous epoch is an exception to the general rule, and that the fauna and flora of the earth at successive periods, from the oldest Silurian to the newest Tertiary was as diversified as now. The shells, corals, and other classes of organic remains demonstrate the fact that the earth might then have been divided into separate zoological provinces, in a manner analogous to that observed in the geographical distribution of species now living.

CHAPTER XI.

ON THE SUPPOSED FORMER INTENSITY OF THE IGNEOUS FORCES.

Volcanic action at successive geological periods — Plutonic rocks of different ages — Gradual development of subterranean movements — Faults — Doctrine of the sudden upheaval of parallel mountain-chains — Objections to the proof of the suddenness of the upheaval, and the contemporaneousness of parallel chains — Trains of active volcanos not parallel — As large tracts of land are rising or sinking slowly, so narrow zones of land may be pushed up gradually to great heights — Bending of strata by lateral pressure — Adequacy of the volcanic power to effect this without paroxysmal convulsions.

When reasoning on the intensity of volcanic action at former periods, as well as on the power of moving water, already treated of, geologists have been ever prone to represent Nature as having been prodigal of violence and parsimonious of time. Now, although it is less easy to determine the relative ages of the volcanic than of the fossiliferous formations, it is undeniable that igneous rocks have been produced at all geological periods, or as often as we find distinct deposits marked by peculiar animal and vegetable remains. It can be shown that rocks commonly called trappean have been injected into fissures, and ejected at the surface, both before and during the deposition of the Carboniferous series, and at the time when the Magnesian Limestone, and when the Upper New Red Sandstone were formed, or when the Lias, Oolite, Green Sand, Chalk, and the several tertiary groups newer than the chalk, originated in succession. Nor is this all; distinct volcanic products may be referred to the subordinate divisions of each period, such as the Carboniferous, as in the county of Fife, in Scotland, where certain masses of contemporaneous trap are associated with the Lower, others with the Upper Coal-measures. And if one of these masses is more minutely examined, we find it to consist of the products of a great many successive outbursts, by which scoriæ and lava were again and again emitted, and afterwards consolidated, then fissured, and finally traversed by melted matter constituting what are called dikes.* As we enlarge, therefore, our knowledge of the ancient rocks formed by subterranean heat, we find ourselves compelled to regard them as the aggregate effects of innumerable eruptions, each of which may have been comparable in violence to those now experienced in volcanic regions.

It may indeed be said that we have as yet no data for estimating the relative volume of matter simultaneously in a state of fusion at two given periods, as if we were to compare the columnar basalt of Staffa and its environs with the lava poured out in Iceland in 1783; but for this very reason it would be rash and unphilosophical to assume an excess of ancient as contrasted with modern outpourings of melted matter at particular periods of time.† It would be still more presumptuous to take for granted that the more deep-seated effects of subterranean heat surpassed at remote eras the corresponding effects of internal heat in our own times. Certain porphyries and granites, and all the rocks commonly called plutonic, are now generally supposed to have resulted from the slow cooling of materials fused and solidified under great pressure; and we cannot doubt that beneath existing volcanos there are large spaces filled with melted stone, which must for centuries remain in an incandescent state, and then cool and become hard and crystalline when the subterranean heat shall be exhausted. That lakes of lava are continuous for hundreds of miles beneath the Chilian Andes, seems established by observations made in the year 1835.‡

Now, wherever the fluid contents of such reservoirs are poured out uccessively from craters in the open air, or at the bottom of the sea, he matter so ejected may afford evidence by its arrangement of aving originated at different periods; but if the subterranean residue fter the withdrawal of the heat be converted into crystalline or pluonic rock, the entire mass may seem to have been formed at once, owever countless the ages required for its fusion and subsequent rerigeration. As the idea that all the granite in the earth's crust was roduced simultaneously, and in a primitive state of the planet, has ow been universally abandoned; so the suggestion above adverted o, may put us on our guard against too readily adopting another pinion, namely, that each large mass of granite was generated in a rief period of time.

Modern writers indeed, of authority, seem more and more agreed that in the case of granitic rocks, the passage from a liquid or pasty to a solid and crystalline state must have been an extremely gradual process.

---

* See Manual of Geology, chap. 29. o 33. inclusive.

† See ch. 26. *infrà.*

‡ See ch. 27. *infrà.*

The doctrine so much insisted upon formerly, that crystalline rocks, such as granite, gneiss, mica-schist, quartzite, and others were produced in the greatest abundance in the earlier ages of the planet, and that their formation has ceased altogether in our own times, will be controverted in the next chapter.

Gradual development of subterranean movements.—The extreme violence of the subterranean forces in remote ages has been often inferred from the facts that the older rocks are more fractured and dislocated than the newer. But what other result could we have anticipated if the quantity of movement had been always equal in equal periods of time? Time must, in that case, multiply the derangement of strata in the ratio of their antiquity. Indeed the numerous exceptions to the above rule which we find in nature, present at first sight the only objection to the hypothesis of uniformity. For the more ancient formations remain in many places horizontal, while in others much newer strata are curved and vertical. This apparent anomaly, however, will be seen in the next chapter to depend on the irregular manner in which the volcanic and subterranean agency affect different parts of the earth in succession, being often renewed again and again in certain areas, while others remain during the whole time at rest.

That the more impressive effects of subterranean power, such as the upheaval of mountain-chains, may have been due to multiplied convulsions of moderate intensity rather than to a few paroxysmal explosions, will appear the less improbable when the gradual and intermittent development of volcanic eruptions in times past is once established. It is now very generally conceded that these eruptions have their source in the same causes as those which give rise to the permanent elevation and sinking of land; the admission, therefore, that one of the two volcanic or subterranean processes has gone on gradually draws with it the conclusion that the effects of the other have been elaborated by successive and gradual efforts.

Faults.—The same reasoning is applicable to great *faults*, or those striking instances of the upthrow or downthrow of large masses of rock, which have been thought by some to imply tremendous catastrophes wholly foreign to the ordinary course of nature. Thus we have in England faults, in which the vertical displacement is between 600 and 3000 feet, and the horizontal extent thirty miles or more, the width of the fissures since filled up with rubbish varying from ten to fifty feet. But when we inquire into the proofs of the mass having risen or fallen suddenly on the one side of these great rents, several hundreds or thousands of feet above or below the rock with which it was once continuous on the other side, we find the evidence defective. There are grooves, it is said, and scratches on the rubbed and polished walls, which have often one common direction, favouring the theory that the movement was accomplished by a single stroke, and not by a eries of interrupted movements. But, in fact, the striæ are not lways parallel in such cases, but often irregular, and sometimes the tones and earth which are in the middle of the fault, or fissure, ave been polished and striated by friction in different directions, howing that there have been slidings subsequent to the first introuction of the fragmentary matter. Nor should we forget that the ast movement must always tend to obliterate the signs of previous rituration, so that neither its instantaneousness nor the uniformity of ts direction can be inferred from the parallelism of the striæ that ave been last produced.

When rocks have been once fractured, and freedom of motion ommunicated to detached portions of them, these will naturally coninue to yield in the same direction, if the process of upheaval or of ndermining be repeated again and again. The incumbent mass will lways give way along the lines of least resistance, or where it was ormerly rent asunder. Probably, the effects of reiterated movement, hether upward or downward, in a fault, may be undistinguishable rom those of a single and instantaneous rise or subsidence; and the ame may be said of the rising or falling of continental masses, such s Sweden or Greenland, which we know to take place slowly and nsensibly.

Doctrine of the sudden upheaval of parallel mountain-chains.— The doctrine of the suddenness of many former revolutions in the physical geography of the globe has been thought by some to derive dditional confirmation from a theory respecting the origin of mountain-chains, advanced in 1833 by a distinguished geologist, M. Elie de Beaumont. In several essays on this subject, the last published in 1852, he has attempted to establish two points; first, that a variety of independent chains of mountains have been thrown up suddenly at particular periods; and, secondly, that the contemporaneous chains thus thrown up, preserve a parallelism the one to the other.

These opinions, and others by which they are accompanied, are so adverse to the method of interpreting the history of geological changes which I have recommended in this work, that I am desirous of explaining the grounds of my dissent, a course which I feel myself the more called upon to adopt, as the generalizations alluded to are those of a skilful writer, and an original observer of great talent and experience. I shall begin, therefore, by giving a brief summary of the principal propositions laid down in the works above referred to.*

1st. M. de Beaumont supposes "that in the history of the earth there have been long periods of comparative repose, during which the deposition of sedimentary matter has gone on in regular continuity; and there have also been short periods of paroxysmal violence, during which that continuity was broken.

---

* Ann. des Sci. Nat., Septembre, Novembre, et Décembre, 1829. Revue Française, No. 15. May, 1830. Bulletin de la Société Géol. de France, p. 864. May, 1847. The latest edition of M. de Beaumont's theory will be found in the 12th vol. of the Dictionnaire Universel d'Hist. Nat. 1852, art. "Systèmes des Montagnes;" also the same printed separately.

"2dly. At each of these periods of violence or 'revolution,' in the state of the earth's surface, a great number of mountain-chains have been formed suddenly.

"3dly. The chains thrown up by a particular revolution have one uniform direction, being parallel to each other within a few degrees of the compass, even when situated in remote regions; whilst the chains thrown up at different periods have, for the most part, different directions.

"4thly. Each 'revolution,' or 'great convulsion,' has fallen in with the date of another geological phenomenon; namely, 'the passage from one independent sedimentary formation to another,' characterized by a considerable difference in 'organic types.'

"5thly. There has been a recurrence of these paroxysmal movements from the remotest geological periods; and they may still be reproduced, and the repose in which we live may hereafter be broken by the sudden upthrow of another system of parallel chains of mountains.

"6thly. The origin of these chains depends not on partial volcanic action, or a reiteration of ordinary earthquakes, but on the secular refrigeration of the entire planet. For the whole globe, with the exception of a thin envelope, much thinner in proportion than the shell to an egg, is a fused mass, kept fluid by heat, but constantly cooling and contracting its dimensions. The external crust does not gradually collapse and accommodate itself century after century to the shrunken nucleus, subsiding as often as there is a slight failure of support, but it is sustained throughout whole geological periods, so as to become partially separated from the nucleus, until at last it gives way suddenly, cracking and falling in along determinate lines of fracture During such a crisis the rocks are subjected to great lateral pressure the unyielding ones are crushed, and the pliant strata bent, an are forced to pack themselves more closely into a smaller space, havin no longer the same room to spread themselves out horizontally. A the same time, a large portion of the mass is squeezed upward because it is in the upward direction only that the excess in size o the envelope, as compared to the contracted nucleus, can find relie This excess produces one or more of those folds or wrinkles in th earth's crust which we call mountain-chains.

Lastly, some chains are comparatively modern; such as the Alp which were partly upheaved after the middle tertiary period. Th elevation of the Andes was much more recent, and was accompanie by the simultaneous outburst for the first time of 270 of the princip volcanos now active.*

The agitation of the waters of the ocean caused by this convulsio probably occasioned that transient and general deluge which i noticed in the traditions of so many nations.†

---

* Système de Mont. p. 762.

† Ibid. pp. 761. and 773.

Several of the topics enumerated in the above summary, such as the cause of interruptions in the sedimentary series, will be discussed in the thirteenth chapter, and I shall now confine myself to what I conceive to be the insufficiency of the proofs adduced in favour of the suddenness of the upthrow, and the contemporaneousness of the origin of the parallel chains referred to. At the same time I may remark, that the great body of facts collected together by M. de Beaumont will always form a most valuable addition to our knowledge, tending as they do to confirm the doctrine that different mountain-chains have been formed in succession, and, as Werner first pointed out, that there are certain determinate lines of direction or strike in the strata of various countries.

The following may serve as an analysis of the evidence on which the theory above stated depends. "We observe," says M. de Beaumont, "when we attentively examine nearly all mountain-chains, that the most recent rocks extend horizontally up to the foot of such chains, as we should expect would be the case if they were deposited in seas or lakes, of which these mountains have partly formed the shores; whilst the other sedimentary beds, tilted up, and more or less contorted, on the flanks of the mountains, rise in certain points even to their highest crests."* There are, therefore, in and adjacent to each chain, two classes of sedimentary rocks, the ancient or inclined beds, and the newer or horizontal. It is evident that the first appearance of the chain itself was an event "intermediate between the period when the beds now upraised were deposited, and the period when the strata were produced horizontally at its feet."

Fig. 11.



Thus the chain A assumed its present position after the deposition of the strata *b*, which have undergone great movements, and before the deposition of the group *c*, in which the strata have not suffered derangement.

If we then discover another chain B, in which we find not only the formation *b*, but the group *c* also, disturbed and thrown on its edges, we may infer that the latter chain is of subsequent date to A; for B must have been elevated *after* the deposition of *c*, and before

Fig. 12.



---

*Phil. Mag. and Annals, No. 58. New Series, p. 242.

that of the group *d;* whereas A had originated *before* th
were formed.

It is then argued, that in order to ascertain whether other
ranges are of contemporaneous date with A and B, or are re
distinct periods, we have only to inquire whether the inc
undisturbed sets of strata in each range correspond with
from those in the typical chains A and B.

Now all this reasoning is perfectly correct, so long as the
time required for the deposition of the strata *b* and *c* is
identical in duration with the period of time during w
animals and plants found fossil in *b* and *c* may have flouri
the latter, that is to say, the duration of certain groups o
may have greatly exceeded, and probably did greatly ex
former, or the time required for the accumulation of cert
deposits, such as *b* and *c* (figs. 11. and 12.). In order, mor
render the reasoning correct, due latitude must be given to
contemporaneous; for this term must be understood to allu
a moment of time, but to the interval, whether brief or p
which elapsed between two events, namely, between the acc
of the inclined and that of the horizontal strata.

But, unfortunately, no attempt has been made in the
under review to avoid this manifest source of confusion, a
the very terms of each proposition are equivocal; and the
length of some of the intervals is so vast, that to affirm th
chains raised in such intervals were *contemporaneous* is an
language.

In order to illustrate this argument, I shall select the Py
an example. Originally M. E. de Beaumont spoke of this
mountains as having been uplifted suddenly (*à un seul je*
has since conceded that in this chain, in spite of the gene
and simplicity of its structure, six, if not seven, systems o
tion of different dates can be recognized.* In reference,
to the latest, and by far the most important of these convul
chain is said to have attained its present elevation at a cert
in the earth's history, namely, between the deposition of t
or rocks of about that age, and that of certain tertiary f
"as old as the plastic clay;" for the chalk is seen in vertica
and distorted beds on the flanks of the chain, as the beds
while the tertiary formations rest upon them in horizontal
its base, as *c*, ibid.

The proof, then, of the extreme suddenness of the con
supposed to be the shortness of the time which intervened
the formation of the chalk and the origin of certain tertiar
Even if the interval were reducible within these limits, it m
prise an indefinite lapse of time. In strictness of reasoning,
the author cannot exclude the Cretaceous or Tertiary peri

---

* Système de Montagnes, 1852. p. 429.

† Phil. Mag. and Anna New Series, p. 243.

the possible duration of the interval during which the elevation may have taken place. For, in the first place, it cannot be assumed that the movement of upheaval took place after the close of the Cretaceous period; we can merely say, that it occurred after the deposition of certain strata of that period; secondly, although it were true that the event happened before the formation of all the tertiary strata now at the base of the Pyrenees, it would by no means follow that it preceded the whole Tertiary epoch.

The age of the strata, both of the inclined and horizontal series, may have been accurately determined by M. de Beaumont, and still the upheaving of the Pyrenees may have been going on before the animals of the Chalk period, such as are found fossil in England, had ceased to exist, or when the Maestricht beds were in progress, or during the indefinite ages which may have elapsed between the extinction of the Maestricht animals and the introduction of the Eocene tribes, or during the Eocene epoch, or the rise may have been going on throughout one, or several, or all of these periods.

It would be a purely gratuitous assumption to say that the inclined cretaceous strata (*b*, fig. 11.) on the flanks of the Pyrenees, were the very last which were deposited during the Cretaceous period, or that, as soon as they were upheaved, all or nearly all the species of animals and plants now found fossil in them were suddenly exterminated; yet, unless this can be affirmed, we cannot say that the Pyrenees were not upheaved during the Cretaceous period. Consequently, another range of mountains, at the base of which cretaceous rocks may lie in horizontal stratification, may have been elevated, like the chain A, fig. 12., during some part of the same great period.

There are mountains in Sicily two or three thousand feet high, the tops of which are composed of limestone, in which a large proportion of the fossil shells agree specifically with those now inhabiting the Mediterranean. Here, as in many other countries, the deposits now in progress in the sea, must inclose shells and other fossils specifically identical with those of the rocks constituting the contiguous land. So there are islands in the Pacific, where a mass of dead coral has emerged to a considerable altitude, while other portions of the mass remain beneath the sea, still increasing by the growth of living zoophytes and shells. The chalk of the Pyrenees, therefore, may at a remote period have been raised to an elevation of several thousand feet, while the species found fossil in the same chalk still continued to be represented in the fauna of the neighbouring ocean. In a word, we cannot assume that the origin of a new range of mountains caused the Cretaceous period to cease, and served as the prelude to a new order of things in the animate creation.

To illustrate the grave objections above advanced, against the theory considered in the present chapter, let us suppose, that in some country three styles of architecture had prevailed in succession, each for a period of one thousand years; first the Greek, then the Roman, and then the Gothic; and that a tremendous earthquake was known to have occurred in the same district during one of the three periods

—a convulsion of such violence as to have levelled to the gro
the buildings then standing. If an antiquary, desirous of disc
the date of the catastrophe, should first arrive at a city where
Greek temples were lying in ruins and half engulphed in the
while many Gothic edifices were standing uninjured, could he
mine on these data the era of the shock ? Could he even excl
one of the three periods, and decide that it must have ha
during one of the other two ? Certainly not. He could merely
that it happened at some period after the introduction of the
style, and before the Gothic had fallen into disuse. Should
tend to define the date of the convulsion with greater precisi
decide that the earthquake must have occurred after the Gre
before the Gothic period, that is to say, when the Roman style
use, the fallacy in his reasoning would be too palpable to
detection for a moment.

Yet such is the nature of the erroneous induction which I a
exposing. For as, in the example above proposed, the erecti
particular edifice is perfectly distinct from the period of archi
in which it may have been raised, so is the deposition of chalk,
other set of strata, from the geological epochs characterized by
fossils to which they may belong.

It is almost superfluous to enter into any farther analysis
theory of parallelism, because the whole force of the ar
depends on the accuracy of the data by which the contempo
or non-contemporaneous date of the elevation of two inde
chains can be demonstrated. In every case, this evidence, a
by M. de Beaumont, is equivocal, because he has not include
possible interval of time between the deposition of the derang
the horizontal formations, part of the periods to which each o
classes of formations are referable. Even if all the geologic
therefore, adduced by the author were true and unquestiona
the conclusion that certain chains were or were not simulta
upraised is by no means a legitimate consequence.

In the third volume of my first edition of the Principles, wh
peared in April, 1833, I controverted the views of M. de Be
then just published, in the same terms as I have now restate
At that time I took for granted that the chronological date
newest rocks entering into the disturbed series of the Pyren
been correctly ascertained. It now appears, however, that
the most modern of those disturbed strata belong to the num
formation, which are regarded by the majority of geologists as
or older tertiary, an opinion not assented to by M. E. de Be
and which I cannot discuss here without being led into too
digression.*

Perhaps a more striking illustration of the difficulties we en
when we attempt to apply the theory under consideratio
to the best known European countries, is afforded by what i

---

* Système de Montagnes, 1852, p. 429.

"The System of the Longmynds." This small chain, situated in Shropshire, is the third of the typical systems to which M. E. de Beaumont compares other mountain ranges corresponding in *strike* and structure. The date assigned to its upheaval is "after the unfossiliferous greywacke, or Cambrian strata, and before the Silurian." But Sir R. I. Murchison had shown in 1838, in his "Silurian System," and the British government surveyors, since that time, in their sections (about 1845), that the Longmynds and other chains of similar composition in North Wales are *post-Silurian.* In all of them fossiliferous beds of the lower Silurian formation or Llandeilo flags are highly inclined, and often vertical. In one limited region the Caradoc sandstone, a member of the lower Silurian, rests unconformably on the denuded edges of the inferior (or Llandeilo) member of the same group; whilst in some cases both of these sets of strata are upturned. When, therefore, so grave an error is detected in regard to the age of a typical chain, we are entitled to inquire with surprise, by what means nine other *parallel* chains in France, Germany, and Sweden, assumed to be "ante-Silurian," have been made to agree precisely in date with the Longmynds? If they are correctly represented as having been all deposited before the deposition of the Silurian strata, they cannot be contemporaneous with the Longmynds, and they only prove how little reliance can be placed on parallelism as a test of simultaneousness of upheaval. But in truth it is impossible, for reasons already given, to demonstrate that each of those nine chains coincide in date with one another, any more than with the Longmynds.

The reader will see in the sequel (chap. 31.*) that Mr. Hopkins has inferred from astronomical calculations, that the solid crust of the earth cannot be less than 800 or 1000 miles thick, and may be more. Even if it be solid to the depth of 100 miles, such a thickness would be inconsistent with M. E. de Beaumont's hypothesis, who requires a shell not more than thirty miles thick, or even less. Mr. Hopkins admits that the exterior of the planet, though solid as a whole, may contain within it vast lakes or seas of lava. If so, the gradual fusion of rocks, and the expansive power of heat exerted for ages, as well as the subsequent contraction of the same during slow refrigeration, may perhaps account for the origin of mountain-chains, for these, as Dolomieu has remarked, are "far less important, proportionally speaking, than the inequalities on the surface of an egg-shell, which to the eye appears smooth." A "centripetal force" affecting the whole planet as it cools, seems a mightier cause than is required to produce wrinkles of such insignificant size.

In pursuing his investigations, M. E. de Beaumont has of late greatly multiplied the number of successive periods of instantaneous upheaval, admitting at the same time that occasionally new lines of upthrow have taken the direction of older ones.† These admissions render his views much more in harmony with the principles advocated in this work, but they impair the practical utility of parallelism considered as a chronological test; for no rule is laid down for limiting the interval whether in time or space, which may separate two parallel lines of upheaval of different dates.*

---

* For page, see Index, "Hopkins."

† Art. Système de Montagnes, p. 775.

Among the various propositions above laid down (p. 164.), it will be seen that the sudden rise of the Andes is spoken of as a modern event, but Mr. Darwin has brought together ample data in proof of the local persistency of volcanic action throughout a long succession of geological periods, beginning with times antecedent to the deposition of the oolitic and cretaceous formations of Chili, and continuing to the historical epoch. It appears that some of the parallel ridges which compose the Cordilleras, instead of being contemporaneous, were successively and slowly upheaved at widely different epochs. The whole range, after twice subsiding some thousands of feet, was brought up again by a slow movement in mass, during the era of the Eocene tertiary formations, after which the whole sank down once more several hundred feet, to be again uplifted to its present level by a slow and often interrupted movement.† In a portion of this latter period the "Pampean mud" was formed, in which the Megatherium mylodon and other extinct quadrupeds are buried. This mud contains in it recent species of shells, some of them proper to brackish water, and is believed by Mr. Darwin to be an estuary or delta deposit. M. A. d'Orbigny, however, has advanced an hypothesis referred to by M. E. de Beaumont, that the agitation and displacement of the waters of the ocean, caused by the elevation of the Andes, gave rise to a deluge, of which this Pampean mud, which rises sometimes to the height of 12,000 feet, is the result and monument.‡

In studying many chains of mountains, we find that the strike or line of outcrop of continuous sets of strata, and the general direction of the chain, may be far from rectilinear. Curves forming angles of 20° or 30° may be found in the same range as in the Alleghanies; just as trains of active volcanos and the zones throughout which modern earthquakes occur are often linear, without running in straight lines. Nor are all of these, though contemporaneous or belonging to our own epoch, by any means parallel, but some at right angles, the one to the other.

Slow upheaval and subsidence.—Recent observations have disclosed to us the wonderful fact, that not only the west coast of South America, but also other large areas, some of them several thousand miles in circumference, such as Scandinavia, and certain archipelagos in the Pacific, are slowly and insensibly rising; while other regions, such as Greenland, and parts of the Pacific and Indian Oceans, in which atolls or circular coral islands abound, are as gradually sinking.

---

* M. E. de Beaumont in his later inquiries (Comptes rendus, Sept. 1850, and Systèmes des Montagnes) has come to the conclusion, that the principal mountain ranges, if prolonged, would intersect each other at certain angles, so as to produce a regular geometric arrangement, which he calls "a pentagonal network." This theory has been ably discussed and controverted by Mr. Hopkins, in his Anniversary Address as President of the Geol. Soc., Feb. 1853.

† Darwin's Geology of South America, p. 248. London, 1846.

‡ Système de Montagnes, p. 748.

That all the existing continents and submarine abysses may have originated in movements of this kind, continued throughout incalculable periods of time, is undeniable, and the denudation which the dry land appears every where to have suffered, favours the idea that it was raised from the deep by a succession of upward movements, prolonged throughout indefinite periods. For the action of waves and currents on land slowly emerging from the deep, affords the only power by which we can conceive so many deep valleys and wide spaces to have been denuded as those which are unquestionably the effects of running water.

But perhaps it may be said that there is no analogy between the slow upheaval of broad plains or table lands, and the manner in which we must presume all mountain-chains, with their inclined strata, to have originated. It seems, however, that the Andes have been rising century after century, at the rate of several feet, while the Pampas on the east have been raised only a few inches in the same time. Crossing from the Atlantic to the Pacific, in a line passing through Mendoza, Mr. Darwin traversed a plain 800 miles broad, the eastern part of which has emerged from beneath the sea at a very modern period. The slope from the Atlantic is at first very gentle, then greater, until the traveller finds, on reaching Mendoza, that he has gained, almost insensibly, a height of 4000 feet. The mountainous district then begins suddenly, and its breadth from Mendoza to the shores of the Pacific is 120 miles, the average height of the principal chain being from 15,000 to 16,000 feet, without including some prominent peaks, which ascend much higher. Now all we require, to explain the origin of the principal inequalities of level here described, is to imagine, first, a zone of more violent movement to the west of Mendoza, and, secondly, to the east of that place, an upheaving force, which died away gradually as it approached the Atlantic. In short, we are only called upon to conceive, that the region of the Andes was pushed up four feet in the same period in which the Pampas near Mendoza rose one foot, and the plains near the shores of the Atlantic one inch. In Europe we have learnt that the land at the North Cape ascends about five feet in a century, while farther to the south the movements diminish in quantity first to a foot, and then, at Stockholm, to three inches in a century, while at certain points still farther south there is no movement.

But in what manner, it is asked, can we account for the great lateral pressure which has been exerted not only in the Andes, Alps, and other chains, but also on the strata of many low and nearly level countries? Do not the folding and fracture of the beds, the anticlinal and synclinal ridges and troughs, as they are called, and the vertical, and even sometimes the inverted position of the beds, imply an abruptness and intensity in the disturbing force wholly different in kind and energy to that which now rends the rocks during ordinary earthquakes? I shall treat more fully in the sequel (end of chap. 32.) of the probable subterranean sources, whether of upward or downward movement, and of great lateral pressure; but it i be well briefly to state in this place that in our own times, as, f example, in Chili, in 1822, the volcanic force has overcome the sistance, and permanently uplifted a country of such vast extent th the weight and volume of the Andes must be insignificant in co parison, even if we indulge the most moderate conjectures as the thickness of the earth's crust above the volcanic foci.

To assume that any set of strata with which we are acquaint are made up of such cohesive and unyielding materials, as to able to resist a power of such stupendous energy, if its directi instead of being vertical, happened to be oblique or horizontal, wo be extremely rash. But if they could yield to a sideway thrust, ev in a slight degree, they would become squeezed and folded to a amount if subjected for a sufficient number of times to the repeated action of the same force. We can scarcely doubt that a mass of rock several miles thick was uplifted in Chili in 1822 and 1835, and that a much greater volume of solid matter is upheaved wherever the rise of the land is very gradual, as in Scandinavia, the development of heat being probably, in that region, at a greater distance from the surface. If continents, rocked, shaken and fissured, like the western region of South America, or very gently elevated, like Norway and Sweden, do not acquire in a few days or hours an additional height of several thousand feet, this can arise from no lack of mechanical force in the subterranean moving cause, but simply because the antagonist power, or the strength, toughness, and density of the earth's crust is insufficient to resist, so long, as to allow the volcanic energy an indefinite time to accumulate. Instead of the explosive charge augmenting in quantity for countless ages, it finds relief continuously, or by a succession of shocks of moderate violence, so as never to burst or blow up the covering of incumbent rock in one grand paroxysmal convulsion. Even in its most energetic efforts it displays an intermittent and mitigated intensity, being never permitted to lay a whole continent in ruins. Hence the numerous eruptions of lava from the same vent, or chain of vents, and the recurrence of similar earthquakes for thousands of years along certain areas or zones of country. Hence the numerous monuments of the successive ejection and injection of melted matter in ancient geological epochs, and the fissures formed in distinct ages, and often widened and filled at different eras.

Among the causes of lateral pressure, the expansion by heat of large masses of solid stone intervening between others which have a different degree of expansibility, or which happen not to have their temperature raised at the same time, may play an important part. But as we know that rocks have so often sunk down thousands of feet below their original level, we can hardly doubt that much of the bending of pliant strata, and the packing of the same into smaller spaces, has frequently been occasioned by subsidence. Whether the failure of support be produced by the melting of porous rocks, which, when fluid, and subjected to great pressure, may occupy less room than before, or which, by passing from a pasty to a crystalline condition, may, as in the case of granite, according to the experiments of Deville, suffer a contraction of 10 per cent, or whether the sinking be due to the subtraction of lava driven elsewhere to some volcanic orifice, and there forced outwards, or whether it be brought on by the shrinking of solid and stony masses during refrigeration, or by the condensation of gases, or any other imaginable cause, we have no reason to incline to the idea that the consequent geological changes are brought about so suddenly, as that large parts of continents are swallowed up at once in unfathomable subterranean abysses. If cavities be formed, they will be enlarged gradually, and as gradually filled. We read, indeed, accounts of engulphed cities and areas of limited extent which have sunk down many yards at once; but we have as yet no authentic records of the sudden disappearance of mountains, or the submergence or emergence of great islands. On the other hand, the creeps in coal mines* demonstrate that gravitation begins to act as soon as a moderate quantity of matter is removed even at a great depth. The roof sinks in, or the floor of the mine rises, and the bent strata often assume as regularly a curved and crumpled arrangement as that observed on a grander scale in mountain-chains. The absence, indeed, of chaotic disorder, and the regularity of the plications in geological formations of high antiquity, although not unfrequently adduced to prove the unity and instantaneousness of the disturbing force, might with far greater propriety be brought forward as an argument in favour of the successive application of some irresistible but moderated force, such as that which can elevate or depress a continent.

In conclusion, I may observe that one of the soundest objections to the theory of the sudden upthrow or downthrow of mountain-chains is this, that it provides us with too much force of one kind, namely, that of subterranean movement, while it deprives us of another kind of mechanical force, namely, that exerted by the waves and currents of the ocean, which the geologist requires for the denudation of land during its slow upheaval or depression. It may be safely affirmed that the quantity of igneous and aqueous action,—of volcanic eruption and denudation,—of subterranean movement and sedimentary deposition,—not only of past ages, but of one geological epoch, or even the fraction of an epoch, has exceeded immeasurably all the fluctuations of the inorganic world which have been witnessed by man. But we have still to inquire whether the time to which each chapter or page or paragraph of the earth's autobiography relates, was not equally immense when contrasted with a brief era of 3000 or 5000 years. The real point on which the whole controversy turns, is the relative amount of work done by mechanical force in given quantities of time, past and present. Before we can determine the relative intensity of the force employed, we must have some fixed standard by which to measure the time expended in its development at two distinct periods. It is not the magnitude of the effects, however gigantic their proportions, which can inform us in the slightest degree whether the operation was sudden or gradual, insensible or paroxysmal. It must be shown that a slow process could never in any series of ages give rise to the same results.

---

* See Lyell's Manual of Elementary Geology, ch. 5.

The advocate of paroxysmal energy might assume an uniform and fixed rate of variation in times past and present for the animate world, that is to say, for the dying-out and coming-in of species, and then endeavour to prove that the changes of the inanimate world have not gone on in a corresponding ratio. But the adoption of such a standard of comparison would lead, I suspect, to a theory by no means favourable to the pristine intensity of natural causes. That the present state of the organic world is not stationary, can be fairly inferred from the fact, that some species are known to have become extinct in the course even of the last three centuries, and that the exterminating causes always in activity, both on the land and in the waters, are very numerous; also, because man himself is an extremely modern creation; and we may therefore reasonably suppose that some of the mammalia now contemporary with man, as well as a variety of species of inferior classes, may have been recently introduced into the earth, to supply the places of plants and animals which have from time to time disappeared. But granting that some such secular variation in the zoological and botanical worlds is going on, and is by no means wholly inappreciable to the naturalist, still it is certainly far less manifest than the revolution always in progress in the inorganic world. Every year some volcanic eruptions take place, and a rude estimate might be made of the number of cubic feet of lava and scoriæ poured or cast out of various craters. The amount of mud and sand deposited in deltas, and the advance of new land upon the sea, or the annual retreat of wasting sea-cliffs, are changes the minimum amount of which might be roughly estimated. The quantity of land raised above or depressed below the level of the sea might also be computed, and the change arising from such movements in a century might be conjectured. Suppose the average rise of the land in some parts of Scandinavia to be as much as five feet in a hundred years, the present sea-coast might be uplifted 700 feet in fourteen thousand years; but we should have no reason to anticipate, from any zoological data hitherto acquired, that the molluscous fauna of the northern seas would in that lapse of years undergo any sensible amount of variation. We discover sea-beaches in Norway 700 feet high, in which the shells are identical with those now inhabiting the German Ocean; for the rise of land in Scandinavia, however insensible to the inhabitants, has evidently been rapid when compared to the rate of contemporaneous change in the testaceous fauna of the German Ocean. Were we to wait therefore until the mollusca shall have undergone as much fluctuation as they underwent between the period of the Lias and the Upper Oolite formations, or between the Oolite and Chalk, nay, even between any two of eight subdivisions of the Eocene series, what stupendous revolutions in physical geography ought we not to expect, and how many mountain-chains might not be produced by the repetition of shocks of moderate violence, or by movements not even perceptible by man!

Or, if we turn from the mollusca to the vegetable kingdom, and ask the botanist how many earthquakes and volcanic eruptions might be expected, and how much the relative level of land and sea might be altered, or how far the principal deltas will encroach upon the ocean, or the sea-cliffs recede from the present shores, before the species of European forest-trees will die out, he would reply that such alterations in the inanimate world might be multiplied indefinitely before he should have reason to anticipate, by reference to any known data, that the existing species of trees in our forests would disappear and give place to others. In a word, the movement of the inorganic world is obvious and palpable, and might be likened to the minute-hand of a clock, the progress of which can be seen and heard, whereas the fluctuations of the living creation are nearly invisible, and resemble the motion of the hour-hand of a timepiece. It is only by watching it attentively for some time, and comparing its relative position after an interval, that we can prove the reality of its motion.*

CHAPTER XII.

DIFFERENCE IN TEXTURE OF THE OLDER AND NEWER ROCKS.

Consolidation of fossiliferous strata—Some deposits originally solid—Transition and slaty texture—Crystalline character of Plutonic and Metamorphic rocks—Theory of their origin—Essentially subterranean—No proofs that they were produced more abundantly at remote periods.

ANOTHER argument in favour of the dissimilarity of the causes operating at remote and recent eras has been derived by many geologists from the more compact, stony, and crystalline texture of the older as compared to the newer rocks.

Consolidation of strata.—This subject may be considered, first, in reference to the fossiliferous strata; and, secondly, in reference to those crystalline and stratified rocks which contain no organic remains, such as gneiss and mica-schist. There can be no doubt that the former of these classes, or the fossiliferous, are generally more compact and stony in proportion as they are more ancient. It is also certain that a great part of them were originally in a soft and incoherent state, and that they have been since consolidated. Thus we find occasionally that shingle and sand have been agglutinated firmly together by a ferruginous or siliceous cement, or that lime in solution has been introduced, so as to bind together materials previously incoherent. Organic remains have sometimes suffered a singular transformation, as, for example, where shells, corals, and wood are silicified, their calcareous or ligneous matter having been replaced by nearly pure silica. The constituents of some beds have probably set and become hard for the first time when they emerged from beneath the water.

---

* See the Author's Anniversary Address, Quart. Journ. Geol. Soc. 1850, vol. vi. p. 46., from which some of the above passages are extracted.

But, on the other hand, we observe in certain formations now in progress, particularly in coral reefs, and in deposits from the waters of mineral springs, both calcareous and siliceous, that the texture of rocks may sometimes be stony from the first. This circumstance may account for exceptions to the general rule, not unfrequently met with, where solid strata are superimposed on others of a plastic and incoherent nature, as in the neighbourhood of Paris, where the tertiary formations, consisting often of compact limestone and siliceous grit, are more stony than the subjacent chalk.

It will readily be understood, that the various solidifying causes, including those above enumerated, together with the pressure of incumbent rocks and the influence of subterranean heat, must all of them require time in order to exert their full power. If in the course of ages they modify the aspect and internal structure of stratified deposits, they will give rise to a general distinctness of character in the older as contrasted with the newer formations. But this distinctness will not be the consequence of any original diversity: they will be unlike, just as the wood in the older trees of a forest usually differs in texture and hardness from that of younger individuals of the same species.

Transition texture.—In the original classification of Werner, the highly crystalline rocks, such as granite and gneiss, which contain no organic remains, were called primary, and the fossiliferous strata secondary, while to another class of an age intermediate between the primary and secondary he gave the name of transition. They were termed transition because they partook in some degree in their mineral composition of the nature of the most crystalline rocks, such as gneiss and mica-schist, while they resembled the fossiliferous series in containing occasionally organic remains, and exhibiting evident signs of a mechanical origin. It was at first imagined, that the rocks having this intermediate texture had been all deposited subsequently to the series called primary, and before all the more earthy and fossiliferous formations. But when the relative position and organic remains of these transition rocks were better understood, it was perceived that they did not all belong to one period. On the contrary, the same mineral characters were found in strata of very different ages, and some formations occurring in the Alps, which several of the ablest scholars of Werner had determined to be transition, were ultimately ascertained, by means of their fossil contents and position, to be members of the Cretaceous, and even of the nummulitic or Eocene period. These strata had, in fact, acquired the *transition* texture from the influence of causes which, since their deposition, had modified their internal arrangement.

Texture and origin of Plutonic and metamorphic rocks. — Among the most singular of the changes superinduced on rocks, we have occasionally to include the slaty texture, the divisional planes of which sometimes intersect the true planes of stratification, and even pass directly through imbedded fossils. If, then, the crystalline, the slaty, and other modes of arrangement, once deemed characteristic of certain periods in the history of the earth, have in reality been assumed by fossiliferous rocks of different ages and at different times, we are prepared to inquire whether the same may not be true of the most highly crystalline state, such as that of gneiss, mica-schist, and statuary marble. That the peculiar characteristics of such rocks are really due to a variety of modifying causes has long been suspected by many geologists, and the doctrine has gained ground of late, although a considerable difference of opinion still prevails. According to the original Neptunian theory, all the crystalline formations were precipitated from a universal menstruum or chaotic fluid antecedently to the creation of animals and plants, the unstratified granite having been first thrown down so as to serve as a floor or foundation on which gneiss and other stratified rocks might repose. Afterwards, when the igneous origin of granite was no longer disputed, many conceived that a thermal ocean enveloped the globe, at a time when the first-formed crust of granite was cooling, but when it still retained much of its heat. The hot waters of this ocean held in solution the ingredients of gneiss, mica-schist, hornblende-schist, clay-slate, and marble, rocks which were precipitated, one after the other, in a crystalline form. No fossils could be inclosed in them, the high temperature of the fluid and the quantity of mineral matter which it held in solution, rendering it unfit for the support of organic beings.

It would be inconsistent with the plan of this work to enter here into a detailed account of what I have elsewhere termed the *metamorphic theory**; but I may state that it is now demonstrable in some countries that fossiliferous formations, some of them of the age of the Silurian strata, as near Christiana in Norway, others belonging to the Oolitic period, as around Carrara in Italy, have been converted partially into gneiss, mica-schist, and statuary marble. The transmutation has been effected apparently by the influence of subterranean heat, acting under great pressure, or by chemical and electrical causes operating in a manner not yet understood, and which have been termed *Plutonic* action, as expressing, in one word, all the modifying causes which may be brought into play at great depths, and under conditions never exemplified at the surface. To this Plutonic action the fusion of granite itself in the bowels of the earth, as well as the super-inducement of the metamorphic texture into

---

* See Lyell's Manual of Elementary Geology.

sedimentary strata, must be attributed; and in accordance wi
views the age of each metamorphic formation may be said t
fold, for we have first to consider the period when it origi
an aqueous deposit, in the form of mud, sand, marl, or li
secondly, the date at which it acquired a crystalline textu
same strata, therefore, may, according to this view, be very
in reference to the time of their deposition, and very m
regard to the period of their assuming the metamorphic char

*No proofs that these crystalline rocks were produced mo
dantly at remote periods.*—Several modern writers, without
the truth of the Plutonic or metamorphic theory, still cont
the crystalline and non-fossiliferous formations, whether str
unstratified, such as gneiss and granite, are essentially anc
class of rocks. They were generated, say they, most abund
a primeval state of the globe, since which time the quantity
has been always on the decrease, until it became very incons
in the Oolitic and Cretaceous periods, and quite evanescen
the commencement of the tertiary epoch.

Now the justness of these views depends almost entirel
question whether granite, gneiss, and other rocks of the sam
ever originated at the surface, or whether, according to the
above adopted, they are essentially subterranean in their ori
therefore entitled to the appellation of *hypogene*. If th
formed superficially in their present state, and as copiousl
modern as in the more ancient periods, we ought to see a
abundance of tertiary and secondary than of primary gra
gneiss; but if we adopt the hypogene theory before explain
rapid diminution in volume among the visible rocks in th
crust in proportion as we investigate the formations of newer
quite intelligible. If a melted mass of matter be now cooli
slowly at the depth of several miles beneath the crater of a
volcano, it must remain invisible until great revolutions in th
crust have been brought about. So also if stratified rocks ha
subjected to Plutonic action, and after having been baked or
to semi-fusion, are now cooling and crystallizing far under gr
will probably require the lapse of many periods before t
be forced up to the surface and exposed to view, even at
point. To effect this purpose there may be need of as
development of subterranean movement as that which in t
Andes, and Himalaya has raised marine strata containing am
to the height of 8000, 14,000, and 16,000 feet. By parity of
ing we can hardly expect that any hypogene rocks of the
periods will have been brought within the reach of human
tion, seeing that the emergence of such rocks must always be
posterior to the date of their origin, and still less can forma
this class become generally visible until so much time has el
to confer on them a high relative antiquity. Extensive den
must also combine with upheaval before they can be displaye
surface throughout wide areas.

All geologists who reflect on subterranean movements now going
n, and the eruptions of active volcanos, are convinced that great
ianges are now continually in progress in the interior of the earth's
rust far out of sight. They must be conscious, therefore, that the
iaccessibility of the regions in which these alterations are taking
lace, compels them to remain in ignorance of a great part of the
orking of existing causes, so that they can only form vague con-
ctures in regard to the nature of the products which volcanic heat
iay elaborate under great pressure.

But when they find in mountain-chains of high antiquity, that
hat was once the interior of the earth's crust has since been forced
utwards and exposed to view, they will naturally expect in the
xamination of those mountainous regions, to have an opportunity
f gratifying their curiosity by obtaining a sight not only of the
uperficial strata of remote eras, but also of the contemporaneous
ether-formed rocks. Having recognized, therefore, in such mountain-
hains some ancient rocks of aqueous and volcanic origin, correspond-
ng in character to superficial formations of modern date, they will
egard any other class of ancient rocks, such as granite and gneiss, as
he *residual phenomena* of which they are in search. These latter
ocks will not answer the expectations previously formed of their
robable nature and texture, unless they wear a foreign and mys-
erious aspect, and have in some places been fused or altered by
ubterranean heat; in a word, unless they differ wholly from the
ossiliferous strata deposited at the surface, or from the lava and
coriæ thrown out by volcanos in the open air. It is the total
listinctness, therefore, of crystalline formations, such as granite,
ornblende-schist, and the rest, from every substance of which the
rigin is familiar to us, that constitutes their claim to be regarded as
the effects of causes now in action in the subterranean regions.
They belong not to an order of things which has passed away; they
are not the monuments of a primeval period, bearing inscribed upon
them in obsolete characters the words and phrases of a dead language;
but they teach us that part of the living language of nature, which
we cannot learn by our daily intercourse with what passes on the
habitable surface.

CHAPTER XIII.

UNIFORMITY IN THE SERIES OF PAST CHANGES IN TH AND INANIMATE WORLD.

Supposed alternate periods of repose and disorder—Observed fa doctrine has originated—These may be explained by supposin uninterrupted series of changes—Threefold consideration of this reference to the living creation, extinction of species, and origi and plants; secondly, in reference to the changes produced in th the continuance of subterranean movements in certain areas, and after long periods to new areas; thirdly, in reference to govern the formation of fossiliferous strata, and the shifting of the tary deposition—On the combined influence of all these m of change in producing breaks and chasms in the chain of record remarks on the identity of the ancient and present system of ter

Origin of the doctrine of alternate periods of repose —It has been truly observed, that when we arrange the formations in chronological order, they constitute a defective series of monuments: we pass without any gradations, from systems of strata which are horizon systems which are highly inclined, from rocks of pecu composition to others which have a character wholly dis one assemblage of organic remains to another, in whic all the species, and most of the genera, are diffe violations of continuity are so common, as to constit rather than the exception, and they have been conside geologists as conclusive in favour of sudden revolu inanimate and animate world. According to the sp some writers, there have been in the past history o alternate periods of tranquillity and convulsion, the for for ages, and resembling that state of things now ex man: the other brief, transient, and paroxysmal, giving mountains, seas, and valleys, annihilating one set of or and ushering in the creation of another.

It will be the object of the present chapter to dem these theoretical views are not borne out by a fair inte geological monuments. It is true that in the solid fram globe, we have a chronological chain of natural reco many links in this chain are wanting; but a careful co all the phenomena will lead to the opinion that th originally defective,—that it has been rendered still time—that a great part of what remains is inaccessibl even of that fraction which is accessible, nine tenths a unexplored.

How the facts may be explained by assuming a uniform series of hanges.—The readiest way, perhaps, of persuading the reader that e may dispense with great and sudden revolutions in the geological rder of events, is by showing him how a regular and uninterrupted ries of changes in the animate and inanimate world, may give rise such breaks in the sequence, and such unconformability of stratified cks, as are usually thought to imply convulsions and catastrophes. is scarcely necessary to state, that the order of events thus assumed occur, for the sake of illustration, must be in harmony with all the nclusions legitimately drawn by geologists from the structure of the rth, and must be equally in accordance with the changes observed man to be now going on in the living as well as in the inorganic eation. It may be necessary in the present state of science to pply some part of the assumed course of nature hypothetically; but so, this must be done without any violation of probability, and ways consistently with the analogy of what is known both of the st and present economy of our system. Although the discussion of comprehensive a subject must carry the beginner far beyond his pth, it will also, it is hoped, stimulate his curiosity, and prepare n to read some elementary treatises on geology with advantage, d teach him the bearing on that science of the changes now in gress on the earth. At the same time it may enable him the ter to understand the intimate connexion between the second and rd books of this work, the former of which is occupied with the nges of the inorganic, the latter with those of the organic creation.

n pursuance, then, of the plan above proposed, I shall consider in chapter, first, what may be the course of fluctuation in the mate world; secondly, the mode in which contemporaneous subanean movements affect the earth's crust; and, thirdly, the laws ich regulate the deposition of sediment.

IFORMITY OF CHANGE CONSIDERED FIRST IN REFERENCE TO THE LIVING CREATION.

irst, in regard to the vicissitudes of the living creation, all are eed that the sedimentary strata found in the earth's crust are isible into a variety of groups, more or less dissimilar in their anic remains and mineral composition. The conclusion universally wn from the study and comparison of these fossiliferous groups is , that at successive periods, distinct tribes of animals and plants e inhabited the land and waters, and that the organic types of the rer formations are more analogous to species now existing, than se of more ancient rocks. If we then turn to the present state he animate creation, and inquire whether it has now become fixed stationary, we discover that, on the contrary, it is in a state of tinual flux—that there are many causes in action which tend the extinction of species, and which are conclusive against the trine of their unlimited durability. But natural history has n successfully cultivated for so short a period, that a few examples only of local, and perhaps but one or two of absolute, extirpation can as yet be proved, and these only where the interference of man has been conspicuous. It will nevertheless appear evident, from the facts and arguments detailed in the third book (from the thirty-seventh to the forty-second chapters inclusive) that man is not the only exterminating agent; and that, independently of his intervention, the annihilation of species is promoted by the multiplication and gradual diffusion of every animal or plant. It will also appear, that every alteration in the physical geography and climate of the globe cannot fail to have the same tendency. If we proceed still farther, and inquire whether new species are substituted from time to time for those which die out, and whether there are certain laws appointed by the Author of Nature to regulate such new creations, we find that the period of human observation is as yet too short to afford data for determining so weighty a question. All that can be done is to show, that the successive introduction of new species may be a constant part of the economy of the terrestrial system, without our having any right to expect that we should be in possession of direct proof of the fact. The appearance again and again of new species may easily have escaped detection, since the numbers of known animals and plants have augmented so rapidly within the memory of persons now living as to have doubled in some classes, and quadrupled in others. It will also be remarked in the sequel (book iii. chap. 43.), that it must always be more easy if species proceeded originally from single stocks, to prove that one which formerly abounded in a given distric has ceased to be, than that another has been called into being fo the first time. If, therefore, there be as yet only one or two unequivocal instances of extinction, namely, those of the dodo and solitair (see ch. 41.), it is scarcely reasonable as yet to hope that we shoul be cognizant of a single instance of the first appearance of a ne species.

Recent origin of man, and gradual approach in the tertiary fossi of successive periods from an extinct to the recent fauna.—Th geologist, however, if required to advance some fact which ma lend countenance to the opinion that in the most modern times, th is to say, after the greater part of the existing fauna and flora we established on the earth, there has still been a new species superadde may point to man himself as furnishing the required illustration, for man must be regarded by the geologist as a creature of yesterd not merely in reference to the past history of the organic wor but also in relation to that particular state of the animate creation which he forms a part. The comparatively modern introduction the human race is proved by the absence of the remains of man a his works, not only from all strata containing a certain proportion fossil shells of extinct species, but even from a large part of t newest strata, in which all the fossil individuals are referable species still living.

To enable the reader to appreciate the full force of this eviden I shall give a slight sketch of the information obtained from strata, respecting fluctuations in the animate world in times liately antecedent to the appearance of man.

tracing the series of fossiliferous formations from the more t to the more modern, the first deposits in which we meet with blages of organic remains, having a near analogy to the fauna tain parts of the globe in our own time, are those commonly tertiary. Even in the Eocene, or oldest subdivision of these y formations, some few of the testacea belong to existing s, although almost all of them, and apparently all the associated rata, are now extinct. These Eocene strata are succeeded by it number of more modern deposits, which depart gradually in aracter of their fossils from the Eocene type, and approach and more to that of the living creation. In the present state of e, it is chiefly by the aid of shells that we are enabled to arrive se results, for of all classes the testacea are the most generally d in a fossil state, and may be called the medals principally yed by nature, in recording the chronology of past events. In liocene deposits, which are next in succession to the Eocene, gin to find a considerable number, although still a minority, of species, intermixed with some fossils common to the preceding . We then arrive at the Pliocene strata, in which species now nporary with man begin to preponderate, and in the newest of nine tenths of the fossils agree with species still inhabiting the bouring sea.

thus passing from the older to the newer members of the ry system we meet with many chasms, but none which separate ly, by a broad line of demarcation, one state of the organic from another. There are no signs of an abrupt termination of auna and flora, and the starting into life of new and wholly ct forms. Although we are far from being able to demonstrate gically an insensible transition from the Eocene to the Miocene, n from the latter to the recent fauna, yet the more we enlarge erfect our general survey, the more nearly do we approximate h a continuous series, and the more gradually are we conducted times when many of the genera and nearly all the species were t, to those in which scarcely a single species flourished which not know to exist at present. Dr. A. Philippi, indeed, after an ate comparison of the fossil tertiary shells of Sicily with those iving in the Mediterranean, announces as the result of his extion that there are strata in that island, which attest a very al passage from a period, when only thirteen in a hundred of hells were like the species now living in the sea, to an era the recent species had attained a proportion of ninety-five in dred. There is therefore evidence, he says, in Sicily of this ition in the animate world having been effected "without the ention of any convulsion or abrupt changes, certain species g from time to time died out, and others having been introduced, at length the existing fauna was elaborated."

had often been objected that the evidence of fossil species occurring in two consecutive formations, was confined to the testacea or zoophytes, the characters of which are less marked and decisive than those afforded by the vertebrate animals. But Mr. Owen has lately insisted on the important fact, that not a few of the quadrupeds which now inhabit our island, and among others the horse, the ass, the hog, the smaller wild ox, the goat, the red deer, the roe, the beaver, and many of the diminutive rodents, are the same as those which once co-existed with the mammoth, the great northern hippopotamus, two kinds of rhinoceros, and other mammalia long since extinct. "A part," he observes, "and not the whole of the modern tertiary fauna has perished, and hence we may conclude that the cause of their destruction has not been a violent and universal catastrophe from which none could escape."*

Had we discovered evidence that man had come into the earth at a period as early as that when a large number of the fossil quadrupeds now living, and almost all the recent species of land, freshwater, and marine shells were in existence, we should have been compelled to ascribe a much higher antiquity to our species, than even the boldest speculations of the ethnologist require, for no small part of the great physical revolution depicted on the map of Europe (Pl. 3.) before described, took place very gradually after the recent testacea abounded almost to the exclusion of the extinct. Thus, for example, in the deposits called the "northern drift," or the glacial formation of Europe and North America, the fossil marine shells can easily be identified with species either now inhabiting the neighbouring sea, or living in the seas of higher latitudes. Yet they exhibit no memorials of the human race, or of articles fabricated by the hand of man. Some of the newest of these strata passing by the name of "raised beaches," occur at moderate elevations on the coast of England, Scotland, and Ireland. Other examples are met with on a more extended scale in Scandinavia, as at the height of 200 feet at Uddevalla in Sweden, and at twice that elevation, near Christiania, in Norway, also at an altitude of 600 or 700 feet in places farther north. They consist of beds of sand and clay, filling hollows in a district of granite and gneiss, and they must closely resemble the accumulations of shelly matter now in progress at the bottom of the Norwegian fiords. The rate at which the land is now rising in Scandinavia, is far too irregular in different places to afford a saf

---

* Reports to Brit. Assoc. 1842, 1843, and Introd. to Brit. Foss. Mamm. p. 31. The conchological evidence respecting the British Miocene, Pliocene, and Pleistocene fossils, examined by Mr. Forbes, in the paper before cited, p. 88. note, bear out some of the most important conclusions of M. Deshayes, quoted by me in the first edition of the Principles, 1831, and the recent observations of Philippi in regard to the passage of species from one formation to another. I refer to these authorities more especially because this doctrine of a gradual transition has been opposed by some living naturalists of high distinction, amon whom I may mention M. A. d'Orbign and M. Agassiz. I have long been convinced that we must abandon many c the identifications formerly made c Eocene with recent shells; but som errors of this kind do not affect the g neral reasoning on the subject. See discussion on this question, Quarterl Journ. of Geog. Soc., No. 5. p. 47., Fe 1846.

l for estimating the minimum of time required for the up-
f the fundamental granite, and its marine shelly covering, to
ht of so many hundred feet; but according to the greatest
, of five or six feet in a century, the period required would be
isiderable, and nearly the whole of it, as well as the ante-
poch of submergence, seems to have preceded the introduction
into these parts of the earth.

; are other post-tertiary formations of fluviatile origin, in the
f Europe, in which the absence of human remains is perhaps
re striking, because, when formed, they must have been
led by dry land. I allude to the silt or *loess* of the basin of
ne, which must have gradually filled up the great valley of
er since the time when its waters, and the contiguous lands,
abited by the existing species of freshwater and terrestrial
s. Showers of ashes, thrown out by some of the last erup-
the Eifel volcanos, fell during the deposition of this fluviatile
l were interstratified with it. But these volcanos became
ed, the valley was re-excavated through the silt, and again
to its present form before the period of human history. The
herefore, of this shelly silt reveals to us the history of a long
f events, which occurred after the testacea now living inha-
e land and rivers of Europe, and the whole terminated with-
signs of the coming of man into that part of the globe.

te a still more remarkable example, we observe in Sicily a
le-land and hills, sometimes rising to the height of 3000 feet,
with a limestone, in which from 70 to 85 per cent. of the
stacea are specifically identical with those now inhabiting the
ranean. These calcareous and other argillaceous strata of
e age are intersected by deep valleys which have been gradu-
ned by denudation, but have not varied materially in width
h since Sicily was first colonized by the Greeks. The lime-
ioreover, which is of so late a date in geological chronology,
arried for building those ancient temples of Girgenti and
e, of which the ruins carry us back to a remote era in human
If we are lost in conjectures when speculating on the ages
l to lift up these formations to the height of several thousand
ve the sea, how much more remote must be the era when the
cks were gradually formed beneath the waters!

nclude, it appears that, in going back from the recent to the
period, we are carried by many successive steps from the
ow contemporary with man to an assemblage of fossil species
different from those now living. In this retrospect we have
succeeded in tracing back a perfect transition from the
o an extinct fauna; but there are usually so many species in
to the groups which stand next in succession as to show
re is no great chasm, no signs of a crisis when one class of
beings was annihilated to give place suddenly to another.
alogy, therefore, derived from a period of the earth's history
an best be compared with the present state of things, and

more thoroughly investigated than any other, leads to the conclusion that the extinction and creation of species, has been and is the result of a slow and gradual change in the organic world.

UNIFORMITY OF CHANGE CONSIDERED, SECONDLY, IN REFERENCE TO SUBTERRANEAN MOVEMENTS.

To pass on to another of the three topics before proposed for discussion, the reader will find, in the account given in the second book of the earthquakes recorded in history, that certain countries have from time immemorial, been rudely shaken again and again, whil others, comprising by far the largest part of the globe, have remaine to all appearance motionless. In the regions of convulsion rock have been rent asunder, the surface has been forced up into ridge chasms have opened, or the ground throughout large spaces has bee permanently lifted up above or let down below its former level. I the regions of tranquillity some areas have remained at rest, bu others have been ascertained by a comparison of measurements, mad at different periods, to have risen by an insensible motion, as i Sweden, or to have subsided very slowly, as in Greenland. Tha these same movements, whether ascending or descending, have continued for ages in the same direction has been established by geological evidence. Thus, we find both on the east and west coast o Sweden, that ground which formerly constituted the bottom of th Baltic and of the ocean has been lifted up to an elevation of severa hundred feet above high-water mark. The rise within the historica period has not amounted to many yards, but the greater extent o antecedent upheaval is proved by the occurrence in inland spot several hundred feet high, of deposits filled with fossil shells of specie now living either in the ocean or the Baltic.

To detect proofs of slow and gradual subsidence must in genera be more difficult; but the theory which accounts for the form o circular coral reefs and lagoon islands, and which will be explaine in the last chapter of the third book, will satisfy the reader that ther are spaces on the globe, several thousand miles in circumferenc throughout which the downward movement has predominated fo ages, and yet the land has never, in a single instance, gone dow suddenly for several hundred feet at once. Yet geology demonstrate that the persistency of subterranean movements in one direction ha not been perpetual throughout all past time. There have been gre oscillations of level by which a surface of dry land has been submerged to a depth of several thousand feet, and then at a period lon subsequent raised again and made to emerge. Nor have the regio now motionless been always at rest; and some of those which are present the theatres of reiterated earthquakes have formerly enjoye a long continuance of tranquillity. But although disturbances hav ceased after having long prevailed, or have recommenced after suspension for ages, there has been no universal disruption of t earth's crust or desolation of the surface since times the most remot

The non-occurrence of such a general convulsion is proved by the perfect horizontality now retained by some of the most ancient fossiliferous strata throughout wide areas.

Inferences derived from unconformable strata.—That the subterranean forces have visited different parts of the globe at successive periods, is inferred chiefly from the unconformability of strata belonging to groups of different ages. Thus, for example, on the borders of Wales and Shropshire we find the slaty beds of the ancient Silurian system curved and vertical, while the beds of the overlying carboniferous shale and sandstone are horizontal. All are agreed, that in such a case the older set of strata had suffered great dislocation before the deposition of the newer or carboniferous beds, and that these last have never since been convulsed by any movements of excessive violence. But the strata of the inferior group suffered only a local derangement, and rocks of the same age are by no means found every where in a curved or vertical position. In various parts of Europe, and particularly near Lake Wener in the south of Sweden, and in many parts of Russia, beds of the same Silurian system maintain the most perfect horizontality; and a similar observation may be made respecting limestones and shales of the like antiquity in the great lake district of Canada and the United States. They are still as flat and horizontal as when first formed; yet since their origin not only have most of the actual mountain-chains been uplifted, but the very rocks of which those mountains are composed have been formed.

It would be easy to multiply instances of similar unconformability in formations of other ages; but a few more will suffice. The Coal-measures before alluded to as horizontal on the borders of Wales are vertical in the Mendip Hills in Somersetshire, where the overlying beds of the New Red Sandstone are horizontal. Again, in the Wolds of Yorkshire the last mentioned sandstone supports on its curved and inclined beds the horizontal Chalk. The Chalk again is vertical on the flanks of the Pyrenees, and the tertiary strata repose unconformably upon it.

Consistency of local disturbances with general uniformity.—As almost every country supplies illustrations of the same phenomena, they who advocate the doctrine of alternate periods of disorder and repose may appeal to the facts above described, as proving that every district has been by turns convulsed by earthquakes and then respited for ages from convulsions. But so it might with equal truth be affirmed that every part of Europe has been visited alternately by winter and summer, although it has always been winter and always summer in some part of the planet, and neither of these seasons has ever reigned simultaneously over the entire globe. They have been always shifting about from place to place; but the vicissitudes which recur thus annually in a single spot are never allowed to interfere with the invariable uniformity of seasons throughout the whole planet.

So, in regard to subterranean movements,
perpetual uniformity of the force which they

crust is quite consistent with the admission of their alternate development and suspension for indefinite periods within limited geographical areas.

UNIFORMITY OF CHANGE CONSIDERED, THIRDLY, IN REFERENCE TO SEDIMENTARY DEPOSITION.

It now remains to speak of the laws governing the deposition of new strata. If we survey the surface of the globe we immediately perceive that it is divisible into areas of deposition and non-deposition, or, in other words, at any given time there are spaces which are the recipients, others which are not the recipients of sedimentary matter. No new strata, for example, are thrown down on dry land, which remains the same from year to year; whereas, in many parts of the bottom of seas and lakes, mud, sand, and pebbles are annually spread out by rivers and currents. There are also great masses of limestone growing in some seas, or in mid ocean, chiefly composed of corals and shells.

No sediment deposited on dry land.—As to the dry land, so far from being the receptacle of fresh accessions of matter, it is exposed almost every where to waste away. Forests may be as dense and lofty as those of Brazil, and may swarm with quadrupeds, birds, and insects, yet at the end of ten thousand years one layer of black mould, a few inches thick, may be the sole representative of those myriads of trees, leaves, flowers, and fruits, those innumerable bones and skeletons of birds, quadrupeds, and reptiles, which tenanted the fertile region. Should this land be at length submerged, the waves of the sea may wash away in a few hours the scanty covering of mould, and it may merely impart a darker shade of colour to the next stratum of marl, sand, or other matter newly thrown down. So also at the bottom of the ocean where no sediment is accumulating, sea-weed, zoophytes, fish, and even shells, may multiply for ages and decompose, leaving no vestige of their form or substance behind. Their decay, in water, although more slow, is as certain and eventually as complete as in the open air. Nor can they be perpetuated for indefinite periods in a fossil state, unless imbedded in some matrix which is impervious to water, or which at least does not allow a free percolation of that fluid, impregnated as it usually is, with a slight quantity of carbonic or other acid. Such a free percolation may be prevented either by the mineral nature of the matrix itself, or by the superposition of an impermeable stratum: but if unimpeded the fossil shell or bone will be dissolved and removed, particle after particle, and thus entirely effaced, unless petrifaction or the substitution of mineral for organic matter happen to take place.

That there has been land as well as sea at all former geological periods, we know from the fact, that fossil trees and terrestrial plants are imbedded in rocks of every age. Occasionally lacustrine and fluviatile shells, insects, or the bones of amphibious or land reptiles, point to the same conclusion. The existence of dry land at all periods of the past implies, as before mentioned, the partial deposition of sediment, or its limitation to certain areas; and the next point to which I shall call the reader's attention, is the shifting of these areas from one region to another.

First, then, variations in the site of sedimentary deposition are brought about independently of subterranean movements. There is always a slight change from year to year, or from century to century. The sediment of the Rhone, for example, thrown into the Lake of Geneva, is now conveyed to a spot a mile and a half distant from that where it accumulated in the tenth century, and six miles from the point where the delta began originally to form. We may look forward to the period when this lake will be filled up, and then the distribution of the transported matter will be suddenly altered, for the mud and sand brought down from the Alps will thenceforth, instead of being deposited near Geneva, be carried nearly 200 miles southwards, where the Rhone enters the Mediterranean.

In the deltas of large rivers, such as those of the Ganges and Indus, the mud is first carried down for many centuries through one arm, and on this being stopped up it is discharged by another, and may then enter the sea at a point 50 or 100 miles distant from its first receptacle. The direction of marine currents is also liable to be changed by various accidents, as by the heaping up of new sand banks, or the wearing away of cliffs and promontories.

But, secondly, all these causes of fluctuation in the sedimentary areas are entirely subordinate to those great upward or downward movements of land which have been already described as prevailing over large tracts of the globe. By such elevation or subsidence certain spaces are gradually submerged, or made gradually to emerge:—in the one case sedimentary deposition may be suddenly renewed after having been suspended for ages, in the other as suddenly made to cease after having continued for an indefinite period.

Causes of variation in mineral character of successive sedimentary groups.—If deposition be renewed after a long interval, the new strata will usually differ greatly from the sedimentary rocks previously formed in the same place, and especially if the older rocks have suffered derangement, which implies a change in the physical geography of the district since the previous conveyance of sediment to the same spot. It may happen, however, that, even when the inferior group is horizontal and conformable to the upper strata, these last may still differ entirely in mineral character, because since the origin of the older formation the geography of some distant country has been altered. In that country rocks before concealed may have become exposed by denudation; volcanos may have burst out and covered the surface with scoriæ and lava, or new lakes may have been formed by subsidence; and other fluctuations may have occurred, by which the materials brought down from thence by rivers to the sea have acquired a distinct mineral character.

It is well known that the stream of the Mississippi is charged with sediment of a different colour from that of the Arkansas and Red Rivers, which are tinged with red mud, derived from rocks of porphyry in "the far west." The waters of the Uruguay, says Darwin, draining a granitic country, are clear and black, those of the Parana, red.* The mud with which the Indus is loaded, says Burnes, is of a clayey hue, that of the Chenab, on the other hand, is reddish, that of the Sutlej is more pale.† The same causes which make these several rivers, sometimes situated at no great distance the one from the other, to differ greatly in the character of their sediment, will make the waters draining the same country at different epochs, especially before and after great revolutions in physical geography, to be entirely dissimilar. It is scarcely necessary to add, that marine currents will be affected in an analogous manner in consequence of the formation of new shoals, the emergence of new islands, the subsidence of others, the gradual waste of neighbouring coasts, the growth of new deltas, the increase of coral reefs, and other changes.

Why successive sedimentary groups contain distinct fossils.—If, in the next place, we assume, for reasons before stated, a continual extinction of species and introduction of others into the globe, it will then follow that the fossils of strata formed at two distant periods on the same spot, will differ even more certainly than the mineral composition of the same. For rocks of the same kind have sometimes been reproduced in the same district after a long interval of time, whereas there are no facts leading to the opinion that species which have once died out have ever been reproduced. The submergence then of land must be often attended by the commencement of a new class of sedimentary deposits, characterized by a new set of fossil animals and plants, while the reconversion of the bed of the sea into land may arrest at once and for an indefinite time the formation of geological monuments. Should the land again sink, strata will again be formed; but one or many entire revolutions in animal or vegetable life may have been completed in the interval.

Conditions requisite for the original completeness of a fossiliferous series.—If we infer, for reasons before explained, that fluctuations in the animate world are brought about by the slow and successive removal and creation of species, we shall be convinced that a rare combination of circumstances alone can give rise to such a series of strata as will bear testimony to a gradual passage from one state of organic life to another. To produce such strata nothing less will be requisite than the fortunate coincidence of the following conditions: first, a never-failing supply of sediment in the same region throughout a period of vast duration; secondly, the fitness of the deposit in every part for the permanent preservation of imbedded fossils; and, thirdly, a gradual subsidence to prevent the sea or lake from being filled up and converted into land.

---

* Darwin's Journal, p. 163. 2d ed. p. 139.

† Journ. Roy. Geograph. Soc. vol. iii. p. 142.

It will appear in the chapter on coral reefs*, that, in certain parts of the Pacific and Indian Oceans, most of these conditions, if not all, are complied with, and the constant growth of coral, keeping pace with the sinking of the bottom of the sea, seems to have gone on so slowly, for such indefinite periods, that the signs of a gradual change in organic life might probably be detected in that quarter of the globe, if we could explore its submarine geology. Instead of the growth of coralline limestone, let us suppose, in some other place, the continuous deposition of fluviatile mud and sand, such as the Ganges and Brahmapootra have poured for thousands of years into the Bay of Bengal. Part of this bay, although of considerable depth, might at length be filled up before an appreciable amount of change was effected in the fish, mollusca, and other inhabitants of the sea and neighbouring land. But, if the bottom be lowered by sinking at the same rate that it is raised by fluviatile mud, the bay can never be turned into dry land. In that case one new layer of matter may be superimposed upon another for a thickness of many thousand feet, and the fossils of the inferior beds may differ greatly from those entombed in the uppermost, yet every intermediate gradation may be indicated in the passage from an older to a newer assemblage of species. Granting, however, that such an unbroken sequence of monuments may thus be elaborated in certain parts of the sea, and that the strata happen to be all of them well adapted to preserve the included fossils from decomposition, how many accidents must still concur before these submarine formations will be laid open to our investigation! The whole deposit must first be raised several thousand feet, in order to bring into view the very foundation; and during the process of exposure the superior beds must not be entirely swept away by denudation.

In the first place, the chances are as three to one against the mere emergence of the mass above the waters, because three fourths of the globe are covered by the ocean. But if it be upheaved and made to constitute part of the dry land, it must also, before it can be available for our instruction, become part of that area already surveyed by geologists; and this area comprehends perhaps less than a tenth of the whole earth. In this small fraction of land already explored, and still very imperfectly known, we are required to find a set of strata, originally of limited extent, and probably much lessened by subsequent denudation.

Yet it is precisely because we do not encounter at every step the evidence of such gradations from one state of the organic world to another, that so many geologists embrace the doctrine of great and sudden revolutions in the history of the animate world. Not content with simply availing themselves, for the convenience of classification, of those gaps and chasms which here and there interrupt the continuity of the chronological series, as at present known, they deduce, from the frequency of these breaks in the chain of records, an irregular mode of succession in the events themselves both in the organic and inorganic world. But, besides that some links of the chain which once existed are now clearly lost and others concealed from view, we have good reason to suspect that it was never complete originally. It may undoubtedly be said, that strata have been always forming somewhere, and therefore at every moment of past time nature has added a page to her archives; but, in reference to this subject, it should be remembered that we can never hope to compile a consecutive history by gathering together monuments which were originally detached and scattered over the globe. For as the species of organic beings contemporaneously inhabiting remote regions are distinct, the fossils of the first of several periods which may be preserved in any one country, as in America, for example, will have no connection with those of a second period found in India, and will therefore no more enable us to trace the signs of a gradual change in the living creation, than a fragment of Chinese history will fill up a blank in the political annals of Europe.

---

* Book iii. ch. 50.

The absence of any deposits of importance containing recent shells in Chili, or any where on the western coast of South America, naturally led Mr. Darwin to the conclusion that "where the bed of the sea is either stationary or rising, circumstances are far less favourable than where the level is sinking to the accumulation of conchiferous strata of sufficient thickness and extension to resist the average vast amount of denudation."* An examination of the superficial clay, sand, and gravel of the most modern date in Norway and Sweden, where the land is also rising, would incline us to admit a similar proposition. Yet in these cases there has been a supply of sediment from the waste of the coast and the interior, especially in Patagonia and Chili. Nevertheless wherever the bottom of the sea has been continually elevated, the total thickness of sedimentary matter accumulating at depths suited to the habitation of most of the species of shells can never be great, nor can the deposits be thickly covered by superincumbent matter, so as to be consolidated by pressure. When they are upheaved, therefore, the waves on the beach will bear down and disperse the loose materials; whereas if the bed of the sea subsides slowly, a mass of strata containing abundance of such species as live at moderate depths may increase in thickness to any amount, and may extend over a broad area, as the water gradually encroaches on the land. If then at particular periods, as in the Miocene epoch, for example, both in Europe and North America, contemporaneous shelly deposits have originated and have been preserved at very distant points, it may arise from the prevalence at that period of simultaneous subsidence throughout very wide areas. The absence in the same quarters of the globe of strata marking the ages which immediately succeeded, may be accounted for by supposing that the level of the bed of the sea and the adjoining land was stationary or was undergoing slow upheaval.

---

* Darwin's S. America, pp. 136. 139.

How far some of the great violations of continuity which now exist in the chronological table of fossiliferous rocks, will hereafter be removed or lessened, must at present be mere matter of conjecture. The hiatus which exists in Great Britain between the fossils of the Lias and those of the Magnesian Limestone, is supplied in Germany by the rich fauna and flora of the Muschelkalk, Keuper, and Bunter Sandstein, which we know to be of a date precisely intermediate; those three formations being interposed in Germany between others which agree perfectly in their organic remains with our Lias and Magnesian Limestone. Until lately the fossils of the Coal-measures were separated from those of the antecedent Silurian group by a very abrupt and decided line of demarcation; but recent discoveries have brought to light in Devonshire, Belgium, the Eifel, and Westphalia, the remains of a fauna of an intervening period. This connecting link is furnished by the fossil shells, fish, and corals of the Devonian or Old Red Sandstone group, and some species of this newly intercalated fauna are found to be common to it and the subjacent Silurian rocks, while other species belong to it in common with the Coal-measures. We have also in like manner had some success of late years in diminishing the hiatus which still separates the Cretaceous and Eocene periods in Europe. Still we must expect, for reasons before stated, that some such chasms will for ever continue to occur in some parts of our sedimentary series.

Consistency of the theory of gradual change, with the existence of great breaks in the series. — To return to the general argument pursued in this chapter, it is assumed, for reasons above explained, that a slow change of species is in simultaneous operation everywhere throughout the habitable surface of sea and land; whereas the fossilization of plants and animals is confined to those areas where new strata are produced. These areas, as we have seen, are always shifting their position; so that the fossilizing process, by means of which the commemoration of the particular state of the organic world, at any given time, is affected, may be said to move about, visiting and revisiting different tracts in succession.

To make still more clear the supposed working of this machinery, I shall compare it to a somewhat analogous case that might be imagined to occur in the history of human affairs. Let the mortality of the population of a large country represent the successive extinction of species, and the births of new individuals the introduction of new species. While these fluctuations are gradually taking place every where, suppose commissioners to be appointed to visit each province of the country in succession, taking an exact account of the number, names, and individual peculiarities of all the inhabitants, and leaving in each district a register containing a record of this information. If, after the completion of one census, another is immediately made on the same plan, and then another, there will, at last, be a series of statistical documents in each province. When those belonging to any one province are arranged in chronological order, the contents of such as stand next to each other will differ according to the length of the intervals of time between the taking of each census. If, for example, there are sixty provinces, and all the registers are made in a single year and renewed annually, the number of births and deaths will be so small, in proportion to the whole of the inhabitants, during the interval between the compiling of two consecutive documents, that the individuals described in such documents will be nearly identical; whereas, if the survey of each of the sixty provinces occupies all the commissioners for a whole year, so that they are unable to revisit the same place until the expiration of sixty years, there will then be an almost entire discordance between the persons enumerated in two consecutive registers in the same province. There are, undoubtedly, other causes besides the mere quantity of time, which may augment or diminish the amount of discrepancy. Thus, at some periods a pestilential disease may have lessened the average duration of human life, or a variety of circumstances may have caused the births to be unusually numerous, and the population to multiply; or, a province may be suddenly colonized by persons migrating from surrounding districts.

These exceptions may be compared to the accelerated rate of fluctuation in the fauna and flora of a particular region, in which the climate and physical geography may be undergoing an extraordinary degree of alteration.

But I must remind the reader, that the case above proposed has no pretensions to be regarded as an exact parallel to the geological phenomena which I desire to illustrate; for the commissioners are supposed to visit the different provinces in rotation; whereas the commemorating processes by which organic remains become fossilized, although they are always shifting from one area to the other, are yet very irregular in their movements. They may abandon and revisit many spaces again and again, before they once approach another district; and, besides this source of irregularity, it may often happen that, while the depositing process is suspended, denudation may take place, which may be compared to the occasional destruction by fire or other causes of some of the statistical documents before mentioned. It is evident that, where such accidents occur, the want of continuity in the series may become indefinitely great, and that the monuments which follow next in succession will by no means be equidistant from each other in point of time.

If this train of reasoning be admitted, the occasional distinctness of the fossil remains, in formations immediately in contact, would be a necessary consequence of the existing laws of sedimentary deposition and subterranean movement, accompanied by a constant mortality and renovation of species.

As all the conclusions above insisted on are directly opposed to opinions still popular, I shall add another comparison, in the hope of preventing any possible misapprehension of the argument. Suppose we had discovered two buried cities at the foot of Vesuvius, immediately superimposed upon each other, with a great mass of tuff and lava intervening, just as Portici and Resina, if now covered with ashes, would overlie Herculaneum. An antiquary might possibly be entitled to infer, from the inscriptions on public edifices, that the inhabitants of the inferior and older city were Greeks, and those of the modern towns Italians. But he would reason very hastily if he also concluded from these data, that there had been a sudden change from the Greek to the Italian language in Campania. But if he afterwards found *three* buried cities, one above the other, the intermediate one being Roman, while, as in the former example, the lowest was Greek and the uppermost Italian, he would then perceive the fallacy of his former opinion, and would begin to suspect that the catastrophes, by which the cities were inhumed, might have no relation whatever to the fluctuations in the language of the inhabitants: and that, as the Roman tongue had evidently intervened between the Greek and Italian, so many other dialects may have been spoken in succession, and the passage from the Greek to the Italian may have been very gradual; some terms growing obsolete, while others were introduced from time to time.

If this antiquary could have shown that the volcanic paroxysms of Vesuvius were so governed as that cities should be buried one above the other, just as often as any variation occurred in the language of the inhabitants, then, indeed, the abrupt passage from a Greek to a Roman, and from a Roman to an Italian city, would afford proof of fluctuations no less sudden in the language of the people.

So, in Geology, if we could assume that it is part of the plan of Nature to preserve, in every region of the globe, an unbroken series of monuments to commemorate the vicissitudes of the organic creation, we might infer the sudden extirpation of species, and the simultaneous introduction of others, as often as two formations in contact are found to include dissimilar organic fossils. But we must shut our eyes to the whole economy of the existing causes, aqueous, igneous, and organic, if we fail to perceive *that such is not the plan of Nature.*

Concluding remarks on the identity of the ancient and present system of terrestrial changes.—I shall now conclude the discussion of a question with which we have been occupied since the beginning of the fifth chapter; namely, whether there has been any interruption, from the remotest periods, of one uniform system of change in the animate and inanimate world. We were induced to enter into that inquiry by reflecting how much the progress of opinion in Geology had been influenced by the assumption that the analogy was slight in kind, and still more slight in degree, between the causes which produced the former revolutions of the globe, and those now in everyday operation. It appeared clear that the earlier geologists had not only a scanty acquaintance with existing changes, but were singularly unconscious of the amount of their ignorance. With the presumption naturally in[illegible]red by this unconsciousness, they had no hesitation in deciding at [illegible] t time could never enable the existing powers of nature to w[illegible] s of great magnitude, still less such important revolutions as those which are brought to light by Geolog They, therefore, felt themselves at liberty to indulge their imaginatio in guessing at what *might be*, rather than inquiring *what is*; in oth words, they employed themselves in conjecturing what might hav been the course of nature at a remote period, rather than in the investigation of what was the course of nature in their own times.

It appeared to them more philosophical to speculate on the possibilities of the past, than patiently to explore the realities of the present; and having invented theories under the influence of suc maxims, they were consistently unwilling to test their validity by th criterion of their accordance with the ordinary operations of nature On the contrary, the claims of each new hypothesis to credibility appeared enhanced by the great contrast, in kind or intensity, of the causes referred to and those now in operation.

Never was there a dogma more calculated to foster indolence, and to blunt the keen edge of curiosity, than this assumption of the discordance between the ancient and existing causes of change. It produced a state of mind unfavourable in the highest degree to the candid reception of the evidence of those minute but incessant alterations which every part of the earth's surface is undergoing, and by which the condition of its living inhabitants is continually made to vary. The student, instead of being encouraged with the hope of interpreting the enigmas presented to him in the earth's structure,—instead of being prompted to undertake laborious inquiries into the natural history of the organic world, and the complicated effects o the igneous and aqueous causes now in operation, was taught t despond from the first. Geology, it was affirmed, could never rise t the rank of an exact science,—the greater number of phenomen must for ever remain inexplicable, or only be partially elucidated b ingenious conjectures. Even the mystery which invested the subjec was said to constitute one of its principal charms, affording, as it did full scope to the fancy to indulge in a boundless field of speculation.

The course directly opposed to this method of philosophizing consists in an earnest and patient inquiry, how far geological appearance are reconcileable with the effect of changes now in progress, or whic may be in progress in regions inaccessible to us, and of which th reality is attested by volcanos and subterranean movements. It al endeavours to estimate the aggregate result of ordinary operatio multiplied by time, and cherishes a sanguine hope that the resourc to be derived from observation and experiment, or from the study nature such as she now is, are very far from being exhausted. F this reason all theories are rejected which involve the assumptio of sudden and violent catastrophes and revolutions of the whol earth, and its inhabitants,—theories which are restrained by no r ference to existing analogies, and in which a desire is manifested cut, rather than patiently to untie, the Gordian knot.

We have now, at least, the advantage of knowing, from experienc that an opposite method has always put geologists on the road th leads to truth,—suggesting views which, although imperfect at fir have been found capable of improvement, until at last adopted by universal consent; while the method of speculating on a former distinct state of things and causes, has led invariably to a multitude of contradictory systems, which have been overthrown one after the other,—have been found incapable of modification,—and which have often required to be precisely reversed.

The remainder of this work will be devoted to an investigation of the changes now going on in the crust of the earth and its inhabitants. The importance which the student will attach to such researches will mainly depend in the degree of confidence which he feels in the principles above expounded. If he firmly believes in the resemblance or identity of the ancient and present system of terrestrial changes, he will regard every fact collected respecting the causes in diurnal action as affording him a key to the interpretation of some mystery in the past. Events which have occurred at the most distant periods in the animate and inanimate world, will be acknowledged to throw light on each other, and the deficiency of our information respecting some of the most obscure parts of the present creation will be removed. For as, by studying the external configuration of the existing land and its inhabitants, we may restore in imagination the appearance of the ancient continents which have passed away, so may we obtain from the deposits of ancient seas and lakes an insight into the nature of the subaqueous processes now in operation, and of many forms of organic life, which, though now existing, are veiled from sight. Rocks, also, produced by subterranean fire in former ages, at great depths in the bowels of the earth, present us, when upraised by gradual movements, and exposed to the light of heaven, with an image of those changes which the deep-seated volcano may now occasion in the nether regions. Thus, although we are mere sojourners on the surface of the planet, chained to a mere point in space, enduring but for a moment of time, the human mind is not only enabled to number worlds beyond the unassisted ken of mortal eye, but to trace the events of indefinite ages before the creation of our race, and is not even withheld from penetrating into the dark secrets of the ocean, or the interior of the solid globe; free, like the spirit which the poet described as animating the universe,

——— ire per omnes
Terrasque, tractusque maris, cœlumque profundum.

BOOK II.

CHANGES IN THE INORGANIC WORLD.

AQUEOUS CAUSES.

CHAPTER XIV.

Division of the subject into changes of the organic and inorganic world — Inorganic causes of change divided into aqueous and igneous — Aqueous causes first considered — Fall of rain — Recent rain-prints in mud — Destroying and transporting power of running water — Newly formed valleys in Georgia — Sinuosities of rivers — Two streams when united do not occupy a bed of double surface — Inundations in Scotland — Floods caused by landslips in the White Mountains — Bursting of a lake in Switzerland — Devastations caused by the Anio at Tivoli — Excavations in the lavas of Etna by Sicilian rivers — Gorge of the Simeto — Gradual recession of the cataract of Niagara.

Division of the subject. — GEOLOGY was defined to be the science which investigates the former changes that have taken place in the organic as well as in the inorganic kingdoms of nature. As vicissitudes in the inorganic world are most apparent, and as on them all fluctuations in the animate creation must in a great measure depend, they may claim our first consideration. The great agents of change in the inorganic world may be divided into two principal classes, the aqueous and the igneous. To the aqueous belong Rain, Rivers, Torrents, Springs, Currents, and Tides; to the igneous, Volcanoes, and Earthquakes. Both these classes are instruments of decay as well as of reproduction; but they may also be regarded as antagonist forces. For the aqueous agents are incessantly labouring to reduce the inequalities of the earth's surface to a level; while the igneous are equally active in restoring the unevenness of the external crust, partly by heaping up new matter in certain localities, and partly by depressing one portion, and forcing out another, of the earth's envelope.

It is difficult, in a scientific arrangement, to give an accurate view of the combined effects of so many forces in simultaneous operation; because, when we consider them separately, we cannot easily estimate either the extent of their efficacy, or the kind of results which they produce. We are in danger, therefore, when we attempt to examine the influence exerted singly by each, of overlooking the modifications which they produce on one another; and these are so complicated, that sometimes the igneous and aqueous forces co-operate to produce a joint effect, to which neither of them unaided by the other could give rise,—as when repeated earthquakes unite with running water to widen a valley; or when a thermal spring rises up from a great depth, and conveys the mineral ingredients with which it is impregnated from the interior of the earth to the surface. Sometimes the organic combine with the inorganic causes; as when a reef, composed of shells and corals, protects one line of coast from the destroying power of tides or currents, and turns them against some other point; or when drift timber, floated into a lake, fills a hollow to which the stream would not have had sufficient velocity to convey earthy sediment.

It is necessary, however, to divide our observations on these various causes, and to classify them systematically, endeavouring as much as possible to keep in view that the effects in nature are mixed and not simple, as they may appear in an artificial arrangement.

In treating, in the first place, of the aqueous causes, we may consider them under two divisions; first, those which are connected with the circulation of water from the land to the sea, under which are included all the phenomena of rain, rivers, glaciers, and springs; secondly, those which arise from the movements of water in lakes, seas, and the ocean, wherein are comprised the phenomena of waves, tides, and currents. In turning our attention to the former division, we find that the effects of rivers may be subdivided into, first, those of a destroying and transporting, and, secondly, those of a renovating nature; in the former are included the erosion of rocks and the transportation of matter to lower levels; in the renovating class, the formation of deltas by the influx of sediment, and the shallowing of seas; but these processes are so intimately related to each other, that it will not always be possible to consider them under their separate heads.

Fall of rain.—It is well known that the capacity of the atmosphere to absorb aqueous vapour, and hold it in suspension, increases with every increment of temperature. This capacity is also found to augment in a higher ratio than the augmentation of the heat. Hence, as was first suggested by the geologist, Dr. Hutton, when two volumes of air, of different temperatures, both saturated with moisture, mingle together, clouds and rain are produced, for a mean degree of heat having resulted from the union of the two moist airs, the excess of vapour previously held in suspension by the warmer of the two is given out, and if it be in sufficient abundance is precipitated in the form of rain.

As the temperature of the atmosphere diminishes gradually from the equator towards the pole, the evaporation of water and the quantity of rain diminish also. According to Humboldt's computation, the average annual depth of rain at the equator is 96 inches, while in lat. 45° it is only 29 inches, and in lat. 60° not more than 17 inches. But there are so many disturbing causes, that the actual discharge, in any given [illegible]ality, may deviate very widely from this rule. In England, for ex[illegible]e, where the average fall at London is 24½ inches, as ascertained [illegible] Greenwich Observatory, there is such irregu-

[illegible]

larity in some districts, that while at Whitehaven, in Cumberland, there fell in 1849, 32 inches, the quantity of rain in Borrowdale, near Keswick (only 15 miles to the westward), was no less than 142 inches![*] In like manner, in India, Colonel Sykes found by observations made in 1847 and 1848, that at places situated between 17° and 18° north lat., on a line drawn across the Western Ghauts in the Deccan, the fall of rain varied from 21 to 219 inches.[†] The annual average in Bengal is probably below 80 inches, yet Dr. G. Hooker witnessed at Churrapoonjee, in the year 1850, a fall of 30 inches in 24 hours, and in the same place during a residence of six months (from June to November) 530 inches! This occurred on the south face of the Khasia (or Garrow) mountains in Eastern Bengal (see map, Chap. XVIII.), where the depth during the whole of the same year probably exceeded 600 inches. So extraordinary a discharge of water, which, as we shall presently see, is very local, may be thus accounted for. Warm, southerly winds, blowing over the Bay of Bengal, and becoming laden with vapour during their passage, reach the low level delta of the Ganges and Brahmapootra, where the ordinary heat exceeds that of the sea, and where evaporation is constantly going on from countless marshes and the arms of the great rivers. A mingling of two masses of damp air of different temperatures probably causes the fall of 70 or 80 inches of rain, which takes place on the plains. The monsoon having crossed the delta, impinges on the Khasia mountains, which rise abruptly from the plain to a mean elevation of between 4000 and 5000 feet. Here the wind not only encounters the cold air of the mountains, but, what is far more effective as a refrigerating cause, the aerial current is made to flow upwards, and to ascend to a height of several thousand feet above the sea. Both the air and the vapour contained in it, being thus relieved of much atmospheric pressure, expand suddenly, and are cooled by rarefaction. The vapour is condensed, and about 500 inches of rain are thrown down annually, nearly twenty times as much as falls in Great Britain in a year, and almost all of it poured down in six months. The channel of every torrent and river is swollen at this season, and much sandstone horizontally stratified, and other rocks are reduced to sand and gravel by the flooded streams. So great is the superficial waste (or *denudation*), that what would otherwise be a rich and luxuriantly wooded region, is converted into a wild and barren moorland.

After the current of warm air has been thus drained of a large portion of its moisture, it still continues its northerly course to the opposite flank of the Khasia range, only 20 miles farther north, and here the fall of rain is reduced to 70 inches in the year. The same wind then blows northwards across the valley of the Brahmapootra, and at length arrives so dry and exhausted at the Bhootan Himalaya (lat. 28 N.), that those mountains, up to the height of 5000 feet, are naked and sterile, and all their outer valleys arid and dusty.

---

[*] Miller, Phil. Trans. 1851, p. 155.

[†] Phil. Trans. 1850, p. 354.

The aerial current still continuing its northerly course and ascending to a higher region, becomes further cooled, condensation again ensues, and Bhootan, above 5000 feet, is densely clothed with vegetation.*

In another part of India, immediately to the westward, similar phenomena are repeated. The same warm and humid winds, copiously charged with aqueous vapour from the Bay of Bengal, hold their course due north for 300 miles, across the flat and hot plains of the Ganges, till they encounter the lofty Sikkim mountains. (See map, Chap. XVIII.) On the southern flank of these they discharge such a deluge of rain that the rivers in the rainy season rise twelve feet in as many hours. Numerous landslips, some of them extending three or four thousand feet along the face of the mountains, composed of granite, gneiss, and slate, descend into the beds of streams, and dam them up for a time, causing temporary lakes, which soon burst their barriers. "Day and night," says Dr. Hooker, "we heard the crashing of falling trees, and the sound of boulders thrown violently against each other in the beds of torrents. By such wear and tear rocky fragments swept down from the hills are in part converted into sand and fine mud; and the turbid Ganges, during its annual inundation, derives more of its sediment from this source than from the waste of the fine clay of the alluvial plains below.†

On the verge of the tropics a greater quantity of rain falls annually than at the equator. Yet parts even of the tropical latitudes are entirely destitute of rain: Peru, for example, which owes its vegetation solely to rivers and nightly dews. In that country easterly winds prevail, blowing from the Pacific, and these being intercepted by the Andes, and cooled as they rise, are made to part with all their moisture before reaching the low region to the leeward. The desert zone of North Africa, between lat. 15° and 30° N., is another instance of a rainless region. Five or six consecutive years may pass in Upper Egypt, Nubia, and Dongola, or in the Desert of Sahara, without rain.

From the facts above mentioned the reader will infer that in the course of successive geological periods there will be great variations in the quantity of rain falling in one and the same region. At one time there may be none whatever during the whole year; at another a fall of 100 or 500 inches; and these two last averages may occur on the two opposite flanks of a mountain-chain, not more than 20 miles wide. While, therefore, the valleys in one district are widened and deepened annually, they may remain stationary in another, the superficial soil being protected from waste by a dense covering of vegetation. This diversity depends on many geographical circumstances, but principally on the height of the land above the sea, the direction of the prevailing winds, and the relative position, at the time being, of the plains, hills, and the ocean, conditions all of which are liable in the course of ages to undergo a complete revolution.

Recent rain-prints.—When examining, in 1842, the extensive mud-flats of Nova Scotia, which are exposed at low tide on the borders of the Bay of Fundy, I observed not only the foot-print birds which had recently passed over the mud, but also very disti impressions of rain-drops. A peculiar combination of circumstan renders these mud-flats admirably fitted to receive and retain markings which may happen to be made on their surface. The s ment with which the waters are charged is extremely fine, being rived from the destruction of cliffs of red sandstone and shale, and the tides rise fifty feet and upwards, large areas are laid dry nearly a fortnight between the spring and neap tides. In this terval the mud is baked in summer by a hot sun, so that it solidi and becomes traversed by cracks, caused by shrinkage. Portions the hardened mud between these cracks may then be taken up removed without injury. On examining the edges of each slab, observe numerous layers, formed by successive tides, each layer be usually very thin, sometimes only one-tenth of an inch thick. Wh a shower of rain falls, the highest portion of the mud-covered fla usually too hard to receive any impressions; while that recently covered by the tide near the water's edge is too soft. Between th areas a zone occurs, almost as smooth and even as a looking-glass, which every drop forms a cavity of circular or oval form, and, if shower be transient, these pits retain their shape permanently, be dried by the sun, and being then too firm to be effaced by the ac of the succeeding tide, which deposits upon them a new laye mud. Hence we often find, on splitting open a slab an inch or m thick, on the upper surface of which the marks of recent rain oc that an inferior layer, deposited during some previous rise of tide, exhibits on its under side perfect casts of rain-prints, wh stand out in relief, the moulds of the same being seen on the l below. But in some cases, especially in the more sandy layers, markings have been somewhat blunted by the tide, and by sev rain-prints having been joined into one by a repetition of drops ing on the same spot; in which case the casts present a very irr lar and blistered appearance.

---

* Hooker's Himalayan Journal, ined.

† Ibid.

The finest examples which I have seen of these rain-prints sent to me by Dr. Webster, from Kentville, on the borders of the Ba Mines, in Nova Scotia. They were made by a heavy shower, w fell on the 21st of July, 1849, when the rise and fall of the were at their maximum. The impressions (see fig. 13.) consist of shaped or hemispherical cavities, the average size of which is one-eighth to one-tenth of an inch across, but the largest are half an inch in diameter, and one-tenth of an inch deep. The d is chiefly below the general surface or plane of stratification, bu walls of the cavity consist partly of a prominent rim of sandy formed of the matter which has been forcibly expelled from th All the cavities having an oval form are deeper at one end, w they have also a higher rim, and all the deep ends have the sam rection, showing towards which quarter the wind was blowing. or more drops are sometimes seen to have interfered with each o

Fig. 13.



Recent rain-prints, formed July 21. 1849, at Kentville, Bay of Fundy, Nova Scotia. The arrow represents the direction of the shower.

in which case it is usually possible to determine which drop fell last, its rim being unbroken.

On some of the specimens the winding tubular tracks of worms are seen, which have been bored just beneath the surface (see fig. 13., *left side*). They occasionally pass under the middle of a rain-mark, having been formed subsequently. Sometimes the worms have dived beneath the surface, and then reappeared. All these appearances, both of rain-prints and worm-tracks, are of great geological interest, as their exact counterparts are seen in rocks of various ages even in formations of very high antiquity.* Small cavities, often corresponding in size to those produced by rain, are also caused by air bubbles rising up through sand or mud; but these differ in character from rain-prints, being usually deeper than they are wide, and having their sides steeper. These, indeed, are occasionally vertical, or overarching, the opening at the top being narrower than the pit below. In their mode, also, of mutual interference they are unlike rain-prints.†

In consequence of the effects of mountains in cooling currents of moist air, and causing the condensation of aqueous vapour in the manner above described, it follows that in every country, as a general rule, the more elevated regions become perpetual reservoirs of water, which descends and irrigates the lower valleys and plains. The largest quantity of water is first carried to the highest region, and then made to descend by steep declivities towards the sea; so that it acquires superior velocity, and removes more soil, than it would do if the rain had been distributed over the plains and mountains equally in proportion to their relative areas. The water is also made by these means to pass over the greatest distances before it can regain the sea.

---

* See Manual of Geology, Index *Rain-prints.*

† See Lyell on recent and fossil rains. Quart. Journ. Geol. Soc. 1851, vol. vii. p. 239.

It has already been observed that in higher latitudes, where th atmosphere being colder is capable of holding less water in suspensio a diminished fall of rain takes place. Thus at St. Petersburg, th amount is only 16 inches, and at Uleaborg, in the Gulf of Bothni (N. lat. 65°), only 13½ inches, or less than half the average o England, and even this small quantity descends more slowly in th temperate zone, and is spread more equally over the year than i tropical climates. But in reference to geological changes frost in th colder latitude acts as a compensating power in the disintegration rocks, and the transportation of stones to lower levels.

Water when converted into ice augments in bulk more than on twentieth of its volume, and owing to this property it widens t minute crevices (or *joints*) of rocks into which it penetrates. Ice a in various ways, as will be shown in the next chapter, gives buoya to mud and sand, even to huge blocks of stone, enabling rivers moderate size and velocity to carry them to a great distance.

The mechanical force exerted by running water in underminin cliffs, and rounding off the angles of hard rock, is mainly due to th intermixture of foreign ingredients. Sand and pebbles when hurrie along by the violence of the stream, are thrown against every obstacl lying in their way, and thus a power of attrition is acquired, capabl of wearing through the hardest siliceous stones, on which water alone could make no impression.

Newly formed valleys. When travelling in Georgia and Alabama, in 1846, I saw in both those States the commencement of hundreds of valleys in places where the native forest had recently been removed. One of these newly formed gulleys or ravines is represented in the annexed woodcut (fig. 14.), from a drawing which I made on the spot. It occurs three miles and a half due west of Milledgeville, the capital of Georgia, and is situated on the farm of Pomona, on the direct road to Macon.*

Twenty years ago, before the land was cleared, it had no existence but when the trees of the forest were cut down, cracks three feet dee were caused by the sun's heat in the clay; and, during the rains, sudden rush of water through the principal crack deepened it at it lower extremity, from whence the excavating power worked backwards, till, in the course of twenty years, a chasm, measuring no les than 55 feet in depth, 300 yards in length, and varying in width fro 20 to 180 feet, was the result. The high road has been several time turned to avoid this cavity, the enlargement of which is still pr ceeding, and the old line of road may be seen to have held its cours directly over what is now the widest part of the ravine. In th perpendicular walls of this great chasm appear beds of clay and san red, white, yellow, and green, produced by the decomposition in sit of hornblendic gneiss, with layers and veins of quartz, which remai entire to prove that the whole mass was once solid and crystalline.

---

* Lyell's Second Visit to the United States, 1846, vol. ii. p. 25.

Fig. 14.



Ravine on the farm of Pomona, near Milledgeville, Georgia, as it appeared January, 1846.

Excavated in twenty years, 55 feet deep, and 180 feet broad.

I infer, from the rapidity of the denudation which only began here after the removal of the native wood, that this spot, elevated about 600 feet above the sea, has been always covered with a dense forest, from the remote time when it first emerged from the sea. The termination of the cavity on the right hand in the foreground is the head or upper end of the ravine, and in almost every case, such gulleys are lengthened by the streams cutting their way backwards. The depth at the upper end is often, as in this case, considerable, and there is usually at this point, during floods, a small cascade.

Sinuosities of rivers.—In proportion as such valleys are widened, sinuosities are caused by the deflection of the stream first to one side and then to the other. The unequal hardness of the materials through which the channel is eroded tends partly to give new directions to the lateral force of excavation. When by these, or by accidental shiftings of the alluvial matter in the channel, the current is made to cross its general line of descent, it eats out a curve in the opposite bank, or in the side of the hills bounding the valley, from which curve it is turned back again at an equal angle, so that it recrosses the line of descent, and gradually hollows out another curve lower down in the opposite bank, till the whole sides of the valley, or river bed, present a succession of salient and retiring angles. Among the causes of deviation from a straight course by which torrents and rivers tend in mountainous regions to widen the valleys through which they flow, may be mentioned the confluence of lateral torrents, swollen irregularly at different seasons by partial storms, and discharging at different times unequal quantities of sand, mud, and pebbles, into the main channel.

When the tortuous flexures of a river are extremely great, as often happens in alluvial plains, the aberration from the direct line of descent may be restored by the river cutting through the isthmus which separates two neighbouring curves. Thus, in the annexed diagram, the extreme sinuosity of the river has caused it to return for a brief space in a contrary direction to its main course, so that a peninsula is formed, and the isthmus (at a) is consumed on both sides by currents flowing in opposite directions. In this case an island is soon formed,—on either side of which a portion of the stream usually remains.

Fig. 15.



Transporting power of water.—In regard to the transporting power of water, we may often be surprised at the facility with which streams of a small size, and descending a slight declivity, bear along coarse sand and gravel; for we usually estimate the weight of rocks in air, and do not reflect on their comparative buoyancy when submerged in a denser fluid. The specific gravity of many rocks is not more than twice that of water, and very rarely more than thrice, so that almost all the fragments propelled by a stream have lost a third, and many of them half, of what we usually term their weight.

It has been proved by experiment, in contradiction to the theories of the earlier writers on hydrostatics, to be a universal law, regulating the motion of running water, that the velocity at the bottom of the stream is everywhere less than in any part above it, and is greatest at the surface. Also, that the superficial particles in the middle of the stream move swifter than those at the sides. This retardation of the lowest and lateral currents is produced by friction; and when the velocity is sufficiently great, the soil composing the sides and bottom gives way. A velocity of three inches per second at the bottom is ascertained to be sufficient to tear up fine clay,—six inches per second, fine sand,—twelve inches per second, fine gravel, —and three feet per second, stones of the size of an egg.*

When this mechanical power of running water is considered, we are prepared for the transportation before alluded to of large quantities of gravel, sand, and mud, by torrents which descend from mountainous regions. But a question naturally arises, How the more tranquil rivers of the valleys and plains, flowing on comparatively level ground, can remove the prodigious burden which is discharged into them by their numerous tributaries, and by what means they are enabled to convey the whole mass to the sea? If they had not this removing power, their channels would be annually choked up, and the valleys of the lower country, and plains at the base of mountain-chains, would be continually strewed over with fragments of rock and sterile sand. But this evil is prevented by a general law regulating the conduct of running water,—that two equal streams do not, when united, occupy a bed of double surface. Nay, the width of the principal river, after the junction of a tributary, sometimes remains the same as before, or is even lessened. The cause of this apparent paradox was long ago explained by the Italian writers who had studied the confluence of the Po and its feeders in the plains of Lombardy.

The addition of a smaller river augments the velocity of the main stream, often in the same proportion as it does the quantity of water. Thus the Venetian branch of the Po swallowed up the Ferranese branch and that of Panaro without any enlargement of its own dimensions. The cause of the greater velocity is, first, that after the union of two rivers the water, in place of the friction of four shores, has only that of two to surmount; 2dly, because the main body of the stream being farther distant from the banks, flows on with less interruption; and lastly, because a greater quantity of water moving more swiftly, digs deeper into the river's bed. By this beautiful adjustment, the water which drains the interior country is made continually to occupy less room as it approaches the sea; and thus the most valuable part of our continents, the rich deltas and great alluvial plains, are prevented from being constantly under water.

River floods in Scotland, 1829.—Many remarkable illustrations of the power of running water in moving stones and heavy materials were afforded by the storm and floods which occurred on the 3d and 4th of August, 1829, in Aberdeenshire and other counties in Scotland. The elements during this storm assumed all the characters which mark the tropical hurricanes; the wind blowing in sudden gusts and whirlwinds, the lightning and thunder being such as is rarely witnessed in our climate, and heavy rain falling without intermission. The floods extended almost simultaneously, and with equal violence over that part of the north-east of Scotland, which would be cut off by two lines drawn from the head of Lochrannoch, one towards Inverness and the other to Stonehaven. The united line of

---

* Encyc. Brit. art. *Rivers.*

the different rivers which were flooded could not be less
five to six hundred miles in length; and the whole of th
were marked by the destruction of bridges, roads, crops, and
Sir T. D. Lauder has recorded the destruction of thirty-eig
and the entire obliteration of a great number of farms an
On the Nairn, a fragment of sandstone, fourteen feet long
feet wide and one foot thick, was carried above 200 yards
river. Some new ravines were formed on the sides of
where no streams had previously flowed, and ancient river
which had never been filled from time immemorial, gave p
copious flood.*

The bridge over the Dee at Ballater consisted of fiv
having upon the whole a water-way of 260 feet. The b
river, on which the piers rested, was composed of rolled
granite and gneiss. The bridge was built of granite, and
uninjured for twenty years; but the different parts were s
in succession by the flood, and the whole mass of masonry di
in the bed of the river. "The river Don," observes Mr. Far
in his account of the inundations, "has upon my own premi
a mass of four or five hundred tons of stones, many of the
three hundred pounds' weight, up an inclined plane, rising
in eight or ten yards, and left them in a rectangular heap, abo
feet deep on a flat ground:— the heap ends abruptly at i
extremity."†

The power even of a small rivulet, when swollen by rain, in r
heavy bodies, was exemplified in August, 1827, in the C
small stream which flows at a slight declivity from the easter
shed of the Cheviot Hills. Several thousand tons' weight o
and sand were transported to the plain of the Till, and a brid
in progress of building, was carried away, some of the arc
of which, weighing from half to three quarters of a ton ea
propelled two miles down the rivulet. On the same occas
current tore away from the abutment of a mill-dam a large
greenstone-porphyry, weighing nearly two tons, and transp
to the distance of a quarter of a mile. Instances are re
occurring repeatedly, in which from one to three thousand
gravel are, in like manner, removed by this streamlet to still
distances in one day.‡

Floods caused by landslips, 1826.— The power which
water may exert, in the lapse of ages, in widening and deep
valley, does not so much depend on the volume and velocit
stream usually flowing in it, as on the number and magnitud
obstructions which have, at different periods, opposed its free
If a torrent, however small, be effectually dammed up, the si
valley above the barrier, and its declivity below, and not th

---

* Sir T. D. Lauder's Account of the Great Floods in Morayshire, August, 1829.

† Quarterly Journ. of Sci, xii. New Series, p. 331.

‡ Culley, Proceed. Geol. So

ons of the torrent, will determine the violence of the débâcle. The ost universal source of local deluges are landslips, slides, or ava-nches, as they are sometimes called, when great masses of rock and il, or sometimes ice and snow, are precipitated into the bed of a river, e boundary cliffs of which have been thrown down by the shock of n earthquake, or undermined by springs or other causes. Volumes ight be filled with the enumeration of instances on record of these errific catastrophes; I shall therefore select a few examples of recent ccurrence, the facts of which are well authenticated.

Two dry seasons in the White Mountains, in New Hampshire (United States), were followed by heavy rains on the 28th August, 1826, when from the steep and lofty declivities which rise abruptly on both sides of the river Saco, innumerable rocks and stones, many of sufficient size to fill a common apartment, were detached, and in their descent swept down before them, in one promiscuous and frightful ruin, forests, shrubs, and the earth which sustained them. Although there are numerous indications on the steep sides of these hills of former slides of the same kind, yet no tradition had been handed down of any similar catastrophe within the memory of man, and the growth of the forest on the very spots now devastated, clearly showed that for a long interval nothing similar had occurred. One of these moving masses was afterwards found to have slid three miles, with an average breadth of a quarter of a mile. The natural excavations commenced generally in a trench a few yards in depth and a few rods in width, and descended the mountains, widening and deepening till they became vast chasms. At the base of these hollow ravines was seen a confused mass of ruins, consisting of transported earth, gravel, rocks, and trees. Forests of spruce-fir and hemlock, a kind of fir somewhat resembling our yew in foliage, were prostrated with as much ease as if they had been fields of grain; for, where they disputed the ground, the torrent of mud and rock accumulated behind, till it gathered ufficient force to burst the temporary barrier.

The valleys of the Amonoosuck and Saco presented, for many miles, n uninterrupted scene of desolation; all the bridges being carried way, as well as those over their tributary streams. In some places, he road was excavated to the depth of from fifteen to twenty feet; others, it was covered with earth, rocks, and trees, to as great a eight. The water flowed for many weeks after the flood, as densely harged with earth as it could be without being changed into mud, nd marks were seen in various localities of its having risen on either ide of the valley to more than twenty-five feet above its ordinary evel. Many sheep and cattle were swept away, and the Willey amily, nine in number, who in alarm had deserted their house, were estroyed on the banks of the Saco; seven of their mangled bodies ere afterwards found near the river, buried beneath drift-wood and ountain ruins.* Eleven years after the event, the deep channels orn by the avalanches of mud and stone, and the immense heaps of boulders and blocks of granite in the river channel, still formed Professor Hubbard, a picturesque feature in the scenery.*

---

* Silliman's Journal, vol. xv. No. 2. p. 216. Jan. 1829.

When I visited the country in 1845, eight years after Pro Hubbard, I found the signs of devastation still very striking; I particularly remarked that although the surface of the bare gr rocks had been smoothed by the passage over them of so much and stone, there were no continuous parallel and rectilinear fur nor any of the fine scratches or striæ which characterize *glacial* The absence of these is nowhere more clearly exemplified than in bare rocks over which passed the great "Willey slide" of 1826.†

But the catastrophes in the White Mountains are insignif when compared to those which are occasioned by earthquakes, the boundary hills, for miles in length, are thrown down into hollow of a valley. I shall have opportunities of alluding to ins tions of this kind, when treating expressly of earthquakes, and content myself at present with selecting an example of a flood d a different cause.

Flood in the valley of Bagnes, 1818.—The valley of Bagn one of the largest of the lateral embranchments of the main vall the Rhone, above the Lake of Geneva. Its upper portion wa 1818, converted into a lake by the damming up of a narrow pa avalanches of snow and ice, precipitated from an elevated gla into the bed of the river Dranse. In the winter season, du continued frost, scarcely any water flows in the bed of this river preserve an open channel, so that the ice barrier remained en until the melting of the snows in spring, when a lake was form above, about half a league in length, which finally attained in so parts a depth of about two hundred feet, and a width of ab seven hundred feet. To prevent or lessen the mischief apprehend from the sudden bursting of the barrier, an artificial gallery, se hundred feet in length, was cut through the ice, before the wat had risen to a great height. When at length they accumulated a flowed through this tunnel, they dissolved the ice, and thus dee ened their channel, until nearly half of the whole contents of t lake were slowly drained off. But at length, on the approach of t hot season, the central portion of the remaining mass of ice gave w with a tremendous crash, and the residue of the lake was emptied half an hour. In the course of its descent, the waters encounter several narrow gorges, and at each of these they rose to a gr height, and then burst with new violence into the next basin, swee ing along rocks, forests, houses, bridges, and cultivated land. I the greater part of its course the flood resembled a moving mass rock and mud, rather than of water. Some fragments of gran rocks, of enormous magnitude, and which from their dimensio might be compared without exaggeration to houses, were torn out a more ancient alluvion, and borne down for a quarter of a mile. O

---

[*] Silliman's Journal, vol. xxxiv. p. 115.

[†] See Lyell's Second Visit to the vol. i. p. 69.

of the fragments moved was sixty paces in circumference.[*] The velocity of the water, in the first part of its course, was thirty-three feet per second, which diminished to six feet before it reached the Lake of Geneva, where it arrived in six hours and a half, the distance being forty-five miles.[†]

This flood left behind it, on the plains of Martigny, thousands of trees torn up by the roots, together with the ruins of buildings. Some of the houses in that town were filled with mud up to the second story. After expanding in the plain of Martigny, it entered the Rhone, and did no farther damage; but some bodies of men, who had been drowned above Martigny, were afterwards found, at the distance of about thirty miles, floating on the farther side of the Lake of Geneva, near Vevay.

The waters, on escaping from the temporary lake, intermixed with mud and rock, swept along, for the first four miles, at the rate of above twenty miles an hour; and M. Escher, the engineer, calculated that the flood furnished 300,000 cubic feet of water every second—an efflux which is five times greater than that of the Rhine below Basle. Now, if part of the lake had not been gradually drained off, the flood would have been nearly double, approaching in volume to some of the largest rivers in Europe. It is evident, therefore, that, when we are speculating on the excavating force which a river may have exerted in any particular valley, the most important question is, not the volume of the existing stream, nor the present levels of its channel, nor even the nature of the rocks, but the probability of a succession of floods at some period since the time when the valley may have been first elevated above the sea.

For several months after the débâcle of 1818, the Dranse, having no settled channel, shifted its position continually from one side to the other of the valley, carrying away newly-erected bridges, undermining houses, and continuing to be charged with as large a quantity of earthy matter as the fluid could hold in suspension. I visited this valley four months after the flood, and was witness to the sweeping away of a bridge, and the undermining of part of a house. The greater part of the ice-barrier was then standing, presenting vertical cliffs 150 feet high, like ravines in the lava-currents of Etna or Auvergne, where they are intersected by rivers.

Inundations, precisely similar, are recorded to have occurred at former periods in this district, and from the same cause. In 1595, for example, a lake burst and the waters, descending with irresistible fury, destroyed the town of Martigny, where from sixty to eighty persons perished. In a similar flood, fifty years before, 140 persons were drowned.

Flood at Tivoli, 1826.—I shall conclude with one more example derived from a land of classic recollections, the ancient Tibur, and

---

[*] This block was measured by Capt. B. Hall, R.N.

[†] Inundation of the Val de Bagnes, in 1818, Ed. Phil. Journ., vol. i. p. 187., from memoir of M. Escher.

which, like all the other inundations above alluded to, occurred wit
the present century. The younger Pliny, it will be remembe
describes a flood on the Anio, which destroyed woods, rocks,
houses, with the most sumptuous villas and works of arts.* For f
or five centuries consecutively, this "headlong stream," as Ho
truly called it, has often remained within its bounds, and then, af
so long an interval of rest, has at different periods inundated
banks again, and widened its channel. The last of these catastrop
happened 15th Nov. 1826, after heavy rains, such as produced
floods before alluded to in Scotland. The waters appear also
have been impeded by an artificial dike, by which they were se
rated into two parts, a short distance above Tivoli. They bro
through this dike; and leaving the left trench dry, precipitat
themselves, with their whole weight, on the right side. Here th
undermined, in the course of a few hours, a high cliff, and wide
the river's channel about fifteen paces. On this height stood t
church of St. Lucia, and about thirty-six houses of the town
Tivoli, which were all carried away, presenting as they sank in
the roaring flood, a terrific scene of destruction to the spectat
on the opposite bank. As the foundations were gradually remov
each building, some of them edifices of considerable height, was fi
traversed with numerous rents, which soon widened into lar
fissures, until at length the roofs fell in with a crash, and th
the walls sunk into the river, and were hurled down the catar
below.†

The destroying agency of the flood came within two hundred yar
of the precipice on which the beautiful temple of Vesta stands; b
fortunately this precious relic of antiquity was spared, while the wre
of modern structures was hurled down the abyss. Vesta, it will
remembered, in the heathen mythology, personified the stability of t
earth; and when the Samian astronomer, Aristarchus, first taught th
the earth revolved on its axis, and round the sun, he was public
accused of impiety, "for moving the everlasting Vesta from her plac
Playfair observed, that when Hutton ascribed instability to the eart
surface, and represented the continents which we inhabit as t
theatre of incessant change and movement, his antagonists, who r
garded them as unalterable, assailed him in a similar manner wi
accusations founded on religious prejudices.‡ We might appeal
the excavating power of the Anio as corroborative of one of the m
controverted parts of the Huttonian theory; and if the days of ome
had not gone by, the geologists who now worship Vesta might reg
the late catastrophe as portentous. We may, at least, recommend t
modern votaries of the goddess to lose no time in making a pilgrim
to her shrine, for the next flood may not respect the temple.

Excavation of rocks by running water.—The rapidity with wh
even the smallest streams hollow out deep channels in soft and

---

* Lib. viii. Epist. 17.

† When at Tivoli, in 1829, I received this account from eye-witnesses of event.

‡ Illustr. of Hutt. Theory, § 3. p. 147.

structible soils is remarkably exemplified in volcanic countries, where the sand and half-consolidated tuffs opposed but a slight resistance to the torrents which descend the mountain side. After the heavy rains which followed the eruption of Vesuvius in 1824, the water flowing from the Atrio del Cavallo cut, in three days, a new chasm through strata of tuff and ejected volcanic matter, to the depth of twenty-five feet. I found the old mule-road, in 1828, intersected by this new ravine.

The gradual erosion of deep chasms through some of the hardest rocks, by the constant passage of running water, charged with foreign matter, is another phenomenon of which striking examples may be adduced. Illustrations of this excavating power are presented by many valleys in central France where the channels of rivers have been barred up by solid currents of lava, through which the streams have re-excavated a passage, to the depth of from twenty to seventy feet and upwards, and often of great width. In these cases there are decisive proofs that neither the sea, nor any denuding wave or extraordinary body of water, has passed over the spot since the melted lava was consolidated. Every hypothesis of the intervention of sudden and violent agency is entirely excluded, because the cones of *loose* scoriæ, out of which the lavas flowed, are oftentimes at no great elevation above the rivers, and have remained undisturbed during the whole period which has been sufficient for the hollowing out of such enormous ravines.

Recent excavation by the Simeto.—But I shall at present confine myself to examples derived from events which have happened since the time of history.

At the western base of Etna, a current of lava (A A, fig. 16.), descending from near the summit of the great volcano, has flowed to the distance of five or six miles, and then reached the alluvial plain of the Simeto, the largest of the Sicilian rivers, which skirts the base of Etna, and falls into the sea a few miles south of Catania. The lava entered the river about three miles above the town of Aderno, and not only occupied its channel for some distance, but, crossing to the opposite side of the valley, accumulated there in a rocky mass.

Fig. 16.



Recent excavation of lava at the foot of Etna by the river Simeto.

Gemmellaro gives the year 1603 as the date of the eruption.[*] The appearance of the current clearly proves, that it is one of the most modern of those of Etna; for it has not been covered or crossed by subsequent streams or ejections, and the olives which had been planted on its surface were all of small size, when I examined the spot in 1828, yet they were older than the natural wood on the same lava. In the course, therefore, of about two centuries, the Simeto has eroded a passage from fifty to several hundred feet wide, and in some parts from forty to fifty feet deep.

The portion of lava cut through is in no part porous or scoriaceous, but consists of a compact homogeneous mass of hard blue rock, somewhat inferior in weight to ordinary basalt, and containing crystals of olivine and glassy felspar. The general declivity of this part of the bed of the Simeto is not considerable; but, in consequence of the unequal waste of the lava, two water-falls occur at Passo Manzanelli, each about six feet in height. Here the chasm (B, fig. 16.) is about forty feet deep, and only fifty broad.

The sand and pebbles in the river-bed consist chiefly of a brown quartzose sandstone, derived from the upper country; but the materials of the volcanic rock itself must have greatly assisted the attrition. This river, like the Caltabiano on the eastern side of Etna, has not yet cut down to the ancient bed of which it was dispossessed, and of which the probable position is indicated in the annexed diagram (C, fig. 16.).

On entering the narrow ravine where the water foams down the two cataracts, we are entirely shut out from all view of the surrounding country; and a geologist who is accustomed to associate the characteristic features of the landscape with the relative age of certain rocks, can scarcely dissuade himself from the belief that he is contemplating a scene in some rocky gorge of a primary district. The external forms of the hard blue lava, are as massive as any of the most ancient trap-rocks of Scotland. The solid surface is in some parts smoothed and almost polished by attrition, and covered in others with a white lichen, which imparts to it an air of extreme antiquity, so as greatly to heighten the delusion. But the moment we re-ascend the cliff the spell is broken; for we scarcely recede a few paces, before the ravine and river disappear, and we stand on the black and rugged surface of a vast current of lava, which seems unbroken, and which we can trace up nearly to the distant summit of that majestic cone which Pindar called "the pillar of heaven," and which still continues to send forth a fleecy wreath of vapour, reminding us that its fires are not extinct, and that it may again give out a rocky stream, wherein other scenes like that now described may present themselves to future observers.

Falls of Niagara.—The falls of Niagara afford a magnificent example of the progressive excavation of a deep valley in solid rock. That river flows over a flat table land, in a depression of which

---

[*] Quadro Istorico dell' Etna, 1824.

Fig. 17.


Lake Erie.
The Falls.
Lime-
stone
Shale.
Lewiston.
Niagara River.
Queenstown.

P 4

Lake Erie is situated. Where it issues from the lake, it is nearly a mile in width, and 330 feet above Lake Ontario, which is about 30 miles distant. For the first fifteen miles below Lake Erie the surrounding country, comprising Upper Canada on the west, and the state of New York on the east, is almost on a level with its banks, and nowhere more than thirty or forty feet above them.* (See fig. *17.*) The river being occasionally interspersed with low wooded islands, and having sometimes a width of three miles, glides along at first with a clear, smooth, and tranquil current, falling only fifteen feet in as many miles, and in this part of its course resembling an arm of Lake Erie. But its character is afterwards entirely changed, on approaching the Rapids, where it begins to rush and foam over a rocky and uneven limestone bottom, for the space of nearly a mile, till at length it is thrown down perpendicularly 165 feet at the Falls. Here the river is divided into two sheets of water by an island, the largest cataract being more than a third of a mile broad, the smaller one having a breadth of six hundred feet. When the water has precipitated itself into an unfathomable pool, it rushes with great velocity down the sloping bottom of a narrow chasm, for a distance of seven miles. This ravine varies from 200 to 400 yards in width from cliff to cliff; contrasting, therefore, strongly in its breadth with that of the river above. Its depth is from 200 to 300 feet, and it intersects for about seven miles the table land before described, which terminates suddenly at Queenstown in an escarpment or long line of inland cliff facing northwards, towards Lake Ontario. The Niagara, on reaching the escarpment and issuing from the gorge, enters the flat country, which is so nearly on a level with Lake Ontario, that there is only a fall of about four feet in the seven additional miles which intervene between Queenstown and the shores of that lake.

It has long been the popular belief that the Niagara once flowed in a shallow valley across the whole platform, from the present site of the Falls to the escarpment (called the Queenstown heights), where it is supposed that the cataract was first situated, and that the river has been slowly eating its way backwards through the rocks for the distance of seven miles. This hypothesis naturally suggests itself to every observer, who sees the narrowness of the gorge at its termination, and throughout its whole course, as far up as the Falls, above which point the river expands as before stated. The boundary cliffs of the ravine are usually perpendicular, and in many places undermined on one side by the impetuous stream. The uppermost rock of the table-land at the Falls consists of hard limestone (a member of the Silurian series), about ninety feet thick, beneath which lie soft shales of equal thickness, continually undermined by the action of the spray, which rises from the pool into which so large a body of water is projected, and is driven violently by gusts of wind against the base of the precipice. In consequence of this action, and that of frost, the shale disintegrates and crumbles away, and portions of the incumbent rock overhang 40 feet, and often when unsupported tumble down, so that the Falls do not remain absolutely stationary at the same spot, even for half a century. Accounts have come down to us, from the earliest period of observation, of the frequent destruction of these rocks, and the sudden descent of huge fragments in 1818 and 1828, are said to have shaken the adjacent country like an earthquake. The earliest travellers, Hennepin and Kalm, who in 1678 and 1751 visited the Falls, and published views of them, attest the fact, that the rocks have been suffering from dilapidation for more than a century and a half, and that some slight changes, even in the scenery of the cataract have been brought about within that time. The idea, therefore, of perpetual and progressive waste is constantly present to the mind of every beholder; and as that part of the chasm, which has been the work of the last hundred and fifty years resembles precisely in depth, width, and character, the rest of the gorge which extends seven miles below, it is most natural to infer, that the entire ravine has been hollowed out in the same manner, by the recession of the cataract.

---

* The reader will find in my Travels in North America, vol. i. ch. 2., a coloured geological map and section of the Niagara district, also a bird's-eye view of the Falls and adjacent country, coloured geologically, of which the first idea was suggested by the excellent original sketch given by Mr. Bakewell. I have referred more fully to these and to Mr. Hall's Report on the Geology of New York, as well as to the earlier writings of Hennepin and Kalm in the same work, and have speculated on the origin of the escarpment over which the falls may have been originally precipitated. Vol. i. p. 32., and vol. ii. p. 93.

It must at least be conceded, that the river supplies an adequate cause for executing the whole task thus assigned to it, provided we grant sufficient time for its completion. As this part of the country was a wilderness till near the end of the last century, we can obtain no accurate data for estimating the exact rate at which the cataract has been receding. Mr. Bakewell, son of the eminent geologist of that name, who visited the Niagara in 1829, made the first attempt to calculate from the observations of one who had lived forty years at the Falls, and who had been the first settler there, that the cataract had during that period gone back about a yard annually. But after the most careful inquiries which I was able to make, during my visit to the spot in 1841–2, I came to the conclusion that the average of one foot a year would be a much more probable conjecture. In that case, it would have required thirty-five thousand years for the retreat of the Falls, from the escarpment of Queenstown to their present site. It seems by no means improbable that such a result would be no exaggeration of the truth, although we cannot assume that the retrograde movement has been uniform. An examination of the geological structure of the district, as laid open in the ravine, shows that at every step in the process of excavation, the height of the precipice, the hardness of the materials at its base, and the quantity of fallen matter to be removed, must have varied. At some points it may have receded much faster than at present, but in general its progress was probably slower, because the cataract, when it began to recede, must have had nearly twice its present height.

From observations made by me in 1841, when I had the advantage of being accompanied by Mr. Hall, State geologist of New York, and in 1842, when I re-examined the Niagara district, I obtained geological evidence of the former existence of an old river-bed, which, I have no doubt, indicates the original channel through which the waters once flowed from the Falls to Queenstown, at the height of nearly three hundred feet above the bottom of the present gorge. The geological monuments alluded to, consist of patches of sand and gravel, forty feet thick, containing fluviatile shells of the genera Unio, Cyclas, Melania, &c., such as now inhabit the waters of the Niagara above the Falls. The identity of the fossil species with the recent is unquestionable, and these freshwater deposits occur at the edge of the cliffs bounding the ravine, so that they prove the former extension of an elevated shallow valley, four miles below the Falls, a distinct prolongation of that now occupied by the Niagara, in the elevated region intervening between Lake Erie and the Falls. Whatever theory be framed for the hollowing out of the ravine further down, or for the three miles which intervene between the whirlpool and Queenstown, it will always be necessary to suppose the former existence of a barrier of *rock*, not of loose and destructible materials, such as those composing the drift in this district, somewhere immediately below the whirlpool. By that barrier the waters were held back for ages, when the fluviatile deposit, 40 feet in thickness, and 250 feet above the present channel of the river, originated. If we are led by this evidence to admit that the cataract has cut back its way for four miles, we can have little hesitation in referring the excavation of the remaining three miles below to a like agency, the shape of the chasm being precisely similar.

There have been many speculations respecting the future recession of the Falls, and the deluge that might be occasioned by the sudden escape of the waters of Lake Erie, if the ravine should ever be prolonged 16 miles backwards. But a more accurate knowledge of the geological succession of the rocks, brought to light by the State Survey, has satisfied every geologist that the Falls would diminish gradually in height before they travelled back two miles, and in consequence of a gentle dip of the strata to the south, the massive limestone now at the top would then be at their base, and would retard, and perhaps put an effectual stop to, the excavating process.

CHAPTER XV.

TRANSPORTATION OF SOLID MATTER BY ICE.

Carrying power of river-ice — Rocks annually conveyed into the St. Lawrence by its tributaries — Ground-ice; its origin and transporting power — Glaciers — Theory of their downward movement — Smoothed and grooved rocks — The moraine unstratified — Icebergs covered with mud and stones — Limits of glaciers and icebergs — Their effects on the bottom when they run aground. — Packing of coast-ice — Boulders drifted by ice on coast of Labrador — Blocks moved by ice in the Baltic.

The power of running water to carry sand, gravel, and fragments of rock to considerable distances is greatly augmented in those regions where, during some part of the year, the frost is of sufficient intensity to convert the water, either at the surface or bottom of rivers, into ice.

This subject may be considered under three different heads: — first, the effect of surface-ice and ground-ice in enabling streams to remove gravel and stones to a distance; secondly, the action of glaciers in the transport of boulders, and in the polishing and scratching of rocks; thirdly, the floating off of glaciers charged with solid matter into the sea, and the drifting of icebergs and coast-ice.

River-ice. — Pebbles and small pieces of rock may be seen entangled in ice, and floating annually down the Tay in Scotland, as far as the mouth of that river. Similar observations might doubtless be made respecting almost all the larger rivers of England and Scotland; but there seems reason to suspect that the principal transfer from place to place of pebbles and stones adhering to ice goes on unseen by us under water. For although the specific gravity of the compound mass may cause it to sink, it may still be very buoyant, and easily borne along by a feeble current. The ice, moreover, melts very slowly at the bottom of running streams in winter, as the water there is often nearly at the freezing point, as will be seen from what will be said in the sequel of ground-ice.

As we traverse Europe in the latitudes of Great Britain, we find the winters more severe, and the rivers more regularly frozen over. M. Lariviere relates that, being at Memel on the Baltic in 1821, when the ice of the river Niemen broke up, he saw a mass of ice thirty feet long which had descended the stream, and had been thrown ashore. In the middle of it was a triangular piece of granite, about a yard in diameter, resembling in composition the red granite of Finland.*

When rivers in the northern hemisphere flow from south to north, the ice first breaks up in the higher part of their course, and the flooded waters, bearing along large icy fragments, often arrive at parts of the stream which are still firmly frozen over. Great inundations are thus frequently occasioned by the obstructions thrown in the way of the descending waters, as in the case of the Mackenzie in North America, and the Irtish, Obi, Yenesi, Lena, and other rivers of Siberia. (See map, fig. 1. p. 79.) A partial stoppage of this kind lately occurred (Jan. 31. 1840) in the Vistula, about a mile and a half above the city of Dantzic, where the river, choked up by packed ice, was made to take a new course over its right bank, so that it hollowed out in a few days a deep and broad channel, many leagues in length through a tract of sand-hills which were from 40 to 60 feet high.

---

* Consid. sur les Blocs Errat. 1829.

In Canada, where the winter's cold is intense, in a latitude corresponding to that of central France, several tributaries of the St. Lawrence begin to thaw in their upper course, while they remain frozen over lower down, and thus large slabs of ice are set free and thrown upon the unbroken sheet of ice below. Then begins what is called the packing of the drifted fragments; that is to say, one slab is made to slide over another, until a vast pile is built up, and the whole being frozen together, is urged onwards by the force of the dammed up waters and drift-ice. Thus propelled, it not only forces along boulders, but breaks off from cliffs, which border the rivers, huge pieces of projecting rock. By this means several buttresses of solid masonry, which, up to the year 1836, supported a wooden bridge on the St. Maurice, which falls into the St. Lawrence, near the town of Trois Rivières, lat. 46° 20′, were thrown down, and conveyed by the ice into the main river; and instances have occurred at Montreal of wharfs and stone-buildings, from 30 to 50 feet square, having been removed in a similar manner. We learn from Captain Bayfield that anchors laid down within high-water mark, to secure vessels hauled on shore for the winter, must be cut out of the ice on the approach of spring, or they would be carried away. In 1834, the Gulnare's bower-anchor, weighing half a ton, was transported some yards by the ice, and so firmly was it fixed, that the force of the moving ice broke a chain-cable suited for a 10-gun brig, and which had rode the Gulnare during the heaviest gales in the gulf. Had not this anchor been cut out of the ice, it would have been carried into deep water and lost.*

The scene represented in the annexed plate (pl. 2.), from a drawing by Lieutenant Bowen, R. N., will enable the reader to comprehend the incessant changes which the transport of boulders produces annually on the low islands, shores, and bed of the St. Lawrence above Quebec. The fundamental rocks at Richelieu Rapid, situated in lat. 46° N., are limestone and slate, which are seen at low water to be covered with boulders of granite. These boulders owe their

---

* Capt. Bayfield, Geol. Soc. Proceedings, vol. ii. p. 223.

PLATE II.



BOULDERS DRIFTED BY ICE ON SHORES OF THE ST. LAWRENCE.

View taken by Lieut. Bowen, from the N.E., in the Spring of 1835, at Richelieu Rapid, lat. 46. N.

spheroidal form chiefly to weathering, or the action of frost, which causes the surface to exfoliate in concentric plates, so that all the more prominent angles are removed. At the point *a* is a cavity in the mud or sand of the beach, now filled with water, which was occupied during the preceding winter (1835) by the huge erratic *b*, a mass of granite, 70 tons' weight, found in the spring following (1836) at the distance of several feet from its former position. Many small islands are seen on the river, such as *c d*, which afford still more striking proofs of the carrying and propelling power of ice. These islets are never under water, yet every winter ice is thrown upon them in such abundance, that it *packs* to the height of 20, and even 30 feet, bringing with it a continual supply of large stones or boulders, and carrying away others; the greatest number being deposited, according to Lieutenant Bowen, on the edge of deep water. On the island *d*, on the left of the accompanying view, a lighthouse is represented, consisting of a square wooden building, which having no other foundation than the boulders, requires to be taken down every winter, and rebuilt on the re-opening of the river.

These effects of frost, which are so striking on the St. Lawrence above Quebec, are by no means displayed on a smaller scale below that city, where the gulf rises and falls with the tide. On the contrary, it is in the estuary, between the latitudes 47° and 49°, that the greatest quantity of gravel and boulders of large dimensions are carried down annually towards the sea. Here the frost is so intense, that a dense sheet of ice is formed at low water, which, on the rise of the tide, is lifted up, broken, and thrown in heaps on the extensive shoals which border the estuary. When the tide recedes, this packed ice is exposed to a temperature sometimes 30° below zero, which freezes together all the loose pieces of ice, as well as the granitic and other boulders. The whole of these are often swept away by a high tide, or when the river is swollen by the melting of the snow in spring. One huge block of granite, 15 feet long by 10 feet both in width and height, and estimated to contain 1500 cubic feet, was conveyed in this manner to some distance in the year 1837, its previous position being well known, as up to that time it had been used by Captain Bayfield as a mark for the surveying station.

Ground ice.—When a current of cold air passes over the surface of a lake or stream it abstracts from it a quantity of heat, and the specific gravity of the water being thereby increased, the cooled portion sinks. This circulation may continue until the whole body of fluid has been cooled down to the temperature of 40° F., after which, if the cold increase, the vertical movement ceases, the water which is uppermost expands and floats over the heavier fluid below, and when it has attained a temperature of 32° Fahr. it sets into a sheet of ice. It should seem therefore impossible, according to this law of congelation, that ice should ever form at the bottom of a river; and yet such is the fact, and many speculations have been hazarded to account for so singular a phenomenon. M. Arago is of opinion that the mechanical action of a running stream produces a circulation by which the entire body of water is mixed up together and cooled alike, and the whole being thus reduced to the freezing point, ice begins to form at the bottom for two reasons, first, because there is less motion there, and secondly, because the water is in contact with solid rock or pebbles which have a cold surface.* Whatever explanation we adopt, there is no doubt of the fact, that in countries where the intensity and duration of the cold is great, rivers and torrents acquire an increase of carrying power by the formation of what is called ground-ice. Even in the Thames we learn from Dr. Plott that pieces of this kind of ice, having gravel frozen on to their under side, rise up from the bottom in winter, and float on the surface. In the Siberian rivers, Weitz describes large stones as having been brought up from the river's bed in the same manner, and made to float.†

Glaciers. — In the temperate zone, the snow lies for months in winter on the summit of every high mountain, while in the arctic regions, a long summer's day of half a year's duration is insufficient to melt the snow, even on land just raised above the level of the sea. It is therefore not surprising, since the atmosphere becomes colder in proportion as we ascend in it, that there should be heights, even in tropical countries, where the snow never melts. The lowest limit to which the perpetual snow extends downwards, from the tops of mountains at the equator, is an elevation of not less than 16,000 feet above the sea; while in the Swiss Alps, in lat. 46° N. it reaches as low as 8,500 feet above the same level, the loftier peaks of the Alpine chain being from 12,000 to 15,000 feet high. The frozen mass augmenting from year to year would add indefinitely to the altitude of alpine summits, were it not relieved by its descent through the larger and deeper valleys to regions far below the general snow-line. To these it slowly finds its way in the form of rivers of ice called glaciers, the consolidation of which is produced by pressure, and by the congelation of water infiltered into the porous mass, which is always undergoing partial liquefaction, and receiving in summer occasional showers of rain on its surface. In a day of hot sunshine, or mild rain, innumerable rills of pure and sparkling water run in icy channels along the surface of the glaciers, which in the night shrink, and come to nothing. They are often precipitated in bold cascades into deep fissures in the ice, and contribute together with springs to form torrents, which flow in tunnels at the bottom of the glaciers for many a league, and at length issue at their extremities from beneath beautiful caverns or arches. The waters of these streams are always densely charged with the finest mud, produced by the grinding of rock and sand under the weight of the moving mass. (See fig. 18.)

---

* M. Arago, Annuaire, &c. 1833; and Rev. J. Farquharson, Phil. Trans. 1835, p. 329.

† Journ. of Roy. Geograph. Soc. vol. vi. p. 416.

Fig. 18.



Glacier with medial and lateral moraines and with terminal cave.

ıe length of the Swiss glaciers is sometimes twenty miles, their h in the middle portion where they are broadest, occasionally or three miles; their depth or thickness sometimes more than feet. When they descend steep slopes, and precipices, or are ›d through narrow gorges, the ice is broken up, and assumes the fantastic and picturesque forms, with lofty peaks and pinnacles, ›cting above the general level. These snow-white masses are ı relieved by a dark back-ground of pines, as in the valley of nouni; and are not only surrounded with abundance of the wild odendron in full flower, but encroach still lower into the region ultivation, and trespass on fields where the tobacco-plant is ·ishing by the side of the peasant's hut.

he cause of glacier motion has of late been a subject of careful stigation and much keen controversy. Although a question of ıics, rather than of geology, it is too interesting to allow me to it by without some brief mention. De Saussure, whose travels in Alps are full of original observations, as well as sound and com·ensive general views, conceived that the weight of the ice might ufficient to urge it down the slope of the valley, if the sliding on were aided by the water flowing at the bottom. For this ıvitation theory" Charpentier, followed by Agassiz, substituted ıypothesis of dilatation. The most solid ice is always permeable to water, and penetrated by innumerable fissures and capillary tub often extremely minute. These tubes imbibe the aqueous fluid duri the day, which freezes, it is said, in the cold of the night, and expar while in the act of congelation. The distension of the whole m exerts an immense force, tending to propel the glacier in the directi of least resistance—"in other words, down the valley." This theo was opposed by Mr. Hopkins on mathematical and mechanical groun in several able papers. Among other objections, he pointed out th the friction of so enormous a body as a glacier on its bed is so gre that the vertical direction would always be that of least resistan and if a considerable distension of the mass should take place, by t action of freezing, it would tend to increase its thickness, rather th accelerate its downward progress. He also contended (and his arg ments were illustrated by many ingenious experiments) that a glaci can move along an extremely slight slope, solely by the influence gravitation, owing to the constant dissolution of ice in contact wi the rocky bottom, and the number of separate fragments into whi the glacier is divided by fissures, so that freedom of motion imparted to its several parts somewhat resembling that of an impe fect fluid. To this view Professor James Forbes objected, that grav tation would not supply an adequate cause for the sliding of solid i down slopes having an inclination of no more than four or five degre still less would it explain how the glacier advances where the chann expands and contracts. The Mer de Glace in Chamouni, for examp after being 2000 yards wide, passes through a strait only 900 yar in width. Such a gorge, it is contended, would be choked up by t advance of any solid mass, even if it be broken up into numero fragments. The same acute observer remarked, that water in t fissures and pores of glaciers cannot, and does not part with its lat heat, so as to freeze every night to a great depth, or far in the inter of the mass. Had the dilatation theory been true, the chief moti of the glacier would have occurred about sunset, when the freezi of the water must be greatest, and it had, in fact, been at first assum by those who favoured that hypothesis, that the mass moved faster the sides, where the melting of ice was promoted by the sun's he reflected from boundary precipices.

Agassiz appears to have been the first to commence, in 184 aided by a skilful engineer, M. Escher de la Linth, a series exact measurements to ascertain the laws of glacier motion, a he soon discovered, contrary to his preconceived notions, that t stream of ice moved more slowly at the sides than at the centre, a faster in the middle region of the glacier than at its extremity Professor James Forbes, who had joined Mr. Agassiz during h earlier investigations in the Alps, undertook himself an independ series of experiments, which he followed up with great perseveran

---

[*] See Système Glaciaire, by Agassiz, Guyot, and Desor, pp. 436, 437. 445. Mr. Agassiz, at p. 462., states that he published in the Deutsche Vierteljahrschrift for 1841, this result as to central motion being greater than th the sides, and was, therefore, the fi correct his own previous mistake.

rmine the laws of glacier motion. These he found to agree osely with the laws governing the course of rivers, their pro- eing greater in the centre than at the sides, and more rapid at face than at the bottom. This fact was verified by carefully a great number of marks in the ice, arranged in a straight line, gradually assumed a beautiful curve, the middle part pointing he glacier, and showing a velocity there, double or treble that lateral parts.* He ascertained that the rate of advance by vas nearly the same as by day, and that even the hourly march icy stream could be detected, although the progress might not t to more than six or seven inches in twelve hours. By the nt though invisible advance of the marks placed on the ice, " says Mr. Forbes, "was marked out as by a shadow on a dial, e unequivocal evidence which I obtained, that even whilst g on a glacier we are, day by day, and hour by hour, imper- y carried on by the resistless flow of the icy stream, filled me dmiration." (Travels in the Alps, p. 133.) In order to ex- his remarkable regularity of motion, and its obedience to laws tly analogous to those of fluids, the same writer proposed the that the ice, instead of being solid and compact, is a viscous tic body, capable of yielding to great pressure, and the more proportion as its temperature is higher, or as it approaches nearly to the melting point. He endeavours to show that this esis will account for many complicated phenomena, especially ibboned or veined structure which is every where observable ice, and might be produced by lines of discontinuity, arising the different rates at which the various portions of the semi- glacier advance and pass each other.' Many examples are ed to prove that a glacier can model itself to the form of the d over which it is forced, exactly as would happen if it possessed ain ductility, and this power of yielding under intense pressure, wn not to be irreconcileable with the idea of the ice being ently compact to break into fragments when the strain upon rts is excessive; as where the glacier turns a sharp angle, or ds upon a rapid or convex slope. The increased velocity in er is attributed partly to the greater plasticity of the ice, when posed to intense cold, and partly to the hydrostatic pressure of ater in the capillary tubes, which imbibe more of this liquid in t season.

the assumption of the ice being a rigid mass, Mr. Hopkins uted the more rapid motions in the centre to the unequal rate ich the broad stripes of ice, intervening between longitudinal s, advance; but besides that there are parts of the glacier where h fissures exist, such a mode of progression, says Mr. Forbes, cause the borders of large transverse rents or "crevasses," to gged like a saw, instead of being perfectly even and straight- .† An experiment recently made by Mr. Christie, secretary

---

Forbes. 8th Letter on Glaciers, 844.

† See Mr. Hopkins on Motion of Glaciers, Cambridge Phil. Trans. 1844,

to the Royal Society, appears to demonstrate that ice, under great pressure, possesses a sufficient degree of moulding and self-adapting power to allow it to be acted upon, as if it were a pasty substance. A hollow shell of iron an inch and a half thick, the interior being ten inches in diameter, was filled with water, in the course of a severe winter, and exposed to the frost, with the fuze-hole uppermost. A portion of the water expanded in freezing, so as to protrude a cylinder of ice from the fuze-hole; and this cylinder continued to grow inch by inch in proportion as the central nucleus of water froze. As we cannot doubt that an outer shell of ice is first formed, and then another within, the continued rise of the column through the fuze-hole must proceed from the squeezing of successive shells of ice concentrically formed, through the narrow orifice; and yet the protruded cylinder consisted of entire, and not fragmentary ice.*

The agency of glaciers in producing permanent geological changes consists partly in their power of transporting gravel, sand, and huge stones to great distances, and partly in the smoothing, polishing, and scoring of their rocky channels, and the boundary walls of the valleys through which they pass. At the foot of every steep cliff or precipice in high Alpine regions, a talus is seen of rocky fragments detached by the alternate action of frost and thaw. If these loose masses, instead of accumulating on a stationary base, happen to fall upon a glacier, they will move along with it, and, in place of a single heap they will form in the course of years a long stream of blocks. If a glacier be 20 miles long, and its annual progression about 500 feet, it will require about two centuries for a block thus lodged upon its surface to travel down from the higher to the lower regions, or to the extremity of the icy mass. This terminal point remains usually unchanged from year to year, although every part of the ice is in motion, because the liquefaction by heat is just sufficient to balance the onward movement of the glacier, which may be compared to an endless file of soldiers, pouring into a breach, and shot down as fast as they advance.

The stones carried along on the ice are called in Switzerland the "moraines" of the glacier. There is always one line of blocks on each side or edge of the icy stream, and often several in the middle, where they are arranged in long ridges on mounds, often several yards high. (See fig. 18. p. 323.) The cause of these "medial moraines" was first explained by Agassiz, who referred them to the confluence of tributary glaciers.† Upon the union of two streams of ice, the right lateral moraine of one of the streams comes in contact with the left lateral moraine of the other, and they afterwards move on together, in the centre, if the confluent glaciers are equal in size, or nearer to one side if unequal.

---

and Phil. Mag. 1845. Some of the late concessions of this author as to a certain plasticity in the mass, appear to me to make the difference between him and Professor Forbes little more than one of degree. (For the latest summary of Prof. Forbes' views, see Phil. Trans. 1846, pt 2.)

[*] This experiment is cited by Mr. Forbes, Phil. Trans. 1846, p. 206.; and I have conversed with Mr. Christie on the subject.

[†] Etudes sur les Glaciers, 1840.

All sand and fragments of soft stone which fall through fissures and reach the bottom of the glaciers, or which are interposed between the glacier and the steep sides of the valley, are pushed along, and ground down into mud, while the larger and harder fragments have their angles worn off. At the same time the fundamental and boundary rocks are smoothed and polished, and often scored with parallel furrows, or with lines and scratches produced by hard minerals, such as crystals of quartz, which act like the diamond upon glass.* This effect is perfectly different from that caused by the action of water, or a muddy torrent forcing along heavy fragments; for when stones are fixed firmly in the ice, and pushed along by it under great pressure, in straight lines, they scoop out long rectilinear furrows or grooves parallel to each other.† The discovery of such markings at various heights far above the surface of the existing glaciers and for miles beyond their present terminations, affords geological evidence of the former extension of the ice beyond its present limits in Switzerland and other countries.

The moraine of the glacier, observes Charpentier, is entirely devoid of stratification, for there has been no sorting of the materials, as in the case of sand, mud, and pebbles, when deposited by running water. The ice transports indifferently, and to the same spots, the heaviest blocks and the finest particles, mingling all together, and leaving them in one confused and promiscuous heap wherever it melts.‡

Icebergs.—In countries situate in high northern latitudes, like Spitzbergen, between 70° and 80° N., glaciers, loaded with mud and rock, descend to the sea, and there huge fragments of them float off and become icebergs. Scoresby counted 500 of these bergs drifting along in latitudes 69° and 70° N., which rose above the surface from the height of 100 to 200 feet, and measured from a few yards to a mile in circumference.§ Many of them were loaded with beds of earth and rock of such thickness, that the weight was conjectured to be from 50,000 to 100,000 tons. Specimens of the rocks were obtained, and among them were granite, gneiss, mica-schist, clay-slate, granular felspar, and greenstone. Such bergs must be of great magnitude; because the mass of ice below the level of the water is about eight times greater than that above. Wherever they are dissolved, it is evident that the "moraine" will fall to the bottom of the sea. In this manner may submarine valleys, mountains, and platforms become strewed over with gravel, sand, mud, and scattered blocks of foreign rock, of a nature perfectly dissimilar from all in the vicinity, and which may have been transported across unfathomable abysses. If the bergs happen to melt in still water, so that the earthy and stony materials may fall tranquilly to the bottom, the deposit will probably be unstratified, like the terminal moraine of a glacier; but whenever the materials are under the influence of a curre of water as they fall, they will be sorted and arranged according their relative weight and size, and therefore more or less perfect stratified.

---

* See Manual of Geol. ch. xi.

† Agassiz, Jam. Ed. New Phil. Journ. No. 54. p. 388.

‡ Charpentier, Ann. des Mines, tom. viii.; see also Papers by MM. Venetz and Agassiz.

§ Voyage in 1822, p. 233.

In a former chapter it was stated that some ice islands have bee known to drift from Baffin's Bay to the Azores, and from the Sout Pole to the immediate neighbourhood of the Cape of Good Hope, s that the area over which the effects of moving ice may be experienced comprehends a large portion of the globe.

We learn from Von Buch that the most southern point on the co tinent of Europe at which a glacier comes down to the sea is i Norway, in lat. 67° N.[*] But Mr. Darwin has shown, that the extend to the sea, in South America, in latitudes more than 20 nearer the equator than in Europe; as, for example, in Chili, where in the Gulf of Penas, lat. 46° 40′ S., or the latitude of central France and in Sir George Eyre's Sound, in the latitude of Paris, they giv origin to icebergs, which were seen in 1834 carrying angular piece of granite, and stranding them in fiords, where the shores were com posed of clay-slate.[†] A large proportion, however, of the ice-island seen floating both in the northern and southern hemispheres, ar probably not generated by glaciers, but rather by the accumulatio of coast ice. When the sea freezes at the base of a lofty precipice the sheet of ice is prevented from adhering to the land by the ris and fall of the tide. Nevertheless, it often continues on the shore the foot of the cliff, and receives accessions of drift snow blown fr the land. Under the weight of this snow the ice sinks slowly if th water be deep, and the snow is gradually converted into ice by parti liquefaction and re-congelation. In this manner, islands of ice great thickness and many leagues in length, originate, and are eve tually blown out to sea by off-shore winds. In their interior enclosed many fragments of stone which had fallen upon them fr overhanging cliffs during their formation. Such floating icebergs commonly flat-topped, but their lower portions are liable to melt latitudes where the ocean at a moderate depth is usually warmer th the surface water and the air. Hence their centre of gravity chang continually, and they turn over and assume very irregular shapes.

In a voyage of discovery made in the antarctic regions in 18 a dark-coloured angular mass of rock was seen imbedded in an i berg, drifting along in mid ocean in lat. 61° S. That part of rock which was visible was about 12 feet in height, and from 5 in width, but the dark colour of the surrounding ice indicated much more of the stone was concealed. A sketch made by Mr. M nab, when the vessel was within a quarter of a mile of it, is published.[‡] This iceberg, one of many observed at sea on same day, was between 250 and 300 feet high, and was no less th 1400 miles from any certainly known land. It is exceedingly i probable, says Mr. Darwin, in his notice of this phenomenon, th any land will hereafter be discovered within 100 miles of the spot, and it must be remembered that the erratic was still firmly fixed in ice, and may have sailed for many a league farther before it dropped to the bottom.[*]

---

[*] Travels in Norway.

[†] Darwin's Journal, p. 283.

[‡] Journ. of Roy. Geograph. vol. ix. p. 526.

Captain Sir James Ross, in his antarctic voyage, in 1841-2 and 3, saw multitudes of icebergs transporting stones and rocks of various sizes, with frozen mud, in high southern latitudes. His companion, Dr. J. Hooker, informs me that he came to the conclusion, that most of the southern icebergs have stones in them, although they are usually concealed from view by the quantity of snow which falls upon them.

In the account given by Messrs. Dease and Simpson, of their recent arctic discoveries, we learn that in lat. 71° N., long. 156° W., they found "a long low spit, named Point Barrow, composed of gravel and coarse sand, in some parts more than a quarter of a mile broad, which the pressure of the ice had forced up into numerous mounds, that, viewed from a distance, assumed the appearance of huge boulder rocks."[†]

This fact is important, as showing how masses of drift ice, when stranding on submarine banks, may exert a lateral pressure capable of bending and dislocating any yielding strata of gravel, sand or mud. The banks on which icebergs occasionally run aground between Baffin's Bay and Newfoundland, are many hundred feet under water, and the force with which they are struck will depend not so much on the velocity as the momentum of the floating ice-islands. The same berg is often carried away by a change of wind, and then driven back again upon the same bank, or it is made to rise and fall by the waves of the ocean, so that it may alternately strike the bottom with its whole weight, and then be lifted up again, until it has deranged the superficial beds over a wide area. In this manner the geologist may account, perhaps, for the circumstance that in Scandinavia, Scotland, and other countries where erratics are met with, the beds of sand, loam, and gravel are often vertical, bent, and contorted into the most complicated folds, while the underlying strata, although composed of equally pliant materials, are horizontal. But some of these curvatures of loose strata may also have been due to repeated alternations of layers of gravel and sand, ice and snow, the melting of the latter having caused the intercalated beds of indestructible matter to assume their present anomalous position.

There can be little doubt that icebergs must often break off the peaks and projecting points of submarine mountains, and must grate upon and polish their surface, furrowing or scratching them in precisely the same way as we have seen that glaciers act on the solid rocks over which they are propelled.[‡]

---

[*] Journ. of Roy. Geograph. Soc. vol. ix. p. 529.

[†] Ibid. vol. viii. p. 221.

[‡] In my Travels in N. America, 19, 23, &c., and Second Visit to the U. S., vol. i. ch. 2., also in my Manual of Geology, a more full account of the action of floating ice and coast-ice, and its bearing on geology, will be found.

To conclude; it appears that large stones, mud, and grav carried down by the ice of rivers, estuaries, and glaciers, into th where the tides and currents of the ocean, aided by the wind, them to drift for hundreds of miles from the place of their Although it will belong more properly to the seventh and chapters, to treat of the transportation of solid matter by the ments of the ocean, I shall add here what I have farther to this subject in connection with ice.

The saline matter which sea-water holds in solution, preven congelation except where the most intense cold prevails. Bu drifting of the snow from the land often renders the surface brackish near the coast, so that a sheet of ice is readily formed and by this means a large quantity of gravel is frequently con from place to place, and heavy boulders also, when the coast packed into dense masses. Both the large and small stones, thu veyed, usually travel in one direction like shingle-beaches, was observed to take place on the coast of Labrador and Gulf Lawrence, between the latitudes 50° and 60° N., by Capt. Bay during his late survey. The line of coast alluded to, is strewed for a distance of 700 miles with iceborne boulders, often 6 fe diameter, which are for the most part on their way from nor south, or in the direction of the prevailing current. Some points this coast have been observed to be occasionally deserted, and again at another season thickly bestrewed with erratics.

The accompanying drawing (fig. 19.), for which I am indebted

Fig. 19.



Boulders, chiefly of granite, stranded by ice on the coast of Labrador, between lat. [illegible]
(Lieut. Bowen, R. N.)

Lieut. Bowen, R. N., represents the ordinary appearance of the Lab dor coast, between the latitudes of 50° and 60° N. Countless bloc chiefly granitic, and of various sizes, are seen lying between high low-water mark. Capt. Bayfield saw similar masses carried by through the Straits of Belle Isle, between Newfoundland and the American continent, which he conceives may have travelled in the course of years from Baffin's Bay, a distance which may be compared in our hemisphere to the drifting of erratics from Lapland and Iceland as far south as Germany, France, and England.

It may be asked, in what manner have these blocks been orginally detached? We may answer that some have fallen from precipitous cliffs, others have been lifted up from the bottom of the sea, adhering by their tops to the ice, while others have been brought down by rivers and glaciers.

The erratics of North America are sometimes angular, but most of them have been rounded either by friction or decomposition. The granite of Canada, as before remarked (p. 221.), has a tendency to concentric exfoliation, and scales off in spheroidal coats when exposed to the spray of the sea during severe frosts. The range of the thermometer in that country usually exceeds, in the course of the year, 100°, and sometimes 120° F.; and, to prevent the granite used in the buildings of Quebec from peeling off in winter, it is necessary to oil and paint the squared stones.

In parts of the Baltic, such as the Gulf of Bothnia, where the quantity of salt in the water amounts in general to one fourth only of that in the ocean, the entire surface freezes over in winter to the depth of 5 or 6 feet. Stones are thus frozen in, and afterwards lifted up about 3 feet perpendicularly on the melting of the snow in summer, and then carried by floating ice-islands to great distances. Professor Von Baer states, in a communication on this subject to the Academy of St. Petersburg, that a block of granite, weighing a million of pounds, was carried by ice during the winter of 1837–8 from Finland to the island of Hockland, and two other huge blocks were transported about the years 1806 and 1814 by packed ice on the south coast of Finland, according to the testimony of the pilots and inhabitants, one block having travelled about a quarter of a mile, and lying about 18 feet above the level of the sea.*

More recently Dr. Forchhammer has shown that in the Sound, the Great Belt, and other places near the entrance of the Baltic, ground-ce forms plentifully at the bottom, and then rises to the surface, charged with sand, gravel, stones, and sea-weed. Sheets of ice, also, rith included boulders, are driven up on the coast during storms, nd "packed" to a height of 50 feet. To the motion of such masses, ut still more to that of the ground-ice, the Danish professor atibutes the striation of rocky surfaces, forming the shores and bed of he sea, and he relates a striking fact to prove that large quantities of ocky fragments are annually carried by ice out of the Baltic. "In he year 1807," he says, "at the time of the bombardment of the anish fleet, an English sloop of war, riding at anchor in the roads at openhagen, blew up. In 1844, or thirty-seven years afterwards, ne of our divers, known to be a trustworthy man, went down to save whatever might y[illegible] ren[illegible] a [illegible] [illegible]l. He found the space between de[illegible] entire, but covered with [illegible]ocks from 6 to 8 cubic feet in size, and some of them heaped [illegible] upon the other. He also affirmed, that all the sunk ships which he [illegible]d visited in the Sound, were in like manner [illegible]d over with blocks."

---

* Jam. Ed. New Phil. Journ. No. xlviii. p. 439.

Dr. Forchhammer also infor[illegible] that during an intense frost in February, 1844, the Sound [illegible]s [illegible]d[illegible]nly frozen over, and sheets of ice, driven by a sto[illegible] [illegible]v[illegible] e[illegible] [illegible]ped up at the bottom of the Bay of Täarbeijk, threa[illegible]n[illegible] to [illegible]oy a fishing-village on the shore. The whole was soon [illegible]t[illegible] into one mass, and forced up on the beach, forming a [illegible] re t[illegible]an 16 feet high, which threw down the walls of s[illegible]e[illegible]ou[illegible] "When I visited the spot next day, I saw ridges of i[illegible], [illegible] pebbles, not only on the shore, but extending far out into [illegible]bott[illegible] of the sea, showing how greatly its bed had been chang[illegible] a[illegible] how [illegible]asily, where it is composed of rock, it may be furrowed [illegible]s[illegible]ed by stones firmly fixed in the moving ice."*

CHAPTER XVI.

PHENOMENA OF SPRINGS.

Origin of springs—Artesian wells—Borings at Paris—Distinct causes by which mineral and thermal waters may be raised to the surface—Their connection with volcanic agency—Calcareous springs—Travertin of the Elsa—Baths of San Vignone and of San Filippo, near Radicofani—Spheroidal structure in travertin—Lake of the Solfatara, near Rome—Travertin at Cascade of Tivoli—Gypseous, siliceous, and ferruginous springs—Brine springs—Carbonated springs—Disintegration of granite in Auvergne—Petroleum springs—Pitch lake of Trinidad.

Origin of springs.—THE action of running water on the surface of the land having been considered, we may next turn our attention to what may be termed "the subterranean drainage," or the phenomena of springs. Every one is familiar with the fact, that certain porous soils, such as loose sand and gravel, absorb water with rapidity, and that the ground composed of them soon dries up after heavy showers. If a well be sunk in such soils, we often penetrate to considerable depths before we meet with water; but this is usually found on our approaching the lower parts of the formation, where it rests on some impervious bed; for here the water, unable to make its way downwards in a direct line, accumulates as in a reservoir, and is ready to ooze out into any opening which may be made, in the same manner as we see the salt water flow into, and fill, any hollow which we dig in the sands of the shore at low tide.

---

* Bulletin de la Soc. Géol. de France, 1847, tom. iv. [illegible] 1182, 1183.

The facility with which water can percolate loose and gravelly soils is clearly illustrated by the effect of the tides in the Thames between Richmond and London. The river, in this part of its course, flows through a bed of gravel overlying clay, and the porous superstratum is alternately saturated by the water of the Thames as the tide rises, and then drained again to the distance of several hundred feet from the banks when the tide falls, so that the wells in this tract regularly ebb and flow.

If the transmission of water through a porous medium be so rapid, we cannot be surprised that springs should be thrown out on the side of a hill, where the upper set of strata consist of chalk, sand, or other permeable substances, while the subjacent are composed of clay or other retentive soils. The only difficulty, indeed, is to explain why the water does not ooze out every where along the line of junction of the two formations, so as to form one continuous land-soak, instead of a few springs only, and these far distant from each other. The principal cause of this concentration of the waters at a few points is, first, the frequency of rents and fissures, which act as natural drains; secondly, the existence of inequalities in the upper surface of the impermeable stratum, which lead the water, as valleys do on the external surface of a country, into certain low levels and channels.

That the generality of springs owe their supply to the atmosphere is evident from this, that they become languid, or entirely cease to flow, after long droughts, and are again replenished after a continuance of rain. Many of them are probably indebted for the constancy and uniformity of their volume to the great extent of the subterranean reservoirs with which they communicate, and the time required for these to empty themselves by percolation. Such a gradual and regulated discharge is exhibited, though in a less perfect degree, in every great lake which is not sensibly affected in its level by sudden showers, but only slightly raised; so that its channel of efflux, instead of being swollen suddenly like the bed of a torrent, is enabled to carry off the surplus water gradually.

Much light has been thrown, of late years, on the theory of springs, by the boring of what are called by the French "Artesian wells," because the method has long been known and practised in Artois; and it is now demonstrated that there are sheets, and in some places currents of fresh water, at various depths in the earth. The instrument employed in excavating these wells is a large auger, and the cavity bored is usually from three to four inches in diameter. If a hard rock is met with, it is first triturated by an iron rod, and the materials, being thus reduced to small fragments or powder, are readily extracted. To hinder the sides of the well from falling in, as also to prevent the spreading of the ascending water in the surrounding soil, a jointed pipe is introduced, formed of wood in Artois, but in other countries more commonly of metal. It frequently happens that, after passing through hundreds of feet of retentive soils, a water-bearing stratum is at length pierced, when the fluid immediately ascends to the surface and flows over. The first rush of the water up the tube is often violent, so that for a time the water plays like a fountain, and then, sinking, continues to flow over tranquilly, or sometimes remains stationary at a certain depth below the orifice of the well. This spouting of the water in the first instance is probably owing to the disengagement of air and carbonic acid gas, for both of these have been seen to bubble up with the water.*

At Sheerness, at the mouth of the Thames, a well was bored on a low tongue of land near the sea, through 300 feet of the blue clay of London, below which a bed of sand and pebbles was entered, belonging, doubtless, to the plastic clay formation: when this stratum was pierced, the water burst up with impetuosity, and filled the well. By another perforation at the same place, the water was found at the depth of 328 feet below the surface clay; it first rose rapidly to the height of 189 feet, and then, in the course of a few hours, ascended to an elevation of eight feet above the level of the ground. In [illegible] a well was dug at Fulham, near the Thames, at the Bishop of London's, to the depth of 317 feet, which, after traversing the tertiary strata, was continued through 67 feet of chalk. The water immediately rose to the surface, and the discharge was about [illegible] gallons per minute. In the garden of the Horticultural Society at Chiswick, the borings passed through 19 feet of gravel, 242½ feet of clay and loam, and 67½ feet of chalk, and the water then rose to the surface from a depth of 329 feet.† At the Duke of Northumberland's, above Chiswick, the borings were carried to the extraordinary depth of 620 feet, so as to enter the chalk, when a considerable volume of water was obtained, which rose four feet above the surface of the ground. In a well of Mr. Brooks, at Hammersmith, the rush of water from a depth of 360 feet was so great, as to inundate several buildings and do considerable damage; and at Tooting, a sufficient stream was obtained to turn a wheel, and raise the water to the upper stories of the houses.‡ In 1838, the total supply obtained from the chalk near London was estimated at six million gallons a day, and, in 1851, at nearly double that amount, the increase being accompanied by an average fall of no less than two feet a year in the level to which the water rose. The water stood commonly, in 1822, at high-water mark, and had sunk in 1851 to 45, and in some wells to 65 feet below high-water mark.§ This fact shows the limited capacity of the subterranean reservoir. In the last of three wells bored through the chalk at Tours, to the depth of several hundred feet, the water rose 32 feet above the level of the soil, and the discharge amounted to 300 cubic yards of water every twenty-four hours.‖

By way of experiment, the sinking of a well was commenced at Paris in 1834, which had reached, in November, 1839, a depth of more than 1600 English feet, and yet no water ascended to the surface. The government were persuaded by M. Arago to persevere, if necessary, to the depth of more than 2000 feet; but when they had descended above 1800 English feet below the surface, the water rose through the tube (which was about ten inches in diameter), so as to discharge half a million of gallons of limpid water every twenty-four hours. The temperature of the water increased at the rate of 1° 8′ F. for every 101 English feet, as they went down, the result agreeing very closely with the anticipations of the scientific advisers of this most spirited undertaking.

---

* Consult J. Prestwich, Water-bearing Strata around London. 1851. (Van Voorst.)

† Sabine, Journ. of Sci. No. xxxiii. p. 72. 1824.

‡ Héricart de Thury, "Puits Forés," p. 49.

§ Prestwich, p. 69.

‖ Bull. de la Soc. Géol. de France, tom. iii. p. 194.

Mr. Briggs, the British consul in Egypt, obtained water between Cairo and Suez, in a calcareous sand, at the depth of thirty feet; but it did not rise in the well.* But other borings in the same desert, of variable depth, between 50 and 300 feet, and which passed through alternations of sand, clay, and siliceous rock, yielded water at the surface.†

The rise and overflow of the water in Artesian wells is generally referred, and apparently with reason, to the same principle as the play of an artificial fountain. Let the porous stratum or set of strata, *a a*, rest on the impermeable rock *d*, and be covered by another mass of an impermeable nature. The whole mass *a a* may easily, in such a position, become saturated with water, which may descend from its higher and exposed parts — a hilly region to which clouds are attracted, and where rain falls in abundance. Suppose that at some point, as at *b*, an opening be made, which gives a free passage upwards to the waters confined in *a a*, at so low a level that they are subjected to the pressure of a considerable column of water collected in the more elevated portion of the same stratum. The water will then rush out, just as the liquid from a large barrel which is tapped, and it will rise to a height corresponding to the level of its point of departure, or, rather, to a height which balances the pressure previously exerted by the confined waters against the roof and sides of the stratum or reservoir *a a*. In like manner, if there happen to be a natural fissure *c*, a spring will be produced at the surface on precisely the same principle.

Fig. 20.



Among the causes of the failure of Artesian wells, we may mention those numerous rents and faults which abound in some rocks, and the deep ravines and valleys by which many countries are traversed; for, when these natural lines of drainage exist, there remains a small quantity only of water to escape by artificial issues. We are also liable to be baffled by the great thickness either of porous or impervious strata, or by the dip of the beds, which may car waters from adjoining high lands to some trough in an direction, as when the borings are made at the foot of an es where the strata incline inwards, or in a direction opposit face of the cliffs.

---

* Boué Résumé des Prog. de la Géol. en 1832, p. 184.

† Seventh Rep. Brit. Ass. 1837, p. 66.

The mere distance of hills or mountains need not discou from making trials; for the waters which fall on these high readily penetrate to great depths through highly inclined or strata, or through the fissures of shattered rocks, and after for a great distance, must often re-ascend and be brought by other fissures, so as to approach the surface in the lower Here they may be concealed beneath a covering of un horizontal beds, which it may be necessary to pierce in reach them. It should be remembered, that the course flowing under ground bears but a remote resemblance to rivers on the surface, there being, in the one case, a constan from a higher to a lower level from the source of the strea sea; whereas, in the other, the water may at one time sink the level of the ocean, and afterwards rise again high above

Among other curious facts ascertained by aid of the bo proved that in strata of different ages and compositions, often open passages by which the subterranean waters Thus, at St. Ouen, in France, five distinct sheets of wa intersected in a well, and from each of these a supply obtai the third water-bearing stratum, at the depth of 150 feet, was found in which the borer fell suddenly about a foot, an the water ascended in great volume.* The same falling o strument, as in a hollow space, has been remarked in Eng other countries. At Tours, in 1830, a well was perfora through the chalk, when the water suddenly brought up depth of 364 feet, a great quantity of fine sand, with much matter and shells. Branches of a thorn, several inches lo blackened by their stay in the water, were recognised, as stems of marsh plants, and some of their roots, which white, together with the seeds of the same in a state of pres which showed that they had not remained more than thre months in the water. Among the seeds were those of th plant *Galium uliginosum*; and among the shells, a freshwat (*Planorbis marginatus*), and some land species, as *Helix* and *H. striata*. M. Dujardin, who, with others, observed nomenon, supposes that the waters had flowed from some Auvergne or the Vivarais since the preceding autumn.†

An analogous phenomenon is recorded at Reimke, near in Westphalia, where the water of an Artesian well bro from a depth of 156 feet, several small fish, three or four inc the nearest streams in the country being at the distance leagues.‡

In both cases it is evident that water had penetrated depths, not simply by filtering through a porous mass, for then it would have left behind the shells, fish, and fragments of plants, but by flowing through some open channels in the earth. Such examples may suggest the idea that the leaky beds of rivers are often the feeders of springs.

---

* H. de Thury, p. 295.

† Bull. de la Soc. Géol. de France, tom. i. p. 93.

‡ Ibid. tom

MINERAL AND THERMAL SPRINGS.

Almost all springs, even those which we consider the purest, are impregnated with some foreign ingredients, which, being in a state of chemical solution, are so intimately blended with the water, as not to affect its clearness, while they render it, in general, more agreeable to our taste, and more nutritious than simple rain-water. But the springs called mineral contain an unusual abundance of earthy matter in solution, and the substances with which they are impregnated correspond remarkably with those evolved in a gaseous form by volcanos. Many of these springs are thermal, *i. e.* their temperature is above the mean temperature of the place, and they rise up through all kinds of rock; as, for example, through granite, gneiss, limestone, or lava, but are most frequent in volcanic regions, or where violent earthquakes have occurred at eras comparatively modern.

The water given out by hot springs is generally more voluminous and less variable in quantity at different seasons than that proceeding from any others. In many volcanic regions, jets of steam, called by the Italians "stufas," issue from fissures, at a temperature high above the boiling point, as in the neighbourhood of Naples, and in the Lipari Isles, and are disengaged unceasingly for ages. Now, if such columns of steam, which are often mixed with other gases, should be condensed before reaching the surface by coming in contact with strata filled with cold water, they may give rise to thermal and mineral springs of every degree of temperature. It is, indeed, by this means only, and not by hydrostatic pressure, that we can account for the rise of such bodies of water from great depths; nor can we hesitate to admit the adequacy of the cause, if we suppose the expansion of the same elastic fluids to be sufficient to raise columns of lava to the lofty summits of volcanic mountains. Several gases, the carbonic acid in particular, are disengaged in a free state from the soil in many districts, especially in the regions of active or extinct volcanos; and the same are found more or less intimately combined with the waters of all mineral springs, both cold and thermal. Dr. Daubeny and other writers have remarked, not only that these springs are most abundant in volcanic regions, but that when remote from them, their site usually coincides with the position of some great derangement in the strata; a fault, for example,. or great fissure, ndicating that a channel of communication has been opened with the nterior of the earth at same former period of local convulsion. It is lso ascertained that at great heights in the Pyrenees and Himalaya mountains, hot springs burst out from granitic rocks, and they are bundant in the Alps also, these chains having all been disturbed and dislocated at times comparatively modern, as can be show independent geological evidence.

The small area of volcanic regions may appear, at first vie present an objection to these views, but not so when we include ea quakes among the effects of igneous agency. A large proportio the land hitherto explored by geologists, can be shown to have rent or shaken by subterranean movements since the oldest tert strata were formed. It will also be seen, in the sequel, that springs have burst out, and others have had the volume of t waters augmented, and their temperature suddenly raised after ea quakes, so that the description of these springs might almost equal propriety have been given under the head of "igneous cau as they are agents of a mixed nature, being at once igneous aqueous.

But how, it will be asked, can the regions of volcanic heat forth such inexhaustible supplies of water? The difficulty of solv this problem would, in truth, be insurmountable, if we believed all the atmospheric waters found their way into the basin of ocean; but in boring near the shore, we often meet with stream fresh water at the depth of several hundred feet below the sea le and these probably descend, in many cases, far beneath the botto the sea, when not artificially intercepted in their course. Yet, much greater may be the quantity of salt water which sinks bene the floor of the ocean, through the porous strata of which it is composed, or through fissures rent in it by earthquakes. Af penetrating to a considerable depth, this water may encounter a h of sufficient intensity to convert it into vapour, even under the hi pressure to which it would then be subjected. This heat wo probably be nearest the surface in volcanic countries, and farth from it in those districts which have been longest free from eruptio or earthquakes.

It would follow from the views above explained, that there m be a twofold circulation of terrestrial waters; one caused by sol heat, and the other by heat generated in the interior of our plan We know that the land would be unfit for vegetation, if deprived the waters raised into the atmosphere by the sun; but it is also tr that mineral springs are powerful instruments in rendering the surfa subservient to the support of animal and vegetable life. Their he is said to promote the development of the aquatic tribes in ma parts of the ocean, and the substances which they carry up from t bowels of the earth to the habitable surface, are of a nature and in form which adapts them peculiarly for the nutrition of animals a plants.

As these springs derive their chief importance to the geolog from the quantity and quality of the earthy materials which, li volcanos, they convey from below upwards, they may properly considered in reference to the ingredients which they hold in soluti These consist of a great variety of substances; but chiefly salts w bases of lime, magnesia, alumine, and iron, combined with carbo sulphuric, and muriatic acids. Muriate of soda, silica, and f carbonic acid are frequently present; also springs of petroleum or liquid bitumen, and of naphtha.

Calcareous springs.—Our first attention is naturally directed to springs which are highly charged with calcareous matter, for these produce a variety of phenomena of much interest in geology. It is known that rain-water collecting carbonic acid from the atmosphere has the property of dissolving the calcareous rocks over which it flows, and thus, in the smallest ponds and rivulets, matter is often supplied for the earthy secretions of testacea, and for the growth of certain plants on which they feed. But many springs hold so much carbonic acid in solution, that they are enabled to dissolve a much larger quantity of calcareous matter than rain-water; and when the acid is dissipated in the atmosphere, the mineral ingredients are thrown down, in the form of porous tufa or of more compact travertin.*

Auvergne.—Calcareous springs, although most abundant in limestone districts, are by no means confined to them, but flow out indiscriminately from all rock formations. In central France, a district where the primary rocks are unusually destitute of limestone, springs copiously charged with carbonate of lime rise up through the granite and gneiss. Some of these are thermal, and probably derive their origin from the deep source of volcanic heat, once so active in that region. One of these springs, at the northern base of the hill upon which Clermont is built, issues from volcanic peperino, which rests on granite. It has formed, by its incrustations, an elevated mound of travertin, or white concretionary limestone, 240 feet in length, and, at its termination, sixteen feet high and twelve wide. Another encrusting spring in the same department, situated at Chaluzet, near Pont Gibaud, rises in a gneiss country, at the foot of a regular volcanic cone, at least twenty miles from any calcareous rock. Some masses of tufaceous deposit, produced by this spring, have an oolitic texture.

Valley of the Elsa.—If we pass from the volcanic district of France to that which skirts the Apennines in the Italian peninsula, we meet with innumerable springs which have precipitated so much calcareous matter, that the whole ground in some parts of Tuscany is coated over with tufa and travertin, and sounds hollow beneath the foot.

In other places in the same country, compact rocks are seen descending the slanting sides of hills, very much in the manner of lava currents, except that they are of a white colour and terminate abruptly when they reach the course of a river. These consist of a calcareous precipitate from springs, some of which are still flowing, while others have disappeared or changed their position. Such masses are frequent on the slope of the hills which bound the valley of the Elsa, one of the tributaries of the Arno, which flows near Colle, through a valley several hundred feet deep, shaped out of a lacustrine formation, containing fossil shells of existing speci I observed here that the travertin was unconformable to the lacustrin beds, its inclination according with the slope of the sides of th valley. One of the finest examples which I saw was at the Molin delle Caldane, near Colle. The Sena, and several other sma rivulets which feed the Elsa, have the property of encrusting wo and herbs with calcareous stone. In the bed of the Elsa itself, aquati plants, such as Charæ, which absorb large quantities of carbonate o lime, are very abundant.

---

* See Glossary, "Tufa," "Travertin."

Baths of San Vignone.—Those persons who have merely seen the action of petrifying waters in England, will not easily form an adequate conception of the scale on which the same process is exhibited in those regions which lie nearer to the active centres of volcanic disturbance. One of the most striking examples of the rapid precipitation of carbonate of lime from thermal waters, occurs in the hill of San Vignone in Tuscany, at a short distance from Radicofani, and only a few hundred yards from the high road between Sienna and Rome. The spring issues from near the summit of a rocky hill, about 100 feet in height. The top of the hill stretches in a gently inclined platform to the foot of Mount Amiata, a lofty eminence, which consists in great part of volcanic products. The fundamental rock, from which the spring issues, is a black slate, with serpentine (*b b*, fig. 21.), belonging to the older Apennine formation. The water is hot, has a strong taste, and, when not in very small quantity, is of a bright green colour. So rapid is the deposition near the source, that in the bottom of a conduit-pipe for carrying off the water to the baths, and which is inclined at an angle of 30°, half a foot of solid travertin is formed every year. A more compact rock is produced where the water flows slowly; and the precipitation in winter, when there is least evaporation, is said to be more solid, but less in quantity by one fourth, than in summer. The rock is generally white; some parts of it are compact, and ring to the hammer; others are cellular, and with such cavities as are seen in the carious part of bone or the siliceous millstone of the Paris basin. A portion of it also below the village of San Vignone consists of incrustations of long vegetable tubes, and may be called tufa. Some-

Baths of San Vignone.

Fig. 21.



Section of travertin, San Vignone.

ɜs the travertin assumes precisely the botryoidal and mammillary ns, common to similar deposits in Auvergne, of a much older ; and, like them, it often scales off in thin, slightly undulating ɜrs.

\ large mass of travertin (*c*, fig. 21.) descends the hill from the nt where the spring issues, and reaches to the distance of about f a mile east of San Vignone. The beds take the slope of the hill about an angle of 6°, and the planes of stratification are pertly parallel. One stratum, composed of many layers, is of a npact nature, and fifteen feet thick; it serves as an excellent ilding stone, and a mass of fifteen feet in length was, in 1828, t out for the new bridge over the Orcia. Another branch of it fig. 21.), descends to the west, for 250 feet in length, of varying ckness, but sometimes 200 feet deep: it is then cut off by the small er Orcia, as some glaciers in Switzerland descend into a valley l their progress is suddenly arrested by a transverse stream of iter.

The abrupt termination of the mass of rock at the river, where thickness is undiminished, clearly shows that it would proceed ich farther if not arrested by the stream, over which it impends ghtly. But it cannot encroach upon the channel of the Orcia, ing constantly undermined, so that its solid fragments are seen ewed amongst the alluvial gravel. However enormous, therefore, e mass of solid rock may appear which has been given out by this igle spring, we may feel assured that it is insignificant in volume ien compared to that which has been carried to the sea since the ne when it began to flow. What may have been the length of that riod of time we have no data for conjecturing. In quarrying the ivertin, Roman tiles have been sometimes found at the depth of five six feet.

Baths of San Filippo.—On another hill, not many miles from at last mentioned, and also connected with Mount Amiata, the mmit of which is about three miles distant, are the celebrated baths San Filippo. The subjacent rocks consist of alternations of black ite, limestone, and serpentine. There are three warm springs conining carbonate and sulphate of lime, and sulphate of magnesia. ie water which supplies the baths falls into a pond, where it has en known to deposit a solid mass *thirty feet thick* in about *twenty* *ırs.*[*] A manufactory of medallions in basso-relievo is carried on these baths. The water is conducted by canals into several pits, which it deposits travertin and crystals of sulphate of lime. After ng thus freed from its grosser parts, it is conveyed by a tube the summit of a small chamber, and made to fall through a ce of ten or twelve feet. The current is broken in its descent numerous crossed sticks, by which the spray is dispersed around m certain moulds, which are rubbed lightly over with a solution soap, and a deposition of solid matter like marble is the result, yielding a beautiful cast of the figures formed in the mould. T geologist may derive from these experiments considerable ligh regard to the high slope of the strata at which some semi-crystal precipitations can be formed; for some of the moulds are disp almost perpendicularly, yet the deposition is nearly equal in parts.

---

[*] Dr. Grosse on the Baths of San Filippo, Ed. Phil. Journ. vol. ii. p. 292.

A hard stratum of stone, about a foot in thickness, is obtained f the waters of San Filippo in four months; and, as the springs powerful, and almost uniform in the quantity given out, we are at loss to comprehend the magnitude of the mass which descends hill, which is a mile and a quarter in length and the third of a in breadth, in some places attaining a thickness of 250 feet at le To what length it might have reached it is impossible to conject as it is cut off, like the travertin of San Vignone, by a small stre where it terminates abruptly. The remainder of the matter held solution is carried on probably to the sea.

Spheroidal structure in travertin.—But what renders this roc limestone of peculiar interest to the geologist, is the spheroidal f which it assumes, analogous to that of the cascade of Tivoli, aft wards to be described. (See fig. 22. p. 244.) The lamination of so of the concentric masses is so minute that sixty may be counted the thickness of an inch, yet, notwithstanding these marks of grad and successive deposition, sections are sometimes exhibited of what might seem to be perfect spheres. This tendency to a mammillary and globular structure arises from the facility with which the calcareous matter is precipitated in nearly equal quantities on all sides of any fragment of shell or wood, or any inequality of the surface over which the mineral water flows, the form of the nucleus being readily transmitted through any number of successive envelopes. But these masses can never be perfect spheres, although they often appear such when a transverse section is made in any line not in the direction of the point of attachment. There are, indeed, occasionally seen small oolitic and pisolitic grains, of which the form is globular; for the nucleus, having been for a time in motion in the water, has received fresh accessions of matter on all sides.

In the same manner I have seen, on the vertical walls of large steam-boilers, the heads of nails or rivets covered by a series of enveloping crusts of calcareous matter, usually sulphate of lime; so that a concretionary nodule is formed, preserving a nearly globular shape, when increased to a mass several inches in diameter. In these, as in many travertins, there is often a combination of the concentric and radiated structure.

Campagna di Roma.—The country around Rome, like many parts of the Tuscan States already referred to, has been at some former period the site of numerous volcanic eruptions; and th springs are still copiously impregnated with lime, carbonic acid, an sulphuretted hydrogen. A hot spring was discovered about 18 near Civita Vecchia, by Signor Riccioli, which deposits alternat beds of a yellowish travertin, and a white granular rock, not di tinguishable, in hand specimens, either in grain, colour, or composition, from statuary marble. There is a passage between this and ordinary travertin. The mass accumulated near the spring is in some places about six feet thick.

Lake of the Solfatara.—In the Campagna, between Rome and Tivoli, is the Lake of the Solfatara, called also Lago di Zolfo (lacus albula), into which flows continually a stream of tepid water from a smaller lake, situated a few yards above it. The water is a saturated solution of carbonic acid gas, which escapes from it in such quantities in some parts of its surface, that it has the appearance of being actually in ebullition. "I have found by experiment," says Sir Humphry Davy, "that the water taken from the most tranquil part of the lake, even after being agitated and exposed to the air, contained in solution more than its own volume of carbonic acid gas, with a very small quantity of sulphuretted hydrogen. Its high temperature, which is pretty constant at 80° of Fahr., and the quantity of carbonic acid that it contains, render it peculiarly fitted to afford nourishment to vegetable life. The banks of travertin are every where covered with reeds, lichen, confervæ, and various kinds of aquatic vegetables; and at the same time that the process of vegetable life is going on, the crystallizations of the calcareous matter, which is every where deposited, in consequence of the escape of carbonic acid, likewise proceed.—There is, I believe, no place in the world where there is a more striking example of the opposition or contrast of the laws of animate and inanimate nature, of the forces of inorganic chemical affinity, and those of the powers of life."*

The same observer informs us that he fixed a stick in a mass of travertin covered by the water in the month of May, and in April following he had some difficulty in breaking, with a sharp-pointed hammer, the mass which adhered to the stick, and which was several inches in thickness. The upper part was a mixture of light tufa and the leaves of confervæ; below this was a darker and more solid travertin, containing black and decomposed masses of confervæ; in the inferior part the travertin was more solid, and of a grey colour, but with cavities probably produced by the decomposition of vegetable matter.†

The stream which flows out of this lake fills a canal about nine feet broad and four deep, and is conspicuous in the landscape by a line of vapour which rises from it. It deposits calcareous tufa in this channel, and the Tiber probably receives from it, as well as from numerous other streams, much carbonate of lime in solution, which may contribute to the rapid growth of its delta. A large proportion of the most splendid edifices of ancient and modern Rome are built of travertin, derived from the quarries of Ponte Lucano, where there has evidently been a lake at a remote period, on the same plain as that already described.

---

* Consolations in Travel, pp. 123—125.

† Ibid. p. 127.

Travertin of Tivoli.—In the same neighbourhood the cal waters of the Anio incrust the reeds which grow on its ban the foam of the cataract of Tivoli forms beautiful pendant stal On the sides of the deep chasm into which the cascade throws there is seen an extraordinary accumulation of horizontal b tufa and travertin, from four to five hundred feet in thickness.

Fig. 22.



Section of spheroidal concretionary Travertin under the Cascade of Tivoli.

section immediately under the temples of Vesta and the Sibyl, plays, in a precipice about four hundred feet high, some sph which are from *six to eight feet in diameter*, each concentric l being about the eighth of an inch in thickness. The pres diagram exhibits about fourteen feet of this immense mass, as se the path cut out of the rock in descending from the temple of V to the Grotto di Nettuno. I have not attempted to express in drawing the innumerable thin layers of which these magni spheroids are composed, but the lines given mark some of the m divisions into which they are separated by minute variations i size or colour of the laminæ. The undulations also are much sm in proportion to the whole circumference than in the drawing.

beds (*a a*) are of hard travertin and soft tufa; below them is a pisolite (*b*), the globules being of different sizes: underneath this appears a mass of concretionary travertin (*c c*), some of the spheroids being of the above-mentioned extraordinary size. In some places (as at *d*) there is a mass of amorphous limestone, or tufa, surrounded by concentric layers. At the bottom is another bed of pisolite (*b*), in which the small nodules are about the size and shape of beans, and some of them of filberts, intermixed with some smaller oolitic grains. In the tufaceous strata, wood is seen converted into a light tufa.

There can be little doubt that the whole of this deposit was formed in an extensive lake which existed when the external configuration of this country varied greatly from that now observed. The Anio throws itself into a ravine excavated in the ancient travertin, and its waters give rise to masses of calcareous stone, scarcely if at all distinguishable from the older rock. I was shown, in 1828, in the upper part of the travertin, the hollow left by a cart-wheel, in which the outer circle and the spokes had been decomposed, and the spaces which they filled left void. It seemed to me at the time impossible to explain the position of this mould, without supposing that the wheel was imbedded before the lake was drained; but Sir R. Murchison suggests that it may have been washed down by a flood into the gorge in modern times, and then incrusted with calcareous tufa in the same manner as the wooden beam of the church of St. Lucia was swept down in 1826, and stuck fast in the Grotto of the Syren, where it still remains, and will eventually be quite imbedded in travertin.

I have already endeavoured to explain (p. 241.), when speaking of the travertin of San Filippo, how the spheroidal masses represented in figure 22. may have been formed.

Sulphureous and gypseous springs.—The quantity of other mineral ingredients wherewith springs in general are impregnated is insignificant in comparison to lime, and this earth is most frequently combined with carbonic acid. But, as sulphuric acid and sulphuretted hydrogen are very frequently supplied by springs, gypsum may, perhaps, be deposited largely in certain seas and lakes. Among other gypseous precipitates at present known on the land, I may mention those of Baden, near Vienna, which feed the public bath. Some of hese supply singly from 600 to 1000 cubic feet of water per hour, and deposit a fine powder, composed of a mixture of sulphate of lime with sulphur and muriate of lime.* The thermal waters of Aix, in Savoy, in passing through strata of Jurassic limestone, turn them into gypsum or sulphate of lime. In the Andes, at the Puenta del nca, Lieutenant Brand found a thermal spring at the temperature of 1° Fahr., containing a large proportion of gypsum with carbonate f lime and other ingredients.† Many of the mineral springs of celand, says Mr. R. Bunsen, deposit gypsum ‡, and sulphureous acid as escapes plentifully from them as from the volcanos of the same island. It may, indeed, be laid down as a general rule, that the mineral substances dissolved in hot springs agree very closely with those which are disengaged in a gaseous form from the craters of active volcanos.

---

* C. Prevost, Essai sur la Constitution hysique du Bassin de Vienne, p. 10.

† Travels across the Andes, p. 240.

‡ Annalen der Chem. 1847.

Siliceous springs.—A[illegible]—[illegible] order that water should hold a very large quantity of [illegible] in [illegible]ution, it seems necessary that it should be raised to a [illegible] h[illegible] [illegible]ture.* The hot springs of the Valle das Fernas, in the i[illegible] of [illegible] Michael, rising through volcanic rocks, precipitate vast q[illegible] siliceous sinter. Around the circular basin, of the largest [illegible]ing, which is between twenty and thirty feet in diameter, alte[illegible] te[illegible] are seen of a coarser variety of sinter mixed with clay, incl[illegible]ing grass, ferns, and reeds, in different states of petrifaction. In so[illegible] instances, alumina, which is likewise deposited from the hot waters, is the mineralizing material. Branches of the same ferns which now flourish in the island are found completely petrified, preserving the same appearance as when vegetating, except that they acquire an ash-grey colour. Fragments of wood, and one entire bed from three to five feet in depth, composed of reeds now common in the island, have become completely mineralised.

The most abundant variety of siliceous sinter occurs in layers, from a quarter to half an inch in thickness, accumulated on each other often to the height of a foot and upwards, and constituting parallel, and for the most part horizontal, strata many yards in extent. This sinter has often a beautiful semi-opalescent lustre. A recent breccia is also in the act of forming, composed of obsidian, pumice, and scoriæ, cemented by siliceous sinter.†

Geysers of Iceland.—But the hot springs in various parts of Iceland, particularly the celebrated geysers, afford the most remarkable example of the deposition of silex.‡ The circular reservoirs into which the geysers fall, are lined in the interior with a variety of opal, and round the edges with sinter. The plants incrusted with the latter substance have much the same appearance as those incrusted with calcareous tufa in our own country. They consist of various grasses, the horse-tail (*Equisetum*), and leaves of the birch-tree, which are the most common of all, though no trees of this species now exist in the surrounding country. The petrified stems also of the birch occur in a state much resembling agatized wood.§

By analysis of the water, Mr. Faraday has ascertained that the solution of the silex is promoted by the presence of the alkali, soda. He suggests that the deposition of silica in an insoluble state takes place partly because the water when cooled by exposure to the air is unable to retain as much silica as when it issues from the earth at a temperature of 180° or 190° Fahr.; and partly because the evaporation of the water decomposes the compound of silica and soda which previously existed. This last change is probably hastened by the carbonic acid of the atmosphere uniting with the soda. The

---

[*] Daubeny on Volcanos, p. 222.

[†] Dr. Webster on the Hot Springs of Furnas, Ed. Phil. Journ. vol. vi. p. 306.

[‡] See a cut of the Icelandic geyser, chap. 32.

[§] M. Robert, Bulletin de la Soc. Géol. de France, tom. vii. p. 11.

alkali, when disunited from the silica, would readily be dissolved in and removed by running water.*

Mineral waters, even when charged with a small proportion of silica, as those of Ischia, may supply certain species of corals, sponges, and infusoria, with matter for their siliceous secretions; but there is little doubt that rivers obtain silex in solution from another and far more general source, namely, the decomposition of felspar. When this mineral, which is so abundant an ingredient in the hypogene and trappean rocks, has disintegrated, it is found that the residue, called porcelain clay, contains a small proportion only of the silica which existed in the original felspar, the other part having been dissolved and removed by water.†

Ferruginous springs.—The waters of almost all springs contain some iron in solution; and it is a fact familiar to all, that many of them are so copiously impregnated with this metal, as to stain the rocks or herbage through which they pass, and to bind together sand and gravel into solid masses. We may naturally, then, conclude that this iron, which is constantly conveyed from the interior of the earth into lakes and seas, and which does not escape again from them into the atmosphere by evaporation, must act as a colouring and cementing principle in the subaqueous deposits now in progress. Geologists are aware that many ancient sandstones and conglomerates are bound together or coloured by iron.

Brine springs.—So great is the quantity of muriate of soda in some springs, that they yield one fourth of their weight in salt. They are rarely, however, so saturated, and generally contain, intermixed with salt, carbonate and sulphate of lime, magnesia, and other mineral ingredients. The brine springs of Cheshire are the richest in our country; those of Northwich being almost saturated. Those of Barton also, in Lancashire, and Droitwich in Worcestershire, are extremely rich.‡ They are known to have flowed for more than 1000 years, and the quantity of salt which they have carried into the Severn and Mersey must be enormous. These brine springs rise up through strata of sandstone and red marl, which contain large beds of rock salt. The origin of the brine, therefore, may be derived in this and many other instances from beds of fossil salt; but as muriate of soda is one of the products of volcanic emanations and of springs in volcanic regions, the original source of salt may be as deep seated as that of lava.

Many springs in Sicily contain muriate of soda, and the "fiume salso," in particular, is impregnated with so large a quantity, that cattle refuse to drink of it. A hot spring, rising through granite, at Saint Nectaire, in Auvergne, may be mentioned as one of many, containing a large proportion of muriate of soda, together with magnesia and other ingredients.§

---

* Barrow's Iceland, p. 209.

† See Lyell's Manual of Elementary Geology; and Dr. Turner, Jam. Ed. New Phil. Journ. No. xxx. p. 246.

‡ L. Horner, Geol. Trans. vol. ii. p. 94.

§ Ann. de l'Auvergne, tome i. p. 234.

Carbonated springs. — *Auvergne.* — Carbonic acid gas is v
plentifully disengaged from springs in almost all countries, b
particularly near active or extinct volcanos. This elastic fluid h
the property of decomposing many of the hardest rocks with wh
it comes in contact, particularly that numerous class in whose co
position felspar is an ingredient. It renders the oxide of iron solu
in water, and contributes, as was before stated, to the solution
calcareous matter. In volcanic districts these gaseous emanati
are not confined to springs, but rise up in the state of pure gas fr
the soil in various places. The Grotto del Cane, near Naples, affo
an example, and prodigious quantities are now annually disenga
from every part of the Limagne d'Auvergne, where it appears
have been developed in equal quantity from time immemorial.
the acid is invisible, it is not observed, except an excavation be ma
wherein it immediately accumulates, so that it will extinguis
candle. There are some springs in this district, where the wate
seen bubbling and boiling up with much noise, in consequence
the abundant disengagement of this gas. In the environs of Po
Gibaud, not far from Clermont, a rock belonging to the gne
formation, in which lead-mines are worked, has been found to
quite saturated with carbonic acid gas, which is constantly dise
gaged. The carbonates of iron, lime, and manganese are so dis
solved, that the rock is rendered soft, and the quartz alone remain
unattacked.* Not far off is the small volcanic cone of Chaluze
which once broke up through the gneiss, and sent forth a lava-strea

Supposed atmosphere of carbonic acid. — Prof. Bischoff in hi
history of volcanos†, has shown what enormous quantities of car
bonic acid gas are exhaled in the vicinity of the extinct crate
of the Rhine, (in the neighbourhood of the Laacher-see, for ex
ample, and the Eifel,) and also in the mineral springs of Nassa
and other countries, where there are no immediate traces of vol
canic action. It would be easy to calculate in how short a perio
the solid carbon, thus emitted from the interior of the earth in a
invisible form, would amount to a quantity as great as could b
obtained from the trees of a large forest, and how many thousan
years would be required to supply the materials of a dense seam c
pure coal from the same source. Geologists who favour the doctrin
of the former existence of an atmosphere highly charged with car
bonic acid, at the period of the ancient coal-plants, have not suffi
ciently reflected on the continual disengagement of carbon, which i
taking place in a gaseous form from springs, as also in a free state fro
the ground and from volcanic craters into the air. We know that a
plants are now engaged in secreting carbon, and many thousands
large trees are annually floated down by great rivers, and buried i
their alluvial deposits; but before we can assume that the quantity
carbon which becomes permanently locked up in the earth by suc

---

* Ann. Scient. de l'Auvergne, tome ii. June, 1829.

† Edinb. New Phil. Journ. O 1839.

agency will bring about an essential change in the chemical composition of the atmosphere, we must be sure that the trees annually buried, contain more carbon than is given out from the interior of the earth in the same lapse of time. Every large area covered by a dense mass of peat bears ample testimony to the fact, that several million tons of carbon have been taken from the air, by the powers of vegetable life, and stored up in the earth's crust, a large quantity of oxygen having been at the same time set free; but we cannot infer from these circumstances, that the constitution of the atmosphere has been materially deranged, until we have data for estimating the rate at which dead animal and vegetable substances are daily putrefying, —organic remains and various calcareous rocks decomposing, and volcanic regions emitting fresh volumes of carbonic acid gas. That the ancient carboniferous period was one of vast duration all geologists are agreed; instead, therefore, of supposing an excess of carbonic acid in the air at that epoch, for the support of a peculiar flora, we may imagine Time to have multiplied the quantity of carbon given out annually by mineral springs, volcanic craters, and other sources, until the component elements of any given number of coal seams had been evolved from below, without any variation taking place in the constitution of the atmosphere. It has been too common, in reasoning on this question, to compute the loss of carbon by the volume of coal stored up in the ancient strata, and to take no account of the annual gain, by the restoration of carbonic acid to the atmosphere, through the machinery above alluded to.*

Disintegrating effects of carbonic acid.—The disintegration of granite is a striking feature of large districts in Auvergne, especially in the neighbourhood of Clermont. This decay was called by Dolomieu, "la maladie du granite;" and the rock may with propriety be said to have *the rot*, for it crumbles to pieces in the hand. The phenomenon may, without doubt, be ascribed to the continual disengagement of carbonic acid gas from numerous fissures.

In the plains of the Po, between Verona and Parma, especially at Villa Franca, south of Mantua, I observed great beds of alluvium, consisting chiefly of primary pebbles, percolated by spring-water, charged with carbonate of lime and carbonic acid in great abundance. They are for the most part incrusted with calc-sinter; and the rounded blocks of gneiss, which have all the outward appearance of solidity, have been so disintegrated by the carbonic acid as readily to fall to pieces.

The subtraction of many of the elements of rocks by the solvent power of carbonic acid, ascending both in a gaseous state and mixed with spring-water in the crevices of rocks, must be one of the most powerful sources of those internal changes and re-arrangements of particles so often observed in strata of every age. The calcareous matter, for example, of shells, is often entirely removed and replaced by carbonate of iron, pyrites, silex, or some other ingredient, such as mineral waters usually contain in solution. It rarely happens, except in limestone rocks, that the carbonic acid can dissolve all the constituent parts of the mass; and for this reason, probably, calcareous rocks are almost the only ones in which great caverns and long winding passages are found.

---

* See Lyell's Travels in N. America, vol. i. p. 150.

Petroleum springs.—Springs of which the waters contain a mixture of petroleum, and the various minerals allied to it, as bitumen, naphtha, asphaltum, and pitch, are very numerous, and are, in many cases, undoubtedly connected with subterranean fires, which raise or sublime the more subtle parts of the bituminous matters contained in rocks. Many springs in the territory of Modena and Parma, in Italy, produce petroleum in abundance; but the most powerful, perhaps, yet known, are those on the Irawadi, in the Burman empire. In one locality there are said to be 520 wells, which yield annually 400,000 hogsheads of petroleum.*

Pitch lake of Trinidad.—Fluid bitumen is seen to ooze from the bottom of the sea, on both sides of the island of Trinidad, and to rise up to the surface of the water. Near Cape La Braye there is a vortex which, in stormy weather, according to Captain Mallet, gushes out, raising the water five or six feet, and covers the surface for a considerable space with petroleum, or tar; and the same author quotes Gumilla, as stating, in his "Description of the Orinoco," that about seventy years ago, a spot of land on the western coast of Trinidad, near half-way between the capital and an Indian village, sank suddenly, and was immediately replaced by a small lake of pitch, to the great terror of the inhabitants.†

It is probable that the great pitch lake of Trinidad owes its origin to a similar cause; and Dr. Nugent has justly remarked, that in that district all the circumstances are now combined from which deposits of pitch may have originated. The Orinoco has for ages been rolling down great quantities of woody and vegetable bodies into the surrounding sea, where, by the influence of currents and eddies, they may be arrested and accumulated in particular places. The frequent occurrence of earthquakes and other indications of volcanic action in those parts lend countenance to the opinion, that these vegetable substances may have undergone, by the agency of subterranean fire, those transformations and chemical changes which produce petroleum; and this may, by the same causes, be forced up to the surface, where, by exposure to the air, it becomes inspissated, and forms the different varieties of pure and earthy pitch, or asphaltum, so abundant in the island.‡

It may be stated generally, that a large portion of the finer particles and the more crystalline substances, found in sedimentary rocks of different ages, are composed of the same elements as are now held in solution by springs, while the coarser materials bear an equally strong resemblance to the pebbles and sedimentary matter carried down by torrents and rivers. It should also be remembered, that it is not only during inundations, when the muddy sediment is apparent, that rivers are busy in conveying solid matter to the sea, but that even when their waters are perfectly transparent, they are annually bearing along vast masses of carbon, lime, and silica to the ocean.

---

* Symes, Embassy to Ava, vol. ii. Geol. Trans. second series, vol. ii. part iii. p. 388.

† Dr. Nugent, Geol. Trans. vol. i. p. 69.

‡ Ibid. p. 67.

CHAP. XVII.

REPRODUCTIVE EFFECTS OF RIVERS.

Lake deltas — Growth of the delta of the Upper Rhine in the Lake of Geneva — Computation of the age of deltas — Recent deposits in Lake Superior — Deltas of inland seas — Course of the Po — Artificial embankments of the Po and Adige — Delta of the Po, and other rivers entering the Adriatic — Rapid conversion of that gulf into land — Mineral characters of the new deposits — Marine delta of the Rhone — Various proofs of its increase — Stony nature of its deposits — Coast of Asia Minor — Delta of the Nile.

DELTAS IN LAKES.

I HAVE already spoken in the 14th chapter of the action of running water, and of the denuding power of rivers, but we can only form a just conception of the excavating and removing force exerted by such bodies of water, when we have the advantage of examining the reproductive effects of the same agents: in other words, of beholding in a palpable form the aggregate amount of matter, which they have thrown down at certain points in their alluvial plains, or in the basins of lakes and seas. Yet it will appear, when we consider the action of currents, that the growth of deltas affords a very inadequate standard by which to measure the entire carrying power of running water, since a considerable portion of fluviatile sediment is swept far out to sea.

Deltas may be divided into, first, those which are formed in lakes; secondly, those in inland seas, where the tides are almost imperceptible; and, thirdly, those on the borders of the ocean. The most characteristic distinction between the lacustrine and marine deltas consists in the nature of the organic remains which become imbedded in their deposits; for, in the case of a lake, it is obvious that these must consist exclusively of such genera of animals as inhabit the land or the waters of a river or lake; whereas, in the other case, there will be an admixture, and most frequently a predominance, of animals which inhabit salt water. In regard, however, to the distribution of inorganic matter, the deposits of lakes and seas are formed under very analogous circumstances.

Lake of Geneva.—Lakes exemplify the first reproductive operations in which rivers are engaged when they convey the detritus of rocks and the ingredients of mineral springs from mountain regions. The accession of new land at the mouth of the Rhone, at t upper end of the Lake of Geneva, or the Leman Lake, presents with an example of a considerable thickness of strata which ha accumulated since the historical era. This sheet of water is abo thirty-seven miles long, and its breadth is from two to eight mil The shape of the bottom is very irregular, the depth having be found by late measurements to vary from 20 to 160 fathoms.* Th Rhone, where it enters at the upper end, is turbid and discoloure but its waters, where it issues at the town of Geneva, are beautiful clear and transparent. An ancient town, called Port Vallais (Port Valesiæ of the Romans), once situated at the water's edge, at t upper end, is now more than a mile and a half inland—this inte vening alluvial tract having been acquired in about eight centuri The remainder of the delta consists of a flat alluvial plain, about f or six miles in length, composed of sand and mud, a little rai above the level of the river, and full of marshes.

Sir Henry De la Beche found, after numerous soundings in parts of the lake, that there was a pretty uniform depth of from 1 to 160 fathoms throughout the central region, and on approachi the delta, the shallowing of the bottom began to be very sensible a distance of about a mile and three quarters from the mouth of th Rhone; for a line drawn from St. Gingoulph to Vevey gives a mea depth of somewhat less than 600 feet, and from that part to th Rhone, the fluviatile mud is always found along the bottom.† W may state, therefore, that the new strata annually produced are throw down upon a slope about two miles in length; so that, notwithstand ing the great depth of the lake, the new deposits are inclined at slight an angle, that the dip of the beds would be termed, in ordinar geological language, horizontal.

The strata probably consist of alternations of finer and coars particles; for, during the hotter months from April to August, whe the snows melt, the volume and velocity of the river are greate and large quantities of sand, mud, vegetable matter, and drift-woo are introduced; but, during the rest of the year, the influx comparatively feeble, so much so, that the whole lake, according Saussure, stands six feet lower. If, then, we could obtain a sectio of the accumulation formed in the last eight centuries, we should a great series of strata, probably from 600 to 900 feet thick (t supposed original depth of the head of the lake), and nearly tw miles in length, inclined at a very slight angle. In the mean time, great number of smaller deltas are growing around the borders of t lake, at the mouths of rapid torrents, which pour in large masses sand and pebbles. The body of water in these torrents is too sm to enable them to spread out the transported matter over so extensi an area as the Rhone does. Thus, for example, there is a depth eighty fathoms within half a mile of the shore, immediately opposite the great torrent which enters east of Ripaille, so that the dip of the strata in that minor delta must be about four times as great as those deposited by the main river at the upper extremity of the lake.*

---

* De la Beche, Ed. Phil. Journ. vol. ii. p. 107. Jan. 1820.

† De la Beche, MS

‡ Ibid.

Chronological computations of the age of deltas.—The capacity of this basin being now ascertained, it would be an interesting subject of inquiry, to determine in what number of years the Leman Lake will be converted into dry land. It would not be very difficult to obtain the elements for such a calculation, so as to approximate at least to the quantity of time required for the accomplishment of the result. The number of cubic feet of water annually discharged by the river into the lake being estimated, experiments might be made in the winter and summer months, to determine the proportion of matter held in suspension or in chemical solution by the Rhone. It would be also necessary to allow for the heavier matter drifted along at the bottom, which might be estimated on hydrostatical principles, when the average size of the gravel and the volume and velocity of the stream at different seasons were known. Supposing all these observations to have been made, it would be more easy to calculate the future than the former progress of the delta, because it would be a laborious task to ascertain, with any degree of precision, the original depth and extent of that part of the lake which is already filled up. Even if this information were actually obtained by borings, it would only enable us to approximate within a certain number of centuries to the time when the Rhone began to form its present delta; but this would not give us the date of the origin of the Leman Lake in its present form, because the river may have flowed into it for thousands of years, without importing any sediment whatever. Such would have been the case, if the waters had first passed through a chain of upper lakes; and that this was actually the fact, seems indicated by the course of the Rhone between Martigny and the Lake of Geneva, and, still more decidedly, by the channels of many of its principal feeders.

If we ascend, for example, the valley through which the Dranse flows, we find that it consists of a succession of basins, one above the other, in each of which there is a wide expanse of flat alluvial lands, separated from the next basin by a rocky gorge, once perhaps the barrier of a lake. The river seems to have filled these lakes, one after the other, and to have partially cut through the barriers, some of which it is still gradually eroding to a greater depth. Before, therefore, we can pretend even to hazard a conjecture as to the era at which the principal delta of Lake Leman or any other delta commenced, we must be thoroughly acquainted with the geographical features and geological history of the whole system of higher valleys which communicate with the main stream, and all the changes which they have undergone since the last series of convulsions which agitated and altered the face of the country.

Lake Superior.—Lake Superior is the largest body of fresh water in the world, being above 1700 geographical miles in circumference when we follow the sinuosities of its coasts, and its length, on a curved line drawn through its centre, being more than 400, and its extreme breadth above 150 geographical miles. Its surface is nearly as large as the whole of England. Its average depth varies from 80 to 150 fathoms; but, according to Captain Bayfield, there is reason to think that its greatest depth would not be overrated at 200 fathoms, so that its bottom is, in some parts, nearly 600 feet below the level of the Atlantic, its surface being about as much above it. There are appearances in different parts of this, as of the other Canadian lakes, leading us to infer that its waters formerly occupied a higher level than they reach at present; for at a considerable distance from the present shores, parallel lines of rolled stones and shells are seen rising one above the other, like the seats of an amphitheatre. These ancient lines of shingle are exactly similar to the present beaches in most bays, and they often attain an elevation of 40 or 50 feet above the present level. As the heaviest gales of wind do not raise the waters more than three or four feet, the elevated beaches have by some been referred to the subsidence of the lake at former periods, in consequence of the wearing down of its barrier, by others to the upraising of the shores by earthquakes, like those which have produced similar phenomena on the coast of Chili.

---

* De la Beche, MS.

The streams which discharge their waters into Lake Superior are several hundred in number, without reckoning those of smaller size; and the quantity of water supplied by them is many times greater than that discharged at the Falls of St. Mary, the only outlet. The evaporation, therefore, is very great, and such as might be expected from so vast an extent of surface. On the northern side, which is encircled by primary mountains, the rivers sweep in many large boulders with smaller gravel and sand, chiefly composed of granitic and trap rocks. There are also currents in the lake in various directions, caused by the continued prevalence of strong winds, and to their influence we may attribute the diffusion of finer mud far and wide over great areas; for by numerous soundings made during Capt. Bayfield's survey, it was ascertained that the bottom consists generally of a very adhesive clay, containing shells of the species at present existing in the lake. When exposed to the air, this clay immediately becomes indurated in so great a degree, as to require a smart blow to break it. It effervesces slightly with diluted nitric acid, and is of different colours in different parts of the lake; in one district blue, in another red, and in a third white, hardening into a substance resembling pipeclay.* From these statements, the geologist will not fail to remark how closely these recent lacustrine formations in America resemble the tertiary argillaceous and calcareous marls of lacustrine origin in Central France. In both cases many of the genera of shells most abundant, as Limnea and Planorbis, are the same; and in regard to other classes of organic remains there must be the closest analogy, as I shall endeavour more fully to explain when speaking of the imbedding of plants and animals in recent deposits.

---

* Trans. of Lit. and Hist. Soc. of Quebec, vol. i. p. 5. 1829.

DELTAS OF INLAND SEAS.

Having thus briefly considered some of the lacustrine deltas now in progress, we may next turn our attention to those of inland seas.

Course of the Po.—The Po affords an instructive example of the manner in which a great river bears down to the sea the matter poured into it by a multitude of tributaries descending from lofty chains of mountains. The changes gradually effected in the great plain of Northern Italy, since the time of the Roman republic, are considerable. Extensive lakes and marshes have been gradually filled up, as those near Placentia, Parma, and Cremona, and many have been drained naturally by the deepening of the beds of rivers. Deserted river-courses are not unfrequent, as that of the Serio Morto, which formerly fell into the Adda, in Lombardy. The Po also itself has often deviated from its course, having after the year 1390, deserted part of the territory of Cremona, and invaded that of Parma; its old channel being still recognisable, and bearing the name of Po Morto. There is also an old channel of the Po in the territory of Parma, called Po Vecchio, which was abandoned in the twelfth century, when a great number of towns were destroyed.

Artificial embankments of Italian rivers.—To check these and similar aberrations, a general system of embankment has been adopted; and the Po, Adige, and almost all their tributaries, are now confined between high artificial banks. The increased velocity acquired by streams thus closed in, enables them to convey a much larger portion of foreign matter to the sea; and, consequently, the deltas of the Po and Adige have gained far more rapidly on the Adriatic since the practice of embankment became almost universal. But, although more sediment is borne to the sea, part of the sand and mud, which in the natural state of things would be spread out by annual inundations over the plain, now subsides in the bottom of the river-channels; and their capacity being thereby diminished, it is necessary, in order to prevent inundations in the following spring, to extract matter from the bed, and to add it to the banks of the river. Hence it happens that these streams now traverse the plain on the top of high mounds, like the waters of aqueducts, and at Ferrara the surface of the Po has become more elevated than the roofs of the houses.[*] The magnitude of these barriers is a subject of increasing expense and anxiety, it having been sometimes found necessary to give an additional height of nearly one foot to the banks of the Adige and Po in a single season.

The practice of embankment was adopted on some of the Italian rivers as early as the thirteenth century; and Dante, writing in the beginning of the fourteenth, describes, in the seventh circle of hell, a rivulet of tears separated from a burning sandy desert by embankments "like those which, between Ghent and Bruges, were raised against the ocean, or those which the Paduans had erected along the Brenta to defend their villas on the melting of the Alpine snows."

---

[*] Prony, see Cuvier, Disc. Prelim. p. 146.

> Quale i Fiamminghi tra Guzzante e Bruggia,
> Temendo il fiotto che in ver lor s'avventa,
> Fanno lo schermo, perchè il mar si fuggia,
> E quale i Padovan lungo la Brenta,
> Per difender lor ville e lor castelli,
> Anzi che Chiarentana il caldo senta —
>
> *Inferno*, Canto xv.

In the Adriatic, from the northern part of the Gulf of Trieste, where the Isonzo enters, down to the south of Ravenna, there is an uninterrupted series of recent accessions of land, more than 100 miles in length, which within the last 2000 years have increased from *two to twenty miles in breadth.* A line of sand bars of great length has been formed nearly all along the western coast of this gulf, inside of which are lagunes, such as those of Venice, and the large lagune of Comacchio, 20 miles in diameter. Newly deposited mud brought down by the streams is continually lessening the depth of the lagunes, and converting part of them into meadows.* The Isonzo, Tagliamento, Piave, Brenta, Adige, and Po, besides many other inferior rivers, contribute to this advance of the coast-line and to the shallowing of the lagunes and the gulf.

Delta of the Po.—The Po and the Adige may now be considered as entering by one common delta, for two branches of the Adige are connected with arms of the Po, and thus the principal delta has been pushed out beyond those bars which separate the lagunes from the sea. The rate of the advance of this new land has been accelerated, as before stated, since the system of embanking the rivers became general, especially at that point where the Po and Adige enter. The waters are no longer permitted to spread themselves far and wide over the plains, and to leave behind them the larger portion of their sediment. Mountain torrents also have become more turbid since the clearing away of forests, which once clothed the southern flanks of the Alps. It is calculated that the mean rate of advance of the delta of the Po on the Adriatic between the years 1200 and 1600 was 25 yards or metres a year, whereas the mean annual gain from 1600 to 1804 was 70 metres.†

Adria was a seaport in the time of Augustus, and had, in ancient times, given its name to the gulf; it is now about twenty Italian miles inland. Ravenna was also a seaport, and is now about four miles from the main sea. Yet even before the practice of embankment was introduced, the alluvium, of the Po advanced with rapidity on the Adriatic; for Spina, a very ancient city, originally built in the district of Ravenna, at the mouth of a great arm of the Po, was, so early as the commencement of our era, eleven miles distant from the sea.*

---

* See De Beaumont, Géologie Pratique, vol. i. p. 323. 1841.

† Prony, cited by Cuvier, Discours Prelimin.

But although so many rivers are rapidly converting the Adriatic into land, it appears, by the observations of M. Morlot, that since the time of the Romans, there has been a general subsidence of the coast and bed of this sea in the same region to the amount of five feet, so that the advance of the new-made land has not been so fast as it would have been had the level of the coast remained unaltered. The signs of a much greater depression anterior to the historical period have also been brought to light by an Artesian well, bored in 1847, to the depth of more than 400 feet, which still failed to penetrate through the modern fluviatile deposit. The auger passed chiefly through beds of sand and clay, but at four several depths, one of them very near the bottom of the excavation, it pierced beds of turf, or accumulations of vegetable matter, precisely similar to those now formed superficially on the extreme borders of the Adriatic. Hence we learn that a considerable area of what was once land has sunk down 400 feet in the course of ages.†

The greatest depth of the Adriatic, between Dalmatia and the mouths of the Po, is twenty-two fathoms; but a large part of the Gulf of Trieste and the Adriatic, opposite Venice, is less than twelve fathoms deep. Farther to the south, where it is less affected by the influx of great rivers, the gulf deepens considerably. Donati, after dredging the bottom, discovered the new deposits to consist partly of mud and partly of rock, the rock being formed of calcareous matter, incrusting shells. He also ascertained, that particular species of testacea were grouped together in certain places, and were becoming slowly incorporated with the mud or calcareous precipitates.‡ Olivi, also, found some deposits of sand, and others of mud, extending half way across the gulf; and he states that their distribution along the bottom was evidently determined by the prevailing current.§ It is probable, therefore, that the finer sediment of all the rivers at the head of the Adriatic may be intermingled by the influence of the current; and all the central parts of the gulf may be considered as slowly filling up with horizontal deposits, similar to those of the Subapennine hills, and containing many of the same species of shells. The Po merely introduces at present fine sand and mud, for it carries no pebbles farther than the spot where it joins the Trebia, west of Piacenza. Near the northern borders of the basin, the Isonzo, Tagliamento, and many other streams, are forming immense beds of sand and some conglomerate; for here some high mountains of Alpine limestone approach within a few miles of the sea.

In the time of the Romans, the hot-baths of Monfalcone were on one of several islands of Alpine limestone, between which and mainland, on the north, was a channel of the sea, about a broad. This channel is now converted into a grassy plain, wh surrounds the islands on all sides. Among the numerous cha on this coast, we find that the present channel of the Isonzo several miles to the west of its ancient bed, in part of which, Ronchi, the old Roman bridge which crossed the Via Appia w lately found buried in fluviatile silt.

---

* Brocchi, Conch. Foss. Subap. vol. i. p. 118.

† Archiac, Histoire des Progrès de la Géol. 1848, vol. ii. p. 232.

‡ Brocchi, Conch. Foss. Subap. vol. i. p. 39.

§ Ibid. vol. ii. p. 94.

Marine delta of the Rhone.—The lacustrine delta of the Rhone Switzerland has already been considered (p. 251.), its contemporane marine delta may now be described. Scarcely has the river pa out of the Lake of Geneva before its pure waters are again filled w sand and sediment by the impetuous Arve, descending from the hig Alps, and bearing along in its current the granitic detritus annu brought down by the glaciers of Mont Blanc. The Rhone afterw receives vast contributions of transported matter from the Alps Dauphiny, and the primary and volcanic mountains of Central Fra and when at length it enters the Mediterranean, it discolours the b waters of that sea with a whitish sediment, for the distance of betw six and seven miles, throughout which space the current of fr water is perceptible.

Strabo's description of the delta is so inapplicable to its present configuration, as to attest a complete alteration in the physical features of the country since the Augustan age. It appears, however, that the head of the delta, or the point at which it begins to ramify, has remained unaltered since the time of Pliny, for he states that the Rhone divided itself at Arles into two arms. This is the case at present; one of the branches, the western, being now called Le Petit Rhône, which is again subdivided before entering the Mediterranean. The advance of the base of the delta, in the last eighteen centuries, is demonstrated by many curious antiquarian monuments. The most striking of these is the great and unnatural détour of the old Roman road from Ugernum to Beziers (*Bæterræ*) which went round by Nismes (*Nemausus*). It is clear that, when this was first constructed, it was impossible to pass in a direct line, as now, across the delta, and that either the sea or marshes intervened in a tract now consisting of terra firma.* Astruc also remarks, that all the places on low lands, lying to the north of the old Roman road between Nismes and Beziers, have names of Celtic origin, evidently given to them by the first inhabitants of the country; whereas, the places lying south of that road, towards the sea, have names of Latin derivation, and were clearly founded after the Roman language had been introduced.

Another proof, also, of the great extent of land which has come into existence since the Romans conquered and colonised Gaul, is derived from the fact, that the Roman writers never mention the thermal waters of Balaruc in the delta, although they were well acquainted with those of Aix, and others still more distant, and attached great importance to them, as they invariably did to all hot

---

* Mém. d'Astruc, cited by Von Hoff, vol. i. p. 288.

. The waters of Balaruc, therefore, must have formerly issued he sea — a common phenomenon on the borders of the Medi- an; and on the advance of the delta they continued to flow ough the new deposits.

ng the more direct proofs of the increase of land, we find that lescribed under the appellation of Mesua Collis by Pomponius and stated by him to be nearly an island, is now far inland. Dame des Ports, also, was a harbour in 898, but is now a from the shore. Psalmodi was an island in 815, and is now gues from the sea. Several old lines of towers and sea-marks t different distances from the present coast, all indicating the ive retreat of the sea, for each line has in its turn become use- mariners; which may well be conceived, when we state that wer of Tignaux, erected on the shore so late as the year 1737, dy a mile remote from it.†

he confluence of the Rhone and the currents of the Mediterra- riven by winds from the south, sand-bars are often formed across uths of the river: by these means considerable spaces become l off from the sea, and subsequently from the river also, when it ts channels of efflux. As some of these lagoons are subject to asional ingress of the river when flooded, and of the sea during they are alternately salt and fresh. Others, after being filled alt water, are often lowered by evaporation till they become alt than the sea; and it has happened, occasionally, that a rable precipitate of muriate of soda has taken place in these l salterns. During the latter part of Napoleon's career, when cise laws were enforced with extreme rigour, the police was 'ed to prevent such salt from being used. The fluviatile and shells enclosed in these small lakes often live together in brack- er; but the uncongenial nature of the fluid usually produces a h size, and sometimes gives rise to strange varieties in form lour.

tain Smyth, in his survey of the coast of the Mediterranean, the sea, opposite the mouth of the Rhone, to deepen gradually our to forty fathoms, within a distance of six or seven miles, hich the discoloured fresh water extends; so that the in- n of the new deposits must be too slight to be appreciable in a extent of section as a geologist usually obtains in examining t formations. When the wind blew from the south-west, the mployed in the survey were obliged to quit their moorings; ien they returned, the new sand-banks in the delta were found d over with a great abundance of marine shells. By this we learn how occasional beds of drifted marine shells may interstratified with freshwater strata at a river's mouth.

y *nature of its deposits.*—That a great proportion, at least, new deposit in the delta of the Rhone consists of *rock*, and not

---

. ii. c. v.

ache, Chorographic et Hist. de Provence, vol. i. p. 23., cited by Von Hoff, . 290.

of loose incoherent matter, is perfectly ascertained. In the Museu at Montpelier is a cannon taken up from the sea near the mouth the river, imbedded in a crystalline calcareous rock. Large masse also, are continually taken up of an arenaceous rock, cemented b calcareous matter including multitudes of broken shells of recen species. The observations lately made on this subject corrobora the former statement of Marsilli, that the earthy deposits of the coast of Languedoc form a stony substance, for which reason he ascribes a certain bituminous, saline, and glutinous nature to the substances brought down with sand by the Rhone.* If the number of mineral springs charged with carbonate of lime which fall into the Rhone and its feeders in different parts of France be considered, we shall feel no surprise at the lapidification of the newly deposited sediment in this delta. It should be remembered, that the fresh water introduced by rivers being lighter than the water of the sea floats over the latter, and remains upon the surface for a considerable distance. Consequently it is exposed to as much evaporation as the waters of a lake; and the area over which the river-water is spread, at the junction of great rivers and the sea, may well be compared, in point of extent, to that of considerable lakes.

Now, it is well known, that so great is the quantity of water carried off by evaporation in some lakes, that it is nearly equal to the water flowing in; and in some inland seas, as the Caspian, it is quite equal. We may, therefore, well suppose that, in cases where a strong current does not interfere, the greater portion not only of the matter held mechanically in suspension, but of that also which is in chemical solution, may be precipitated at no great distance from the shore. When these finer ingredients are extremely small in quantity, they may only suffice to supply crustaceous animals, corals, and marine plants, with the earthy particles necessary for their secretions; but whenever it is in excess, as generally happens if the basin of a river lie partly in a district of active or extinct volcanoes, then will solid deposits be formed, and the shells will at once be included in a rocky mass.

Coast of Asia Minor.—Examples of the advance of the land upon the sea are afforded by the southern coast of Asia Minor. Admiral Sir F. Beaufort has pointed out in his survey the great alterations effected since the time of Strabo, where havens are filled up, islands joined to the mainland, and where the whole continent has increased many miles in extent. Strabo himself, on comparing the outline of the coast in his time with its ancient state, was convinced, like our countrymen, that it had gained very considerably upon the sea. The new-formed strata of Asia Minor [illegible] of loose incoherent materials. Almost all the streams and rivers, like many of those in Tuscany and the south of Italy, hold abundance of carbonate of lime in solution, and precipitate travertin, or sometimes bind together the sand and gravel into solid sandstones and conglomerates: every delta and sand-bar thus acquires solidity, which often prevents streams from forcing their way through them, so that their mouths are constantly changing their position.*

---

* [illegible]

Delta of the Nile.—That Egypt was "the gift of the Nile," was the opinion of her priests before the time of Herodotus; and Rennell observes, that the "configuration and composition of the low lands leave no room for doubt that the sea once washed the base of the rocks on which the pyramids of Memphis stand, the *present* base of which is washed by the inundation of the Nile, at an elevation of 70 or 80 feet above the Mediterranean. But when we attempt to carry back our ideas to the remote period when the foundation of the delta was first laid, we are lost in the contemplation of so vast an interval of time."† Herodotus observes, "that the country round Memphis seemed formerly to have been an arm of the sea gradually filled by the Nile, in the same manner as the Meander, Achelous, and other streams, had formed deltas. Egypt, therefore, he says, like the Red Sea, was once a long narrow bay, and both gulfs were separated by a small neck of land. If the Nile, he adds, should by any means have an issue into the Arabian Gulf, it might choke it up with earth in 20,000 or even, perhaps, in 10,000 years; and why may not the Nile have filled a still greater gulf with mud in the space of time which has passed before our age?"‡

The distance between Memphis and the most prominent part of the delta in a straight line north and south, is about 100 geographical miles; the length of the base of the delta is more than 200 miles if we follow the coast between the ancient extreme eastern and western arms; but as these are now blocked up, that part only of Lower Egypt which intervenes between the Rosetta and Damietta branches, is usually called the delta, the coast line of which is about 90 miles in length. The bed of the river itself, says Sir J. G. Wilkinson, undergoes a gradual increase of elevation varying in different places, and always lessening in proportion as the river approaches the sea. "This increase of elevation in perpendicular height is much smaller in Lower than in Upper Egypt, and in the delta it diminishes still more; so that, according to an approximate calculation, the land about Elephantine, or the first cataract, lat. 24° 5′, has been raised nine feet in 1700 years; at Thebes, lat. 25° 43′, about seven feet; and at Heliopolis and Cairo, lat. 30°, about five feet ten inches. At Rosetta and the mouths of the Nile, lat. 31° 30′, the diminution n the perpendicular thickness of the deposit is lessened in a much greater decreasing ratio than in the straightened valley of Central nd Upper Egypt, owing to the great extent, east and west, over which the inundation spreads."§

For this reason the alluvial deposit does not cause the delta to protrude rapidly into the sea, although some ancient cities are mile or more inland, and the mouths of the Nile, mentioned b earlier geographers, have been many of them silted up, and the o of the coast entirely changed.

---

* Karamania, or a brief Description the Coast of Asia Minor, &c. London, 17.

† Geog. Syst. of Herod. vol. ii. p. 107.

‡ Euterpe, XI.

§ Journ. of Roy. Geograph. Soc. vol. ix. p. 432.

The bed of the Nile always keeps pace with the general elev of the soil, and the banks of this river, like those of the Missi and its tributaries (see p. 265.), are much higher than the flat at a distance, so that they are seldom covered during the hi inundations. In consequence of the gradual rise of the river's the annual flood is constantly spreading over a wider area, and alluvial soil encroaches on the desert, covering, to the depth of seven feet, the base of statues and temples which the waters reached 3000 years ago. Although the sands of the Libyan de have in some places been drifted into the valley of the Nile, these aggressions, says Wilkinson, are far more than counterbal by the fertilizing effect of the water which now reaches farther i towards the desert, so that the number of square miles of arabl is greater at present than at any previous period.

Mud of the Nile.—On comparing the different analyses w have been published of this mud, it will be found that it cont large quantity of argillaceous matter, with much peroxide of some carbonate of lime, and a small proportion of carbonate of m nesia. The latest and most careful analysis by M. Lassaigne sh a singularly close resemblance in the proportions of the ingredie of silica, alumina, iron, carbon, lime, and magnesia, and those served in ordinary mica*; but a much larger quantity of calcare matter is sometimes present.

In many places, as at Cairo, where artificial excavations have b made, or where the river has undermined its banks, the mud is s to be thinly stratified, the upper part of each annual layer consist of earth of a lighter colour than the lower, and the whole separat easily from the deposit of the succeeding year. These annual lay are variable in thickness; but, according to the calculations of Gir and Wilkinson, the mean annual thickness of a layer at Cairo can exceed that of a sheet of thin pasteboard, and a stratum of two three feet must represent the accumulation of a thousand years.

The depth of the Mediterranean is about twelve fathoms a small distance from the shore of the delta; it afterwards incre gradually to 50, and then suddenly descends to 380 fathoms, wh is, perhaps, the original depth of the sea where it has not b rendered shallower by fluviatile matter. We learn from Lieut. N bold that nothing but the finest and lightest ingredients reach Mediterranean, where he has observed the sea discoloured by the the distance of 40 miles from the shore.† The small progress of delta in the last 2000 years affords, perhaps, no measure for mating its rate of growth when it was an inland bay, and had not yet protruded itself beyond the coast-line of the Mediterranean. A powerful current now sweeps along the shores of Africa, from the Straits of Gibraltar to the prominent convexity of Egypt, the western side of which is continually the prey of the waves; so that not only are fresh accessions of land checked, but ancient parts of the delta are carried away. By this cause Canopus and some other towns have been overwhelmed; but to this subject I shall again refer when speaking of tides and currents.

---

* Quart. Journ. Geol. Soc. vol. v.; Memoirs, p. 20.; and Lassaigne, Journ. le Pharm. t. v. p. 468.

† Quart. Journ. Geol. Soc. 1848 iv. p. 342.

CHAPTER XVIII.

REPRODUCTIVE EFFECTS OF RIVERS — *continued.*

Deltas formed under the influence of tides — Basin and delta of the Mississippi — Alluvial plain — River-banks and bluffs — Curves of the river — Natural rafts and snags — New lakes, and effects of earthquakes — Antiquity of the delta — Delta of the Ganges and Brahmapootra — Head of the delta and Sunderbunds — Islands formed and destroyed — Crocodiles — Amount of fluviatile sediment in the water — Artesian boring at Calcutta — Proofs of subsidence — Age of the delta — Convergence of deltas — Origin of existing deltas not contemporaneous — Grouping of strata and stratification in deltas — Conglomerates — Constant interchange of land and sea.

IN the last chapter several examples were given of the deltas of inland seas, where the influence of the tides is almost imperceptible. We may next consider those marine or oceanic deltas, where the tides play an important part in the dispersion of fluviatile sediment, as in the gulf of Mexico, where they exert a moderate degree of force, and then in the Bay of Bengal, where they are extremely powerful. In regard to estuaries, which Rennel termed "negative deltas," they will be treated of more properly when our attention is specially turned to the operations of tides and currents (chapters 20, 21, and 22.). In this case, instead of the land gaining on the sea at the river's mouth, the tides penetrate far inland beyond the general coast line.

BASIN AND DELTA OF THE MISSISSIPPI.

Alluvial plain. — The hydrographical basin of the Mississippi displays, on the grandest scale, the action of running water on the surface of a vast continent. This magnificent river rises nearly in the forty-ninth parallel of north latitude, and flows to the Gulf of Mexico in the twenty-ninth — a course, including its meanders, of more than three thousand miles. It passes from a cold climate, where the hunter obtains his furs and peltries, traverses the temperate latitudes, and discharges its waters into the sea in the region of rice, the cotton plant, and the sugar cane. From near its mouth at the Balize a steam-boat may ascend for 2000 miles with scarcely any perceptible difference in the width of the river. Several of its tributaries, the

Red [illegible] the Arka[illegible], t[illegible]i, the [illegible], and others, would be [illegible] of [illegible] first impo[illegible]e, and, taken together, [illegible] vi[illegible]le for a [illegible] times exceeding that of the main [illegible] No river [illegible]rds a [illegible]e striking illustration of the law before m[illegible]ti[illegible], that [illegible]ation of volume does not occasion a pro-[illegible] l inc[illegible] of [illegible]en sometimes attended with a [illegible]rowing of [illegible]nn[illegible] The [illegible]sippi is half a mile wide at its [illegible]tion with the [illegible] the [illegible]eing also of equal width; yet [illegible]ted waters have [illegible]y, fr[illegible] t[illegible]r confluence to the mouth of the Ohio, a medial width of ab[illegible] half a mile. The junction of the Ohio seems also to produce no increase, but rather a decrease, of surface.* The St. Francis, White, Arkansas, and Red rivers are also absorbed by the main stream with scarcely any apparent increase of its width, although here and there it expands to a breadth of 1½, or even to 2 miles. On arriving at New Orleans, it is somewhat less than half a mile wide. Its depth there is very variable, the greatest at high water being 168 feet. The mean rate at which the whole body of water flows is variously estimated; according to Mr. Forshey the mean velocity of the current at the surface, somewhat exceeds 2½ miles an hour when the water is at a mean height. For 300 miles above New Orleans the distance measured by the winding river is about twice as great as the distance in a right line. For the first 100 miles from the mouth the rate of fall is 1·80 inch, per mile, for the second hundred 2 inches, for the third 2·30, for the fourth 2·57.

The alluvial plain of the Mississippi begins to be of great width below Cape Girardeau, 50 miles above the junction of the Ohio. At this junction it is about 50 miles broad, south of which it contracts to about 30 miles at Memphis, expands again to 80 miles at the mouth of the White River, and then, after various contractions and expansions, protrudes beyond the general coast-line, in a large delta, about 90 miles in width, from N. E. to S. W. Mr. Forshey estimates the area of the great plain as above defined at 31,200 square miles, with a circumference of about 3000 miles, exceeding the area of Ireland. If that part of this plain which lies below, or to the south of the branching off of the highest arm, called the Atchafalaya, be termed the delta, it constitutes less than half of the whole, being 14,000 square British miles in area. The delta may be said to be bounded on the east, west, and south by the sea; on the north chiefly by the broad valley-plain which entirely resembles it in character as in origin. The east and west boundaries of the alluvial region above the head of the delta consists of cliffs or bluffs, which on the east side of the Mississippi are very abrupt, and are undermined by the river at many points. They consist, from Baton Rouge in Louisiana, where they commence, as far north as the borders of Kentucky, of geological formations newer than the cretaceous, the lowest beiing Eocene, and the uppermost consisting of loam, resembling the loess of the Rhine, and containing freshwater and land shells almost all of existing species. (See fig. 23.) These recent shells are associated with the bones of the mastodon, elephant, tapir, mylodon, horse, ox, and other quadrupeds, most of them of extinct species.

---

* Flint's Geography, vol. i. p. 142. Lyell's Second Visit to the United States, vol. ii. chaps. 28. to 34.

I have endeavoured to show in my Second Visit to the United States, that this extensive formation of loam is either an ancient alluvial plain or a delta of the great river, formed originally at a lower level, and since upheaved, and partially denuded.

The Mississippi in that part of its course which is below the mouth of the Ohio, frequently washes the eastern bluffs, but never once comes in contact with the western. These are composed of similar formations; but I learn from Mr. Forshey that they rise up more gently from the alluvial plain (as at *a*, fig. 23.). It is supposed that the waters are thrown to the eastern side, because all the large tributary rivers entering from the west have filled that side of the great valley with their deltas, or with a sloping mass of clay and sand; so that the opposite bluffs are undermined, and the Mississippi is slowly but incessantly advancing eastward.*

Fig. 23.

VALLEY OF THE MISSISSIPPI.



1. Modern alluvium of Mississippi. 2. Loam or Loess. 3. *f.* Eocene. 4. Cretaceous.

Curves of the Mississippi.—The river traverses the plain in a meandering course, describing immense curves. After sweeping round the half of a circle, it is carried in a rapid current diagonally across the ordinary direction of its channel, to another curve of similar shape. Opposite to each of these, there is always a sand-bar, answering, in the convexity of its form, to the concavity of "the bend," as it is called.† The river, by continually wearing these curves deep, returns, like many other streams before described, on its own tract, so that a vessel in some places, after sailing for twenty-five or thirty miles, is brought round again to within a mile of the place whence it started. When the waters approach so near to each other, it often happens at high floods that they burst through the small tongue of land, and insulate a portion, rushing through what is called the "cut off," so that vessels may pass from one point to another in half a mile to a distance which it previously required a voyage of twenty miles to reach. As soon as the river has excavated the new passage, bars of sand and mud are formed at the two points of junction with the old bend, which is soon entirely separated from the main river by a continuous mud-bank covered with wood. The old bend then becomes a semicircular lake of clear water, inhabited by large gar-fish, alligators, and wild fowl, which the steam-boats have nearly driven away from the main river. A multitude of such crescent-shaped lakes, scattered far and wide over the alluvial plain, the greater number of them to the west, but some of them also eastward of the Mississippi, bear testimony to the extensive wanderings of the great stream in former ages. For the last two hundred miles above its mouth the course of the river is much less winding than above, there being only in the whole of that distance one great curve, that called the "English Turn." This greater straightness of the stream is ascribed by Mr. Forshey to the superior tenacity of the banks, which are more clayey in this region.

---

* Geograph. Descrip. of Louisiana, by W. Darby, Philadelphia, 1816, p. 102.

† Flint's Geography, vol. i. p. 152.

The Mississippi has been incorrectly described by some of the earlier geographers, as a river running along the top of a long hill, or mound in a plain. In reality it runs in a valley, from 100 to 200 or more feet in depth, as *a*, *c*, *b*, fig. 24., its banks forming long strips of land parallel to the course of the main stream, and to the swamps *g*, *f*, and *d*, *e*, lying on each side. These extensive morasses, which are commonly well-wooded, though often submerged for months continuously, are rarely more than fifteen feet below the summit level of the banks. The banks themselves are occasionally overflowed, but are usually above water for a breadth of about two miles. They follow all the curves of the great river, and near New Orleans are raised artificially by embankments (or levees), *a b*, fig. 24., through which the river when swollen sometimes cuts a deep channel (or crevasse), inundating the adjoining low lands and swamps, and not sparing the lower streets of the great city.

Fig. 24.



Section of channel, bank, levees (*a* and *b*), and swamps of Mississippi river.

The cause of the uniform upward slope of the river bank above the adjoining alluvial plain is this: when the waters charged with sediment pass over the banks in the flood season, their velocity is checked among the herbage and reeds, and they throw down at once the coarser and more sandy matter with which they are charged. But the fine particles of mud are carried farther on, so that at the distance of about two miles, a thin film of fine clay only subsides, forming a stiff unctuous black soil, which gradually envelopes the base of trees growing on the borders of the swamps.

Waste of the banks.—It has been said of a mountain torrent, that "it lays down what it will remove, and removes what it has laid down;" and in like manner the Mississippi, by the continual shifting of its course, sweeps away, during a great portion of the year, considerable tracts of alluvium, which were gradually accumulated by the overflow of former years, and the matter now left during the spring-floods will be at some future time removed. After the flood season, when the river subsides within its channel, it acts with destructive force upon the alluvial banks, softened and diluted by the recent overflow. Several acres at a time, thickly covered with wood, are precipitated into the stream; and large portions of the islands are frequently swept away.

"Some years ago," observes Captain Hall, "when the Mississippi was regularly surveyed, all its islands were numbered, from the confluence of the Missouri to the sea; but every season makes such revolutions, not only in the number but in the magnitude and situation of these islands, that this enumeration is now almost obsolete. Sometimes large islands are entirely melted away; at other places they have attached themselves to the main shore, or, which is the more correct statement, the interval has been filled up by myriads of logs cemented together by mud and rubbish."*

Rafts.—One of the most interesting features in the great rivers of this part of America is the frequent accumulation of what are termed "rafts," or masses of floating trees, which have been arrested in their progress by snags, islands, shoals, or other obstructions, and made to accumulate, so as to form natural bridges reaching entirely across the stream. One of the largest of these was called the raft of the Atchafalaya, an arm of the Mississippi, which was certainly at some former time the channel of the Red River, when the latter found its way to the Gulf of Mexico by a separate course. The Atchafalaya being in a direct line with the general direction of the Mississippi, catches a large portion of the timber annually brought down from the north; and the drift trees collected in about thirty-eight years previous to 1816 formed a continuous raft, no less than ten miles in length, 220 yards wide, and eight feet deep. The whole rose and fell with the water, yet was covered with green bushes and trees, and its surface enlivened in the autumn by a variety of beautiful flowers. It went on increasing till about 1835, when some of the trees upon it had grown to the height of about sixty feet. Steps were then taken by the state of Louisiana to clear away the whole raft and open the navigation, which was effected, not without great labour, in the space of four years.

The rafts on Red River are equally remarkable: in some parts of its course, cedar trees are heaped up by themselves, and in other places pines. On the rise of the waters in summer hundreds of these are seen, some with their green leaves still upon them, just as they have fallen from a neighbouring bank, others leafless, broken and worn in their passage from a far distant tributary: wherever they accumulate on the edge of a sand bar they arrest the current and soon become covered with sediment. On this mud the young willows and the poplars called cotton-wood spring up, their boughs still farther retarding the stream, and as the inundation rises, accelerating the deposition of new soil. The bank continuing to enlarge, the channel at length becomes so narrow that a single long tree may reach from side to side, and the remaining space is then soon choked up by a quantity of other timber.

---

* Travels in North America, vol. iii. p. 361.

"Unfortunately for the navigation of the Mississippi," observes Captain Hall, "some of the largest trunks, after being cast down from the position on which they grew, get their roots entangled with the bottom of the river, where they remain anchored, as it were, in the mud. The force of the current naturally gives their tops a tendency downwards, and, by its flowing past, soon strips them of their leaves and branches. These fixtures, called snags, or planters, are extremely dangerous to the steam-vessels proceeding up the stream, in which they lie like a lance in rest, concealed beneath the water, with their sharp ends pointed directly against the bows of the vessels coming up. For the most part these formidable snags remain so still, that they can be detected only by a slight ripple above them, not perceptible to inexperienced eyes. Sometimes, however, they vibrate up and down, alternately showing their heads above the surface, and bathing them beneath it."* So imminent until lately was the danger caused by these obstructions, that almost all the boats on the Mississippi were constructed on a particular plan, to guard against fatal accidents; but in the last ten years, by aid of the power of steam, and the machinery of a snag-boat, as it is called, the greater number of these trunks of trees have been drawn out of the mud.†

The prodigious quantity of wood annually drifted down by the Mississippi and its tributaries, is a subject of geological interest, not merely as illustrating the manner in which abundance of vegetable matter becomes, in the ordinary course of nature, imbedded in submarine and estuary deposits, but as attesting the constant destruction of soil and transportation of matter to lower levels by the tendency of rivers to shift their courses. Each of these trees must have required many years, some of them centuries, to attain their full size; the soil, therefore, whereon they grew, after remaining undisturbed for long periods, is ultimately torn up and swept away.

It is also found in excavating at New Orleans, even at the depth of several yards below the level of the sea, that the soil of the delta contains innumerable trunks of trees, layer above layer, some prostrate, as if drifted, others broken off near the bottom, but remaining still erect, and with their roots spreading on all sides, as if in their natural position. In such situations they appeared to me to indicate a sinking of the ground, as the trees must formerly have grown in marshes above the sea-level. In the higher parts of the alluvial plain, for many hundred miles above the head of the delta similar stools and roots of trees are also seen buried in stiff clay at different levels, one above the other, and exposed to view in the banks at low water. They point clearly to the successive growth of forests in the extensive swamps of the plain, where the ground was slowly raised, year after year, by the mud thrown down during inundations. These roots and stools belong chiefly to the deciduous cypress (*Taxodium distichum*) and other swamp trees, and they bear testimony to the constant shifting of the course of the great river which is always excavating land originally formed at some distance from its banks.

---

* Travels in North America, vol. iii. p. 362.

† "The boats are fitted," says Captain Hall, "with what is called a snag-chamber; — a partition formed of stout planks, which is caulked, and made so effectually water-tight, that the foremost end of the vessel is cut off as entirely from the rest of the hold as if it belonged to another boat. If the steam-vessel happen to run against a snag, and that a hole is made in her bow, under the surface, this chamber merely fills with water."—Travels in North America, vol. iii. p. 363.

Formation of lakes in Louisiana.—Another striking feature in the basin of the Mississippi, illustrative of the changes now in progress, is the formation by natural causes of great lakes, and the drainage of others. These are especially frequent in the basin of the Red River in Louisiana, where the largest of them, called Bistineau, is more than *thirty miles* long, and has a medium depth of from *fifteen* to *twenty* feet. In the deepest parts are seen numerous cypress trees, of all sizes, now dead, and most of them with their tops broken by the wind, yet standing erect under water. This tree resists the action of air and water longer than any other, and, if not submerged throughout the whole year, will retain life for an extraordinary period. Lake Bistineau, as well as Black Lake, Cado Lake, Spanish Lake, Natchitoches Lake, and many others, have been formed, according to Darby, by the gradual elevation of the bed of Red River, in which the alluvial accumulations have been so great as to raise its channel, and cause its waters, during the flood season, to flow up the mouths of many tributaries, and to convert parts of their courses into lakes. In the autumn, when the level of Red River is again depressed, the waters rush back, and some lakes become grassy meadows, with streams meandering through them.* Thus, there is a periodical flux and reflux between Red River and some of these basins, which are merely reservoirs, alternately emptied and filled, like our tide estuaries—with this difference, that in the one case the land is submerged for several months continuously, and in the other twice in every twenty-four hours. It has happened, in several cases, that a raft of timber or a bar has been thrown by Red River across some of the openings of these channels, and then the lakes become, like Bistineau, constant repositories of water. But, even in these cases, their level is liable to annual elevation and depression, because the flood of the main river, when at its height, passes over the bar; just as, where sand-hills close the entrance of an estuary on the Norfolk or Suffolk coast, the sea, during some high tide or storm, has often breached the barrier and inundated again the interior.

I am informed by Mr. Featherstonhaugh that the plains of the Red River and the Arkansas are so low and flat, that whenever the Mississippi rises thirty feet above its ordinary level, those great tributaries are made to flow back, and inundate a region of vast extent. Both the streams alluded to contain red sediment, derived from the decomposition of red porphyry; and since 1833, when there was a great inundation in the Arkansas, an immense swamp has been formed near the Mammelle mountain, comprising 30,000 acres, with here and there large lagoons where the old bed of the river was situated; in which innumerable trees, for the most part dead, are seen standing, of cypress, cotton-wood, or poplar, the triple-thorned acacia, and others, which are of great size. Their trunks appear as if painted red for about fifteen feet from the ground; at which height a perfectly level line extends through the whole forest, marking the rise of the waters during the last flood.*

---

* Darby's Louisiana, p. 33.

But most probably the causes above assigned for the recent origin of these lakes are not the only ones. Subterranean movements have altered, so lately as the years 1811–12, the relative levels of various parts of the basin of the Mississippi, situated 300 miles north-east of Lake Bistineau. In those years the great valley, from the mouth of the Ohio to that of the St. Francis, including a tract 300 miles in length, and exceeding in area the whole basin of the Thames, was convulsed to such a degree, as to create new islands in the river, and lakes in the alluvial plain. Some of these were on the left or east bank of the Mississippi, and were twenty miles in extent; as, for example, those named Reelfoot and Obion in Tenessee, formed in the channels or valleys of small streams bearing the same names.†

But the largest area affected by the great convulsion lies eight or ten miles to the westward of the Mississippi, and inland from the town of New Madrid, in Missouri. It is called "the sunk country," and is said to extend along the course of the White Water and its tributaries, for a distance of between seventy and eighty miles north and south, and thirty miles or more east and west. Throughout this area, innumerable submerged trees, some standing leafless, others prostrate, are seen; and so great is the extent of lake and marsh, that an active trade in the skins of musk-rats, mink, otters, and other wild animals, is now carried on there. In March, 1846, I skirted the borders of the "sunk country" nearest to New Madrid, passing along the Bayou St. John and Little Prairie, where dead trees of various kinds, some erect in the water, others fallen, and strewed in dense masses over the bottom, in the shallows, and near the shore, were conspicuous. I also beheld countless rents in the adjoining dry alluvial plains, caused by the movements of the soil in 1811–12, and still open, though the rains, frost, and river inundations, have greatly diminished their original depth. I observed, moreover, numerous circular cavities, called "sunk holes," from ten to thirty yards wide, and twenty feet or more in depth, which interrupt the general level of the plain. These were formed by the spouting out of large quantities of sand and mud during the earthquakes.*

---

* Featherstonhaugh, Geol. Report, Washington, 1835, p. 84.

† Trees submerged in an upright position have been observed in other parts of N. America. Thus Captains Clark and Lewis found, about the year 1807, a forest of pines standing erect under water in the body of the Columbia river, which they supposed, from the appearance of the trees, to have been submerged only about twenty years. (Travels, &c. vol. ii. p. 241.) More lately (1835), the Rev. Mr. Parker observed on the same river (lat. 45° N., long. 121° W.) trees standing in their natural position in spots where the water was more than twenty feet deep. The tops of the trees had disappeared; but between high and low water-mark the trunks were only partially decayed; and the roots were seen through the clear water, spreading as they had grown in their native forest. (Tour beyond the Rocky Mountains, p. 132.) Some have inferred from these facts that a tract of land, more than twenty miles in length, must have subsided vertically; but Capt. Frémont, Dec. 1845 (Rep. of Explor. Exped. p. 195.), satisfied himself that the submerged forests have been formed by immense land-slides from the mountains, which here closely shut in the river.

That the prevailing changes of level in the delta and alluvial plain of the Mississippi have been caused by the subsidence, rather than the upheaval of land, appears to me established by the fact, that there are no protuberances of upraised alluvial soil, projecting above the level surface of the great plain. It is true that the gradual elevation of that plain, by new accessions of matter, would tend to efface every inequality derived from this source, but we might certainly have expected to find more broken ground between the opposite bluffs, had local upthrows of alluvial strata been of repeated occurrence.

Antiquity of the delta.—The vast size of the alluvial plain both above and below the head of the delta, or the branching off of the uppermost arm of the Atchafalaya, has been already alluded to. Its superficial dimensions, according to Mr. Forshey, exceed 30,000 square miles, nearly half of which belong to the true delta. The deposits consist partly of sand originally formed upon or near the banks of the river, and its tributaries, partly of gravel, swept down the main channel, of which the position has continually shifted, and partly of fine mud slowly accumulated in the swamps. The farther we descend the river towards its mouth, the finer becomes the texture of the sediment. The whole alluvial formation, from the base of the delta upwards, slopes with a very gentle inclination, rising about three inches in a mile from the level of the sea at the Balize, to the height of about 200 feet in a distance of about 800 miles.

That a large portion of this fluviatile deposit, together with the fluvio-marine strata now in progress near the Balize, consists of mud and sand with much vegetable matter intermixed, may be inferred from what has been said of the abundance of drift trees floated down every summer. These are seen matted together into a net-work around the extensive mud banks at the extreme mouths of the river. Every one acquainted with the geography of Louisiana is aware that the most southern part of the delta forms a long narrow tongue of land protruding for 50 miles into the Gulf of Mexico, at the end of which are numerous channels of discharge. This singular promontory consists simply of the river and its two low, flat banks, covered with reeds, young willows, and poplars. Its appearance answers precisely to that of the banks far in the interior, when nothing appears above water during inundations but the higher part of the sloping glacis or bank. In the one case we have the swamps o expanse of fresh water with the tops of trees appearing above, in other the bluish green surface of the Gulf of Mexico. An opi has very commonly prevailed that this narrow promontory, the ne product of the river, has gained very rapidly upon the sea, since foundation of New Orleans; but after visiting the Balize in 1846 company with Dr. Carpenter, and making many inquiries of pilots, and comparing the present outline of the coast with the ex lent Spanish chart, published by Charlevoix 120 years before, came to a different conclusion. The rate of permanent advance the new land has been very slow, not exceeding perhaps one mil a century. The gain may have been somewhat more rapid in for years, when the new strip of soil projected less far into the gulf, s it is now much more exposed to the action of a strong marine curr The tides also, when the waters of the river are low, enter into opening, and scour them out, destroying the banks of mud and sand bars newly formed during the flood season.

---

* For an account of the "sunk country," shaken by the earthquake of 1811–1812, see Lyell's Second Visit to the United States, ch. 33.

An observation of Darby, in regard to the strata composing pa this delta, deserves attention. In the steep banks of the Atchafal before alluded to, the following section, he says, is observable at water:—first an upper stratum, consisting invariably of bluish c common to the banks of the Mississippi; below this a stratum of re ochreous earth, peculiar to Red River, under which the blue clay o the Mississippi again appears; and this arrangement is constant, proving, as that geographer remarks, that the waters of the Mississippi and the Red River occupied alternately, at some former periods, considerable tracts below their present point of union.* Such alternations are probably common in submarine spaces situated between two converging deltas; for, before the two rivers unite, there must almost always be a certain period when an intermediate tract will by turns be occupied and abandoned by the waters of each stream; since it can rarely happen that the season of highest flood will precisely correspond in each. In the case of the Red River and Mississippi, which carry off the waters from countries placed under widely distant latitudes, an exact coincidence in the time of greatest inundation is very improbable.

The antiquity of the delta, or length of the period which has been occupied in the deposition of so vast a mass of alluvial matter, is a question which may well excite the curiosity of every geologist. Sufficient data have not yet been obtained to afford a full and satisfactory answer to the inquiry, but some approximation may already be made to the minimum of time required.

When I visited New Orleans, in February 1846, I found that Dr. Riddell had made numerous experiments to ascertain the proportion of sediment contained in the waters of the Mississippi; and he concluded that the mean annual amount of solid matter was to the water as $\frac{1}{1245}$ in weight, or about $\frac{1}{3000}$ in volume.† From the observations of the same gentleman, and those of Dr. Carpenter and Mr. Forshey, an eminent engineer, to whom I have before alluded, the average width, depth, and velocity of the Mississippi, and thence the mean annual discharge of water, were deduced. I assumed 528 feet, or the tenth of a mile, as the probable thickness of the deposit of mud and sand in the delta; founding my conjecture chiefly on the depth of the Gulf of Mexico, between the southern point of Florida and the Balize, which equals on an average 100 fathoms, and partly on some borings 600 feet deep in the delta, near Lake Pontchartrain, north of New Orleans, in which the bottom of the alluvial matter is said not to have been reached. The area of the delta being about 13,600 square statute miles, and the quantity of solid matter annually brought down by the river 3,702,758,400 cubic feet, it must have taken 67,000 years for the formation of the whole; and if the alluvial matter of the plain above be 264 feet deep, or half that of the delta†, it must have required 33,500 more years for its accumulation, even if its area be estimated as only equal to that of the delta, whereas it is in fact larger. If some deduction be made from the time here stated, in consequence of the effect of the drift-wood, which must have aided in filling up more rapidly the space above alluded to, a far more important allowance must be made on the other hand, for the loss of matter owing to the finer particles of mud not settling at the mouths of the river, but being swept out far to sea during the predominant action of the tides, and the waves in the winter months, when the current of fresh water is feeble. Yet, however vast the time during which the Mississippi has been transporting its earthy burden to the ocean, the whole period, though far exceeding perhaps 100,000 years, must be insignificant in a geological point of view, since the bluffs or cliffs, bounding the great valley, and therefore older in date, and which are from 50 to 250 feet in perpendicular height, consist in great part of loam containing land, fluviatile, and lacustrine shells of species still inhabiting the same country. (See fig. 23. p. 265.)

---

* Darby's Louisiana, p. 103.

† The calculations here given were communicated to the British Associatio in a lecture which I delivered at South

Before we take leave of the great delta, we may derive an in-

---

ampton in September, 1846. (See Athenæum Journal, Sept. 26. 1846, and Report of British Association, 1846, p. 117.) Dr. Riddell has since repeated his experiments on the quantity of sediment in the river at New Orleans without any material variation in the results.

Mr. Forshey, in a memoir on the Physics of the Mississippi, published in 1850, adopts Dr. Riddell's estimate for the quantity of mud, but takes 447,199 cubic feet per second as the average discharge of water for the year at Carrolton, nine miles above New Orleans, a result deduced from thirty years of observations. This being one tenth more than I had assumed would add a tenth to the sediment, and would diminish by one eleventh the number of years required to accomplish the task above alluded to. "The cubic contents of sedimentary matter," says Forshey, "are equal to 4,083,333,333, and this sediment would annually cover twelve miles square one foot deep."

† The Mississippi is continually shifting its course in the great alluvial plain, cutting frequently to the depth of 100. and even sometimes to the depth of 250 feet. As the old channels become afterwards filled up, or in a great degree obliterated, this excavation alone must have given a considerable depth to the basin, which receives the alluvial deposit, and subsidences like those accompanying the earthquake of New Madrid in 1811 — 1812 may have given still more depth.

structive lesson from the reflection that the new deposits al formed, or now accumulating, whether marine or freshwater, greatly resemble in composition, and the general character of organic remains, many ancient strata which enter largely into the structure. Yet there is no sudden revolution in progress, whethe the land or in the waters, whether in the animate or the inani world. Notwithstanding the excessive destruction of soil uprooting of trees, the region which yields a never-failing supp drift-wood is densely clothed with noble forests, and is al unrivalled in its power of supporting animal and vegetable life. spite of the undermining of many a lofty bluff and the encroach of the delta on the sea—in spite of the earthquake, which rende fissures the soil, or causes areas more than sixty miles in lengt sink down several yards in a few months, the general features o district remain unaltered, or are merely undergoing a slow insensible change. Herds of wild deer graze on the pastures, or br upon the trees; and if they diminish in number, it is only where give way to man and the domestic animals which follow in his The bear, the wolf, the fox, the panther, and the wild-cat maintain themselves in the fastnesses of the forests of cypress gum-tree. The racoon and the opossum are everywhere abund while the musk-rat, otter, and mink still frequent the rivers lakes, and a few beavers and buffaloes have not yet been driv from their ancient haunts. The waters teem with alligators, toises, and fish, and their surface is covered with millions of mig tory waterfowl, which perform their annual voyage between Canadian lakes and the shores of the Mexican Gulf. The pow of man begins to be sensibly felt, and many parts of the wilder to be replaced by towns, orchards, and gardens. The gilded ste boats, like moving palaces, stem the force of the current, or sho rapidly down the descending stream, through the solitudes of forests and prairies. Already does the flourishing population of great valley far exceed that of the thirteen United States when they declared their independence. Such is the state of a contin where trees and stones are hurried annually, by a thousand torre from the mountains to the plains, and where sand and finer ma are swept down by a vast current to the sea, together with the wr of countless forests and the bones of animals which perish in inundations. When these materials reach the gulf, they do render the waters unfit for aquatic animals; but, on the contr the ocean here swarms with life, as it generally does where the in of a great river furnishes a copious supply of organic and min matter. Yet many geologists, when they behold the spoils of land heaped in successive strata, and blended confusedly with remains of fishes, or interspersed with broken shells and cor when they see portions of erect trunks of trees with their ro still retaining their natural position, and one tier of these preserv in a fossil state above another, imagine that they are viewing signs of a turbulent instead of a tranquil and settled state of planet. They read in such phenomena the proof of chaotic disorder and reiterated catastrophes, instead of indications of a surface as habitable as the most delicious and fertile districts now tenanted by man.

DELTA OF THE GANGES AND BRAHMAPOOTRA.

As an example of a still larger delta advancing upon the sea in opposition to more powerful tides, I shall next describe that of the Ganges and Brahmapootra (or Burrampooter). These, the two principal rivers of India, descend from the highest mountains in the world, and partially mingle their waters in the low plains of Hindoostan, before reaching the head of the Bay of Bengal. The Brahmapootra, somewhat the larger of the two, formerly passed to the east of Dacca, even so lately as the beginning of the present century, pouring most of its waters into one of the numerous channels in the delta called "the Megna." By that name the main stream was always spoken of by Rennell and others in their memoirs on this region. But the main trunk now unites with an arm of the Ganges considerably higher up, at a point about 100 miles distant from the sea; and it is constantly, according to Dr. Hooker, working its way westward, having formerly, as may be seen by ancient maps, moved eastward for a long period.

The area of the delta of the combined rivers, for it is impossible now to distinguish what belongs to each, is considerably more than double that of the Nile, even if we exclude from the delta a large extent of low, flat, alluvial plain, doubtless of fluviatile origin, which stretches more than 100 miles to the hills west of Calcutta (see map, fig. 25.), and much farther in a northerly direction beyond the head of

Fig. 26.



Map of the Delta of the Ganges and Brahmapootra.

the great delta. The head of a delta is that point where the first a is given off. Above that point a river receives the waters of trib taries flowing from higher levels; below it, on the contrary, it giv out portions of its waters to lower levels through channels which fl into adjoining swamps, or which run directly to the sea. The Miss sippi, as before described, has a single head, which originated at unknown period when the Red River joined it. In the great de of Bengal there may be said to be two heads nearly equidistant fr the sea, that of the Ganges (G, map, fig. 25.), about 30 miles bel Rajmahal, or 216 statute miles in a direct line from the sea, and th of the Brahmapootra (B) below Chirapoonjee, where the river iss from the Khasia mountains, a distance of 224 miles from the Bay Bengal.

It will appear, by reference to the map, that the great body of fre water derived from the two rivers enters the bay on its eastern sid and that a large part of the delta bordering on the sea is composed a labyrinth of rivers and creeks, all filled with salt water, except tho immediately communicating with the Hoogly, or principal arm of th Ganges. This tract alone, known by the name of the Woods, Sunderbunds (more properly Soonderbuns), a wilderness infested tigers and crocodiles, is, according to Rennell, equal in extent to th whole principality of Wales.*

On the sea-coast there are eight great openings, each of which ha evidently, at some ancient period, served in its turn as the princip channel of discharge. Although the flux and reflux of the tid extend even to the heads of the delta when the rivers are low, ye when they are periodically swollen by tropical rains, their volum and velocity counteract the tidal current, so that, except very ne the sea, the ebb and flow become insensible. During the floo season, therefore, the Ganges and Brahmapootra almost assume their delta the character of rivers entering an inland sea; the move ments of the ocean being then subordinate to the force of the river and only slightly disturbing their operations. The great gain of th delta in height and area takes place during the inundations; an during other seasons of the year, the ocean makes reprisals, scourin out the channels, and sometimes devouring rich alluvial plains.

Islands formed and destroyed. — Major R. H. Colebrooke, in h account of the course of the Ganges, relates examples of the rap filling up of some of its branches, and the excavation of new channel where the number of square miles of soil removed in a short tim (the column of earth being 114 feet high) was truly astonishin Forty square miles, or 25,600 acres, are mentioned as having bee carried away, in one place, in the course of a few years.† Th immense transportation of earthy matter by the Ganges and Brahma pootra is proved by the great magnitude of the islands formed i their channels during a period far short of that of a man's life. So

---

[*] Account of the Ganges and Burrampooter rivers, by Major Rennell, Phil. Trans. 1781.

[†] Trans. of the Asiatic Society, v vii. p. 14.

of these, many miles in extent, have originated in large sand-banks thrown up round the points at the angular turning of the rivers, and afterwards insulated by breaches of the streams. Others, formed in the main channel, are caused by some obstruction at the bottom. A large tree, or a sunken boat, is sometimes sufficient to check the current, and cause a deposit of sand, which accumulates till it usurps a considerable portion of the channel. The river then undermines its banks on each side, to supply the deficiency in its bed, and the island is afterwards raised by fresh deposits during every flood. In the great gulf below Luckipour, formed by the united waters of the Ganges and Megna, some of the islands, says Rennell, rival in size and fertility the Isle of Wight. While the river is forming new islands in one part, it is sweeping away old ones in others. Those newly formed are soon overrun with reeds, long grass, the Tamarix Indica, and other shrubs, forming impenetrable thickets, where the tiger, the rhinoceros, the buffalo, deer, and other wild animals, take shelter. It is easy, therefore, to perceive, that both animal and vegetable remains may occasionally be precipitated into the flood, and become imbedded in the sediment which subsides in the delta.

Three or four species of crocodile, of two distinct sub-genera, abound in the Ganges, and its tributary and contiguous waters; and Mr. H. T. Colebrooke informed me, that he had seen both forms in places far inland, many hundred miles from the sea. The Gangetic crocodile, or Gavial, (in correct orthography, Garial,) is confined to the fresh water, living exclusively on fish, but the commoner kinds, called Koomiah and Muggar, frequent both fresh and salt, being much larger and fiercer in salt and brackish water.* These animals swarm in the brackish water along the line of sand-banks, where the advance of the delta is most rapid. Hundreds of them are seen together in the creeks of the delta, or basking in the sun on the shoals without. They will attack men and cattle, destroying the natives when bathing, and tame and wild animals which come to drink. "I have not unfrequently," says Mr. Colebrooke, "been witness to the horrid spectacle of a floating corpse seized by a crocodile with such avidity, that he half emerged above the water with his prey in his mouth." The geologist will not fail to observe how peculiarly the habits and distribution of these saurians expose them to become imbedded in the horizontal strata of fine mud, which are annually deposited over many hundred square miles in the Bay of Bengal. The inhabitants of the land, which happen to be drowned or thrown into the water, are usually devoured by these voracious reptiles; but we may suppose the remains of the saurians themselves to be con-

---

[*] Cuvier referred the true crocodiles of the Ganges to a single species, *C. biporcatus*. But I learn from Dr. Falconer that there are three well-marked species, *C. biporcatus*, *C. palustris*, and *C. bombifrons*. *C. bombifrons* occurs in the northern branches of the Ganges, 1000 miles from Calcutta; *C. biporcatus* appears to be confined to the estuary; and *C. palustris*, to range from the estuary to the central parts of Bengal. The Garial is found along with *C. bombifrons* in the north, and descends to the region of *C. biporcatus* in the estuary.

tinually entombed in the new formations. The number, als bodies of the poorer class of Hindoos thrown annually into Ganges is so great, that some of their bones or skeletons can h fail to be occasionally enveloped in fluviatile mud.

It sometimes happens, at the season when the periodical flood its height, that a strong gale of wind, conspiring with a high spr tide, checks the descending current of the river, and gives ris most destructive inundations. From this cause, in the year 1763, waters at Luckipour rose six feet above their ordinary level, and inhabitants of a considerable district, with their houses and ca were totally swept away.

The population of all oceanic deltas are particularly exposed suffer by such catastrophes, recurring at considerable interval time; and we may safely assume that such tragical events have h pened again and again since the Gangetic delta was inhabited by m If human experience and forethought cannot always guard ag these calamities, still less can the inferior animals avoid them; the monuments of such disastrous inundations must be looked fo great abundance in strata of all ages, if the surface of our planet h always been governed by the same laws. When we reflect on general order and tranquillity that reigns in the rich and popu delta of Bengal, notwithstanding the havoc occasionally committed b the depredations of the ocean, we perceive how unnecessary it is t attribute the imbedding of successive races of animals in older stra to extraordinary energy in the causes of decay and reproduction i the infancy of our planet, or to those general catastrophes and sudd revolutions so often resorted to.

Deposits in the delta.—The quantity of mud held in suspensi by the waters of the Ganges and Brahmapootra is found, as might b expected, to exceed that of any of the rivers alluded to in this or th preceding chapters; for, in the first place, their feeders flow fro mountains of unrivalled altitude, and do not clear themselves in an lakes, as does the Rhine in the Lake of Constance, or the Rhone i that of Geneva. And, secondly, their whole course is nearer th equator than that of the Mississippi, or any great river, respectin which careful experiments have been made, to determine the quanti of its water and earthy contents. The fall of rain, moreover, as w have before seen, is excessive on the southern flanks of the first ran of mountains which rise from the plains of Hindoostan, and still mo remarkable is the quantity sometimes poured down in one day. (S above, p. 200.) The sea, where the Ganges and Brahmapootra discha their main stream at the flood season, only recovers its transparen at the distance of from 60 to 100 miles from the delta; and we m take for granted that the current continues to transport the finer pa ticles much farther south than where the surface water first becom clear. The general slope, therefore, of the new strata must be e tremely gentle. According to the best charts, there is a gradu deepening from four to about sixty fathoms, as we proceed from t base of the delta to the distance of about one hundred miles into t

Bay of Bengal. At some few points seventy, or even one hundred, fathoms are obtained at that distance.

One remarkable exception, however, occurs to the regularity of the shape of the bottom. Opposite the middle of the delta, at the distance of thirty or forty miles from the coast, a deep submarine valley occurs, called the "swatch of no ground," about fifteen miles in diameter, where soundings of 180, and even 300, fathoms fail to reach the bottom. (See map, p. 275.) This phenomenon is the more extraordinary, since the depression runs north to within five miles of the line of shoals; and not only do the waters charged with sediment pass over it continually, but, during the monsoons, the sea, loaded with mud and sand, is beaten back in that direction towards the delta. As the mud is known to extend for eighty miles farther into the gulf, an enormous thickness of matter must have been deposited in "the swatch." We may conclude, therefore, either that the original depth of this part of the Bay of Bengal was excessive, or that subsidences have occurred in modern times. The latter conjecture is the less improbable, as the whole area of the delta has been convulsed in the historical æra by earthquakes, and actual subsidences have taken place in the neighbouring coast of Chittagong, while "the swatch" lies not far from the volcanic band which connects Sumatra, Barren Island, and Ramree.*

Opposite the mouth of the Hoogly river, and immediately south of Saugor Island, four miles from the nearest land of the delta, a new islet was formed about twenty years ago, called Edmonstone Island, on the centre of which a beacon was erected as a landmark in 1817. In 1818 the island had become two miles long and half a mile broad, and was covered with vegetation and shrubs. Some houses were then built upon it, and in 1820 it was used as a pilot station. The severe gale of 1823 divided it into two parts, and so reduced its size as to leave the beacon standing out in the sea, where, after remaining seven years, it was washed away. The islet in 1836 had been converted by successive storms into a sand-bank, half a mile long, on which a sea-mark was placed.

Although there is evidence of gain at some points, the general progress of the coast is very slow; for the tides, when the river water is low, are actively employed in removing alluvial matter. In the Sunderbunds the usual rise and fall of the tides is no more than eight feet, but, on the east side of the delta, Dr. Hooker observed, in the winter of 1851, a rise of from sixty to eighty feet, producing among the islands at the mouths of the Megna and Fenny rivers, a lofty wave or "bore" as they ascend, and causing the river water to be ponded back, and then to sweep down with great violence when the tide ebbs. The bay for forty miles south of Chittagong is so fresh that neither algæ nor mangroves will grow in it. We may, therefore, conceive how effective may be the current formed by so great a volume of water in dispersing fine mud over a wide area. Its power is sometimes augmented by the agitation of the bay during hurrica in the month of May. The new superficial strata consist entirely fine sand and mud; such, at least, are the only materials which exposed to view in regular beds on the banks of the numerous cree Neither here nor higher up the Ganges, could Dr. Hooker disco any land or freshwater shells in sections of the banks, which in t plains higher up sometimes form cliffs eighty feet in height at l water. In like manner I have stated* that I was unable to fi any buried shells in the delta or modern river cliffs of the Mississip

---

* See below, ch. 22. and 29.

No substance so coarse as gravel occurs in any part of the de of the Ganges and Brahmapootra, nor nearer the sea than 400 mil Yet it is remarkable that the boring of an Artesian well Fort William, near Calcutta, in the years 1835—1840, display at the depth of 120 feet, clay and sand with pebbles. This bor was carried to a depth of 481 feet below the level of Calc and the geological section obtained in the operation has b recorded with great care. Under the surface soil, at a depth about ten feet, they came to a stiff blue clay about forty feet thickness; below which was sandy clay, containing in its lo portion abundance of decayed vegetable matter, which at the bott assumed the character of a stratum of black peat two feet thi This peaty mass was considered as a clear indication (like the "dirt-bed" of Portland) of an ancient terrestrial surface, with a forest or Sunderbund vegetation. Logs and branches of a red-coloured wood occur both above and immediately below the peat, so little altered that Dr. Wallich was able to identify them with the Soondri tree, *Heritiera littoralis*, one of the most prevalent forms at the base of the delta. Dr. Falconer tells me that similar peat has been met with at other points round Calcutta at the depth of nine feet and twenty-five feet. It appears, therefore, that there has been a sinking down of what was originally land in this region, to the amount of seventy feet or more perpendicular; for Calcutta is only a few feet above the level of the sea, and the successive peat-beds seem to imply that the subsidence of the ground was gradual or interrupted by several pauses. Below the vegetable mass they entered upon a stratum of yellowish clay about ten feet thick, containing horizontal layers of kunkar (or kankar), a nodular, concretionary, argillaceous limestone, met with abundantly at greater or less depths in all parts of the valley of the Ganges, over many thousand square miles, and always presenting the same characters, even at a distance of one thousand miles north of Calcutta. Some of this kunkar is said to be of very recent origin in deposits formed by river inundations near Saharanpoor. After penetrating 120 feet, they found loam containing water-worn fragments of mica-slate and other kinds of rock, which the current of the Ganges can no longer transport to this region. In the various beds pierced through below, consisting of clay, marl, and friable sandstone, with kunkar here and there intermixed, no organic remains of decidedly marine origin were met

---

* Second Visit to the United States, vol. ii. p. 145.

Too positive a conclusion ought not, it is true, to be drawn such a fact, when we consider the narrow bore of the auger and fect in crushing shells and bones. Nevertheless, it is worthy of rk, that the only fossils obtained in a recognizable state were of riatile or terrestrial character. Thus, at the depth of 350 feet, ony shell of a tortoise, or trionyx, a freshwater genus, was found nd, resembling the living species of Bengal. From the same m, also, they drew up the lower half of the humerus of a ruminant, st referred to a hyæna. It was of the size and shape, says alconer, of the shoulder bone of the *Cervus porcinus*, or common eer, of India. At the depth of 380 feet, clay with fragments of rine shells was incumbent on what appears clearly to have been er "dirt-bed," or stratum of decayed wood, implying a period of e of some duration, and a forest-covered land, which must have ded 300 feet, to admit of the subsequent superposition of the ying deposits. It has been conjectured that, at the time when rea supported trees, the land extended much farther out into Bay of Bengal than now, and that in later times the Ganges, enlarging its delta, has been only recovering lost ground from ea.

the depth of about 400 feet below the surface, an abrupt change bserved in the character of the strata, which were composed in part of sand, shingle, and boulders, the only fossils observed the vertebræ of a crocodile, shell of a trionyx, and fragments ood very little altered, and similar to that buried in beds far e. These gravelly beds constituted the bottom of the section at depth of 481 feet, when the operations were discontinued in equence of an accident which happened to the auger.

he occurrence of pebbles at the depths of 120 and 400 feet im- an important change in the geographical condition of the region nd or near Calcutta. The fall of the river, or the general slope e alluvial plain, may have been formerly greater; or, before a ral and perhaps unequal subsidence, hills once nearer the present of the delta may have risen several hundred feet, forming islands e bay, which may have sunk gradually, and become buried under atile sediment.

ntiquity of the delta.—It would be a matter of no small scientific rest, if experiments were made to enable us to determine, with degree of accuracy, the mean quantity of earthy matter discharged ally into the sea by the united waters of the Ganges and Brahootra. The Rev. Mr. Everest instituted, in 1831–2, a series of rvations on the earthy matter brought down by the Ganges, at zepoor, 500 miles from the sea. He found that, in 1831, the ber of cubic feet of water discharged by the river per second at place was during the

Rains (4 months) - - - -	494,208
Winter (5 months) - - -	71,200
Hot weather (3 months) - - -	36,330

so that we may state in round numbers that 500,000 cubic feet per second flow down during the four months of the flood season, from June to September, and less than 60,000 per second during the remaining eight months.

The average quantity of solid matter suspended in the water during the rains was, by weight, $\frac{1}{428}$th part; but as the water is about one half the specific gravity of the dried mud, the solid matter discharged is $\frac{1}{856}$th part in bulk, or 577 cubic feet per second. This gives a total of 6,082,041,600 cubic feet for the discharge in the 122 days of the rain. The proportion of sediment in the waters at other seasons was comparatively insignificant, the total amount during the five winter months being only 247,881,600 cubic feet, and during the three months of hot weather 38,154,240 cubic feet. The total annual discharge, then, would be 6,368,077,440 cubic feet.

This quantity of mud would in one year raise a surface of 228½ square miles, or a square space, each side of which should measure 15 miles, a height of one foot. To give some idea of the magnitude of this result, we will assume that the specific gravity of the dried mud is only one half that of granite (it would, however, be more): in that case, the earthy matter discharged in a year would equal 3,184,038,720 cubic feet of granite. Now about 12½ cubic feet of granite weigh one ton; and it is computed that the great Pyramid of Egypt, if it were a solid mass of granite, would weigh about 6,000,000 tons. The mass of matter, therefore, carried down annually would, according to this estimate, more than equal in weight and bulk forty-two of the great pyramids of Egypt, and that borne down in the four months of the rains would equal forty pyramids. But if, without any conjecture as to what may have been the specific gravity of the mud, we attend merely to the weight of solid matter actually proved by Mr. Everest to have been contained in the water, we find that the number of tons weight which passed down in the 122 days of the rainy season was 339,413,760, which would give the weight of fifty-six pyramids and a half; and in the whole year 355,361,464 tons, or nearly the weight of sixty pyramids.

The base of the great Pyramid of Egypt covers eleven acres, and its perpendicular height is about five hundred feet. It is scarcely possible to present any picture to the mind which will convey an adequate conception of the mighty scale of this operation, so tranquilly and almost insensibly carried on by the Ganges, as it glides through its alluvial plain, even at a distance of 500 miles from the sea. It may, however, be stated, that if a fleet of more than eighty Indiamen, each freighted with about 1400 tons' weight of mud, were to sail down the river every hour of every day and night for four months continuously, they would only transport from the higher country to the sea a mass of solid matter equal to that borne down by the Ganges, even in this part of its course, in the four months of the flood season. Or the exertions of a fleet of about 2000 such ships going down daily with the same burden, and discharging it into the gulf, ould be no more than equivalent to the operations of the great iver.

The most voluminous current of lava which has flowed from Etna ithin historical times was that of 1669. Ferrara, after correcting orelli's estimate, calculated the quantity of cubic yards of lava in his current at 140,000,000. Now, this would not equal in bulk one fth of the sedimentary matter which is carried down in a single year y the Ganges, past Ghazepoor, according to the estimate above ex- lained ; so that it would require five grand eruptions of Etna to ansfer a mass of lava from the subterranean regions to the surface, ual in volume to the mud carried down in one year to that place.

Captain R. Strachey, of the Bengal Engineers, has remarked to me, t only that Ghazepoor, where Mr. Everest's observations were ade, is 500 miles from the sea, but that the Ganges has not been ined there by its most important feeders. These drain upon the hole 750 miles of the Himalaya, and no more than 150 miles of that ountain-chain have sent their contributions to the main trunk at hazepoor. Below that place, the Ganges is joined by the Gogra, unduk, Khosee, and Teesta from the north, to say nothing of the ne flowing from the south, one of the largest of the rivers which e in the table-land of central India. (See map, fig. 25. p. 275.) oreover the remaining 600 miles of the Himalaya comprise that stern portion of the basin where the rains are heaviest. (See above, 200.) The quantity of water therefore carried down to the sea ay probably be four or five times as much as that which passes hazepoor.

The Brahmapootra, according to Major Wilcox*, in the month of nuary, when it is near its minimum, discharges 150,000 cubic feet water per second at Gwalpara, not many miles above the head of delta. Taking the proportions observed at Ghazepoor at the dif- rent seasons as a guide, the probable average discharge of the rahmapootra for the whole year may be estimated at about the me as that of the Ganges. Assuming this ; and secondly, in order avoid the risk of exaggeration, that the proportion of sediment in eir waters is about a third less than Mr. Everest's estimate, the mud rne down to the Bay of Bengal in one year would equal 40,000 illions of cubic feet, or between six and seven times as much as at brought down to Ghazepoor, according to Mr. Everest's calcu- tions in 1831, and ten times as much as that conveyed annually by e Mississippi to the Gulf of Mexico.

Captain Strachey estimates the annually inundated portion of the lta at 250 miles in length by 80 in breadth, making an area of 0,000 square miles. The space south of this in the bay, where diment is thrown down, may be 300 miles from E. to W. by 150 . and S., or 45,000 square miles, which, added to the former, gives a rface of 65,000 square miles, over which the sediment is spread out by the two rivers. Suppose then the solid matter to amo to 40,000 millions of cubic feet per annum, the deposit, he serves, must be continued for forty-five years and three tenth raise the whole area, a height of one foot, or 13,600 years to rais 300 feet; and this, as we have seen, is much less than the thicknes the fluviatile strata actually penetrated, (and the bottom not reach by the auger at Calcutta.

---

* Asiatic Researches, vol. xvii. p. 466.

Nevertheless we can by no means deduce from these data alo what will be the future rate of advance of the delta, nor even predi whether the land will gain on the sea, or remain stationary. At t end of 13,000 years the bay may be less shallow than now, provide a moderate depression, corresponding to that experienced in part Greenland for many centuries shall take place (see chap. 30.). subsidence quite insensible to the inhabitants of Bengal, not exceeding two feet three inches in a century, would be more tha sufficient to counterbalance all the efforts of the two mighty river to extend the limits of their delta. We have seen that the Artesia borings at Calcutta attest, what the vast depth of the "swatch may also in all likelihood indicate, that the antagonist force o subsidence has predominated for ages over the influx of fluviatil mud, preventing it from raising the plains of Bengal, or from fillin up a larger portion of the bay.

CONCLUDING REMARKS ON DELTAS.

Convergence of deltas.—If we possessed an accurate series of map of the Adriatic for many thousand years, our retrospect would, without doubt, carry us gradually back to the time when the number rivers descending from the mountains into that gulf by independen deltas was far greater in number. The deltas of the Po and th Adige, for instance, would separate themselves within the *recent* er as, in all probability, would those of the Isonzo and the Torre. I on the other hand, we speculate on future changes, we may anticipat the period when the number of deltas will greatly diminish; for th Po cannot continue to encroach at the rate of a mile in a hundre years, and other rivers to gain as much in six or seven centuries upo the shallow gulf, without new junctions occurring from time to time so that Eridanus, "the king of rivers," will continually boast a great number of tributaries. The Ganges and the Brahmapootra hav perhaps become partially confluent in the same delta within the hi torical, or at least within the human, era; and the date of the juncti of the Red River and the Mississippi would, in all likelihood, ha been known, if America had not been so recently discovered. T union of the Tigris and the Euphrates must undoubtedly have be one of the modern geographical changes of our Earth, for C Rawlinson informs me that the delta of those rivers has advanced t miles in the last sixty years, and is supposed to have encroach about forty miles upon the Gulf of Persia in the course of the l twenty-five centuries.

When the deltas of rivers, having many mouths, converge, a partial union at first takes place by the confluence of some one or more of their arms; but it is not until the main trunks are connected above the head of the common delta, that a complete intermixture of their joint waters and sediment takes place. The union, therefore, of the Po and Adige, and of the Ganges and Brahmapootra, is still incomplete. If we reflect on the geographical extent of surface drained by rivers such as now enter the Bay of Bengal, and then consider how complete the blending together of the greater part of their transported matter has already become, and throughout how vast a delta it is spread by numerous arms, we no longer feel so much surprise at the area occupied by some ancient formations of homogeneous mineral composition. But our surprise will be still farther lessened, when we afterwards inquire (ch. 21.) into the action of tides and currents in disseminating sediment.

Age of existing deltas. — If we could take for granted, that the relative level of land and sea had remained stationary ever since all the existing deltas began to be formed — could we assume that their growth commenced at one and the same, instant when the present continents acquired their actual shape — we might understand the language of geologists who speak of "the epoch of existing continents." They endeavour to calculate the age of deltas from this imaginary fixed period; and they calculate the gain of new land upon the sea, at the mouths of rivers, as having begun everywhere simultaneously. But the more we study the history of deltas, the more we become convinced that upward and downward movements of the land and contiguous bed of the sea have exerted, and continue to exert, an influence on the physical geography of many hydrographical basins, on a scale comparable in magnitude or importance to the amount of fluviatile deposition effected in an equal lapse of time. In the basin of the Mississippi, for example, proofs both of descending and ascending movements to a vertical amount of several hundred feet can be shown to have taken place since the existing species of land and freshwater shells lived in that region.*

The deltas also of the Po and Ganges have each, as we have seen (p. 257.), when probed by the Artesian auger, borne testimony to a gradual subsidence of land to the extent of several hundred feet — old terrestrial surfaces, turf, peat, forest-land, and "dirt-beds," having been pierced at various depths. The changes of level at the mouth of the Indus in Cutch (see below, chap. 27.), and those of New Madrid in the valley of the Mississippi (see p. 270. and chap. 27.), are equally instructive, as demonstrating unceasing fluctuations in the levels of those areas into which running water is transporting sediment. If, therefore, the exact age of all modern deltas could be known, it is scarcely probable that we should find any two of them in the world to have coincided in date, or in the time when their earliest deposits originated.

* Lyell's Second Visit to the United States, vol. ii. chap. 34.

Grouping of strata in deltas. — The changes which have tak place in deltas, even within the times of history, may suggest ma important considerations in regard to the manner in which subaque sediment is distributed. With the exception of some cases hereaf to be noticed, there are some general laws of arrangement whi must evidently hold good in almost all the lakes and seas now filli up. If a lake, for example, be encircled on two sides by lofty mou tains, receiving from them many rivers and torrents of different siz and if it be bounded on the other sides, where the surplus wat issue, by a comparatively low country, it is not difficult to def some of the leading geological features which must characterise th lacustrine formation, when this basin shall have been gradually co verted into dry land by the influx of sediment. The strata would divisible into two principal groups: the *older* comprising th deposits which originated on the side adjoining the mountains, wh numerous deltas first began to form; and the *newer* group consisti of beds deposited in the more central parts of the basin, and towar the side farthest from the mountains. The following charact would form the principal marks of distinction between the strata each series: — The more ancient system would be composed, for th most part, of coarser materials, containing many beds of pebbles and sand, often of great thickness, and sometimes dipping at a considerable angle. These, with associated beds of finer ingredients, would, if traced round the borders of the basin, be seen to vary greatly in colour and mineral composition, and would also be very irregular in thickness. The beds, on the contrary, in the newer group, would consist of finer particles, and would be horizontal, or very slightly inclined. Their colour and mineral composition would be very homogeneous throughout large areas, and would differ from almost all the separate beds in the older series.

The following causes would produce the diversity here alluded to between the two great members of such lacustrine formations: — When the rivers and torrents first reach the edge of the lake, the detritus washed down by them from the adjoining heights sinks at once into deep water, all the heavier pebbles and sand subsiding near the shore. The finer mud is carried somewhat farther out, but not to the distance of many miles, for the greater part may be seen, as, for example, where the Rhone enters the Lake of Geneva, to fall down in clouds to the bottom, not far from the river's mouth. Thus alluvial tracts are soon formed at the mouths of every torrent and river, and many of these in the course of ages become of considerable extent. Pebbles and sand are then transported farther from the mountains; but in their passage they decrease in size by attrition, and are in part converted into mud and sand. At length some of the numerous deltas, which are all directed towards a common centre, approach near to each other; those of adjoining torrents become united, and each is merged, in its turn, in the delta of the largest river, which advances most rapidly into the lake, and renders all the minor streams, one after the other, its tributaries. The various mineral ingredients of all are thus blended together into one homogeneous mixture, and the sediment is poured out from a common channel into the lake.

As the average size of the transported particles decreases, while the force and volume of the main river augments, the newer deposits are diffused continually over a wider area, and are consequently more horizontal than the older. When at first there were many independent deltas near the borders of the basin, their separate deposits differed entirely from each other; one may have been charged, like the Arve where it joins the Rhone, with white sand and sediment derived from granite — another may have been black, like many streams in the Tyrol, flowing from the waste of decomposing rocks of dark slate — a third may have been coloured by ochreous sediment, like the Red River in Louisiana — a fourth, like the Elsa in Tuscany, may have held much carbonate of lime in solution. At first they would each form distinct deposits of sand, gravel, limestone, marl, or other materials; but, after their junction, new chemical combinations and a distinct colour would be the result, and the particles, having been conveyed ten, twenty, or a greater number of miles over alluvial plains, would become finer.

In those deltas where the tides and strong marine currents interfere, the above description would only be applicable, with certain modifications. If a series of earthquakes accompany the growth of a delta, and change the levels of the land from time to time, as in the region where the Indus now enters the sea, the phenomena will depart still more widely from the ordinary type. If, after a protracted period of rest, a delta sink down, pebbles may be borne along in shallow water near the foot of the boundary hills, so as to form conglomerates overlying the fine mud previously thrown into deeper water in the same area.

Causes of stratification in deltas. — The stratified arrangement, which is observed to prevail so generally in aqueous deposits, is most frequently due to variations in the velocity of running water, which cannot sweep along particles of more than a certain size and weight when moving at a given rate. Hence, as the force of the stream augments or decreases, the materials thrown down in successive layers at particular places are rudely sorted, according to their dimensions, form, and specific gravity. Where this cause has not operated, as where sand, mud, and fragments of rock are conveyed by a glacier, a confused heap of rubbish devoid of all stratification is produced.

Natural divisions are also occasioned in deltas, by the interval of time which separates annually the deposition of matter during the periodical rains, or melting of the snow upon the mountains. The deposit of each year may acquire some degree of consistency before that of the succeeding year is superimposed. A variety of circumstances also give rise annually, or sometimes from day to day, to slight variations in colour, fineness of the particles, and other characters, by which alternations of strata distinct in texture, and mineral ingredients, must be produced. Thus, for example, at one perio the year, drift wood may be carried down, and, at another, mud was before stated to be the case in the delta of the Mississippi; or one time, when the volume and velocity of the stream are greates pebbles, and sand may be spread over a certain area, over which when the waters are low, fine matter or chemical precipitates are formed. During inundations, the turbid current of fresh water ofte repels the sea for many miles; but when the river is low, salt water again occupies the same space. When two deltas are converging, the intermediate space is often, for reasons before explained, alternately the receptacle of different sediments derived from the converging streams (see p. 272.). The one is, perhaps, charged with calcareous, the other with argillaceous matter; or one sweeps dow sand and pebbles, the other impalpable mud. These differences ma be repeated, with considerable regularity, until a thickness of hundreds of feet of alternating beds is accumulated. The multiplication also, of shells and corals in particular spots, and for limited periods gives rise occasionally to lines of separation, and divides a mas which might otherwise be homogeneous into distinct strata.

An examination of the shell marl now forming in the Scotch lakes or the sediment termed "warp," which subsides from the mudd water of the Humber and other rivers, shows that recent deposit are often composed of a great number of extremely thin layers, eithe even or slightly undulating, and preserving a general parallelism t the planes of stratification. Sometimes, however, the laminæ i modern strata are disposed diagonally at a considerable angle, whic appears to take place where there are conflicting movements in th waters. In January, 1829, I visited, in company with Professo L. A. Necker, of Geneva, the confluence of the Rhone and Arve when those rivers were very low, and were cutting channels throug the vast heaps of débris thrown down from the waters of the Arv in the preceding spring. One of the sand-banks which had formed in the spring of 1828, where the opposing currents of the two river neutralized each other, and caused a retardation in the motion, ha been undermined; and the following is an exact representation o the arrangement of laminæ exposed in a vertical section. The lengt of the portion here seen is about twelve feet, and the height five The strata A A consist of irregular alternations of pebbles and san in undulating beds: below these are seams of very fine sand B B some as thin as paper, others about a quarter of an inch thick. Th strata C C are composed of layers of fine greenish-grey sand as thi as paper. Some of the inclined beds will be seen to be thicker a their upper, others at their lower extremity, the inclination of som being very considerable. These layers must have accumulated on on the other by lateral apposition, probably when one of the river was very gradually increasing or diminishing in velocity, so that th point of greatest retardation caused by their conflicting current shifted slowly, allowing the sediment to be thrown down in successiv layers on a sloping bank. The same phenomenon is exhibited in older strata of all ages.*

Fig. 26.



Section of a sand-bank in the bed of the Arve at its confluence with the Rhone, showing the stratification of deposits where currents meet.

If the bed of a lake or of the sea be sinking, whether at a uniform or an unequal rate, or oscillating in level during the deposition of sediment, these movements will give rise to a different class of phenomena, as, for example, to repeated alternations of shallow-water and deep-water deposits, each with peculiar organic remains, or to frequent repetitions of similar beds, formed at a uniform depth, and inclosing the same organic remains, and to other results too complicated and varied to admit of enumeration here.

Formation of conglomerates. — Along the base of the Maritime Alps, between Toulon and Genoa, the rivers, with few exceptions, are now forming strata of conglomerate and sand. Their channels are often several miles in breadth, some of them being dry, and the rest easily forded for nearly eight months in the year, whereas during the melting of the snow they are swollen, and a great transportation of mud and pebbles takes place. In order to keep open the main road from France to Italy, now carried along the sea-coast, it is necessary to remove annually great masses of shingle brought down during the flood season. A portion of the pebbles are seen in some localities, as near Nice, to form beds of shingle along the shore, but the greater part are swept into a deep sea. The small progress made by the deltas of minor rivers on this coast need not surprise us, when we recollect that there is sometimes a depth of two thousand feet at a few hundred yards from the beach, as near Nice. Similar observations might be made respecting a large proportion of the rivers in Sicily, and, among others, respecting that which, immediately north of the port of Messina, hurries annually vast masses of granitic pebbles into the sea.

Constant interchange of land and sea. — I may here conclude my remarks on deltas, observing that, imperfect as is our information of the changes which they have undergone within the last three thousand years, they are sufficient to show how constant an interchange of sea and land is taking place on the face of our globe. In the Mediterranean alone, many flourishing inland towns, and a still greater number of ports, now stand where the sea rolled its waves since the era of the early civilization of Europe. If we could compare with equal accuracy the ancient and actual state of all the islands and continents, we should probably discover that millions of our race are now supported by lands situated where deep seas prevailed in earlier ages. In many districts not yet occupied by man, land animals and forests now abound where ships once sailed; and, on the other hand, we shall find, on inquiry, that inroads of the ocean have been no less considerable. When to these revolutions, produced by aqueous causes, we add analogous changes wrought by igneous agency, we shall, perhaps, acknowledge the justice of the conclusion of Aristotle, who declared that the whole land and sea on our globe periodically changed places.*

---

* See Manual of Geology by the Author.

CHAPTER XIX.

DESTROYING AND TRANSPORTING EFFECTS OF TIDES AND CURRENTS.

Differences in the rise of the tides—Lagullas and Gulf currents—Velocity of currents—Causes of currents—Action of the sea on the British coast—Shetland Islands—Large blocks removed—Isles reduced to clusters of rocks—Orkney isles—Waste of East coast of Scotland—and East coast of England—Waste of the cliffs of Holderness, Norfolk, and Suffolk—Sand-dunes how far chronometers—Silting up of estuaries—Yarmouth estuary—Suffolk coast—Dunwich—Essex coast—Estuary of the Thames—Goodwin Sands—Coast of Kent—Formation of the Straits of Dover—South coast of England—Sussex—Hants—Dorset—Portland—Origin of the Chesil Bank—Cornwall—Coast of Brittany.

Although the movements of great bodies of water, termed tides and currents, are in general due to very distinct causes, their effects cannot be studied separately; for they produce, by their joint action, aided by that of the waves, those changes which are objects of geological interest. These forces may be viewed in the same manner as we before considered rivers, first, as employed in destroying portions of the solid crust of the earth, and removing them to other places; secondly, as reproductive of new strata.

Tides.—It would be superfluous at the present day to offer any remarks on the cause of the tides. They are not perceptible in lakes or in most inland seas; in the Mediterranean even, deep and extensive as is that sea, they are scarcely sensible to ordinary observation, their effects being quite subordinate to those of the winds and currents. In some places, however, as in the Straits of Messina, there is an ebb and flow to the amount of two feet and upwards; at Naples and at the Euripus, of twelve or thirteen inches; and at Venice, according to Rennell, of five feet.* In the Syrtes, also, of the ancients, two wide shallow gulfs, which penetrate very far within the northern coast of Africa, between Carthage and Cyrene, the rise is said to exceed five feet.†

---

* See p. 13.

In islands remote from any continent, the ebb and flow of the ocean is very slight, as at St. Helena, for example, where it is rarely above three feet.‡ In any given line of coast, the tides are greatest in narrow channels, bays, and estuaries, and least in the intervening tracts where the land is prominent. Thus, at the entrance of the estuary of the Thames and Medway, the rise of the spring tides is eighteen feet; but when we follow our eastern coast from thence northward, towards Lowestoff and Yarmouth, we find a gradual diminution, until, at the places last mentioned, the highest rise is only seven or eight feet. From this point there begins again to be an increase, so that at Cromer, where the coast again retires towards the west, the rise is sixteen feet; and towards the extremity of the gulf called "the Wash," as at Lynn and in Boston Deeps, it is from twenty-two to twenty-four feet, and in some extraordinary cases twenty-six feet. From thence again there is a decrease towards the north, the elevation at the Spurn Point being from nineteen to twenty feet, and at Flamborough Head and the Yorkshire coast from fourteen to sixteen feet.§

At Milford Haven in Pembrokeshire, at the mouth of the Bristol Channel, the tides rise thirty-six feet; and at King-Road near Bristol, forty-two feet. At Chepstow on the Wye, a small river which opens into the estuary of the Severn, they reach fifty feet and sometimes sixty-nine, and even seventy-two feet. A current which sets in on the French coast, to the west of Cape La Hague, becomes pent up by Guernsey, Jersey, and other islands, till the rise of the tide is from twenty to forty-five feet, which last height it attains at Jersey, and at St. Malo, a seaport of Brittany. The tides in the Basin of Mines, at the head of the Bay of Fundy in Nova Scotia, rise to the height of seventy feet.

There are, however, some coasts where the tides seem to offer an exception to the rule above mentioned; for while there is scarcely any rise in the estuary of the Plata in S. America, there is an extremely high tide on the open coast of Patagonia, farther to the south. Yet even in this region the tides reach their greatest elevation (about fifty feet) in the Straits of Magellan, and so far at least they conform to the general rule.

Currents.—The most extensive and best determined system of currents, is that which has its source in the Indian Ocean under the influence of the trade winds; and which, after doubling the Cape of Good Hope, inclines to the northward, along the western coast of Africa, then crosses the Atlantic, near the equator, where it is called the equatorial current, and is lost in the Caribbean Sea, yet seems to be again revived in the current which issues from the Gulf of Mexico. From thence it flows rapidly through the Straits of Bahama, taking the name of the Gulf Stream, and passing in a north-easterly direction, by the Banks of Newfoundland, towards the Azores.

---

* Geog. of Herod. vol. ii. p. 331.

† Ibid. p. 328.

‡ Romme, Vents et Courans, vol. ii. p. 2. Rev. F. Fallows, Quart. Journ. of Science, March, 1829.

§ The heights of these tides were given me by the late Captain Hewett, R. N.

‖ On the authority of Admiral Sir F. Beaufort, R. N.

We learn from the posthumous work of Rennell on this subject, that the Lagullas current, so called from the cape and bank of that name, is formed by the junction of two streams, flowing from the Indian Ocean; the one from the channel of Mozambique, down the south-east coast of Africa; the other, from the ocean at large. The collective stream is from ninety to one hundred miles in breadth, and runs at the rate of from two and a half to more than four miles per hour. It is at length turned westward by the Lagullas bank, which rises from a sea of great depth to within one hundred fathoms of the surface. It must therefore be inferred, says Rennell, that the current here is more than one hundred fathoms deep, otherwise the main body of it would pass across the bank, instead of being deflected westward, so as to flow round the Cape of Good Hope. From this cape it flows northward, as before stated, along the western coast of Africa, taking the name of the South Atlantic current. It then enters the Bight, or Bay of Benin, and is turned westward, partly by the form of the coast there, and partly, perhaps, by the Guinea current, which runs from the north into the same great bay. From the centre of this bay proceeds the equatorial current already mentioned, holding a westerly direction across the Atlantic, which it traverses from the coast of Guinea to that of Brazil, flowing afterwards by the shores of Guiana to the West Indies. The breadth of this current varies from 160 to 450 geographical miles, and its velocity is from twenty-five to seventy-nine miles per day, the mean rate being about thirty miles. The length of its whole course is about 4000 miles. As it skirts the coast of Guiana, it is increased by the influx of the waters of the Amazon and Orinoco, and by their junction acquires accelerated velocity. After passing the island of Trinidad it expands, and is almost lost in the Caribbean Sea; but there appears to be a general movement of that sea towards the Mexican Gulf, which discharges the most powerful of all currents through the Straits of Florida, where the waters run in the northern part with a velocity of four or five miles an hour, having a breadth of from thirty-five to fifty miles.*

The temperature of the Gulf of Mexico is 86° F. in summer, or 6° higher than that of the ocean, in the same parallel (25° N. lat.), and a large proportion of this warmth is retained, even where the stream reaches the 43° N. lat. After issuing from the Straits of Florida the current runs in a northerly direction to Cape Hatteras, in North Carolina, about 35° N. lat., where it is more than seventy miles broad, and still moves at the rate of seventy-five miles per day. In about the 40° N. lat., it is turned more towards the Atlantic by the extensive banks of Nantucket and St. George, which are from 200 to 300 feet beneath the surface of the sea; a clear proof that the current exceeds that depth. On arriving near the Azores, the stream widens, and overflows, as it were, forming a large expanse of warm water in the centre of the North Atlantic, over a space of 200 or 300 miles from north to south, and having a temperature of from 8° to 10° Fahr. above the surrounding ocean. The whole area, covered by the Gulf water, is estimated by Rennell at 2000 miles in length, and, at a mean, 350 miles in breadth; an area more extensive than that of the Mediterranean. The warm water has been sometimes known to reach the Bay of Biscay, still retaining five degrees of temperature above that of the adjoining ocean; and a branch of the Gulf current occasionally drifts fruits, plants, and wood, the produce of America and the West Indies, to the shores of Ireland and the Hebrides.

---

* Consult the map of Currents by Captain F. Beechy, R. N., Admiralty Manual, 1849, London.

From the above statements we may understand why Rennell has characterized some of the principal currents as oceanic rivers, which he describes as being from 50 to 250 miles in breadth, and having a rapidity exceeding that of the largest navigable rivers of the continents, and so deep as to be sometimes obstructed, and occasionally turned aside, by banks, the tops of which do not rise within forty, fifty, or even one hundred fathoms of the surface of the sea.[*]

Greatest velocity of currents.—The ordinary velocity of the principal currents of the ocean is from one to three miles per hour; but when the boundary lands converge, large bodies of water are driven gradually into a narrow space, and then wanting lateral room, are compelled to raise their level. Whenever this occurs, their velocity is much increased. The current which runs through the Race of Alderney, between the island of that name and the main land, has a velocity of about eight English miles an hour. Captain Hewett found that in the Pentland Firth, the stream, in ordinary spring tides, runs ten miles and a half an hour, and about thirteen miles during violent storms. The greatest velocity of the tidal current through the "Shoots" or New Passage, in the Bristol Channel, is fourteen English miles an hour; and Captain King observed, in his survey of the Straits of Magellan, that the tide ran at the same rate through the "First Narrows," and about eight geographical miles an hour in other parts of those straits.

Causes of currents. — That movements of no inconsiderable magnitude should be impressed on an expansive ocean, by winds blowing for many months in one direction, may easily be conceived, when we observe the effects produced in our own seas by the temporary action of the same cause. It is well known that a stron south-west or north-west wind invariably raises the tides to unusual height along the west coast of England and in the Channel and that a north-west wind of any continuance causes the Balt to rise two feet and upwards above its ordinary level. Smeato ascertained by experiment, that in a canal four miles in length, t water was kept up four inches higher at one end than at the oth merely by the action of the wind along the canal; and Renne informs us that a large piece of water, ten miles broad, and general only three feet deep, has, by a strong wind, had its waters driven one side, and sustained so as to become six feet deep, while the win ward side was laid dry.*

---

[*] Rennell on Currents, p. 58.

As water, therefore, he observes, when pent up so that it cann escape, acquires a higher level, so, in a place *where it can escape*, t same operation produces a current; and this current will extend to greater or less distance, according to the force by which it is produce By the side of the principal oceanic currents, such as the Lagull and the Gulf Stream, are parallel "counter currents" runni steadily in an opposite direction.

Currents flowing alternately in opposite directions are occasion by the rise and fall of the tides. The effect of this cause is, as bef observed, most striking in estuaries and channels between islands.

A third cause of oceanic currents is evaporation by solar heat, which the great current setting through the Straits of Gibraltar i the Mediterranean is a remarkable example, and will be fully c sidered in the next chapter. A stream of colder water also flows fr the Black Sea into the Mediterranean. It must happen in many ot parts of the world, that large quantities of water raised from one tr of the ocean by solar heat, are carried to some other where the vap is condensed and falls in the shape of rain, and this, in flowing b again to restore equilibrium, will cause sensible currents.

These considerations naturally lead to the inquiry whether level of those seas out of which currents flow, is higher than that seas into which they flow. If not, the effect must be immediat equalized by under-currents or counter-currents. Arago is of opin that, so far as observations have gone, there are no exact proofs any such difference of level. It was inferred from the measureme of M. Lepère, that the level of the Mediterranean, near Alexand was lower by 26 feet 6 inches, than the Red Sea near Suez at water, and about 30 feet lower than the Red Sea at the same plac high water †, but Mr. Robert Stephenson affirms, as the result more recent survey, that there is no difference of level between two seas. ‡

It was formerly imagined that there was an equal, if not grea diversity in the relative levels of the Atlantic and Pacific, on opposite sides of the Isthmus of Panama. But the levellings carried across that isthmus by Capt. Lloyd, in 1828, to ascertain the relative height of the Pacific Ocean at Panama, and of the Atlantic at the mouth of the river Chagres, have shown, that the difference of mean level between those oceans is not considerable, and, contrary to expectation, the difference which does exist is in favour of the greater height of the Pacific. According to this survey, the mean height of the Pacific is three feet and a half, or 3·52 above the Atlantic, if we assume the mean level of a sea to coincide with the mean between the extremes of the elevation and depression of the tides; for between the extreme levels of the greatest tides in the Pacific, at Panama, there is a difference of 27·44 feet; and at the usual spring tides 21·22 feet: whereas at Chagres this difference is only 1·16 feet, and is the same at all seasons of the year.

---

* Rennell on the Channel current.

† An. du Bureau des Long. 1836.

‡ Second Parliamentary Report on Steam Communication with India, J 1851.

The tides, in short, in the Caribbean Sea are scarcely perceptible, not equalling those in some parts of the Mediterranean, whereas the rise is very high in the Bay of Panama; so that the Pacific is at high tide lifted up several feet above the surface of the Gulf of Mexico, and then at low water let down as far below it.* But astronomers are agreed that, on mathematical principles, the rise of the tidal wave above the mean level of a particular sea must be greater than the fall below it; and although the difference has been hitherto supposed insufficient to cause an appreciable error, it is, nevertheless, worthy of observation, that the error, such as it may be, would tend to reduce the small difference, now inferred, from the observations of Mr. Lloyd, to exist between the levels of the two oceans.

There is still another way in which heat and cold must occasion great movements in the ocean, a cause to which, perhaps, currents are principally due. Whenever the temperature of the surface of the sea is lowered, condensation takes place, and the superficial water, having its specific gravity increased, falls to the bottom, upon which lighter water rises immediately and occupies its place. When this circulation of ascending and descending currents has gone on for a certain time in high latitudes, the inferior parts of the sea are made to consist of colder or heavier fluid than the corresponding depths of the ocean between the tropics. If there be a free communication, if no chain of submarine mountains divide the polar from the equatorial basins, a horizontal movement will arise by the flowing of colder water from the poles to the equator, and there will then be a reflux of warmer superficial water from the equator to the poles. A well known experiment has been adduced to elucidate this mode of action in explanation of the "trade winds."† If a long trough, divided in the middle by a sluice or partition, have one end filled with water and the other with quicksilver, both fluids will remain quiet so long as they are divided; but when the sluice is drawn up, the heavier fluid will rush along the bottom of the trough, while the lighter, being displaced, will rise, and, flowing in an opposite direction, spread itself at the top. In like manner the expansion and contraction of sea-water by heat and cold, have a tendency to set under-currents in motion from the poles to the equator, and to cause counter-currents at the surface, which are impelled in a direction contrary to that of the prevailing trade winds. The geographical and other circumstances being very complicated, we cannot expect to trace separately the movements due to each cause, but must be prepared for many anomalies, especially as the configuration of the bed of the ocean must often modify and interfere with the course of the inferior currents, as much as the position and form of continents and islands alter the direction of those on the surface. Thus on sounding at great depths in the Mediterranean, Captains Berard and D'Urville have found that the cold does not increase in a high ratio as in the tropical regions of the ocean, the thermometer remaining fixed at about 55° F. between the depths of 1000 and 6000 feet. This might have been anticipated, as Captain Smyth in his survey had shown that the deepest part of the Straits of Gibraltar is only 1320 feet, so that a submarine barrier exists there which must prevent the influx of any under-current of the ocean cooled by polar ice.

---

* Phil. Trans. 1830, p. 59.

† See Capt. B. Hall, On Theory of Trade Winds, Fragments of Voy. second series, vol. i., and Appendix to Daniell's Meteorology.

Each of the four causes above mentioned, the wind, the tides, evaporation, and the expansion and contraction of water by heat and cold, may be conceived to operate independently of the others, and although the influence of all the rest were annihilated. But there is another cause, the rotation of the earth on its axis, which can only come into play when the waters have already been set in motion by some one or all of the forces above described, and when the direction of the current so raised happens to be from south to north, or from north to south.

The principle on which this cause operates is probably familiar to the reader, as it has long been recognized in the case of the trade winds. Without enlarging, therefore, on the theory, it will be sufficient to offer an example of the mode of action alluded to. When a current flows from the Cape of Good Hope towards the Gulf of Guinea, it consists of a mass of water, which, on doubling the Cape, in lat. 35°, has a rotatory velocity of about 800 miles an hour; but when it reaches the line, where it turns westward, it has arrived at a parallel where the surface of the earth is whirled round at the rate of 1000 miles an hour, or about 200 miles faster. If this great mass of water was transferred suddenly from the higher to the lower latitude, the deficiency of its rotatory motion, relatively to the land and water with which it would come into juxtaposition, would be such as to cause an apparent motion of the most rapid kind (of no less than 200 miles an hour) from east to west.

In the case of such a sudden transfer, the eastern coast of America, being carried round in an opposite direction, might strike against a large body of water with tremendous violence, and a considerable part of the continent might be submerged. This disturbance does not occur, because the water of the stream, as it advances gradually into new zones of the sea which are moving more rapidly, acquires by friction an accelerated velocity. Yet as this motion is not imparted instantaneously, the fluid is unable to keep up with the full speed of the new surface over which it is successively brought. Hence, to borrow the language of Herschel, when he speaks of the trade winds, "it lags or hangs back, in a direction opposite to the earth's rotation, that is, from east to west,"* and thus a current, which would have run simply towards the north but for the rotation, may acquire a relative direction towards the west.

We may next consider a case where the circumstances are the converse of the above. The Gulf Stream flowing from about lat. 20° is at first impressed with a velocity of rotation of about 940 miles an hour, and runs to the lat. 40°, where the earth revolves only at the rate of 766 miles, or 174 miles slower. In this case a relative motion of an opposite kind may result; and the current may retain an excess of rotatory velocity, tending continually to deflect it eastward. Polar currents, therefore, or those flowing from high to low latitudes, are driven towards the eastern shores of continents, while tropical currents flowing towards the poles are directed against their western shores.

Thus it will be seen that currents depend, like the tides, on no temporary or accidental circumstances, but on the laws which preside over the motions of the heavenly bodies. But although the sum of their influence in altering the surface of the earth may be very constant throughout successive epochs, yet the points where these operations are displayed in fullest energy shift perpetually. The height to which the tides rise, and the violence and velocity of currents, depend in a great measure on the actual configuration of the land, the contour of a long line of continental or insular coast, the depth and breadth of channels, the peculiar form of the bottom of seas—in a word, on a combination of circumstances which are made to vary continually by many igneous and aqueous causes, and, amongst the rest, by the tides and currents themselves. Although these agents, therefore, of decay and reproduction are local in reference to periods of short duration, such as those which history embraces, they are nevertheless universal, if we extend our views to a sufficient lapse of ages.

Destroying and transporting power of currents.—After these preliminary remarks on the nature and causes of currents, their velocity and direction, we may next consider their action on the solid materials of the earth. We shall find that their efforts are, in many respects, strictly analogous to those of rivers. I have already treated in the third chapter, of the manner in which currents sometimes combine with ice, in carrying mud, pebbles, and large fr ments of rock to great distances. Their operations are more concea from our view than those of rivers, but extend over wider areas, are therefore of more geological importance.

---

* Treatise on Astronomy, chap. 3.

Waste of the British coasts.—Shetland Islands.—If we fol the eastern and southern shores of the British islands, from Ultima Thule in Shetland to the Land's End in Cornwall, we s find evidence of a series of changes since the historical era, v illustrative of the kind and degree of force exerted by tides currents co-operating with the waves of the sea. In this survey shall have an opportunity of tracing their joint power on isla promontories, bays, and estuaries; on bold, lofty cliffs, as well as low shores; and on every description of rock and soil, from granit blown sand.

The northernmost group of the British islands, the Shetland, composed of a great variety of rocks, including granite, gneiss, mi slate, serpentine, greenstone, and many others, with some second rocks, chiefly sandstone and conglomerate. These islands are expo continually to the uncontrolled violence of the Atlantic, for no l intervenes between their western shores and America. The pre lence, therefore, of strong westerly gales, causes the waves to sometimes driven with irresistible force upon the coast, while th is also a current setting from the north. The spray of the sea the decomposition of the rocks, and prepares them to be breached the mechanical force of the waves. Steep cliffs are hollowed into deep caves and lofty arches; and almost every promontory e in a cluster of rocks, imitating the forms of columns, pinnacles, obelisks.

Drifting of large masses of rock.—Modern observations show t the reduction of continuous tracts to such insular masses is a pro in which nature is still actively engaged. "The isle of Stenne says Dr. Hibbert, "presents a scene of unequalled desolation. stormy winters, huge blocks of stones are overturned, or are remo from their native beds, and hurried up a slight acclivity to a dista almost incredible. In the winter of 1802, a tabular-shaped m eight feet two inches by seven feet, and five feet one inch thick, dislodged from its bed, and removed to a distance of from eight ninety feet. I measured the recent bed from which a block had b carried away the preceding winter (A. D. 1818), and found it to seventeen feet and a half by seven feet, and the depth two feet ei inches. The removed mass had been borne to a distance of th feet, when it was shivered into thirteen or more lesser fragme some of which were carried still farther, from 30 to 120 feet. block, nine feet two inches by six feet and a half, and four feet th was hurried up the acclivity to a distance of 150 feet."*

---

* Descrip. of Shetland Islands, p. 527. Edin. 1822, to which work I am indebted for the following representa of rocks in the Shetland Isles.

Fig. 27.



Stony fragments drifted by the sea. Northmavine, Shetland.

At Northmavine, also, angular blocks of stone have been removed in a similar manner to considerable distances by the waves of the sea, some of which are represented in the annexed figure.

Effects of lightning.—In addition to numerous examples of masses detached and driven by the waves, tides, and currents from their place, some remarkable effects of lightning are recorded in these isles. At Funzie, in Fetlar, about the middle of the last century, a rock of mica-schist, 105 feet long, ten feet broad, and in some places four feet thick, was in an instant torn by a flash of lightning from its bed, and broken into three large and several smaller fragments. One of these, twenty-six feet long, ten feet broad, and four feet thick, was simply turned over. The second, which was twenty-eight feet long, seventeen broad and five feet in thickness, was hurled across a high point to the distance of fifty yards. Another broken mass, about forty feet long, was thrown still farther, but in the same direction, quite into the sea. There were also many smaller fragments scattered up and down.*

When we thus see electricity co-operating with the violent movements of the ocean in heaping up piles of shattered rocks on dry land and beneath the waters, we cannot but admit that a region which shall be the theatre, for myriads of ages, of the action of such disturbing causes, might present, at some future period, if upraised far above the bosom of the deep, a scene of havoc and ruin that may compare with any now found by the geologist on the surface of our continents.

In some of the Shetland Isles, as on the west of Meikle Roe, dikes, or veins of soft granite, have mouldered away; while the matrix in which they were inclosed, being of the same substance, but of a firmer texture, has remained unaltered. Thus, long narrow ravines, sometimes twenty feet wide, are laid open, and often give access to the waves. After describing some huge cavernous apertures into which the sea flows for 250 feet in Roeness, Dr. Hibbert, writing in 1822, enumerates other ravages of the ocean. "A mass of rock, the average dimensions of which may perhaps be rated at twelve or thirteen feet square, and four and a half or five in thickness, was first moved from its bed, about fifty years ago, to a distance of thirty feet, and has since been twice turned over."

Passage forced by the sea through porphyritic rocks.—"But the most sublime scene is where a mural pile of porphyry, escaping the process of disintegration that is devastating the coast, appears to have been left as a sort of rampart against the inroads of the ocean —the Atlantic, when provoked by wintry gales, batters against it with all the force of real artillery—the waves having, in their repeated assaults, forced themselves an entrance. This breach named the Grind of the Navir (fig. 28.), is widened every winter by the overwhelming surge that, finding a passage through it, separates large stones from its sides, and forces them to a distance of no less than 180 feet. In two or three spots, the fragments which have been detached are brought together in immense heaps, that appear as an accumulation of cubical masses, the product of some quarry."*

---

* Dr. Hibbert, from MSS. of Rev. George Low, of Fetlar.

Fig. 28.



Grind of the Navir—passage forced by the sea through rocks of hard porphyry.

It is evident from this example, that although the greater indestructibility of some rocks may enable them to withstand, for a longer time, the action of the elements, yet they cannot permanently resist. There are localities in Shetland, in which rocks of almost every variety of mineral composition are suffering disintegration; thus the sea makes great inroads on the clay slate of Fitfel Head, on the serpentine of the Vord Hill in Fetlar, and on the mica-schist of the Bay of Triesta, on the east coast of the same island, which decomposes into angular blocks. The quartz rock on the east of Walls, and the gneiss and mica-schist of Garthness, suffer the same fate.

Destruction of islands.—Such devastation cannot be incessantly committed for thousands of years without dividing islands, until they become at last mere clusters of rocks, the last shreds of masses once continuous. To this state many appear to have been reduced, and innumerable fantastic forms are assumed by rocks adjoining these islands to which the name of Drongs is applied, as it is to those of similar shape in Feroe.

---

* Hibbert, p. 528.

granitic rocks (fig. 29.) between Papa Stour and Hillswick
ifford an example. A still more singular cluster of rocks is

Fig. 29.



Granitic rocks named the Drongs, between Papa Stour and Hillswick Ness.

o the south of Hillswick Ness (fig. 30.), which presents a
y of forms as viewed from different points, and has often been
l to a small fleet of vessels with spread sails.* We may

Fig. 30.



Granitic rocks to the south of Hillswick Ness, Shetland.

ie that in the course of time Hillswick Ness itself may
t a similar wreck, from the unequal decomposition of the rocks
of it is composed, consisting of gneiss and mica-schist traversed
directions by veins of felspar-porphyry.

way between the groups of Shetland and Orkney is Fair
l, said to be composed of sandstone with high perpendicular
The current runs with such velocity, that during a calm, and
there is no swell, the rocks on its shores are white with the
of the sea driven against them. The Orkneys, if carefully
ned, would probably illustrate our present topic as much as the

---

* Hibbert, p. 519.

Shetland group. The north-east promontory of Sanda, one of these islands, has been cut off in modern times by the sea, so that it became what is now called Start Island, where a lighthouse was erected in 1807, since which time the new strait has grown broader.

East coast of Scotland.—To pass over to the main land of Scotland, we find that in Inverness-shire there have been inroads of the sea at Fort George, and others in Morayshire, which have swept away the old town of Findhorn. On the coast of Kincardineshire, an illustration was afforded, at the close of the last century, of the effect of promontories in protecting a line of low-shore. The village of Mathers, two miles south of Johnshaven, was built on an ancient shingle beach, protected by a projecting ledge of limestone rock. This was quarried for lime to such an extent that the sea broke through, and in 1795 carried away the whole village in one night, and penetrated 150 yards inland, where it has maintained its ground ever since, the new village having been built farther inland on the new shore. In the Bay of Montrose, we find the North Esk and the South Esk rivers pouring annually into the sea large quantities of sand and pebbles; yet they have formed no deltas, for the waves, aided by the current, setting across their mouths, sweep away all the materials. Considerable beds of shingle, brought down by the North Esk, are seen along the beach.

Proceeding southwards, we learn that at Arbroath, in Forfarshire, which stands on a rock of red sandstone, gardens and houses have been carried away since the commencement of the present century by encroachments of the sea. It had become necessary before 1828, to remove the lighthouses, at the mouth of the estuary of the Tay, in the same county, at Button Ness, which were built on a tract of blown sand, the sea having encroached for three quarters of a mile.

Force of waves and currents in estuaries.—The combined power which waves and currents can exert in *estuaries* (a term which I confine to bays entered both by rivers and the tides of the sea) was remarkably exhibited during the building of the Bell Rock Lighthouse, off the mouth of the Tay. The Bell Rock is a sunken reef, consisting of red sandstone, being from twelve to sixteen feet under the surface at high water, and about twelve miles from the mainland. At the distance of 100 yards, there is a depth, in all directions, of two or three fathoms at low water. In 1807, during the erection of the lighthouse, six large blocks of granite, which had been landed on the reef, were removed by the force of the sea, and thrown over a rising ledge to the distance of twelve or fifteen paces; and an anchor, weighing about 22 cwt., was thrown up upon the rock.* Mr. Stevenson informs us, moreover, that drift stones, measuring upwards of thirty cubic feet, or more than two tons' weight, have, during storms, been often thrown upon the rock from the deep water.†

---

* Account of Erection of Bell Rock Lighthouse, p. 163.

† Ed. Phil. Journ. vol. iii. p. 54. 1820.

Submarine forests.—Among the proofs that the sea has encroached on the land bordering the estuary of the Tay, Dr. Fleming has mentioned a submarine forest which has been traced for several miles along the northern shore of the county of Fife.* But subsequent surveys seem to have shown that the bed of peat containing tree-roots, leaves, and branches, now occurring at a lower level than the Tay, must have come into its present position by a general sinking of the ground on which the forest grew. The peat bed alluded to is not confined, says Mr. Buist, to the present channel of the Tay, but extends far beyond it, and is covered by stratified clay from fifteen to twenty-five feet in thickness, in the midst of which, in some places, is a bed full of sea-shells.† Recent discoveries having established the fact that upward and downward movements have affected our island since the general coast-line had nearly acquired its present shape, we must hesitate before we attribute any given change to a single cause, such as the local encroachment of the sea upon low land.

On the coast of Fife, at St. Andrew's, a tract of land, said to have intervened between the castle of Cardinal Beaton and the sea, has been entirely swept away, as were the last remains of the Priory of Crail, in the same county, in 1803. On both sides of the Frith of Forth, land has been consumed; at North Berwick in particular, and at Newhaven, where an arsenal and dock, built in the reign of James IV., in the fifteenth century, has been overflowed.

East coast of England.—If we now proceed to the English coast, we find records of numerous lands having been destroyed in Northumberland, as those near Bamborough and Holy Island, and at Tynemouth Castle, which now overhangs the sea, although formerly separated from it by a strip of land. At Hartlepool, and several other parts of the coast of Durham composed of magnesian limestone, the sea has made considerable inroads.

Coast of Yorkshire.—Almost the whole coast of Yorkshire, from the mouth of the Tees to that of the Humber, is in a state of gradual dilapidation. That part of the cliffs which consist of lias, the oolite series, and chalk, decays slowly. They present abrupt and naked precipices, often 300 feet in height; and it is only at a few points that the grassy covering of the sloping talus marks a temporary relaxation of the erosive action of the sea. The chalk cliffs are worn into caves and needles in the projecting headland of Flamborough, where they are decomposed by the salt spray, and slowly crumble away. But the waste is most rapid between that promontory and Spurn Point, or the coast of Holderness, as it is called, a tract consisting of beds of clay, gravel, sand, and chalk rubble. The irregular intermixture of the argillaceous beds causes many springs to be thrown out, and this facilitates the undermining process, the waves beating against them, and a strong current setting chiefly from the north. The wasteful action is very conspicuous at Dimlington Height, the loftiest point in Holderness, where the beacon stands on a cliff 146 feet above high water, the whole being composed of clay, with pebbles scattered through it.[*] "For many years," says Professor Phillips, "the rate at which the cliffs recede from Bridlington to Spurn, a distance of thirty-six miles, has been found by measurement to equal on an average two and a quarter yards annually, which upon thirty-six miles of coast would amount to about thirty acres a year. At this rate, the coast, the mean height of which above the sea is about forty feet, has lost one mile in breadth since the Norman Conquest, and more than two miles since the occupation of York (Eboracum) by the Romans."[†] The extent of this denudation, as estimated by the number of cubic feet of matter removed annually will be again spoken of in chapter 22.

---

* Quart. Journ. of Sci. &c., No. XIII. *N. S.* March, 1880.

† Buist, Quart. Journ. of Agricult., No. XLV. p. 34. June, 1839.

In the old maps of Yorkshire, we find spots, now sand-banks in the sea, marked as the ancient sites of the towns and villages of Auburn, Hartburn, and Hyde. "Of Hyde," says Pennant, "only the tradition is left; and near the village of Hornsea, a street called Hornsea Beck has long since been swallowed."[‡] Owthorne and its church have also been in great part destroyed, and the village of Kilnsea; but these places are now removed farther inland. The annual rate of encroachment at Owthorne for several years preceding 1830, is stated to have averaged about four yards. Not unreasonable fears are entertained that at some future time the Spurn Point will become an island, and that the ocean, entering into the estuary of the Humber, will cause great devastation.[§] Pennant, after speaking of the silting up of some ancient ports in that estuary, observes, "But, in return, the sea has made most ample reprisals; the site, and even the very names of several places, once towns of note upon the Humber, are now only recorded in history; and Ravensper was at one time a rival to Hull (Madox, Ant. Exch. i. 422.), and a port so very considerable in 1332, that Edward Baliol and the confederated English barons sailed from hence to invade Scotland; and Henry IV., in 1399, made choice of this port to land at, to effect the deposal of Richard II.; yet the whole of this has long since been devoured by the merciless ocean; extensive sands, dry at low water, are to be seen in their stead."[*]

Pennant describes Spurn Head as a promontory in the form of a sickle, and says the land, for some miles to the north, was "perpetually preyed on by the fury of the German Sea, which devours whole acres at a time, and exposes on the shores considerable quantities of beautiful amber."

Lincolnshire. — The maritime district of Lincolnshire consists chiefly of lands that lie below the level of the sea, being protected by mbankments. Some of the fens were embanked and drained by the lomans; but after their departure the sea returned, and large tracts vere covered with beds of silt containing marine shells, now again onverted into productive lands. Many dreadful catastrophes are reorded by incursions of the sea, whereby several parishes have been t different times overwhelmed.

---

[*] Phillips's Geology of Yorkshire, p. 61.

[†] Rivers, Mountains, and Sea-coast of Yorkshire, p. 122. 1853, London.

[‡] Arctic Zoology, vol. i. p. 10. Introduction.

[§] Phillips's Geol. of York. p. 60.

[‖] Arct. Zool. vol. i. p. 13. Introd.

Norfolk. — The decay of the cliffs of Norfolk and Suffolk is inessant. At Hunstanton, on the north, the undermining of the lower renaceous beds at the foot of the cliff, causes masses of red and white halk to be precipitated from above. Between Hunstanton and Veybourne, low hills, or dunes, of blown sand, are formed along the hore, from fifty to sixty feet high. They are composed of dry sand, ound in a compact mass by the long creeping roots of the plant alled Marram (*Arundo arenaria*). Such is the present set of the ides, that the harbours of Clay, Wells, and other places are securely lefended by these barriers; affording a clear proof that it is not the trength of the material at particular points that determines whether he sea shall be progressive or stationary, but the general contour of he coast.

The waves constantly undermine the low chalk cliffs, covered with and and clay, between Weybourne and Sherringham, a certain ortion of them being annually removed. At the latter town I scertained, in 1829, some facts which throw light on the rate at which the sea gains upon the land. It was computed, when the present inn was built, in 1805, that it would require seventy years for the sea to reach the spot: the mean loss of land being calculated, from previous observations, to be somewhat less than one yard, annually. The distance between the house and the sea was fifty yards; but no allowance was made for the slope of the ground being *from* the sea, in consequence of which the waste was naturally accelerated every year, as the cliff grew lower, there being at each succeeding period less matter to remove when portions of equal area fell down. Between the years 1824 and 1829, no less than seventeen yards were swept away, and only a small garden was then left between the building and the sea. There was, in 1829, a depth of twenty feet (sufficient to float a frigate) at one point in the harbour of that port, where, only forty-eight years before, there stood a cliff fifty feet high, with houses upon it! If once in half a century an equal amount of change were produced suddenly by the momentary shock of an earthquake, history would be filled with records of such wonderful revolutions of the earth's surface; but, if the conversion of high land into deep sea be gradual, it excites only local attention. The flag-staff of the Preventive Service station, on the south side of this harbour, was thrice removed inland between the years 1814 and 1829, in consequence of the advance of the sea.

Farther to the south we find cliffs, composed, like those of Holderness before mentioned, of alternating strata of blue clay, gravel, loam, and fine sand. Although they sometimes exceed 300 feet in height, the havoc made on the coast is most formidable. The whole site of ancient Cromer now forms part of the German Ocean, the inhabitants having gradually retreated inland to their present situation, from whence the sea still threatens to dislodge them. In the winter of 1825, a fallen mass was precipitated from near the lighthouse, which covered twelve acres, extending far into the sea, the cliffs being 250 feet in height.* The undermining by springs has sometimes caused large portions of the upper part of the cliffs, with houses still standing upon them, to give way, so that it is impossible, by erecting breakwaters at the base of the cliffs, permanently to ward off the danger.

On the same coast, says Mr. R. C. Taylor, the ancient villages of Shipden, Wimpwell, and Eccles have disappeared; several manors and large portions of neighbouring parishes having, piece after piece, been swallowed up; nor has there been any intermission, from time immemorial, in the ravages of the sea along a line of coast twenty miles in length, in which these places stood.† Of Eccles, however, a monument still remains in the ruined tower of the old church, which is half buried in the dunes of sand within a few paces (60 ?) of the sea beach (fig. 31.). So early as 1605 the inhabitants petitioned James I. for a reduction of taxes, as 300 acres of land, and all their houses, save fourteen, had then been destroyed by the sea. Not one half that number of acres now remains in the parish, and hills of blown sand now occupy the site of the houses which were still extant in 1605. When I visited the spot in 1839, the sea was fast encroaching on the sandhills, and had laid open on the beach the

Fig. 31.



Tower of the buried Church of Eccles, Norfolk, A. D. 1839.

The inland slope of the hills of blown sand is shown in this view, with the lighthouse at Hasborough in the distance.

---

* Taylor's Geology of East Norfolk, p. 32.

† Ibid.

of a house fourteen yards square, the upper part of which
tly been pulled down before it had been buried under
body of the church has also been long buried, but the
·emains visible.

Beaumont has suggested that sand-dunes in Holland
countries may serve as natural chronometers, by which
the existing continents may be ascertained. The sands,
continually blown inland by the force of the winds, and
ıg the rate of their march we may calculate the period
ıovement commenced.* But the example just given will
'y geologist that we cannot ascertain the starting-point of
oasts being liable to waste, and the shores of the Low Coun-
ticular, being not only exposed to inroads of the sea, but, as
mont himself has well shown, having even in historical
rgone a change of level. The dunes may indeed, in some
ıade use of as chronometers, to enable us to assign a
ıf antiquity to existing coast-lines; but this test must be
h great caution, so variable is the rate at which the sands
ɔe into the interior.

blown sand, between Eccles and Winterton, have barred
cluded the tide for many hundred years from the mouths
small estuaries; but there are records of nine breaches,
› 120 yards wide, having been made through these, by
ense damage was done to the low grounds in the interior.
les south of Happisburgh, also, are hills of blown sand,
nd to Yarmouth. These *dunes* afford a temporary protec-
coast, and an inland cliff about a mile long, at Winterton,
·ly that at that point the sea must have penetrated formerly
n at present.

ıp of estuaries.—At Yarmouth, the sea has not advanced
ınds in the slightest degree since the reign of Elizabeth.
of the Saxons, a great estuary extended as far as Norwich,
is represented, even in the thirteenth and fourteenth
as "situated on the banks of an arm of the sea." The
reon Yarmouth is built, first became firm and habitable
ɔut the year 1008, from which time a line of dunes has
increased in height and breadth, stretching across the
ance of the ancient estuary, and obstructing the ingress
es so completely, that they are only admitted by the
ısage which the river keeps open, and which has gradually
reral miles to the south. The ordinary tides at the
ıth rise, at present, only to the height of three or four
ıring tides to about eight or nine.

ɪxclusion of the sea, thousands of acres in the interior have
ltivated lands; and, exclusive of smaller pools, upwards of
ıwater lakes have been formed, varying in depth from

---

* De Beaumont, Géologie Pratique, p. 218.

fifteen to thirty feet, and in extent from one acre to twelve hundred. The Yare, and other rivers, frequently communicate with these sheets of water; and thus they are liable to be filled up gradually with lacustrine and fluviatile deposits, and to be converted into land covered with forests. Yet it must not be imagined, that the acquisition of new land fit for cultivation in Norfolk and Suffolk indicates any permanent growth of the eastern limits of our island to compensate its reiterated losses. No *delta* can form on such a shore.

Immediately off Yarmouth, and parallel to the shore, is a great range of sand-banks, the shape of which varies slowly from year to year, and often suddenly after great storms. Captain Hewitt, R.N., found in these banks, in 1836, a broad channel sixty-five feet deep, where there was only a depth of four feet during a prior survey in 1822. The sea had excavated to the depth of sixty feet in the course of fourteen years, or perhaps a shorter period. The new channel thus formed serves at present (1838), for the entrance of ships into Yarmouth Roads; and the magnitude of this change shows how easily a new set of the waves and currents might endanger the submergence of the land gained within the ancient estuary of the Yare.

That great banks should be thrown across the mouths of estuaries on our eastern coast, where there is not a large body of river-water to maintain an open channel, is perfectly intelligible, when we bear in mind that the marine current, sweeping along the coast, is charged with the materials of wasting cliffs, and ready to form a bar anywhere the instant its course is interrupted or checked by any opposing stream. The mouth of the Yare has been, within the last five centuries, diverted about four miles to the south. In like manner it is evident that, at some remote period, the river Alde entered the sea at Aldborough, until its ancient outlet was barred up and at length transferred to a point no less than ten miles distant to the south-west. In this case, ridges of sand and shingle, like those of Lowestoff Ness, which will be described by and bye, have been thrown up between the river and the sea; and an ancient sea-cliff is to be seen now inland.

It may be asked why the rivers on our east coast are always deflected southwards, although the tidal current flows alternately from the south and north? The cause is to be found in the superior force of what is commonly called "the flood tide from the north," a tidal wave derived from the Atlantic, a small part of which passes eastward up the English Channel, and through the Straits of Dover and then northwards, while the principal body of water, moving much more rapidly in a more open sea, on the western side of Britain, first passes the Orkneys, and then turning, flows down between Norway and Scotland, and sweeps with great velocity along our eastern coast. It is well known that the highest tides on this coast are occasioned by a powerful north-west wind, which raises the eastern part of the Atlantic, and causes it to pour a greater volume of water into the German Ocean. This circumstance of a violent *off-shore* wind being attended with a rise of the waters, instead of a general retreat of the sea, naturally excites the wonder of the inhabitants of our coast. In many districts they look with confidence for a rich harvest of that valuable manure, the sea-weed, when the north-westerly gales prevail, and are rarely disappointed.

---

* Taylor's Geology of East Norfolk, p. 10.

Coast of Suffolk.—The cliffs of Suffolk, to which we next proceed, are somewhat less elevated than those of Norfolk, but composed of similar alternations of clay, sand, and gravel. From Gorleston in Suffolk, to within a few miles north of Lowestoff, the cliffs are slowly undermined. Near the last-mentioned town, there is an inland cliff about sixty feet high, the sloping talus of which is covered with turf and heath. Between the cliff and the sea is a low flat tract of sand, called the Ness, nearly three miles long, and for the most part out of reach of the highest tides. The point of the Ness projects from the base of the original cliff to the distance of 660 yards. This accession of land, says Mr. Taylor, has been effected at distinct and distant intervals, by the influence of currents running between the land and a shoal about a mile off Lowestoff, called the Holm Sand. The lines of growth in the Ness are indicated by a series of concentric ridges or embankments inclosing limited areas, and several of these ridges have been formed within the observation of persons now living. A rampart of heavy materials is first thrown up to an unusual altitude by some extraordinary tide, attended with a violent gale. Subsequent tides extend the base of this high bank of shingle, and the interstices are then filled with sand blown from the beach. The Arundo and other marine plants by degrees obtain a footing; and creeping along the ridge, give solidity to the mass, and form in some cases a matted covering of turf. Meanwhile another mound is forming externally, which by the like process rises and gives protection to the first. If the sea forces its way through one of the external and incomplete mounds, the breach is soon repaired. After awhile the marine plants within the areas inclosed by these embankments are succeeded

Fig. 32.



Map of Lowestoff Ness, Suffolk.*

a, a. The dotted lines express a series of sand and shingle, forming the extremity of the triangular space called the Ness.
b, b, b. The dark line represents the inland cliff on which the town of Lowestoff stands, between which and the sea is the Ness.

---

* From Mr. R. C. Taylor's Mem., see Phil. Mag., Oct. 1827, p. 297.

by a better species of herbage affording good pasturage, and the sands become sufficiently firm to support buildings.

Destruction of Dunwich *sea.* — Of the gradual destruction of Dunwich, once the considerable seaport on this coast, we have many authentic records. Gardner, in his history of that borough, published in 1754, shows, by reference to documents, beginning with Doomsday Book, that the cliffs at Dunwich, Southwold, Eastern, and Pakefield, have been always subject to wear away. At Dunwich, in particular, two tracts of land which had been taxed in the eleventh century, in the time of King Edward the Confessor, are mentioned, in the Conqueror's survey, made but a few years afterwards, as having been devoured by the sea. The losses, at a subsequent period, of a monastery, — at another of several churches, — afterwards of the old port, — then of four hundred houses at once, — of the church of St. Leonard, the high-road, town-hall, gaol, and many other buildings, are mentioned, with the dates when they perished. It is stated that, in the sixteenth century, not one quarter of the town was left standing; yet the inhabitants retreating inland, the name was preserved, as has been the case with many other ports when their ancient site has been blotted out. There is, however, a church, of considerable antiquity, still standing, the last of twelve mentioned in some records. In 1740, the laying open of the churchyard of St. Nicholas and St. Francis, in the sea-cliffs, is well described by Gardner, with the coffins and skeletons exposed to view — some lying on the beach, and rocked

> "In cradle of the rude imperious surge."

Of these cemeteries no remains can now be seen. Ray also says, "that ancient writings make mention of a wood a mile and a half to the east of Dunwich, the site of which must at present be so far within the sea."* This city, once so flourishing and populous, is now a small vilage, with about twenty houses, and one hundred inhabitants.

There is an old tradition, "that the tailors sat in their shops at Dunwich, and saw the ships in Yarmouth Bay;" but when we consider how far the coast at Lowestoff Ness projects between these places, we cannot give credit to the tale, which, nevertheless, proves how much the inroads of the sea in times of old had prompted men of lively imagination to indulge their taste for the marvellous.

Gardner's description of the cemeteries laid open by the waves reminds us of the scene which has been so well depicted by Bewick†, and of which numerous points on the same coast might have suggested the idea. On the verge of a cliff, which the sea has undermined, are represented the unshaken tower and western end of an abbey. The eastern aisle is gone, and the pillars of the cloister are soon to follow. The waves have almost isolated the promontory, and invaded the cemetery, where they have made sport with the mortal relics, and thrown up a skull upon the beach. In the foreground is seen a broken tombstone, erected, as its legend tells, "to *perpetuate* the memory"—of one whose name is obliterated, as is that of the county for which he was "Custos Rotulorum." A cormorant is perched on the monument, defiling it, as if to remind some moralizer, like Hamlet, of "the base uses" to which things sacred may be turned. Had this excellent artist desired to satirize certain popular theories of geology, he might have inscribed the stone to the memory of some philosopher who taught "the permanency of existing continents"—"the era of repose"—"the impotence of modern causes."

---

* Consequences of the Deluge, Phys. Theol. Discourses.

† History of British Birds, vol. ii. p. 220. ed. 1821.

The incursions of the sea at Aldborough were formerly very destructive, and this borough is known to have been once situated a quarter of a mile east of the present shore. The inhabitants continued to build farther inland, till they arrived at the extremity of their property, and then the town decayed greatly; but two sandbanks, thrown up at a short distance, now afford a temporary safeguard to the coast. Between these banks and the present shore, where the current now flows, the sea is twenty-four feet deep on the spot where the town formerly stood.

Essex.—Harwich is said to have owed its rise to the destruction of Orwell, a town which stood on the spot now called "the west rocks," and was overwhelmed by an inroad of the sea since the Conquest. Apprehensions have been entertained that the isthmus on which Harwich stands may at no remote period become an island, for the sea may be expected to make a breach near Lower Dover Court, where Beacon Cliff is composed of horizontal beds of London clay containing septaria. It had wasted away considerably between the years 1829 and 1838, at both which periods I examined this coast. In that short interval several gardens and many houses had been swept into the sea, and in April, 1838, a whole street was threatened with destruction. The advance of the sea is much accelerated by the traffic carried on in septaria, which are shipped off for cement as fast as they fall down upon the beach. These stones, if allowed to remain in heaps on the shore, would break the force of the waves, and retard the conversion of the peninsula into an island, an event which might be followed by the destruction of the town of Harwich. Captain Washington, R. N., ascertained in 1847, that Beacon Cliff above mentioned, which is about fifty feet high, had given way at the rate of forty feet in forty-seven years, between 1709 and 1756; eighty feet between 1756 and 1804; and three hundred and fifty feet between the latter period and 1841; showing a rapidly accelerated rate of destruction.*

Among other losses it is recorded, that, since the year 1807, a field called the Vicar's Field, which belonged to the living of Harwich, has been overwhelmed†; and in the year 1820 there was a considerable space between the battery at I built in the beginning of the present century, and the ; p ' the fortification had been swept away in 1829, and the r n overhung the water.

---

* Tidal Harbour Commissioners' First Report, 1845, p. 176.

† On authority of Dr. Mitchell, F. G. S.

At Walton Naze, in the ie (nty, the cliffs, composed of London clay, capped by the ılly s of the crag, reach the height of about 100 feet, and are an ly undermined by the waves. The old churchyard of Walton has washed away, and the cliffs to the south are constantly disapp

Kent.—Isle of Sheppey.—On the coast bounding the estuary of the Thames, there are numerous examples both of the gain and loss of land. The Isle of Sheppey, which is now about six miles long by four in breadth, is composed of London clay. The cliffs on the north, which are from sixty to eighty feet high, decay rapidly, fifty acres having been lost in twenty years, between 1810 and 1830. The church at Minster, now near the coast, is said to have been in the middle of the island in 1780; and if the present rate of destruction should continue, we might calculate the period, and that not a very remote one, when the whole island will be annihilated. On the coast of the mainland to the east of Sheppey is Herne Bay; a place still retaining the name of a bay, although it is no longer appropriate, as the waves and currents have swept away the ancient headlands. There was formerly a small promontory in the line of the shoals where the present pier is built, by which the larger bay was divided into two called the Upper and Lower.*

Fig. 33.



View of Reculver Church, taken in the year 1781.

1. Isle of Sheppey. 2. Ancient chapel now destroyed. The cottage between this chapel and the cliff was demolished by the sea, in 1782.

Still farther east stands the church of Reculver, upon a cliff composed of clay and sand, about twenty-five feet high. Reculver (Regulvium) was an important military station in the time of the Romans, and appears, from Leland's account, to have been, so late as Henry VIII.'s reign, nearly one mile distant from the sea. In the

---

* On the authority of W. Gunnel, Esq., and W. Richardson, Esq., F.G.S.

"Gentleman's Magazine" there is a view of it, taken in 1781, which still represents a considerable space as intervening between the north wall of the churchyard and the cliff.* Some time before the year 1780, the waves had reached the site of the ancient Roman camp, or fortification, the walls of which had continued for several years after they were undermined to overhang the sea, being firmly cemented into one mass. They were eighty yards nearer the sea than the church, and they are spoken of in the "Topographica Britannica," in the year 1780, as having recently fallen down. In 1804, part of the churchyard with some adjoining houses was washed away, and the ancient church, with its two spires, was dismantled and abandoned as a place of worship, but kept in repair as a landmark well known to mariners. I visited the spot in June, 1851, and saw human bones and part of a wooden coffin projecting from the cliff, near the top. The whole building would probably have been swept away long ere this, had not the force of the waves been checked by an artificial causeway of stones and large wooden piles driven into the sands on the beach to break the force of the waves.

Fig. 34.



Reculver Church, in 1834.

Isle of Thanet.—The isle of Thanet was, in the time of the Romans, separated from the rest of Kent by a navigable channel, through which the Roman fleets sailed on their way to and from London. Bede describes this small estuary as being, in the beginning of the eighth century, three furlongs in breadth; and it is supposed that it began to grow shallow about the period of the Norman con-

---

[*] Vol. ii. New ser. 1809, p. 801.

quest. It was so far silted up in the year 1485, that an act was then obtained to build a bridge across it; and it has since become marsh land with small streams running through it. On the coast, Bedlam Farm, belonging to the hospital of that name, lost eight acres in the twenty years preceding 1830, the land being composed of chalk from forty to fifty feet above the level of the sea. It has been computed, that the average waste of the cliff between the North Foreland and the Reculvers, a distance of about eleven miles, is not less than two feet per annum. The chalk cliffs on the south of Thanet, between Ramsgate and Pegwell Bay, have on an average lost three feet per annum for the last ten years (preceding 1830).

Goodwin Sands.—The Goodwin Sands lie opposite this part of the Kentish coast. They are about ten miles in length, and are in some parts three, and in others seven, miles distant from the shore; and, for a certain space, are laid bare at low water. That they are a remnant of land, and not "a mere accumulation of sea sand," as Rennell imagined*, may be presumed from the fact that, when the erection of a lighthouse on this shoal was in contemplation by the Trinity Board in the year 1817, it was found, by borings, that the bank consisted of fifteen feet of sand, resting on blue clay; and, by subsequent borings, the subjacent chalk has been reached. An obscure tradition has come down to us, that the estates of Earl Goodwin, the father of Harold, who died in the year 1053, were situated here, and some have conjectured that they were overwhelmed by the flood mentioned in the Saxon chronicle, *sub anno* 1099. The last remains of an island, consisting, like Sheppey, of clay, may perhaps have been carried away about that time.

Fig. 35.



Shakspeare's Cliff in 1836, seen from the north-east.

There are other records of waste in the county of Kent, as at Deal; and at Dover, where Shakspeare's Cliff, composed entirely of chalk, has suffered greatly, and continually diminishes in height, the slope of the hill being towards the land. (See fig. 35.) There was an immense landslip from this cliff in 1810, by which Dover was shaken as if by an earthquake, and a still greater one in 1772.* We may suppose, therefore, that the view from the top of the precipice in the year 1600, when the tragedy of King Lear was written, was more "fearful and dizzy" than it is now. The best antiquarian authorities are agreed, that Dover Harbour was formerly an estuary, the sea flowing up a valley between the chalk hills. The remains found in different excavations confirm the description of the spot given by Cæsar and Antoninus, and there is clear historical evidence to prove that at an early period there was no shingle at all at Dover.†

---

* Geog. of Herod. vol. ii. p. 326.

Straits of Dover.—In proceeding from the northern parts of the German Ocean towards the Straits of Dover, the water becomes gradually more shallow, so that, in the distance of about two hundred leagues, we pass from a depth of 120 to that of 58, 38, 18, and even less than 2 fathoms. The shallowest part follows a line drawn between Romney Marsh and Boulogne. From this point the English Channel again deepens progressively as we proceed westward, so that the Straits of Dover may be said to part two seas.‡

Whether England was formerly united with France has often been a favourite subject of speculation. So early as 1605 our countryman Verstegan, in his "Antiquities of the English Nation," observed that many preceding writers had maintained this opinion, but without supporting it by any weighty reasons. He accordingly endeavours himself to confirm it by various arguments, the principal of which are, first, the proximity and identity of the composition of the opposite cliffs and shores of Albion and Gallia, which, whether flat and sandy, or steep and chalky, correspond exactly with each other; secondly, the occurrence of a submarine ridge, called "our Lady's Sand," extending from shore to shore at no great depth, and which, from its composition appears to be the original basis of the isthmus; thirdly, the identity of the noxious animals in France and England, which could neither have swum across, nor have been introduced by man. Thus no one, he says, would have imported wolves, therefore "these wicked beasts did of themselves pass over." He supposes the ancient isthmus to have been about six English miles in breadth, composed entirely of chalk and flint, and in some places of no great height above the sea-level. The operation of the waves and tides, he says, would have been more powerful when the straits were narrower, and even now they are destroying cliffs composed of similar materials. He suggests the possible co-operation of earthquakes; and when we consider how many submarine forests skirt the southern and eastern shores of England, and that there are raised beaches at many points above the sea-level, containing fossil shells of recent species, it seems reasonable to suppose that such upward and downward movements, taking place perhaps as slowly as those now in progress in Sweden and Greenland, may have greatly assisted the denuding force of "the ocean stream," *Ποταμοιο μεγα σθενος Ωκεανοιο.*

---

* Dodsley's Ann. Regist. 1772.

† See J. B. Redman on Changes of S.E. Coast of England, Proceed. Instit. Civil Engin. vol ii. 1851, 1852.

‡ Stevenson, Ed. Phil. Journ. No. v. p. 45., and Dr. Fitton, Geol. Trans., 2d series, vol. iv. plate 9.

Folkstone. — At Folkstone, the sea undermines the chalk and subjacent strata. About the year 1716 there was a remarkable sinking of a tract of land near the sea, so that houses became visible from certain points at sea, and from particular spots on the sea cliffs, from whence they could not be seen previously. In the description of this subsidence in the Phil. Trans. 1716, it is said, "that the land consisted of a solid stony mass (chalk), resting on wet clay (gault), so that it slid forwards towards the sea, just as a ship is launched on tallowed planks." It is also stated that, within the memory of persons then living, the cliff there had been washed away to the extent of ten rods.

Encroachments of the sea at Hythe are also on record; but between this point and Rye there has been a gain of land within the times of history; the rich level tract called Romney Marsh, or Dungeness, about ten miles in width and five in breadth, and formed of silt, having received great accession. It has been necessary, however, to protect it from the sea, from the earliest periods, by embankments, the towns of Lydd and Romney being the only parts of the marsh above the level of the highest tides.[*] Mr. Redman has cited numerous old charts and trustworthy authorities to prove that the average annual increase of the promontory of shingle called Dungeness amounted for two centuries, previous to 1844, to nearly six yards. Its progress, however, has fluctuated during that period; for between 1689 and 1794, a term of 105 years, the rate was as much as 8¼ yards per annum.[†] It is ascertained that the shingle is derived from the westward. Whether the pebbles are stopped by the meeting of the tide from the north flowing through the Straits of Dover, with that which comes up the Channel from the west, as was formerly held, or by the check given to the tidal current by the waters of the Rother, as some maintain, is still a disputed question.

Rye, situated to the south of Romney Marsh, was once destroyed by the sea, but it is now two miles distant from it. The neighbouring town of Winchelsea was destroyed in the reign of Edward I., the mouth of the Rother stopped up, and the river diverted into another channel. In its old bed, an ancient vessel, apparently a Dutch merchantman, was found about the year 1824. It was built entirely of oak, and much blackened.[‡] Large quantities of hazel-nuts, peat, and wood are found in digging in Romney Marsh.

South coast of England. — Westward of Hastings, or of St. Leonard's, the shore-line has been giving way as far as Pevensey Bay, where formerly there existed a haven now entirely blocked up by shingle. The degradation has equalled for a series of years seven feet per annum in some places, and several martello towers had in consequence, before 1851, been removed by the Ordnance.[*] At the promontory of Beachy Head a mass of chalk, three hundred feet in length, and from seventy to eighty in breadth, fell in the year 1813 with a tremendous crash; and similar slips have since been frequent.[†]

---

[*] On the authority of Mr. J. Meryon, of Rye.

[†] Redman, ibid. see p. 315.

[‡] Edin. Journ. of Sci. No. xix. p. 56.

About a mile to the west of the town of Newhaven, the remains of an ancient entrenchment are seen on the brow of Castle Hill. This earthwork, supposed to be Roman, was evidently once of considerable extent and of an oval form, but the greater part has been cut away by the sea. The cliffs, which are undermined here, are high; more than one hundred feet of chalk being covered by tertiary clay and sand, from sixty to seventy feet in thickness. In a few centuries the last vestiges of the plastic clay formation on the southern borders of the chalk of the South Downs on this coast will probably be annihilated, and future geologists will learn, from historical documents, the ancient geographical boundaries of this group of strata in that direction. On the opposite side of the estuary of the Ouse, on the east of Newhaven harbour, a bed of shingle, composed of chalk flints derived from the waste of the adjoining cliffs, had accumulated at Seaford for several centuries. In the great storm of November, 1824, this bank was entirely swept away, and the town of Seaford inundated. Another great beach of shingle is now forming from fresh materials.

The whole coast of Sussex has been incessantly encroached upon by the sea from time immemorial; and, although sudden inundations only, which overwhelmed fertile or inhabited tracts, are noticed in history, the records attest an extraordinary amount of loss. During a period of no more than eighty years, there are notices of about *twenty* inroads, in which tracts of land of from twenty to *four hundred acres* in extent were overwhelmed at once, the value of the tithes being mentioned in the Taxatio Ecclesiastica.[‡] In the reign of Elizabeth, the town of Brighton was situated on that tract where the chain pier now extends into the sea. In the year 1665 twenty-two tenements had been destroyed under the cliff. At that period there still remained under the cliff 113 tenements, the whole of which were overwhelmed in 1703 and 1705. No traces of the ancient town are now perceptible, yet there is evidence that the sea has merely resumed its ancient position at the base of the cliffs, the site of the whole town having been merely a beach abandoned by the ocean for ages.

Hampshire. — *Isle of Wight.* — It would be endless to allude to all the localities on the Sussex and Hampshire coasts where the land has given way; but I may point out the relation which the geological structure of the Isle of Wight bears to its present shape, as attesting that the coast owes its outline to the continued action of the sea. Through the middle of the island runs a high ridge of chalk strata, in a vertical position, and in a direction east and west. This chalk forms the projecting promontory of Culver Cliff on the east, and of the Needles on the west; while Sandown Bay on the one side, and Compton Bay on the other, have been hollowed out of the softer sands and argillaceous strata, which are inferior, in geological position, to the chalk.

---

[*] Redman as cited, p. 315.

[†] Webster, Geol. Trans. vol. ii. p. 192. 1st series.

[‡] Mantell, Geology of Sussex, p. 293.

The same phenomena are repeated in the Isle of Purbeck, where the line of vertical chalk forms the projecting promontory of Handfast Point; and Swanage Bay marks the deep excavation made by the waves in the softer strata, corresponding to those of Sandown Bay.

Hurst Castle bank—progressive motion of sea beaches.—Although the loose pebbles and grains of sea composing any given line of sea-beach are carried sometimes one way, sometimes another, they have, nevertheless, an ultimate motion in one particular direction.* Their progress, for example, on the south coast of England, is from west to east, which is owing partly to the action of the waves driven eastwards by the prevailing wind, and partly to the current, or the motion of the general body of water caused by the tides and winds. The force of the waves gives motion to pebbles which the velocity of the currents alone would be unable to carry forwards; but as the pebbles are finally reduced to sand or mud, by continual attrition, they are brought within the influence of a current; and this cause must determine the course which the main body of matter derived from wasting cliffs will eventually take.

It appears, from the observations of Mr. Palmer and others, that if a pier or groin be erected anywhere on our southern or south-eastern coast to stop the progress of the beach, a heap of shingle soon collects on the western side of such artificial barriers. The pebbles continue to accumulate till they rise as high as the pier or groin, after which they pour over in great numbers during heavy gales.†

The western entrance of the Channel, called the Solent, is crossed for more than two thirds of its width by the shingle-bank of Hurst Castle, which is about two miles long, seventy yards broad and twelve feet high, presenting an inclined plane to the west. This singular bar consists of a bed of rounded chalk flints, resting on a submarine argillaceous base. The flints and a few other pebbles, intermixed, are derived from the waste of Hordwell, and other cliffs to the westward, where tertiary strata, capped with a covering of broken chalk flints, from five to fifty feet thick, are rapidly undermined. In the great storm of November, 1824, this bank of shingle was moved bodily forwards for forty yards towards the north-east; and certain piles, which served to mark the boundaries of two manors, were nd after the storm on the opposite side of the bar. At the same e many acres of pasture land were covered by shingle, on the n of Westover, near Lymington. But the bar was soon restored ts old position by pebbles drifted from the west; and it appears n ancient maps that it has preserved the same general outline and ition for centuries.*

---

* See Palmer on Shingle Beaches, Phil. Trans. 1834, p. 568.

† Groins are formed of piles and wooden planks, or of faggots staked down; and are used either to break the force of the waves, or to retain the beach.

Ir. Austen remarks that, as a general rule, it is only when high s concur with a gale of wind, that the sea reaches the base of cliffs is to undermine them and throw down earth and stone. But the ves are perpetually employed in abrading and fashioning the maials already strewed over the beach. Much of the gravel and ngle is always travelling up and down, between high-water mark l a slight depth below the level of the lowest tides, and occaaally the materials are swept away and carried into deeper water. ing to these movements every portion of our southern coast y be seen at one time or other in the condition of bare rock. t other beds of sand and shingle soon collect, and, although comed of new materials, invariably exhibit on the same spots precisely ilar characters.†

The cliffs between Hurst Shingle Bar and Christchurch are underaed continually, the sea having often encroached for a series of rs at the rate of a yard annually. Within the memory of persons r living, it has been necessary thrice to remove the coast-road ther inland. The tradition, therefore, is probably true, that the rch of Hordwell was once in the middle of that parish, although r (1830) very near the sea. The promontory of Christchurch ad gives way slowly. It is the only point between Lymington l Poole Harbour, in Dorsetshire, where any hard stony masses ur in the cliffs. Five layers of large ferruginous concretions, newhat like the septaria of the London clay, have occasioned a istance at this point, to which we may ascribe this headland. In mean time, the waves have cut deeply into the soft sands and m of Poole Bay; and, after severe frosts, great landslips take ce, which by degrees become enlarged into narrow ravines, or nes, as they are called, with vertical sides. One of these chines, r Boscomb, has been deepened twenty feet within a few years. At head of each there is a spring, the waters of which have been efly instrumental in producing these narrow excavations, which sometimes from 100 to 150 feet deep.

Isle of Portland.—The peninsulas of Purbeck and Portland are tinually wasting away. In the latter, the soft argillaceous subtum (Kimmeridge clay) hastens the dilapidation of the superinnbent mass of limestone.

n 1665 the cliffs adjoining the principal quarries in Portland e way to the extent of one hundred yards, and fell into the sea; l in December, 1734, a slide to the extent of 150 yards occurred

---

Redman as cited, p. 315.

Rob. A. C. Austen on the Valley of the English Channel, Quart. Journ. G. S. vol. vi. p. 72.

on the east side of the isle, by which several skeletons, buried between slabs of stone, were discovered. But a much more memorable occurrence of this nature, in 1792, occasioned probably by the undermining of the cliffs, is thus described in Hutchin's History of Dorsetshire: — "Early in the morning the road was observed to crack: this continued increasing, and before two o'clock the ground had sunk several feet, and was in one continued motion, but attended with no other noise than what was occasioned by the separation of the roots and brambles, and now and then a falling rock. At night it seemed to stop a little, but soon moved again; and, before morning, the ground from the top of the cliff to the water-side had sunk in some places fifty feet perpendicular. The extent of ground that moved was about *a mile and a quarter* from north to south, and 600 yards from east to west."

Formation of the Chesil Bank. — Portland is connected with the mainland by the Chesil Bank, a ridge of shingle about seventeen miles in length, and, in most places, nearly a quarter of a mile in breadth. The pebbles forming this immense barrier are chiefly siliceous, all loosely thrown together, and rising to the height of from twenty to thirty feet above the ordinary high-water mark; and at the south-eastern end, which is nearest the Isle of Portland, where the pebbles are largest, forty feet. The fundamental rocks whereon the shingle rests are found at the depth of a few yards only below the level of the sea. The formation of that part of the bar which attaches Portland to the mainland may have been due to an original shoal or reef, or to the set of the tides in the narrow channel, by which the course of the pebbles, which are always coming from the west, has been arrested. It is a singular fact, that, throughout the Chesil Bank, the pebbles increase gradually in size as we proceed south-eastward, or as we go farther from the quarter which supplied them. Had the case been reversed, we should naturally have attributed the circumstance to the constant wearing down of the pebbles by friction, as they are rolled along a beach seventeen miles in length. But the true explanation of the phenomenon is doubtless this, the tidal current runs strongest from west to east, and its power is greater in the more open channel or farther from the land. In other words its force increases southwards, and as the direction of the bank is from north-west to south-east, the size of the masses coming from the westward and thrown ashore must always be largest where the motion of the water is most violent. Colonel Reid states that all calcareous stones rolled along from the west are soon ground into sand, and in this form they pass round Portland Island.*

The storm of 1824 burst over the Chesil Bank with great fury, and the village of Chesilton, built upon its southern extremity, was overwhelmed, with many of the inhabitants. The same storm carried away part of the Breakwater at Plymouth, and huge masses of from two to five tons in weight, were lifted from the bottom of eather side, and rolled fairly to the top of the pile. One block iestone, weighing seven tons, was washed round the western mity of the Breakwater, and carried 150 feet.* The propelling : is derived in these cases from the breaking of the waves, ı run fastest in shallow water, and for a short space far exceed ost rapid currents in swiftness. It was in the same month and .uring a spring-tide, that a great flood is mentioned on the coasts gland, in the year 1099. Florence of Worcester says, "On the day of the nones of Nov. 1099, the sea came out upon the shore uried towns and men very many, and oxen and sheep innumer- We also read in the Saxon Chronicle, for the year 1099, s year eke on St. Martin's mass day, the 11th of Novembre, g up so much of the sea flood, and so myckle harm did, as no ninded that it ever afore did, and there was the ylk day a new ."

---

* See Palmer on Motion of Shingle Beaches, Phil. Trans. 1834, p. 568.; and Col. Sir W. Reid, Papers of Royal Engineers, 1838, vol. ii. p. 128.

ıth of the Bill, or southern point of Portland, is a remarkable in the channel at the depth of seven fathoms, called "the Sham- consisting entirely of rolled and broken shells of Purpura lapillus, us edulis, and other species now living. This mass of light mate- is always in motion, varying in height from day to day, and yet ıoal remains constant.

rsetshire — Devonshire. — At Lyme Regis, in Dorsetshire, the ırch Cliffs," as they are called, consisting of lias about one hun- feet in height, gradually fell away at the rate of one yard a year, 1800 to 1829.†

extraordinary landslip occurred on the 24th of December, on the coast between Lyme Regis and Axmouth, which has described by the Rev. W. D. Conybeare, to whose kindness I ıdebted for the accompanying section, fig. 36. The tract of

Fig. 36.



Landslip, near Axmouth, Dec. 1839. (Rev. W. D. Conybeare.)

ːt of Downs still remaining at their original level.
' ravine.
ꞁunk and fractured strip united to A, before the convulsion.
Ꝭendon undercliff as before, but more fissured, and thrust forward about fifty feet toward sea.
ɜmidal crag, sunk from seventy to twenty feet in height.
' reef upheaved from the sea.

---

e la Beche, Geolog. Manual, p.

† According to the measurement of Carpenter of Lyme.

downs ranging there along the coast is capped by chalk (*h*), which rests on sandstone, alternating with chert (*i*), beneath which is more than 100 feet of loose sand (*k*), with concretions at the bottom, and belonging, like *i*, to the green-sand formation; the whole of the above masses, *h*, *i*, *k*, reposing on retentive beds of clay (*l*), belonging to the lias, which shelves towards the sea. Numerous springs issuing from the loose sand (*k*) have gradually removed portions of it, and thus undermined the superstratum, so as to have caused subsidences at former times, and to have produced a line of undercliff between D and E. In 1839 an excessively wet season had saturated all the rocks with moisture, so as to increase the weight of the incumbent mass, from which the support had already been withdrawn by the action of springs. Thus the superstrata were precipitated into hollows prepared for them, and the adjacent masses of partially undermined rock, to which the movement was communicated, were made to slide down on a slippery basis of watery sand towards the sea. These causes gave rise to a convulsion, which began on the morning of the 24th of December, with a crashing noise; and, on the evening of the same day, fissures were seen opening in the ground, and the walls of tenements rending and sinking, until a deep chasm or ravine, B, was formed extending nearly three quarters of a mile in length, with a depth of from 100 to 150 feet, and a breadth exceeding 240 feet. At the bottom of this deep gulf lie fragments of the original surface thrown together in the wildest confusion. In consequence of lateral movements, the tract intervening between the new fissure and the sea, including the ancient undercliff, was fractured, and the whole line of sea-cliff carried bodily forwards for many yards. "A remarkable pyramidal crag, F, off Culverhole Point, which lately formed a distinguishing landmark, has sunk from a height of about seventy to twenty feet, and the main cliff, E, before more than fifty feet distant from this insulated crag, is now brought almost close to it. This motion of the sea-cliff has produced a farther effect, which may rank among the most striking phenomena of this catastrophe. The lateral pressure of the descending rocks has urged the neighbouring strata, extending beneath the shingle of the shore, by their state of unnatural condensation, to burst upwards in a line parallel to the coast — thus an elevated ridge, G, more than a mile in length, and rising more than forty feet, covered by a confused assemblage of broken strata, and immense blocks of rock, invested with sea-weed and corallines, and scattered over with shells and star-fish, and other productions of the deep, forms an extended reef in front of the present range of cliffs." *

A full account of this remarkable landslip, with a plan, sections and many fine illustrative drawings, was published by Messrs. Conybeare and Buckland †, from one of which the annexed cut has been reduced, fig. 37.

---

* Rev. W. D. Conybeare, letter dated Axminster, Dec. 31. 1839.

† London, J. Murray, 1840.

) Axmouth landslip from Great Bindon, looking westward to the Sidmouth hills, and estuary of the Exe. From an original drawing by Mrs. Buckland.

all.—Near Penzance, in Cornwall, there is a projecting ' land, called the "Green," formed of granitic sand, from)re than thirty acres of pasture land have been gradually ay, in the course of the last two or three centuries.‡ It is that St. Michael's Mount, now an insular rock, was formerly n a wood, several miles from the sea; and its old Cornish 'araclowse in Cowse) signifies, according to Carew, the)ck in the wood.† Between the Mount and Newlyn there nder the sand, black vegetable mould, full of hazel nuts, and :hes, leaves, roots, and trunks of forest trees, all of indigenous This stratum has been traced seaward as far as the ebb and many proofs of a submerged vegetable accumulation, nps of trees in the position in which they grew, have been ays Sir Henry De la Beche, round the shores of Devon, , and Western Somerset. The facts not only indicate a ı the relative level of the sea and land, since the species of ınd plants were the same as those now living in this district; at is very remarkable, there seems evidence of the sub- ɜ having been effected, in part at least, since the country bited by man.‡

)marine forest occurring at the mouth of the Parret in shire, on the south side of the Bristol Channel, was described . Horner, in 1815, and its position attributed to subsidence. ' peat is there seen below the level of the sea, and the trunks trees, such as the oak and yew, having their roots still g as they grew, and fixed in blue clay.§

, Trans. Royal Geol. Soc. of vol. ii. p. 129.

, ibid. vol. ii. p. 135.

‡ De la Beche's Report on the Geology of Devon, &c. chap. xiii.

§ Geol. Trans. 1st series, vol. iii. p. 383.

Tradition of loss of land in Cornwall.—The oldest historians mention a tradition in Cornwall, of the submersion of the Lionnesse, a country said to have stretched from the Land's End to the Scilly Islands. The tract, if it existed, must have been thirty miles in length, and perhaps ten in breadth. The land now remaining on either side is from two hundred to three hundred feet high; the intervening sea about three hundred feet deep. Although there is no authentic evidence for this romantic tale, it probably originated in some former inroads of the Atlantic, accompanying, perhaps, a subsidence of land on this coast.*

West coast of England.—Having now brought together an ample body of proofs of the destructive operations of the waves, tides, and currents, on our eastern and southern shores, it will be unnecessary to enter into details of changes on the western coast, for they present merely a repetition of the same phenomena, and in general on an inferior scale. On the borders of the estuary of the Severn the flats of Somersetshire and Gloucestershire have received enormous accessions, while, on the other hand, the coast of Cheshire, between the rivers Mersey and Dee, has lost, since the year 1764, many hundred yards, and some affirm more than half a mile, by the advance of the sea upon the abrupt cliffs of red clay and marls. Within the period above mentioned several lighthouses have been successively abandoned.† There are traditions in Pembrokeshire ‡ and Cardiganshire § of far greater losses of territory than that which the Lionnesse tale of Cornwall pretends to commemorate. They are all important, as demonstrating that the earliest inhabitants were familiar with the phenomenon of incursions of the sea.

Loss of land on the coast of France.—The French coast, particularly that of Brittany, where the tides rise to an extraordinary height, is the constant prey of the waves. In the ninth century many villages and woods are reported to have been carried away, the coast undergoing great change, whereby the hill of St. Michael was detached from the mainland. The parish of Bourgneuf, and several others in that neighbourhood, were overflowed in the year 1500. In 1735, during a great storm, the ruins of Palnel were seen uncovered in the sea. ||

---

* Boase, vol. ii. p. 130.

† Stevenson, Jameson's Ed. New Phil. Journ. No. 8. p. 386.

‡ Camden, who cites Gyraldus; also Ray, "On the Deluge," Phys. Theol. p. 228.

§ Meyrick's Cardigan.

|| Von Hoff, Geschichte, &c. vol. i. p. 48.

CHAPTER XX.

ACTION OF TIDES AND CURRENTS—*continued.*

:he sea at the mouths of the Rhine in Holland—Changes in the arms :hine—Proofs of subsidence of land—Estuary of the Bies Bosch, ı 1421—Zuyder Zee, in the 13th century—Islands destroyed—the Ems converted into a bay—Estuary of the Dollart formed—Ent of the sea on the coast of Sleswick—On shores of North America—re, called the Bore—Influence of tides and currents on the mean level Action of currents in inland lakes and seas—Baltic—Cimbrian deluge of Gibraltar—No under-current there—Whether salt is precipitated diterranean—Waste of shores of Mediterranean.

f the sea at the mouths of the Rhine.—THE line of British idered in the preceding chapter offered no example of the two great antagonist forces; the influx, on the one hand, draining a large continent, and, on the other, the action res, tides, and currents, of the ocean. But when we pass e Straits of Dover to the Continent, and proceed northwe find an admirable illustration of such a contest, where and the Rhine are opposed to each other, each disputing l now occupied by Holland; the one striving to shape out, the other to form a delta. There was evidently a period river obtained the ascendancy, when the shape and ıe relative level of the coast and set of the tides were ·ent; but for the last two thousand years, during which itnessed and actively participated in the struggle, the result in favour of the ocean; the area of the whole territory ·ome more and more circumscribed; natural and artificial aving given way, one after another; and many hundred .uman beings having perished in the waves.

in the arms of the Rhine.—The Rhine, after flowing :rison Alps, copiously charged with sediment, first purifies e Lake of Constance, where a large delta is formed; then the Aar and numerous other tributaries, it flows for more ıundred miles towards the north; when, entering a low vides into two arms, about ten miles north-east of Cleves, which must therefore be considered the head of its delta. ·, fig. 38.) In speaking of the delta, I do not mean to assume ıt part of Holland which is comprised within the several : Rhine can be called a delta in the strictest sense of the ıuse some portion of the country thus circumscribed, as, le, a part of Gelderland and Utrecht, consists of strata · have been deposited in the sea before the Rhine existed. :r tracts may either have been raised like the Ullah Bund during the period when the sediment of the Rhine was

Fig. 38.



The dark tint between Antwerp and Nieuport, represents part of the Netherlands which wa land in the time of the Romans, then overflowed by the sea before and during the 5th century, and after wards reconverted into land.

converting a part of the sea into land, or they may have constituted islands previously.

When the river divides north of Cleves, the left arm takes the name of the Waal; and the right, retaining that of the Rhine, is connected, a little farther to the north, by an artificial canal with the river Yssel. The Rhine then flowing westward divides again south-east of Utrecht, and from this point it takes the name of the Leck, a name which was given to distinguish it from the northern arm called the Old Rhine, which was sanded up until after the year 1825, when a channel was cut for it, by which it now enters the sea at Catwyck. It is common, in all great deltas, that the principal channels of discharge should shift from time to time, but in Holland so many magnificent canals have been constructed, and have so diverted, from time to time, the course of the waters, that the geographical changes in this delta are endless, and their history, since the Roman era, forms a complicated topic of antiquarian research. The present head of the delta is about forty geographical miles from the nearest part of the gulf called the Zuyder Zee, and more than twice that distance from the general coast line. The present head of the delta of the Nile is about 80 or 90 geographical miles from the sea; that of the Ganges, as before stated, 220; and that of the Mississippi about 180, reckoning from the point where the Atchafalaya branches off to the extremity of the new tongue of land in the Gulf of Mexico. But the comparative distance between the heads of tas and the sea affords no positive data for estimating the relativ nagnitude of the alluvial tracts formed by their respective rivers, or the ramifications depend on many varying and temporary cirumstances, and the area over which they extend does not hold any onstant proportion to the volume of water in the river.

The Rhine therefore has at present three mouths. About two hirds of its waters flow to the sea by the Waal, and the remainder s carried partly to the Zuyder Zee by the Yssel, and partly to the cean by the Leck. As the whole coast to the south as far as Ostend, nd on the north to the entrance of the Baltic, has, with few exeptions, from time immemorial, yielded to the force of the waves, it s evident that the common delta of the Rhine, Meuse, and Scheldt, or these three rivers may all be considered as discharging their vaters into the same part of the sea, would, if its advance had not een checked, have become extremely prominent; and even if it had emained stationary, would long ere this have projected far beyond he rounded outline of the coast, like that strip of land already lescribed at the mouth of the Mississippi. But we find, on the contrary, that the islands which skirt the coast have not only lessened in size, but in number also, while great bays have been formed in the interior by incursions of the sea.

In order to explain the incessant advance of the ocean on the shores and inland country of Holland, M. E. de Beaumont has suggested that there has in all probability been a general depression or sinking of the land below its former level over a wide area. Such a change of level would enable the sea to break through the ancient line of sand-banks and islands which protected the coast, — would lead to the enlargement of bays, the formation of new estuaries, and ultimately to the entire submergence of land. These views appear to be supported by the fact that several peat-mosses of fresh-water origin now occur under the level of the sea, especially on the site of the Zuyder Zee and Lake Flevo, presently to be mentioned. Several excavations also made for wells at Utrecht, Amsterdam, and Rotterdam have proved, that below the level of the ocean, the soil near the coast consists of alternations of sand with marine shells, and beds of peat and clay, which have been traced to the depth of fifty feet and upwards.[*]

I have said that the coast to the south as far as Ostend has given way. This statement may at first seem opposed to the fact, that the tract between Antwerp and Nieuport, shaded black in the annexed map (fig. 38.), although now dry land, and supporting a large population, has, within the historical period, been covered with the sea. This region, however, consisted, in the time of the Romans, of woods, marshes, and peat-mosses, protected from the ocean by a chain of sandy dunes, which were afterwards broken through during storms, especially in the fifth century. The waters of the sea during these irruptions threw down upon the barren peat a horizontal bed of fertile clay, which is in some places three yards thick, full of recent shells and works of art. The inhabitants, by the aid of embankments and the sand dunes of the coast, have succeeded although not without frequent disasters, in defending the soil thus raised by the marine deposit.*

---

[*] E. de Beaumont, Géologie Pratique, vol. i. p. 316. and ibid. p. 260.

Inroads of the Sea in Holland.—If we pass to the northward of the territory just alluded to, and cross the Scheldt, we find that between the fourteenth and eighteenth centuries parts of the islands Walcheren and Beveland were swept away, and several populous districts of Kadzand, losses which far more than counterbalance the gain of land caused by the sanding up of some pre-existing creeks. In 1658 the island Orisant was annihilated. One of the most memorable inroads of the sea occurred in 1421, when the tide, pouring into the mouth of the united Meuse and Waal, burst through a dam in the district between Dort and Gertrudenberg, and overflowed seventy-two villages, forming a large sheet of water called the Bies Bosch. (See map, fig. 38.) Thirty-five of the villages were irretrievably lost, and no vestige, even of their ruins, was afterwards seen. The rest were redeemed, and the site of the others, though still very generally represented on maps as an estuary, has in fact been gradually filled up by alluvial deposits, and had become in 1835, as I was informed by Professor Moll, an immense plain, yielding abundant crops of hay, though still uninhabited. To the north of the Meuse is a long line of shore covered with sand dunes, where great encroachments have taken place from time to time, in consequence chiefly of the prevalence of south-easterly winds, which blow down the sands towards the sea. The church of Scheveningen, not far from the Hague, was once in the middle of the village, and now stands on the shore, half the place having been overwhelmed by the waves in 1570. Catwyck, once far from the sea, is now upon the shore; two of its streets having been overflowed, and land torn away to the extent of 200 yards in 1719. It is only by aid of embankments that Petten, and several other places farther north, have been defended against the sea.

Formation of the Zuyder Zee and Straits of Staveren.—Still more important are the changes which have taken place on the coast opposite the right arm of the Rhine, or the Yssel, where the ocean has burst through a large isthmus, and entered the inland lake Flevo, which, in ancient times, was, according to Pomponius Mela, formed by the overflowing of the Rhine over certain lowlands. It appears that, in the time of Tacitus, there were several lakes on the present site of the Zuyder Zee, between Friesland and Holland. The successive inroads by which these, and a great part of the adjoining territory, were transformed into a great gulf, began about the commencement, and were completed towards the close, of the thirteenth century. Alting gives the following relation of the occurrence, drawn from manuscript documents of contemporary inhabitants of the neighbouring provinces. In the year 1205, the island now called Wieringen, to the south of the Texel, was still a part of the main-

---

* Belpaire, Mém. de l'Acad. Roy. de Bruxelles, tom. x. 1837. Dumont, Bulletin of the same Soc. tom. v. p. 643.

nd, but during several high floods, of which the dates are given,
nding in December, 1251, it was separated from the continent. By
ubsequent incursions, the sea consumed great parts of the rich and
opulous isthmus, a low tract which stretched on the north of Lake
levo, between Staveren in Friesland and Medemblick in Holland,
ill at length a breach was completed about the year 1282, and after-
rards widened. Great destruction of land took place when the sea
rst broke in, and many towns were swept away; but there was
fterwards a reaction to a certain extent, large tracts, at first sub-
erged, having been gradually redeemed. The new straits south of
taveren are more than half the width of those of Dover, but are very
hallow, the greatest depth not exceeding two or three fathoms. The
ew bay is of a somewhat circular form, and between *thirty* and *forty*
iles in diameter. How much of this space may formerly have been
ccupied by Lake Flevo is unknown. (See map, fig. 38.)

Destruction of islands.— A series of islands stretching from the
exel to the mouths of the Weser and Elbe are probably the last
elics of a tract once continuous. They have greatly diminished in
ize, and have lost about a third of their number, since the time of
liny; for that naturalist counted twenty-three islands between the
exel and Eider, whereas there are now only sixteen, including
eligoland and Neuwerk.* The island of Heligoland, at the mouth
f the Elbe, consists of a rock of red marl of the keuper formation
of the Germans), and is bounded by perpendicular red cliffs, above
00 feet high. Although, according to some accounts, it has been
reatly reduced in size since the year 800, M. Wiebel assures us,
hat the ancient map by Meyer cannot be depended upon, and that
he island, according to the description still extant by Adam of
remen, was not much larger than now, in the time of Charlemagne.
n comparing the map made in the year 1793 by the Danish
ngineer Wessel, the average encroachment of the sea on the cliffs,
etween that period and the year 1848 (or about half a century), did
ot amount to more than three feet.† On the other hand, some few
slands have extended their bounds in one direction, or become con-
ected with others, by the sanding-up of channels; but even these,
ike Juist, have generally given way as much on the north towards
he sea as they have gained on the south, or land side.

The Dollart formed.—While the delta of the Rhine has suffered
o materially from the movements of the ocean, it can hardly be sup-
osed that minor rivers on the same coast should have been per-
itted to extend their deltas. It appears that in the time of the
omans there was an alluvial plain of great fertility, where the Ems
ntered the sea by three arms. This low country stretched between
roningen and Friesland, and sent out a peninsula to the north-east
owards Emden. A flood in 1277 first destroyed part of the penin-
ula. Other inundations followed at different periods throughout the

---

* Von Hoff, vol. i. p. 364.

† Quart. Journ. Geol. Soc. vol. iv. p. 32.; Memoirs.

fifteenth century. In 1507, a part only of Torum, a considerable town, remained standing; and in spite of the erection of dams, the remainder of that place, together with market-towns, villages, and monasteries, to the number of fifty, were finally overwhelmed. The new gulf, which was called the Dollart, although small in comparison to the Zuyder Zee, occupied no less than six square miles at first; but part of this space was, in the course of the two following centuries, again redeemed from the sea. The small bay of Leybucht, farther north, was formed in a similar manner in the thirteenth century; and the bay of Harlbucht in the middle of the sixteenth. Both of these have since been partially reconverted into dry land. Another new estuary, called the Gulf of Jahde, near the mouth of the Weser, scarcely inferior in size to the Dollart, has been gradually hollowed out since the year 1016, between which era and 1651 a space of about four square miles has been added to the sea. The rivulet which now enters this inlet is very small; but Arens conjectures that an arm of the Weser had once an outlet in that direction.

Coast of Sleswick.—Farther north we find so many records of waste on the western coast of Sleswick, as to lead us to anticipate that, at no distant period in the history of the physical geography of Europe, Jutland may become an island, and the ocean may obtain a more direct entrance into the Baltic. Indeed, the temporary insulation of the northern extremity of Jutland has been effected no less than four times within the records of history, the ocean having as often made a breach through the bar of sand, which usually excludes it from the Lym Fiord. This long frith is 120 miles in length including its windings, and communicates at its eastern end with the Baltic. The last irruption of salt water happened in 1824, and the fiord was still open in 1837, when some vessels of thirty tons' burden passed through.

The Marsh islands between the rivers Elbe and Eider are mere banks, like the lands formed of the "warp" in the Humber, protected by dikes. Some of them, after having been inhabited with security for more than ten centuries, have been suddenly overwhelmed. In this manner, in 1216, no less than ten thousand of the inhabitants of Eiderstede and Ditmarsch perished; and on the 11th of October, 1634, the islands and the whole coast, as far as Jutland, suffered by a dreadful deluge.

Destruction of Northstrand by the sea. — Northstrand, up to the year 1240, was, with the islands Sylt and Föhr, so nearly connected with the mainland as to appear a peninsula, and was called North Friesland, a highly cultivated and populous district. It measured from nine to eleven geographical miles from north to south, and six to eight from east to west. In the above-mentioned year it was torn asunder from the continent, and in part overwhelmed. The Isle of Northstrand, thus formed, was, towards the end of the sixteenth century, only four geographical miles in circumference, and was still celebrated for its cultivation and numerous population. After many losses, it still contained nine thousand inhabitants. At last, n the year 1634, on the evening of the 11th of October, a flood assed over the whole island, whereby 1300 houses, with many hurches, were lost; fifty thousand head of cattle perished, and bove six thousand men. Three small islets, one of them still called Northstrand, alone remained, which are now continually wasting.

The redundancy of river water in the Baltic, especially during he melting of ice and snow in spring, causes in general an outward urrent through the channel called the Cattegat. But after a ontinuance of north-westerly gales, especially during the height f the spring-tides, the Atlantic rises, and pouring a flood of vater into the Baltic, commits dreadful devastations on the isles f the Danish Archipelago. This current even acts, though with liminished force, as far eastward as the vicinity of Dantzic.* Acounts written during the last ten centuries attest the wearing down f promontories on the Danish coast, the deepening of gulfs, the evering of peninsulas from the mainland, and the waste of islands, while in several cases marsh land, defended for centuries by dikes, as at last been overflowed, and thousands of the inhabitants whelmed n the waves. Thus the island Barsoe, on the coast of Sleswick, has ost, year after year, an acre at a time, and the island Alsen suffers n like manner.

Cimbrian deluge.—As we have already seen that during the flood efore mentioned, 6000 men and 50,000 head of cattle perished on Northstrand on the western coast of Jutland, we are well prepared o find that this peninsula, the Cimbrica Chersonesus of the ancients, as from a remote period been the theatre of like catastrophes. Accordingly, Strabo records a story, although he treats it as an ncredible fiction, that, during a high tide, the ocean rose upon this oast so rapidly, that men on horseback were scarcely able to escape.† Florus, alluding to the same tradition, says, "Cimbri, Teutoni, atque Tigurini, ab extremis Galliæ profugi, cùm terras eorum inundasset Oceanus, novas sedes toto orbe quærebant."‡ This event, commonly called the "Cimbrian Deluge," is supposed to have happened about three centuries before the Christian era; but it is not improbable that the principal catastrophe was preceded and followed by many devastations like those experienced in modern times on the islands and shores of Jutland, and such calamities may well be conceived to have forced on the migration of some maritime tribes.

Inroads of the sea on the eastern shores of North America.—After so many authentic details respecting the destruction of the coast in parts of Europe best known, it will be unnecessary to multiply examples of analogous changes in more distant regions of the world. It must not, however, be imagined that our own seas form any exception to the general rule. Thus, for example, if we pass over to the eastern coast of North America, where the tides rise, in the Bay of Fundy, to a great elevation, we find many facts attesting the incessant demolition of land. Cliffs, often several hundred feet high, composed of sandstone, red marl, and other rocks, which border that bay and its numerous estuaries, are perpetually undermined. The ruins of these cliffs are gradually carried, in the form of mud, sand, and large boulders, into the Atlantic by powerful currents, aided at certain seasons by drift ice, which forms along the coast, and freezes round large stones.

---

* See examples in Von Hoff, vol. i. . 73., who cites Pisansky.

† Book vii. Cimbri.

‡ Lib. iii. cap. 3.

At Cape May, on the north side of Delaware Bay, in the United States, the encroachment of the sea was shown by observations made consecutively for sixteen years, from 1804 to 1820, to average about nine feet a year [*]; and at Sullivan's Island, which lies on the north side of the entrance of the harbour of Charlestown, in South Carolina, the sea carried away a quarter of a mile of land in three years, ending in 1786. [†]

Tidal wave called "the Bore." — Before concluding my remarks on the action of the tides, I must not omit to mention the wave called "the Bore," which is sometimes produced in a river where a large body of water is made to rise suddenly, in consequence of the contraction of the channel. This wave terminates abruptly on the inland side; because the quantity of water contained in it is so great, and its motion so rapid, that time is not allowed for the surface of the river to be immediately raised by means of transmitted pressure. A tide wave thus rendered abrupt has a close analogy, observes Mr. Whewell, to the waves which curl over and break on a shelving shore.[‡]

The Bore which enters the Severn, where the phenomenon is of almost daily occurrence, is sometimes nine feet high, and at spring-tides rushes up the estuary with extraordinary rapidity. The finest example which I have seen of this wave was in Nova Scotia[§], where the tide is said to rise in some places seventy feet perpendicular, and to be the highest in the world. In the large estuary of the Shubenacadie, which connects with another estuary called the Basin of Mines, itself an embranchment of the Bay of Fundy, a vast body of water comes rushing up, with a roaring noise, into a long narrow channel, and while it is ascending, has all the appearance of pouring down a slope as steep as that of the celebrated rapids of the St. Lawrence. In picturesque effect, however, it bears no comparison, for instead of the transparent green water and snow-white foam of the St. Lawrence, the whole current of the Shubenacadie is turbid and densely charged with red mud. The same phenomenon is frequently witnessed in the principal branches of the Ganges and in the Megna as before mentioned (p. 279.). "In the Hoogly," says Rennell, "the Bore commences at Hoogly Point, the place where the river first contracts itself, and is perceptible above Hoogly Town; and so quick is its motion, that it hardly employs four hours in travelling from one to the other, though the distance is nearly seventy miles. At Calutta it sometimes occasions an instantaneous rise of five feet; and oth here, and in every other part of its track, the boats, on its pproach, immediately quit the shore, and make for safety to the iddle of the river. In the channels, between the islands in the outh of the Megna, the height of the Bore is said to exceed twelve eet; and is so terrific in its appearance, and dangerous in its consequences, that no boat will venture to pass at spring-tide."* These aves may sometimes cause inundations, undermine cliffs, and still ore frequently sweep away trees and land animals from low shores, o that they may be carried down, and ultimately imbedded in fluviaile or submarine deposits.

---

[*] New Monthly Mag. vol. vi. p. 69.

[†] Von Hoff, vol. i. p. 96.

[‡] Phil. Trans. 1833, p. 204.

[§] See Lyell's Travels in North America, in 1842, vol. ii. p. 166. London, 1845.

CURRENTS IN INLAND LAKES AND SEAS.

In such large bodies of water as the North American lakes, the ontinuance of a strong wind in one direction often causes the elevaion of the water, and its accumulation on the leeward side; and hile the equilibrium is restoring itself, powerful currents are occaioned. In October, 1833, a strong current in Lake Erie, caused artly by the set of the waters towards the outlet of the Lake, and artly by the prevailing wind, burst a passage through the extensive eninsula called Long Point, and soon excavated a channel more than ine feet deep and nine hundred feet wide. Its width and depth ave since increased, and a new and costly pier has been erected; for t is hoped that this event will permanently improve the navigation f Lake Erie for steam-boats.† On the opposite, or southern coast ot his lake, in front of the town of Cleveland, the degradation of the liffs had been so rapid for several years preceding a survey made in 1837, as to threaten many towns with demolition.‡ In the Black Sea, also, although free from tides, we learn from Pallas that there is a sufficiently strong current to undermine the cliffs in many parts, and particularly in the Crimea.

Straits of Gibraltar.—It is well known that a powerful current sets constantly from the Atlantic into the Mediterranean, and its influence extends along the whole southern borders of that sea, and even to the shores of Asia Minor. Captain Smyth found, during his survey, that the central current ran constantly at the rate of from three to six miles an hour eastward into the Mediterranean, the body of water being three miles and a half wide. But there are also two lateral currents — one on the European, and one on the African side; each of them about two miles and a half broad, and flowing at about the same rate as the central stream. These lateral currents ebb and flow with the tide, setting alternately into the Mediterranean and into the Atlantic. The excess of water constantly flowing in is very great, and there is only one cause to which this can be attributed, the loss of water in the Mediterranean by evaporation. That the level of this sea should be considerably depressed by this cause is quite conceivable, since we know that the winds blowing from the shores of Africa are hot and dry; and hygrometrical experiments recently made in Malta and other places, show that the mean quantity of moisture in the air investing the Mediterranean is equal only to one half of that in the atmosphere of England. The temperature also of the great inland sea is upon an average higher, by 3½° of Fahrenheit, than the eastern part of the Atlantic Ocean in the same latitude, which must greatly promote its evaporation. The Black Sea being situated in a higher latitude, and being the receptacle of rivers flowing from the north, is much colder, and its expenditure far less; accordingly it does not draw any supply from the Mediterranean, but, on the contrary, contributes to it by a current flowing outwards, for the most part of the year, through the Dardanelles. The discharge, however, at the Bosphorus is so small, when compared to the volume of water carried in by rivers, as to imply a great amount of evaporation in the Black Sea.

---

* Rennell, Phil. Trans. 1781.

† MS. of Capt. Bayfield, R. N.

‡ Silliman's Journ. vol. xxxiv. p. 349.

Whether salt be precipitated in the Mediterranean.—It is, however, objected, that evaporation carries away only fresh water, and that the current from the Atlantic is continually bringing in salt water: why, then, do not the component parts of the waters of the Mediterranean vary? or how can they remain so nearly the same as those of the ocean? Some have imagined that the excess of salt might be carried away by an under-current running in a contrary direction to the superior; and this hypothesis appeared to receive confirmation from a late discovery, that the water taken up about fifty miles within the Straits, from a depth of 670 fathoms, contained a quantity of salt *four times greater* than the water of the surface. Dr. Wollaston *, who analysed this water obtained by Captain Smyth, truly inferred that an under-current of such denser water flowing outward, if of equal breadth and depth with the current near the surface, would carry out as much salt below as is brought in above, although it moved with less than one fourth part of the velocity, and would thus prevent a perpetual increase of saltness in the Mediterranean beyond that existing in the Atlantic. It was also remarked by others, that the result would be the same, if the swiftness being equal, the inferior current had only one fourth of the volume of the superior. At the same time there appeared reason to conclude that this great specific gravity was only acquired by water at immense depths; for two specimens of the water, taken within the Mediterranean, at the distance of some hundred miles from the Straits, and at depths of 400 and even 450 fathoms, were found by Dr. Wollaston not to exceed in density that of many ordinary samples of sea water. Such being the case we can now prove that the vast amount of salt brought into the Mediterranean *does not* pass out again by the Straits; for it appears by Captain

---

* Phil. Trans. 1829, part i. p. 29.

Smyth's soundings, which Dr. Wollaston had not seen, that between the capes of Trafalgar and Spartel, which are twenty-two miles apart, and where the Straits are shallowest, the deepest part, which is on the side of Cape Spartel, is only 220 fathoms. It is therefore evident, that if water sinks in certain parts of the Mediterranean, in consequence of the increase of its specific gravity, to greater depths than 220 fathoms, it can never flow out again into the Atlantic, since it must be stopped by the submarine barrier which crosses the shallowest part of the Straits of Gibraltar.

The idea of the existence of a counter-current, at a certain depth, first originated in the following circumstance:—M. De l'Aigle, commander of a privateer called the Phœnix of Marseilles, gave chase to a Dutch merchant-ship, near Ceuta Point, and coming up with her in the middle of the gut, between Tariffa and Tangier, gave her one broadside, which directly sunk her. A few days after, the sunken ship, with her cargo of brandy and oil, was cast ashore near Tangier, which is at least four leagues to the westward of the place where she went down, and to which she must have floated in a direction contrary to the course of the *central* current.* This fact, however, affords no evidence of an under-current, because the ship, when it approached the coast, would necessarily be within the influence of a lateral current, which running westward twice every twenty-four hours, might have brought back the vessel to Tangier.

What, then, becomes of the excess of salt?—for this is an inquiry of the highest geological interest. The Rhone, the Po, the Nile, and many hundred minor streams and springs, pour annually into the Mediterranean large quantities of carbonate of lime, together with iron, magnesia, silica, alumina, sulphur, and other mineral ingredients in a state of chemical solution. To explain why the influx of this matter does not alter the composition of this sea has never been regarded as a difficulty; for it is known that calcareous rocks are forming in the delta of the Rhone, in the Adriatic, on the coast of Asia Minor, and in other localities. Precipitation is acknowledged to be the means whereby the surplus mineral matter is disposed of, after the consumption of a certain portion in the secretions of testacea, zoophytes, and other marine animals. But before muriate of soda can, in like manner, be precipitated, the whole Mediterranean ought, according to the received principles of chemistry, to become as much saturated with salt as Lake Aral, the Dead Sea, or the brine-springs of Cheshire.

It is undoubtedly true, in regard to small bodies of water, that every particle must be fully saturated with muriate of soda before a single crystal of salt can be formed; such is probably the case in all natural salterns: such, for example, as those described by travellers as occurring on the western borders of the Black Sea, where extensive marshes are said to be covered by thin films of salt after a rapid evaporation of sea water. The salt *étangs* of the Rhone, where salt has sometimes been precipitated in considerable abundance, have been already mentioned. In regard to the depth of the Mediterranean it appears that between Gibraltar and Ceuta, Captain Smyth sounded to the enormous depth of 950 fathoms, and found there a gravelly bottom, with fragments of broken shells. Saussure sounded to the depth of two thousand feet, within a few yards of the shore, at Nice; and M. Bérard has lately fathomed to the depth of more than six thousand feet in several places without reaching the bottom.*

---

* Phil. Trans. 1724.

The central abysses, therefore, of this sea are, in all likelihood, at least as deep as the Alps are high; and, as at the depth of seven hundred fathoms only, water has been found to contain a proportion of salt four times greater than at the surface, we may presume that the excess of salt may be much greater at the depth of two or three miles. After evaporation, the surface water becomes impregnated with a slight excess of salt, and its specific gravity being thus increased, it instantly falls to the bottom, while lighter water rises to the top, or flows in laterally, being always supplied by rivers and the current from the Atlantic. The heavier fluid, when it arrives at the bottom, cannot stop if it can gain access to any lower part of the bed of the sea, not previously occupied by water of the same density.

How far this accumulation of brine can extend before the inferior strata of water will part with any of their salt, and what difference in such a chemical process the immense pressure of the incumbent ocean, or the escape of heated vapours, thermal springs, or submarine volcanic eruptions, might occasion, are questions which cannot be answered in the present state of science.

The Straits of Gibraltar are said to become gradually wider by the wearing down of the cliffs on each side at many points; and the current sets along the coast of Africa, so as to cause considerable inroads in various parts, particularly near Carthage. Near the Canopic mouth of the Nile, at Aboukir, the coast was greatly devastated in the year 1784, when a small island was nearly consumed. By a series of similar operations, the old site of the cities of Nicopolis, Taposiris, Parva, and Canopus, have become a sand-bank.†

---

* Bull. de la Soc. Géol. de France,— Résumé, p. 72. 1832.

† Clarke's Travels in Europe, Asia, and Africa, vol. iii. pp. 340. and 363. 4th edition.

CHAPTER XXI.

REPRODUCTIVE EFFECTS OF TIDES AND CURRENTS.

ies how formed — Silting up of estuaries does not compensate the loss of on the borders of the ocean — Bed of the German Ocean — Composition extent of its sand-banks — Strata deposited by currents in the English nnel — On the shores of the Mediterranean — At the mouths of the Amazon, ioco, and Mississippi — Wide area over which strata may be formed by this e.

the facts enumerated in the last chapter, it appears that on the rs of the ocean, currents and tides co-operating with the waves e sea are most powerful instruments in the destruction and portation of rocks; and as numerous tributaries discharge their al burden into the channel of one great river, so we find that rivers deliver their earthy contents to one marine current, to be by it to a distance, and deposited in some deep receptacle of the . The current, besides receiving this tribute of sedimentary r from streams draining the land, acts also itself on the coast, es a river on the cliffs which bound a valley. Yet the waste of by marine currents constitutes on the whole a very insignificant on of the denudation annually effected by aqueous causes, as I point out in the sequel of this chapter (p. 339.).

inland seas, where the tides are insensible, or on those parts e borders of the ocean where they are feeble, it is scarcely pos- to prevent a harbour at a river's mouth from silting up; for a f sand or mud is formed at points where the velocity of the d river is checked by the sea, or where the river and a marine nt neutralize each other's force. For the current, as we have may, like the river, hold in suspension a large quantity of sedi- , or, co-operating with the waves, may cause the progressive n of a shingle beach in one direction. I have already alluded e erection of piers and groins at certain places on our southern , to arrest the course of the shingle and sand (see p. 318.). The ediate effect of these temporary obstacles is to cause a great nulation of pebbles on one side of the barrier, after which the n still moves on round the end of the pier at a greater distance the land. This system, however, is often attended with a serious for during storms the waves throw suddenly into the harbour ast heap of pebbles which have collected for years behind the or pier, as happened during a great gale (Jan. 1839) at Dover. ne formation and keeping open of large estuaries are due to the *ined influence* of tidal currents and rivers; for when the tide a large body of water suddenly enters the mouth of the river e, becoming confined within narrower bounds, while its momen tum is not destroyed, it is urged on, and, having to pass through a contracted channel, rises and runs with increased velocity, just as a stream when it reaches the arch of a bridge scarcely large enough to give passage to its waters, rushes with a steep fall through the arch. During the ascent of the tide, a body of fresh water, flowing down in an opposite direction from the higher country, is arrested in its course for several hours; and thus a large lake of fresh and brackish water is accumulated, which, when the sea ebbs, is let loose, as on the removal of an artificial sluice or dam. By the force of this retiring water, the alluvial sediment both of the river and of the sea is swept away, and transported to such a distance from the mouth of the estuary, that a small part only can return with the next tide.

It sometimes happens, that during a violent storm a large bar of sand is suddenly made to shift its position, so as to prevent the free influx of the tides, or efflux of river water. Thus about the year 1500 the sands at Bayonne were suddenly thrown across the mouth of the Adour. That river, flowing back upon itself, soon forced a passage to the northward along the sandy plain of Capbreton, till at last it reached the sea at Boucau, at the distance of *seven leagues* from the point where it had formerly entered. It was not till the year 1579 that the celebrated architect Louis de Foix undertook, at the desire of Henry III., to re-open the ancient channel, which he at last effected with great difficulty.*

In the estuary of the Thames at London, and in the Gironde, the tide rises only for five hours and ebbs seven, and in all estuaries the water requires a longer time to run down than up; so that the preponderating force is always in the direction which tends to keep open a deep and broad passage. But for reasons already explained, there is naturally a tendency in all estuaries to silt up partially, since eddies and backwaters, and points where opposing streams meet, are very numerous, and constantly change their position.

Many writers have declared that the gain on our eastern coast, since the earliest periods of history, has more than counterbalanced the loss; but they have been at no pains to calculate the amount of loss, and have often forgotten that, while the new acquisitions are manifest, there are rarely any natural monuments to attest the former existence of the land that has been carried away. They have also taken into their account those tracts artificially recovered, which are often of great agricultural importance, and may remain secure, perhaps, for thousands of years, but which are only a few feet above the mean level of the sea, and are therefore exposed to be overflowed again by a small proportion of the force required to move cliffs of considerable height on our shores. If it were true that the area of land annually abandoned by the sea in estuaries were equal to that invaded by it, there would still be no compensation *in kind*.

The tidal current which flows out from the north-west, and bears against the eastern coast of England, transports, as we have seen, iaterials of various kinds. Aided by the waves, it undermines and weeps away the granite, gneiss, trap rocks, and sand-stone of Shetind, and removes the gravel and loam of the cliffs of Holderness, Iorfolk, and Suffolk, which are between twenty and three hundred eet in height, and which waste at various rates of from one foot to ix yards annually. It also bears away, in co-operation with the hames and the tides, the strata of London clay on the coast of Essex nd Sheppey. The sea at the same time consumes the chalk with its ints for many miles continuously on the shores of Kent and Sussex – commits annual ravages on the freshwater beds, capped by a thick overing of chalk-flint gravel, in Hampshire, and continually saps the oundations of the Portland limestone. It receives, besides, during e rainy months, large supplies of pebbles, sand, and mud, which umerous streams from the Grampians, Cheviots, and other chains, end down to the sea. To what regions, then, is all this matter conigned? It is not retained in mechanical suspension by the waters f the ocean, nor does it mix with them in a state of chemical solution, –it is deposited *somewhere*, yet certainly not in the immediate eighbourhood of our shores; for, in that case, there would soon be a essation of the encroachment of the sea, and large tracts of low ind, like Romney Marsh, would almost everywhere encircle our land.

---

* Nouvelle Chronique de la Ville de Bayonne, pp. 113. 139. 1827.

As there is now a depth of water exceeding thirty feet, in some pots where towns like Dunwich flourished but a few centuries ago, ; is clear that the current not only carries far away the materials of he wasted cliffs, but is capable also of excavating the bed of the sea o a certain moderate depth.

So great is the quantity of matter held in suspension by the tidal urrent on our shores, that the waters are in some places artificially ntroduced into certain lands below the level of the sea; and by reeating this operation, which is called "warping," for two or three ears, considerable tracts have been raised, in the estuary of the Iumber, to the height of about six feet. If a current, charged with uch materials, meets with deep depressions in the bed of the ocean, t must often fill them up; just as a river, when it meets with a lake n its course, fills it gradually with sediment.

I have said (p. 337.) that the action of the waves and curents on sea-cliffs, or their power to remove matter from above to elow the sea level, is insignificant in comparison with the power of ivers to perform the same task. As an illustration we may take the oast of Holderness described in the last chapter (p. 304). It is omposed, as we have seen, of very destructible materials, is thirty-six niles long, and its average height may be taken at forty feet. As it has vasted away at the rate of two and a quarter yards annually, for a long eriod, it will be found on calculation that the quantity of matter thrown lown into the sea every year, and removed by the current, amounts o 51,321,600 cubic feet. It has been shown that the united Ganges nd Brahmapootra carry down to the Bay of Bengal 40,000,000,000 f cubic feet of solid matter every year, so that their transporting power is no less than 780 times greater than that of the sea on the coast above mentioned; and in order to produce a result equal to that of the two Indian rivers, we must have a line of wasting coast, like that of Holderness, nearly 28,000 miles in length, or longer than the entire circumference of the globe by above 3000 miles. The reason of so great a difference in the results may be understood when we reflect that the operations of the ocean are limited to a single line of cliff surrounding a large area, whereas great rivers with their tributaries, and the mountain torrents which flow into them, act simultaneously on a length of bank almost indefinite.

Nevertheless we are by no means entitled to infer, that the denuding force of the great ocean is a geological cause of small efficacy, or inferior to that of rivers. Its chief influence is exerted at moderate depths below the surface, on all those areas which are slowly rising, or are attempting, as it were, to rise above the sea. From data hitherto obtained respecting subterranean movements, we can scarcely speculate on an average rate of upheaval of more than two or three feet in a century. An elevation to this amount is taking place in Scandinavia, and probably in many submarine areas as vast as those which we know to be sinking from the proofs derived from circular lagoon islands or coral atolls. (See chap. 50.) Suppose strata as destructible as those of the Wealden, or the lower and upper cretaceous formation, or the tertiary deposits of the British Isles to be thus slowly upheaved, how readily might they all be swept away by waves and currents in an open sea! How entirely might each stratum disappear as it was brought up successively and exposed to the breakers! Shoals of wide extent might be produced, but it is difficult to conceive how any continent could ever be formed under such circumstances. Were it not indeed for the hardness and toughness of the crystalline and volcanic rocks which are often capable of resisting the action of the waves few lands might ever emerge from the midst of an open sea.

Supposed filling up of the German Ocean.—The German Ocean is deepest on the Norwegian side, where the soundings give 190 fathoms; but the mean depth of the whole basin may be stated at no more than thirty-one fathoms.* The bed of this sea is traversed by several enormous banks, the greatest of which is the Dogger Bank, extending for upwards of 354 miles from north to south. The whole superficies of these shoals is equal to about one-third of the whole extent of England and Scotland. The average height of the banks measures, according to Mr. Stevenson, about seventy-eight feet: the upper portion of them consisting of fine and coarse siliceous sand, mixed with comminuted corals and shells.† It had been supposed that these vast submarine hills were made up bodily of loose materials supplied from the waste of the English, Dutch, and other coasts; but the survey of the North Sea, conducted by Captain Hewett, affords ground for suspecting this opinion to be oneous. If such immense mounds of sand and mud had been :umulated under the influence of currents, the same causes ought ırly to have reduced to one level the entire bottom of the :rman Ocean; instead of which some long narrow ravines are ınd to intersect the banks. One of these varies from seventeen to ty-four fathoms in depth, and has very precipitous sides; in one :t, called the "Inner Silver Pits," it is fifty-five fathoms deep. ıe shallowest parts of the Dogger Bank were found to be forty-two t under water, except in one place, where the wreck of a ship had ısed a shoal. Such uniformity in the minimum depth of water :ms to imply that the currents, which vary in their velocity from nile to two miles and a half per hour, have power to prevent the :umulation of drift matter in places of less depth.

---

* Stevenson on bed of German Ocean, Ed. Phil. Journ. No. v. p. 44. 1820.

† Stevenson, ibid. p. 47. 1820.

Strata deposited by currents.—It appears extraordinary, that in ne tracts of the sea, adjoining the coast of England, where we know ıt currents are not only sweeping along rocky masses, thrown down, m time to time, from the high cliffs, but also occasionally scooping : channels in the regular strata, there should exist fragile shells and ıder zoophytes in abundance, which live uninjured by these violent ıvements. The ocean, however, is in this respect a counterpart of : land; and as, on the continents, rivers may undermine their banks, root trees, and roll along sand and gravel, while their waters are in- ɔited by testacea and fish, and their alluvial plains are adorned with h vegetation and forests, so the sea may be traversed by rapid cur- ıts, and its bed may here and there suffer great local derangement, thout any interruption of the general order and tranquillity. It ı been ascertained by soundings* in all parts of the world, that ere new deposits are taking place in the sea, coarse sand and small ɔbles commonly occur near the shore, while farther from land, and deeper water, finer sand and broken shells are spread out over the ttom. Still farther out, the finest mud and ooze are alone met with. :. Austen observes that this rule holds good in every part of the ıglish Channel examined by him. He also informs us, that where ı tidal current runs rapidly in what are called "races," where :face undulations are perceived in the calmest weather, over deep aks, the discoloration of the water does not arise from the power of :h a current to disturb the bottom at a depth of 40 or 80 fathoms, some have supposed. In these cases, a column of water sometimes 0 feet in height, is moving onwards with the tide clear and trans- rent above, while the lower portion holds fine sediment in suspen- n (a fact ascertained by soundings), when suddenly it impinges on a bank, and its height is reduced to 300 feet. It is thus made boil up and flow off at the surface, a process which forces up the rer strata of water charged with fine particles of mud, which in :ir passage from the coast had gradually sunk to a depth of 300 t or more.*

---

* Robt. A. C. Austen, Quart. Journ. Geol. Soc. vol. vi. p. 76

One important character in the formations produced by currents is, the immense extent over which they may be the means of diffusing homogeneous mixtures, for these are often co-extensive with a great line of coast; and, by comparison with their deposits, the deltas of rivers must shrink into significance. In the Mediterranean, the same current which is rapidly destroying many parts of the African coast, between the Straits of Gibraltar and the Nile, checks also the growth of the delta of the Nile, and drifts the sediment of that great river to the eastward. To this source may be attributed the rapid accretions of land on parts of the Syrian shores where rivers do not enter.

Among the greatest deposits now in progress, and of which the distribution is chiefly determined by currents, we may class those between the mouths of the Amazon and the southern coast of North America. Captain Sabine found that the equatorial current before mentioned (p. 292.) was running with the rapidity of four miles an hour where it crosses the stream of the Amazon, which river preserves part of its original impulse, and has its waters not wholly mingled with those of the ocean at the distance of 300 miles from its mouth.* The sediment of the Amazon is thus constantly carried to the north-west as far as to the mouths of the Orinoco, and an immense tract of swamp is formed along the coast of Guiana, with a long range of muddy shoals bordering the marshes, and becoming converted into land.† The sediment of the Orinoco is partly detained, and settles near its mouth, causing the shores of Trinidad to extend rapidly, and is partly swept away into the Carribean Sea by the Guinea current. According to Humboldt, much sediment is carried again out of the Carribean Sea into the Gulf of Mexico.

It should not be overlooked that marine currents, even on coasts where there are no large rivers, may still be the agents of spreading not only sand and pebbles, but the finest mud, far and wide over the bottom of the ocean. For *several thousand miles* along the western coast of South America, comprising the larger parts of Peru and Chili, there is a perpetual rolling of shingle along the shore, part of which, as Mr. Darwin has shown, are incessantly reduced to the finest mud by the waves, and swept into the depths of the Pacific by the tides and currents. The same author however has remarked that, notwithstanding the great force of the waves on that shore, all rocks 60 feet under water are covered by sea weed, showing that the bed of the sea is not denuded at that depth, the effects of the winds being comparatively superficial.

In regard to the distribution of sediment by currents it may be observed, that the rate of subsidence of the finer mud carried down by every great river into the ocean, or of that caused by the rolling of the waves upon a shore, must be extremely slow; for the more minute the separate particles of mud, the slower will they sink to the bottom, and the sooner will they acquire what is called their terminal velocity. It is well known that a solid body, descending through a resisting medium, falls by the force of gravity, which is constant, but its motion is resisted by the medium more and more as its velocity increases, until the resistance becomes sufficient to counteract the further increase of velocity. For example, a leaden ball, one inch diameter, falling through air of density as at the earth's surface, will never acquire greater velocity than 260 feet per second, and, in water, its greatest velocity will be 8 feet 6 inches per second. If the diameter of the ball were $\frac{1}{10}$ of an inch, the terminal velocities in air would be 26 feet, and in water ·86 of a foot per second.

---

* Experiments to determine the Figure of the Earth, &c. p. 445.

† Lochead on Nat. Hist. of Guiana, Edin. Trans. vol. iv.

Now, every chemist is familiar with the fact, that minute particles descend with extreme slowness through water, the extent of their surface being very great in proportion to their weight, and the resistance of the fluid depending on the amount of surface. A precipitate of sulphate of baryta, for example, will sometimes require more than five or six hours to subside one inch*; while oxalate and phosphate of lime require nearly an hour to subside about an inch and a half and two inches respectively†, so exceedingly small are the particles of which these substances consist.

When we recollect that the depth of the ocean is supposed frequently to exceed three miles, and that currents run through different parts of that ocean at the rate of four miles an hour, and when at the same time we consider that some fine mud carried away from the mouths of rivers and from sea-beaches, where there is a heavy surf, as well as the impalpable powder showered down by volcanos, may subside at the rate of only an inch per hour, we shall be prepared to find examples of the transportation of sediment over areas of indefinite extent.

It is not uncommon for the emery powder used in polishing glass to take more than an hour to sink one foot. Suppose mud composed of coarser particles to fall at the rate of two feet per hour, and these to be discharged into that part of the Gulf Stream which preserves a mean velocity of three miles an hour for a distance of two thousand miles; in twenty-eight days these particles will be carried 2016 miles, and will have fallen only to a depth of 224 fathoms.

In this example, however, it is assumed that the current retains its superficial velocity at the depth of 224 fathoms, for which we have as yet no data, although we have seen that the motion of a current may continue at the depth of 100 fathoms. (See above, p. 28.) Experiments should be made to ascertain the rate of currents at considerable distances from the surface, and the time taken by the finest sediment to settle in sea-water of a given depth, and then the geologist may determine the area over which homogeneous mixtures may be simultaneously distributed in certain seas.

---

* On the authority of Mr. Faraday. † On the authority of Mr. R. Phillips.

CHAPTER XXII.

IGNEOUS CAUSES.

Changes of the inorganic world, *continued*—Igneous causes—Division of the subject—Distinct volcanic regions—Region of the Andes—System of volcanos extending from the Aleutian isles to the Molucca and Sunda islands—Polynesian archipelago—Volcanic region extending from Central Asia to the Azores—Tradition of deluges on the shores of the Bosphorus, Hellespont, and Grecian isles—Periodical alternation of earthquakes in Syria and Southern Italy—Western limits of the European region—Earthquakes rarer and more feeble as we recede from the centres of volcanic action—Extinct volcanos not to be included in lines of active vents.

We have hitherto considered the changes wrought, since the times of history and tradition, by the continued action of aqueous causes on the earth's surface; and we have next to examine those resulting from igneous agency. As the rivers and springs on the land, and the tides and currents in the sea, have, with some slight modifications, been fixed and constant to certain localities from the earliest periods of which we have any records, so the volcano and the earthquake have, with few exceptions, continued, during the same lapse of time, to disturb the same regions. But as there are signs, on almost every part of our continent, of great power having been exerted by running water on the surface of the land, and by waves, tides, and currents on cliffs bordering the sea, where, in modern times, no rivers have excavated, and no waves or tidal currents undermined—so we find signs of volcanic vents and violent subterranean movements in places where the action of fire or internal heat has long been dormant. We can explain why the intensity of the force of aqueous causes should be developed in succession in different districts. Currents, for example, tides, and the waves of the sea, cannot destroy coasts, shape out or silt up estuaries, break through isthmuses, and annihilate islands, form shoals in one place, and remove them from another, without the direction and position of their destroying and transporting power becoming transferred to new localities. Neither can the relative levels of the earth's crust, above and beneath the waters, vary from time to time, as they are admitted to have varied at former periods, and as it will be demonstrated that they still do, without the continents being, in the course of ages, modified, and even entirely altered, in their external configuration. Such events must clearly be accompanied by a complete change in the volume, velocity, and direction of the streams and land floods to which certain regions give passage. That we should find, therefore, cliffs where the sea once committed ravages, and from which it has now retired—estuaries where high tides once rose, but which are now dried up—valleys hollowed out by water, where no streams now flow, is no more than we should expect;—these and similar phenomena are the necessary consequences of physical causes now in operation; and if there be no instability in the laws of nature, similar fluctuations must recur again and again in time to come.

But, however natural it may be that the force of running water in numerous valleys, and of tides and currents in many tracts of the sea, should now be *spent*, it is by no means so easy to explain why the violence of the earthquake and the fire of the volcano should also have become locally extinct at successive periods. We càn look back to the time when the marine strata, whereon the great mass of Etna rests, had no existence; and that time is extremely modern in the earth's history. This alone affords ground for anticipating that the eruptions of Etna will one day cease.

> Nec quæ sulfureis ardet fornacibus Ætna
> Ignea semper erit, *neque enim fuit ignea semper*,
> (Ovid, *Metam.* lib. 15—340.)

are the memorable words which are put into the mouth of Pythagoras by the Roman poet, and they are followed by speculations as to the cause of volcanic vents shifting their positions. Whatever doubts the philosopher expresses as to the nature of these causes, it is assumed, as incontrovertible, that the points of eruption will hereafter vary, *because they have formerly done so;* a principle of reasoning which, as I have endeavoured to show in former chapters, has been too much set at nought by some of the earlier schools of geology, which refused to conclude that great revolutions in the earth's surface are now in progress, or that they will take place hereafter, *because* they have often been repeated in former ages.

Division of the subject.—Volcanic action may be defined to be "the influence exerted by the heated interior of the earth on its external covering." If we adopt this definition, without connecting it, as Humboldt has done, with the theory of secular refrigeration, or the cooling down of an original heated and fluid nucleus, we may then class under a general head all the subterranean phenomena, whether of volcanos, or earthquakes, and those insensible movements of the land, by which, as will afterwards appear, large districts may be depressed or elevated, without convulsions. According to this view, I shall consider first, the volcano; secondly, the earthquake; thirdly, the rising or sinking of land in countries where there are no volcanos or earthquakes; fourthly, the probable *causes* of the changes which result from subterranean agency.

It is a very general opinion that earthquakes and volcanos have a common origin; for both are confined to certain regions, although the subterranean movements are least violent in the immediate proximity of volcanic vents, especially where the discharge of aeriform fluids and melted rock is made constantly from the same crater. But as there are particular regions, to which both the points of eruption and the movements of great earthquakes are confined, I shall begin by tracing out the geographical boundaries of some of these, that the reader may be aware of the magnificent scale on which the agency of subterranean fire is now simultaneously developed. Over the whole of the vast tracts alluded to, active volcanic vents are distributed at intervals, and most commonly arranged in a linear direction. Throughout the intermediate spaces there is often abundant evidence that the subterranean fire is at work continuously, for the ground is convulsed from time to time by earthquakes; gaseous vapours, especially carbonic acid gas, are disengaged plentifully from the soil; springs often issue at a very high temperature, and their waters are usually impregnated with the same mineral matters as are discharged by volcanos during eruptions.

VOLCANIC REGIONS.

Region of the Andes.—Of these great regions, that of the Andes of South America is one of the best defined, extending from the southward of Chili to the northward of Quito, from about lat. 43° S. to about 2° N. of the equator. In this range, however, comprehending forty-five degrees of latitude, there is an alternation on a grand scale of districts of active with those of extinct volcanos, or which, if not spent, have at least been dormant for the last three centuries. How long an interval of rest may entitle us to consider a volcano as entirely extinct is not easily determined; but we know that in Ischia there intervened between two consecutive eruptions a pause of seventeen centuries; and the discovery of America is an event of far too recent a date to allow us even to conjecture whether different portions of the Andes, nearly the whole of which are subject to earthquakes, may not experience alternately a cessation and renewal of eruptions.

The first line of active vents which have been seen in eruption in the Andes extends from lat. 43° 28′ S.; or, from Yantales, opposite the isle of Chiloe, to Coquimbo, in lat. 30° S.; to these thirteen degrees of latitude succeed more than eight degrees, in which no recent volcanic eruptions have been observed. We then come to the volcanos of Bolivia and Peru, reaching six degrees from S. to N., or from lat. 21° S. to lat. 15° S. Between the Peruvian volcanos and those of Quito, another space intervenes of no less than fourteen degrees of latitude, said to be free from volcanic action so far as yet known. The volcanos of Quito then succeed, beginning about 100 geographical miles south of the equator, and continuing for about 130 miles north of the line, when there occurs another undisturbed interval of more than six degrees of latitude, after which we arrive at the volcanos of Guatemala or Central America, north of the Isthmus of Panama.*

Having thus traced out the line from south to north, I may first state, in regard to the numerous vents of Chili, that the volcanos of

---

* See Von Buch's Description of Canary Islands (Paris, ed. 1836) for a valuable sketch of the principal volcanos of the globe.

Yantales and Osorno were in eruption during the great earthquake of 1835, at the same moment that the land was shaken in Chiloe, and in some parts of the Chilian coast permanently upheaved; whilst at Juan Fernandez, at the distance of no less than 720 geographical miles from Yantales, an eruption took place beneath the sea. Some of the volcanos of Chili are of great height, as that of Antuco, in lat. 37° 40′ S., the summit of which is at least 16,000 feet above the sea. From the flanks of this volcano, at a great height, immense currents of lava have issued, one of which flowed in the year 1828. This event is said to be an exception in the general rule; few volcanos in the Andes, and none of those in Quito, having been seen in modern times to pour out lava, but having merely ejected vapour or scoriæ.

Both the basaltic (or augitic) lavas, and those of the felspathic class, occur in Chili and other parts of the Andes; but the volcanic rocks of the felspathic family are said by Von Buch to be generally not trachyte, but a rock which has been called andesite, or a mixture of augite and albite. The last-mentioned mineral contains soda instead of the potash found in common felspar.

The volcano of Rancagua, lat. 34° 15′ S., is said to be always throwing out ashes and vapours like Stromboli, a proof of the permanently heated state of certain parts of the interior of the earth below. A year rarely passes in Chili without some slight shocks of earthquakes, and in certain districts not a month. Those shocks which come from the side of the ocean are the most violent, and the same is said to be the case in Peru. The town of Copiapo was laid waste by this terrible scourge in the years 1773, 1796, and 1819, or in both cases after regular intervals of twenty-three years. There have, however, been other shocks in that country in the periods intervening between the dates above mentioned, although probably all less severe, at least on the exact site of Copiapo. The evidence against a regular recurrence of volcanic convulsions at stated periods is so strong as a general fact, that we must be on our guard against attaching too much importance to a few striking but probably accidental coincidences. Among these last might be adduced the case of Lima, violently shaken by an earthquake on the 17th of June, 1578, and again on the very same day, 1678; or the eruptions of Coseguina in the year 1709 and 1809, which are the only two recorded of that volcano previous to that of 1835.*

Of the permanent upheaval of land after earthquakes in Chili, I shall have occasion to speak in the next chapter, when it will also be seen that great shocks often coincide with eruptions, either submarine, or from the cones of the Andes, showing the identity of the force which elevates continents with that which causes volcanic outbursts.†

The space between Chili and Peru, in which no volcanic action has been observed, is 160 nautical leagues from south to north. It is, however, as Von Buch observes, that part of the Andes which is least known, being thinly peopled, [illegible] in some parts entirely desert. The volcanos of Peru rise from a lofty platform to vast heights above the level of the sea, from 17,000 to 20,000 feet. The lava which has issued from Viejo, lat. 16° 55′ S., accompanied by pumice, is composed of a mixture of crystals of albi[illegible] felspar, hornblende, and mica, a rock which has been considered [illegible] one of the varieties of andesite. Some tremendous earthquakes w[illegible] have visited Peru in modern times will be mentioned in a subseq[illegible]nt chapter.

---

* Darwin, Geol. Trans. 2d series, vol. v. p. 612.

† Ibid. p. 606.

The volcanos of Quito, occurring between the second degree of south and the third degree of north [illegible]atitude, rise to vast elevations above the sea, many of them being between 14,000 and 18,000 feet high. The Indians of Lican have a tradition that the mountain called L'Altar, or Capac Urcu, whi[illegible] means "the chief," was once the highest of those near the equator, being higher than Chimborazo; but in the reign of Ouainia Ab[illegible]atha, before the discovery of America, a prodigous eruption to[illegible]lace, which lasted eight years, and broke it down. The f[illegible] trachyte, says M. Boussingault, which once formed the co[illegible]nmit of this celebrated mountain, are at this day spread over t[illegible]n.* Cotopaxi is the most lofty of all the South American vo[illegible] which have been in a state of activity in modern times, its h[illegible]nt [illegible]eing 18,858 feet; and its eruptions have been more frequent and destructive than those of any other mountain. It is a perfect cone, usually covered with an enormous bed of snow, which has, however, been sometimes melted suddenly during an eruption; as in January 1803, for example, when the snows were dissolved in one night.

Deluges are often caused in the Andes by the liquefaction of great masses of snow, and sometimes by the rending open, during earthquakes, of subterranean cavities filled with water. In these inundations fine volcanic sand, loose stones, and other materials which the water meets with in its descent, are swept away, and a vast quantity of mud, called "moya," is thus formed and carried down into the lower regions. Mud derived from this source descended, in 1797, from the sides of Tunguragua in Quito, and filled valleys a thousand feet wide to the depth of six hundred feet, damming up rivers and causing lakes. In these currents and lakes of moya, thousands of small fish are sometimes enveloped, which, according to Humboldt, have lived and multiplied in subterranean cavities. So great a quantity of these fish were ejected from the volcano of Imbaburu in 1691, that fevers, which prevailed at the period, were attributed to the effluvia arising from the putrid animal matter.

In Quito, many important revolutions in the physical features of the country are said to have resulted, within the memory of man, from the earthquakes by which it has been convulsed. M. Boussingault declares his belief, that if a full register had been kept of all the convulsions experienced here and in other populous districts of the Andes, it would be found that the trembling of the earth had

---

* Bull. de la Soc. Géol. tom. vi. p. 55.

n incessant. The frequency of the movement, he thinks, is not
e to volcanic explosions, but to the continual falling in of masses
rock which have been fractured and upheaved in a solid form at a
nparatively recent epoch ; but a longer series of observations would
requisite to confirm this opinion. According to the same author,
height of several mountains of the Andes has diminished in modern
nes.*

The great crest or cordillera of the Andes is depressed at the Isthmus
Panama to a height of about 1000 feet, and at the lowest point of
paration between the two seas near the gulf of San Miguel, to 150
et. What some geographers regard as a continuation of that chain
Central America lies to the east of a series of volcanos, many of
ich are active in the provinces of Pasto, Popayan, and Guatemala.
seguina, on the south side of the Gulf of Fonseca, was in eruption
January 1835, and some of its ashes fell at Truxillo on the shores
the Gulf of Mexico. What is still more remarkable, on the same
y, at Kingston in Jamaica, the same shower of ashes fell, having
en carried by an upper counter current against the regular east wind
ich was then blowing. Kingston is about 700 miles distant from
seguina, and these ashes must have been more than four days in
e air, having travelled 170 miles a day. Eight leagues to the south-
rd of the crater, the ashes covered the ground to the depth of three
rds and a half, destroying the woods and dwellings. Thousands of
tle perished, their bodies being in many instances one mass of
rched flesh. Deer and other wild animals sought the towns for pro-
ction ; many birds and quadrupeds were found suffocated in the ashes,
d the neighbouring streams were strewed with dead fish.† Such
ts throw light on geological monuments, for in the ashes thrown
t at remote periods from the volcanos of Auvergne, now extinct,
find the bones and skeletons of lost species of quadrupeds.

Mexico.—The great volcanic chain, after having thus pursued its
urse for several thousand miles from south to north, sends off a
anch in a new direction in Mexico, in the parallel of the city of
at name, and is prolonged in a great platform, between the eighteenth
d twenty-second degrees of north latitude. Five active volcanos
averse Mexico from west to east—Tuxtla, Orizaba, Popocatepetl,
rullo, and Colima. Jorullo, which is in the centre of the great
atform, is no less than 120 miles from the nearest ocean—an impor-
nt circumstance, as showing that the proximity of the sea is not a
cessary condition, although certainly a very general characteristic,
the position of active volcanos. The extraordinary eruption of this
ountain, in 1759, will be described in the sequel. If the line which
onnects these five vents be prolonged in a westerly direction, it cuts
he volcanic group of islands called the Isles of Revillagigedo.

To the north of Mexico there are said to be three, or according to
ome, five volcanos in the peninsula of California; and a volcano is

---

* Bull. de la Soc. Géol. de France, om. vi. p. 56.

† Caldcleugh, Phil. Trans. 1836, p. 27.

reported to have been in eruption in the N. W. coast of America, the Colombia river, lat. 45° 37′ N.

West Indies. — To return to e Andes of Quito; Von Buch ind to the belief, that if we were b ter acquainted with the region east of the Madalena, and with New Granada and the Caraccas, might find the volcanic chain of the Andes to be connected with of the west Indian, or Caribbee Islands. The truth of this conjec has almost been set at rest by the eruption, in 1848, of the vol of Zamba in New G ada, at e mouth of the river Madalena.[*]

Of the West Indian t ere are two parallel series, the on the west, which are all v ic, and which rise to the heigh several thousand feet; ot rs to the east, for the most part posed of calcareous ro , and very low. In the former or vol series, are Granada, Vincent, St Lucia, Martinique, Domi Guadaloupe, Montserrat, Nevis, and St Eustace. In the calcar chain are Tobago, Barbadoes, Mariegallante, Grandeterre, Desi Antigua, Barbuda, St. Bartholomew, and St. Martin. The most siderable eruptions in modern times have been those of St. Vin Great earthquakes have agitated St. Domingo, as will be seen in twenty-ninth chapter.

I have before mentioned (p. 270.) the violent earthquake which 1812 convulsed the valley of the Mississippi at New Madrid, for space of 300 miles in length, of which more will be said in the twen seventh chapter. This happened exactly at the same time as the gr earthquake of Caraccas, so that it is possible that these two points parts of one subterranean volcanic region. The island of Jama with a tract of the contiguous sea, has often experienced tremend shocks; and these are frequent along a line extending from Jam to St. Domingo and Porto Rico.

Thus it will be seen that, without taking account of the W Indian and Mexican branches, a linear train of volcanos and tr shaken by earthquakes may be traced from the island of Chiloe opposite coast to Mexico, or even perhaps to the mouth of the lumbia river — a distance upon the whole as great as from the p to the equator. In regard to the western limits of the region, th lie deep beneath the waves of the Pacific, and must continue unkno to us. On the east they are not prolonged, except where they inc the West Indian Islands, to a great distance; for there seem to be indications of volcanic disturbances in Buenos Ayres, Brazil, and United States of North America.

Volcanic region from the Aleutian Isles to the Moluccas and Is of Sunda. — On a scale, which equals, or surpasses, that of Andes, is another line of volcanic action, which commences, on north, with the Aleutian Isles in Russian America, and extends, fi in a westerly direction for nearly 200 geographical miles, and th southwards, with few interruptions, throughout a space of betw sixty and seventy degrees of latitude to the Moluccas, where it se

---

[*] Comptes Rendus, 1849, vol. xxix. p. 531.



MAP OF ACTIVE VOLCANOS AND ATOLLS of THE INDIAN ARCHIPELAGO, and Part of the adjoining PACIFIC OCEAN.

● Active volcanos. ▬ Trains of active volcanos. ● Areas of subsidence containing atolls or coral islands with lagoons.

off a branch to the south-east, while the principal train continues westerly through Sumbawa and Java to Sumatra, and then in a north-westerly direction to the Bay of Bengal.* This volcanic line, observes Von Buch, may be said to follow throughout its course the external border of the continent of Asia; while the branch which has been alluded to as striking south-east from the Moluccas, passes from New-Guinea to New Zealand, conforming, though somewhat rudely, to the outline of Australia.†

The connexion, however, of the New Guinea volcanos with the line in Java (as laid down in Von Buch's map) is not clearly made out. By consulting Darwin's map of coral reefs and active volcanos ‡, the reader will see that we might almost with equal propriety include the Mariana and Bonin volcanos in a band with New Guinea. Or if we allow so much latitude in framing zones of volcanic action, we must also suppose the New Hebrides, Salomon Isles, and New Ireland to constitute one line (see map, fig. 39. p. 351.).

The northern extremity of the volcanic region of Asia, as described by Von Buch, is on the borders of Cook's Inlet, north-east of the Peninsula of Alaska, where one volcano, in about the sixtieth degree of latitude, is said to be 14,000 feet high. In Alaska itself are cones of vast height, which have been seen in eruption, and which are covered for two thirds of their height downwards with perpetual snow. The summit of the loftiest peak is truncated, and is said to have fallen in during an eruption in 1786. From Alaska the line is continued through the Aleutian or Fox Islands to Kamtschatka. In the Aleutian Archipelago eruptions are frequent, and about thirty miles to the north of Unalaska, near the Isle of Umnack, a new island was formed in 1796. It was first observed after a storm, at a point in the sea from which a column of smoke had been seen to rise. Flames then issued from the new islet which illuminated the country for ten miles round; a frightful earthquake shook the new-formed cone, and showers of stones were thrown as far as Umnack. The eruption continued for several months, and eight years afterwards, in 1804, when it was explored by some hunters, the soil was so hot in some places that they could not walk on it. According to Langsdorf and others, this new island, which is now several thousand feet high, and two or three miles in circumference, has been continually found to have increased in size when successively visited by different travellers; but we have no accurate means of determining how much of its growth, if any, has been due to upheaval, or how far it has been exclusively formed by the ejection of ashes and streams of lava. It seems, however, to be well attested that earthquakes of the most terrific description agitate and alter the bed of the sea and surface of the land throughout this tract.

---

* See map of volcanic lines in Von Buch's work on the Canaries.

† Von Buch, ibid. p. 409.

‡ Darwin, Structure and Distrib. of Coral Reefs, &c., London, 1842. In the subjoined map, fig. 39., I have copied with permission a small part of the valuable map accompanying this work.

The line is continued in the southern extremity of the Peninsula of Kamtschatka, where there are many active volcanos, which, in some eruptions, have scattered ashes to immense distances. The largest and most active of these is Klutschew, lat. 56° 3′ N., which rises at once from the sea to the prodigious height of 15,000 feet. Within 700 feet of the summit, Erman saw, in 1829, a current of lava, emitting a vivid light, flow down the north-west side to the foot of the cone. A flow of lava from the summit of Mont Blanc to its base in the valley of Chamouni would afford but an inadequate idea of the declivity down which this current descended. Large quantities of ice and snow opposed for a time a barrier to the lava, until at length the fiery torrent overcame, by its heat and pressure, this obstacle, and poured down the mountain side with a frightful noise, which was heard for a distance of more than fifty miles.*

The Kurile chain of islands constitutes the prolongation of the Kamtschatka range, where a train of volcanic mountains, nine of which are known to have been in eruption, trends in a southerly direction. The line is then continued to the south-west in the great island of Jesso, and again in Nipon, the principal of the Japanese group. It then extends by Loo Choo and Formosa to the Philippine Islands, and thence by Sangir and the north-eastern extremity of Celebes to the Moluccas (see map, fig. 39.). Afterwards it passes westward through Sumbawa to Java.

There are said to be thirty-eight considerable volcanos in Java, some of which are more than 10,000 feet high. They are remarkable for the quantity of sulphur and sulphureous vapours which they discharge. They rarely emit lava, but rivers of mud issue from them, like the moya of the Andes of Quito. The memorable eruption of Galongoon, in 1822, will be described in the twenty-fifth chapter. The crater of Taschem, at the eastern extremity of Java, contains a lake strongly impregnated with sulphuric acid, a quarter of a mile long, from which a river of acid water issues, which supports no living creature, nor can fish live in the sea near its confluence. There is an extinct crater near Batur, called Guevo Upas, or the Valley of Poison, about half a mile in circumference, which is justly an object of terror to the inhabitants of the country. Every living being which penetrates into this valley falls down dead, and the soil is covered with the carcasses of tigers, deer, birds, and even the bones of men; all killed by the abundant emanations of carbonic acid gas, by which the bottom of the valley is filled.

In another crater in this land of wonders, near the volcano of Talaga Bodas, we learn from Mr. Reinwardt, that the sulphureous exhalations have killed tigers, birds, and innumerable insects; and the soft parts of these animals, such as the fibres, muscles, nails, hair, and skin, are very well preserved, while the bones are corroded, and entirely destroyed.

---

* Von Buch, Descrip. des Iles Canar. p. 450., who cites Erman and others.

We learn from observations made in 1844, by Mr. Jukes, that a recent tertiary formation composed of limestone and resembling the coral rock of a fringing reef, clings to the flanks of all the volcanic islands from the east end of Timor to the west end of Java. These modern calcareous strata are often white and chalk-like, sometimes 1000 feet and upwards above the sea, regularly stratified in thick horizontal beds, and they show that there has been a general elevation of these islands at a comparatively modern period.*

The same linear arrangement which is observed in Java holds good in the volcanos of Sumatra, some of which are of great height, as Berapi, which is more than 12,000 feet above the sea, and is continually smoking. Hot springs are abundant at its base. The volcanic line then inclines slightly to the north-west, and points to Barren Island, lat. 12° 15′ N., in the Bay of Bengal. This volcano was in eruption in 1792, and will be described in the twenty-sixth chapter. The volcanic train then extends, according to Dr. Macclelland, to the island of Narcondam, lat. 13° 22′ N., which is a cone seven or eight hundred feet high, rising from deep water, and said to present signs of lava currents descending from the crater to the base. Afterwards the train stretches in the same direction to the volcanic island of Ramree, about lat. 19° N., and the adjoining island of Cheduba, which is represented in old charts as a burning mountain. Thus we arrive at the Chittagong coast, which in 1762 was convulsed by a tremendous earthquake (see chap. 29.).†

To enumerate all the volcanic regions of the Indian and Pacific oceans would lead me far beyond the proper limits of this treatise; but it will appear in the last chapter of this volume, when coral reefs are treated of, that the islands of the Pacific consist alternately of linear groups of two classes, the one lofty, and containing active volcanos, and marine strata above the sea-level, and which have been undergoing upheaval in modern times; the other very low, consisting of reefs of coral, usually with lagoons in their centres, and in which there is evidence of a gradual subsidence of the ground. The extent and direction of these parallel volcanic bands has been depicted with great care by Darwin in his map before cited (p. 351.)

The most remarkable theatre of volcanic activity in the Northern Pacific — or, perhaps, in the whole world — occurs in the Sandwich islands, which have been admirably treated of in a recent work by Mr. Dana.‡

Volcanic region from central Asia to the Azores.— Another great region of subterranean disturbance is that which has been imagined to extend through a large part of Central Asia to the Azores, that is to say, from China and Tartary through Lake Aral and the Caspian to the Caucasus, and the countries bordering the Black Sea, then again through part of Asia Minor to Syria, and westward to the recian islands, Greece, Naples, Sicily, the southern part of Spain, ›rtugal, and the Azores. Respecting the eastern extremity of this ıe in China, we have little information, but many violent earthıakes are known to have occurred there. The volcano said to have en in eruption in the seventh century in Central Tartary is situated . the northern declivity of the Celestial Mountains, not far distant ›m the large lake called Issikoul; and Humboldt mentions other nts and solfataras in the same quarter, which are all worthy of ›tice, as being far more distant from the ocean (260 geographical iles) than any other known points of eruption.

---

* Paper read at meeting of Brit. Assoc. Southampton, Sept. 1846.

† Macclelland, Report on Coal and Min. Resources of India. Calcutta, 1838.

‡ Geology of the American Exploring Expedition. See also Lyell's Manual, "Sandwich I. Volcanos" — Index.

We find on the western shores of the Caspian, in the country und Baku, a tract called the Field of Fire, which continually emits flammable gas, while springs of naphtha and petroleum occur in the me vicinity, as also mud volcanos. Syria and Palestine abound in ›lcanic appearances, and very extensive areas have been shaken, different periods, with great destruction of cities and loss of lives. ontinual mention is made in history of the ravages committed by ırthquakes in Sidon, Tyre, Berytus, Laodicea, and Antioch, and in ıe Island of Cyprus. The country around the Dead Sea appears ridently, from the accounts of modern travellers, to be volcanic. . district near Smyrna, in Asia Minor, was termed by the Greeks atacecaumene, or "the burnt up," where there is a large arid tertory, without trees, and with a cindery soil.* This country was isited in 1841 by Mr. W. J. Hamilton, who found in the valley of ıe Hermus perfect cones of scoriæ, with lava-streams, like those of ıuvergne, conforming to the existing river-channels, and with their ırface undecomposed.†

Grecian Archipelago.—Proceeding westwards, we reach the ƚrecian Archipelago, where Santorin, afterwards to be described, is ıe grand centre of volcanic action.

It was Von Buch's opinion that the volcanos of Greece were rranged in a line running N. N. W. and S. S. E., and that they fforded the only example in Europe of active volcanos having a near direction; but M. Virlet, on the contrary, announces as the esult of his investigations, made during the French expedition to the lorea in 1829, that there is no one determinate line of direction for he volcanic phenomena in Greece, whether we follow the points f eruptions, or the earthquakes, or any other signs of igneous gency.‡

Macedonia, Thrace, and Epirus, have always been subject to earthıakes, and the Ionian Isles are continually convulsed.

Respecting Southern Italy, Sicily, and the Lipari Isles, it is ınnecessary to enlarge here, as I shall have occasion again to allude o them. I may mention, however, that a band of volcanic action ıas been traced by Dr. Daubeny across the Italian Peninsula, from

---

* Strabo, ed. Fal., p 900.

† Researches in Asia Minor, vol. ii. ı. 39.

‡ Virlet, Bulletin de la Soc. Géol. de France, tom. iii. p. 109.

Ischia to Mount Vultur, in Apulia, the commencement of the line being found in the hot springs of Ischia, after which it is prolonged through Vesuvius to the Lago d'Ansanto, where gases similar to those of Vesuvius are evolved. Its farther extension strikes Mount Vultur, a lofty cone composed of tuff and lava, from one side of which carbonic acid and sulphuretted hydrogen are emitted.*

Traditions of deluges. — The traditions which have come down to us from remote ages of great inundations said to have happened in Greece and on the confines of the Grecian settlements, had doubtless their origin in a series of local catastrophes, caused principally by earthquakes. The frequent migrations of the earlier inhabitants, and the total want of written annals long after the first settlement of each country, make it impossible for us at this distance of time to fix either the true localities or probable dates of these events. The first philosophical writers of Greece were, therefore, as much at a loss as ourselves to offer a reasonable conjecture on these points, or to decide how many catastrophes might sometimes have become confounded in one tale, or how much this tale may have been amplified, in after times, or obscured by mythological fiction. The floods of Ogyges and Deucalion are commonly said to have happened before the Trojan war; that of Ogyges more than seventeen, and that of Deucalion more than fifteen centuries before our era. As to the Ogygian flood, it is generally described as having laid waste Attica, and was referred by some writers to a great overflowing of rivers, to which cause Aristotle also attributed the deluge of Deucalion, which, he says, affected Hellas only, or the central part of Thessaly. Others imagined the same event to have been due to an earthquake, which drew down masses of rock, and stopped up the course of the Peneus in the narrow defile between mounts Ossa and Olympus.

As to the deluge of Samothrace, which is generally referred to a distinct date, it appears that the shores of that small island and the adjoining mainland of Asia were inundated by the sea. Diodorus Siculus says that the inhabitants had time to take refuge in the mountains, and save themselves by flight; he also relates, that long after the event the fishermen of the island drew up in their nets the capitals of columns, "which were the remains of cities submerged by that terrible catastrophe."† These statements scarcely leave any doubt that there occurred, at the period alluded to, a subsidence of the coast, accompanied by earthquakes and inroads of the sea. It is not impossible that the story of the bursting of the Black Sea through the Thracian Bosphorus into the Grecian Archipelago, which accompanied, and, as some say, caused the Samothracian deluge, may have reference to a wave or succession of waves, raised in the Euxine by the same convulsion.

We know that subterranean movements and volcanic eruptions are often attended not only by incursions of the sea, but also by violent rains, and the complete derangement of the river drainage of the inland country, and by the damming up of the outlets of lakes by landslips, or obstructions in the courses of subterranean rivers, such as abound in Thessaly and the Morea. We need not therefore be surprised at the variety of causes assigned for the traditional floods of Greece, by Herodotus, Aristotle, Diodorus, Strabo, and others. As to the area embraced, had all the Grecian deluges occurred simultaneously, instead of being spread over many centuries, and had they, instead of being extremely local, reached at once from the Euxine to the south-western limit of the Peloponnese, and from Macedonia to Rhodes, the devastation would still have been more limited than that which visited Chili in 1835, when a volcanic eruption broke out in the Andes, opposite Chiloe, and another at Juan Fernandez, distant 720 geographical miles, at the same time that several lofty cones, in the Cordillera, 400 miles to the eastward of that island, threw out vapour and ignited matter. Throughout a great part of the space thus recently shaken in South America, cities were laid in ruins, or the land was permanently upheaved, or mountainous waves rolled inland from the Pacific.

---

* Daubeny on Mount Vultur, Ashmolean Memoirs. Oxford, 1835.

† Book v. ch. xlvi. — See Letter of M. Virlet, Bulletin de la Soc. Géol. de France, tom. ii. p. 341.

Periodical alternation of Earthquakes in Syria and Southern Italy.—It has been remarked by Von Hoff, that from the commencement of the thirteenth to the latter half of the seventeenth century, there was an almost entire cessation of earthquakes in Syria and Judea; and, during this interval of quiescence, the Archipelago, together with part of the adjacent coast of Lesser Asia, as also Southern Italy and Sicily, suffered greatly from earthquakes; while volcanic eruptions were unusually frequent in the same regions. A more extended comparison, also, of the history of the subterranean convulsions of these tracts seems to confirm the opinion, that a violent crisis of commotion never visits both at the same time. It is impossible for us to declare, as yet, whether this phenomenon is constant in this and other regions, because we can rarely trace back a connected series of events farther than a few centuries; but it is well known that, where numerous vents are clustered together within a small area, as in many archipelagos for instance, two of them are never in violent eruption at once. If the action of one becomes very great for a century or more, the others assume the appearance of spent volcanos. It is, therefore, not improbable that separate provinces of the same great range of volcanic fires may hold a relation to one deep-seated focus, analogous to that which the apertures of a small group bear to some more superficial rent or cavity. Thus, for example, we may conjecture that, at a comparatively small distance from the surface, Ischia and Vesuvius mutually communicate with certain fissures, and that each affords relief alternately to elastic fluids and lava there generated. So we may suppose Southern Italy and Syria to be connected, at a much greater depth, with a lower part of the very same system of fissures; in which case any obstruction occurring in one duct may have the effect of causing almost all the vapour and melted matter to be forced up the other, and if they cannot get vent, they may be the cause of violent earthquakes. Some objections advanced against this doctrine that "volcanos act as safety-valves," will be considered in the sequel.*

The north-eastern portion of Africa, including Egypt, which lies six or seven degrees south of the volcanic line already traced, has been almost always exempt from earthquakes; but the north-western portion, especially Fez and Morocco, which fall within the line, suffer greatly from time to time. The southern part of Spain also, and Portugal, have generally been exposed to the same scourge simultaneously with Northern Africa. The provinces of Malaga, Murcia, and Granada, and in Portugal the country round Lisbon, are recorded at several periods to have been devastated by great earthquakes. It will be seen, from Michell's account of the great Lisbon shock in 1755, that the first movement proceeded from the bed of the ocean ten or fifteen leagues from the coast. So late as February 2, 1816, when Lisbon was vehemently shaken, two ships felt a shock in the ocean west from Lisbon; one of them at the distance of 120, and the other 262 French leagues from the coast† — a fact which is more interesting, because a line drawn through the Grecian Archipelago, the volcanic region of Southern Italy, Sicily, Southern Spain, and Portugal, will, if prolonged westward through the ocean, strike the volcanic group of the Azores, which may possibly therefore have a submarine connection with the European line.

In regard to the volcanic system of Southern Europe, it may be observed, that there is a central tract where the greatest earthquakes prevail, in which rocks are shattered, mountains rent, the surface elevated or depressed, and cities laid in ruins. On each side of this line of greatest commotion there are parallel bands of country where the shocks are less violent. At a still greater distance (as in Northern Italy, for example, extending to the foot of the Alps), there are spaces where the shocks are much rarer and more feeble, yet possibly of sufficient force to cause, by continued repetition, some appreciable alteration in the external form of the earth's crust. Beyond these limits, again, all countries are liable to slight tremors, at distant intervals of time, when some great crisis of subterranean movement agitates an adjoining volcanic region; but these may be considered as mere vibrations, propagated mechanically through the external covering of the globe, as sounds travel almost to indefinite distances through the air. Shocks of this kind have been felt in England, Scotland, Northern France, and Germany — particularly during the Lisbon earthquake. But these countries cannot, on this account, be supposed to constitute parts of the southern volcanic region, any more than the Shetland and Orkney islands can be considered as belonging to the

---

* See ch. 32., *Cause of Volcanic Eruptions.*

† Verneur, Journal des Voyages, tom. iv. p. 111.—Von Hoff, vol. ii. p. 275.

Icelandic circle, because the sands ejected from Hecla have been wafted thither by the winds.

Besides the continuous spaces of subterranean disturbance, of which we have merely sketched the outline, there are other disconnected volcanic groups, of which several will be mentioned hereafter.

Lines of active and extinct Volcanos not to be confounded. — We must always be careful to distinguish between lines of extinct and active volcanos, even where they appear to run in the same direction; for ancient and modern systems may interfere with each other. Already, indeed, we have proof that this is the case; so that it is not by geographical position, but by reference to the species of organic beings alone, whether aquatic or terrestrial, whose remains occur in beds interstratified with lavas, that we can clearly distinguish the relative age of volcanos of which no eruptions are recorded. Had Southern Italy been known to civilized nations for as short a period as America, we should have had no record of eruptions in Ischia; yet we might have assured ourselves that the lavas of that isle had flowed since the Mediterranean was inhabited by the species of testacea now living in the Neapolitan seas. With this assurance, it would not have been rash to include the numerous vents of that island in the modern volcanic group of Campania.

On similar grounds we may infer, without much hesitation, that the eruptions of Etna, and the modern earthquakes of Calabria, are a continuation of that action which, at a somewhat earlier period, produced the submarine lavas of the Val di Noto in Sicily. But on the other hand, the lavas of the Euganean hills and the Vicentin, although not wholly beyond the range of earthquakes in Northern Italy, must not be confounded with any existing volcanic system; for when they flowed, the seas were inhabited by animals almost all of them distinct from those now known to live, whether in the Mediterranean or other parts of the globe.

CHAPTER XXIII.

VOLCANIC DISTRICT OF NAPLES.

History of the volcanic eruptions in the district round Naples—Early convulsions in the island of Ischia—Numerous cones thrown up there—Lake Avernus—The Solfatara—Renewal of the eruptions of Vesuvius, A. D. 79.—Pliny's description of the phenomena—His silence respecting the destruction of Herculaneum and Pompeii—Subsequent history of Vesuvius—Lava discharged in Ischia in 1302—Pause in the eruptions of Vesuvius—Monte Nuovo thrown up—Uniformity of the volcanic operations of Vesuvius and Phlegræan Fields in ancient and modern times.

I SHALL next give a sketch of the history of some of the volcanic vents dispersed throughout the great regions before described, and consider the composition and arrangement of their lavas and ejected matter. The only volcanic region known to the ancients was that of the Mediterranean; and even of this they have transmitted to us very imperfect records relating to the eruptions of the three principal districts, namely, that round Naples, that of Sicily and its isles, and that of the Grecian Archipelago. By far the most connected series of records throughout a long period relates to the first of these provinces; and these cannot be too attentively considered, as much historical information is indispensable in order to enable us to obtain a clear view of the connection and alternate mode of action of the different vents in a single volcanic group.

Early convulsions in the Island of Ischia. — The Neapolitan volcanos extend from Vesuvius, through the Phlegræan Fields, to Procida and Ischia, in a somewhat linear arrangement, ranging from the north-east to the south-west, as will be seen in the annexed map of the volcanic district of Naples (fig. 40.). Within the space above limited, the volcanic force is sometimes developed in single eruptions from a considerable number of irregularly scattered points; but a great part of its action has been confined to one principal and habitual vent, Vesuvius or Somma. Before the Christian era, from the remotest periods of which we have any tradition, this principal vent was in a state of inactivity. But terrific convulsions then took place from time to time in Ischia (Pithecusa), and seem to have extended to the neighbouring isle of Procida (Prochyta); for Strabo[*] mentions a story of Procida having been torn asunder from Ischia; and Pliny[†] derives its name from its having been poured forth by an eruption from Ischia.

The present circumference of Ischia along the water's edge is eighteen miles, its length from west to east about five, and its breadth from north to south three miles. Several Greek colonies which settled there before the Christian era were compelled to abandon it in consequence of the violence of the eruptions. First the Erythræans, and afterwards the Chalcidians, are mentioned as having been driven out by earthquakes and igneous exhalations. A colony

---

[*] Lib. v.

[†] Nat. Hist. lib. iii. c. 6.

Fig. 40.



A. Astroni. B. Monte Barbaro. M. Monte Nuovo. S. The Solfatara.

was afterwards established by Hiero, king of Syracuse, about 380 years before the Christian era; but when they had built a fortress, they were compelled by an eruption to fly, and never again returned. Strabo tells us that Timæus recorded a tradition, that, a little before his time, Epomeus, the principal mountain in the centre of the island, vomited fire during great earthquakes; that the land between it and the coast had ejected much fiery matter, which flowed into the sea, and that the sea receded for the distance of three stadia, and then returning, overflowed the island. This eruption is supposed by some to have been that which formed the crater of Monte Corvo on one of the higher flanks of Epomeo, above Foria, the lava-current of which may still be traced, by aid of the scoriæ on its surface, from the crater to the sea.

To one of the subsequent eruptions in the lower parts of the isle, which caused the expulsion of the first Greek colony, Monte Rotaro has been attributed, and it bears every mark of recent origin. The cone, which I examined in 1828, is remarkably perfect, and has a crater on its summit precisely resembling that of Monto Nuovo near Naples; but the hill is larger, and resembles some of the more considerable cones of single eruption near Clermont in Auvergne, and, like some of them, it has given vent to a lava-stream at its base, instead of its summit. A small ravine swept out by a torrent exposes the structure of the cone, which is composed of innumerable inclined and slightly undulating layers of pumice, scoriæ, white lapilli, and enormous angular blocks of trachyte. These last have evidently been thrown out by violent explosions, like those which in 1822 launched from Vesuvius a mass of augitic lava, of many tons' weight, to the distance of three miles, which fell in the garden of Prince Ottajano. The cone of Rotaro is covered with the arbutus, and other beautiful evergreens. Such is the strength of the virgin soil, that the shrubs have become almost arborescent; and the growth of some of the smaller wild plants has been so vigorous, that botanists have scarcely been able to recognize the species.

The eruption which dislodged the Syracusan colony is supposed to have given rise to that mighty current which forms the promontory of Zaro and Caruso. The surface of these lavas is still very arid and bristling, and is covered with black scoriæ; so that it is not without great labour that human industry has redeemed some small spots, and converted them into vineyards. Upon the produce of these vineyards the population of the island is almost entirely supported. It amounted when I was there, in 1828, to about twenty-five thousand, and was on the increase.

From the date of the great eruption last alluded to, down to our own time, Ischia has enjoyed tranquillity, with the exception of one emission of lava hereafter to be described, which, although it occasioned much local damage, does not appear to have devastated the whole country, in the manner of more ancient explosions. There are, upon the whole, on different parts of Epomeo, or scattered through the lower tracts of Ischia, twelve considerable volcanic cones which have been thrown up since the island was raised above the surface of the deep; and many streams of lava may have flowed, like that of "Arso" in 1302, without cones having been produced; so that this island may, for ages before the period of the remotest traditions, have served as a safety-valve to the whole Terra di Lavoro, while the fires of Vesuvius were dormant.

Fig. 40.



View of Ischia from the West.

a, Monte Epomeo, or San Nicola. b, Monte Vico.
c, A [illegible] with a crater.*

---

* See Poulett Scrope, Geol. Trans. 2nd series, vol. ii. pl. 34.

Lake Avernus.—It seems also clear that Avernus, a circular lake ear Puzzuoli, about half a mile in diameter, which is now a salu- rious and cheerful spot, once exhaled mephitic vapours, such as are ften emitted by craters after eruptions. There is no reason for iscrediting the account of Lucretius, that birds could not fly over it ithout being stifled, although they may now frequent it uninjured.* here must have been a time when this crater was in action; and or many centuries afterwards it may have deserved the appellation f "atri jauna Ditis," emitting, perhaps, gases as destructive of nimal life as those suffocating vapours given out by Lake Quilotoa, n Quito, in 1797, by which whole herds of cattle on its shores were illed †, or as those deleterious emanations which annihilated all the attle in the island of Lancerote, one of the Canaries, in 1730.‡ Bory t. Vincent mentions, that in the same isle birds fell lifeless to the round; and Sir William Hamilton informs us that he picked up ead birds on Vesuvius during an eruption.

Solfatara.—The Solfatara, near Puzzuoli, which may be consi- ered as a nearly extinguished crater, appears, by the accounts of trabo and others, to have been before the Christian era in very uch the same state as at present, giving vent continually to aqueous apour, together with sulphureous and muriatic acid gases, like those volved by Vesuvius.

Ancient history of Vesuvius.—Such, then, were the points where he subterranean fires obtained vent, from the earliest period to which radition reaches back, down to the first century of the Christian era; ut we then arrive at a crisis in the volcanic action of this district—ne of the most interesting events witnessed by man during the rief period throughout which he has observed the physical changes n the earth's surface. From the first colonization of Southern Italy y the Greeks, Vesuvius afforded no other indications of its volcanic haracter than such as the naturalist might infer, from the analogy of ts structure to other volcanos. These were recognized by Strabo, ut Pliny did not include the mountain in his list of active vents. he ancient cone was of a very regular form, terminating not as at resent, in two peaks, but with a summit which presented, when een from a distance, the even outline of an abruptly truncated cone. n the summit, as we learn from Plutarch, there was a crater with teep cliffs, and having its interior overgrown with wild vines, and ith a sterile plain at the bottom. On the exterior, the flanks of he mountains were clothed with fertile fields richly cultivated, and t its base were the populous cities of Herculaneum and Pompeii. ut the scene of repose was at length doomed to cease, and the vol- anic fire was recalled to the main channel, which at some former nknown period had given passage to repeated streams of melted lava, and, and scoriæ.

Renewal of its eruptions.—The first symptom of the revival of

---

[*] De Rerum Nat. vi. 740.—Forbes, n Bay of Naples, Edin. Journ. of Sci., o. iii., new series, p. 87. Jan. 1830.

[†] Humboldt, Voy., p. 317.

[‡] Von Buch, Ueber einen vulcanischen Ausbruch auf der Insel Lanzerote.

the energies of this volcano w the occurrence of an earthquake in the year 63 after Christ, whi did considerable injury to the cities in its vicinity. From that the year 79 slight shocks were frequent; and in the month of A of that year they became more numerous and violent, till they ed at length in an eruption. The elder Pliny, who commanded the Roman fleet, was then stationed at Misenum; and in his anxiety to obtain a near view of the phenomena, he lost his life, being suffocated by sulphureous vapours. His nephew, the younger Pliny, remained at Misenum, and has given us, in his Letters, a lively description of the awful scene. A dense column of vapour was first seen rising vertically from Vesuvius, and then spreading itself out laterally, so that its upper portion resembled the head, and its lower the trunk of the pine, which characterises the Italian landscape. This black cloud was pierced occasionally by flashes of fire as vivid as lightning, succeeded by darkness more profound than night. Ashes fell even upon the ships at Misenum, and caused a shoal in one part of the sea—the ground rocked, and the sea receded from the shores, so that many marine animals were seen on the dry sand. The appearances above described agree perfectly with those witnessed in more recent eruptions, especially those of Monte Nuovo in 1538, and of Vesuvius in 1822.

The younger Pliny, although giving a circumstantial detail of so many physical facts, and describing the eruption and earthquake, and the shower of ashes which fell at Stabiæ, makes no allusion to the sudden overwhelming of two large and populous cities, Herculaneum and Pompeii. In explanation of this omission, it has been suggested that his chief object was simply to give Tacitus a full account of the particulars of his uncle's death. It is worthy, however, of remark, that had the buried cities never been discovered, the accounts transmitted to us of their tragical end might well have been discredited by the majority, so vague and general are the narratives, or so long subsequent to the event. Tacitus, the friend and contemporary of Pliny, when adverting in general terms to the convulsions, says merely that "cities were consumed or buried."[*]

Suetonius, although he alludes to the eruption incidentally, is silent as to the cities. They are mentioned by Martial, in an epigram, as immersed in cinders; but the first historian who alludes to them by name is Dion Cassius,[†] who flourished about a century and a half after Pliny. He appears to have derived his information from the traditions of the inhabitants, and to have recorded, without discrimination, all the facts and fables which he could collect. He tells us, "that during the eruption a multitude of men of superhuman stature, resembling giants, appeared, sometimes on the mountain, and sometimes in the environs—that stones and smoke were thrown out, the sun was hidden, and then the giants seemed to rise again, while the sounds of trumpets were heard, &c. &c.; and finally," he relates, "two entire cities, Herculaneum and Pompeii, were buried under showers of ashes, while all the people were sitting in the theatre." That many of these circumstances were invented, would have been obvious, even without the aid of Pliny's letters; and the examination of Herculaneum and Pompeii enables us to prove, that none of the people were destroyed in the theatres, and indeed, that there were very few of the inhabitants who did not escape from both cities. Yet some lives were lost, and there was ample foundation for the tale in its most essential particulars.

---

[*] Haustæ aut obrutæ urbes.—Hist. lib. i.

[†] Hist. Rom. lib. lxvi.

It does not appear that in the year 79 any lava flowed from Vesuvius; the ejected substances, perhaps, consisted entirely of lapilli, sand, and fragments of older lava, as when Monte Nuovo was thrown up in 1538. The first era at which we have authentic accounts of the flowing of a stream of lava, is the year 1036, which is the seventh eruption from the revival of the fires of the volcano. A few years afterwards, in 1049, another eruption is mentioned, and another in 1138 (or 1139), after which a great pause ensued of 168 years. During this long interval of repose, two minor vents opened at distant points. First, it is on tradition that an eruption took place from the Solfatara in the year 1198, during the reign of Frederick II., Emperor of Germany; and although no circumstantial detail of the event has reached us from those dark ages, we may receive the fact without hesitation.* Nothing more, however, can be attributed to this eruption, as Mr. Scrope observes, than the discharge of a light and scoriform trachytic lava, of recent aspect, resting upon the strata of loose tuff which covers the principal mass of trachyte.†

Volcanic eruption in Ischia, 1302.—The other occurrence is well authenticated,—the eruption, in the year 1302, of a lava-stream from a new vent on the south-east end of the Island of Ischia. During part of 1301, earthquakes had succeeded one another with fearful rapidity; and they terminated at last with the discharge of a lava-stream from a point named the Campo del Arso, not far from the town of Ischia. This lava ran quite down to the sea—a distance of about two miles: in colour it varies from iron grey to reddish black, and is remarkable for the glassy felspar which it contains. Its surface is almost as sterile, after a period of five centuries, as if it had cooled down yesterday. A few scantlings of wild thyme, and two or three other dwarfish plants, alone appear in the interstices of the scoriæ, while the Vesuvian lava of 1767 is already covered with a luxuriant vegetation. Pontanus, whose country-house was burnt and overwhelmed, describes the dreadful scene as having lasted two months.‡ Many houses were swallowed up, and a partial emigration of the inhabitants followed. This eruption produced no cone, but only a slight depression, hardly deserving the name of a crater, where heaps of black and red scoriæ lie scattered around. Until this eruption, Ischia is generally believed to have enjoyed an interval of rest for about seventeen centuries; but Julius Obsequens*, who flourished A. D. 214, refers to some volcanic convulsions in the year 662 after the building of Rome (91 B. C.). As Pliny, who lived a century before Obsequens, does not enumerate this among other volcanic eruptions, the statement of the latter author is supposed to have been erroneous; but it would be more consistent, for reasons before stated, to disregard the silence of Pliny, and to conclude, that some kind of subterranean commotion, probably of no great violence, happened at the period alluded to.

---

* The earliest authority, says Mr. Forbes, given for this fact, appears to be Capaccio, quoted in the Terra Tremante of Bonito.—Edin. Journ. of Sci. &c., No. i., new series, p. 127. July, 1829.

† Geol. Trans., second series, vol. ii. p. 346.

‡ Lib. vi. de Bello Neap. in Grævii Thesaur.

History of Vesuvius after 1138.—To return to Vesuvius:—the next eruption occurred in 1306; between which era and 1631 there was only one other (in 1500), and that a slight one. It has been remarked, that throughout this period Etna was in a state of such unusual activity, as to lend countenance to the idea that the great Sicilian volcano may sometimes serve as a channel of discharge to elastic fluids and lava that would otherwise rise to the vents in Campania.

Formation of Monte Nuovo, 1538.—The great pause was also marked by a memorable event in the Phlegræan Fields—the sudden formation of a new mountain in 1538, of which we have received authentic accounts from contemporary writers.

The height of this mountain, called ever since Monte Nuovo, has been determined, by the Italian mineralogist Pini, to be 440 English feet above the level of the bay; its base is about eight thousand feet,

Fig. 42.



Monte Nuovo, formed in the Bay of Baiæ, Sept. 29th, 1538.

1. Cone of Monte Nuovo. 2. Brim of crater of ditto.
3. Thermal spring, called Baths of Nero, or Stufe di Tritoli.

or more than a mile and a half in circumference. According to Pini, the depth of the crater is 421 English feet from the summit of the hill, at its bottom is only nineteen feet above the level of the sea. cone is declared, by the best authorities, to stand partly on the f the Lucrine Lake (4, fig. 43.*), which was nothing more than rater of a pre-existent volcano, and was almost entirely filled g the explosion of 1538. Nothing now remains but a shallow separated from the sea by an elevated beach, raised artificially.

---

* Prodig. libel. c. cxiv.

Fig. 43.



The Phlegræan Fields.

1. Monte Nuovo.
2. Monte Barbaro.
3. Lake Avernus.
4. Lucrine Lake.
5. The Solfatara.
6. Puzzuoli.
7. Bay of Baiæ.

Sir William Hamilton has given us two original letters describing s eruption. The first, by Falconi, dated 1538, contains the follow- passages.† "It is now two years since there have been frequent thquakes at Puzzuoli, Naples, and the neighbouring parts. On the and in the night before the eruption (of Monte Nuovo), above enty shocks, great and small, were felt. The eruption began on the th of September, 1538. It was on a Sunday, about one o'clock in e night, when flames of fire were seen between the hot baths and ipergola. In a short time the fire increased to such a degree, that burst open the earth in this place, and threw up so great a quantity ashes and pumice stones, mixed with water, as covered the whole untry. The next morning (after the formation of Monte Nuovo) e poor inhabitants of Puzzuoli quitted their habitations in terror, vered with the muddy and black shower which continued the whole y in that country — flying from death, but with death painted in eir countenances. Some with their children in their arms, some ith sacks full of their goods; others leading an ass, loaded with their ightened family, towards Naples; others carrying quantities of birds, various sorts, that had fallen dead at the beginning of the erup- on; others, again, with fish which they had found, and which were be met with in plenty on the shore, the sea having left them dry for a considerable time. I accompanied Signor Moramaldo to behold the wonderful effects of the eruption. The sea had retired on the side of Baiæ, abandoning a considerable tract, and the shore appeared almost entirely dry, from the quantity of ashes and broken pumice stones thrown up by the eruption. I saw two springs in the newly discovered ruins; one before the house that was the queen's, of hot and salt water," &c.

---

* This representation of the Phlegræan ields is reduced from part of Plate xxi. of Sir William Hamilton's great ork "Campi Phlegræi." The faithfulness of his coloured delineations of the scenery of that country cannot be too highly praised.

† Campi Phlegræi, p. 70.

So far Falconi: the other account is by Pietro Giacomo di Toledo, which begins thus: — "It is now two years since this province of Campagna has been afflicted with earthquakes, the country about Puzzuoli much more so than any other parts: but the 27th and the 28th of the month of September last, the earthquakes did not cease day or night in the town of Puzzuoli: that plain which lies between Lake Avernus, the Monte Barbaro, and the sea, was *raised a little*, and many cracks were made in it, from some of which issued water; at the same time the sea, immediately adjoining the plain, *dried up about two hundred paces*, so that the fish were left on the sand a prey to the inhabitants of Puzzuoli. At last, on the 29th of the same month, about two o'clock in the night, the earth opened near the lake, and discovered a horrid mouth, from which were vomited furiously smoke, fire, stones, and mud, composed of ashes, making at the time of its opening a noise like the loudest thunder. The stones which followed were by the flames converted to pumice, and some of these were *larger than an ox*. The stones went about as high as a cross-bow can carry, and then fell down, sometimes on the edge, and sometimes into the mouth itself. The mud was of the colour of ashes, and at first very liquid, then by degrees less so, and in such quantities, that in less than twelve hours, with the help of the above-mentioned stones, a mountain was raised of 1000 paces in height. Not only Puzzuoli and the neighbouring country was full of this mud, but the city of Naples also; so that many of its palaces were defaced by it. Now this eruption lasted two nights and two days without intermission, though, it is true, not always with the same force; the third day the eruption ceased, and I went up with many people to the top of the new hill, and saw down into its mouth, which was a round cavity about a quarter of a mile in circumference, in the middle of which, the stones which had fallen were boiling up, just as a caldron of water boils on the fire. The fourth day it began to throw up again, and the seventh much more, but still with less violence than the first night. At this time many persons who were on the hill were knock[illegible] stones and killed, or smothered with the smoke. [illegible] continues, and you often see fire in the [illegible]me."*

[illegible] these accounts, written immediately after [illegible], agree in stating that the sea retired; and [illegible] was upraised; but they attribute the [illegible] to the jets of mud, showers of

---

[illegible]grei, p. 77.

oriæ, and large fragments of rock, cast out from a central orifice, r several days and nights. Baron Von Buch, however, in his xcellent work on the Canary Islands, and volcanic phenomena in eneral, has declared his opinion that the cone and crater of Monte uovo were formed, not in the manner above described, but by the pheaval of solid beds of white tuff, which were previously horizontal, ut which were pushed up in 1538, so as to dip away in all directions rom the centre, with the same inclination as the sloping surface of he cone itself. "It is an error," he says, "to imagine that this hill as formed by eruption, or by the ejection of pumice, scoriæ, and ther incoherent matter; for the solid beds of upraised tuff are visible ll round the crater, and it is merely the superficial covering of the one which is made up of ejected scoriæ."[*]

In confirmation of this view, M. Dufrénoy has cited a passage from he works of Porzio, a celebrated physician of that period, to prove hat in 1538 the ground where Monte Nuovo stands was pushed up n the form of a great bubble or blister, which on bursting, gave rigin to the present deep crater. Porzio, says, "that after two days nd nights of violent earthquakes, the sea retired for nearly 200 yards; so that the inhabitants could collect great numbers of fish on this part of the shore, and see some springs of fresh water which rose up there. At length, on the third day of the calends of October September 29), they saw a large tract of ground intervening between he foot of Monte Barbaro and part of the sea, near the Lake Avernus, rise, and suddenly assume the form of an incipient hill; and at two o'clock at night, this heap of earth, opening as it were its mouth, vomited, with a loud noise, flames, pumice stones, and ashes."[†]

So late as the year 1846 a fourth manuscript (written immediately after the eruption) was discovered and published in Germany. It was written in 1538 by Francesco del Nero[‡], who mentions the drying up of the bed of the sea near Puzzuoli, which enabled the inhabitants of the town to carry off loads of fish. About eight o'clock in the morning of the 29th September, the earth sunk down about 14 feet in that place where the volcanic orifice now appears, and there issued forth a small stream of water, at first cold, and afterwards tepid. At noon, on the same day, the earth began to swell up in the same spot where it had sunk down 14 feet, so as to form a hill. About this time fire issued forth, and gave rise to the great gulf, with such a force, noise, and shining light, that I, who was standing in my garden, was seized with terror. Forty minutes afterwards, although unwell, I got upon a neighbouring height, from which I saw all that took place, and by my troth it was a splendid fire, that threw up for a long time much earth and many stones, which fell back again all round the gulf, in a semicircle of from one to three bow-shots in diameter, and, filling up part of the sea, formed a hill nearly of the height of Monte Morello. Masses of earth and stones, as large as an ox, were shot up from the fiery gulf into the air, to a height which I estimate at a mile and a half. When they descended, some were dry, others in a soft muddy state." He concludes by alluding again to the sinking of the ground, and the elevation of it which followed, and says that to him it was inconceivable how such a mass of stones and ashes could have been poured forth from the gulf. He also refers to the account which Porzio was to draw up for the Viceroy.

---

[*] P. 347. Paris, 1836.

[†] "Magnus terræ tractus, qui inter radices montis, quem Barbarum incolæ appellant, et mare juxta Avernum jacet, sese erigere videb[illegible] et montis subitò nascentis figuram [illegible]ari. Eo ipso die horâ noctis II, iste terræ cumulus, aperto [illegible]re, magno [illegible] fremitu, magnos [illegible]uit; p[illegible]esque, et lapides, cineresque." — Porzio, Opera Omnis, Medica, Phil., et Mathemat., in unum collecta, 1736, cited by Dufrénoy, Mém. pour servir à une Description Géologique de la France, tom. iv. p. 274.

[‡] See Neues Jahr Buch for 1846, and a translation in the Quarterly Journ. of the Geol. Soc. for 1847. vol. iii. p. 20. Memoirs.

On comparing these four accounts, recorded by eye-witnesses, there appears to be no real discrepancy between them. It seems clear that the ground first sunk down 14 feet on the site of the future volcano, and after having subsided it was again propelled upwards by the lava mingled with steam and gases, which were about to burst forth. Jets of red-hot lava, fragments of fractured rock, and occasionally mud composed of a mixture of pumice, tuff, and sea-water, were hurled into the air. Some of the blocks of stone were very large, leading us to infer that the ground which sank and rose again was much shattered and torn to pieces by the elastic vapours. The whole hill was not formed at once, but by an intermittent action extending over a week or more. It seems that the chasm opened between Tripergola and the baths in its suburbs, and that the ejected materials fell and buried that small town. A considerable part, however, of the hill was formed in less than twenty-four hours, and in the same manner as on a smaller scale the mud cones of air volcanos are produced, with a cavity in the middle. There is no difficulty in conceiving that the pumiceous mud, if so thrown out, may have set into a kind of stone on drying, just as some cements, composed of volcanic ashes, are known to consolidate with facility.

I am informed that Baron Von Buch discovered some marine shells of existing species, such as occur fossil in the tuff of the neighbourhood, in beds exposed low down in the walls of the crater of Monte Nuovo. These may have been ejected in the mud mixed with sea-water which was cast out of the boiling gulf; or, as Signor Arcangelo Scacchi has suggested[*], they may have been derived from the older tuff, which contains marine shells of recent species. The same observer remarks that Porzio's account upon the whole corroborates the doctrine of the cone having been formed by eruption, in proof of which he cites the following passage: — "But what was truly astonishing, a hill of pumice-stones and ashes was heaped up round the gulf, to the height of a mile in a single night."[†] Signor Scacchi also adds that the ancient temple of Apollo, now at the foot of Monte Nuovo, and the walls of which still retain their perfect perpendicularity, could not possibly have maintained that position had the cone of Monte Nuovo really been the result of upheaval.

---

[*] Mem. Roy. Acad. Nap. 1849.

[†] "Verum quod omnem superat admirationem, mons circum eam voraginem ex pummicibus et cinere plusquàm mille passuum altitudine unà nocte congestus aspicitur."

Tripergola was much frequented as a watering-place, and contained an hospital for those who resorted there for the benefit of the thermal springs; and it appears that there were no fewer than three inns in the principal street. Had Porzio stated that any of these buildings, or the ruins of them, were seen by himself or others raised up above the plain, a short time before the first eruption, so as to stand on the summit or slope of a newly-raised hillock, we might have been compelled, by so circumstantial a narrative, to adopt M. Dufrénoy's interpretation.

But in the absence of such evidence, we must appeal to the crater itself, where we behold a section of the whole mountain, without being able to detect any original nucleus of upheaved rock distinct from the rest: on the contrary, the whole mass is similar throughout in composition, and the cone very symmetrical in form; nor are there any clefts, such as might be looked for, as the effect of the sudden upthrow of stony masses. M. C. Prevost has well remarked that if beds of solid and non-elastic materials had yielded to a violent pressure directed from below upwards, we should find not simply a deep empty cavity, but an irregular opening, where many rents converged; and these rents would be now seen breaking through the walls of the crater, widening as they approach the centre. (See fig. 44. *a*, *b*.)[*] Not a single fissure of this kind is observable in the interior of Monte Nuovo, where the walls of the crater are continuous and entire; nor are there any dikes implying that rents had existed, which were afterwards filled with lava or other matter.

Fig. 44.



It has moreover been often urged by Von Buch, De Beaumont, and others, who ascribe the conical form of volcanos chiefly to upheaval from below, that in such mountains there are a great number of deep rents and ravines, which diverge on all sides like the spokes of a wheel, from near the central axis to the circumference or base of the cone, as in the case of Palma, Cantal, and Teneriffe. Yet the entire absence of such divergent fissures or ravines, in such cases as Monte Nuovo, Somma, or Etna, is passed by unnoticed, and appears to have raised in their minds no objection to their favourite theory.

It is, indeed, admitted by M. Dufrénoy that there are some facts which it is very difficult to reconcile with his own view of Porzio's record. Thus, for example, there are certain Roman monuments at the base of Monte Nuovo, and on the borders of Lake Avernus, such as the temples of Apollo (before mentioned) and Pluto, which do not seem to have suffered in the least degree by the supposed upheaval. "The walls which still exist have preserved their vertical position, and the vaults are in the same state as other monuments on the shores of the Bay of Baiæ. The long gallery which led to the Sibyl's Cave, on the other side of Lake Avernus, has in like manner escaped injury, the roof of the gallery remaining perfectly horizontal, the only change being that the soil of the chamber in which the Sibyl gave out her oracles is now covered by a few inches of water, which merely indicates a slight alteration in the level of Lake Avernus."* On the supposition, then, that pre-existing beds of pumiceous tuff were upraised in 1538, so as to form Monte Nuovo, it is acknowledged that the perfectly undisturbed state of the contiguous soil on which these ancient monuments stand, is very different from what might have been expected.

---

[*] Mém. de la Soc. Géol. de France, tom. ii. p. 91.

Mr. Darwin, in his "Volcanic Islands," has described several crateriform hills in the Galapagos Archipelago as composed of tuff which has evidently flowed like mud, and yet on consolidating has preserved an inclination of twenty and even thirty degrees. The tuff does not fall in continuous sheets round the hills as would have happened if they had been formed by the upheaval of horizontal layers. The author describes the composition of the tuff as very similar to that of Monte Nuovo, and the high angles at which the beds slope, both those which have flowed and those which have fallen in the form of ashes, entirely removes the difficulty supposed by M. Dufrénoy to exist in regard to the slope of Monte Nuovo, where it exceeds an angle of 18° to 20°.† Mr. Dana, also, in his account of the Sandwich Islands‡, shows that in the "cinder cones" of that region, the strata have an original inclination of between 35° and 40°, while in the "tufa cones" formed near the sea, the beds slope at about an angle of 30°. The same naturalist also observed in the Samoan or Navigator Islands in Polynesia, that fragments of fresh coral had been thrown up together with volcanic matter to the height of 200 feet above the level of the sea in cones of tufa.§

I shall again revert to the doctrine of the origin of volcanic cones by upheaval, when speaking of Vesuvius, Etna, and Santorin, and shall now merely add, that, in 1538, the whole coast, from Monte Nuovo to beyond Puzzuoli, was upraised to the height of many feet above the bed of the Mediterranean, and has since retained the greater part of the elevation then acquired. The proofs of these remarkable changes of level will be considered at length when the phenomena of the temple of Serapis are described.‖

Volcanos of the Phlegræan Fields.—Immediately adjoining Monte Nuovo is the larger volcanic cone of Monte Barbaro (2, fig. 43. p. 367.), the "Gaurus inanis" of Juvenal—an appellation given to it probably from its deep circular crater, which is about a mile in diameter. Large as is this cone, it was probably produced by a single eruption; and it does not, perhaps, exceed in magnitude some of the largest of those formed in Ischia, within the historical era. It is composed chiefly of indurated tufa like Monte Nuovo, stratified conformably to its conical surface. This hill was once very celebrated for its vines, and is still covered with vineyards; but when the vine is not n leaf it has a sterile appearance, and, late in the year, when seen from the beautiful Bay of Baiæ, it often contrasts so strongly in verdure with Monte Nuovo, which is always clothed with arbutus, myrtle, and other wild evergreens, that a stranger might well magine the cone of older date to be that thrown up in the sixteenth century.*

---

* Dufrénoy, Mem. pour servir, &c. p. 277.

† Darwin's Volcanic Islands, 106. note.

‡ Geology of the American Exploring Expedition, in 1838—1842, p. 354.

§ Ibid. p. 328.

‖ See chap. 29.

There is nothing, indeed, so calculated to instruct the geologist as the striking manner in which the recent volcanic hills of Ischia, and that now under consideration, blend with the surrounding landscape. Nothing seems wanting or redundant; every part of the picture is n such perfect harmony with the rest, that the whole has the appearance of having been called into existence by a single effort of creative power. Yet what other result could we have anticipated f nature has ever been governed by the same laws? Each new mountain thrown up — each new tract of land raised or depressed by earthquakes — should be in perfect accordance with those previously formed, if the entire configuration of the surface has been due to a ong series of similar disturbances. Were it true that the greater part of the dry land originated simultaneously in its present state, at some era of paroxysmal convulsion, and that additions were afterwards made slowly and successively during a period of comparative repose; then, indeed, there might be reason to expect a strong line of demarcation between the signs of the ancient and modern changes. But the very continuity of the plan, and the perfect identity of the causes, are to many a source of deception; since by producing a unity of effect, they lead them to exaggerate the energy of the agents which operated in the earlier ages. In the absence of all historical informaion, they are as unable to separate the dates of the origin of different portions of our continents, as the stranger is to determine, by their physical features alone, the distinct ages of Monte Nuovo, Monte Barbaro, Astroni, and the Solfatara.

The vast scale and violence of the volcanic operations in Campania, n the olden time, has been a theme of declamation, and has been contrasted with the comparative state of quiescence of this delightful region in the modern era. Instead of inferring, from analogy, that the ancient Vesuvius was always at rest when the craters of the Phlegræan Fields were burning — that each cone rose in succession, — and that many years, and often centuries, of repose intervened between different eruptions, — geologists seem to have generally conjectured that the whole group sprung up from the ground at once, like the soldiers of Cadmus when he sowed the dragon's teeth. As well might they endeavour to persuade us that on these Phlegræan Fields, as the poets feigned, the giants warred with Jove, ere yet the puny race of mortals were in being.

---

* Hamilton (writing in 1770) says, 'the new mountain produces as yet but a very slender vegetation." — Campi Phlegræi, p. 69. This remark was no longer applicable when I saw it, in 1828.

Modern eruptions of Vesuvius.—For nearly a century after the birth of Monte Nuovo, Vesuvius continued in a state of tranquillity. There had then been no violent eruption for 492 years; and it appears that the crater was then exactly in the condition of the present extinct volcano of Astroni, near Naples. Bracini, who visited Vesuvius not long before the eruption of 1631, gives the following interesting description of the interior:—"The crater was five miles in circumference, and about a thousand paces deep: its sides were covered with brushwood, and at the bottom there was a plain on which cattle grazed. In the woody parts wild boars frequently harboured. In one part of the plain, covered with ashes, were three small pools, one filled with hot and bitter water, another salter than the sea, and a third hot, but tasteless."* But at length these forests and grassy plains were consumed, being suddenly blown into the air, and their ashes scattered to the winds. In December, 1631, seven streams of lava poured at once from the crater, and overflowed several villages, on the flanks and at the foot of the mountain. Resina, partly built over the ancient site of Herculaneum, was consumed by the fiery torrent. Great floods of mud were as destructive as the lava itself,—no uncommon occurrence during these catastrophes; for such is the violence of rains produced by the evolutions of aqueous vapour, that torrents of water descend the cone, and becoming charged with impalpable volcanic dust, and rolling along loose ashes, acquire sufficient consistency to deserve their ordinary appellation of "aqueous lavas."

A brief period of repose ensued, which lasted only until the year 1666, from which time to the present there has been a constant series of eruptions, with rarely an interval of rest exceeding ten years. During these three centuries, no irregular volcanic agency has convulsed other points in this district. Brieslak remarked, that such irregular convulsions had occurred in the Bay of Naples in every second century; as, for example, the eruption of the Solfatara, in the twelfth; of the lava of Arso, in Ischia, in the fourteenth; and of Monte Nuovo in the sixteenth: but the eighteenth has formed an exception to this rule, and this seems accounted for by the unprecedented number of eruptions of Vesuvius during that period; whereas, when the new vents opened, there had always been, as we have seen, a long intermittence of activity in the principal volcano.

---

* Hamilton's Campi Phlegræi, folio, vol. i. p. 62.; and Brieslak, Campania, tome i. p. 186.

CHAPTER XXIV.

VOLCANIC DISTRICT OF NAPLES—*continued.*

ıs and structure of the cone of Vesuvius — Fluidity and motion of lava — -Alluviums called "aqueous lavas" — Origin and composition of the enveloping Herculaneum and Pompeii — Condition and contents of the cities — Small number of skeletons — State of preservation of animal and ıle substances — Rolls of papyrus — Stabiæ — Torre del Greco — Concluding s on the Campanian volcanos.

re of the cone of Vesuvius.—Between the end of the ıth century and the year 1822, the great crater of Vesuvius ːn gradually filled by lava boiling up from below, and by alling from the explosions of minor mouths which were formed vals on its bottom and sides. In place of a regular cavity, e, there was a rough and rocky plain, covered with blocks of l scoriæ, and cut by numerous fissures, from which clouds of were evolved. But this state of things was totally changed eruption of October, 1822, when violent explosions, during e of more than twenty days, broke up and threw out all this ated mass, so as to leave an immense gulf or chasm, of an r, but somewhat elliptical shape, about three miles in circum-when measured along the very sinuous and irregular line of ːme margin, but somewhat less than three quarters of a mile ngest diameter, which was directed from N.E. to S.W.[*] The f this tremendous abyss has been variously estimated; for ː hour of its formation it increased daily by the dilapidation les. It measured, at first, according to the account of some two thousand feet in depth from the extreme part of the summit[†]; but Mr. Scrope, when he saw it, soon after the , estimated its depth at less than half that amount. More ;ht hundred feet of the cone was carried away by the ex-, so that the mountain was reduced in height from about 4200 feet.[‡]

ː ascend the sloping sides, the volcano appears a mass of loose s—a mere heap of rubbish, thrown together without the order; but on arriving at the brim of the crater, and g a view of the interior, we are agreeably surprised to dis-at the conformation of the whole displays in every part the ·fect symmetry and arrangement. The materials are disposed ar strata, slightly undulating, appearing, when viewed in

---

unt of the Eruption of Ve-ı October, 1822, by G. P. sq., Journ. of Sci. &c. vol. xv.

[†] Mr. Forbes, Account of Mount Vesuvius, Edin. Journ. of Sci. No. xviii. p. 195. Oct. 1828.

[‡] Ibid. p. 194.

front, to be disposed in horizontal planes. But, as we make the circuit of the edge of the crater, and observe the cliffs by which it is encircled projecting or receding in salient or retiring angles, we behold transverse sections of the currents of lava and beds of sand and scoriæ, and recognise their true dip. We then discover that they incline outwards from the axis of the cone, at angles varying from 30° to 40°. The whole cone, in fact, is composed of a number of concentric coatings of alternating lavas, sand, and scoriæ. Every shower of ashes which has fallen from above, and every stream of lava descending from the lips of the crater, have conformed to the outward surface of the hill, so that one conical envelope may be said to have been successively folded round another, until the aggregation of the whole mountain was completed. The marked separation into distinct beds results from the different colours and degrees of coarseness in the sands, scoriæ, and lava, and the alternation of these with each other. The greatest difficulty, on the first view, is to conceive how so much regularity can be produced, notwithstanding the unequal distribution of sand and scoriæ, driven by prevailing winds in particular eruptions, and the small breadth of each sheet of lava as it first flows out from the crater.

But, on a closer examination, we find that the appearance of extreme uniformity is delusive; for when a number of beds thin out gradually, and at different points, the eye does not without difficulty recognize the termination of any one stratum, but usually supposes it continuous with some other, which at a short distance may lie precisely in the same plane. The slight undulations, moreover, produced by inequalities on the sides of the hill on which the successive layers were moulded, assist the deception. As countless beds of sand and scoriæ constitute the greater part of the whole mass, these may sometimes mantle continuously round the whole cone; and even lava streams may be of considerable breadth when first they overflow, and since, in some eruptions, a considerable part of the upper portion of the cone breaks down at once, may form a sheet extending as far as the space which the eye usually takes in, in a single section.

The high inclination of some of the beds, and the firm union of the particles even where there is evidently no cement, is another striking feature in the volcanic tuffs and breccias, which seems at first not very easy of explanation. But the last great eruption afforded ample illustration of the manner in which these strata are formed. Fragments of lava, scoriæ, pumice, and sand, when they fall at slight distances from the summit, are only half cooled down from a state of fusion, and are afterwards acted upon by the heat from within, and by fumeroles or small crevices in the cone through which hot vapours are disengaged. Thus heated, the ejected fragments cohere together strongly; and the whole mass acquires such consistency in a few days, that fragments cannot be detached without a smart blow of the hammer. At the same time sand and scoriæ, ejected to a greater distance, remain incoherent.*

---

* Monticelli and Covelli, Storia di Fenom. del Vesuv. en 1821–23.

Sir William Hamilton, in his description of the eruption of 1779, says, that jets of liquid lava, mixed with stones and scoriæ, were thrown up to the height of at least ten thousand feet, having the appearance of a column of fire.[*] Some of these were directed by the winds towards Ottajano, and some of them, falling almost perpendicularly, still red hot and liquid, on Vesuvius, covered its whole cone, part of the mountain of Somma, and the valley between them. The falling matter being nearly as vividly inflamed as that which was continually issuing fresh from the crater, formed with it one complete body of fire, which could not be less than two miles and a half in breadth, and of the extraordinary height above mentioned, casting a heat to the distance of at least six miles round it. Dr. Clarke, also, in his account of the eruption of 1793, says that millions of red-hot stones were shot into the air full half the height of the cone itself, and then bending, fell all round in a fine arch. On another occasion he says that, as they fell, they covered nearly half the cone with fire.

The same author has also described the different appearance of the lava at its source, and at some distance from it, when it had descended into the plains below. At the point where it issued, in 1793, from an arched chasm in the side of the mountain, the vivid torrent rushed with the velocity of a flood. It was in perfect fusion, unattended with any scoriæ on its surface, or any gross materials not in a state of complete solution. It flowed with the translucency of honey, "in regular channels, cut finer than art can imitate, and glowing with all the splendour of the sun." — "Sir William Hamilton," he continues, "had conceived that no stones thrown upon a current of lava would make any impression. I was soon convinced of the contrary. Light bodies, indeed, of five, ten, and fifteen pounds' weight, made little or no impression even at the source; but bodies of sixty, seventy, and eighty pounds were seen to form a kind of bed on the surface of the lava, and float away with it. A stone of three hundred weight, that had been thrown out by the crater, lay near the source of the current of lava: I raised it upon one end, and then let it fall in upon the liquid lava; when it gradually sunk beneath the surface, and disappeared. If I wished to describe the manner in which it acted upon the lava, I should say that it was like a loaf of bread thrown into a bowl of very thick honey, which gradually involves itself in the heavy liquid, and then slowly sinks to the bottom.

"The lava, at a small distance from its source, acquires a darker tint upon its surface, is less easily acted upon, and, as the stream widens, the surface, having lost its state of perfect solution, grows harder and harder, and cracks into innumerable fragments of very porous matter, to which they give the name of scoriæ, and the appearance of which has led many to suppose that it proceeded thus from the mountain. There is, however, no truth in this. All lava, at its first exit from its native volcano, flows out in a liquid state, and all equally in fusion. The appearance of the scoriæ is to be attributed only to the action of the external air, and not to any difference in the materials which compose it, since any lava whatever, separated from its channel, and exposed to the action of the external air, immediately cracks, becomes porous, and alters its form. As we proceeded downward, this became more and more evident; and the same lava which at its original source flowed in perfect solution, undivided, and free from incumbrances of any kind, a little farther down had its surface loaded with the scoriæ in such a manner, that, upon its arrival at the bottom of the mountain, the whole current resembled nothing so much as a heap of unconnected cinders from an iron-foundry." In another place he says, that "the rivers of lava in the plain resembled a vast heap of cinders, or the scoriæ of an iron-foundry, rolling slowly along, and falling with a rattling noise over one another."* Von Buch, who was in company with MM. de Humboldt and Gay-Lussac, describes the lava of 1805 (the most fluid on record) as shooting suddenly before their eyes from top to bottom of the cone in one single instant. Professor J. D. Forbes remarks that the length of the slope of the cone proper being about 1800 feet, this motion must correspond to a velocity of many hundred feet in a few seconds, without interpreting Von Buch's expression literally. The same lava, when it reached the level road at Torre del Greco, moved at the rate of only eighteen inches per minute, or three tenths of an inch per second.† "Although common lava," observes Professor Forbes, "is nearly as liquid as melted iron, when it issues from the orifice of the crater, its fluidity rapidly diminishes, and as it becomes more and more burdened by the consolidated slag through which it has to force its way, its velocity of motion diminishes in an almost inconceivable degree; and at length, when it ceases to present the slightest external trace of fluidity, its movement can only be ascertained by careful and repeated observations, just as in the case of a glacier."‡

---

[*] Campi Phlegræi.

It appears that the intensity of the light and heat of the lava varies considerably at different periods of the same eruption, as in that of Vesuvius in 1819 and 1820, when Sir H. Davy remarked different degrees of vividness in the white heat at the point where the lava originated.§

When the expressions "flame" and "smoke" are used in describing volcanic appearances, they must generally be understood in a figurative sense. We are informed, indeed, by M. Abich, that he distinctly saw, in the eruption of Vesuvius in 1834, the flame of burning hydrogen‖; but what is usually mistaken for flame consists of vapour or scoriæ, and impalpable dust illuminated by that vivid light which is emitted from the crater below, where the lava is said to glow with the splendour of the sun. The clouds of apparent smoke are formed either of aqueous and other vapour, or of finely comminuted scoriæ.

---

* Otter's Life of Dr. Clarke.

† Phil. Trans. 1846, p. 154.

‡ Ibid. p. 148.

§ Ibid. p. 241.

‖ Bulletin de la Soc. Géol. de France, tom. vii. p. 43.; and Illustrations of Vesuvius and Etna, p. 3.

Dikes in the recent cone, how formed.—The inclined strata before mentioned which dip outwards in all directions from the axis of the cone of Vesuvius, are intersected by veins or dikes of compact lava, for the most part in a vertical position. In 1828 these were seen to be about seven in number, some of them not less than four or five hundred feet in height, and thinning out before they reached the uppermost part of the cone. Being harder than the beds through which they pass, they have decomposed less rapidly, and therefore stand out in relief. When I visited Vesuvius, in November 1828, I was prevented from descending into the crater by the constant ejections then thrown out; so that I got sight of three only of the dikes; but Signor Monticelli had previously had drawings made of the whole, which he showed me. The dikes which I saw were on that side of the cone which is encircled by Somma. The eruption before mentioned, of 1828, began in March, and in the November following the ejected matter had filled up nearly one-third of the deep abyss formed at the close of the eruption in 1822. In November I found a single black cone at the bottom of the crater continually throwing out scoriæ, while on the exterior of the cone I observed the lava of 1822, which had flowed out six years before, not yet cool, and still evolving much heat and vapour from crevices.

Hoffmann, in 1832, saw on the north side of Vesuvius, near the peak called Palo, a great many parallel bands of lava, some from six to eight feet thick, alternating with scoriæ and conglomerate. These beds, he says, were cut through by many dikes, some of them five feet broad. They resemble those of Somma, the stone being composed of grains of leucite and augite.[*]

There can be no doubt that the dikes above mentioned have been produced by the filling up of open fissures with liquid lava; but of the date of their formation we know nothing farther than that they are all subsequent to the year 79, and, relatively speaking, that they are more modern than all the lavas and scoriæ which they intersect. A considerable number of the upper strata are not traversed by them. That the earthquakes, which almost invariably precede eruptions, occasion rents in the mass, is well known; and, in 1822, three months before the lava flowed out, open fissures, evolving hot vapours, were numerous. It is clear that such rents must be ejected with melted matter when the column of lava rises, so that the origin of the dikes is easily explained, as also the great solidity and crystalline nature of the rock composing them, which has been formed by lava cooling slowly under great pressure.

It has been suggested that the frequent rending of volcanic cones during eruptions may be connected with the gradual and successive upheaval of the whole mass in such a manner as to increase the inclination of the beds composing the cone; and in accordance with the hypothesis before proposed for the origin of Monte Nuovo, Von Buch supposes that the present cone of Vesuvius was formed in the year 79, not by eruption, but by upheaval. It was not produced by the repeated superposition of scoriæ and lava cast out or flowing from a central source, but by the uplifting of strata previously horizontal. The entire cone rose at once, such as we now see it, from the interior and middle of Somma, and has since received no accession of height, but, on the contrary, has ever since been diminishing in elevation.*

---

[*] Geognost. Beobachtungen, &c. p. 182. Berlin, 1839.

Although I consider this hypothesis of Von Buch to be quite untenable, I may mention some facts which may at first sight seem to favour it. These are recorded by M. Abich in his account of the Vesuvian eruptions of 1833 and 1834, a work illustrated by excellent engravings of the volcanic phenomena which he witnessed.† It appears that, in the year 1834, the great crater of Vesuvius had been filled up nearly to the top with lava, which had consolidated and formed a level and unbroken plain, except that a small cone thrown up by the ejection of scoriæ rose in the middle of it like an island in a lake. At length this plain of lava was broken by a fissure which passed from N. E. to S. W., and along this line a great number of minute cones emitting vapour were formed. The first act of formation of these minor cones is said to have consisted of a partial upheaval of beds of lava previously horizontal, and which had been rendered flexible by the heat and tension of elastic fluids, which, rising from below, escaped from the centre of each new monticule. There would be considerable analogy between this mode of origin and that ascribed by Von Buch to Vesuvius and Somma, if the dimensions of the upraised masses were not on so different a scale, and if it was safe to reason from the inflation of bladders of half-fused lava, from fifteen to twenty-five feet in height, to mountains attaining an altitude of several thousand feet, and having their component strata strengthened by intersecting dikes of solid lava.

At the same time M. Abich mentions, that when, in August 1834, a great subsidence took place in the platform of lava within the great crater, so that the structure of the central cone was laid open, it was seen to have been evidently formed, *not by upheaval*, but by the fall of cinders and scoriæ which had been thrown out during successive eruptions.‡

Previous to the year 79, Vesuvius appears, from the description of its figure given by Strabo, to have been a truncated cone, having a level and even outline as seen from a distance. That it had a crater on its summit, we may infer from a passage in Plutarch, on which Dr. Daubeny has judiciously commented in his treatise on volcanos.§ The walls of the crater were evidently entire, except on one side, where there was a single narrow breach. When Spartacus, in the year 72, encamped his gladiators in this hollow, Clodius, the prætor, besieged him there, keeping the single outlet carefully guarded, and then let down his soldiers by scaling ladders over the steep precipices which surrounded the crater, at the bottom of which the insurgents were encamped. On the side towards the sea, the walls of this original cavity, which must have been three miles in diameter, have been destroyed, and Breislak was the first to announce the opinion that this destruction happened during the tremendous eruption which occurred in 79, when the new cone, now called Vesuvius, was thrown up, which stands encircled on three sides by the ruins of the ancient cone, called Monte Somma.

---

* Von Buch, Descrip. Phys. des Iles Canaries, p. 342. Paris, 1836.

† Vues Illust. de Phénom. Géol. Observ. sur le Vésuve et l'Etna. Berlin, 1837.

‡ Ibid. p. 2.

§ 2d edit. 1848, p. 216.

In the annexed diagram (fig. 45.) it will be seen that on the side of Vesuvius opposite to that where a portion of the ancient cone of Somma (*a*) still remains, is a projection (*b*) called the Pedamentina, which some have supposed to be part of the circumference of the ancient crater broken down towards the sea, and over the edge of which the lavas of the modern Vesuvius have poured; the axis of the present cone of Vesuvius being, according to Visconti, precisely equidistant from the escarpment of Somma and the Pedamentina.

Fig. 45.



Supposed section of Vesuvius and Somma.

a, Monte Somma, or the remains of the ancient cone of Vesuvius.
b, The Pedamentina, a terrace-like projection, encircling the base of the recent cone of Vesuvius, on the south side.
c, Atrio del Cavallo.*
d, *e*, Crater left by eruption of 1822.
f, Small cone thrown up in 1828, at the bottom of the great crater.
g, *g*, Dikes intersecting Somma.
h, *h*, Dikes intersecting the recent cone of Vesuvius.

In the same diagram I have represented the slanting beds of the cone of Vesuvius as becoming horizontal in the Atrio del Cavallo (at *c*), where the base of the new cone meets the precipitous escarpment of Somma; for when the lava flows down to this point, as happened in 1822, its descending course is arrested, and it then runs in another direction along this small valley, circling round the base of the cone. Sand and scoriæ, also, blown by the winds, collect at the base of the cone, and are then swept away by torrents; so that there is always here a flattish plain, as represented. In the same manner, the small interior cone (*f*) must be composed of sloping beds, terminating in a horizontal plain; for, while this monticule was gradually gaining height by successive ejections of lava and scoriæ, in 1828, it was always surrounded by a flat pool of semi-fluid lava, into which scoriæ and sand were thrown.

---

* So called from travellers leaving their horses and mules there when they prepare to ascend the cone on foot.

In the steep semicircular escarpment of Somma, which faces the modern Vesuvius, we see a great number of sheets of lava inclined at an angle of about 26°. They alternate with scoriæ, and are intersected by numerous dikes, which, like the sheets of lava, are composed chiefly of augite, with crystals of leucite, but the rock in the dikes is more compact, having cooled and consolidated under greater pressure. Some of the dikes cut through and shift others, so that they have evidently been formed during successive eruptions. While the higher region of Somma is made up of these igneous products, there appear on its flanks, for some depth from the surface, as seen in a ravine, called the "Fossa Grande," beds of white pumiceous tuff, resembling the tuff which, at Pausilippo, and other places, near Naples, contains shells of living Mediterranean species. It is supposed by Pilla, Von Buch, and others, that the tufaceous beds, which rise in Somma to more than half the height of that mountain, are, in like manner, of submarine origin, because a few sea-shells have been found in them, here and there, together with serpulæ of recent species attached to included blocks of limestone.*

It is contended, therefore, that as these strata were once accumulated beneath the sea, they may have been subjected as they rose to such an upward movement as may have given rise to a conical hill; and this hypothesis, it is said, acquires confirmation from the fact, that the sheets of lava near the summit of Somma, are so compact and crystalline, and of such breadth individually, as would not have been the case had they run down a steep slope. They must, therefore, have consolidated on a nearly level surface, and have been subsequently uplifted into their present inclined position.

Unfortunately there are no sections of sufficient depth and continuity on the flanks of Somma, to reveal to us clearly the relations of the lava, scoriæ, and associated dikes, forming the highest part of the mountain, with the marine tuffs observed on its declivity. Both may, perhaps, have been produced contemporaneously when Somma raised its head, like Stromboli, above the sea, its sides and base being then submerged. Such a state of things may be indicated by a fact noticed by Von Buch, namely, that the pumiceous beds of Naples, when they approach Somma, contain fragments of the peculiar leucitic lava proper to that mountain, which are not found in the same tuff at a greater distance.† Portions, therefore, of this lava were either thrown out by explosions, or torn off by the waves, during the deposition of the pumiceous strata beneath the sea.

We have as yet but a scanty acquaintance with the laws which regulate the flow of lava beneath water, or the arrangement of scoriæ and volcanic dust on the sides of a submarine cone. There can, however, be little doubt that showers of ejected matter may settle on a steep slope, and may include shells and the remains of aquatic animals, which flourish in the intervals between eruptions. Lava under the pressure of water would be less porous; but, as Dr. Daubeny suggests, it may retain its fluidity longer than in the open air; for the rapidity with which heated bodies are cooled by being plunged into water arises chiefly from the conversion of the lower portions of water into steam, which steam absorbing much heat, immediately ascends, and is reconverted into water. But under the pressure of a deep ocean, the heat of the lava would be carried off more slowly, and only by the circulation of ascending and descending currents of water, those portions nearest the source of heat becoming specifically light, and consequently displacing the water above. This kind of circulation would take place with much less rapidity than in the atmosphere, inasmuch as the expansion of water by equal increments of heat is less considerable than that of air.*

---

* Dufrénoy, Mém. pour servir à une Descrip. Géol. de la France, tom. iv. p. 294.

† Descrip. Phys. des Iles Canaries, p. 344.

We learn from the valuable observations made by Mr. Dana on the active volcanos of the Sandwich Islands, that large sheets of compact basaltic lava have been poured out of craters at the top or near the summits of flattened domes higher than Etna, as in the case of Mount Loa for example, where a copious stream two miles broad and twenty-five miles long proceeded from an opening 13,000 feet above the level of the sea. The usual slope of these sheets of lava is between 5° and 10°; but Mr. Dana convinced himself that, owing to the suddenness with which they cool in the air, some lavas may occasionally form on slopes equalling 25°, and still preserve a considerable compactness of texture. It is even proved, he says, from what he saw in the great lateral crater of Kilauea, on the flanks of Mount Loa, that a mass of such melted rock may consolidate at an inclination of 30°, and be continuous for 300 or 400 feet. Such masses are narrow, he admits, "but if the source had been more generous, they would have had a greater breadth, and by a succession of ejections overspreading each cooled layer, a considerable thickness might have been attained."† The same author has also shown, as before mentioned, that in the "cinder cones" of the Sandwich Islands, the strata have an original inclination of between 35° and 40°.‡

Mr. Scrope, writing in 1827, attributed the formation of a volcanic cone chiefly to matter ejected from a central orifice, but partly to the injection of lava into dikes, and "to that force of gaseous expansion, the intensity of which, in the central parts of the cone, is attested by local earthquakes, which so often accompany eruptions."§ It is the opinion of MM. Von Buch, De Beaumont, and Dufrénoy, that the sheets of lava on Somma are so uniform and compact, that their original inclination did not exceed four or five degrees, and that four-fifths, therefore, of their present slope is due to their having been subsequently tilted and upraised. Notwithstanding the light thrown by M. de Beaumont on the laws regulating the flow and consolidation of lava, I do not conceive that these laws are as yet sufficiently determined to warrant us in assigning so much of the inclined position of the beds of Somma to the subsequent rending and dislocation of the cone. Even if this were admitted, it is far more in harmony with the usual mode of development of volcanic forces to suppose the movement which modified the shape of the cone to have been intermittent and gradual, and not to have consisted of a single effort, or one sudden and violent convulsion.*

---

* See Daubeny's Volcanos, p. 400.

† Geol. of American Explor. Exped. p. 359. note. Mr. Dana informed me (Sept. 1852), that an angle of 60° instead of 30°, was given by mistake in his work.

‡ Ibid. p. 354.

§ Geol. Trans. 2nd series, vol. ii. p. 341.

Vesuvian lavas.—The lavas of Somma are characterized by containing disseminated crystals of leucite (called, by the French, amphigène), a mineral said to be very rare in the modern lavas of Vesuvius, which are in general much more scoriaceous and less crystalline than those of Somma.†

At the fortress near Torre del Greco a section is exposed, fifteen feet in height, of a current which ran into the sea; and it evinces especially in the lower part, a decided tendency to divide into rude columns. A still more striking example may be seen to the west of Torre del Annunziata, near Forte Scassato, where the mass is laid open to the depth of twenty feet. In both these cases, however, the rock may rather be said to be divided into numerous perpendicular fissures, than to be prismatic, although the same picturesque effect is produced. In the lava-currents of Central France (those of the Vivarais, in particular), the uppermost portion, often forty feet or, more in thickness, is an amorphous mass passing downwards into lava irregularly prismatic; and under this there is a foundation of regular and vertical columns; but these lavas are often one hundred feet or more in thickness. We can scarcely expect to discover the same phenomenon in the shallow currents of Vesuvius, where the lowest part has cooled more rapidly, although it may be looked for in modern streams in Iceland, which exceed even those of ancient France in volume.

Mr. Scrope mentions that, in the cliffs encircling the modern crater of Vesuvius, he saw many currents offering a columnar division, and some almost as regularly prismatic as any ranges of the older basalts; and he adds, that in some the spheroidal concretionary structure, on a large scale, was equally conspicuous.‡ Brieslak§ also informs us that, in the siliceous lava of 1737, which contains augite, leucite, and crystals of felspar, he found very regular prisms in a quarry near Torre del Greco; an observation confirmed by modern authorities.‖

Effects of decomposition on lavas.—The decomposition of some of the felspathic lavas, either by simple weathering, or by gaseous emanations, converts them from a hard to a soft clayey state, so that they longer retain the smallest resemblance to rocks cooled down from ıtate of fusion. The exhalations of sulphuretted hydrogen and ıriatic acid, which are disengaged continually from the Solfatara, o produce curious changes on the trachyte of that nearly extinct lcano: the rock is bleached, and becomes porous, fissile, and honeynbed, till at length it crumbles into a white siliceous powder.* ımerous globular concretions, composed of concentric laminæ, are o formed by the same vapours in this decomposed rock.†

---

* See a Paper by the Author on "Craters of Denudation," Quart. Journ. Geol. Soc. 1850.

† Dufrénoy, Mém. pour servir, &c. tom. iv. p. 285.

‡ Journal of Science, vol. xv. p. 177.

§ Voy. dans la Campanie, tome i. p. 201.

‖ Mr. Forbes, Edin. Journ. of Sci. No. xviii. Oct. 1828.

Vesuvian minerals.—A great variety of minerals are found in ı lavas of Vesuvius and Somma; augite, leucite, felspar, mica, vine, and sulphur are most abundant. It is an extraordinary fact, ıt, in an area of three square miles round Vesuvius, a greater mber of simple minerals have been found than in any spot of the ne dimensions on the surface of the globe. Häuy enumerated ly 380 species of simple minerals as known to him; and no less ın eighty-two had been found on Vesuvius and in the tuffs on the aks of Somma before the end of the year 1828.‡ Many of these ı peculiar to that locality. Some mineralogists have conjectured ıt the greater part of these were not of Vesuvian origin, but ·own up in fragments from some older formation, through which ı gaseous explosions burst. But none of the older rocks in Italy, elsewhere, contain such an assemblage of mineral products; and ı hypothesis seems to have been prompted by a disinclination to nit that, in times so recent in the earth's history, the laboratory of ture could have been so prolific in the creation of new and rare npounds. Had Vesuvius been a volcano of high antiquity, formed en nature

> Wanton'd as in her prime, and play'd at will
> Her virgin fancies,

vould have been readily admitted that these, or a much greater ·iety of substances, had been sublimed in the crevices of lava, just several new earthy and metallic compounds are known to have n produced by fumeroles, since the eruption of 1822.

Mass enveloping Herculaneum and Pompeii.—In addition to the ctions which fall on the cone, and that much greater mass which ls its way gradually to the neighbouring sea, there is a third ·tion, often of no inconsiderable thickness, composed of alluviums, ead over the valleys and plains at small distances from the volo. Aqueous vapours are evolved copiously from volcanic craters ·ing eruptions, and often for a long time subsequently to the charge of scoriæ and lava: these vapours are condensed in the l atmosphere surrounding the high volcanic peak, and heavy rains thus caused. The floods thus occasioned, sweep along the impable dust and light scoriæ, till a current of mud is produced, ich is called in Campania "lava d' acqua," and is often more

---

Daubeny on Volcanos, p. 169.

Scrope, Geol. Trans. second series, ii. p. 346.

‡ Monticelli and Covelli, Prodrom. della Mineral. Vesuv.

dreaded than an igneous stream (lava di fuoco), from the greater velocity with which it moves. So late as the 27th of October, 1822, one of these alluviums descended the cone of Vesuvius, and, after overspreading much cultivated soil, flowed suddenly into the villages of St. Sebastian and Massa, where, filling the streets and interior of some of the houses, it suffocated seven persons. It will, therefore, happen very frequently that, towards the base of a volcanic cone, alternations will be found of lava, alluvium, and showers of ashes.

To which of these two latter divisions the mass enveloping Herculaneum and Pompeii should be referred, has been a question of the keenest controversy; but the discussion might have been shortened, if the combatants had reflected that, whether volcanic sand and ashes were conveyed to the towns by running water, or through the air, during an eruption, the interior of buildings, so long as the roofs remain entire, together with all underground vaults and cellars, could be filled only by an *alluvium*. We learn from history, that a heavy shower of sand, pumice, and lapilli, sufficiently great to render Pompeii and Herculaneum uninhabitable, fell for eight successive days and nights in the year 79, accompanied by violent rains. We ought, therefore, to find a very close resemblance between the strata covering these towns and those composing the minor cones of the Phlegræan Fields, accumulated rapidly, like Monte Nuovo, during a continued shower of ejected matter; with this difference however, that the strata incumbent on the cities would be horizontal, whereas those on the cones are highly inclined; and that large angular fragments of rock, which are thrown out near the vent, would be wanting at a distance where small lapilli only can be found. Accordingly, with these exceptions, no identity can be more perfect than the form and distribution of the matter at the base of Monte Nuovo, as laid open by the encroaching sea, and the appearance of the beds superimposed on Pompeii. That city is covered with numerous alternations of different horizontal beds of tuff and lapilli, for the most part thin, and subdivided into very fine layers. I observed the following section near the amphitheatre, in November, 1828—(descending series):—

	Feet.	Inches.
1. Black sparkling sand from the eruption of 1822, containing minute regularly formed crystals of augite and tourmaline -	0	2½
2. Vegetable mould - - - - - - -	3	0
3. Brown incoherent tuff, full of *pisolitic globules* in layers, from half an inch to three inches in thickness - - -	1	6
4. Small scoriæ and white lapilli - - - -	0	3
5. Brown earthy tuff, with numerous pisolitic globules - -	0	9
6. Brown earthy tuff, with lapilli divided into layers - -	4	0
7. Layer of whitish lapilli - - - - -	0	1
8. Grey solid tuff - - - - - -	0	3
9. Pumice and white lapilli - - - - -	0	3
	10	3½

---

* The great eruption, in 1822, caused a covering only a few inches thick on Pompeii. Several feet are mentioned by Prof. J. D. Forbes.—Ed. Journ. of

Many of the ashes in these beds are vitrified, and harsh to the touch. Crystals of leucite, both fresh and farinaceous, have been found intermixed.[*] The depth of the bed of ashes above the houses is variable, but seldom exceeds twelve or fourteen feet, and it is said that the higher part of the amphitheatre always projected above the surface; though if this were the case, it seems inexplicable that the city should never have been discovered till the year 1750. It will be observed in the above section, that two of the brown, half-consolidated tuffs are filled with small pisolitic globules. This circumstance is not alluded to in the animated controversy which the Royal Academy of Naples maintained with one of their members, Signor Lippi, as to the origin of the strata incumbent on Pompeii. The mode of aggregation of these globules has been fully explained by Mr. Scrope, who saw them formed in great numbers in 1822, by rain falling during the eruption on fine volcanic sand, and sometimes also produced like hail in the air, by the mutual attraction of the minutest particles of fine damp sand. Their occurrence, therefore, agrees remarkably well with the account of heavy rain, and showers of sand and ashes, recorded in history.[†]

Lippi entitled his work, "Fù il fuoco o l'acqua che sotterò Pompei ed Ercolano?"[‡] and he contended that neither were the two cities destroyed in the year 79, nor by a volcanic eruption, but purely by the agency of water charged with transported matter. His letters, wherein he endeavoured to dispense, as far as possible, with igneous agency, even at the foot of the volcano, were dedicated, with great propriety, to Werner, and afford an amusing illustration of the polemic style in which geological writers of that day indulged themselves. His arguments were partly of an historical nature, derived from the silence of contemporary historians, respecting the fate of the cities, which, as we have already stated, is most remarkable, and partly drawn from physical proofs. He pointed out with great clearness the resemblance of the tufaceous matter in the vaults and cellars at Herculaneum and Pompeii to aqueous alluviums, and its distinctness from ejections which had fallen through the air. Nothing, he observes, but moist pasty matter could have received the impression of a woman's breast, which was found in a vault at Pompeii. or have given the cast of a statue discovered in the theatre at Herculaneum. It was objected to him, that the heat of the tuff in Herculaneum and Pompeii was proved by the carbonization of the timber, corn, papyrus-rolls, and other vegetable substances there discovered: but Lippi replied with truth, that the papyri would have been burnt up, if they had come in contact with fire, and that their

---

Science, No. xix. p. 131. Jan. 1829. But he must have measured in spots where it had drifted. The dust and ashes were five feet thick at the top of the crater, and decreased gradually to ten inches at Torre del Annunziata. The size and weight of the ejected fragments diminished very regularly in the same continuous stratum, as the distance from the centre of projection was greater.

[*] Forbes, ib. p. 130.

[†] Scrope, Geol. Trans., second series, vol. ii. p. 346.

[‡] Napoli, 1816.

being only carbonized was a clear demonstration of their having been enveloped, like fossil wood, in a sediment deposited from water. The Academicians, in their report on his pamphlet, assert, that when the amphitheatre was first cleared out, the matter was arranged on the steps in a succession of concave layers, accommodating themselves to the interior form of the building, just as snow would lie if it had fallen there. This observation is highly interesting, and points to the difference between the stratification of ashes in an open building and of mud derived from the same in the interior of edifices and cellars. Nor ought we to call the allegation in question, because it could not be substantiated at the time of the controversy after the matter had been all removed; although Lippi took advantage of this removal, and met the argument of his antagonists by requiring them to prove the fact. There is decisive evidence that no stream of lava has ever reached Pompeii since it was first built, although the foundations of the town stand upon the old leucitic lava of Somma; several streams of which, with tuff interposed, had been cut through in excavations.

Infusorial beds covering Pompeii.— A most singular and unexpected discovery has been recently made (1844–45) by Professor Ehrenberg, respecting the remote origin of many of the layers of ashes and pumice enveloping Pompeii. They are, he says, in great part, of organic and freshwater origin, consisting of the siliceous cases of microscopic infusoria. What is still more surprising, this fact proves to be by no means an isolated or solitary example of an intimate relation between organic life and the results of volcanic activity. On the Rhine, several beds of tuff and pumiceous conglomerate, resembling the mass incumbent upon Pompeii and closely connected with extinct volcanos, are now ascertained to be made up to a great extent of the siliceous cases of infusoria, (or Diatomaceæ) invisible to the naked eye and often half fused.* No less than 94 distinct species have already been detected in one mass of this kind, more than 150 feet thick, at Hochsimmer, on the left bank of the Rhine, near the Laacher-see. Some of these Rhenish infusorial accumulations appear to have fallen in showers, others to have been poured out of lake-craters in the form of mud, as in the Brohl valley.

In Mexico, Peru, the Isle of France, and several other volcanic regions, analogous phenomena have been observed, and everywhere the species of infusoria belong to freshwater and terrestrial genera, except in the case of the Patagonian pumiceous tuffs, specimens of which, brought home by Mr. Darwin, are found to contain the remains of marine animalcules. In various kinds of pumice ejected by volcanos, the microscope has revealed to Professsor Ehrenberg, the siliceous cases of infusoria often half obliterated by the action of heat.

---

* Not a few of the organic bodies, called by Ehrenberg "infusoria," such as Galionella and Bacillaria, have been recently claimed by many botanists as belonging to the vegetable kingdom, and are referred to the classes called Diatomaceæ and Desmidiæ.

and the fine dust thrown out into the air during eruptions, is sometimes referable to these most minute organic substances, brought up from considerable depths, and sometimes mingled with small particles of vegetable matter.

In what manner did the solid coverings of these most minute plants and animalcules, which can only originate and increase at the surface of the earth, sink down and penetrate into subterranean cavities, so as to be ejected from the volcanic orifices? We have of late years become familiar with the fact in the process of boring Artesian wells, that the seeds of plants, the remains of insects, and even small fish, with other organic bodies, are carried in an uninjured state by the underground circulation of waters, to the depth of many hundred feet. With still greater facility in a volcanic region we may conjecture, that water and mud full of invisible infusoria may be sucked down, from time to time, into subterranean rents and hollows in cavernous lava which has been permeated by gases, or in rocks dislocated by earthquakes. It often happens that a lake which has endured for centuries in a volcanic crater, disappears suddenly on the approach of a new eruption. Violent shocks agitate the surrounding region, and ponds, rivers, and wells are dried up. Large cavities far below may thus become filled with fen-mud chiefly composed of the more indestructible and siliceous portions of infusoria, destined perhaps to be one day ejected in a fragmentary or half-fused state, yet without the obliteration of all traces of organic structure.*

Herculaneum.—It was remarked that no lava has flowed over the site of Pompeii, since that city was built, but with Herculaneum the case is different. Although the substance which fills the interior of the houses and the vaults must have been introduced in a state of mud, like that found in similar situations in Pompeii; yet the superincumbent mass differs wholly in composition and thickness. Herculaneum was situated several miles nearer to the volcano, and has, therefore, been always more exposed to be covered, not only by showers of ashes, but by alluviums and streams of lava. Accordingly, masses of both have accumulated on each other above the city, to a depth of nowhere less than 70, and in many places of 112 feet.†

The tuff which envelopes the buildings consists of comminuted volcanic ashes, mixed with pumice. A mask embedded in this matrix has left a cast, the sharpness of which was compared by Hamilton to those in plaster of Paris; nor was the mask in the least degree scorched, as if it had been imbedded in heated matter. This tuff is porous; and, when first excavated, is soft and easily worked, but acquires a considerable degree of induration on exposure to the air. Above this lowest stratum is placed, according to Hamilton, "the matter of six eruptions," each separated from the other by veins of good soil. In these soils Lippi states that he collected a considerable number of land shells—an observation which is no doubt correct; for many snails burrow in soft soils, and some Italian species descend, when they hybernate, to the depth of five feet and more from the surface. Della Torre also informs us that there is in one part of this super-imposed mass a bed of true siliceous lava (*lava di pietra dura*); and, as no such current is believed to have flowed till near one thousand years after the destruction of Herculaneum, we must conclude, that the origin of a large part of the covering of Herculaneum was long subsequent to the first inhumation of the place. That city, as well as Pompeii, was a seaport. Herculaneum is still very near the shore, but a tract of land, a mile in length, intervenes between the borders of the Bay of Naples and Pompeii. In both cases the gain of land is due to the filling up of the bed of the sea with volcanic matter, and not to elevation by earthquakes, for there has been no change in the relative level of land and sea. Pompeii stood on a slight eminence composed of the lavas of the ancient Vesuvius, and flights of steps led down to the water's edge. The lowermost of these steps are said to be still on an exact level with the sea.

---

* See Ehrenberg, Proceedings (Berichte) of the Royal Acad. of Sci. Berlin, 1844, 1845, and an excellent abstract of his papers by Mr. Ansted in the Quart. Journ. of the Geol. Soc. London, No. 7. Aug. 1846. In regard to marine infusoria found in volcanic tuff, it is well known that on the shores of the island of Cephalonia in the Mediterranean (Proceedings, Geol. Soc. vol. ii. p. 220.), there is a cavity in the rock, into which the sea has been flowing for ages, and many others doubtless exist in the leaky bottom of the ocean. The marine current has been rushing in for many years, and as the infusoria inhabiting the waters of the Mediterranean are exceedingly abundant, a vast store of their cases may accumulate in submarine caverns (the water, perhaps, being converted into steam, and so escaping upwards), and they may then be cast up again to furnish the materials of volcanic tuff, should an eruption occur like that which produced Graham Island, off the coast of Sicily, in 1831.

† Hamilton, Observ. on Mount Vesuvius, p. 94. London, 1774.

Condition and contents of the buried cities.—After these observations on the nature of the strata enveloping and surrounding the cities, we may proceed to consider their internal condition and contents, so far at least as they offer facts of geological interest. Notwithstanding the much greater depth at which Herculaneum was buried, it was discovered before Pompeii, by the accidental circumstances of a well being sunk, in 1713, which came right down upon the theatre, where the statues of Hercules and Cleopatra were soon found. Whether this city or Pompeii, both of them founded by Greek colonies, was the more considerable, is not yet determined; but both are mentioned by ancient authors as among the seven most flourishing cities in Campania. The walls of Pompeii were three miles in circumference; but we have, as yet, no certain knowledge of the dimensions of Herculaneum. In the latter place the theatre alone is open for inspection: the Forum, Temple of Jupiter, and other buildings, having been filled up with rubbish as the workmen proceeded, owing to the difficulty of removing it from so great a depth below ground.[*] Even the theatre is only seen by torchlight, and the most interesting information, perhaps, which the geologist obtains there, is the continual formation of stalactite in the galleries cut through the tuff; for there is a constant percolation of water charged with carbonate of lime mixed with a small portion of magnesia. Such mineral waters must, in the course time, create great changes in many rocks; especially in lavas, the res of which they may fill with calcareous spar, so as to convert em into amygdaloids. Some geologists, therefore, are unreasonable hen they expect that volcanic rocks of remote eras should accord ecisely with those of modern date; since it is obvious that many of ose produced in our own time will not long retain the same aspect d internal composition.

Both at Herculaneum and Pompeii, temples have been found with scriptions commemorating the rebuilding of the edifices after they d been thrown down by an earthquake.* This earthquake hapned in the reign of Nero, sixteen years before the cities were overhelmed. In Pompeii, one fourth of which is now laid open to the y, both the public and private buildings bear testimony to the tastrophe. The walls are rent, and in many places traversed by sures still open. Columns are lying on the ground only half hewn m huge blocks of travertin, and the temple for which they were signed is seen half repaired. In some few places the pavement d sunk in, but in general it was undisturbed, consisting of large egular flags of lava joined neatly together, in which the carriage eels have often worn ruts an inch and a half deep. In the wider eets, the ruts are numerous and irregular; in the narrower, there e only two, one on each side, which are very conspicuous. It is possible not to look with some interest even on these ruts, which re worn by chariot wheels more than seventeen centuries ago; d, independently of their antiquity, it is remarkable to see such ep incisions so continuous in a stone of great hardness.

Small number of skeletons. — A very small number of skeletons ve been discovered in either city; and it is clear that most of the habitants not only found time to escape, but also to carry with em the principal part of their valuable effects. In the barracks at mpeii were the skeletons of two soldiers chained to the stocks, and the vaults of a country house in the suburbs were the skeletons of venteen persons, who appear to have fled there to escape from shower of ashes. They were found inclosed in an indurated tuff, d in this matrix was preserved a perfect cast of a woman, perhaps mistress of the house, with an infant in her arms. Although her m was imprinted on the rock, nothing but the bones remained. these a chain of gold was suspended, and on the fingers of the eletons were rings with jewels. Against the sides of the same vault s ranged a long line of earthen amphoræ.

The writings scribbled by the soldiers on the walls of their rracks, and the names of the owners of each house written over doors are still perfectly legible. The colours of fresco paintings the stuccoed walls in the interior of buildings are almost as vivid if they were just finished. There are public fountains decorated h shells laid out in patterns in the same fashion as those now seen the town of Naples; and in the room of a painter, who was perhaps a naturalist, a large collection of shells was found, comprising a great variety of Mediterranean species, in as good a state of preservation as if they had remained for the same number of years in a museum. A comparison of these remains with those found so generally in a fossil state would not assist us in obtaining the least insight into the time required to produce a certain degree of decomposition or mineralization; for, although under favourable circumstances much greater alteration might doubtless have been brought about in a shorter period, yet the example before us shows that an inhumation of seventeen centuries may sometimes effect nothing towards the reduction of shells to the state in which fossils are usually found.

---

* Swinburne and Lalande. Paderni, Phil. Trans. 1758, vol. i. p. 619.

The wooden beams in the houses at Herculaneum are black on the exterior, but, when cleft open, they appear to be almost in the state of ordinary wood, and the progress made by the whole mass towards the state of lignite is scarcely appreciable. Some animal and vegetable substances of more perishable kinds have of course suffered much change and decay, yet the state of preservation of these is truly remarkable. Fishing-nets are very abundant in both cities, often quite entire; and their number at Pompeii is the more interesting from the sea being now, as we stated, a mile distant. Linen has been found at Herculaneum, with the texture well defined; and in a fruiterer's shop in that city were discovered vessels full of almonds, chesnuts, walnuts, and fruit of the "carubiere," all distinctly recognizable from their shape. A loaf, also, still retaining its form, was found in a baker's shop, with his name stamped upon it. On the counter of an apothecary was a box of pills converted into a fine earthy substance; and by the side of it a small cylindrical roll evidently prepared to be cut into pills. By the side of these was a jar containing medicinal herbs. In 1827, moist olives were found in a square glass-case, and "caviare," or roe of a fish, in a state of wonderful preservation. An examination of these curious condiments has been published by Covelli of Naples, and they are preserved hermetically sealed in the museum there.*

Papyri. — There is a marked difference in the condition and appearance of the animal and vegetable substances found at Pompeii and Herculaneum; those of Pompeii being penetrated by a grey pulverulent tuff, those in Herculaneum seeming to have been first enveloped by a paste which consolidated round them, and then allowed them to become slowly carbonized. Some of the rolls of papyrus at Pompeii still retain their form; but the writing, and indeed almost all the vegetable matter, appear to have vanished, and to have been replaced by volcanic tuff somewhat pulverulent. At Herculaneum the earthy matter has scarcely ever penetrated; and the vegetable substance of the papyrus has become a thin friable black matter, almost resembling in appearance the tinder which remains when stiff paper has been burnt, in which the letters may

---

* Prof. J. D. Forbes, Edin. Journ. of Sci., No. xix. p. 130. Jan. 1829.

›e sometimes traced. The small bundles of papyri, composed of ›r six rolls tied up together, had sometimes lain horizontally, were pressed in that direction, but sometimes they had been d in a vertical position. Small tickets were attached to each le, on which the title of the work was inscribed. In one case have the sheets been found with writing on both sides of the . So numerous are the obliterations and corrections, that many have been original manuscripts. The variety of handwritings te extraordinary: nearly all are written in Greek, but there are in Latin. They were almost all found in a suburban villa in ibrary of one private individual; and the titles of four hundred ›se least injured, which have been read, are found to be unim- nt works, but all entirely new, chiefly relating to music, rhetoric, ookery. There are two volumes of Epicurus "On Nature," and hers are mostly by writers of the same school, only one fragment ıg been discovered, by an opponent of the Epicurean system, sippus.*

obability of future discoveries of MSS.—In the opinion of antiquaries, not one hundredth part of the city has yet been red: and the quarters hitherto cleared out at a great expense, those where there was the least probability of discovering scripts. As Italy could already boast her splendid Roman itheatres and Greek temples, it was a matter of secondary ›st to add to their number those in the dark and dripping ies of Herculaneum; and having so many of the masterpieces cient art, we could have dispensed with the inferior busts and ›s which could alone have been expected to reward our re- hes in the ruins of a provincial town. But from the moment it was ascertained that rolls of papyrus preserved in this city still be deciphered, every exertion ought to have been steadily exclusively directed towards the discovery of other libraries. ıte dwellings should have been searched, before so much labour expense were consumed in examining public edifices. A small ›n of that zeal and enlightened spirit which prompted the late ch and Tuscan expedition to Egypt might long ere this, in a ry nearer home, have snatched from oblivion some of the lost of the Augustan age, or of eminent Greek historians and sophers. A single roll of papyrus might have disclosed more r of intense interest than all that was ever written in hiero- ics.

ıbiæ.—Besides the cities already mentioned, Stabiæ, a small about six miles from Vesuvius, and near the site of the modern l-a-Mare (see map of volcanic district of Naples), was over- ned during the eruption of 79. Pliny mentions that, when his was there, he was obliged to make his escape, so great was the

---

ı one of the manuscripts which ı the hands of the interpreters [visited the museum in 1828, the indulges in the speculation that all the Homeric personages were allegorical — that Agamemnon was the ether, Achilles the sun, Helen the earth, Paris the air, Hector the moon, &c.

quantity of falling stones and ashes. In the ruins of this place, a few skeletons have been found buried in volcanic ejections, together with some antiquities of no great value, and rolls of papyrus, which, like those of Pompeii, were illegible.

Torre del Greco overflowed by lava.—Of the towns hitherto mentioned, Herculaneum alone has been overflowed by a stream of melted matter; but this did not, as we have seen, enter or injure the buildings, which were previously enveloped or covered over with tuff. But burning torrents have often taken their course through the streets of Torre del Greco, and consumed or inclosed a large portion of the town in solid rock. It seems probable that the destruction of three thousand of its inhabitants in 1631, which some accounts attribute to boiling water, was principally due to one of those alluvial floods which we before mentioned: but, in 1737, the lava itself flowed through the eastern side of the town, and afterwards reached the sea; and, in 1794, another current, rolling over the western side, filled the streets and houses, and killed more than four hundred persons. The main street is now quarried through this lava, which supplied building stones for new houses erected where others had been annihilated. The church was half buried in a rocky mass, but the upper portion served as the foundation of a new edifice.

The number of the population at present is estimated at fifteen thousand; and a satisfactory answer may readily be returned to those who inquire how the inhabitants can be so "inattentive to the voice of time and the warnings of nature,"* as to rebuild their dwellings on a spot so often devastated. No neighbouring site unoccupied by a town, or which would not be equally insecure, combines the same advantages of proximity to the capital, to the sea, and to the rich lands on the flanks of Vesuvius. If the present population were exiled, they would immediately be replaced by another, for the same reason that the Maremma of Tuscany and the Campagna di Roma will never be depopulated, although the malaria fever commits more havoc in a few years than the Vesuvian lavas in as many centuries. The district around Naples supplies one amongst innumerable examples, that those regions where the surface is most frequently renewed, and where the renovation is accompanied, at different intervals of time, by partial destruction of animal and vegetable life, may nevertheless be amongst the most habitable and delightful on our globe.

I have already made a similar remark when speaking of tracts where aqueous causes are now most active; and the observation applies as well to parts of the surface which are the abode of aquatic animals, as to those which support terrestrial species. The sloping sides of Vesuvius give nourishment to a vigorous and healthy population of about eighty thousand souls; and the surrounding hills and plains, together with several of the adjoining isles, owe the fertility of their soil to matter ejected by prior eruptions. Had the fundamental limestone of the Apennines remained uncovered throughout the whole area, the country could not have sustained a twentieth part of its present inhabitants. This will be apparent to every geologist who has marked the change in the agricultural character of the soil the moment he has passed the utmost boundary of the volcanic ejections, as when, for example, at the distance of about seven miles from Vesuvius, he leaves the plain and ascends the declivity of the Sorrentine Hills.

---

* Sir H. Davy, Consolations in Travel, p. 66.

Yet, favoured as this region has been by Nature from time immemorial, the signs of the changes imprinted on it during the period that it has served as the habitation of man may appear in after-ages to indicate a series of unparalleled disasters. Let us suppose that at some future time the Mediterranean should form a gulf of the great ocean, and that the waves and tidal current should encroach on the shores of Campania, as it now advances upon the eastern coast of England; the geologist will then behold the towns already buried, and many more which will evidently be entombed hereafter, laid open in the steep cliffs, where he will discover buildings superimposed above each other, with thick intervening strata of tuff or lava — some unscathed by fire, like those of Herculaneum and Pompeii; others half melted down, as in Torre del Greco; and many shattered and thrown about in strange confusion, as in Tripergola, beneath Monte Nuovo. Among the ruins will be seen skeletons of men, and impressions of the human form stamped in solid rocks of tuff. Nor will the signs of earthquakes be wanting. The pavement of part of the Domitian Way, and the temple of the Nymphs, submerged at high tide, will be uncovered at low water, the columns remaining erect and uninjured. Other temples which had once sunk down, like that of Serapis, will be found to have been upraised again by subsequent movements. If they who study these phenomena, and speculate on their causes, assume that there were periods when the laws of Nature or the whole course of natural events differed greatly from those observed in their own time, they will scarcely hesitate to refer the wonderful monuments in question to those primeval ages. When they consider the numerous proofs of reiterated catastrophes to which the region was subject, they may, perhaps, commiserate the unhappy fate of beings condemned to inhabit a planet during its nascent and chaotic state, and feel grateful that their favoured race has escaped such scenes of anarchy and misrule.

Yet what was the real condition of Campania during those years of dire convulsion? "A climate where heaven's breath smells sweet and wooingly — a vigorous and luxuriant nature unparalleled in its productions — a coast which was once the fairy-land of poets, and the favourite retreat of great men. Even the tyrants of the creation loved this alluring region, spared it, adorned it, lived in it, died in it."* The inhabitants, indeed, have enjoyed no immunity from the calamities which are the lot of mankind; but the principal evils which they have suffered must be attributed to moral, not to physical, causes—to disastrous events over which man might have exercised a control, rather than to the inevitable catastrophes which result from subterranean agency. hen Spartacus encamped his army of ten thousand gladiators in t old extinct crater of Vesuvius, the volcano was more justly a subje of terror to Campania, than it has ever been since the rekindli s fires.

---

* Forsyth's Italy, vol. ii.

CHAPTER XXV.

ETNA.

External physiognomy of Etna—Lateral cones—Their successive obliteration—Early eruptions—Monti Rossi in 1669—Towns overflowed by lava—Part of Catania overflowed—Mode of advance of a current of lava—Subterranean caverns—Marine strata at base of Etna—Val del Bove not an ancient crater—Its scenery—Form, composition, and origin of the dikes—Linear direction of cones formed in 1811 and 1819—Lavas and breccias—Flood produced by the melting of snow by lava—Glacier covered by a lava stream—Val del Bove how formed—Structure and origin of the cone of Etna—Whether the inclined sheets of lava were originally horizontal—Antiquity of Etna—Whether signs of diluvial waves are observable on Etna.

External physiognomy of Etna.—AFTER Vesuvius, our most authentic records relate to Etna, which rises near the sea in solitary grandeur to the height of nearly eleven thousand feet.* The base of the cone is almost circular, and eighty-seven English miles in circumference; but if we include the whole district over which its lavas extend, the circuit is probably twice that extent.

Divided into three regions.—The cone is divided by nature into three distinct zones, called the *fertile*, the *woody*, and the *desert* regions. The first of these, comprising the delightful country around the skirts of the mountain, is well cultivated, thickly inhabited, and covered with olives, vines, corn, fruit-trees, and aromatic herbs. Higher up, the woody region encircles the mountain—an extensive forest six or seven miles in width, affording pasturage for numerous flocks. The trees are of various species, the chestnut, oak, and pine being most luxuriant; while in some tracts are groves of cork and beech. Above the forest is the desert region, a waste of black lava and scoriæ; where, on a kind of plain, rises a cone of eruption to the height of about eleven hundred feet, from which sulphureous vapours are continually evolved.

---

* In 1815, Captain Smyth ascertained, trigonometrically, that the height of Etna was 10,874 feet. The Catanians, disappointed that their mountain had lost nearly 2000 feet of the height assigned to it by Recupero, refused to acquiesce in the decision. Afterwards, in 1824, Sir J. Herschel, not being aware of Captain Smyth's conclusions, determined by careful barometrical measurement that the height was 10,872½ feet. This singular agreement of results so differently obtained was spoken of by Herschel as "a happy accident;" but Dr. Wollaston remarked that "it was one of those accidents which would not have happened to two fools."

Cones produced by lateral eruption.—The most grand and original feature in the physiognomy of Etna is the multitude of minor cones which are distributed over its flanks, and which are most abundant in the woody region. These, although they appear but trifling irregularities when viewed from a distance as subordinate parts of so imposing and colossal a mountain, would, nevertheless, be deemed hills of considerable altitude in almost any other region. Without enumerating numerous monticules of ashes thrown out at different points, there are about eighty of these secondary volcanos, of considerable dimensions; fifty-two on the west and north, and twenty-seven on the east side of Etna. One of the largest, called Monte Minardo, near Bronte, is upwards of 700 feet in height, and a double hill near Nicolosi, called Monti Rossi, formed in 1669, is 450 feet high, and the base two miles in circumference; so that it somewhat exceeds in size Monte Nuovo, before described. Yet it ranks only as a cone of the second magnitude amongst those produced by the lateral eruptions of Etna. On looking down from the lower borders of the desert region, these volcanos present us with one of the most delightful and characteristic scenes in Europe. They afford every variety of height and size, and are arranged in beautiful and picturesque groups. However uniform they may appear when seen from the sea, or the plains below, nothing can be more diversified than their shape when we look from above into their craters, one side of which is generally broken down. There are, indeed, few objects in nature more picturesque than a wooded volcanic crater. The cones situated in the higher parts of the forest zone are chiefly clothed with lofty pines; while those at a lower elevation are adorned with chestnuts, oaks, beech, and holm.

Successive obliteration of these cones.—The history of the eruptions of Etna, imperfect and interrupted as it is, affords us, nevertheless, much insight into the manner in which the whole mountain has successively attained its present magnitude and internal structure. The principal cone has more than once fallen in and been reproduced. In 1444 it was 320 feet high, and fell in after the earthquakes of 1537. In the year 1693, when a violent earthquake shook the whole of Sicily, and killed sixty thousand persons, the cone lost so much of its height, says Boccone, that it could not be seen from several places in Valdemone, from which it was before visible. The greater number of eruptions happen either from the great crater, or from lateral openings in the desert region. When hills are thrown up in the middle zone, and project beyond the general level, they gradually lose their height during subsequent eruptions; for when lava runs down from the upper parts of the mountain, and encounters any of these hills, the stream is divided, and flows round them so as to elevate the gently sloping grounds from which they rise. In this manner a deduction is often made at once of twenty or thirty feet, or even more, from their height. Thus, one of the minor cones, called Monte Peluso, was diminished in altitude by a great lava stream which encircled it in 1444; and another current has recently taken the same course— yet this hill still remains four or five hundred feet high.

There is a cone called Monte Nucilla near Nicolosi, round the base of which several successive currents have flowed, and showers of ashes have fallen, since the time of history, till at last, during an eruption in 1536, the surrounding plain was so raised, that the top of the cone alone was left projecting above the general level. Monte Nero, situated above the Grotta dell' Capre, was in 1766 almost submerged by a current: and Monte Capreolo afforded, in the year 1669, a curious example of one of the last stages of obliteration; for a lava stream, descending on a high ridge which had been built up by the continued superposition of successive lavas, flowed directly into the crater, and nearly filled it. The lava, therefore, of each new lateral cone tends to detract from the relative height of lower cones above their base; so that the flanks of Etna, sloping with a gentle inclination, envelop in succession a great multitude of minor volcanos, while new ones spring up from time to time.

Early eruptions of Etna.—Etna appears to have been in activity from the earliest times of tradition; for Diodorus Siculus mentions an eruption which caused a district to be deserted by the Sicani before the Trojan war. Thucydides informs us, that in the sixth year of the Peloponnesian war, or in the spring of the year 425 B.C., a lava stream ravaged the environs of Catania, and this he says was the third eruption which had happened in Sicily since the colonization of that island by the Greeks.* The second of the three eruptions alluded to by the historian took place in the year 475 B.C., and was that so poetically described by Pindar, two years afterwards, in his first Pythian ode:—

κιων
Δ' ουρανια συνεχει
Νιφοεσσ' Αιτνα, πανετες
Χιονος οξειας τιθηνα.

In these and the seven verses which follow, a graphic description is given of Etna, such as it appeared five centuries before the Christian era, and such as it has been seen when in eruption in modern times. The poet is only making a passing allusion to the Sicilian volcano, as the mountain under which Typhœus lay buried, yet by a few touches of his master hand every striking feature of the scene has been faithfully pourtrayed. We are told of "the snowy Etna, the pillar of heaven,—the nurse of everlasting frost, in whose deep caverns lie concealed the fountains of unapproachable fire—a stream of eddying smoke by day—a bright and ruddy flame by night; and burning rocks rolled down with loud uproar into the sea."

---

* Book iii., at the end.

Eruption of 1669 — *Monti Rossi formed.* — The great eruption which happened in the year 1669 is the first which claims particular attention. An earthquake had levelled to the ground all the houses in Nicolosi, a town situated near the lower margin of the woody region, about twenty miles from the summit of Etna, and ten from the sea at Catania. Two gulfs then opened near that town, from whence sand and scoriæ were thrown up in such quantity, that in the course of three or four months, a double cone was formed, called Monti Rossi, about 450 feet high. But the most extraordinary phenomenon occurred at the commencement of the convulsion in the plain of S. Lio. A fissure six feet broad, and of unknown depth, opened with a loud crash, and ran in a somewhat tortuous course to within a mile of the summit of Etna. Its direction was from north to south, and its length twelve miles. It emitted a most vivid light. Five other parallel fissures of considerable length afterwards opened one after the other, and emitted smoke, and gave out bellowing sounds which were heard at the distance of forty miles. This case seems to present the geologist with an illustration of the manner in which those continuous dikes of vertical porphyry were formed, which are seen to traverse some of the older lavas of Etna; for the light emitted from the great rent of S. Lio appears to indicate that the fissure was filled to a certain height with incandescent lava, probably to the height of an orifice not far distant from Monti Rossi, which at that time opened and poured out a lava current. When the melted matter in such a rent has cooled, it must become a solid wall or dike, intersecting the older rocks of which the mountain is composed; similar rents have been observed during subsequent eruptions as in 1832, when they ran in all directions from the centre of the volcano.

Fig. 46.



Minor cones on the flanks of Etna.

1. Monti Rossi, near Nicolosi, formed in 1669. 2. Vampeluso ?[*]

---

[*] The hill which I have here introduced was called by my guide Vampolara, but the name given in the text is the nearest to this, which I find in Gemmellaro's Catalogue of Minor Cones.

It has been justly remarked by M. Elie de Beaumont, that such star-shaped fractures may indicate a slight upheaval of the whole of Etna. They may be the signs of the stretching of the mass, which may thus be raised gradually by a force from below.*

The lava current of 1669, before alluded to, soon reached in its course a minor cone called Mompiliere, at the base of which it entered a subterranean grotto, communicating with a suite of those caverns which are so common in the lavas of Etna. Here it appears to have melted down some of the vaulted foundations of the hill, so that the whole of that cone became slightly depressed and traversed by numerous open fissures.

Part of Catania destroyed. — The lava, after overflowing fourteen towns and villages, some having a population of between three and four thousand inhabitants, arrived at length at the walls of Catania. These had been purposely raised to protect the city; but the burning flood accumulated till it rose to the top of the rampart, which was sixty feet in height, and then it fell in a fiery cascade and overwhelmed part of the city. The wall, however, was not thrown down, but was discovered long afterwards, by excavations made in the rock by the Prince of Biscari; so that the traveller may now see the solid lava curling over the top of the rampart as if still in the very act of falling.

This great current performed the first thirteen miles of its course in twenty days, or at the rate of 162 feet per hour, but required twenty-three days for the last two miles, giving a velocity of only twenty-two feet per hour; and we learn from Dolomieu that the stream moved during part of its course at the rate of 1500 feet an hour, and in others took several days to cover a few yards.† When it entered the sea it was still six hundred yards broad, and forty feet deep. It covered some territories in the environs of Catania, which had never before been visited by the lavas of Etna. While moving on, its surface was in general a mass of solid rock; and its mode of advancing, as is usual with lava streams, was by the occasional fissuring of the solid walls. A gentleman of Catania, named Pappalardo, desiring to secure the city from the approach of the threatening torrent, went out with a party of fifty men whom he had dressed in skins to protect them from the heat, and armed with iron crows and hooks. They broke open one of the solid walls which flanked the current near Belpasso, and immediately forth issued a rivulet of melted matter which took the direction of Paternó; but the inhabitants of that town, being alarmed for their safety, took up arms and put a stop to farther operations.‡

As another illustration of the solidity of the walls of an advancing lava stream, I may mention an adventure related by Recupero, who in 1766, had ascended a small hill formed of ancient volcanic matter.

---

* Mém. pour servir, &c., tom. iv. p. 116.

† See Prof. J. D. Forbes, Phil. Trans., 1846, p. 155., on Velocity of Lava.

‡ Ferrara, Descriz. dell' Etna, p. 108.

hold the slow and gradual approach of a fiery current, two miles half broad; when suddenly two small threads of liquid matter ıg from a crevice detached themselves from the main stream, and rapidly towards the hill. He and his guide had just time to ıe, when they saw the hill, which was fifty feet in height, surded, and in a quarter of an hour melted down into the burning , so as to flow on with it.

ıt it must not be supposed that this complete fusion of rocky er coming in contact with lava is of universal, or even common, rrence. It probably happens when fresh portions of incandesmatter come successively in contact with fusible materials. In of the dikes which intersect the tuffs and lavas of Etna, there arcely any perceptible alteration effected by heat on the edges of ıorizontal beds, in contact with the vertical and more crystalline . On the site of Mompiliere, one of the towns overflowed in the t eruption above described, an excavation was made in 1704; by immense labour the workmen reached, at the depth of thirtyfeet, the gate of the principal church, where there were three es, held in high veneration. One of these, together with a bell, money, and other articles, were extracted in a good state of ervation from beneath a great arch formed by the lava. It seems extraordinary that any works of art, not encased with tuff, like in Herculaneum, should have escaped fusion in hollow spaces open in this lava current, which was so hot at Catania eight after it entered the town, that it was impossible to hold the in some of the crevices.

ubterranean caverns on Etna.—Mention was made of the ence of a lava-stream into a subterranean grotto, whereby the dations of a hill were partially undermined. Such underground ıges are among the most curious features on Etna, and appear to been produced by the hardening of the lava, during the escape reat volumes of elastic fluids, which are often discharged for days in succession, after the crisis of the eruption is over. Nicolosi, not far from Monti Rossi, one of these great openings be seen, called the Fossa della Palomba, 625 feet in circumference mouth, and seventy-eight deep. After reaching the bottom of we enter another dark cavity, and then others in succession, times descending precipices by means of ladders. At length the ts terminate in a great gallery ninety feet long, and from fifteen ifty broad, beyond which there is still a passage, never yet ored; so that the extent of these caverns remains unknown.* walls and roofs of these great vaults are composed of rough and ling scoriæ, of the most fantastic forms.

arine strata at base of Etna.—If we skirt the fertile region at ase of Etna on its southern and eastern sides, we behold marine a of clay sand, and volcanic tuff, cropping out from beneath the ern lavas. The marine fossil shells occurring in these strata are all of them, or nearly all, identical with species now inhabiting the Mediterranean; and as they appear at the height of from 600 to 800 feet above the sea near Catania, they clearly prove that there has been in this region, as in other parts of Sicily farther to the south, an upward movement of the ancient bed of the sea. It is fair, therefore, to infer that the whole mountain, with the exception of those parts which are of very modern origin, has participated in this upheaval.

---

* Ferrara, Descriz. dell' Etna. Palermo, 1818.

If we view Etna from the south, we see the marine deposits above alluded to, forming a low line of hills (*e*, *e*, fig. 47.) or a steep inland slope or cliff (*f*), as in the annexed drawing taken from the limestone platform of Primosole. It should be observed however, in reference to this view, that the height of the volcanic cone is ten times greater than the hills at its base (*e*, *e*), although it appears less elevated, because the summit of the cone is ten or twelve times more distant from the plain of Catania than is Licodia.

Fig. 47.



View of Etna from the summit of the limestone platform of Primosole.

a, Highest cone. *b*, Montagnuola.
c, Monte Minardo, with smaller lateral cones above.
d, Town of Licodia dei Mooaci.
e, Marine formation called creta, argillaceous and sandy beds with a few shells, and associated volcanic rocks.
f, Escarpment of stratified subaqueous volcanic tuff, &c., north-west of Catania.
g, Town of Catania.
h, *i*, Dotted line expressing the highest boundary along which the marine strata are occasionally seen.
k, Plain of Catania.
l, Limestone platform of Primosole of the Newer Pliocene period.
m, La Motta di Catania.

The mountain is in general of a very symmetrical form, a flattened cone broken on its eastern side, by a deep valley, called the Val del Bove, or in the provincial dialect of the peasants, "Val di Bué," for here the herdsman

> —— "in reductâ valle *mugientium*
> Prospectat errantes greges."

Dr. Buckland was, I believe, the first English geologist who examined this valley with attention, and I am indebted to him for having described it to me, before I visited Sicily, as more worthy of attention than any single spot in that island, or perhaps in Europe.

The Val del Bove commences near the summit of Etna, and descending into the woody region, is farther continued on one side by a second and narrower valley, called the Val di Calanna. Below this another, named the Val di St. Giacomo, begins,—a long nar-

PLATE III



[illegible] BOVE, ETNA

row ravine, which is prolonged to the neighbourhood of Zaffarana (*e*, fig. 48.), on the confines of the fertile region. These natural incisions into the side of the volcano are of such depth that they expose

FIG. 48.



Great valley on the east side of Etna.

a, Highest cone. *b*, Montagnuola.
c, Head of Val del Bove. *d*, *d*, Serre del Solfizio.
e, Village of Zaffarana on the lower border of the woody region.
f, One of the lateral cones. *g*, Monti Rossi.

to view a great part of the structure of the entire mass, which, in the Val del Bove, is laid open to the depth of from 3000 to above 4000 feet from the summit of Etna. The geologist thus enjoys an opportunity of ascertaining how far the internal conformation of the cone corresponds with what he might have anticipated as the result of that mode of increase which has been witnessed during the historical era.

Description of Plate III.—The accompanying view (Pl. III.) is part of a panoramic sketch which I made in November, 1828, and may assist the reader in comprehending some topographical details to be alluded to in the sequel, although it can convey no idea of the picturesque grandeur of the scene.

The great lava-currents of 1819 and 1811 are seen pouring down from the higher parts of the valley, overrunning the forests of the great plain, and rising up in the foreground on the left with a rugged surface, on which many hillocks and depressions appear, such as often characterize a lava-current immediately after its consolidation.

The small cone, No. 7., was formed in 1811, and was still smoking when I saw it in 1828. The other small volcano to the left, from which vapour is issuing, was, I believe, one of those formed in 1819.

The following are the names of some of the other points indicated in the sketch:—

1, Montagnuola.
2, Torre del Filosofo.
3, Highest cone.
4, Lepra.
5, Finocchio.
6, Capra.
7, Cone of 1811.
8, Cima del Asino.
9, Musara.
10, Zocolaro.
11, Rocca di Calanna.

Description of Plate IV.—The second view (Pl. IV.) represents the same valley as seen from above, or looking directly down the Val del Bove, from the summit of the principal crater formed in 1819.*

* This view is taken from a sketch made by Mr. James Bridges, corrected after comparison with several sketches of my own.

I am unable to point out the precise spot which this crater would occupy in the view represented in Plate III.; but I conceive that it would appear in the face of the great precipice, near which the smoke issuing from the cone No. 7. is made to terminate. There are many ledges of rock on the face of that precipice where eruptions have occurred.

The circular form of the Val del Bove is well shown in this view. (Pl. IV.) To the right and left are the lofty precipices which form the southern and northern sides of the great valley, and which are intersected by dikes projecting in the manner afterwards to be described. In the distance appears the "fertile region" of Etna, extending like a great plain along the sea coast.

The spots particularly referred to in the plate are the following:—

a, Cape Spartivento, in Italy, of which the outline is seen in the distance.
b, The promontory of Taormino, on the Sicilian coast.
c, The river Alcantra.
d, The small village of Riposto.
f, The town of Aci Reale.
g, Cyclopian islands, or "Faraglioni," in the Bay of Trezza.
h, The great harbour of Syracuse.
k, The Lake of Lentini.
i, The city of Catania, near which is marked the course of the lava which flowed from the Monti Rossi in 1669, and destroyed part of the city.
, To the left of the view is the crater of 1811, which is also shown at No. 7. in Plate III.
m, Rock of Musara, also seen at No. 9. in Plate III.
e, Valley of Calanna.

The Val del Bove is of truly magnificent dimensions, a vast amphitheatre four or five miles in diameter, surrounded by nearly vertical precipices, varying from 1000 to above 3000 feet in height, the loftiest being at the upper end, and the height gradually diminishing on both sides. The feature which first strikes the geologist as distinguishing the boundary cliffs of this valley, is the prodigious multitude of vertical dikes which are seen in all directions traversing the volcanic beds. The circular form of this great chasm, and the occurrence of these countless dikes, amounting perhaps to several thousands in number, so forcibly recalled to my mind the phenomena of the Atrio del Cavallo, on Vesuvius, that I at first imagined that I had entered a vast crater, on a scale as far exceeding that of Somma, as Etna surpasses Vesuvius in magnitude.

But I was soon undeceived when I had attentively explored the different sides of the great amphitheatre, in order to satisfy myself whether the semicircular wall of the Val del Bove had ever formed the boundary of a crater, and whether the beds had the same quâ-quâ-versal dip which is so beautifully exhibited in the escarpment of Somma. Had the supposed analogy between Somma and the Val del Bove held true, the tuffs and lavas at the head of the valley would have dipped to the west, those on the north side towards the north, and those on the southern side to the south. But such I did not find to be the inclination of the beds; they all dip towards the

PLATE IV



VIEW OF THE VAL DEL BOVE, ETNA, AS SEEN FROM ABOVE, OR FROM THE CRATER OF 1819.

early east, as in the valleys of St. Giacomo and Calanna

y of the Val del Bove.—Let the reader picture to himself a hitheatre, five miles in diameter, and surrounded on three precipices from 2000 to 3000 feet in height. If he has at most picturesque scene in the chain of the Pyrenees, the l "cirque of Gavarnie," he may form some conception of ificent circle of precipitous rocks which inclose, on three great plain of the Val del Bove. This plain has been y repeated streams of lava; and although it appears almost en viewed from a distance, it is, in fact, more uneven than ce of the most tempestuous sea. Besides the minor irre- of the lava, the valley is in one part interrupted by a ridge two of which, Musara and Capra, are very prominent. It y be said that they

> ——— "like giants stand
> To sentinel enchanted land;"

igh, like the Trosachs, in the Highlands of Scotland, they gantic dimensions, and appear almost isolated, as seen from nts, yet the stern and severe grandeur of the scenery which n is not such as would be selected by a poet for a vale of ient. The character of the scene would accord far better ton's picture of the infernal world; and if we imagine to behold in motion, in the darkness of the night, one of y currents which have so often traversed the great valley, well recall

> ——— "yon dreary plain, forlorn and wild,
> The seat of desolation, void of light,
> Save what the glimmering of these livid flames
> Casts pale and dreadful."

ice of the precipices already mentioned is broken in the turesque manner by the vertical walls of the lava which them. These masses usually stand out in relief, are gly diversified in form, and of immense altitude. In the their black outline may often be seen relieved by clouds of pour which settle behind them, and do not disperse until continuing to fill the valley while the sun is shining on ier part of Sicily, and on the higher regions of Etna.

n as the vapours begin to rise, the changes of scene are the highest degree, different rocks being unveiled and y turns, and the summit of Etna often breaking through the r a moment with its dazzling snows, and being then as withdrawn from the view.

iusual silence prevails; for there are no torrents dashing rocks, nor any movement of running water in this valley may almost invariably be heard in mountainous regions. rop of water that falls from the heavens, or flows from the ice and snow, is instantly absorbed by the porous lava; and such is the dearth of springs, that the herdsman is compelled to supply his flocks, during the hot season, from stores of snow laid up in hollows of the mountain during winter.

The strips of green herbage and forest land, which have here and there escaped the burning lavas, serve, by contrast, to heighten the desolation of the scene. When I visited the valley, nine years after the eruption of 1819, I saw hundreds of trees, or rather the white skeletons of trees, on the borders of the black lava, the trunks and branches being all leafless, and deprived of their bark by the scorching heat emitted from the melted rock; an image recalling those beautiful lines:—

> ——— "As when heaven's fire
> Hath scath'd the forest oaks, or mountain pines,
> With singed top their stately growth, though bare,
> Stands on the blasted heath."

Form, composition, and origin of the dikes.—But without indulging the imagination any longer in descriptions of scenery, I may observe that the dikes before mentioned form unquestionably the most interesting geological phenomenon in the Val del Bove. Some of these are composed of trachyte, others of compact blue basalt with olivine. They vary in breadth from two to twenty feet and upwards, and usually project from the face of the cliffs, as represented in the annexed drawing (fig. 49.). They consist of harder materials than the strata which they traverse, and therefore waste away less rapidly under the influence of that repeated congelation and thawing to

Fig. 49.



Dikes at the base of the Serre del Solfizio, Etna.

which the rocks in this zone of Etna are exposed. The dikes are, for the most part, vertical but sometimes they run in a tortuous course through the tuffs and breccias, as represented in fig. 50. In the escarpment of Somma, where similar walls of lava cut through alternating beds of sand and scoriæ, a coating of coal-black rock, approaching in its nature and appearance to pitchstone, is seen at the contact of the dike with the intersected beds. I did not observe such parting layers at the junction of the Etnean dikes which I examined, but they may perhaps be discoverable.

Fig. 50.



Tortuous veins of lava, at Punto di Giumento, Etna.

The geographical position of these dikes is most interesting, as they are very numerous near the head of the Val del Bove, where the cones of 1811 and 1819 were thrown up, as also in that zone of the mountain where lateral eruptions are frequent; whereas in the Valley of Calanna, which is below that parallel, and in a region where lateral eruptions are extremely rare, scarcely any dikes are seen, and none whatever still lower in the valley of St. Giacomo. This is precisely what we might have expected, if we consider the vertical fissures now filled with rock to have been the feeders of lateral cones, or, in other words, the channels which gave passage to the lava currents and scoriæ that have issued from vents in the forest zone. In other parts of Etna there may be numerous dikes at as low a level as the Valley of Calanna, because the line of lateral eruptions is not everywhere at the same height above the sea; but in the section above alluded to, there appeared to me an obvious connection between the frequency of dikes and of lateral eruptions.

Some fissures may have been filled from above, but I did not see any which by terminating downwards, gave proof of such an origin. Almost all the isolated masses in the Val del Bove, such as Capra, Musara, and others, are traversed by dikes, and may, perhaps, have partly owed their preservation to that circumstance, if at least the action of occasional floods has been one of the destroying causes in the Val del Bove; for there is nothing which affords so much protection to a mass of strata against the undermining action of running water as a perpendicular dike of hard rock.

In the accompanying drawing (fig. 51.) the flowing of the lavas of 1811 and 1819, between the rocks Finochio, Capra, and Musara, is represented. The height of the two last-mentioned isolated masses has been much diminished by the elevation of their base, caused by these currents. They may, perhaps, be the remnants of lateral cones which existed before the Val del Bove was formed, and may hereafter be once more buried by the lavas that are now accumulating in the valley.

Fig. 51.



View of the rocks Finochio, Capra, and Musara, Val del Bove.

From no point of view are the dikes more conspicuous than from the summit of the highest cone of Etna: a view of some of them is given in the annexed drawing. (Fig. 52.)

Eruption of 1811.—I have alluded to the streams of lava which were poured forth in 1811 and 1819. Gemmellaro, who witnessed these eruptions, informs us that the great crater in 1811 first testified by its loud detonations, that a column of lava had ascended to near the summit of the mountain. A violent shock was then felt, and a stream broke out from the side of the cone, at no great distance from its apex. Shortly after this had ceased to flow, a second stream burst forth at another opening, considerably below the first; then a third still lower, and so on till seven different issues had been thus successively formed, all lying upon the same straight line. It has been supposed that this line was a perpendicular rent in the internal framework of the mountain, which rent was probably not produced at one shock, but prolonged successively downwards, by the lateral pressure and intense heat of the internal column of lava, as it subsided by gradual discharge through each vent.*

Eruption of 1819.—In 1819 three large mouths or caverns opened very near those which were formed in the eruptions of 1811, from which flames, red-hot cinders, and sand were thrown up with loud

---

* Scrope on Volcanos, p. 153.

Fig. 52.



View from the summit of Etna into the Val del Bove.*

explosions. A few minutes afterwards another mouth opened below, from which flames and smoke issued; and finally a fifth, lower still, whence a torrent of lava flowed, which spread itself with great velocity over the deep and broad valley called "Val del Bove." This stream flowed two miles in the first twenty-four hours, and nearly as far in the succeeding day and night. The three original mouths at length united into one large crater, and sent forth lava, as did the inferior apertures, so that an enormous torrent poured down the "Val del Bove." When it arrived at a vast and almost perpendicular precipice, at the head of the valley of Calanna, it poured over in a cascade, and, being hardened in its descent, made an inconceivable crash as it was dashed against the bottom. So immense was the column of dust raised by the abrasion of the tufaceous hill over which the hardened mass descended, that the Catanians were in great alarm, supposing a new eruption to have burst out in the woody region, exceeding in violence that near the summit of Etna.

Mode of advance of the lava.—Of the cones thrown up during this eruption, not more than two are of sufficient magnitude to be numbered among those eighty which were before described as adorning the flanks of Etna. The surface of the lava which deluged the

---

* This drawing is part of a panoramic sketch which I made from the summit of the cone, December 1. 1828, when every part of Etna was free from clouds except the Val del Bove. The small cone, and the crater nearest the foreground, were among those formed during the eruptions of 1810 and 1811.

"Val del Bove," consists of rocky and *angular blocks*, tossed together in the utmost disorder. Nothing can be more rugged, or more unlike the smooth and even superficies, which those who are unacquainted with volcanic countries may have pictured to themselves, in a mass of matter which had consolidated from a liquid state. Mr. Scrope observed this current in the year 1819, slowly advancing down a considerable slope, at the rate of about a yard an hour, nine months after its emission. The lower stratum being arrested by the resistance of the ground, the upper or central part gradually protruded itself, and, being unsupported, fell down. This in its turn was covered by a mass of more liquid lava, which swelled over it from above. The current had all the appearance of a huge heap of rough and large cinders rolling over and over upon itself by the effect of an extremely slow propulsion from behind. The contraction of the crust as it solidified, and the friction of the scoriform cakes against one another, produced a crackling sound. Within the crevices a dull red heat might be seen by night, and vapour issuing in considerable quantity was visible by day.*

It was stated that when the lava of 1819 arrived at the head of the Valley of Calanna, after flowing down the Val del Bove, it descended in a cascade. This stream, in fact, like many previous currents of lava which have flowed down successively from the higher regions of Etna, was turned by a great promontory projecting from the southern side of the Val del Bove. This promontory consists of the hills called Zocolaro and Calanna, and of a ridge of inferior height which connects them. (See fig. 53.)

Fig. 53.



A, Zocolaro. B, Monte di Calanna.
C, Plain at the head of the Valley of Calanna.
a, Lava of 1819 descending the precipice and flowing through the valley.
b, Lavas of 1811 and 1819 flowing round the hill of Calanna.

It happened in 1811 and 1819 that the flows of lava overtopped the ridge intervening between the hills of Zocolaro and Calanna, so that they fell in a cascade over a lofty precipice, and began to fill up the valley of Calanna (*a*, fig. 53.). Other portions of the same lava-current (*b*) flowed round the promontory, and they exhibit one of the peculiar characteristics of such streams, namely that of becoming solid externally, even while yet in motion. Instead of thinning out gradually at their edges, their sides may often be compared to two rocky walls which are sometimes inclined at an angle of between thirty and forty degrees. When such streams are turned from their course by a projecting rock, they move right onwards in a new direction; and in the valley of Calanna a considerable space has thus been left between the steep sides of the lavas, *b b*, so deflected, and the precipitous escarpment of Zocolaro, A, which bounds the plain C.

---

* Scrope on Volcanos, p. 102.

Lavas and breccias.—In regard to the volcanic masses which are intersected by dikes in the Val del Bove, they consist in great part of greystone lavas, of an intermediate character between basalt and trachyte, and partly of porphyritic lava resembling trachyte, but to which that name cannot, according to Von Buch and G. Rose, be in strictness applied, because the felspar belongs to the variety called Labradorite. There is great similarity in the composition of the ancient and modern lavas of Etna, both consisting of felspar, augite, olivine, and titaniferous iron. The alternating breccias are made up of scoriæ, sand, and angular blocks of lava. Many of these fragments may have been thrown out by volcanic explosions, which, falling on the hardened surface of moving lava-currents, may have been carried to a considerable distance. It may also happen that when lava advances very slowly, in the manner of the flow of 1819, the angular masses resulting from the frequent breaking of the mass as it rolls over upon itself, may produce these breccias. It is at least certain that the upper portion of the lava-currents of 1811 and 1819 now consist of angular masses to the depth of many yards. D'Aubuisson has compared the surface of one of the ancient lavas of Auvergne to that of a river suddenly frozen over by the stoppage of immense fragments of drift-ice, a description perfectly applicable to these modern Etnean flows. The thickness of the separate beds of conglomerate or breccia which are seen in the same vertical section, is often extremely different, varying from 3 to nearly 50 feet, as I observed in the hill of Calanna.

Flood produced by the melting of snow by lava.—It is possible that some of the breccias or conglomerates may be referred to aqueous causes, as great floods occasionally sweep down the flanks of Etna, when eruptions take place in winter, and when the snows are melted by lava. It is true that running water in general exerts no power on Etna, the rain which falls being immediately imbibed by the porous lavas; so that, vast as is the extent of the mountain, it feeds only a few small rivulets, and these, even, are dry throughout the greater portion of the year. The enormous rounded boulders, therefore, of felspar-porphyry and basalt, a line of which can be traced from the sea, from near Giardini, by Mascali, and Zafarana, to the "Val del Bove," would offer a perplexing problem to the geologist, if history had not preserved the memorials of a tremendous flood which happened in this district in the year 1755. It appears that two streams of lava flowed in that year, on the 2d of March, from the highest crater: they were immediately precipitated upon an enormous mass of snow which then covered the whole mountain, and was extremely deep near the summit. The sudden melting of this frozen mass, by a fiery torrent three miles in length, produced a frightful inundation, which devastated the sides of the mountain for eight miles in length, and afterwards covered the lower flanks of Etna, where they were less steep, together with the plains near the sea, with great deposits of sand, scoriæ, and blocks of lava.

Many absurd stories circulated in Sicily respecting this event; such as that the water was boiling, and that it was vomited from the highest crater; that it was as salt as the sea, and full of marine shells; but these were mere inventions, to which Recupero, although he relates them as tales of the mountaineers, seems to have attached rather too much importance.

Floods of considerable violence have also been produced on Etna by the fall of heavy rains, aided, probably, by the melting of snow. By this cause alone, in 1761, sixty of the inhabitants of Acicatena were killed, and many of their houses swept away.[*]

Glacier covered by a lava-stream.—A remarkable discovery was made on Etna in 1828 of a great mass of ice, preserved for many years, perhaps for centuries, from melting, by the singular accident of a current of red-hot lava having flowed over it. The following are the facts in attestation of a phenomenon which must at first sight appear of so paradoxical a character. The extraordinary heat experienced in the South of Europe, during the summer and autumn of 1828, caused the supplies of snow and ice which had been preserved in the spring of that year, for the use of Catania and the adjoining parts of Sicily and the island of Malta, to fail entirely. Great distress was consequently felt for want of a commodity regarded in those countries as one of the necessaries of life rather than an article of luxury, and the abundance of which contributes in some of the larger cities to the salubrity of the water and the general health of the community. The magistrates of Catania applied to Signor M. Gemmellaro, in the hope that his local knowledge of Etna might enable him to point out some crevice or natural grotto on the mountain, where drift snow was still preserved. Nor were they disappointed; for he had long suspected that a small mass of perennial ice at the foot of the highest cone was part of a large and continuous glacier covered by a lava-current. Having procured a large body of workmen, he quarried into this ice, and proved the super-position of the lava for several hundred yards, so as completely to satisfy himself that nothing but the subsequent flowing of the lava over the ice could account for the position of the glacier. Unfortunately for the geologist, the ice was so extremely hard, and the excavation so expensive, that there is no probability of the operations being renewed.

On the first of December, 1828, I visited this spot, which is on the ıth-east side of the cone, and not far above the Casa Inglese; but ɜ fresh snow had already nearly filled up the new opening, so that had only the appearance of the mouth of a grotto. I do not, wever, question the accuracy of the conclusion of Signor Gem-ıllaro, who, being well acquainted with all the appearances of drift ɔw in the fissures and cavities of Etna, had recognised, even fore the late excavations, the peculiarity of the position of the ice this locality. We may suppose that, at the commencement of the ıption, a deep mass of drift snow had been covered by volcanic ıd showered down upon it before the descent of the lava. A dense atum of this fine dust mixed with scoriæ is well known to be an tremely bad conductor of heat; and the shepherds in the higher gions of Etna are accustomed to provide water for their flocks ring summer, by strewing a layer of volcanic sand a few inches ick over the snow, which effectually prevents the heat of the sun ɔm penetrating.

---

[*] Ferara, Descriz. dell' Etna, p. 116.

Suppose the mass of snow to have been preserved from liquefac-ɔn until the lower part of the lava had consolidated, we may then adily conceive that a glacier thus protected, at the height of ten ousand feet above the level of the sea, would endure as long as the ıows of Mont Blanc, unless melted by volcanic heat from below. hen I visited the great crater in the beginning of winter (December st, 1828), I found the crevices in the interior encrusted with thick e, and in some cases hot vapours were actually streaming out etween masses of ice and the rugged and steep walls of the crater.*

After the discovery of Signor Gemmellaro, it would not be ırprising to find in the cones of the Icelandic volcanos, which are overed for the most part with perpetual snow, repeated alternations f lava-streams and glaciers. We have, indeed, Lieutenant Kendall's ıthority for the fact that Deception Island, in New South Shetland, ıt. 62° 55′ S., is principally composed of alternate layers of volcanic ıhes and ice.†

Origin of the Val del Bove. — It is recorded, as will be stated in ıe history of earthquakes (ch. 29.), that in the year 1772 a great ıbsidence took place on Papandayang, the largest volcano in the land of Java; an extent of ground *fifteen miles in length, and six in readth*, covered by no less than forty villages, was engulphed, and ıe cone lost 4000 feet of its height. In like manner the summit of arguairazo, one of the loftiest of the Andes of Quito, fell in on the 19th uly, 1698; and another mountain of still greater altitude in the same chain called Capac Urcu, a short time before the conquest of America by the Spaniards.

---

* Mr. Nasmyth, the inventor of the eam-hammer, has lately illustrated, by very striking experiment, the non-con-ıctibility of a thin layer of dry sand ıd clay. Into a cauldron of iron one-ırth of an inch thick, lined with sand ıd clay five-eighths of an inch thick, e poured eight tons of melted iron at a hite heat. After the fused metal had sen twenty minutes in the cauldron the palm of the hand could be applied to the outside without inconvenience, and after forty minutes there was not heat enough to singe writing paper. This fact may help us to explain how strata in contact with dikes, or beds of fused matter, have sometimes escaped without perceptible alteration by heat.

† Journ. of Roy. Geograph. Soc. vol. i. p. 64.

It will also be seen in the next chapter that, so late as the year 1822, during a violent earthquake and volcanic eruption in Java, one side of the mountain called Galongoon, which was covered by a dense forest, became an enormous gulf in the form of a semicircle. The new cavity was about midway between the summit and the plain, and surrounded by steep rocks.

Now we might imagine a similar event, or a series of subsidences to have formerly occurred on the eastern side of Etna, although such catastrophes have not been witnessed in modern times, or only on a very trifling scale. A narrow ravine, about a mile long, twenty feet wide, and from twenty to thirty-six in depth, has been formed, within the historical era, on the flanks of the volcano, near the town of Mascalucia; and a small circular tract, called the Cisterna, near the summit, sank down in the year 1792, to the depth of about forty feet, and left on all sides of the chasm a vertical section of the beds, exactly resembling those which are seen in the precipices of the Val del Bove. At some remote periods, therefore, we might suppose more extensive portions of the mountain to have fallen in during great earthquakes.

But we ought not to exclude entirely from our speculations another possibly agency, by which the great cavity may in part at least have been excavated, namely, the denuding action of the sea. Whether its waves may once have had access to the great valley before the ancient portion of Etna was upheaved to its present elevation is a question which will naturally present itself to every geologist. Marine shells have been traced to a height of 800 feet above the base of Etna, and would doubtless be seen to ascend much higher, were not the structure of the lower region of the mountain concealed by floods of lava. We cannot ascertain to what extent a change in the relative level of land and sea may have been carried in this spot, but we know that some of the tertiary strata in Sicily of no ancient date reach a height of 3000 feet, and the marine deposits on the flanks of Etna, full of recent species of shells, may ascend to equal or greater heights. The narrow valley of Calanna leading out of the Val del Bove, and that of San Giacomo lower down, have much the appearance of ravines swept out by aqueous action.

Structure and origin of the cone of Etna. — Our data for framing a correct theory of the manner in which the cone of Etna has acquired its present dimensions and internal structure are very imperfect, because it is on its eastern side only, in the Val del Bove above described, that we see a deep section exposed. Even here we obtain no insight into the interior composition of the mountain beyond a depth of between three and four thousand feet below the base of that highest cone, which has been several times destroyed and renewed. The precipices seen at the head of the Val del Bove, in the escarpment called the Serre del Solfizio, exhibit merely the same series of alternating lavas and breccias which, descending with a general dip towards the sea, form the boundary cliffs of all other parts of the Val del Bove. If then we estimate the height of Etna at about 11,000 feet, we may say that we know from actual observation less than one half of its component materials, assuming it to extend downwards to the level of the sea; namely, first, the highest cone, which is about 1000 feet above its base; and, secondly, the alternations of lava, tuff, and volcanic breccia, which constitute the rocks between the Cisterna, near the base of the upper cone, and the foot of the precipices at the head of the Val del Bove. At the lowest point to which the vertical section extends, there are no signs of any approach to a termination of the purely volcanic mass, which may perhaps penetrate many thousand feet farther downwards. There is, indeed, a rock called Rocca Gianicola, near the foot of the great escarpment, which consists of a large mass between 150 and 200 feet wide, not divided into beds, and almost resembling granite in its structure, although agreeing very closely in mineral composition with the lavas of Etna in general.* This mass may doubtless be taken as a representative of those crystalline or plutonic formations which would be met with in abundance if we could descend to greater depths in the direction of the central axis of the mountain. For a great body of geological evidence leads us to conclude, that rocks of this class result from the consolidation, under great pressure, of melted matter, which has risen up and filled rents and chasms, such, for example, as may communicate with the principal and minor vents of eruption in a volcano like Etna.

But, if we speculate on the nature of the formations which the lava may have pierced in its way upwards, we may fairly presume that a portion of these consist of marine tertiary rocks, like those of the neighbouring Val di Noto, or those which skirt the borders of the Etnean cone, on its southern and eastern sides. Etna may, in fact, have been at first an insular volcano, raising its summit but slightly above the level of the sea; but we have no grounds for concluding that any of the beds exposed in the deep section of the Val del Bove have formed a part of such a marine accumulation. On the contrary, all the usual signs of subaqueous origin are wanting; and even if we believe the foundations of the mountain to have been laid in the sea, we could not expect this portion to be made visible in sections which only proceed downwards from the summit through one half the thickness of the mountain, especially as the highest points attained by the tertiary strata in other parts of Sicily very rarely exceed 3000 feet above the sea.

On the eastern and southern base of Etna, a marine deposit, already alluded to, is traced up to the height of 800 or 1000 feet, before it becomes concealed beneath that covering of modern lavas which is continually extending its limits during successive eruptions, and prevents us from ascertaining how much higher the marine strata may ascend. As the imbedded shells belong almost entirely

* Hoffmann, Geognost. Beobachtungen, p. 701. Berlin, 1839.

to species now inhabiting the Mediterranean, it is evident that there has been here an upheaval of the region at the base of Etna at a very modern period. It is fair, therefore, to infer that the volcanic nucleus of the mountain, partly perhaps of submarine, and partly of subaërial origin, participated in this movement, and was carried up bodily. Now, in proportion as a cone gains height by such a movement, combined with the cumulative effects of eruptions, throwing out matter successively from one or more central vents, the hydrostatic pressure of the columns of lava augments with their increasing height, until the time arrives when the flanks of the cone can no longer resist the increased pressure; and from that period they give way more readily, lateral outbursts becoming more frequent. Hence, independently of any local expansion of the fractured volcanic mass, those general causes by which the modern tertiary strata of a great part of Sicily have been raised to the height of several thousand feet above their original level, would tend naturally to render the discharge of lava and scoriæ from the summit of Etna less copious, and the lateral discharge greater.

If, then, a conical or dome-shaped mass of volcanic materials was accumulated to the height of 4000, or perhaps 7000 feet, before the upward movement began, or, what is much more probable, during the continuance of the upward movement, that ancient mass would not be buried under the products of newer eruptions, because these last would then be poured out chiefly at a lower level.

Since I visited Etna in 1828, M. de Beaumont has published a most valuable memoir on the structure and origin of that mountain, which he examined in 1834*; and an excellent description of it has also appeared in the posthumous work of Hoffmann.†

In M. de Beaumont's essay, in which he has explained his views with uncommon perspicuity and talent, he maintains that all the alternating stony and fragmentary beds, more than 3000 feet thick, which are exposed in the Val del Bove, were formed originally on a surface so nearly flat that the slope never exceeded three degrees. From this horizontal position they were at length heaved up suddenly (d'un seul coup) into a great mountain, to which no important additions have since been made. Prior to this upthrow, a platform is supposed to have existed above the level of the sea, in which various fissures opened; and from these melted matter was poured forth again and again, which spread itself around in thin sheets of uniform thickness. From the same rents issued showers of scoriæ and fragmentary matter, which were spread out so as to form equally uniform and horizontal beds, intervening between the sheets of lava. But although, by the continued repetition of these operations, a vast pile of volcanic matter, 4000 feet or more in thickness, was built up precisely in that region where Etna now rises, and to which nothing similar was produced elsewhere in Sicily, still we are told that Etna was not yet a mountain. No hypothetical diagram has been given to help us to conceive how this great mass of materials of supramarine origin could have been disposed of in horizontal beds, so as not to constitute an eminence towering far above the rest of Sicily; but it is assumed that a powerful force from below at length burst suddenly through the horizontal formation, uplifted it to a considerable height, and caused the beds to be, in many places, highly inclined. This elevatory force was not all expended on a single central point as Von Buch has imagined in the case of Palma, Teneriffe, or Somma, but rather followed for a short distance a linear direction.*

---

* Mém. pour servir, &c. tom. iv. Paris, 1838.

† Geognost. Beobachtungen, &c. Berlin, 1839.

Among other objections that may be advanced against the theory above proposed, I may mention, first, that the increasing number of dikes as we approach the head of the Val del Bove, or the middle of Etna, and the great thickness of lava, scoriæ, and conglomerates in that region, imply that the great centre of eruption was always where it now is, or nearly at the same point, and there must, therefore, have been a tendency, from the beginning, to a conical or dome-shaped arrangement in the ejected materials. Secondly, were we to admit a great number of separate points of eruption, scattered over a plain or platform, there must then have been a great number of cones thrown up over these different vents; and these hills, some of which would probably be as lofty as those now seen on the flanks of Etna, or from 300 to 750 feet in height, would break the continuity of the sheets of lava, while they would become gradually enveloped by them. The ejected materials, moreover, would slope at a high angle on the sides of these cones, and where they fell on the surrounding plain, would form strata thicker near the base of each cone than at a distance.

What then are the facts, it will be asked, to account for which this hypothesis of original horizontality, followed by a single and sudden effort of upheaval, which gave to the beds their present slope, has been invented? M. de Beaumont observes, that in the boundary precipices of the Val del Bove, sheets of lava and intercalated beds of cinders, mixed with pulverulent and fragmentary matter evidently cast out during eruptions, are sometimes inclined at steep angles, varying from 15° to 27°. It is impossible, he says, that the lavas could have flowed originally on planes so steeply inclined, for streams which descend a slope even of 10° form narrow stripes, and never acquire such a compact texture. Their thickness, moreover, always inconsiderable, varies with every variation of steepness, in the declivity down which they flow; whereas, in several parts of the Val del Bove, the sheets of lava are continuous for great distances, in spite of their steep inclination, and are often compact, and perfectly parallel one to the other, even where there are more than 100 beds of interpolated fragmentary matter.

The intersecting dikes also terminate upwards in many instances, at different elevations, and blend (or, as M. de Beaumont terms it, articulate) with sheets of lava, which they meet at right angles. It is

---

* De Beaumont, Mém. pour servir, &c. tom. iv. pp. 187, 188.

therefore assumed that such dikes were the feeders
lava with which they unite, and they are supposed
platform, on the surface of which the melted matt
was at first so flat, that the fluid mass spread fre
every direction, and not towards one point only o
would happen if it had descended the sloping side
argument is ingeniously and plainly put in the fo
"Had the melted matter poured down an inclin
suing from a rent, the sheet of lava would, after c
formed an elbow with the dike, like the upper ba
instead of extending itself on both sides like tha
also contended that a series of sheets of lava, form
dome-shaped mountain, would have been more n
farthest from the central axis, since every dike w
source of a lava-stream, must have poured its con
and never upwards.

In reference to the facts here stated, I may ment
which I saw in the Val del Bove were either vertic
all of them a near approach to the perpendicular
have been the case had they been the feeders of hori
and had they consequently joined them originally
then the dikes, as at *a*, *b*, *c*, fig. 54., ought subsequentl

Fig. 54.



Dikes as they would now appear had they been originally pe

a considerable slope, like the beds which they inter
urge another objection to the views above set forth,
the dikes been linear vents, or orifices of eruption,
the inter-stratified scoriæ and lapilli, as well as
come out of them, and in that case the irregular he
mentary matter around the vents would, as before
turbed that uniform thickness and parallelism of th
de Beaumont describes.

If, however, some of the sheets of lava join the
manner, as to imply that they were in a melted sta
with the contents of the fissures,—a point not easily
the precipices are for the most part inaccessible,—t

---

* Mém. pour servir, tom. iv. p. 149.

of a different interpretation from that proposed by the French geologist. Rents like those before alluded to (p. 399.), which opened in the plain of S. Lio in 1669, filled below with incandescent lava, may have lain in the way of currents of melted matter descending from higher openings. In that case, the matter of the current would have flowed into the fissure and mixed with the lava at its bottom. Numerous open rents of this kind are described by Mr. Dana as having been caused, during a late eruption, in one of the volcanic domes of the Sandwich Islands. They remained open at various heights on the slopes of the great cone, running in different directions, and demonstrate the possibility of future junctions, of slightly inclined lava-streams with perpendicular walls of lava.

To me, therefore, it appears far more easy to explain the uniform thickness and parallelism of so many lavas and beds of fragmentary matter seen in the Val del Bove, by supposing them to have issued successively out of one or more higher vents near the summit of a great dome, than to imagine them to have proceeded from lateral dikes or rents opening in a level plain. In the Sandwich Islands, we have examples of volcanic domes 15,000 feet high, produced by successive outpourings from vents at or near the summit. One of these, Mount Loa, has a slope in all directions, of 6° 30′; another, Mount Kea, a mean inclination of 7° 46′. That their lavas may occasionally consolidate on slopes of 25°, and even more, and still preserve considerable solidity of texture, has been already stated; see above, p. 383.

We know not how large a quantity of modern lava may have been poured into the bottom of the Val del Bove, yet we perceive that eruptions breaking forth near the centre of Etna have already made some progress in filling up this great hollow. Even within the memory of persons now living, the rocks of Musara and Capra have, as before stated, lost much of their height and picturesque grandeur by the piling up of recent lavas round their base (see fig. 51. p. 408.), and the great chasm has intercepted many streams which would otherwise have deluged the fertile region below, as has happened on the side of Catania. The volcanic forces are now labouring, therefore, to repair the breach which subsidence has caused on one side of the great cone; and unless their energy should decline, or a new sinking take place, they may in time efface this inequality. In that event, the restored portion will always be unconformable to the more ancient part, yet it will consist, like it, of alternating beds of lava, scoriæ, and conglomerates, which, with all their irregularities, will have a general slope from the centre and summit of Etna towards the sea.

I shall conclude, then, by remarking that I conceive the general inclination of the alternating stony and fragmentary beds of the Val del Bove, from the axis of Etna towards its circumference or base, and the greater thickness of the volcanic pile as we approach the central parts of the mountain, to be due to the preponderance of eruptions from that centre. These gave rise, from the first, to a dome-shaped mass, which has ever since been increasing in height and area, being fractured again and again by the expansive force of vapours, and the severed parts made to cohere together more firmly after the solidification of the lava with which every open fissure and chasm has been filled. At the same time the cone may have gained a portion of its height by the elevatory effect of such dislocating movements, and the sheets of lava may have acquired in some places a greater, in others a less, inclination than that which at first belonged to them.

But had the mountain been due solely, or even principally, to upheaval, its structure would have resembled that which geologists have so often recognized in certain dome-shaped hills, or elevated regions, which all consider as having been thrust up by a force from below. In this case there is often an elliptical cavity at the summit, due partly to the fracture of the upraised rocks, but still more to aqueous denudation, as they rose out of the sea. The central cavity, or valley, exposes to view the subjacent formation *c*, fig. 55., and the incumbent mass dips away on all sides from the axis, but has no tendency to thin out near the base of the dome, or at *x*, *x*; whereas at this point the volcanic mass terminates (see fig. 56.) and allows the fundamental rock *c* to appear at the surface. In the last diagram the more ordinary case is represented of a great hollow or crater at the summit of the volcanic cone; but instead of this, we have seen that in the case of Etna there is a deep lateral depression, called the Val del Bove, the upper part of which approaches near to the central axis, and the origin of which we have attributed to subsidence.

Fig. 55.



[Non-volcanic protuberance and valley of elevation.

Fig. 56.



Volcanic mountain and crater.

Antiquity of the cone of Etna. — It was before remarked that confined notions in regard to the quantity of past time have tended, more than any other prepossessions, to retard the progress of sound theoretical views in geology *; the inadequacy of our conceptions of the earth's antiquity having cramped the freedom of our speculations in this science, very much in the same way as a belief in the existence of a vaulted firmament once retarded the progress of astronomy. It was not until Descartes assumed the indefinite extent f the celestial spaces, and removed the supposed boundaries of the niverse, that just opinions began to be entertained of the relative istances of the heavenly bodies ; and until we habituate ourselves contemplate the possibility of an indefinite lapse of ages having een comprised within each of the modern periods of the earth's istory, we shall be in danger of forming most erroneous and partial iews in geology.

---

* P. 62, *supra.*

If history had bequeathed to us a faithful record of the eruptions f Etna, and a hundred other of the principal active volcanos of the lobe, during the last three thousand years, — if we had an exact ccount of the volume of lava and matter ejected during that period, nd the times of their production, — we might, perhaps, be able to orm a correct estimate of the average rate of the growth of a volanic cone. For we might obtain a mean result from the comparison f the eruptions of so great a number of vents, however irregular ight be the development of the igneous action in any one of them, if ontemplated singly during a brief period.

It would be necessary to balance protracted periods of inaction gainst the occasional outburst of paroxysmal explosions. Sometimes e should have evidence of a repose of seventeen centuries, like that hich was interposed in Ischia, between the end of the fourth entury B.C., and the beginning of the fourteenth century of our ra.[*] Occasionally a tremendous eruption, like that of Jorullo, would e recorded, giving rise, at once, to a considerable mountain.

If we desire to approximate to the age of a cone such as Etna, we ught first to obtain some data in regard to the thickness of matter hich has been added during the historical era, and then endeavour o estimate the time required for the accumulation of such alternating avas and beds of sand and scoriæ as are superimposed upon each ther in the Val del Bove; afterwards we should try to deduce, from bservations on other volcanos, the more or less rapid increase of urning mountains in all the different stages of their growth.

There is a considerable analogy between the mode of increase of a olcanic cone and that of trees of *exogenous* growth. These trees ugment, both in height and diameter, by the successive application xternally of cone upon cone of new ligneous matter; so that if we ake a transverse section near the base of the trunk, we intersect a uch greater number of layers than nearer to the summit. When ranches occasionally shoot out from the trunk, they first pierce the ark, and then, after growing to a certain size, if they chance to be roken off, they may become inclosed in the body of the tree, as it ugments in size, forming knots in the wood, which are themselves omposed of layers of ligneous matter, cone within cone.

In like manner, a volcanic mountain, as we have seen, consists of a uccession of conical masses enveloping others, while lateral cones, aving a similar internal structure, often project, in the first instance, like branches from the surface of the main cone, and then becoming buried again, are hidden like the knots of a tree.

---

[*] See p. 366.

We can ascertain the age of an oak or pine by counting the number of concentric rings of annual growth seen in a transverse section near the base, so that we may know the date at which the seedling began to vegetate. The Baobab-tree of Senegal (*Adansonia digitata*) is supposed to exceed almost any other in longevity. Adanson inferred that one which he measured, and found to be thirty feet in diameter, had attained the age of 5150 years. Having made an incision to a certain depth, he first counted three hundred rings of annual growth, and observed what thickness the tree had gained in that period. The average rate of growth of younger trees, of the same species, was then ascertained, and the calculation made according to a supposed mean rate of increase. De Candolle considers it not improbable that the celebrated Taxodium of Chapultepec, in Mexico (*Cupressus disticha* Linn.), which is 117 feet in circumference, may be still more aged.†

It is, however, impossible, until more data are collected respecting the average intensity of the volcanic action, to make any thing like an approximation to the age of a cone like Etna; because, in this case, the successive envelopes of lava and scoriæ are not continuous like the layers of wood in a tree, and afford us no definite measure of time. Each conical envelope is made up of a great number of distinct lava-currents and showers of sand and scoriæ, differing in quantity, and which may have been accumulated in unequal periods of time. Yet we cannot fail to form the most exalted conception of the antiquity of this mountain, when we consider that its base is about ninety miles in circumference; so that it would require ninety flows of lava, each a mile in breadth at their termination, to raise the present base of the volcano as much as the average height of one lava-current.

There are no records within the historical era which lead to the opinion that the altitude of Etna has materially varied within the last two thousand years. Of the eighty most conspicuous minor cones which adorn its flanks, only one of the largest, Monti Rossi, has been produced within the times of authentic history. Even this hill, thrown up in the year 1669, although 450 feet in height, only ranks as a cone of second magnitude. Monte Minardo, near Bronte, rises, even now, to the height of 750 feet, although its base has been elevated by the modern lavas and ejections. The dimensions of these larger cones appear to bear testimony to *paroxysms* of volcanic activity, after which we may conclude, from analogy, that the fires of Etna remained dormant for many years—since nearly a century of rest has sometimes followed a violent eruption in the historical era. It must also be remembered, that of the small number of eruptions which occur in a century, one only is estimated to issue from the summit of Etna for every two that proceed from the sides. Nor do all the lateral eruptions give rise to such cones as would be reckoned amongst the smallest of the eighty hills above enumerated; some of them produce merely insignificant monticules, which are soon afterwards buried by showers of ashes.

---

* On the Longevity of Trees, Bibliot. Univ., May, 1831.

How many years then must we not suppose to have been expended in the formation of the eighty cones? It is difficult to imagine that a fourth part of them have originated during the last thirty centuries. But if we conjecture the whole of them to have been formed in twelve thousand years, how inconsiderable an era would this portion of time constitute in the history of the volcano! If we could strip off from Etna all the lateral monticules now visible, together with the lavas and scoriæ that have been poured out from them, and from the highest crater, during the period of their growth, the diminution of the entire mass would be extremely slight: Etna might lose, perhaps, several miles in diameter at its base, and some hundreds of feet in elevation; but it would still be the loftiest of Sicilian mountains, studded with other cones, which would be recalled, as it were, into existence by the removal of the rocks under which they are now buried.

There seems nothing in the deep sections of the Val del Bove to indicate that the lava-currents of remote periods were greater in volume than those of modern times; and there are abundant proofs that the countless beds of solid rock and scoriæ were accumulated as now, in succession. On the grounds, therefore, already explained, we must infer that a mass so many thousand feet in thickness must have required an immense series of ages anterior to our historical periods for its growth; yet the whole must be regarded as the product of a modern portion of the tertiary epoch. Such, at least, is the conclusion that seems to follow from geological data, which show that the oldest parts of the mountain, if not of posterior date to the marine strata around its base, were at least of coeval origin.

Some geologists contend, that the sudden elevation of large continents from beneath the waters of the sea have again and again produced waves which have swept over vast regions of the earth.* But it is clear that no devastating wave has passed over the forest zone of Etna since any of the lateral cones before mentioned were thrown up; for none of these heaps of loose sand and scoriæ could have resisted for a moment the denuding action of a violent flood. To some, perhaps, it may appear that hills of such incoherent materials cannot be of very great antiquity, because the mere action of the atmosphere must, in the course of several thousand years, have obliterated their original forms. But there is no weight in this objection; for the older hills are covered with trees and herbage, which protect them from waste; and in regard to the newer ones, such is the porosity of their component materials, that the rain which falls upon them is instantly absorbed; and for the same reason that the rivers on Etna have a subterranean course, there are none descending the sides of the minor cones.

No sensible alteration has been observed in the form of these cones since the earliest [illegible] of w[illegible]ich there are memorials; and there seems no reason for [illegible] si[illegible] that in the course of the next ten thousand or twenty th[illegible] y[illegible] they will undergo any great alteration in their app[illegible]e, un[illegible] they should be shattered by earthquakes or covered by volcanic [illegible]ctions.

---

* Sedgwick, Anniv. Address to Geol. Soc. p. 35. Feb. 1831.

In other parts of Europe, as in [illegible]avergne and Velay, in France, similar loose cones of sco[illegible] pro[illegible]ly of as high antiquity as the whole mass of Etna, stand un[illegible] at inferior elevations above the level of the sea.

CHAPTER XXVI.

Volcanic eruption in Iceland in 1783—New island thrown up—Lava currents of Skaptár Jokul, in same year—Their immense volume—Eruption of Jorullo in Mexico—Humboldt's theory of the convexity of the plain of Malpais—Eruption of Galongoon in Java—Submarine volcanos—Graham island, formed in 1831—Volcanic archipelagos—Submarine Eruptions in mid-Atlantic—The Canaries—Teneriffe—Cones thrown up in Lancerote, 1730–36—Santorin and its contiguous isles—Barren island in the Bay of Bengal—Mud volcanos—Mineral composition of volcanic products.

Volcanic eruptions in Iceland.—WITH the exception of Etna and Vesuvius, the most complete chronological records of a series of eruptions are those of Iceland, for their history reaches as far back as the ninth century of our era; and, from the beginning of the twelfth century, there is clear evidence that, during the whole period, there has never been an interval of more than forty, and very rarely one of twenty years, without either an eruption or a great earthquake. So intense is the energy of the volcanic action in this region, that some eruptions of Hecla have lasted six years without ceasing. Earthquakes have often shaken the whole island at once, causing great changes in the interior, such as the sinking down of hills, the rending of mountains, the desertion by rivers of their channels, and the appearance of new lakes.* New islands have often been thrown up near the coast, some of which still exist; while others have disappeared, either by subsidences or the action of the waves.

In the interval between eruptions, innumerable hot springs afford vent to subterranean heat, and solfataras discharge copious streams of inflammable matter. The volcanos in different parts of this island are observed, like those of the Phlegræan Fields, to be in activity by turns, one vent often serving for a time as a safety-valve to the rest. Many cones are often thrown up in one eruption, and in this case [illegible] take a linear direction, running generally from north-east to [illegible]h-w[illegible] from the north-eastern part of the island, where the [illegible] Krabla lies, to the promontory Reykianas.

---

* Von Hoff, vol. ii. p. 393.

New island thrown up in 1783.—The convulsions of the year 783 appear to have been more tremendous than any recorded in the aodern annals of Iceland; and the original Danish narrative of the atastrophe, drawn up in great detail, has since been substantiated y several English travellers, particularly in regard to the prodigious xtent of country laid waste, and the volume of lava produced.* About a month previous to the eruption on the mainland, a submarine olcano burst forth in the sea in lat. 63° 25′ N., long. 23° 44′ W., at distance of thirty miles in a south-west direction from Cape Reykianas, and ejected so much pumice, that the ocean was covered rith that substance to the distance of 150 miles, and ships were onsiderably impeded in their course. A new island was thrown up, onsisting of high cliffs, within which fire, smoke, and pumice were mitted from two or three different points. This island was claimed y his Danish Majesty, who denominated it Nyöe, or the New Island; ut before a year had elapsed, the sea resumed its ancient domain, nd nothing was left but a reef of rocks from five to thirty fathoms nder water.

Great eruption of Skaptár Jokul.—Earthquakes which had long een felt in Iceland, became violent on the 11th of June, 1783, when Skaptár Jokul, distant nearly two hundred miles from Nyöe, threw ut a torrent of lava which flowed down into the river Skaptâ, and ompletely dried it up. The channel of the river was between high ocks, in many places from four hundred to six hundred feet in lepth, and near two hundred in breadth. Not only did the lava fill up this great defile to the brink, but it overflowed the adjacent ields to a considerable extent. The burning flood, on issuing from he confined rocky gorge, was then arrested for some time by a deep ake, which formerly existed in the course of the river, between Skaptardal and Aa, which it entirely filled. The current then advanced again, and reaching some ancient lava full of subterraneous averns, penetrated and melted down part of it; and in some places, where the steam could not gain vent, it blew up the rock, throwing ragments to the height of more than 150 feet. On the 18th of June, another ejection of liquid lava rushed from the volcano, which lowed down with amazing velocity over the surface of the first stream. By the damming up of the mouths of some of the tributaries of the Skaptâ, many villages were completely overflowed with water, and hus great destruction of property was caused. The lava, after lowing for several days, was precipitated down a tremendous cataract called Stapafoss, where it filled a profound abyss, which that great waterfall had been hollowing out for ages, and after this, the fiery current again continued its course.

---

* The first narrative of the eruption ras drawn up by Stephenson, then Chief Justice in Iceland, appointed commissioner by the King of Denmark for stimating the damage done to the country, that relief might be afforded to he sufferers. Henderson was enabled o correct some of the measurements given by Stephenson, of the depth, width, and length of the lava currents, by reference to the MS. of Mr. Paulson, who visited the tract in 1794, and examined the lava with attention. (Journal of a Residence in Iceland, &c. p. 229.) Some of the principal facts are also corroborated by Sir William Hooker, in his "Tour in Iceland," vol. ii. p. 128.

On the third of August fresh floods of lava still pouring from the volcano, a new branch was sent off in a different direction; for the channel of the Skaptâ was now so entirely choked up, and every opening to the west and north so obstructed, that the melted matter was forced to take a new course, so that it ran in a south-east direction, and discharged itself into the bed of the river Hverfisfliot, where a scene of destruction scarcely inferior to the former was occasioned. These Icelandic lavas (like the ancient streams which are met with in Auvergne, and other provinces of Central France), are stated by Stephenson to have accumulated to a prodigious depth in narrow rocky gorges; but when they came to wide alluvial plains, they spread themselves out into broad burning lakes, sometimes from twelve to fifteen miles wide, and one hundred feet deep. When the "fiery lake" which filled up the lower portion of the valley of the Skaptâ had been augmented by new supplies, the lava flowed up the course of the river to the foot of the hills from whence the Skaptâ takes its rise. This affords a parallel case to one which can be shown to have happened at a remote era in the volcanic region of the Vivarais in France, where lava issued from the cone of Thueyts, and while one branch ran down, another more powerful stream flowed up the channel of the river Ardêche.

The sides of the valley of the Skaptâ present superb ranges of basaltic columns of older lavas, resembling those which are laid open in the valleys descending from Mont Dor in Auvergne, where more modern lava-currents, on a scale very inferior in magnitude to those of Iceland, have also usurped the beds of the existing rivers. The eruption of Skaptár Jokul did not entirely cease till the end of two years; and when Mr. Paulson visited the tract eleven years afterwards in 1794, he found columns of smoke still rising from parts of the lava, and several rents filled with hot water.*

Although the population of Iceland was very much scattered, and did not exceed fifty thousand, no less than twenty villages were destroyed, besides those inundated by water; and more than nine thousand human beings perished, together with an immense number of cattle, partly by the depredations of the lava, partly by the noxious vapours which impregnated the air, and, in part, by the famine caused by showers of ashes throughout the island, and the desertion of the coasts by the fish.

Immense volume of the lava.—But the extraordinary volume of melted matter produced in this eruption deserves the particular attention of the geologist. Of the two branches, which flowed in nearly opposite directions, the greatest was fifty, and the lesser forty miles in length. The extreme breadth which the Skaptâ branch attained in the low countries was from twelve to fifteen miles, that of the other about seven. The ordinary height of both currents was one hundred feet, but in narrow defiles it sometimes amounted to six hundred. Professor Bischoff has calculated, that, the mass of lava brought up from the subterranean regions by this single eruption "surpassed in magnitude the bulk of Mont Blanc."* But a more distinct idea will be formed of the dimensions of the two streams, if we consider how striking a feature they would now form in the geology of England, had they been poured out on the bottom of the sea after the deposition, and before the elevation of our secondary and tertiary rocks. The same causes which have excavated valleys through parts of our marine strata, once continuous, might have acted with equal force on the igneous rocks, leaving, at the same time, a sufficient portion undestroyed to enable us to discover their former extent. Let us, then, imagine the termination of the Skaptá branch of lava to rest on the escarpment of the inferior and middle oolite, where it commands the vale of Gloucester. The great platform might be one hundred feet thick, and from ten to fifteen miles broad, exceeding any which can be found in Central France. We may also suppose great tabular masses to occur at intervals, capping the summit of the Cotswold Hills between Gloucester and Oxford, by Northleach, Burford, and other towns. The wide valley of the Oxford clay would then occasion an interruption for many miles; but the same rocks might recur on the summit of Cumnor and Shotover Hills, and all the other oolitic eminences of that district. On the chalk of Berkshire, extensive plateaus, six or seven miles wide, would again be formed; and, lastly crowning the highest sands of Highgate and Hampstead, we might behold some remnants of the current five or six hundred feet in thickness, causing those hills to rival, or even to surpass, in height, Salisbury Craigs and Arthur's Seat.

---

* Henderson's Journal, &c. p. 228.

The distance between the extreme points here indicated would not exceed ninety miles in a direct line; and we might then add, at the distance of nearly two hundred miles from London, along the coast of Dorsetshire, and Devonshire, for example, a great mass of igneous rocks, to represent those of contemporary origin, which were produced beneath the level of the sea, where the island of Nyöe rose up.

Volume of ancient and modern flows of lava compared. — Yet, gigantic as must appear the scale of these modern volcanic operations, we must be content to regard them as perfectly insignificant in comparison to currents of the primeval ages, if we embrace the theoretical views of many geologists, which were not inaccurately expressed by the late Professor Alexander Brongniart, when he declared that "aux époques gèognostiques anciennes, tous les phénomènes géologiques se passoient dans des dimensions *centuples* de celles qu'i présentent aujourd'hui."† Had Skaptár Jokul, therefore, been volcano of the olden time, it would have poured forth lavas a single eruption a hundred times more voluminous than those wh were witnessed by the present generation in 1783. But it ma the contrary, be affirmed that, among the older formations, no igneous rock of such colossal magnitude has yet been met with; nay, it would be most difficult to point out a mass of ancient date (distinctly referable to a single eruption) which would even rival in volume the matter poured out from Skaptár Jokul in 1783.

---

* Jameson's Phil. Journ. vol. xxvi. p. 291.

† Tableau des Terrains qui cor l'Ecorce du Globe, p. 52. Paris

Eruption of Jorullo in 1759. — As another example of the stupendous scale of modern volcanic eruptions, I may mention that of Jorullo in Mexico, in 1759. The great region to which this mountain belongs has already been described. The plain of Malpais forms part of an elevated platform, between two and three thousand feet above the level of the sea, and is bounded by hills composed of basalt, trachyte, and volcanic tuff, clearly indicating that the country had previously, though probably at a remote period, been the theatre of igneous action. From the era of the discovery of the New World to the middle of the last century, the district had remained undisturbed, and the space, now the site of the volcano, which is thirty-six leagues distant from the nearest sea, was occupied by fertile fields of sugar-cane and indigo, and watered by the two brooks Cuitimba and San Pedro. In the month of June, 1759, hollow sounds of an alarming nature were heard, and earthquakes succeeded each other for two months, until, at the end of September, flames issued from the ground, and fragments of burning rocks were thrown to prodigious heights. Six volcanic cones, composed of scoriæ and fragmentary lava, were formed on the line of a chasm which ran in the direction from N.N.E. to S.S.W. The least of these cones was 300 feet in height; and Jorullo, the central volcano, was elevated 1600 feet above the level of the plain. It sent forth great streams of basaltic lava, containing included fragments of granitic rocks, and its ejections did not cease till the month of February, 1760.*

Humboldt visited the country more than forty years after this occurrence, and was informed by the Indians, that when they returned, long after the catastrophe, to the plain, they found the ground uninhabitable from the excessive heat. When he himself visited the place, there appeared, around the base of the cones, and spreading from them, as from a centre, over an extent of four square miles, a mass of matter of a convex form, about 550 feet high at its junction with the cones, and gradually sloping from them in all directions towards the plain. This mass was still in a heated state, the tempe-

Fig. 57.



a, Summit of Jurullo. b, c, Inclined plane sloping at an angle of 6° from the base of the cones.

ure in the fissures being on the decrease from year to year, but in
) it was still sufficient to light a cigar at the depth of a few inches.
his slightly convex protuberance, the slope of which must form

---

* Daubeny on Volcanos, p. 337.

an angle of about 6° with the horizon, were thousands of flattish conical mounds, from six to nine feet high, which, as well as large fissures traversing the plain, acted as fumeroles, giving out clouds of sulphurous acid and hot aqueous vapour. The two small rivers before mentioned disappeared during the eruption, losing themselves below the eastern extremity of the plain, and reappearing as hot springs at its western limit.

Cause of the convexity of the plain of Malpais. — Humboldt attributed the convexity of the plain to inflation from below; supposing the ground, for four square miles in extent, to have risen up in the shape of a bladder to the elevation of 550 feet above the plain in the highest part. But Mr. Scrope has suggested that the phenomena may be accounted for far more naturally, by supposing that lava flowing simultaneously from the different orifices, and principally from Jorullo, united into a sort of pool or lake. As they were poured forth on a surface previously flat, they would, if their liquidity was not very great, remain thickest and deepest near their source, and diminish in bulk from thence towards the limits of the space which they covered. Fresh supplies were probably emitted successively during the course of an eruption which lasted more than half a year; and some of these, resting on those first emitted, might only spread to a small distance from the foot of the cone, where they would necessarily accumulate to a great height. The average slope of the great dome-shaped volcanos of the Sandwich Islands, formed almost exclusively of lava, with scarce any scoriæ, is between 6° 30′ and 7° 46′, so that the inclination of the convex mass around Jorullo, if we adopt Mr. Scrope's explanation (see fig. 57.), is quite in accordance with the known laws which govern the flow of lava.

The showers, also, of loose and pulverulent matter from the six craters, and principally from Jorullo, would be composed of heavier and more bulky particles near the cones, and would raise the ground at their base, where, mixing with rain, they might have given rise to the stratum of black clay, which is described as covering the lava. The small conical mounds (called "hornitos," or little ovens) may resemble those five or six small hillocks which existed in 1823 on the Vesuvian lava, and sent forth columns of vapour, having been produced by the disengagement of elastic fluids heaving up small dome-shaped masses of lava. The fissures mentioned by Humboldt as of frequent occurrence, are such as might naturally accompany the consolidation of a thick bed of lava, contracting as it congeals; and the disappearance of rivers is the usual result of the occupation of the lower part of a valley or plain by lava, of which there are many beautiful examples in the old lava-currents of Auvergne. The heat of the "hornitos" is stated to have diminished from the first; and Mr. Bullock, who visited the spot many years after Humboldt, found the temperature of the hot spring very low,—a fact which seems clearly to indicate the gradual congelation of a subjacent bed of lava, which from its immense thickness may have been enabled to retain its heat for half a century. The reader may be reminded, that when we thus suppose the lava near the volcano to have been, together with the ejected ashes, more than five hundred feet in depth, we merely assign a thickness which the current of Skaptár Jokul attained in some places in 1783.

Hollow sound of the plain when struck. — Another argument adduced in support of the theory of inflation from below, was, the hollow sound made by the steps of a horse upon the plain; which, however, proves nothing more than that the materials of which the convex mass is composed are light and porous. The sound called "rimbombo" by the Italians is very commonly returned by *made ground* when struck sharply; and has been observed not only on the sides of Vesuvius and other volcanic cones where there is a cavity below, but in such regions as the Campagna di Roma, composed in a great measure of tuff and porous volcanic rocks. The reverberation, however, may perhaps be assisted by grottos and caverns, for these may be as numerous in the lavas of Jorullo as in many of those of Etna; but their existence would lend no countenance to the hypothesis of a great arched cavity, four square miles in extent, and in the centre 550 feet high.*

No recent eruptions of Jorullo.—In a former edition I stated that I had been informed by Captain Vetch, that in 1819 a tower at Guadalaxara was thrown down by an earthquake, and that ashes, supposed to have come from Jorullo, fell at the same time at Guanaxuato, a town situated 140 English miles from the volcano. But Mr. Burkhardt, a German director of mines, who examined Jorullo in 1827, ascertained that there had been no eruption there since Humboldt's visit in 1803. He went to the bottom of the crater, and observed a slight evolution of sulphurous acid vapours, but the "hornitos" had entirely ceased to send forth steam. During the twenty-four years intervening between his visit and that of Humboldt, vegetation had made great progress on the flanks of the new hills, the rich soil of the surrounding country was once more covered with luxuriant crops of sugar-cane and indigo, and there was an abundant growth of natural underwood on all the uncultivated tracts.†

Galongoon, Java, 1822.—The mountain of Galongoon (or Galung Gung) was in 1822 covered by a dense forest, and situated in a fruitful and thickly-peopled part of Java. There was a circular hollow at its summit, but no tradition existed of any former eruption. In July, 1822, the waters of the river Kunir, one of those which flowed from its flanks, became for a time hot and turbid. On the 8th of October following a loud explosion was heard, the earth shook, and immense columns of hot water and boiling mud, mixed with burning brimstone, ashes, and lapilli, of the size of nuts, were projected from the mountain like a water-spout, with such prodigious violence that large quantities fell beyond the river Tandoi, which is forty miles distant. Every valley within the range of this eruption became filled with a burning torrent, and the rivers, swollen with hot water and mud, overflowed their banks, and carried away great numbers of the people, who were endeavouring to escape, and the bodies of cattle, wild beasts, and birds. A space of twenty-four miles between the mountain and the river Tandoi was covered to such a depth with bluish mud that people were buried in their houses, and not a trace of the numerous villages and plantations throughout that extent was visible. Within this space the bodies of those who perished were buried in mud and concealed, but near the limits of the volcanic action they were exposed, and strewed over the ground in great numbers, partly boiled and partly burnt.

---

* See Scrope on Volcanos, p. 267.

† Leonhard and Bronn's Neues Jahrbuch, 1835, p. 36.

It was remarked, that the boiling mud and cinders were projected with such violence from the mountain, that while many remote villages were utterly destroyed and buried, others much nearer the volcano were scarcely injured.

The first eruption lasted nearly five hours, and on the following days the rain fell in torrents, and the rivers densely charged with mud, deluged the country far and wide. At the end of four days (October 12th) a second eruption occurred more violent than the first, in which hot water and mud were again vomited, and great blocks of basalt were thrown to the distance of seven miles from the volcano. There was at the same time a violent earthquake, and in one account it is stated that the face of the mountain was utterly changed, its summits broken down, and one side, which had been covered with trees, became an enormous gulf in the form of a semicircle. This cavity was about midway between the summit and the plain, and surrounded by steep rocks, said to be newly heaped up during the eruption. New hills and valleys are said to have been formed, and the rivers Banjarang and Wulan changed their course, and in one night (October 12th) 2000 persons were killed.

The first intimation which the inhabitants of Bandong received of this calamity on the 8th of October, was the news that the river Wulna was bearing down into the sea the dead bodies of men, and the carcasses of stags, rhinoceroses, tigers, and other animals. The Dutch painter Payen determined to travel from thence to the volcano, and he found that the quantity of the ashes diminished as he approached the base of the mountain. He alludes to the altered form of the mountain after the 12th, but does not describe the new semicircular gulf on its side.

The official accounts state that 114 villages were destroyed, and above 4000 persons killed.*

Submarine volcanos. — Although we have every reason to believe that volcanic eruptions as well as earthquakes are common in the bed of the sea, it was not to be expected that many opportunities would occur to scientific observers of witnessing the phenomena. The crews of vessels have sometimes reported that they have seen in different places sulphurous smoke, flame, jets of water, and steam, rising up from the sea, or they have observed the waters greatly discoloured, and in a state of violent agitation as if boiling. New shoals have also been encountered, or a reef of rocks just emerging above the surface, where previously there was always supposed to have been deep water. On some few occasions the gradual formation of an island by a submarine eruption has been observed, as that of Sabrina, in the year 1811, off St. Michael's in the Azores. The throwing up of ashes in that case, and the formation of a cone about three hundred feet in height, with a crater in the centre, closely resembled the phenomena usually accompanying a volcanic eruption on land. Sabrina was soon washed away by the waves. Previous eruptions in the same part of the sea were recorded to have happened in 1691 and 1720. The rise of Nyöe, also, a small island off the coast of Iceland, in 1783, has already been alluded to; and another volcanic isle was produced by an eruption near Reikiavig, on the same coast, in June, 1830.*

---

* Van der Boon Mesch, de Incendiis Montium Javæ, &c. Lugd. Bat. 1826; and Official Report of the President, Baron Van der Capellen; also, Von Buch, Iles Canar. p. 424.

Graham Island†, 1831.—We have still more recent and minute information respecting the appearance, in 1831, of a new volcanic island in the Mediterranean, between the S. W. coast of Sicily and that projecting part of the African coast where ancient Carthage stood. The site of the island was not any part of the great shoal, or bank, called "Nerita," as was first asserted, but a spot where Captain W. H. Smyth had found, in his survey a few years before, a depth of more than one hundred fathoms' water.‡

The position of the island (lat. 37° 8′ 30″ N., long. 12° 42′ 15″ E.) was about thirty miles S. W. of Sciacca, in Sicily, and thirty-three miles N. E. of Pantellaria.§ On the 28th of June, about a fortnight before the eruption was visible, Sir Pulteney Malcolm, in passing over the spot in his ship, felt the shocks of an earthquake, as if he had struck on a sand-bank; and the same shocks were felt on the west coast of Sicily, in a direction from S. W. to N. E. About the 10th of July, John Corrao, the captain of a Sicilian vessel, reported that, as he passed near the place, he saw a column of water like a water-spout, sixty feet high, and 800 yards in circumference, rising from the sea, and soon afterwards a dense steam in its place, which ascended to the height of 1800 feet. The same Corrao, on his return from Girgenti, on the 18th of July, found a small island, twelve feet high with a crater in its centre, ejecting volcanic matter, and immense columns of vapour; the sea around being covered with floating cinders

---

* Journ. de Géol. tome i.

† In a former edition, I selected the name of Sciacca out of seven which had been proposed; but the Royal and Geographical Societies have now adopted Graham Island; a name given by Capt. Senhouse, R. N., the first who succeeded in landing on it. The seven rival names are Nerita, Ferdinanda, Hotham, Graham, Corrao, Sciacca, Julia. As the isle was visible for only about three months, this is an instance of a wanton multiplication of synonyms which has scarcely ever been outdone even in the annals of zoology and botany.

‡ Phil. Trans. 1832, p. 255.

§ Journ. of Roy. Geograph. Soc. 1830–31.

Fig. 58.



orm of the cliffs of Graham Island, as seen from S.S.E., distant one mile, 7th August, 1831.*

l dead fish. The scoriæ were of a chocolate colour, and the water ich boiled in the circular basin, was of a dingy red. The eruption

Fig. 59.



View of the interior of Graham Island, 29th Sept. 1831.

tinued with great violence to the end of the same month; at which e the island was visited by several persons, and among others by

Fig. 60.



Graham Island, 29th Sept. 1831.†

---

* Phil. Trans., part. ii., 1832, reduced m drawings by Captain Wodehouse, N.

† In the annexed sketch (fig. 60.), wn by M. Joinville, who accompanied M. C. Prevost, the beds seem to slope towards the centre of the crater; but I am informed by M. Prevost that these lines were not intended by the artist to represent the dip of the beds.

Capt. Swinburne, R. N., and M. Hoffmann, the Prussian geologist. It was then from fifty to ninety feet in height, and three quarters of a mile in circumference. By the 4th of August it became, according to some accounts, above 200 feet high, and three miles in circumference; after which it began to diminish in size by the action of the waves, and was only two miles round on the 25th of August; and on the 3rd of September, when it was carefully examined by Captain Wodehouse, only three-fifths of a mile in circumference; its greatest height being then 107 feet. At this time the crater was about 780 feet in circumference. On the 29th of September, when it was visited by Mons. C. Prevost, its circumference was reduced to about 700 yards. It was composed entirely of incoherent ejected matter, scoriæ, pumice, and lapilli, forming regular strata, some of which are described as having been parallel to the steep inward slope of the crater, while the rest were inclined outwards, like those of Vesuvius.* When the arrangement of the ejected materials has been determined by their falling continually on two steep slopes, that of the external cone and that of the crater, which is always a hollow inverted cone, a transverse section would probably resemble that given in the annexed figure (61.). But when I visited Vesuvius, in 1828, I saw no beds of scoriæ inclined towards the axis of the cone. (See fig. 45. p. 381.) Such may have once existed; but the explosions or subsidences, or whatever causes produced the great crater of 1822, had possibly destroyed them.

Fig. 61.



Few of the pieces of stone thrown out from Graham Island exceeded a foot in diameter. Some fragments of dolomitic limestone were intermixed; but these were the only non-volcanic substances. During the month of August, there occurred on the S. W. side of the new island a violent ebullition and agitation of the sea, accompanied by the constant ascension of a column of dense white steam, indicating the existence of a second vent at no great depth from the surface. Towards the close of October, no vestige of the crater remained, and the island was nearly levelled with the surface of the ocean, with the exception, at one point, of a small monticule of sand and scoriæ. It was reported that, at the commencement of the year following (1832), there was a depth of 150 feet where the island had been: but this account was quite erroneous; for in the early part of that year Captain Swinburne found a shoal and discoloured water there, and towards the end of 1833 a dangerous reef existed of an oval figure, about three-fifths of a mile in extent. In the centre was a black rock, of the diameter of about twenty-six fathoms, from nine to eleven feet under water; and round this rock are banks of black ıic stones and loose sand. At the distance of sixty fathoms this central mass, the depth increased rapidly. There was also ond shoal at the distance of 450 feet S. W. of the great reef, fifteen feet water over it, also composed of rock, surrounded by sea. We can scarcely doubt that the rock in the middle of the reef is solid lava, which rose up in the principal crater, and the second shoal marks the site of the submarine eruption ved in August, 1831, to the S. W. of the island.

---

* See Memoir by M. C. Prevost, Ann. des Sci. Nat. tom. xxiv.

om the whole of the facts above detailed, it appears that a hill hundred feet or more in height was formed by a submarine nic vent, of which the upper part (only about two hundred feet emerged above the waters, so as to form an island. This cone have been equal in size to one of the largest of the lateral nos on the flanks of Etna, and about half the height of the tain Jorullo in Mexico, which was formed in the course of nine hs, in 1759. In the centre of the new volcano a large cavity kept open by gaseous discharges, which threw out scoriæ; and lava probably rose up in this cavity. It is not uncommon for subsidiary craters to open near the summit of a cone, and one ese may have been formed in the case of Graham Island; a vent ps, connected with the main channel of discharge which gave ge in that direction to elastic fluids, scoriæ, and melted lava. It not appear that, either from this duct, or from the principal there was any overflowing of lava; but melted rock may have d from the flanks or base of the cone (a common occurrence nd), and may have spread in a broad sheet over the bottom of ea.

e dotted lines in the annexed figure are an imaginary restoration upper part of the cone, now removed by the waves: the strong represent the part of the volcano which is still under water: in ntre is a great column, or dike, of solid lava, two hundred feet ameter, supposed to fill the space by which the gaseous fluids and on each side of the dike is a stratified mass of scoriæ and nentary lava. The solid nucleus of the reef, where the black is now found, withstands the movements of the sea; while the unding loose tuffs are cut away to a somewhat lower level. In nanner the lava, which was the lowest part of the island, or, to more correctly, which scarcely ever rose above the level of the

Fig. 62.



Supposed section of Graham Island. (C. Maclaren.*)

---

* Geol. of Fife and the Lothians, p. 41. Edin. 1839.

sea when the island existed, has now become the highest point in the reef.

No appearances observed, either during the eruption or since the island disappeared, give the least support to the opinion promulgated by some writers, that part of the ancient bed of the sea had been lifted up bodily.

The solid products, says Dr. John Davy, whether they consisted of sand, light cinders, or vesicular lava, differed more in form than in composition. The lava contained augite; and the specific gravity was 2·07 and 2·70. When the light spongy cinder, which floated on the sea, was reduced to fine powder by trituration, and the greater part of the entangled air got rid of, it was found to be of the specific gravity 2·64; and that of some of the sand which fell in the eruption was 2·75*; so that the materials equalled ordinary granites in weight and solidity. The only gas evolved in any considerable quantity was carbonic acid.†

Submarine eruptions in mid-Atlantic.—In the Nautical Magazine for 1835, p. 642., and for 1838, p. 361., and in the Comptes Rendus, April, 1838, accounts are given of a series of volcanic phenomena, earthquakes, troubled water, floating scoriæ and columns of smoke, which have been observed at intervals since the middle of the last century, in a space of open sea between longitudes 20° and 22° west, about half a degree south of the equator. These facts, says Mr. Darwin, seem to show, that an island or an archipelago is in process of formation in the middle of the Atlantic: a line joining St. Helena and Ascension would, if prolonged, intersect this slowly nascent focus of volcanic action.‡ Should land be eventually formed here, it will not be the first that has been produced by igneous action in this ocean since it was inhabited by the existing species of testacea. At Porto Praya in St. Jago, one of the Azores, a horizontal, calcareous stratum occurs, containing shells of *recent* marine species, covered by a great sheet of basalt eighty feet thick.§ It would be difficult to estimate too highly the commercial and political importance which a group of islands might acquire, if in the next two or three thousand years they should rise in mid-ocean between St. Helena and Ascension.

CANARY ISLANDS.

Eruption in Lancerote, 1730 *to* 1736.—The effects of an eruption which happened in Lancerote, one of the Canary Islands, between the years 1730 and 1736, were very remarkable; and a detailed description has been published by Von Buch, who had an opportunity, when he visited that island in 1815, of comparing the accounts transmitted to us of the event, with the present state and geological appearances of the country.‖ On the 1st of September, 1730, the earth split open on a sudden two leagues from Yaira. In one night a considerable hill of ejected matter was thrown up; and, a few days later, another vent opened, and gave out a lava-stream, which overran Chinanfaya and other villages. It flowed first rapidly, like water, but became afterwards heavy and slow, like honey. On the 7th of September an immense rock was protruded from the bottom of the lava with a noise like thunder, and the stream was forced to change its course from N. to N.W., so that St. Catalina and other villages were overflowed.

---

* Phil. Trans. 1832, p. 243.

† Ibid. p. 249.

‡ Darwin's Volcanic Islands, p. 92.

§ Ibid. p. 6.

‖ This account was principally derived by Von Buch from the MS. of Don Andrea Lorenzo Curbelo, curate of Yaira, the point where the eruption began.—Ueber einen vulcanischen Ausbruch auf der Insel Lanzerote.

Whether this mass was protruded by an earthquake, or was a mass of ancient lava, blown up like that before mentioned in 1783 in Iceland, is not explained.

On the 11th of September more lava flowed out, and covered the village of Maso entirely, and for the space of eight days precipitated itself with a horrible roar into the sea. Dead fish floated on the waters in indescribable multitudes, or were thrown dying on the shore. After a brief interval of repose, three new openings broke forth immediately from the site of the consumed St. Catalina, and sent out an enormous quantity of lapilli, sand, and ashes. On the 28th of October the cattle throughout the whole country dropped lifeless to the ground, suffocated by putrid vapours, which condensed and fell down in drops. On the 1st of December a lava-stream reached the sea, and formed an island, round which dead fish were strewed.

Number of cones thrown up. — It is unnecessary here to give the details of the overwhelming of other places by fiery torrents, or of a storm which was equally new and terrifying to the inhabitants, as they had never known one in their country before. On the 10th of January, 1731, a high hill was thrown up, which, on the same day, precipitated itself back again into its own crater; fiery brooks of lava flowed from it to the sea. On the 3rd of February a new cone arose. Others were thrown up in March, and poured forth lava-streams. Numerous other volcanic cones were subsequently formed in succession, till at last their number amounted to about thirty. In June, 1731, during a renewal of the eruptions, all the banks and shores in the western part of the island were covered with dying fish, of different species, some of which had never before been seen. Smoke and flame arose from the sea, with loud detonations. These dreadful commotions lasted without interruption for *five successive years*, so that a great emigration of the inhabitants became necessary.

Their linear direction.—As to the height of the new cones, Von Buch was assured that the formerly great and flourishing St. Catalina lay buried under hills 400 feet in height; and he observes that the most elevated cone of the series rose 600 feet above its base, and 1378 feet above the sea, and that several others were nearly as high. The new vents were all arranged *in one line*, about two geographical miles long, and in a direction nearly east and west. If we admit the probability of Von Buch's conjecture, that these vents opened along the line of a cleft, it seems necessary to suppose that this subterranean fissure was only prolonged upwards to the surface by degrees, and that the rent was narrow at first, as is usually the case with fissures caused by earthquakes. Lava and elastic fluids might escape from some point on the rent where there was least resistance, till, the first aperture becoming obstructed by ejections and the consolidation of lava, other orifices burst open in succession along the line of the original fissure. Von Buch found that each crater was lowest on that side on which lava had issued; but some craters were not breached, and were without any lava-streams. In one of these were open fissures, out of which hot vapours rose, which in 1815 raised the thermometer to 145° Fahrenheit, and was probably at the boiling point lower down. The exhalations seemed to consist of aqueous vapour; yet they could not be pure steam, for the crevices were encrusted on either side by siliceous sinter (an opal-like hydrate of silica of a white colour), which extended almost to the middle. This important fact attests the length of time during which chemical processes continue after eruptions, and how open fissures may be filled up laterally by mineral matter, sublimed from volcanic exhalations. The lavas of this eruption covered nearly a third of the whole island, often forming on slightly inclined planes great horizontal sheets several square leagues in area, resembling very much the basaltic platforms of Auvergne.

Pretended distinction between ancient and modern lavas.—One of the new lavas was observed to contain masses of olivine of an olive-green colour, resembling those which occur in one of the lavas of the Vivarais. Von Buch supposes the great crystals of olivine to have been derived from a previously existing basalt melted up by the new volcanos; but we have scarcely sufficient data to bear out such a conjecture. The older rocks of the island consist, in a great measure, of that kind of basaltic lava called dolerite, sometimes columnar, and partly of common basalt and amygdaloid. Some recent lavas assumed, on entering the sea, a prismatic form, and so much resembled the older lavas of the Canaries, that the only geological distinction which Von Buch appears to have been able to draw between them was, that they did not alternate with conglomerates, like the ancient basalts. Some modern writers have endeavoured to discover, in the abundance of these conglomerates, a proof of the dissimilarity of the volcanic action in ancient and modern times; but this character is more probably attributable to the difference between submarine operations and those on the land. All the blocks and imperfectly rounded fragments of lava, transported, during the intervals of eruption, by rivers and torrents, into the adjoining sea, or torn by the continued action of the waves from cliffs which are undermined, must accumulate in stratified breccias and conglomerates, and be covered again and again by other lavas. This is now taking place on the shores of Sicily, between Catania and Trezza, where the sea breaks down and covers the shore with blocks and pebbles of the modern lavas of Etna; and on parts of the coast of Ischia, where numerous currents of trachyte are in like manner undermined in lofty precipices. So often, then, as an island is raised in a volcanic archipelago by earthquakes from the deep, the fundamental and (relatively to all above) the oldest lava will often be distinguishable from those formed by subsequent eruptions on dry land, by their alternation with beds of sandstone and fragmentary rocks.

The supposed want of identity, then, between the volcanic phenomena of different epochs resolves itself partly at least into the marked difference between the operations simultaneously in progress, above and below the waters. Such, indeed, is the source, as was before stated in the First Book (Chap. V.), of many of our strongest theoretical prejudices in geology. No sooner do we study and endeavour to explain submarine appearances, than we feel, to use a common expression, out of our element; and unwilling to concede that our extreme ignorance of processes now continually going on can be the cause of our perplexity, we take refuge in a "pre-existent order of nature."

Recent formation of oolitic travertin in Lancerote.—Throughout a considerable part of Lancerote, the old lavas are covered by a thin stratum of limestone, from an inch to two feet in thickness. It is of a hard stalactitic nature, sometimes oolitic, like the Jura limestone, and contains fragments of lava and terrestrial shells, chiefly helices and spiral bulimi. It sometimes rises to the height of 800 feet above the level of the sea. Von Buch imagines that this remarkable super-stratum has been produced by the furious north-west storms, which in winter drive the spray of the sea in clouds over the whole island; from whence calcareous particles may be deposited stalactitically. Mr. Darwin informs me that he found a limestone in St. Helena, the harder parts of which correspond precisely to the stone of Lancerote. He attributes the origin of this rock in St. Helena not to the spray of the sea, but to drifting by violent winds of the finer particles of shells from the sea-beach. Some parts of this drift are subsequently dissolved by atmospheric moisture, and re-deposited, so as to convert calcareous sand into oolite.

Recent eruption in Lancerote.—From the year 1736 to 1815, when Von Buch visited Lancerote, there had been no eruption; but, in August, 1824, a crater opened near the port of Rescif, and formed by its ejections, in the space of twenty-four hours, a considerable hill. Violent earthquakes preceded and accompanied this eruption.*

Teneriffe.—The Peak of Teneriffe is about 12,000 feet high, and stands, says Von Buch, like a tower encircled by its fosse and bastion. The bastion consists, like the semicircular escarpment of Somma turned towards Vesuvius, of precipitous cliffs, composed of trachyte, basalt, coarse conglomerates, and tuffs, traversed by volcanic dikes, mostly vertical, and of basalt. These cliffs vary in height from 1000 to 1800 feet, and are supposed by Von Buch to have been heaved up into their present position by a force exerted from below, in accordance with the theory proposed by the same author for the origin of the cones of Vesuvius and Etna. According to the observations of M. Deville in 1839*, the trachytes are often granitoid in their aspect, and contain instead of glassy felspar the allied mineral called oligoclase, which had been previously considered as characteristic of more ancient igneous rocks. The same traveller supposes, although he found no limestone or trace of fossils in any of the rocks of Teneriffe, that the alternating trachytes and trachytic conglomerates originated beneath the sea. If this opinion be correct, and it is at least very probable, geologists may still speculate on two modes in which the mass of the island acquired its present form and elevation above the sea. 1st. The advocates of Von Buch's crater-of-elevation hypothesis may imagine that a succession of horizontally super-imposed beds were upheaved by a sudden movement, and tilted so as to dip in all directions outwards from the centre of a new dome-shaped eminence, in the middle of which a large opening or bowl-shaped cavity was produced. 2dly. Or according to the theory which to me appears preferable, a submarine hill in the form of a flattened dome may have gradually accumulated, partly below the waters and partly above by the continued outpouring of sheets of lava and the ejection of ashes from a central orifice. In this case the dikes would represent the fissures, which were filled during successive eruptions, and the original inclination of the beds may have been increased by the distension and upheaval of the mass during reiterated convulsions, acting most forcibly at or near the channel of discharge, which would become partially sealed up with lava from time to time, and then be burst open again during eruptions. At length the whole island may have been raised bodily out of the sea by a gradual upward movement.

---

* Férussac, Bulletin des Sci. Nat. tome v. p. 45. 1825.

Whatever theory we adopt, we must always explain the abrupt termination of the dikes and layers of trachyte and basalt in the steep walls of the escarpments surrounding the great crater by supposing the removal of part of the materials once prolonged farther inward toward the centre. If, according to the elevation-crater hypothesis, a series of sheets of lava and ashes originally spread over a level and even surface have been violently broken and uplifted, why do not the opposite walls of the chasm correspond in such a manner as to imply by their present outline that they were formerly united? It is evident that the precipices on opposite sides of the crateriform hollow would not fit if brought together, there being no projecting masses in one wall to enter into indentations in the other, as would happen with the sides of many mineral veins, trap-dikes, and faults, could we extract the intrusive matter now separating them, and reunite the rocks which have been fractured and disjoined.

The highest crater of the peak has merely disengaged sulphureous vapours ever since it has been known to Europeans; but an eruption happened in June, 1798, not far from the summit, and others are recorded, which poured out streams of lava from great heights, besides many which have broken out nearer the level of the sea. All these, however, seem to be dependent on one great centre of eruption, or on that open channel communicating between the interior of the earth and the atmosphere, which terminates in the highest crater of the peak.

---

* Comptes Rendus Acad. Sci. Paris, Juin, 1846.

We may consider Teneriffe, then, as having been from a remote period the principal and habitual vent of the volcanic archipelago of the Canaries. The discharges which have taken place in the contiguous isles of Palma, Lancerote, and the rest, may be of a subsidiary kind, and have probably been most frequent and violent when the greater crater has been partially sealed up, just as the violent eruptions of Ischia or that of Monte Nuovo coincided with the dormant state of Vesuvius.

SANTORIN.

The Gulf of Santorin, in the Grecian Archipelago, has been for two thousand years a scene of active volcanic operations. The largest of the three outer islands of the group (to which the general name of Santorin is given) is called Thera (or sometimes Santorin), and forms more than two-thirds of the circuit of the gulf (see Map, fig. 63., p. 442.). The length of the exterior coast-line of this and the other two islands named Therasia and Aspronisi, taken together, amounts to about thirty miles, and that of the inner coast-line of the same islands to about eighteen miles. In the middle of the gulf are three other islands, called the Little, the New, and the Old "Kaimenis," or "Burnt Islands." The accompanying map has been reduced from a recent survey executed in 1848 by Captain Graves, R. N., and shortly to be published by the Admiralty.

Pliny informs us that the year 186, B. C., gave birth to the Old Kaimeni, also called Hiera, or the "Sacred Isle," and in the year 19 of our era "Thia" (the Divine) made its appearance above water, and was soon joined by subsequent eruptions to the older island, from which it was only 250 paces distant. The Old Kaimeni also increased successively in size in 726 and in 1427. A century and a half later, in 1573, another eruption produced the cone and crater called Micra-Kaimeni, or "the Small Burnt Island." The next great event which we find recorded occurred in 1650, when a submarine outbreak violently agitated the sea, at a point three and a half miles to the N. E. of Thera, and which gave rise to a shoal (see A in the map) carefully examined during the late survey in 1848 by Captain Graves, and found to have ten fathoms water over it, the sea deepening around it in all directions. This eruption lasted three months, covering the sea with floating pumice. At the same time an earthquake destroyed many houses in Thera, while the sea broke upon the coast and overthrew two churches, exposing to view two villages, one on each side of the mountain of St. Stephen, both of which must have been overwhelmed by showers of volcanic matter during some previous eruptions of un-

Fig. 63.



Map of Santorin in the Grecian Archipelago, from a Survey in 1848, by Captain Graves, R.N.

The soundings are given in fathoms.

A, Shoal formed by submarine volcanic eruption in 1650.
B, Northern entrance. C, Mansell's Rock.
D, Mount St. Elias, 1887 feet high.

Fig. 64.



Section of Santorin, in a N.E. and S.W. direction, from Thera through the Kaimenis to Aspr

Fig. 65.



Part of the section, fig. 64., enlarged.

known date.* The accompanying evolution of sulphur and hydrogen issuing from the sea killed more than fifty persons, and above 1000 domestic animals. A wave, also, 50 feet high, broke upon the rocks of the Isle of Nia, about four leagues distant, and advanced 450 yards into the interior of the Island of Sikino. Lastly, in 1707 and 1709, Nea-Kaimeni, or the New Burnt Island, was formed between the two others, Palaia and Micra, the Old and Little isles. This isle was composed originally of two distinct parts; the first which rose was called the White Island, composed of a mass of pumice, extremely porous. Goree, the Jesuit, who was then in Santorin, says that the rock "cut like bread," and that, when the inhabitants landed on it, they found a multitude of full-grown fresh oysters adhering to it, which they ate.† This mass was afterwards covered, in great part, by the matter ejected from the crater of a twin-island formed simultaneously, and called Black Island, consisting of brown trachyte. The trachytic lava which rose on this spot appears to have been a long time in an intumescent state, for the New Kaimeni was sometimes lowered on one side while it gained height on the other, and rocks rose up in the sea at different distances from the shore and then disappeared again. The eruption was renewed at intervals during the years 1711 and 1712, and at length a cone was piled up to the height of 330 feet above the level of the sea, its exterior slope forming an angle of 33° with the horizon, and the crater on its summit being 80 yards in diameter. In addition to the two points of subaërial eruption on the New and Little Kaimenis, two other cones, indicating the sites of submarine outbursts of unknown date, were discovered under water near the Kaimenis during the late survey.

In regard to the "White Island," which was described and visited by Goree in 1707, we are indebted to Mr. Edward Forbes for having, in 1842, carefully investigated the layer of pumiceous ash of which it is constituted. He obtained from it many shells of marine genera, Pectunculus, Arca, Cardita, Trochus, and others, both univalve and bivalve, all of recent Mediterranean species. They were in a fine state of preservation, the bivalves with the epidermis remaining, and valves closed, showing that they had been suddenly destroyed. Mr. Forbes, from his study of the habits of the mollusca living at different depths in the Mediterranean, was able to decide that such an assemblage of species could not have lived at a less depth than 220 feet, so that a bodily upheaval of the mass to that amount must have taken place in order to bring up this bed of ashes and shells to the level of the sea, and they now rise five or six feet above that level.‡

We may compare this partial elevation of solid matter to the rise of a hardened crust of scoriæ, such as is usually formed on the surface of lava-currents, even while they are in motion, and which, although stony and capable of supporting heavy weights, may be upraised without bursting by the intumescence of the melted matter below. That the upheaval was merely local is proved by the fact that the neighbouring Kaimenis did not participate in the movement, still less the three more distant or outer islands before mentioned. The history, therefore, of the Kaimenis shows that they have been the result of intermittent action, and it lends no support to the hypothesis of the sudden distension of horizontal beds blown up like a bladder by a single paroxysmal effort of expansive gases.

---

* Virlet, Bull. de la Soc. Géol. de France, tom. iii p. 103.

† Phil. Trans. No. 332.

‡ E. Forbes, Brit. Association, Report for 1843.

It will be seen by the accompanying map and sections, that the Kaimenis are arranged in a linear direction, running N.E. and S.W., in a manner different from that represented in the older charts. In their longest diameter they form at their base a ridge nearly bisecting the gulf or crater (see sections, figs. 64, 65.).

On considering these facts we are naturally led to compare the smaller and newer islands in the centre of the gulf to the modern cone of Vesuvius, surrounded by the older semicircular escarpment of Somma, or to liken them to the Peak of Teneriffe before described, as surrounded by its "fosse and bastion." This idea will appear to be still more fully confirmed when we study the soundings taken during the late hydrographical survey. Thera, which constitutes alone more than two-thirds of the outer circuit, presents everywhere towards the gulf, high and steep precipices composed of rocks of volcanic origin. In all places near the base of its cliffs, a depth of from 800 to 1000 feet of water was found, and Lieut. Leycester informs us[*] that if the gulf, which is six miles in diameter, could be drained, a bowl-shaped cavity would appear with walls 2449 feet high in some places, and even on the south-west side, where it is lowest, no where less than 1200 feet high; while the Kaimenis would be seen to form in the centre a huge mountain five and a half miles in circumference at its base, with three principal summits (the Old, the New, and the Little Burnt Islands) rising severally to the heights of 1251, 1629, and 1158 feet above the bottom of the abyss. The rim of the great cauldron thus exposed would be observed to be in all parts perfect and unbroken, except at one point where there is a deep and long chasm or channel, known by mariners as "the northern entrance" (B, fig. 63.) between Thera and Therasia, and called by Lieut. Leycester "the door into the crater." It is no less than 1170 feet deep, and constitutes, as will appear by the soundings (see map), a remarkable feature in the bed of the sea. There is no corresponding channel passing out from the gulf into the Mediterranean at any other point in the circuit between the outer islands, the greatest depth there ranging from 7 to 66 feet.

We may conceive, therefore, if at some former time the whole mass of Santorin stood at a higher level by 1200 feet, that this single ravine or narrow valley now forming "the northern entrance," was the passage by which the sea entered a circular bay and swept out in the form of mud and pebbles, the materials derived by denudation from wasting cliffs. In this manner the original crater may have been slowly widened and deepened, after which the whole archipelago may have been partially submerged to its present depth.

---

[*] See a paper read to the Geographical Society in 1849.

That such oscillations of level may in the course of ages have taken place, will be the more readily admitted when we state that part of Thera has actually sunk down in modern times, as, for example, during the great earthquake before alluded to, which happened in 1650. The subsidence alluded to is proved not only by tradition, but by the fact that a road which formerly led between two places on the east coast of Thera is now twelve fathoms under water.

MM. Boblaye and Virlet mention [*], that the waves are constantly undermining and encroaching on the cliffs of Therasia and Aspronisi, and shoals or submarine ledges were found during the late survey, to occur round a great part of these islands, attesting the recent progress of denudation. M. Virlet also remarks, in regard to the separation of the three islands forming the walls of the crater, that the channels between them are all to the W. and N.W., the quarter most exposed to the waves and currents.

Mr. Darwin, in his work on volcanic islands, has shown that in the Mauritius and in Santiago, there is an external circle of basaltic rocks of vast diameter, in the interior of which more modern eruptions have taken place, the older rocks dipping away from the central space in every direction, as in the outer islands of Santorin. He refers the numerous breaches, some of them very wide in the external ramparts of those islands, to the denuding action of the sea. Every geologist, therefore, will be prepared to call in the aid of the same powerful cause, to account for the removal of a large part of the rocks which must once have occupied the interior space, in the same manner as they attribute the abstraction of matter from elliptical "valleys of elevation," such as those of Woolhope and the Wealden in England, to the waves and currents of the sea.

Thera, Therasia, and Aspronisi are all composed of volcanic matter, except the southern part of Thera, where Mount St. Elias rises to three times the height of the loftiest of the igneous rocks, reaching an elevation of 1887 feet above the sea.[†] This mountain is formed of granular limestone and argillaceous schist, and must have been originally a submarine eminence in the bed of the Mediterranean, before the volcanic cone, one side of the base of which now abuts against it, was formed. The inclination, strike, and fractures of the calcareous and argillaceous strata of St. Elias have no relation to the great cone, but, according to M. Bory St. Vincent, have the same direction as those of the other isles of the Grecian Archipelago, namely, from N.N.W. to S.S.E. Each of the three islands, Thera, Therasia, and Aspronisi, is capped by an enormous mass of white tufaceous conglomerate, from forty to fifty feet thick, beneath which are beds of trachytic lava and tuff, having a gentle inclination of only 3° or 4°. Each bed is usually very narrow and discontinuous, the successive layers being moulded or dove-tailed, as M. Virlet expresses it, into the inequalities of the previously existing surface, on which showers of cinders or streams of melted matter have been poured. Nothing, therefore, seems more evident than that we have in Santorin the basal remains of a great ruined cone, or flattened dome; and the absence of dikes in the cliffs surrounding the gulf would indicate that the eruptions took place originally, as they have done in the last two thousand years, not near the margin but in the centre of the space now occupied by the gulf. The central portions of the dome have since been removed by engulfment, or denudation, or by both these causes.

---

[*] Bull. de la Soc. Géol. de France, tome iii.

[†] Virlet, Bull. de la Soc. Géol. de France, tome iii. p. 103.

An important fact is adduced by M. Virlet, to show that the gentle dip of the lava-streams in the three outer islands towards all points of the compass, away from the centre of the gulf, has not been due to the upheaval of horizontal beds, as conjectured by Von Buch, who had not visited Santorin.* The French geologist found that the vesicles or pores of the trachytic masses were lengthened out in the several directions in which they would have flowed if they had descended from the axis of a cone once occupying the centre of the crater. For it is well known that the bubbles of confined gas in a fluid in motion assume an oval form, and the direction of their longer axis coincides always with that of the stream.

On a review, therefore, of all the facts now brought to light respecting Santorin, I attribute the moderate slope of the beds in Thera and the other external islands to their having originally descended the inclined flanks of a large volcanic cone, the principal orifice or vents of eruption having been always situated where they are now, in or near the centre of the space occupied by the gulf or crater, in other words where the outburst of the Kaimenis has been witnessed in historical times. The single long and deep opening into the crater is a feature common to all those remnants of ancient volcanos, the central portions of which have been removed, and is probably connected with aqueous denudation. This denuding process has been the work of ages when the sea was admitted into an original crater, and has taken place during the gradual emergence of the island from the sea, or during various oscillations in its level.

The volcanic island of St. Paul in the midst of the Indian Ocean, lat. 38° 44′ S., long. 77° 37′ E., surveyed by Capt. Blackwood in 1842, seems to exemplify the first stage in the formation of such an archipelago as that of Santorin. We have there a crater one mile in diameter, surrounded by steep and lofty cliffs on every side save one, where the sea enters by a single passage nearly dry at low water. In the interior of the small circular bay or crater there is a depth of 30 fathoms or 180 feet. The surface of the island slopes away on all sides from the crest of the rocks encircling the crater.†

Barren Island.—There is great analogy between the structure of

---

* Poggendorf's Annalen, 1836, p. 183.

† See Admiralty Chart, with views and sections, 1842.

Barren Island in the Bay of Bengal, lat. 12° 15′, and that of Santorin last described. When seen from the ocean, this island presents,

Fig. 66.



Cone and crater of Barren Island, in the Bay of Bengal. Height of the central cone (according to Capt. Miller, in 1834), 500 feet.

on almost all sides, a surface of bare rocks, rising, with a moderate acclivity, towards the interior; but at one point there is a cleft by which we can penetrate into the centre, and there discover that it is occupied by a great circular basin, filled by the waters of the sea, and bordered all around by steep rocks, in the midst of which rises a volcanic cone, very frequently in eruption. The summit of this cone is about 500 feet in height, corresponding to that of the circular border which incloses the basin; so that it can be seen from the ocean only through the ravine. It is most probable that the exterior inclosure of Barren Island (*c*, *d*, fig. 67.) is nothing more than the remains of a truncated cone, *c*, *a*, *b*, *d*, a great portion of which has been removed by engulfment, explosion, or denudation, which may have preceded the formation of the new interior cone *f*, *e*, *g*.*

Fig. 67.



Supposed section of Barren Island, in the Bay of Bengal.

MUD VOLCANOS.

Iceland.—Mr. R. Bunsen, in his account of the pseudo-volcanic phenomena of Iceland, describes many valleys where sulphurous and aqueous vapours burst forth with a hissing sound, from the hot soil formed of volcanic tuff. In such spots a pool of boiling water is seen, in which a bluish-black argillaceous paste rises in huge bubbles. These bubbles on bursting throw the boiling mud to a height of fifteen feet, and upwards accumulating it in ledges round the crater or basin of the spring.

---

* For height of cone and references, see Buist, Volcanos of India, Trans. Bombay Geol. Soc. vol. x. p. 143.

Baku on the Caspian.—The formation of a new mud volcano was witnessed on the 27th of November, 1827, at Tokmali, on the peninsula of Abscheron, east of Baku. Flames blazed up to an extraordinary height, for a space of three hours, and continued for twenty hours to rise about three feet above a crater, from which mud was ejected. At another point in the same district where flames issued, fragments of rock of large size were hurled up into the air, and scattered around.*

Sicily.—At a place called Macaluba, near Girgenti in Sicily, are several conical mounds from ten to thirty feet in height, with small craters at their summits, from which cold water, mixed with mud and bitumen, is cast out. Bubbles of carbonic acid and carburetted hydrogen gas are also disengaged from these springs, and at certain periods with such violence, as to throw the mud to the height of 200 feet. These "air volcanos," as they are sometimes termed, are known to have been in the same state of activity for the last fifteen centuries; and Dr. Daubeny imagines that the gases which escape may be generated by the slow combustion of beds of sulphur, which is actually in progress in the blue clay, out of which the springs rise.† But as the gases are similar to those disengaged in volcanic eruptions, and as they have continued to stream out for so long a period, they may perhaps be derived from a more deep-seated source.

Fig. 68.



Mud cones and craters of Hinglaj near Beila, district of Lus, 120 miles north-west of mouth of Indus. From original drawing by Capt. Robertson. (See Map, p. 460.)

---

* Humboldt's Cosmos.

† Daubeny, Volcanos, p. 267.

Beila in India.—In the district of Luss or Lus, south of Beila, about 120 miles N.W. of Cutch and the mouths of the Indus. (See Map, fig. 71. p. 460.), numerous mud volcanos are scattered over an area of probably not less than 1000 square miles. Some of these have been well described by Captain Hart, and subsequently by Captain Robertson, who has paid a visit to that region, and made sketches of them, which he has kindly placed at my disposal. From one of these the annexed view has been selected. These conical hills occur to the westward of the Hara mountains and the river Hubb. (See Map, p. 460.) One of the cones is 400 feet high, composed of light-coloured earth, and having at its summit a crater thirty yards in diameter. The liquid mud which fills the crater is continually disturbed by air-bubbles, and here and there is cast up in small jets.*

Mineral composition of volcanic products.—The mineral called felspar forms in general more than half of the mass of modern lavas. When it is in great excess, lavas are called trachytic: they consist generally of a base of compact felspar, in which crystals of glassy felspar are disseminated.† When augite (or pyroxene) predominates, lavas are termed basaltic. They contain about 50 per cent. of silica, or much less than the trachytes, in which there is usually about 75 per cent. of that mineral. They also contain about 11 per cent. of protoxide of iron, and as much of lime, both of which are wanting, or only in insignificant quantities in the trachytic rocks.‡ But lavas occur of an intermediate composition between the trachytic and basaltic, which from their colour have been called greystones. The abundance of quartz, forming distinct crystals or concretions, characterizes the granitic and other ancient rocks, now generally considered by geologists as of igneous origin: whereas that mineral is rarely exhibited in a separate form in recent lavas, although silica enters so largely into their composition. Hornblende, so common in hypogene rocks, or those commonly called "primary," is rare in modern lava; nor does it enter largely into rocks of any age in which augite abounds. It should, however, be stated, that the experiments of Mr. Gustav Rose have made it very questionable, whether the minerals called hornblende and augite can be separated as distinct species, as their different varieties seem to pass into each other, whether we consider the characters derived from their angles of crystallization, their chemical composition, or their specific gravity. The difference in form of the two substances may be explained by the different circumstances under which they have been produced, the form of hornblende being the result of slower cooling. Crystals of augite have been met with in the scoriæ of furnaces, but never those of hornblende; and crystals of augite have been obtained by melting hornblende in a platina crucible; but hornblende itself has not been formed artificially.§ Mica occurs plentifully in some recent trachytes, but is rarely present where augite is in excess.

---

* See Buist, Volcanos of India, Trans. Bombay Geol. Soc. vol. x. p. 154., and Captain Robertson, Journ. of Roy. Asiat. Soc. 1850.

† See Glossary.

‡ Bunsen, Volcanic Rocks of Iceland.

§ Bulletin de la Soc. Géol. de France tom. ii. p. 206.

Frequency of eruptions, and nature of subterranean igneous rocks. — When we speak of the igneous rocks of our own times, we mean that small portion which, in violent eruptions, is forced up by elastic fluids to the surface of the earth, — the sand, scoriæ, and lava, which cool in the open air. But we cannot obtain access to that which is congealed far beneath the surface under great pressure, equal to that of many hundred, or many thousand atmospheres.

During the last century, about fifty eruptions are recorded of the five European volcanic districts, of Vesuvius, Etna, Volcano, Santorin, and Iceland; but many beneath the sea in the Grecian archipelago and near Iceland may doubtless have passed unnoticed. If some of them produced no lava, others, on the contrary, like that of Skaptár Jokul, in 1783, poured out melted matter for five or six years consecutively; which cases, being reckoned as single eruptions, will compensate for those of inferior strength. Now, if we consider the active volcanos of Europe to constitute about a fortieth part of those already known on the globe, and calculate that, one with another, they are about equal in activity to the burning mountains in other districts, we may then compute that there happen on the earth about 2000 eruptions in the course of a century, or about twenty every year.

However inconsiderable, therefore, may be the superficial rocks which the operations of fire produce on the surface, we must suppose the subterranean changes now constantly in progress to be on the grandest scale. The loftiest volcanic cones must be as insignificant when contrasted to the products of fire in the nether regions, as are the deposits formed in shallow estuaries when compared to submarine formations accumulating in the abysses of the ocean. In regard to the characters of these volcanic rocks, formed in our own times in the bowels of the earth, whether in rents and caverns, or by the cooling of lakes of melted lava, we may safely infer that the rocks are heavier and less porous than ordinary lavas, and more crystalline, although composed of the same mineral ingredients. As the hardest crystals produced artificially in the laboratory require the longest time for their formation, so we must suppose that where the cooling down of melted matter takes place by insensible degrees, in the course of ages, a variety of minerals will be produced far harder than any formed by natural processes within the short period of human observation.

These subterranean volcanic rocks, moreover, cannot be stratified in the same manner as sedimentary deposits from water, although it is evident that when great masses consolidate from a state of fusion, they may separate into natural divisions; for this is seen to be the case in many lava-currents. We may also expect that the rocks in question will often be rent by earthquakes, since these are common in volcanic regions; and the fissures will be often injected with similar matter, so that dikes of crystalline rock will traverse masses of similar composition. It is also clear, that no organic remains can be included in such masses, as also that these deep-seated igneous formations considered in mass must underlie all the strata containing organic remains, because the heat proceeds from below upwards, and the intensity required to reduce the mineral ingredients to a fluid state must destroy all organic bodies in rocks included in the midst of them.

If by a continued series of elevatory movements, such masses shall hereafter be brought up to the surface, in the same manner as sedimentary marine strata have, in the course of ages, been upheaved to the summit of the loftiest mountains, it is not difficult to foresee what perplexing problems may be presented to the geologist. He may then, perhaps, study in some mountain-chain the very rocks produced at the depth of several miles beneath the Andes, Iceland, or Java, in the time of Leibnitz, and draw from them the same conclusion which that philosopher derived from certain igneous products of high antiquity; for he conceived our globe to have been, for an indefinite period, in the state of a comet, without an ocean, and uninhabitable alike by aquatic or terrestrial animals.

CHAPTER XXVII.

EARTHQUAKES AND THEIR EFFECTS.

Earthquakes and their effects — Deficiency of ancient accounts — Ordinary atmospheric phenomena — Changes produced by earthquakes in modern times considered in chronological order — Earthquake in Syria, 1837 — Earthquakes in Chili in 1837 and 1835 — Isle of Santa Maria raised ten feet — Chili, 1822 — Extent of country elevated — Aleppo and Ionian Isles — Earthquake of Cutch in 1819 — Subsidence in the Delta of the Indus — Island of Sumbawa in 1815 — Earthquake of Caraccas in 1812 — Shocks at New Madrid in 1811 in the valley of the Mississippi — Aleutian Islands in 1806 — Reflections on the earthquakes of the nineteenth century — Earthquake in Quito, Quebec, &c. — Java, 1786 — Sinking down of large tracts.

In the sketch before given of the geographical boundaries of volcanic regions, I stated, that although the points of eruption are but thinly scattered, constituting mere spots on the surface of those vast districts, yet the subterranean movements extend simultaneously over immense areas. We may now proceed to consider the changes which these movements produce on the surface, and in the internal structure of the earth's crust.

Deficiency of ancient accounts. — It is only within the last century and a half, since Hooke first promulgated, in 1688, his views respecting the connection between geological phenomena and earthquakes, that the permanent changes effected by these convulsions have excited attention. Before that time, the narrative of the historian was almost exclusively confined to the number of human beings who perished, the number of cities laid in ruins, the value of property destroyed, or certain atmospheric appearances which dazzled or terrified the observers. The creation of a new lake, the engulphing of a city, or the raising of a new island, are sometimes, it is true, adverted to, as being too obvious, or of too much geographical or political interest to be passed over in silence. But no researches were made expressly with a view of ascertaining the amount of depression or elevation of the ground, or any particular alterations in the relative position of sea and land; and very little distinction was made between the raising of soil by volcanic ejections, and the upheaving of it by forces acting from below. The same remark applies to a very large proportion of modern accounts: and how much reason we have to regret this deficiency of information appears from this, that in every instance where a spirit of scientific inquiry has animated the eye-witnesses of these events, facts calculated to throw light on former modifications of the earth's structure are recorded.

Phenomena attending earthquakes. — As I shall confine myself almost entirely, in the following notice of earthquakes, to the changes brought about by them in the configuration of the earth's crust, I may mention, generally, some accompaniments of these terrible events which are almost uniformly commemorated in history, that it may be unnecessary to advert to them again. Irregularities in the seasons preceding or following the shocks; sudden gusts of wind, interrupted by dead calms; violent rains at unusual seasons, or in countries where such phenomena are almost unknown; a reddening of the sun's disk, and a haziness in the air, often continued for months; an evolution of electric matter, or of inflammable gas from the soil, with sulphurous and mephitic vapours; noises underground, like the running of carriages, or the discharge of artillery, or distant thunder; animals uttering cries of distress, and evincing extraordinary alarm, being more sensitive than men of the slightest movement; a sensation like sea-sickness, and a dizziness in the head, experienced by men: — these, and other phenomena, less connected with our present subject as geologists, have recurred again and again at distant ages, and in all parts of the globe.

I shall now begin the enumeration of earthquakes with the latest authentic narratives, and so carry back the survey retrospectively, that I may bring before the reader, in the first place, the minute and circumstantial details of modern times, and thus enable him, by observing the extraordinary amount of change within the last 150 years, to perceive how great must be the deficiency in the meagre annals of earlier eras.

EARTHQUAKES OF THE NINETEENTH CENTURY.*

Syria, January, 1837. — It has been remarked that earthquakes affect elongated areas. The violent shock which devastated Syria in

---

[*] Since the publication of the first edition of this work, numerous accounts of recent earthquakes have been published; but as they do not illustrate any

837 was felt on a line 500 miles in length by 90 in breadth*: ıore than 6000 persons perished; deep rents were caused in solid ocks, and new hot springs burst out at Tabereah.

Chili — Valdivia, 1837. — One of the latest earthquakes by which he position of solid land is known to have been permanently altered s that which occurred in Chili, on November 7th, 1837. On that ay Valdivia was destroyed by an earthquake, and a whaler, comıanded by Captain Coste, was violently shaken at sea, and lost her ıasts, in lat. 43° 38′ S. in sight of the land. The captain went on he 11th of December following to a spot near the island of Lemus, ne of the Chonos archipelago, where he had anchored two years efore, and found that the bottom of the sea had been raised more han eight feet. Some rocks formerly covered at all times by the ea were now constantly exposed, and an enormous quantity of shells nd fish in a decaying state, which had been thrown there by the raves, or suddenly laid dry during the earthquake, attested the recent ate of the occurrence. The whole coast was strewed with uprooted rees.†

Chili — Conception, 1835. — Fortunately we have a still more deailed account of the geographical changes produced in the same ountry on the 20th of February, 1835. An earthquake was then elt at all places between Copiapo and Chiloe, from north to south, nd from Mendoza to Juan Fernandez, from east to west. "Vessels," ays Mr. Caldcleugh, "navigating the Pacific, within 100 miles of the oast, experienced the shock with considerable force."‡ Conception, ralcahuano, Chillan, and other towns were thrown down. From the ccount of Captain Fitz Roy, R. N., who was then employed in sureying the coast, we learn that after the shock the sea retired in the Bay of Conception, and the vessels grounded, even those which had een lying in seven fathoms water: all the shoals were visible, and oon afterwards a wave rushed in and then retreated, and was followed y two other waves. The vertical height of these waves does not ppear to have been much greater than from sixteen to twenty feet, lthough they rose to much greater heights when they broke upon a loping beach.

According to Mr. Caldcleugh and Mr. Darwin, the whole volcanic hain of the Chilian Andes, a range 150 miles in length, was in a state f unusual activity, both during the shocks and for some time preeding and after the convulsion, and lava was seen to flow from the rater of Osorno. (See Map, fig. 69.) The island of Juan Fernandez,

---

ew principle, I cannot insert them, as ıey would enlarge too much the size of ıy work. The late Von Hoff published 'om time to time, in Poggendorf's Analen, lists of earthquakes which hapened between 1821 and 1836; and, by onsulting these, the reader will perceive ıat every month is signalized by one r many convulsions in some part of the lobe. See also Mallet's Dynamics of Earthquakes, Trans. Roy. Irish Acad. 1846; and art. "Earthquakes," Admiralty Manual, 1849; also Hopkins' Report, Brit. Assoc. 1847–8.

[*] Darwin, Geol. Proceedings, vol. ii. p. 658.

[†] Dumoulin, Comptes Rendus de l'Acad. des Sci. Oct. 1838, p. 706.

[‡] Phil. Trans. 1836, p. 21.

Fig. 69.



distant 365 geographical miles from Chili, was violently shaken at th same time, and devastated by a great wave. A submarine volcan broke out there near Bacalao Head, about a mile from the shore, i sixty-nine fathoms water, and illumined the whole island during th night.*

---

* Phil. Trans. 1826.

"At Conception," says Captain Fitz Roy, "the earth opened and closed rapidly in numerous places. The direction of the cracks was not uniform, though generally from south-east to north-west. The earth was not quiet for three days after the great shock, and more than 300 shocks were counted between the 20th February and the 4th of March. The loose earth of the valley of the Biobio was everywhere parted from the solid rocks which bound the plain, there being an opening between them from an inch to a foot in width.

Fig. 70.



"For some days after the 20th of February, the sea at Talcahuano," says Captain Fitz Roy, "did not rise to the usual marks by four or five feet vertically. When walking on the shore, even at high water, beds of dead mussels, numerous chitons, and limpets, and withered sea-weed, still adhering, though lifeless, to the rocks on which they had lived, everywhere met the eye." But this difference in the relative level of the land and sea gradually diminished, till in the middle of April the water rose again to within two feet of the former high-water mark. It might be supposed that these changes of level merely indicated a temporary disturbance in the set of the currents or in the height of the tides at Talcahuano; but, on considering what occurred in the neighbouring island of Santa Maria, Captain Fitz Roy concluded that the land had been raised four or five feet in February, and that it had returned in April to within two or three feet of its former level.

Santa Maria, the island just alluded to, is about seven miles long and two broad, and about twenty-five miles south-west of Conception. (See Map, fig. 70.) The phenomena observed there are most important. "It appeared," says Captain Fitz Roy, who visited Santa Maria twice, the first time at the end of March, and afterwards in the beginning of April, "that the southern extremity of the island had been raised eight feet, the middle nine, and the northern end upwards of ten feet. On steep rocks, where vertical measures could be correctly taken, beds of dead mussels were found ten feet above high-water mark. One foot lower than the highest bed of mussels, a few limpets and chitons were seen adhering to the rock where they had grown. Two feet lower than the same, dead mussels, chitons, and limpets were abundant.

"An extensive rocky flat lies around the northern parts of Santa Maria. Before the earthquake this flat was covered by the sea, some projecting rocks only showing themselves. Now, the whole flat is exposed, and square acres of it are covered with dead shell-fish, the stench arising from which is abominable. By this elevation of the land the southern port of Santa Maria has been almost destroyed; little shelter remaining there, and very bad landing." The surrounding sea is also stated to have become shallower in exactly the same proportion as the land had risen; the soundings having diminished a fathom and a half everywhere around the island.

At Tubal, also, to the south-east of Santa Maria, the land was raised six feet, at Mocha two feet, but no elevation could be ascertained at Valdivia.

Among other effects of the catastrophe, it is stated that cattle standing on a steep slope, near the shore, were rolled down into the sea, and many others were washed off by the great wave from low land and drowned.*

In November of the same year (1835), Conception was shaken by a severe earthquake, and on the same day Osorno, at the distance of 400 miles, renewed its activity. These facts prove not only the connection of earthquakes with volcanic eruptions in this region, but also the vast extent of the subterranean areas, over which the disturbing cause acts simultaneously.

Ischia, 1828. — On the 2nd of February the whole island of Ischia was shaken by an earthquake, and in the October following I found all the houses in Casamicciol still without their roofs. On the sides of a ravine between that town and Forio, I saw masses of greenish tuff which had been thrown down. The hot-spring of Rita, which was nearest the centre of the movement, was ascertained by M. Covelli to have increased in temperature, showing, as he observes, that the explosion took place below the reservoirs which heat the thermal waters.†

Bogota, 1827.—On the 16th of November, 1827, the plain of Bogota, in New Granada, or Colombia, was convulsed by an earthquake, and a great number of towns were thrown down. Torrents of rain swelled the Magdalena, sweeping along vast quantities of mud and other substances, which emitted a sulphurous vapour and destroyed the fish. Popayan, which is distant 200 geographical miles S.S.W. of Bogota, suffered greatly. Wide crevices appeared in the road of Guanacas, leaving no doubt that the whole of the Cordilleras sustained a powerful shock. Other fissures opened near Costa, in the plains of Bogota, into which the river Tunza immediately began to flow.* It is worthy of remark, that in all such cases the ancient gravel bed of a river is deserted, and a new one formed at a lower level; so that a want of relation in the position of alluvial beds of the existing water-courses may be no test of the high antiquity of such deposits, at least in countries habitually convulsed by earthquakes. Extraordinary rains accompanied the shocks before mentioned; and two volcanos are said to have been in eruption in the mountain-chain nearest to Bogota.

---

* Darwin's Journ. of Travels in South merica, Voyage of Beagle, p. 372.

† Biblioth. Univ. Oct. 1828, p. 157.

Chili, 1822.—On the 19th of November, 1822, the coast of Chili was visited by a most destructive earthquake. The shock was felt simultaneously throughout a space of 1200 miles from north to south. St. Jago, Valparaiso, and some other places, were greatly injured. When the district round Valparaiso was examined on the morning after the shock, it was found that the coast for a considerable distance was raised above its former level.† At Valparaiso the elevation was three feet, and at Quintero about four feet. Part of the bed of the sea, says Mrs. Graham, remained bare and dry at high water, "with beds of oysters, mussels, and other shells adhering to the rocks on which they grew, the fish being all dead, and exhaling most offensive effluvia."‡

An old wreck of a ship, which before could not be approached, became accessible from the land, although its distance from the original seashore had not altered. It was observed that the water-course of a mill, at the distance of about a mile from the sea, gained a fall of fourteen inches, in little more than one hundred yards; and from this fact it is inferred that the rise in some parts of the inland country was far more considerable than on the borders of the ocean.§ Part of the coast thus elevated consisted of granite, in which parallel fissures were caused, some of which were traced for a mile and a half inland. Cones of earth about four feet high were thrown up in several districts, by the forcing up of water mixed with sand through funnel-shaped hollows,—a phenomenon very common in Calabria, and the explanation of which will hereafter be considered. Those houses in Chili of which the foundations were on rock were less damaged than such as were built on alluvial soil

Mr. Cruickshanks, an English botanist, who resided in the country during the earthquake, has informed me that some rocks of greenstone at Quintero, a few hundred yards from the beach, which had always been under water till the shock of 1822, have since been uncovered when the tide is at half-ebb; and he states that, after the earthquake, it was the general belief of the fishermen and inhabitants of the Chilian coast, *not* that the land had risen, but that the ocean had permanently retreated.

---

* Phil. Mag. July, 1828, p. 37.

† Geol. Trans. vol. i. 2nd ser., and Journ. of Sci. 1824, vol. xvii. p. 40.

‡ Geol. Trans. vol. i. 2nd ser. p. 415.

§ Journ. of Sci. vol. xvii. p. 42.

Dr. Meyen, a Prussian traveller, who visited Valparaiso in 1831, says that on examining the rocks both north and south of the town, nine years after the event, he found, in corroboration of Mrs. Graham's account, that remains of animals, and sea-weed, the *Lessonia* of Bory de St. Vincent, which has a firm ligneous stem, still adhered to those rocks which in 1822 had been elevated above high-water mark.* According to the same author, the whole coast of Central Chili was raised about four feet, and banks of marine shells were laid dry on many parts of the coast. He observed similar banks, elevated at unknown periods, in several places, especially at Copiapo, where the species all agree with those now living in the ocean. Mr. Freyer also, who resided some years in South America, has confirmed these statements†; and Mr. Darwin obtained evidence that the remains of an ancient wall, formerly washed by the sea, and now 11½ feet above high-water mark, acquired several feet of this additional elevation during the earthquake of 1822.‡

The shocks continued up to the end of September, 1823; even then, forty-eight hours seldom passed without one, and sometimes two or three were felt during twenty-four hours. Mrs. Graham observed, after the earthquake of 1822, that besides a beach newly raised above high-water mark, there were several older elevated lines of beach, one above the other, consisting of shingle mixed with shells extending in a parallel direction to the shore, to the height of fifty feet above the sea.§

Extent of country elevated.—By some observers it has been supposed that the whole country from the foot of the Andes to a great distance under the sea was upraised in 1822, the greatest rise being at the distance of about two miles from the shore. "The rise upon the coast was from two to four feet:—at the distance of a mile inland it must have been from five to six or seven feet."‖ It has also been conjectured by the same eye-witnesses to the convulsion, that the area over which this permanent alteration of level extended may have been equal to 100,000 square miles. Although the increased fall of certain water-courses may have afforded some ground for this conjecture, it must be considered as very hypothetical, and the estimate may have exceeded or greatly fallen short of the truth. It may nevertheless be useful to reflect on the enormous amount of change which this single convulsion occasioned, if the extent of country moved upward really amounted to 100,000 square miles,—an extent just equal to half the area of France, or about five sixths of the area of Great Britain and Ireland. If we suppose the elevation to have been only three feet on an average, it will be seen that the mass of rock added to the continent of America by the movement, or, in other words, the mass previously below the level of the sea, and after the shocks permanently above it, must have contained fifty-seven cubic miles in bulk; which would be sufficient to form a conical mountain two miles high (or about as high as Etna), with a circumference at the base of nearly thirty-three miles. We may take the mean specific gravity of the rock at 2·655,—a fair average, and a convenient one in such computations, because at such a rate a cubic yard weighs two tons. Then, assuming the great pyramid of Egypt, if solid, to weigh, in accordance with an estimate before given, six million tons, we may state the rock added to the continent by the Chilian earthquake to have more than equalled 100,000 pyramids.

---

* Reise um die Erde; and see Dr. Meyen's letter cited Foreign Quart. Rev. No. 33. p. 13. 1836.

† Geol. Soc. Proceedings, No. xl. p. 179., Feb. 1835.

‡ Proceed. Geol. Soc. vol. ii. p. 447.

§ Geol. Trans. vol. i. 2nd ser. p. 415.

‖ Journal of Science, vol. xvii. pp. 40. 45.

But it must always be borne in mind that the weight of rock here alluded to constituted but an insignificant part of the whole amount which the volcanic forces had to overcome. The whole thickness of rock between the surface of Chili and the subterranean foci of volcanic action may be many miles or leagues deep. Say that the thickness was only two miles, even then the mass which changed place and rose three feet being 200,000 cubic miles in volume, must have exceeded in weight 363 million pyramids.

It may be instructing to consider these results in connection with others already obtained from a different source, and to compare the working of two antagonist forces — the levelling power of running water, and the expansive energy of subterranean heat. How long, it may be asked, would the Ganges require, according to data before explained (p. 283.), to transport to the sea a quantity of solid matter equal to that which may have been added to the land by the Chilian earthquake? The discharge of mud in one year by the Ganges was estimated at 20,000 million cubic feet. According to that estimate it would require about four centuries (or 418 years) before the river could bear down from the continent into the sea a mass equal to that gained by the Chilian earthquake. In about half that time, perhaps, the united waters of the Ganges and Burrampooter might accomplish the operation.

Cutch, 1819. — A violent earthquake occurred at Cutch, in the delta of the Indus, on the 16th of June, 1819. (See Map, fig. 71.) The principal town, Bhooj, was converted into a heap of ruins, and its stone buildings were thrown down. The movement was felt over an area having a radius of 1000 miles from Bhooj, and extending to Khatmandoo, Calcutta, and Pondicherry.[*] The vibrations were felt in North-west India, at a distance of 800 miles, after an interval of about fifteen minutes after the earthquake at Bhooj. At Ahmedabad the great mosque, erected by Sultan Ahmed nearly 450 years before, fell to the ground, attesting how long a period had elapsed since a shock of similar violence had visited that point. At Anjar, the fort,

---

[*] *See Asiatic Journal*, vol. i.

Fig. 71.



with its tower and guns, were hurled to the ground in one common mass of ruin. The shocks continued until the 20th; when, thirty miles north-west from Bhooj, the volcano called Denodur is said by some to have sent forth flames, but Capt. Grant was unable to authenticate this statement.

Subsidence in the delta of the Indus.—Although the ruin of towns was great, the face of nature in the inland country, says Captain Macmurdo, was not visibly altered. In the hills some large masses only of rock and soil were detached from the precipices; but the eastern and almost deserted channel of the Indus, which bounds the province of Cutch, was greatly changed. This estuary, or inlet of the sea, was, before the earthquake, fordable at Luckput, being only about a foot deep when the tide was at ebb, and at flood tide never more than six feet; but it was deepened at the fort of Luckput, after the shock, to more than *eighteen feet at low water.*[*] On sounding other parts of the channel, it was found, that where previously the depth of the water at flood never exceeded one or two feet, it had become from four to ten feet deep. By these and other remarkable changes of level, a part of the inland navigation of that country, which had been closed for centuries, became again practicable.

Fort and village submerged.[†]—The fort and village of Sindree,

---

[*] Macmurdo. Ed. Phil. Journ. iv. 106.

[†] I was indebted to my friend the late Sir Alexander Burnes for the accompanying sketch (fig. 72.) of the fort of Sindree, as it appeared eleven years before the earthquake.

Fig. 72.



Fort of Sindree, on the eastern branch of the Indus, before it was submerged by the earthquake of 1819, from a sketch of Capt. Grindlay, made in 1808.

on the eastern arm of the Indus, above Luckput, are stated by the same writer to have been overflowed; and, after the shock, the tops of the houses and wall were alone to be seen above the water, for the houses, although submerged, were not cast down. ' Had they been situated, therefore, in the interior, where so many forts were levelled to the ground, their site would, perhaps, have been regarded as having remained comparatively unmoved. Hence we may suspect that great permanent upheavings and depressions of soil may be the result of earthquakes, without the inhabitants being in the least degree conscious of any change of level.

A more recent survey of Cutch, by Sir A. Burnes, who was not in communication with Capt. Macmurdo, confirms the facts above enumerated, and adds many important details.* That officer examined the delta of the Indus in 1826 and 1828, and from his account it appears that, when Sindree subsided in June, 1819, the sea flowed in by the eastern mouth of the Indus, and in a few hours converted a tract of land, 2000 square miles in area, into an inland sea, or lagoon. Neither the rush of the sea into this new depression, nor the movement of the earthquake, threw down entirely the small fort of Sindree, one of the four towers, the north-western, still continuing to stand; and, the day after the earthquake, the inhabitants, who had ascended to the top of this tower, saved themselves in boats.†

Elevation of the Ullah Bund.—Immediately after the shock, the inhabitants of Sindree saw, at the distance of five miles and a half from their village, a long elevated mound, where previously there had been a low and perfectly level plain. (See Map, fig. 71.) To this uplifted tract they gave the name of "Ullah Bund," or the "Mound of God," to distinguish it from several artificial dams previously thrown across the eastern arm of the Indus.

---

* This Memoir is now in the Library of the Royal Asiatic Society of London.

† Several particulars not given in the earlier edition were afterwards obtained by me from personal communication with Sir A. Burnes in London.

Extent of country raised.—It has been ascertained that this new-raised country is *upwards of fifty miles* in length from east to west, running parallel to that line of subsidence before mentioned which caused the grounds around Sindree to be flooded. The range of this elevation extends from Puchum Island towards Gharee; its breadth from north to south is conjectured to be in some parts *sixteen miles*, and its greatest ascertained height above the original level of the delta is ten feet,—an elevation which appears to the eye to be very uniform throughout.

For several years after the convulsion of 1819, the course of the Indus was very unsettled, and at length, in 1826, the river threw a vast body of water into its eastern arm, that called the Pharraun, above Sindree; and forcing its way in a more direct course to the sea, burst through all the artificial dams which had been thrown across its channel, and at length cut right through the "Ullah Bund," whereby a natural section was obtained. In the perpendicular cliffs thus laid open Sir A. Burnes found that the upraised lands consisted of clay filled with shells. The new channel of the river where it intersected the "bund" was eighteen feet deep, and forty yards in width; but in 1828 the channel was still farther enlarged. The Indus, when it first opened this new passage, threw such a body of water into the new mere, or salt lagoon, of Sindree, that it became fresh for many months; but it had recovered its saltness in 1828, when the supply of river-water was less copious, and finally it became more salt than the sea, in consequence, as the natives suggested to Sir A. Burnes, of the saline particles with which the "Runn of Cutch" is impregnated.

In 1828 Sir A. Burnes went in a boat to the ruins of Sindree, where a single remaining tower was seen in the midst of a wide expanse of sea. The tops of the ruined walls still rose two or three feet above the level of the water; and standing on one of these, he could behold nothing in the horizon but water, except in one direction, where a blue streak of land to the north indicated the Ullah Bund. This scene presents to the imagination a lively picture of the revolutions now in progress on the earth—a waste of waters where a few years before all was land, and the only land visible consisting of ground uplifted by a recent earthquake.

Ten years after the visit of Sir A. Burnes above alluded to, my friend, Captain Grant, F.G.S., of the Bombay Engineers, had the kindness to send at my request a native surveyor to make a plan of Sindree and Ullah Bund, in March, 1838. From his description it appears that, at that season, the driest of the whole year, he found the channel traversing the Bund to be 100 yards wide, without water, and encrusted with salt. He was told that it has now only four or five feet of water in it after rains. The sides or banks were nearly perpendicular, and nine feet in height. The lagoon has diminished both in area and depth, and part near the fort was dry land. The annexed drawing, made by Captain Grant from the surveyor's plan, shows the appearance of the fort in the midst of the lake, as seen in 1838 from the west, or from the same point as that from which Captain Grindlay's sketch (see fig. 72.) was taken in 1808, before the earthquake.

Fig. 73.



View of the Fort of Sindree, from the west, in March, 1838.

The Runn of Cutch is a flat region of a very peculiar character, and no less than 7000 square miles in area: a greater superficial extent than Yorkshire, or about one fourth the area of Ireland. It is not a desert of moving sand, nor a marsh, but evidently the dried-up bed of an inland sea, which for a great part of every year has a hard and dry bottom uncovered by weeds or grass, and only supporting here and there a few tamarisks. But during the monsoons, when the sea runs high, the salt-water driven up from the Gulf of Cutch and the creeks at Luckput overflows a large part of the Runn, especially after rains, when the soaked ground permits the sea-water to spread rapidly. The Runn is also liable to be overflowed occasionally in some parts by river-water: and it is remarkable that the only portion which was ever highly cultivated (that anciently called Sayra) is now permanently submerged. The surface of the Runn is sometimes encrusted with salt about an inch in depth, in consequence of the evaporation of the sea-water. Islands rise up in some parts of the waste, and the boundary lands form bays and promontories. The natives have various traditions respecting the former separation of Cutch and Sinde by a bay of the sea, and the drying up of the district called the Runn. But these tales, besides the usual uncertainty of oral tradition, are farther obscured by mythological fictions. The conversion of the Runn into land is chiefly ascribed to the miraculous powers of a Hindoo saint, by name Damorath (or Dhoorunnath), who had previously done penance for twelve years on the summit of Denodur hill. Captain Grant infers, on various grounds, that this saint flourished about the eleventh or twelfth century of our era. In proof of the drying up of the Runn, some towns far inland are still pointed out as having once been ancient ports. It has, moreover, been always said that ships were wrecked and engulphed by the great catastrophe; and in the jets of black muddy water thrown out of fissures in that region, in 1819, there were cast up numerous pieces of wrought iron and ship nails.* Cones of sand six or eight feet in height were at the same time thrown up on these lands.†

We must not conclude without alluding to a *moral* phenomenon connected with this tremendous catastrophe, which we regard as highly deserving the attention of geologists. It is stated by Sir. A. Burnes, that "these wonderful events passed *unheeded* by the inhabitants of Cutch;" for the region convulsed, though once fertile, had for a long period been reduced to sterility by want of irrigation, so that the natives were indifferent as to its fate. Now it is to this profound apathy which all but highly civilized nations feel, in regard to physical events not having an immediate influence on their worldly fortunes, that we must ascribe the extraordinary dearth of historical information concerning changes of the earth's surface, which modern observations show to be by no means of rare occurrence in the ordinary course of nature.

Since the above account was written, a description has been published of more recent geographical changes in the district of Cutch, near the mouth of the Koree, or eastern branch of the Indus, which happened in June, 1845. A large area seems to have subsided, and the Sindree lake had become a salt marsh.‡

Island of Sumbawa, 1815. — In April, 1815, one of the most frightful eruptions recorded in history occurred in the province of Tomboro, in the island of Sumbawa (see Map, fig. 39. p. 351.), about 200 miles from the eastern extremity of Java. In the April of the year preceding the volcano had been observed in a state of considerable activity, ashes having fallen upon the decks of vessels which sailed past the coast.§ The eruption of 1815 began on the 5th of April, but was most violent on the 11th and 12th, and did not entirely cease till July. The sound of the explosions was heard in Sumatra, at the distance of 970 geographical miles in a direct line; and at Ternate, in an opposite direction, at the distance 720 miles. Out of a population of 12,000, in the province of Tomboro, only twenty-six individuals survived. Violent whirlwinds carried up men, horses, cattle, and whatever else came within their influence, into the air; tore up the largest trees by the roots, and covered the whole sea with floating timber.‖ Great tracts of land were covered by lava, several streams of which, issuing from the crater of the Tomboro mountain, reached the sea. So heavy was the fall of ashes, that they broke into the Resident's house at Bima, forty miles east of the volcano, and rendered it as well as many other dwellings in the town unhabitable. On the side of Java the ashes were carried to the distance of 300 miles, and 217 towards Celebes, in sufficient quantity to darken the air. The floating cinders to the westward of Sumatra formed, on the 12th of

---

* Capt. Burnes' Account.

† Capt. Macmurdo's Memoir, Ed. *Phil.* Journ. vol. iv. p. 106.

‡ Quart. Geol. Journ. vol. ii. p 103.

§ MS. of J. Crawfurd, Esq.

‖ Raffles's Java, vol. i. p. 28.

April, a mass two feet thick, and several miles in extent, through which ships with difficulty forced their way.

The darkness occasioned in the daytime by the ashes in Java was so profound, that nothing equal to it was ever witnessed in the darkest night. Although this volcanic dust when it fell was an impalpable powder, it was of considerable weight when compressed, a pint of it weighing twelve ounces and three quarters. "Some of the finest particles," says Mr. Crawfurd, "were transported to the islands of Amboyna and Banda, which last is about 800 miles east from the site of the volcano, although the south-east monsoon was then at its height." They must have been projected, therefore, into the upper regions of the atmosphere, where a counter current prevailed.

Along the sea-coast of Sumbawa and the adjacent isles, the sea rose suddenly to the height of from two to twelve feet, a great wave rushing up the estuaries, and then suddenly subsiding. Although the wind at Bima was still during the whole time, the sea rolled in upon the shore, and filled the lower parts of the houses with water a foot deep. Every prow and boat was forced from the anchorage, and driven on shore.

The town called Tomboro, on the west side of Sumbawa, was overflowed by the sea, which encroached upon the shore so that the water remained permanently eighteen feet deep in places where there was land before. Here we may observe, that the amount of subsidence of land was apparent, in spite of the ashes, which would naturally have caused the limits of the coast to be extended.

The area over which tremulous noises and other volcanic effects extended, was 1000 English miles in circumference, including the whole of the Molucca Islands, Java, a considerable portion of Celebes, Sumatra, and Borneo. In the island of Amboyna, in the same month and year, the ground opened, threw out water, and then closed again.*

In conclusion, I may remind the reader, that but for the accidental presence of Sir Stamford Raffles, then governor of Java, we should scarcely have heard in Europe of this tremendous catastrophe. He required all the residents in the various districts under his authority to send in a statement of the circumstances which occurred within their own knowledge; but, valuable as were their communications, they are often calculated to excite rather than to satisfy the curiosity of the geologists. They mention, that similar effects, though in a less degree, had, about seven years before, accompanied an eruption of Carang Assam, a volcano in the island of Bali, west of Sumatra; but no particulars of that great catastrophe are recorded.†

Caraccas, 1812. — On the 26th of March, 1812, several violent shocks of an earthquake were felt in Caraccas. The surface undulated like a boiling liquid, and terrific sounds were heard underground. The whole city with its splendid churches was in an instant a heap of ruins, under which 10,000 of the inhabitants were buried. On the

---

* Raffles's Hist. of Java, vol. i. p. 25. Ed. Phil. Journ. vol. iii. p. 389.

† Life and Services of Sir Stamford Raffles's, p. 241. London. 1830.

5th of April, enormous rocks were detached from the mountains. It was believed that the mountain Silla lost from 300 to 360 feet of its height by subsidence; but this was an opinion not founded on any measurement. On the 27th of April, a volcano in St. Vincent's threw out ashes; and, on the 30th, lava flowed from its crater into the sea, while its explosions were heard at a distance equal to that between Vesuvius and Switzerland, the sound being transmitted, as Humboldt supposes, through the ground. During the earthquake which destroyed Caraccas, an immense quantity of water was thrown out at Valecillo, near Valencia, as also at Porto Cabello, through openings in the earth; and in the Lake Maracaybo the water sank. Humboldt observed that the Cordilleras, composed of gneiss and mica slate, and the country immediately at their foot, were more violently shaken than the plains.*

South Carolina and New Madrid, Missouri, 1811–12.—Previous to the destruction of La Guayra and Caraccas, in 1812, earthquakes were felt in South Carolina; and the shocks continued till those cities were destroyed. The valley also of the Mississippi, from the village of New Madrid to the mouth of the Ohio in one direction, and to the St. Francis in another, was convulsed in such a degree as to create new lakes and islands. It has been remarked by Humboldt in his Cosmos, that the earthquake of New Madrid presents one of the few examples on record of the incessant quaking of the ground for several successive months *far from any volcano.* Flint, the geographer, who visited the country seven years after the event, informs us, that a tract of many miles in extent, near the Little Prairie, became covered with water three or four feet deep; and when the water disappeared a stratum of sand was left in its place. Large lakes of twenty miles in extent were formed in the course of an hour, and others were drained. The grave-yard at New Madrid was precipitated into the bed of the Mississippi; and it is stated that the ground whereon the town is built, and the river bank for fifteen miles above, sank eight feet below their former level.† The neighbouring forest presented for some years afterwards "a singular scene of confusion; the trees standing inclined in every direction, and many having their trunks and branches broken."‡

The inhabitants relate that the earth rose in great undulations; and when these reached a certain fearful height, the soil burst, and vast volumes of water, sand, and pit-coal were discharged as high as the tops of the trees. Flint saw hundreds of these deep chasms remaining in an alluvial soil, seven years after. The people in the country, although inexperienced in such convulsions, had remarked that the chasms in the earth were in a direction from S. W. to N. E.; and they accordingly felled the tallest trees, and laying them at right angles to the chasms, stationed themselves upon them. By this invention, when chasms opened more than once under these trees, several persons were prevented from being swallowed up.* At one period during this earthquake, the ground not far below New Madrid swelled up so as to arrest the Mississippi in its course, and to cause a temporary reflux of its waves. The motion of some of the shocks is described as having been horizontal, and of others perpendicular; and the vertical movement is said to have been much less desolating than the horizontal.

---

* Humboldt's Pers. Nar. vol. iv. p. 12.; and Ed. Phil. Journ., vol. i. p. 272. 1819.

† Cramer's Navigator, p. 243. Pittsburgh, 1821.

‡ Long's Exped. to the Rocky Mountains, vol. iii. p. 184.

The above account has been reprinted exactly as it appeared in former editions of this work, compiled from the authorities which I have cited; but having more recently (March, 1846) had an opportunity myself of visiting the disturbed region of the Mississippi, and conversing with many eye-witnesses of the catastrophe, I am able to confirm the truth of those statements, and to add some remarks on the present face and features of the country. I skirted, as was before related (p. 270.), part of the territory immediately west of New Madrid, called "the sunk country," which was for the first time permanently submerged during the earthquake of 1811–12. It is said to extend along the course of the White Water and its tributaries for a distance of between 70 and 80 miles north and south, and 30 miles east and west. I saw on its borders many full-grown trees still standing leafless, the bottoms of their trunks several feet under water, and a still greater number lying prostrate. An active vegetation of aquatic plants is already beginning to fill up some of the shallows, and the sediment washed in by occasional floods when the Mississippi rises to an extraordinary height contributes to convert the sunk region into marsh and forest land. Even on the dry ground along the confines of the submerged area, I observed in some places that all the trees of prior date to 1811 were dead and leafless, though standing erect and entire. They are supposed to have been killed by the loosening of their roots during the repeated undulations which passed through the ground for three months in succession.

Mr. Bringier, an experienced engineer of New Orleans, who was on horseback near New Madrid when some of the severest shocks were experienced, related to me (in 1846), that "as the waves advanced the trees bent down, and the instant afterwards, while recovering their position, they often met those of other trees similarly inclined, so that their branches becoming interlocked, they were prevented from righting themselves again. The transit of the wave through the woods was marked by the crashing noise of countless boughs, first heard on one side and then on the other. At the same time powerful jets of water, mixed with sand, mud, and fragments of coaly matter, were cast up, endangering the lives of both horse and rider."

I was curious to ascertain whether any vestiges still remained of these fountains of mud and water, and carefully examined between New Madrid and the Little Prairie several "sink holes" as they are termed. They consist of cavities from 10 to 30 yards in width, and 20 feet or more in depth, and are very conspicuous interrupting the level surface of a flat alluvial plain. I saw abundance of sand, which some of the present inhabitants saw spouting from these deep holes, also fragments of decayed wood and black bituminous shale, probably drifted down at some former period in the main channel of the Mississippi, from the coal-fields farther north. I also found numerous rents in the soil left by the earthquake, some of them still several feet wide, and a yard or two in depth, although the action of rains, frost, and occasional inundations, and especially the leaves of trees blown into them in countless numbers every autumn, have done much to fill them up. I measured the direction of some of the fissures, which usually varied from 10 to 45 degrees W. of north, and were often parallel to each other; I found, however, a considerable diversity in their direction. Many of them are traceable for half a mile and upwards, but they might easily be mistaken for artificial trenches if resident settlers were not there to assure us that within their recollection they were "as deep as wells." Fragments of coaly shale were strewed along the edges of some of these open fissures, together with white sand, in the same manner as round the "sink holes."*

---

* Silliman's Journ. Jan. 1829.

Among other monuments of the changes wrought in 1811-12, I explored the bed of a lake called Eulalie, near New Madrid, 300 yards long by 100 yards in width, which was suddenly drained during the earthquake. The parallel fissures by which the waters escaped are not yet entirely closed, and all the trees growing on its bottom were at the time of my visit less than 34 years old. They consisted of cotton-wood, willows, the honey-locust, and other species, differing from those clothing the surrounding higher grounds, which are more elevated by 12 or 15 feet. On them the hiccory, the black and white oak, the gum and other trees, many of them of ancient date, were flourishing.

Aleutian Islands, 1806.—In the year 1806, a new island, in the form of a peak, with some low conical hills upon it, is said to have risen from the sea among the Aleutian Islands, east of Kamtschatka. According to Langsdorf †, it was four geographical miles in circumference; and Von Buch infers from its magnitude, and from its not having again subsided below the level of the sea, that it did not consist merely of ejected matter, but of a solid rock of trachyte upheaved. ‡ Another extraordinary eruption happened in the spring of the year 1814, in the sea near Unalaschka, in the same archipelago. A new isle was then produced of considerable size, and with a peak three thousand feet high, which remained standing for a year afterwards, though with somewhat diminished height.

Although it is not improbable that earthquakes accompanying these tremendous eruptions may have heaved up part of the bed of the sea, yet the circumstance of the islands not having disappeared like Sabrina (see p. 416.) may have arisen from the emission of lava. If Jorullo, for example, in 1759, had risen from a shallow sea to the height of 1600 feet, instead of attaining that elevation above the Mexican plateau, the massive current of basaltic lava which poured out from its crater would have enabled it to withstand, for a long period, the action of a turbulent sea.

---

* See Lyell's Second Visit to the United States, ch. xxxiii.

† Bemerkungen auf einer Reise um die Welt. bd. ii. s. 209.

‡ Neue Allgem. Geogr. Ephemer. bd. iii. s. 348.

Reflections on the earthquakes of the nineteenth century.—We are now about to pass on to the events of the eighteenth century; but before we leave the consideration of those already enumerated, let us pause for a moment, and reflect how many remarkable facts of geological interest are afforded by the earthquakes above described, though they constitute but a small part of the convulsions even of the last forty years. New rocks have risen from the waters; new hot springs have burst out, and the temperature of others has been raised; the coast of Chili has been thrice permanently elevated; a considerable tract in the delta of the Indus has sunk down, and some of its shallow channels have become navigable; an adjoining part of the same district, upwards of fifty miles in length and sixteen in breadth, has been raised about ten feet above its former level; part of the great plain of the Mississippi, for a distance of eighty miles in length by thirty in breadth, has sunk down several feet; the town of Tomboro has been submerged, and twelve thousand of the inhabitants of Sumbawa have been destroyed. Yet, with a knowledge of these terrific catastrophes, witnessed during so brief a period by the present generation, will the geologist declare with perfect composure that the earth has at length settled into a state of repose? Will he continue to assert that the changes of relative level of land and sea, so common in former ages of the world, have now ceased? If, in the face of so many striking facts, he persists in maintaining this favourite dogma, it is in vain to hope that, by accumulating the proofs of similar convulsions during a series of antecedent ages, we shall shake his tenacity of purpose:—

> Si fractus illabatur orbis
> Impavidum ferient ruinæ.

EARTHQUAKES OF THE EIGHTEENTH CENTURY.

Quito, 1797.—On the morning of February 4th, 1797, the volcano of Tunguragua in Quito, and the surrounding district, for forty leagues from south to north, and twenty leagues from west to east, experienced an undulating movement, which lasted four minutes. The same shock was felt over a tract of 170 leagues from south to north, from Piura to Popayan; and 140 from west to east, from the sea to the river Napo. In the smaller district first mentioned, where the movement was more intense, every town was levelled to the ground; and Riobamba, Quero, and other places, were buried under masses detached from the mountains. At the foot of Tunguragua the earth was rent open in several places; and streams of water and fetid mud, called "moya," poured out, overflowing and wasting every thing. In valleys 1000 feet broad, the water of these floods reached to the height of 600 feet; and the mud deposit barred up the course of the river, so as to form lakes, which in some places continued for more than eighty days. Flames and suffocating vapours escaped from the lake Quilotoa, and killed all the cattle on its shores. The shocks continued all February and March; and on the 5th of April they recurred with almost as much violence as at first. We are told that the form of the surface in the district most shaken was entirely altered, but no exact measurements are given whereby we may estimate the degree of elevation or subsidence.* Indeed it would be difficult, except in the immediate neighbourhood of the sea, to obtain any certain standard of comparison if the levels were really as much altered as the narrations imply.

Cumana, 1797. — In the same year, on the 14th of December, the small Antilles experienced subterranean movements, and four-fifths of the town of Cumana was shaken down by a vertical shock. The form of the shoal of Mornerouge, at the mouth of the river Bourdones, was changed by an upheaving of the ground.†

Canada — Quebec, 1791. — We learn from Captain Bayfield's memoirs, that earthquakes are very frequent on the shore of the estuary of the St. Lawrence, of force sufficient at times to split walls and throw down chimneys. Such were the effects experienced in December, 1721, in St. Paul's Bay, about fifty miles N. E. from Quebec; and the inhabitants say, that about every twenty-five years a violent earthquake returns, which lasts forty days. In the History of Canada it is stated that, in 1663, a tremendous convulsion lasted six months, extending from Quebec to Tadeausac, — a distance of about 130 miles. The ice on the river was broken up, and many landslips caused.‡

Caraccas, 1790. — In the Caraccas, near where the Caura joins the Orinoco, between the towns San Pedro de Alcantara and San Francisco de Aripao, an earthquake, on St. Matthew's day 1790, caused a sinking in of the granitic soil, and left a lake 800 yards in diameter, and from eighty to one hundred in depth. It was a portion of the forest of Aripao which subsided, and the trees remained green for several months under water.§

Sicily, 1790. — On the 18th of March in the same year, at S. Maria di Niscemi, some miles from Terranuova, near the south coast of Sicily, the ground gradually sunk down for a circumference of three Italian miles, during seven shocks; and, in one place, to the depth of thirty feet. It continued to subside to the end of the month. Several fissures sent forth sulphur, petroleum, steam, and hot water, and a stream of mud, which flowed for two hours, and covered a space sixty feet long and thirty broad. This happened far from both the ancient and modern volcanic district, in a group of strata consisting chiefly of blue clay.*

---

* Cavanilles, Journ. de Phys., tome xlix. p. 230. Gilbert's Annalen, bd. vi. Humboldt's Voy. p. 317.

† Humboldt's Voy., Relat. Hist., part. i. p. 309.

‡ Macgregor's Travels in America.

§ Humboldt's Voy., Relat. Hist., part. ii. p. 632.

Java, 1786. — About the year 1786, an earthquake was felt at intervals, for the period of four months, in the neighbourhood of Batur, in Java, and an eruption followed. Various rents were formed, which emitted a sulphurous vapour; separate tracts sunk away, and were swallowed by the earth. Into one of these the rivulet Dotog entered, and afterwards continued to follow a subterraneous course. The village of Jampang was buried in the ground, with thirty-eight of its inhabitants, who had not time to escape. We are indebted to Dr. Horsfield for having verified the above-mentioned facts.†

CHAPTER XXVIII.

EARTHQUAKE IN CALABRIA, 1783.

Earthquake in Calabria, February 5. 1783 — Shocks continued to the end of the year 1786 — Authorities — Area convulsed — Geological structure of the district — Difficulty of ascertaining changes of level — Subsidence of the quay at Messina — Movement in the stones of two obelisks — Shift or fault in the Round Tower of Terranuova — Opening and closing of fissures — Large edifices engulphed — Dimensions of new caverns and fissures — Gradual closing in of rents — Bounding of detached masses into the air — Landslips — Buildings transported entire to great distances — New lakes — Funnel-shaped hollows in alluvial plains — Currents of mud — Fall of cliffs, and shore near Scilla inundated — State of Stromboli and Etna during the shocks — How earthquakes contribute to the formation of valleys — Concluding remarks.

Calabria, 1783. — Of the numerous earthquakes which have occurred in different parts of the globe, during the last 100 years, that of Calabria, in 1783, is almost the only one of which the geologist can be said to have such a circumstantial account as to enable him fully to appreciate the changes which this cause is capable of producing in the lapse of ages. The shocks began in February, 1783, and lasted for nearly four years, to the end of 1786. Neither in duration, nor in violence, nor in the extent of territory moved, was this convulsion remarkable, when contrasted with many experienced in other countries, both during the last and present century; nor were the alterations which it occasioned in the relative level of hill and valley, land and sea, so great as those effected by some subterranean movements in South America, in later times. The importance of the earthquake in question arises from the circumstance, that Calabria is the only spot hitherto visited, both during and after the convulsions, by men possessing sufficient leisure, zeal, and scientific information, to enable them to collect and describe with accuracy the physical facts which throw light on geological questions.

---

* Ferrara, Camp. fl., p. 51.

† Batav. Trans. vol. viii. p. 141.

Authorities.—Among the numerous authorities, Vivenzio, physician to the King of Naples, transmitted to the court a regular statement of his observations during the continuance of the shocks; and his narrative is drawn up with care and clearness.* Francesco Antonio Grimaldi, then secretary of war, visited the different provinces at the king's command, and published a most detailed description of the permanent changes in the surface.† He measured the length, breadth, and depth of the different fissures and gulphs which opened, and ascertained their number in many provinces. His comments, moreover, on the reports of the inhabitants, and his explanations of their relations, are judicious and instructive. Pignataro, a physician residing at Monteleone, a town placed in the very centre of the convulsions, kept a register of the shocks, distinguishing them into four classes, according to their degree of violence. From his work, it appears that, in the year 1783, the number was 949, of which 501 were shocks of the first degree of force; and in the following year there were 151, of which 98 were of the first magnitude.

Fig. 74.



Count Ippolito, also, and many others, wrote descriptions of the earthquake; and the Royal Academy of Naples, not satisfied with these and other observations, sent a deputation from their own body into Calabria, before the shocks had ceased, who were accompanied by artists instructed to illustrate by drawings the physical changes of the district, and the state of ruined towns and edifices. Unfortunately these artists were not very successful in their representations of the condition of the country, particularly when they attempted to express, on a large scale, the extraordinary revolutions which many of the great and minor river-courses underwent. But many of the plates published by the Academy are valuable; and as they are little known, I shall frequently avail myself of them to illustrate the facts about to be described.*

---

* Istoria de' Tremuoti della Calabria del 1783.

† Descriz. de' Tremuoti Accad. nelle Calabria nel 1783. Napoli, 1784.

In addition to these Neapolitan sources of information, our countryman, Sir William Hamilton, surveyed the district, not without some personal risk, before the shocks had ceased; and his sketch, published in the Philosophical Transactions, supplies many facts that would otherwise have been lost. He has explained, in a rational manner, many events which, as related in the language of some eye-witnesses, appeared marvellous and incredible. Dolomieu also examined Calabria during the catastrophe, and wrote an account of the earthquake, correcting a mistake into which Hamilton had fallen, who supposed that a part of the tract shaken had consisted of volcanic tuff. It is, indeed, a circumstance which enhances the geological interest of the commotions which so often modify the surface of Calabria, that they are confined to a country where there are neither ancient nor modern rocks of volcanic or trappean origin; so that at some future time, when the era of disturbance shall have passed by, the cause of former revolutions will be as latent as in parts of Great Britain now occupied exclusively by ancient marine formations.

Extent of the area convulsed. — The convulsion of the earth, sea, and air extended over the whole of Calabria Ultra, the south-east part of Calabria Citra, and across the sea to Messina and its environs; a district lying between the 38th and 39th degrees of latitude. The concussion was perceptible over a great part of Sicily, and as far north as Naples; but the surface over which the shocks acted so forcibly as to excite intense alarm did not generally exceed 500 square miles in area. The soil of that part of Calabria is composed chiefly, like the southern part of Sicily, of calcareo-argillaceous strata of great thickness, containing marine shells. This clay is sometimes associated with beds of sand and limestone. For the most part these formations resemble in appearance and consistency the Subapennine marls, with their accompanying sands and sandstones; and the whole group bears considerable resemblance, in the yielding nature of its materials, to most of our tertiary deposits in France and England. Chronologically considered, however, the Calabrian formations are comparatively of modern date, often abounding in fossil shells referable to species now living in the Mediterranean.

---

* Istoria de' Fenomeni del Tremoto, &c. nell' An. 1783, posta *in luce dalla* Real. Accad., &c. di Nap. Napoli, 1783, *fol.*

We learn from Vivencio, that on the 20th and 26th of March, 1783, earthquakes occurred in the islands of Zante, Cephalonia, and St. Maura; and in the last-mentioned island several public edifices and private houses were overthrown, and many people destroyed.

If the city of Oppido, in Calabria Ultra, be taken as a centre, and round that centre a circle be described, with a radius of twenty-two miles, this space will comprehend the surface of the country which suffered the greatest alteration, and where all the towns and villages were destroyed. The first shock, of February 5th, 1783, threw down, in two minutes, the greater part of the houses in all the cities, towns, and villages, from the western flanks of the Apennines in Calabria Ultra to Messina in Sicily, and convulsed the whole surface of the country. Another occurred on the 28th of March, with almost equal violence. The granitic chain which passes through Calabria from north to south, and attains the height of many thousand feet, was shaken but slightly by the first shock, but more rudely by some which followed.

Some writers have asserted that the wave-like movements which were propagated through the recent strata, from west to east, became very violent when they reached the point of junction with the granite, as if a reaction was produced where the undulatory movement of the soft strata was suddenly arrested by the more solid rocks. But the statement of Dolomieu on this subject is most interesting, and perhaps, in a geological point of view, the most important of all the observations which are recorded.* The Apennines, he says, which consist in great part of hard and solid granite, with some micaceous and argillaceous schists, form bare mountains with steep sides, and exhibit marks of great degradation. At their base newer strata are seen of sand and clay, mingled with shells; a marine deposit containing such ingredients as would result from the decomposition of granite. The surface of this newer (*tertiary*) formation constitutes what is called the plain of Calabria—a platform which is flat and level, except where intersected by narrow valleys or ravines, which rivers and torrents have excavated sometimes to the depth of six hundred feet. The sides of these ravines are almost perpendicular; for the superior stratum, being bound together by the roots of trees, prevents the formation of a sloping bank. The usual effect of the earthquake, he continues, was to disconnect all those masses which either had not sufficient bases for their bulk, or which were supported only by lateral adherence. Hence it follows that throughout almost the whole length of the chain, the soil which adhered to the granite at the base of the mountains Caulone, Esope, Sagra, and Aspramonte, slid over the solid and steeply inclined nucleus, and descended somewhat lower, leaving almost uninterruptedly from St. George to beyond St. Christina, a distance of from nine to ten miles, a chasm between the solid granitic nucleus and the sandy soil. Many lands slipped thus were carried to a considerable distance from their former position, so as entirely to cover others; and disputes arose as to whom the property which had thus shifted its place should belong.

---

* Dissertation on the Calabrian Earthquake, &c., translated in Pinkerton's Voyages and Travels, vol. v.

From this account of Dolomieu we might anticipate, as the result of a continuance of such earthquakes, first, a longitudinal valley following the line of junction of the older and newer rocks; secondly, greater disturbance in the newer strata near the point of contact than at a greater distance from the mountains; phenomena very common in other parts of Italy at the junction of the Apennine and Subapennine formations.

Mr. Mallet, in his valuable essay on the Dynamics of Earthquakes[*], offers the following explanation of the fact to which Dolomieu has called attention. When a wave of elastic compression, of which he considers the earth-wave to consist, passes abruptly from a body having an extremely low elasticity, such as clay and gravel, into another like granite, whose elasticity is remarkably high, it changes not only its velocity but in part also its course, a portion being reflected and a portion refracted. The wave being thus sent back again produces a shock in the opposite direction, doing great damage to buildings on the surface by thus returning upon itself. At the same time, the shocks are at once eased when they get into the more elastic materials of the granitic mountains.

The surface of the country during the Calabrian earthquakes often heaved like the billows of a swelling sea, which produced a swimming in the head, like sea-sickness. It is particularly stated, in almost all the accounts, that just before each shock the clouds appeared motionless; and, although no explanation is offered of this phenomenon, it is obviously the same as that observed in a ship at sea when it pitches violently. The clouds seem arrested in their career as often as the vessel rises in a direction contrary to their course; so that the Calabrians must have experienced precisely the same motion on the land.

Trees, supported by their trunks, sometimes bent during the shocks to the earth, and touched it with their tops. This is mentioned as a well-known fact by Dolomieu; and he assures us that he was always on his guard against the spirit of exaggeration in which the vulgar are ever ready to indulge when relating these wonderful occurrences.

It is impossible to suppose that these waves, which are described in Italy and other regions of earthquakes as passing along the solid surface of the earth in a given direction like a billow on the sea, have any strict analogy with the undulations of a fluid. They are doubtless the effects of vibrations, radiating from some deep-seated point, each of which on reaching the surface lifts up the ground, and then allows it again to subside. As the distance between the source of the subterranean movement and the surface must vary according to the outline of the country, so the vibratory jar will reach different points in succession.

---

[*] *Proceed. Roy. Irish Acad.* 1846, p. 26.

The Academicians relate that in some of the cities of Calabria effects were produced seeming to indicate a whirling or vorticose movement. Thus, for example, two obelisks (fig. 75.) placed at the extremities of a magnificent facade in the convent of S. Bruno, in a small town called Stefano del Bosco, were observed to have undergone a movement of a singular kind. The shock which agitated the building is described as having been horizontal and vorticose. The pedestal of each obelisk remained in its original place; but the separate stones above were turned partially round, and removed sometimes nine inches from their position without falling.

Fig. 75.



Shifts in the stones of two obelisks in the Convent of S. Bruno.

It has been suggested by Mr. Darwin, that this kind of displacement may be due to a vibratory rather than a whirling motion*; and more lately Mr. Mallet, in the paper already cited, has offered a very ingenious solution of the problem. He refers the twisting simply to an elastic wave, which has moved the pedestal forwards and back again, by an alternate horizontal motion within narrow limits, and he has succeeded in showing that a rectilinear movement in the ground may have sufficed to cause an incumbent body to turn partially round upon its bed, provided a certain relation exist between the position of the centre of gravity of the body and its centre of adherence.†

I shall now consider, in the first place, that class of physical changes produced by the earthquake which are connected with alterations in the relative level of the different parts of the land; and afterwards describe those which are more immediately connected with the derangement of the regular drainage of the country, and where the force of running water co-operated with that of the earthquake.

Difficulty of ascertaining changes of level. — In regard to alterations of relative level, none of the accounts establish that they were on a considerable scale; but it must always be remembered that, in proportion to the area moved is the difficulty of proving that the general level has undergone any change, unless the sea-coast happens to have participated in the principal movement. Even then it is often impossible to determine whether an elevation or depression even of several feet has occurred, because there is nothing to attract notice in a band of shingle and sand of unequal breadth above the level of the sea running parallel to a coast; such bands generally marking the point reached by the waves during spring tides, or the most violent tempests. The scientific investigator has not sufficient topographical knowledge to discover whether the extent of beach has diminished or increased; and he who has the necessary local information, scarcely ever feels any interest in ascertaining the amount of the rise or fall of the ground. Add to this the great difficulty of making correct observations, in consequence of the enormous waves which roll in upon a coast during an earthquake, and efface every landmark near the shore.

---

* Journal of a Naturalist, p. 376., and ii. ib. 308.

† Proceedings Roy. Irish Acad. 1846, pp. 14—16.

Subsidence of the quay at Messina.—It is evidently in seaports alone that we can look for very accurate indications of slight changes of level; and when we find them, we may presume that they would not be rare at other points, if equal facilities of comparing relative altitudes were afforded. Grimaldi states (and his account is confirmed by Hamilton and others), that at Messina, in Sicily, the shore was rent; and the soil along the port, which before the shock was perfectly level, was found afterwards to be inclined towards the sea,—the sea itself near the "Banchina" becoming deeper, and its bottom in several places disordered. The quay also sunk down about fourteen inches below the level of the sea, and the houses in its vicinity were much fissured. (*Phil. Trans.* 1783.)

Among various proofs of partial elevation and depression in the interior, the Academicians mention, in their Survey, that the ground was sometimes on the same level on both sides of new ravines and fissures, but sometimes there had been a considerable shifting, either by the upheaving of one side, or the subsidence of the other. Thus, on the sides of long rents in the territory of Soriano, the stratified masses had altered their relative position to the extent of from eight to fourteen palms (six to ten and a half feet).

Polistena.—Similar shifts in the strata are alluded to in the territory of Polistena, where there appeared innumerable fissures in the earth. One of these was of great length and depth; and in parts the level of the corresponding sides was greatly changed. (See fig. 76.)

Terranuova.—In the town of Terranuova some houses were seen uplifted above the common level, and others adjoining sunk down into the earth. In several streets the soil appeared thrust up, and abutted against the walls of houses: a large circular tower of solid masonry, part of which had withstood the general destruction, was divided by a vertical rent, and one side was upraised, and the foundations heaved out of the ground. It was compared by the Academicians to a great tooth half extracted from the alveolus, with the upper part of the fangs exposed. (See fig. 77.)

Along the line of this shift, or "fault," as it would be termed tech-

Fig. 76.



Deep fissure, near Polistena, caused by the earthquake of 1783.

nically by miners, the walls were found to adhere firmly to each other, and to fit so well, that the only signs of their having been disunited was the want of correspondence in the courses of stone on either side of the rent.

Fig. 77.



Shaft or "fault" in the Round Tower of Terranuova in Calabria, occasioned by the earthquake of 1783.

Dolomieu saw a stone well in the convent of the Augustins at Terranuova, which had the appearance of having been driven out of the earth. It resembled a small tower eight or nine feet in height, and a little inclined. This effect, he says, was produced by the consolidation and consequent sinking of the sandy soil in which the well was dug.

In some walls which had been thrown down, or violently shaken, in Monteleone, the separate stones were parted from the mortar, so as to n exact mould where they had rested; whereas in other cases rtar was ground to dust between the stones.

ıpears that the wave-like motions often produced effects of the ıpricious kind. Thus, in some streets of Monteleone, every was thrown down but one; in others, all but two; and the gs which were spared were often scarcely in the least degree . In many cities of Calabria, all the most solid buildings were down, while those which were slightly built escaped; but at o, as also at Messina in Sicily, it was precisely the reverse, the e edifices being the only ones that stood.

ures.—It appears evident that a great part of the rending and ıg of the ground was the effect of a violent motion from below ls; and in a multitude of cases where the rents and chasms and closed alternately, we must suppose that the earth was by ıeaved up, and then let fall again.* We may conceive the same o be produced on a small scale, if, by some mechanical force, a ent composed of large flags of stone should be raised up, and lowed to fall suddenly, so as to resume its original position. If all pebbles happened to be lying on the line of contact of two hey would fall into the opening when the pavement rose, and llowed up, so that no trace of them would appear after the sub- of the stones. In the same manner, when the earth was up- , large houses, trees, cattle, and men were engulphed in an in chasms and fissures; and when the ground sank down the earth closed upon them, so that no vestige of them was dis- ɔle on the surface. In many instances, individuals were swal- up by one shock, and then thrown out again alive, together ırge jets of water, by the shock which immediately succeeded. erocarne, a country which, according to the Academicians, was *ed* in a most extraordinary manner, the fissures ran in every ɔn "like cracks on a broken pane of glass" (see fig. 78.); and

Fig. 78.



Fissures near Jerocarne, in Calabria, caused by the earthquake of 1783.

---

* See Mr. Mallet's attempt to controvert this view, p. 32. ibid.

greatly widened, lengthened, and deepened by the violent con- ions of March 28th. In the territory of San Fili this observer d a new ravine, half a mile in length, two feet and a half broad, twenty-five feet deep; and another of similar dimensions in the tory of Rosarno. A ravine *nearly a mile long,* 105 feet broad thirty feet deep, opened in the district of Plaisano, where, also, gulfs were caused — one in a place called Cerzulle, three quarters mile long, 150 feet broad, and above *one hundred feet deep;* and her at La Fortuna, nearly a quarter of a mile long, above thirty in breadth, and no less than 225 feet deep.

the district of Fosolano three gulfs opened: one of these ured 300 feet square, and above thirty feet deep; another was ly half a mile long, fifteen feet broad, and above thirty feet deep; hird was 750 feet square. Lastly, a calcareous mountain, called io, at the southern extremity of the Italian peninsula, was cleft in for the length of nearly half a mile, and an irregular breadth of y feet. Some of these chasms were in the form of a crescent. annexed cut (fig. 80.) represents one by no means remarkable for limensions, which remained open by the side of a small pass over



hasm in the hill of St. Angelo, near Soriano, in Calabria, caused by the earthquake of 1783.

hill of St. Angelo, near Soriano. The small river Mesima is n in the foreground.

Formation of circular hollows and new lakes. — In the report of Academy, we find that some plains were covered with circular lows, for the most part about the size of carriage-wheels, but often newhat larger or smaller. When filled with water to within a foot two of the surface, they appeared like wells; but, in general, they re filled with dry sand, sometimes with a concave surface, and at er times convex. (See fig. 81.) On digging down, they found m to be funnel-shaped, and the moist loose sand in the centre rked the tube up which the water spouted. The annexed cut (fig. .) represents a section of one of these inverted cones when the ter had disappeared, and nothing but dry micaceous sand remained

Fig. 81.



Circular hollows in the plain of Rosarno, formed by the earthquake of 1783.

A small circular pond of similar character was formed not far from Polistena (see fig. 83.); and in the vicinity of Seminara, a lake was suddenly caused by the opening of a great chasm, from the bottom of which water issued. This lake was called Lago del Tolfilo. It

Fig. 82.



Section of one of the circular hollows formed in the plain of Rosarno.

extended 1785 feet in length, by 937 in breadth, and 52 in depth. The inhabitants, dreading the miasma of this stagnant pool, endeavoured, at great cost, to drain it by canals, but without success, as it was fed by springs issuing from the bottom of the deep chasm.

Vivenzio states, that near Sitizzano a valley was nearly filled up to a level with the high grounds on each side, by the enormous masses detached from the boundary hills, and cast down into the course of two streams. By this barrier a lake was formed of great depth, about two miles long and a mile broad. The same author mentions that, upon the whole, there were fifty lakes occasioned during the convulsions: and he assigns localities to all of these. The government sur-

Fig. 83.



Circular pond near Polistena, in Calabria, caused by the earthquake in 1783.

veyors enumerated 215 lakes; but they included in this number many small ponds.

Cones of sand thrown up. — Many of the appearances exhibited in the alluvial plains, such as springs spouting up their water like fountains at the moment of the shock, have been supposed to indicate the alternate rising and sinking of the ground. The first effect of the more violent shocks was usually to dry up the rivers, but they immediately afterwards overflowed their banks. In marshy places, an immense number of cones of sand were thrown up. These appearances Hamilton explains, by supposing that the first movement raised the fissured plain from below upwards, so that the rivers and stagnant waters in bogs sank down, or at least were not upraised with the soil. But when the ground returned with violence to its former position, the water was thrown up in jets through fissures.*

The phenomenon, according to Mr. Mallet, may be simply an accident contingent on the principal cause of disturbance, the rapid transit of the earth-wave. "The sources," he says, "of copious springs usually lie in flat plates or fissures filled with water, whether issuing from solid rock, or from loose materials; now, if a vein, or thin flat cavity filled with water, be in such a position that the plane of the plate of water or fissure be transverse to the line of transit of the earth-wave, the effect of the arrival of the earth-wave at the watery fissure will be, at the instant, to compress its walls more or less together, and so squeeze out the water, which will, for a moment, gush up at the springhead like a fountain, and again remain in repose after the transit of the wave."

Gradual closing in of fissures. — Sir W. Hamilton was shown several deep fissures in the vicinity of Mileto, which, although not one of them was above a foot in breadth, had opened so wide during the earthquake as to swallow an ox and nearly one hundred goats. The Academicians also found, on their return through districts which they had passed at the commencement of their tour, that many rents had, in that short interval, gradually closed in, so that their width had diminished several feet, and the opposite walls had sometimes nearly met. It is natural that this should happen in argillaceous strata, while, in more solid rocks, we may expect that fissures will remain open for ages. Should this be ascertained to be a general fact in countries convulsed by earthquakes, it may afford a satisfactory explanation of a common phenomenon in mineral veins. Such veins often retain their full size so long as the rocks consist of limestone, granite, or other indurated materials; but they contract their dimensions, become mere threads, or are even entirely cut off, where masses of an argillaceous nature are interposed. If we suppose the filling up of fissures with metallic and other ingredients to be a process requiring ages for its completion, it is obvious that the opposite walls of rents, where strata consist of yielding materials, must collapse or approach very near to each other before sufficient time is allowed for the accretion of a large quantity of veinstone.

---

* Phil. Trans. vol. lxxiii. p. 180.

Thermal waters augmented. — It is stated by Grimaldi, that the thermal waters of St. Eufemia, in Terra di Amato, which first burst out during the earthquake of 1638, acquired, in February, 1783, an augmentation both in quantity and degree of heat. This fact appears to indicate a connection between the heat of the interior and the fissures caused by the Calabrian earthquakes, notwithstanding the absence of volcanic rocks, either ancient or modern, in that district.

Bounding of detached masses into the air. — The violence of the movement of the ground upwards was singularly illustrated by what the Academicians call the "sbalzo," or bounding into the air, to the height of several yards, of masses slightly adhering to the surface. In some towns a great part of the pavement stones were thrown up, and found lying with their lower sides uppermost. In these cases, we must suppose that they were propelled upwards by the momentum which they had acquired; and that the adhesion of one end of the mass being greater than that of the other a rotatory motion had been communicated to them. When the stone was projected to a sufficient height to perform somewhat more than a quarter of a revolution in the air, it pitched down on its edge, and fell with its lower side uppermost.

Effects of earthquakes on the excavations of valleys. — The next class of effects to be considered, are those more immediately connected with the formation of valleys, in which the action of water was often combined with that of the earthquake. The country agitated was composed, as before stated, chiefly of argillaceous strata, intersected by deep narrow valleys, sometimes from 500 to 600 feet deep. As the boundary cliffs were in great part vertical, it will readily be conceived that, amidst the various movements of the earth, the precipices overhanging rivers, being without support on one side, were often thrown down. We find, indeed, that inundations produced by obstructions in river-courses are among the most disastrous consequences of great earthquakes in all parts of the world, for the alluvial plains in the bottoms of valleys are usually the most fertile and well-peopled parts of the whole country; and whether the site of a town is above or below a temporary barrier in the channel of a river, it is exposed to injury by the waters either of a lake or flood.

Landslips. — From each side of the deep valley or ravine of Terranuova, enormous masses of the adjoining flat country were detached, and cast down into the course of the river, so as to give rise to great lakes. Oaks, olive-trees, vineyards, and corn, were often seen growing at the bottom of the ravine, as little injured as their former companions, which still continued to flourish in the plain above, at least 500 feet higher, and at the distance of about three quarters of a mile. In one part of this ravine was an enormous mass, 200 feet high and about 400 feet at its base, which had been detached by some former earthquake. It is well attested, that this mass travelled down the ravine nearly four miles, having been put in motion by the earthquake of the 5th of February. Hamilton, after examining the spot, declared that this phenomenon might be accounted for by the declivity of the valley, the great abundance of rain which fell, and the great weight of the alluvial matter which pressed behind it. Dolomieu also alludes to the fresh impulse derived from other masses falling, and pressing upon the rear of those first set in motion.

The first account sent to Naples of the two great slides or landslips above alluded to, which caused a great lake near Terranuova, was couched in these words: — "Two mountains on the opposite sides of a valley walked from their original position until they met in the middle of the plain, and there joining together, they intercepted the course of a river," &c. The expressions here used resemble singularly those applied to phenomena, probably very analogous, which are said to have occurred at Fez, during the great Lisbon earthquake, as also in Jamaica and Java at other periods.

Not far from Soriano, which was levelled to the ground by the great shock of February, a small valley, containing a beautiful olive-grove, called Fra Ramondo, underwent a most extraordinary revolution. Innumerable fissures first traversed the river-plain in all directions, and absorbed the water until the argillaceous substratum became soaked, so that a great part of it was reduced to a state of fluid paste. Strange alterations in the outline of the ground were the consequence, as the soil to a great depth was easily moulded into any form. In addition to this change, the ruins of the neighbouring hills were precipitated into the hollow; and while many olives were uprooted, others remained growing on the fallen masses, and inclined at various angles (see fig. 84.). The small river Caridi was entirely concealed for many days; and when at length it reappeared, it had shaped for itself an entirely new channel.

Buildings transported entire to great distances. — Near Seminara an extensive olive-ground and orchard were hurled to a distance of two hundred feet, into a valley sixty feet in depth. At the same

Fig. 84.



Changes of the surface at Fra Ramondo, near Soriano, in Calabria.

1. Portion of a hill covered with olives thrown down.
2. New bed of the river Caridi.
3. Town of Soriano.

time a deep chasm was riven in another part of the high platform from which the orchard had been detached, and the river immediately entered the fissure, leaving its former bed completely dry. A small inhabited house, standing on the mass of earth carried down into the valley, went along with it entire, and without injury to the inhabitants. The olive-trees, also, continued to grow on the land which had slid into the valley, and bore the same year an abundant crop of fruit.

Two tracts of land on which a great part of the town of Polistena stood, consisting of some hundreds of houses, were detached into a contiguous ravine, and nearly across it, about half a mile from their original site; and what is most extraordinary, several of the inhabitants were dug out from the ruins alive and unhurt.

Two tenements, near Mileto, called the Macini and Vaticano, occupying an extent of ground about a mile long and half a mile broad, were carried for a mile down a valley. A thatched cottage, together with large olive and mulberry trees, most of which remained erect, were carried uninjured to this extraordinary distance. According to Hamilton, the surface removed had been long undermined by rivulets, which were afterwards in full view on the bare spot deserted by the tenements. The earthquake seems to have opened a passage in the adjoining argillaceous hills, which admitted water charged with loose soil into the subterranean channels of the rivulets immediately under the tenements, so that the foundations of the ground set in motion by the earthquake were loosened. Another example of subsidence, where the edifices were not destroyed, is mentioned by Grimaldi, as having taken place in the city of Catanzaro, the capital of the province of that name. The houses in the quarter called San Giuseppe subsided with the ground to various depths from two to four feet, but the buildings remained uninjured.

It would be tedious, and our space would not permit us, to follow the different authors through their local details of landslips produced in minor valleys; but they are highly interesting, as showing to how great an extent the power of rivers to widen valleys, and to carry away large portions of soil towards the sea, is increased where earthquakes are of periodical occurrence. Among other territories, that of Cinquefrondi, was greatly convulsed, various portions of soil being raised or sunk, and innumerable fissures traversing the country in all directions (see fig. 85.). Along the flanks of a small valley in this district there appears to have been an almost uninterrupted line of landslips.

Fig. 85.



Landslips near Cinquefrondi, caused by the earthquake of 1783.

Currents of mud. — Near S. Lucido, among other places, the soil is described as having been "dissolved," so that large torrents of mud inundated all the low grounds, like lava. Just emerging from this mud, the tops only of trees and of the ruins of farm-houses were seen. Two miles from Laureana, the swampy soil in two ravines became filled with calcareous matter, which oozed out from the ground immediately before the first great shock. This mud, rapidly accumulating, began, ere long, to roll onward, like a flood of lava, into the valley, where the two streams uniting, moved forward with increased impetus from east to west. It now presented a breadth of 225 feet by 15 in depth, and, before it ceased to move, covered a surface equal in length to an Italian mile. In its progress it overwhelmed a flock of thirty goats, and tore up by the roots many olive and mulberry trees, which floated like ships upon its surface. When this calcareous lava had ceased to move, it gradually became dry and hard, during which process the mass was lowered seven feet and a half. It contained fragments of earth of a ferruginous colour, and emitting a sulphureous smell.

Fall of the sea-cliffs.—Along the sea-coast of the Straits of Messina, near the celebrated rock of Scilla, the fall of huge masses detached from the bold and lofty cliffs overwhelmed many villas and gardens. At Gian Greco, a continuous line of cliff, for a mile in length, was thrown down. Great agitation was frequently observed in the bed of the sea during the shocks, and, on those parts of the coast where the movement was most violent, all kinds of fish were taken in abundance, and with unusual facility. Some rare species, as that called Cicirelli, which usually lie buried in the sand, were taken on the surface of the waters in great quantity. The sea is said to have boiled up near Messina and to have been agitated as if by a copious discharge of vapours from its bottom.

Shore near Scilla inundated.—The prince of Scilla had persuaded a great part of his vassals to betake themselves to their fishing-boats for safety, and he himself had gone on board. On the night of the 5th of February, when some of the people were sleeping in the boats, and others on a level plain slightly elevated above the sea, the earth rocked, and suddenly a great mass was torn from the contiguous Mount Jaci, and thrown down with a dreadful crash upon the plain. Immediately afterwards, the sea, rising more than twenty feet above the level of this low tract, rolled foaming over it, and swept away the multitude. It then retreated, but soon rushed back again with greater violence, bringing with it some of the people and animals it had carried away. At the same time every boat was sunk or dashed against the beach, and some of them were swept far inland. The aged prince, with 1430 of his people, was destroyed.

State of Stromboli and Etna during the shocks.—The inhabitants of Pizzo remarked that, on the 5th of February, 1783, when the first great shock afflicted Calabria, the volcano of Stromboli, which is in full view of that town, and at the distance of about fifty miles, smoked less, and threw up a less quantity of inflamed matter than it had done for some years previously. On the other hand, the great crater of Etna is said to have given out a considerable quantity of vapour towards the beginning, and Stromboli towards the close, of the commotions. But as no eruption happened from either of these great vents during the whole earthquake, the sources of the Calabrian convulsions, and of the volcanic fires of Etna and Stromboli, appear to be very independent of each other; unless, indeed, they have the same mutual relation as Vesuvius and the volcanos of the Phlegræan Fields and Ischia, a violent disturbance in one district serving as a safety-valve to the other, and both never being in full activity at once.

Excavation of valleys.—It is impossible for the geologist to consider attentively the effect of this single earthquake of 1783, and to look forward to the alterations in the physical condition of the country to which a continued series of such movements will hereafter give rise, without perceiving that the formation of valleys by running water can never be understood, if we consider the question independently of the agency of earthquakes. It must not be imagined that rivers only begin to act when a country is already elevated far above the level of the sea, for their action must of necessity be most powerful while land is *rising* and *sinking* by successive movements. Whether Calabria is now undergoing any considerable change of relative level, in regard to the sea, or is, upon the whole, nearly stationary, is a question which our observations, confined almost entirely to the last half century, cannot possibly enable us to determine. But we know that strata, containing species of shells identical with those now living in the contiguous parts of the Mediterranean, have been raised in that country, as they have in Sicily, to the height of several thousand feet.

Now, those geologists who grant that the present course of Nature in the inanimate world has continued the same since the existing species of animals were in being, will not feel surprised that the Calabrian streams and rivers have cut out of such comparatively modern strata a great system of valleys, varying in depth from fifty to six hundred feet, and often several miles wide, if they consider how numerous may have been the shocks which accompanied the uplifting of those recent marine strata to so prodigious a height. Some speculators, indeed, who disregard the analogy of existing Nature, and who are always ready to assume that her forces were more energetic in by-gone ages, may dispense with a long series of movements, and suppose that Calabria "rose like an exhalation" from the deep, after the manner of Milton's Pandemonium. But such an hypothesis would deprive them of that peculiar removing force required to form a regular system of deep and wide valleys; for *time*, which they are so unwilling to assume, is essential to the operation. Time must be allowed in the intervals between distinct convulsions, for running water to clear away the ruins caused by landslips, otherwise the fallen masses will serve as buttresses, and prevent the succeeding earthquake from exerting its full power. The sides of the valley must be again cut away by the stream, and made to form precipices and overhanging cliffs, before the next shock can take effect in the same manner.

Possibly the direction of the succeeding shock may not coincide with that of the valley, a great extent of adjacent country being equally shaken. Still it will usually happen that no permanent geographical change will be produced except in valleys. In them alone will occur landslips from the boundary cliffs, and these will frequently divert the stream from its accustomed course, causing the original ravine to become both wider and more tortuous in its direction.

If a single convulsion of extreme violence should agitate at once an entire hydrographical basin, or if the shocks should follow each other too rapidly, the previously existing valleys would be annihilated, instead of being modified and enlarged. Every stream might in that case be compelled to begin its operations anew, and to shape out new channels, instead of continuing to deepen and widen those already excavated. But if the subterranean movements have been intermittent, and if sufficient periods have always intervened between the severer shocks to allow the drainage of the country to be nearly restored to its original state, then are both the kind and degree of force supplied by which running water may hollow out valleys of any depth or size consistent with the elevation above the sea which the districts drained by them may have attained.

When we read of the drying up and desertion of the channels of rivers, the accounts most frequently refer to their deflection into some other part of the same alluvial plain, perhaps several miles distant. Under certain circumstances, a change of level may undoubtedly force the water to flow over into some distinct hydrographical basin; but even then it will fall immediately into some other system of valleys already formed.

We learn from history that, ever since the first Greek colonists settled in Calabria, that region has been subject to devastation by earthquakes; and, for the last century and a half, ten years have seldom elapsed without a shock; but the severer convulsions have not only been separated by intervals of twenty, fifty, or one hundred years, but have not affected precisely the same points when they recurred. Thus the earthquake of 1783, although confined within the same geographical limits as that of 1638, and not very inferior in violence, visited, according to Grimaldi, very different districts. The points where the local intensity of the force is developed being thus perpetually varied, more time is allowed for the removal of separate mountain masses thrown into river-channels by each shock.

Number of persons who perished during the earthquake.— The number of persons who perished during the earthquake in the two Calabrias and Sicily, is estimated by Hamilton at about forty thousand; and about twenty thousand more died by epidemics, which were caused by insufficient nourishment, exposure to the atmosphere, and malaria, arising from the new stagnant lakes and pools.

By far the greater number were buried under the ruins of their houses; but many were burnt to death in the conflagrations which almost invariably followed the shocks. These fires raged the more violently in some cities, such as Oppido, from the immense magazines of oil which were consumed.

Many persons were engulfed in deep fissures, especially the peasants when flying across the open country, and their skeletons may perhaps be buried in the earth to this day, at the depth of several hundred feet.

When Dolomieu visited Messina after the shock of Feb. 5th, he describes the city as still presenting, at least at a distance, an imperfect image of its ancient splendour. Every house was injured, but the walls were standing: the whole population had taken refuge in wooden huts in the neighbourhood, and all was solitude and silence in the streets: it seemed as if the city had been desolated by the plague, and the impression made upon his feelings was that of melancholy and sadness. "But when I passed over to Calabria, and first beheld Polistena, the scene of horror almost deprived me of my faculties; my mind was filled with mingled compassion and terror; nothing had escaped; all was levelled with the dust; not a single house or piece of wall remained; on all sides were heaps of stone so destitute of form, that they gave no conception of there ever having been a town on the spot. The stench of the dead bodies still rose from the ruins. I conversed with many persons who had been buried for three, four, and even for five days; I questioned them respecting their sensations in so dreadful a situation, and they agreed that, of all the physical evils they endured, thirst was the most intolerable; and that their mental agony was increased by the idea that they were abandoned by their friends, who might have rendered them assistance."*

It is supposed that about a fourth part of the inhabitants of Polistena, and of some other towns, were buried alive, and might have been saved had there been no want of hands; but in so general a calamity, where each was occupied with his own misfortunes or those of his family, aid could rarely be obtained. Neither tears, nor supplications, nor promises of high rewards were listened to. Many acts of self-devotion, prompted by parental and conjugal tenderness, or by friendship, or the gratitude of faithful servants, are recorded; but individual exertions were, for the most part, ineffectual. It frequently happened, that persons in search of those most dear to them could hear their moans,—could recognize their voices—were certain of the exact spot where they lay buried beneath their feet, yet could afford them no succour. The piled mass resisted all their strength, and rendered their efforts of no avail.

At Terranuova, four Augustin monks, who had taken refuge in a vaulted sacristy, the arch of which continued to support an immense pile of ruins, made their cries heard for the space of four days. One only of the brethren of the whole convent was saved, and "of what avail was his strength to remove the enormous weight of rubbish which had overwhelmed his companions?" He heard their voices die away gradually; and when afterwards their four corpses were disinterred, they were found clasped in each other's arms. Affecting narratives are preserved of mothers saved after the fifth, sixth, and even seventh day of their interment, when their infants or children had perished with hunger.

It might have been imagined that the sight of sufferings such as these would have been sufficient to awaken sentiments of humanity and pity in the most savage breasts; but while some acts of heroism are related, nothing could exceed the general atrocity of conduct displayed by the Calabrian peasants: they abandoned the farms, and flocked in great numbers into the towns—not to rescue their countrymen from a lingering death, but to plunder. They dashed through the streets, fearless of danger, amid tottering walls and clouds of dust, trampling beneath their feet the bodies of the wounded and half-buried, and often stripping them, while yet living, of their clothes.†

Concluding remarks.—But to enter more fully into these details would be foreign to the purpose of the present work, and several volumes would be required to give the reader a just idea of the sufferings which the inhabitants of many populous districts have undergone during the earthquakes of the last 150 years. A bare mention of the loss of life — as that fifty or a hundred thousand souls perished in one catastrophe — conveys to the reader no idea of the extent of misery inflicted: we must learn, from the narratives of eye-witnesses, the various forms in which death was encountered, the numbers who escaped with loss of limbs or serious bodily injuries, and the multitude who were suddenly reduced to penury and want. It has been often remarked, that the dread of earthquakes is strongest in the minds of those who have experienced them most frequently; whereas, in the case of almost every other danger, familiarity with peril renders men intrepid. The reason is obvious—scarcely any part of the mischief apprehended in this instance is imaginary; the first shock is often the most destructive; and, as it may occur in the dead of the night, or if by day, without giving the least warning of its approach, no forethought can guard against it; and when the convulsion has begun, no skill, or courage, or presence of mind, can point out the path of safety. During the intervals, of uncertain duration, between the more fatal shocks, slight tremors of the soil are not unfrequent; and as these sometimes precede more violent convulsions, they become a source of anxiety and alarm. The terror arising from this cause alone is of itself no inconsiderable evil.

---

* Pinkerton's Voyages and Travels, vol. v. as cited above p. 455. note.

† Dolomieu, ibid.

Although sentiments of pure religion are frequently awakened by these awful visitations, yet we more commonly find that an habitual state of fear, a sense of helplessness, and a belief in the futility of all human exertions, prepare the minds of the vulgar for the influence of a demoralizing superstition.

Where earthquakes are frequent, there can never be perfect security of property under the best government; industry cannot be assured of reaping the fruits of its labour; and the most daring acts of outrage may occasionally be perpetrated with impunity, when the arm of the law is paralysed by the general consternation. It is hardly necessary to add, that the progress of civilization and national wealth must be retarded by convulsions which level cities to the ground, destroy harbours, render roads impassable, and cause the most cultivated valley-plains to be covered with lakes, or the ruins of adjoining hills.

Those geologists who imagine that, at remote periods ere man became a sojourner on earth, the volcanic agency was more energetic than now, should be careful to found their opinion on strict geological evidence, and not permit themselves to be biassed, as they have often been, by a notion, that the disturbing force would probably be mitigated for the sake of man.

I shall endeavour to point out in the sequel, that the general tendency of subterranean movements, when their effects are considered for a sufficient lapse of ages, is eminently beneficial, and that they constitute an essential part of that mechanism by which the integrity of the habitable surface is preserved, and the very existence and perpetuation of dry land secured. Why the working of this same machinery should be attended with so much evil, is a mystery far beyond the reach of our philosophy, and must probably remain so until we are permitted to investigate, not our planet alone and its inhabitants, but other parts of the moral and material universe with which they may be connected. Could our survey embrace other worlds, and the events, not of a few centuries only, but of periods as indefinite as those with which geology renders us familiar, some apparent contradictions might be reconciled, and some difficulties would doubtless be cleared up. But even then, as our capacities are finite, while the scheme of the universe may be infinite, both in time and space, it is presumptuous to suppose that all sources of doubt and perplexity would ever be removed. On the contrary, they might, perhaps, go on augmenting in number, although our confidence in the wisdom of the plan of Nature should increase at the same time; for it has been justly said, that the greater the circle of light, the greater the boundary of darkness by which it is surrounded.*

CHAPTER XXIX.

EARTHQUAKES — *continued.*

Earthquake of Java, 1772 — Truncation of a lofty cone — St. Domingo, 1770 — Lisbon, 1755 — Great area over which the shocks extended — Retreat of the sea — Proposed explanations — Conception Bay, 1750 — Permanent elevation — Peru, 1746 — Java, 1699 — Rivers obstructed by landslips — Subsidence in Sicily, 1693 — Moluccas, 1693 — Jamaica, 1692 — Large tracts engulphed — Portion of Port Royal sunk — Amount of change in the last 150 years — Elevation and subsidence of land in Bay of Baiæ — Evidence of the same afforded by the Temple of Serapis.

IN the preceding chapters we have considered a small part only of those earthquakes which have occurred during the last seventy years, of which accurate and authentic descriptions happen to have been recorded. In examining those of earlier date we find their number so great that allusion can be made to a few only respecting which information of peculiar geological interest has been obtained.

Java, 1772. — *Truncation of a lofty cone.* — In the year 1772, Papandayang, formerly one of the loftiest volcanos in the island of Java, was in eruption. Before all the inhabitants on the declivities of the mountain could save themselves by flight, the ground began to give way, and a great part of the volcano fell in and disappeared.

---

* Sir H. Davy's Consolations in Travel, p. 246.

It is estimated that an extent of ground of the mountain itself and its immediate environs, fifteen miles long and full six broad, was by this commotion swallowed up in the bowels of the earth. Forty villages were destroyed, some being engulphed and some covered by the substances thrown out on this occasion, and 2957 of the inhabitants perished. A proportionate number of cattle were also killed, and most of the plantations of cotton, indigo, and coffee in the adjacent districts were buried under the volcanic matter. This catastrophe appears to have resembled, although on a grander scale, that of the ancient Vesuvius in the year 79. The cone was reduced in height from 9000 to about 5000 feet; and, as vapours still escape from the crater on its summit, a new cone may one day rise out of the ruins of the ancient mountain, as the modern Vesuvius has risen from the remains of Somma.*

St. Domingo, 1770. — During a tremendous earthquake which destroyed a great part of St. Domingo, innumerable fissures were caused throughout the island, from which mephitic vapours emanated and produced an epidemic. *Hot springs* burst forth in many places where there had been no water before; but after a time they ceased to flow.†

In a previous earthquake, in November, 1751, a violent shock destroyed the capital, Port au Prince, and part of the coast, twenty leagues in length, sank down, and has ever since formed a bay of the sea.‡

Hindostan, 1762. — The town of Chittagong, in Bengal, was violently shaken by an earthquake, on the 2nd of April, 1762, the earth opening in many places, and throwing up water and mud of a sulphureous smell. At a place called Bardavan a large river was dried up; and at Bar Charra, near the sea, a tract of ground sunk down, and 200 people, with all their cattle, were lost. It is said, that sixty square miles of the Chittagong coast suddenly and permanently subsided during this earthquake, and that Ces-lung-Toom, one of the Mug mountains, entirely disappeared, and another sank so low, that its summit only remained visible. Four hills are also described as having been variously rent asunder, leaving open chasms from thirty to sixty feet in width. Towns which subsided several cubits, were overflowed with water; among others, Deep Gong, which was submerged to the depth of seven cubits. Two volcanos are said to have opened in the Secta Cunda hills. The shock was also felt at Calcutta.§ While the Chittagong coast was sinking, a corresponding rise of the ground took place at the island of Ramree, and at Cheduba, (see Map, fig. 39. p. 351.).‖

---

* Dr. Horsfield, Batav. Trans. vol. viii. p. 26. Dr. H. informs me that he has seen this truncated mountain; and, though he did not ascend it, he has conversed with those who have examined it. Raffles's account (History of Java, vol. i.) is derived from Horsfield.

† Essai sur l'Hist. Nat. de l'Isle de St. Domingue. Paris, 1776.

‡ Hist. de l'Acad. des Sciences. 1752. Paris.

§ M'Clelland's Report on Min. Resources of India, 1838. Calcutta. For other particulars, see Phil. Trans. vol. lii.

‖ Journ. Asiat. Soc. Bengal, vol. ii. pp. 351. 433.

Lisbon, 1755. — In no part of the volcanic region of southern Europe has so tremendous an earthquake occurred in modern times, as that which began on the 1st of November, 1755, at Lisbon. A sound of thunder was heard underground, and immediately afterwards a violent shock threw down the greater part of that city. In the course of about six minutes, sixty thousand persons perished. The sea first retired and laid the bar dry; it then rolled in, rising fifty feet or more above its ordinary level. The mountains of Arrabida, Estrella, Julio, Marvan, and Cintra, being some of the largest in Portugal, were impetuously shaken, as it were, from their very foundations; and some of them opened at their summits, which were split and rent in a wonderful manner, huge masses of them being thrown down into the subjacent valleys.* Flames are related to have issued from these mountains, which are supposed to have been electric; they are also said to have smoked; but vast clouds of dust may have given rise to this appearance.

The area over which this convulsion extended is very remarkable. It has been computed, says Humboldt †, that on the 1st November, 1755, a portion of the earth's surface four times greater than the extent of Europe was simultaneously shaken. The shock was felt in the Alps, and on the coast of Sweden, in small inland lakes on the shores of the Baltic, in Thuringia, and in the flat country of northern Germany. The thermal springs of Töplitz dried up, and again returned, inundating every thing with water discoloured by ochre. In the islands of Antigua, Barbadoes, and Martinique in the West Indies, where the tide usually rises little more than two feet, it suddenly rose above twenty feet, the water being discoloured and of an inky blackness. The movement was also sensible in the great lakes of Canada. At Algiers and Fez, in the north of Africa, the agitation of the earth was as violent as in Spain and Portugal; and at the distance of eight leagues from Morocco, a village with the inhabitants, to the number of about 8000 or 10,000 persons, are said to have been swallowed up; the earth soon afterwards closing over them.

Subsidence of the quay. — Among other extraordinary events related to have occurred at Lisbon during the catastrophe was the subsidence of a new quay, built entirely of marble at an immense expense. A great concourse of people had collected there for safety, as a spot where they might be beyond the reach of falling ruins; but suddenly the quay sank down with all the people on it, and not one of the dead bodies ever floated to the surface. A great number of boats and small vessels anchored near it, all full of people, were swallowed up, as in a whirlpool.‡ No fragments of these wrecks ever rose again to the surface, and the water in the place where the quay had stood is stated, in many accounts, to be unfathomable; but Whitehurst says he ascertained it to be one hundred fathoms.§

---

* Hist. and Philos. of Earthquakes, p. 317.

† Cosmos, vol. i.

‡ Rev. C. Davy's Letters, vol. ii. Letter ii. p. 12., who was at Lisbon at the time, and ascertained that the boats and vessels said to have been swallowed were missing.

§ On the Formation of the Earth, p. 55.

Circumstantial as are the contemporary narratives, I learn from a correspondent, Mr. F. Freeman, in 1841, that no part of the Tagus was then more than thirty feet deep at high tide, and an examination of the position of the new quay, and the memorials preserved of the time and manner in which it was built, render the statement of so great a subsidence in 1755 quite unintelligible. Perhaps a deep narrow chasm, such as was before described in Calabria (p. 481.), opened and closed again in the bed of the Tagus, after swallowing up some incumbent buildings and vessels. We have already seen that such openings may collapse after the shock suddenly, or in places where the strata are of soft and yielding materials, very gradually. According to the observations made at Lisbon, in 1837, by Mr. Sharpe, the destroying effects of this earthquake were confined to the tertiary strata, and were most violent on the blue clay, on which the lower part of the city is constructed. Not a building, he says, on the secondary limestone or the basalt was injured.*

Shocks felt at sea.—The shock was felt at sea, on the deck of a ship to the west of Lisbon, and produced very much the same sensation as on dry land. Off St. Lucar, the captain of the ship Nancy felt his vessel so violently shaken, that he thought she had struck the ground; but, on heaving the lead, found a great depth of water. Captain Clark, from Denia, in latitude 36° 24′ N., between nine and ten in the morning, had his ship shaken and strained as if she had struck upon a rock, so that the seams of the deck opened, and the compass was overturned in the binnacle. Another ship, forty leagues west of St. Vincent, experienced so violent a concussion, that the men were thrown a foot and a half perpendicularly up from the deck.

Rate at which the movement travelled.—The agitation of lakes, rivers, and springs, in Great Britain, was remarkable. At Loch Lomond, in Scotland, for example, the water, without the least apparent cause, rose against its banks, and then subsided below its usual level. The greatest perpendicular height of this swell was two feet four inches. It is said that the movement of this earthquake was undulatory, and that it travelled at the rate of twenty miles a minute, its velocity being calculated by the intervals between the time when the first shock was felt at Lisbon, and its time of occurrence at other distant places.†

Great wave and retreat of the sea.—A great wave swept over the coast of Spain, and is said to have been sixty feet high at Cadiz. At Tangier, in Africa, it rose and fell eighteen times on the coast. At Funchal, in Madeira, it rose full fifteen feet perpendicular above high-water mark, although the tide, which ebbs and flows there seven feet, was then at half-ebb. Besides entering the city, and committing great havoc, it overflowed other seaports in the island. At Kinsale, in Ireland, a body of water rushed into the harbour, whirled round several vessels, and poured into the market-place.

---

* Geol. Soc. Proceedings, No. 60. p. 36. 1838.

† Michell on Earthquakes, Phil. Trans. vol. li. p. 566. 1760.

It was before stated that the sea first retired at Lisbon; and this retreat of the ocean from the shore, at the commencement of an earthquake, and its subsequent return in a violent wave, is a common occurrence. In order to account for the phenomenon, Michell imagined a subsidence at the bottom of the sea, from the giving way of the roof of some cavity in consequence of a vacuum produced by the condensation of steam. Such condensation, he observes, might be the first effect of the introduction of a large body of water into fissures and cavities already filled with steam, before there has been sufficient time for the heat of the incandescent lava to turn so large a supply of water into steam, which being soon accomplished causes a greater explosion.

Another proposed explanation is, the sudden rise of the land, which would cause the sea to abandon immediately the ancient line of coast; and if the shore, after being thus heaved up, should fall again to its original level, the ocean would return. This theory, however, will not account for the facts observed during the Lisbon earthquake; for the retreat preceded the wave, not only on the coast of Portugal, but also at the island of Madeira, and several other places. If the upheaving of the coast of Portugal had caused the retreat, the motion of the waters, when propagated to Madeira, would have produced a wave previous to the retreat. Nor could the motion of the waters at Madeira have been caused by a different local earthquake; for the shock travelled from Lisbon to Madeira in two hours, which agrees with the time which it required to reach other places equally distant.*

The following is another solution of the problem, which has been offered: — Suppose a portion of the bed of the sea to be suddenly upheaved; the first effect will be to raise over the elevated part a body of water, the momentum of which will carry it much above the level it will afterwards assume, causing a draught or receding of the water from the neighbouring coasts, followed immediately by the return of the displaced water, which will also be impelled by its momentum much farther and higher on the coast than its former level.†

Mr. Darwin, when alluding to similar waves on the coast of Chili, states his opinion, that "the whole phenomenon is due to a common undulation in the water, proceeding from a line or point of disturbance some little way distant. If the waves," he says, "sent off from the paddles of a steam-vessel be watched breaking on the sloping shore of a still river, the water will be seen first to retire two or three feet, and then to return in little breakers, precisely analogous to those consequent on an earthquake." He also adds, that "the earthquake-wave occurs some time after the shock, the water at first retiring both from the shores of the mainland and of outlying islands, and then returning in mountainous breakers. Their size is modified by the form of the neighbouring coast; for it is ascertained in South America, that places situated at the head of shoaling bays have suffered most, whereas towns like Valparaiso, seated close on the border of a profound ocean, have never been inundated, though severely shaken by earthquakes."*

---

* Michell, Phil. Trans. vol. li. p. 614.

† Quarterly Review, No. lxxxvi. p. 459.

More recently (February, 1846), Mr. Mallet, in his memoir above cited (p. 475.), has endeavoured to bring to bear on this difficult subject the more advanced knowledge obtained of late years respecting the true theory of waves. He conceives that when the origin of the shock is beneath the deep ocean, one wave is propagated through the land, and another moving with inferior velocity is formed on the surface of the ocean. This last rolls in upon the land long after the earth-wave has arrived and spent itself. However irreconcileable it may be to our common notions of solid bodies, to imagine them capable of transmitting, with such extreme velocity, motions analogous to tidal waves, it seems nevertheless certain that such undulations are produced, and it is supposed that when the shock passes a given point, each particle of the solid earth describes an ellipse in space. The facility with which all the particles of a solid mass can be made to vibrate may be illustrated, says Gay Lussac, by many familiar examples. If we apply the ear to one end of a long wooden beam, and listen attentively when the other end is struck by a pin's head, we hear the shock distinctly; which shows that every fibre throughout the whole length has been made to vibrate. The rattling of carriages on the pavement shakes the largest edifices; and in the quarries underneath some quarters in Paris, it is found that the movement is communicated through a considerable thickness of rock.†

The great sea-wave originating directly over the centre of disturbance is propagated, as Michell correctly stated, in every direction, like the circle upon a pond when a pebble is dropped into it, the different rates at which it moves depending (as he also suggested) on variations in the depth of the water. This wave of the sea, says Mr. Mallet, is raised by the impulse of the shock immediately below it, which in great earthquakes lifts up the ground two or three feet perpendicularly. The velocity of the shock, or earth-wave is greater because it "depends upon a function of the elasticity of the crust of the earth, whereas the velocity of the sea-wave depends upon a function of the depth of the sea."

"Although the shock in its passage under the deep ocean gives no trace of its progress, it no sooner gets into soundings or shallow water, than it gives rise to another and smaller wave of the sea. It carries, as it were, upon its back, this lesser aqueous undulation; a long narrow ridge of water which corresponds in form and velocity to itself, being pushed up by the partial elevation of the bottom. It is this small wave, called technically the 'forced sea-wave,' which communicates the earthquake-shock to ships at sea, as if they had struck upon a rock. It breaks upon a coast at the same moment that the shock reaches it, and sometimes it may cause an apparent slight recession from the shore, followed by its flowing up somewhat higher than the usual tide mark: this will happen where the beach is very sloping, as is usual where the sea is shallow, for then the velocity of the low flat earth-wave is such, that it slips as it were, from under the undulation in the fluid above. It does this at the moment of reaching the beach, which it elevates by a vertical height equal to its own, and as instantly lets drop again to its former level."

---

* Darwin's Travels in South America, &c. 1832 to 1836. Voyage of H. M. S. Beagle, vol. iii. p. 377.

† Ann. de Ch. et de Ph., tom. xxii. p. 428.

"While the shock propagated through the solid earth has thus travelled with extra rapidity to the land, the great sea-wave has been following at a slower pace, though advancing at the rate of several miles in a minute. It consists in the deep ocean, of a long low swell of enormous volume, having an equal slope before and behind, and that so gentle that it might pass under a ship without being noticed. But when it reaches the edge of soundings, its front slope, like that of a tidal wave under similar circumstances, becomes short and steep, while its rear slope is long and gentle. If there be water of some depth close into shore, this great wave may roll in long after the shock, and do little damage: but if the shore be shelving, there will be first a retreat of the water, and then the wave will break upon the beach and roll in far upon the land."*

The various opinions which have been offered by Michell and later writers, respecting the remote causes of earthquake shocks in the interior of the earth, will more properly be discussed in the thirty-second chapter.

Chili, 1751.—On the 24th of May, 1751, the ancient town of Conception, otherwise called Penco, was totally destroyed by an earthquake, and the sea rolled over it. (See plan of the bay, fig. 70. p. 455.) The ancient port was rendered entirely useless, and the inhabitants built another town about ten miles from the sea-coast, in order to be beyond the reach of similar inundations. At the same time, a colony recently settled on the sea-shore of Juan Fernandez was almost entirely overwhelmed by a wave which broke upon the shore.

It has been already stated, that in 1835, or eighty-four years after the destruction of Penco, the same coast was overwhelmed by a similar flood from the sea during an earthquake; and it is also known that twenty-one years before (or in 1730), a like wave rolled over these fated shores, in which many of the inhabitants perished. A series of similar catastrophes has also been tracked back as far as the year 1590†, beyond which we have no memorials save those of oral tradition. Molina, who has recorded the customs and legends of the aborigines, tells us, that the Araucanian Indians, a tribe inhabiting the country between the Andes and Pacific, including the part now called Chili, "had among them a tradition of a great deluge, in which only a few persons were saved, who took refuge upon a high mountain called Thegtheg, "the thundering," which had three points. Whenever a violent earthquake occurs, these people fly for safety to the mountains, assigning as a reason, that they are fearful, after the shock, that the sea will again return and deluge the world.*

---

* Mallet, Proceed. Roy. Irish Acad. 1846.

† See Father Acosta's work; and Sir Woodbine Parish, Geol. Soc. Proceedings, vol. ii. p. 215.

Notwithstanding the tendency of writers in his day to refer all traditionary inundations to one remote period, Molina remarks that this flood of the Araucanians "was probably very different from that of Noah." We have, indeed, no means of conjecturing how long this same tribe had flourished in Chili, but we can scarcely doubt, that if its experience reached back even for three or four centuries, several inroads of the ocean must have occurred within that period. But the memory of a succession of physical events, similar in kind, though distinct in time, can never be preserved by a people destitute of written annals. Before two or three generations have passed away all dates are forgotten, and even the events themselves, unless they have given origin to some customs, or religious rites and ceremonies. Oftentimes the incidents of many different earthquakes and floods become blended together in the same narrative; and in such cases the single catastrophe is described in terms so exaggerated, or is so disguised by mythological fictions, as to be utterly valueless to the antiquary or philosopher.

Proofs of elevation of twenty-four feet.—During a late survey of Conception Bay, Captains Beechey and Sir E. Belcher discovered that the ancient harbour, which formerly admitted all large merchant vessels which went round the Cape, is now occupied by a reef of sandstone, certain points of which project above the sea at low water, the greater part being very shallow. A tract of a mile and a half in length, where, according to the report of the inhabitants, the water was formerly four or five fathoms deep, is now a shoal; consisting, as our hydrographers found, of hard sandstone, so that it cannot be supposed to have been formed by recent deposits of the river Biobio, an arm of which carries down loose micaceous sand into the same bay.

It is impossible at this distance of time to affirm that the bed of the sea was uplifted at once to the height of twenty-four feet, during the single earthquake of 1751, because other movements may have occurred subsequently; but it is said, that ever since the shock of 1751, no vessels have been able to approach within a mile and a half of the ancient port of Penco. (See Map, p. 455.) In proof of the former elevation of the coast near Penco our surveyors found above high-water mark an enormous bed of shells of the same species as those now living in the bay, filled with micaceous sand like that which the Biobio now conveys to the bay. These shells, as well as others, which cover the adjoining hills of mica-schist to the height of several hundred feet, have lately been examined by experienced conchologists in London, and identified with those taken at the same time in a living state from the bay and its neighbourhood.†

---

* Molina, Hist. of Chili, vol. ii. p.

† Captain Belcher has shown me these shells, and the collection has been examined by Mr. Broderip.

Ulloa, therefore, was perfectly correct in his statement that, at various heights above the sea between Talcahuano and Conception, "mines were found of various sorts of shells used for lime of the very same kinds as those found in the adjoining sea." Among them he mentions the great mussel called Choros, and two others which he describes. Some of these, he says, are entire, and others broken; they occur at the bottom of the sea, in four, six, ten, or twelve fathom water, where they adhere to a sea-plant called Cochayuyo. They are taken in dredges, and have no resemblance to those found on the shore or in shallow water; yet beds of them occur at various heights on the hills. "I was the more pleased with the sight," he adds, "as it appeared to me a convincing proof of the universality of the deluge, although I am not ignorant that some have attributed their position to other causes." * It has, however, been ascertained that the foundation of the Castle of Penco was so low in 1835, or at so inconsiderable an elevation above the highest spring tides, as to discountenance the idea of any permanent upheaval in modern times, on the site of that ancient port; but no exact measurements or levellings appear as yet to have been made to determine this point, which is the more worthy of investigation, because it may throw some light on an opinion often promulgated of late years, that there is a tendency in the Chilian coast, after each upheaval, to sink gradually and return towards its former position.

Peru, 1746.—Peru was visited, on the 28th of October, 1746, by a tremendous earthquake. In the first twenty-four hours, two hundred shocks were experienced. The ocean twice retired and returned impetuously upon the land: Lima was destroyed, and part of the coast near Callao was converted into a bay: four other harbours, among which were Cavalla and Guanape, shared the same fate. There were twenty-three ships and vessels, great and small, in the harbour of Callao, of which nineteen were sunk; and the other four, among which was a frigate called St. Fermin, were carried by the force of the waves to a great distance up the country, and left on dry ground at a considerable height above the sea. The number of inhabitants in this city amounted to four thousand. Two hundred only escaped, twenty-two of whom were saved on a small fragment of the fort of Vera Cruz, which remained as the only memorial of the town after this dreadful inundation. Other portions of its site were completely covered with heaps of sand and gravel.

A volcano in Lucanas burst forth the same night, and such quantities of water descended from the cone that the whole country was overflowed; and in the mountain near Pataz, called Conversiones de Caxamarquilla, three other volcanos burst out, and frightful torrents of water swept down their sides.†

There are several records of prior convulsions in Peru, accompanied by similar inroads in the sea, one of which happened fifty-nine years before (in 1687), when the ocean, according to Ulloa, first retired and then returned in a mountainous wave, overwhelming Callao and its environs, with the miserable inhabitants.* This same wave, according to Lionel Wafer, carried ships a league into the country, and drowned man and beast for fifty leagues along the shore.† Inundations of still earlier dates are carefully recorded by Ulloa, Wafer, Acosta, and various writers, who describe them as having expended their chief fury some on one part of the coast some on another.

---

* Ulloa's Voyage to South America, vol. ii. book viii. ch. vi.

† Ibid. vol. ii. book vii. chap. vii.

But all authentic accounts cease when we ascend to the era of the conquest of Peru by the Spaniards. The ancient Peruvians, although far removed from barbarism, were without written annals, and therefore unable to preserve a distinct recollection of a long series of natural events. They had, however, according to Antonio de Herrera, who, in the beginning of the seventeenth century, investigated their antiquities, a tradition, "that many years before the reign of the Incas, at a time when the country was very populous, there happened a great flood; the sea breaking out beyond its bounds, so that the land was covered with water and all the people perished. To this the Guacas, inhabiting the vale of Xausca, and the natives of Chiquito, in the province of Callao, add that some persons remained in the hollows and caves of the highest mountains, who again peopled the land. Others of the mountain people affirm that all perished in the deluge, only six persons being saved on a float, from whom descended all the inhabitants of that country."‡

On the mainland near Lima, and on the neighbouring island of San Lorenzo, Mr. Darwin found proofs that the ancient bed of the sea had been raised to the height of more than eighty feet above water within the human epoch, strata having been discovered at that altitude, containing pieces of cotton thread and plaited rush, together with sea-weed and marine shells.§ The same author learnt from Mr. Gill, a civil engineer, that he discovered in the interior near Lima, between Casma and Huaraz, the dried-up channel of a large river, sometimes worn through solid rock, which, instead of continually ascending towards its source, has, in one place, a steep downward slope in that direction, for a ridge or line of hills has been uplifted directly across the bed of the stream, which is now arched. By these changes the water has been turned into some other course: and a district, once fertile, and still covered with ruins, and bearing the marks of ancient cultivation, has been converted into a desert.‖

Java, 1699. — On the 5th of January, 1699, a terrible earthquake visited Java, and no less than 208 considerable shocks were reckoned. Many houses in Batavia were overturned, and the flame and noise of a volcanic eruption were seen and heard in that city, which were afterwards found to proceed from Mount Salek¶, a volcano six days' journey distant. Next morning the Batavian river, which has its rise from that mountain, became very high and muddy, and brought down abundance of bushes and trees, half burnt. The channel of the river being stopped up, the water overflowed the country round the gardens about the town, and some of the streets, so that fishes lay dead in them. All the fish in the river, except the carps, were killed by the mud and turbid water. A great number of drowned buffaloes, tigers, rhinoceroses, deer, apes, and other wild beasts, were brought down by the current; and, "notwithstanding," observes one of the writers, "that a crocodile is amphibious, several of them were found dead among the rest."*

---

* Ulloa's Voyage, vol. ii. p. 82.

† Wafer, cited by Sir W. Parish, Geol. Soc. Proceedings, vol. ii. p. 215.

‡ Hist. of America, decad. iii. book xi. ch. i.

§ Darwin's Journal, p. 451.

‖ Ibid. p. 413.

¶ Misspelt "Sales" in Hooke's Account.

It is stated that seven hills bounding the river sank down; by which is merely meant, as by similar expressions in the description of the Calabrian earthquakes, seven great landslips. These hills, descending some from one side of the valley and some from the other, filled the channel, and the waters then finding their way under the mass, flowed out thick and muddy, The Tangaran river was also dammed up by nine hills, and in its channel were large quantities of drift trees. Seven of its tributaries also are said to have been "covered up with earth." A high tract of forest land, between the two great rivers before mentioned, is described as having been changed into an open country, destitute of trees, the surface being spread over with a fine red clay. This part of the account may, perhaps, merely refer to the sliding down of woody tracts into the valleys, as happened to so many extensive vineyards and olive-grounds in Calabria, in 1783. The close packing of large trees in the Batavian river is represented as very remarkable, and it attests in a striking manner the destruction of soil bordering the valleys which had been caused by floods and landslips.†

Quito, 1698. — In Quito, on the 19th of July, 1698, during an earthquake, a great part of the crater and summit of the volcano Carguairazo fell in, and a stream of water and mud issued from the broken sides of the hill.‡

Sicily, 1693. — Shocks of earthquakes spread over all Sicily in 1693, and on the 11th of January the city of Catania and forty-nine other places were levelled to the ground, and about one hundred thousand people killed. The bottom of the sea, says Vicentino Bonajutus, sank down considerably, both in ports, inclosed bays, and open parts of the coast, and water bubbled up along the shores. Numerous long fissures of various breadths were caused, which threw out sulphurous water; and one of them, in the plain of Catania (the delta of the Simeto), at the distance of four miles from the sea, sent forth water as salt as the sea. The stone buildings of a street in the city of Noto, for the length of half a mile, sank into the ground, and remained hanging on one side. In another street, an opening large enough to swallow a man and horse appeared.§

---

* Hooke's Posthumous Works, p. 437. 1705.

† Phil. Trans. 1700.

‡ Humboldt, Atl. Pit. p. 106.

§ Phil. Trans. 1693-4.

Moluccas, 1693.—The small Isle of Sorea, which consists of one great volcano, was in eruption in the year 1693. Different parts of the cone fell, one after the other, into a deep crater, until almost half the space of the island was converted into a fiery lake. Most of the inhabitants fled to Banda; but great pieces of the mountain continued to fall down, so that the lake of lava became wider; and finally the whole population was compelled to emigrate. It is stated that, in proportion as the burning lake increased in size, the earthquakes were less vehement.*

Jamaica, 1692.—In the year 1692, the island of Jamaica was visited by a violent earthquake; the ground swelled and heaved like a rolling sea, and was traversed by numerous cracks, two or three hundred of which were often seen at a time, opening and then closing rapidly again. Many people were swallowed up in these rents; some the earth caught by the middle, and squeezed to death; the heads of others only appeared above ground; and some were first engulphed, and then cast up again with great quantities of water. Such was the devastation, that even in Port Royal, then the capital, where more houses are said to have been left standing than in the whole island beside, three quarters of the buildings, together with the ground they stood on, sank down with their inhabitants entirely under water.

Subsidence in the harbour.—The large store-houses on the harbour side subsided, so as to be twenty-four, thirty-six, and forty-eight feet under water; yet many of them appear to have remained standing, for it is stated that, after the earthquake, the mast-heads of several ships wrecked in the harbour, together with the chimney-tops of houses, were just seen projecting above the waves. A tract of land round the town, about a thousand acres in extent, sank down in less than one minute, during the first shock, and the sea immediately rolled in. The Swan frigate, which was repairing in the wharf, was driven over the tops of many buildings, and then thrown upon one of the roofs, through which it broke. The breadth of one of the streets is said to have been doubled by the earthquake.

According to Sir H. De la Beche, the part of Port Royal described as having sunk was built upon newly formed land, consisting of sand, in which piles had been driven; and the *settlement* of this loose sand, charged with the weight of heavy houses, may, he suggests, have given rise to the subsidences alluded to.†

There have undoubtedly been instances in Calabria and elsewhere of slides of land on which the houses have still remained standing; and it is possible that such may have been the case at Port Royal. The fact at least of submergence is unquestionable, for I was informed by the late Admiral Sir Charles Hamilton that he frequently saw the submerged houses of Port Royal in the year 1780, in that part of the harbour which lies between the town and the usual anchorage of men-of-war. Bryan Edwards also says, in his history of the West Indies, that in 1793 the *ruins* were visible in clear weather from the boats which sailed over them.* Lastly, Lieutenant B. Jeffery, R. N., tells me that, being engaged in a survey between the years 1824 and 1835, he repeatedly visited the site in question, where the depth of the water is from four to six fathoms, and whenever there was but little wind perceived distinct traces of houses. He saw these more clearly when he used the instrument called the "diver's eye," which is let down below the ripple of the wave.†

---

* Phil. Trans. 1693.

† Manual of Geol., p. 133., second edition.

At several thousand places in Jamaica the earth is related to have opened. On the north of the island, several plantations, with their inhabitants, were swallowed up, and a lake appeared in their place, covering above a thousand acres, which afterwards dried up, leaving nothing but sand and gravel, without the least sign that there had ever been a house or a tree there. Several tenements at Yallows were buried under land-slips; and one plantation was removed half a mile from its place, the crops continuing to grow upon it uninjured. Between Spanish Town and Sixteen-mile Walk, the high and perpendicular cliffs bounding the river fell in, stopped the passage of the river and flooded the latter place for nine days, so that the people "concluded it had been sunk as Port Royal was." But the flood at length subsided, for the river had found some new passage at a great distance.

Mountains shattered.—The Blue and other of the highest mountains are declared to have been strangely torn and rent. They appeared shattered and half-naked, no longer affording a fine green prospect, as before, but stripped of their woods and natural verdure. The rivers on these mountains first ceased to flow for about twenty-four hours, and then brought down into the sea, at Port Royal and other places, several hundred thousand tons of timber, which looked like floating islands on the ocean. The trees were in general barked, most of their branches having been torn off in the descent. It is particularly remarked in this, as in the narratives of so many earthquakes, that fish were taken in great numbers on the coast during the shocks. The correspondents of Sir Hans Sloane, who collected with care the accounts of eye-witnesses of the catastrophe, refer constantly to *subsidences*, and some supposed the whole of Jamaica to have sunk down.‡

Reflections on the amount of change in the last one hundred and sixty years.—I have now only enumerated some few of the earthquakes of the last 160 years, respecting which facts illustrative of geological inquiries are on record. Even if my limits permitted, it would be an unprofitable task to examine all the obscure and ambiguous narratives of similar events of earlier epochs; although, if the places were now examined by geologists well practised in the art of interpreting the monuments of physical changes, many events which have happened within the historical era might doubtless be still determined with precision. It must not be imagined that, in the above sketch of the occurrences of a short period, I have given an account of all, or even the greater part, of the mutations which the earth has undergone by the agency of subterranean movements. Thus, for example, the earthquake of Aleppo, in the present century, and of Syria, in the middle of the eighteenth, would doubtless have afforded numerous phenomena, of great geological importance, had those catastrophes been described by scientific observers. The shocks in Syria in 1759, were protracted for three months, throughout a space of ten thousand square leagues: an area compared to which that of the Calabrian earthquake in 1783 was insignificant. Accon, Saphat, Balbeck, Damascus, Sidon, Tripoli, and many other places, were almost entirely levelled to the ground. Many thousands of the inhabitants perished in each; and, in the valley of Balbeck alone, 20,000 men are said to have been victims to the convulsion. In the absence of scientific accounts, it would be as irrelevant to our present purpose to enter into a detailed account of such calamities, as to follow the tract of an invading army, to enumerate the cities burnt or rased to the ground, and reckon the number of individuals who perished by famine or the sword.

---

* Vol. i. p. 235. 8vo ed. 3 vols. 1801.

† Letter to the Author, May 1838.

‡ Phil. Trans. 1694.

Deficiency of historical records.—If such, then, be the amount of ascertained changes in the last 160 years, notwithstanding the extreme deficiency of our records during that brief period, how important must we presume the physical revolutions to have been in the course of thirty or forty centuries, during which some countries habitually convulsed by earthquakes have been peopled by civilized nations! Towns engulphed during one earthquake may, by repeated shocks, have sunk to great depths beneath the surface, while the ruins remain as imperishable as the hardest rocks in which they are enclosed. Buildings and cities, submerged, for a time, beneath seas or lakes, and covered with sedimentary deposits, must, in some places, have been re-elevated to considerable heights above the level of the ocean. The signs of these events have, probably, been rendered visible by subsequent mutations, as by the encroachments of the sea upon the coast, by deep excavations made by torrents and rivers, by the opening of new ravines, and chasms, and other effects of natural agents, so active in districts agitated by subterranean movements.

If it be asked why, if such wonderful monuments exist, so few have hitherto been brought to light, we reply—because they have not been searched for. In order to rescue from oblivion the memorials of former occurrences, the inquirer must know what he may reasonably expect to discover, and under what peculiar local circumstances. He must be acquainted with the action and effect of physical causes, in order to recognize, explain, and describe correctly the phenomena when they present themselves.

The best known of the great volcanic regions, of which the boundaries were sketched in the twenty-second chapter, is that which includes Southern Europe, Northern Africa, and Central Asia; yet nearly the whole, even of this region, must be laid down, in a geological map, as "Terra Incognita." Even Calabria may be regarded as unexplored, as also Spain, Portugal, the Barbary States, the Ionian Isles, Asia Minor, Cyprus, Syria, and the countries between the Caspian and Black seas. We are, in truth, beginning to obtain some insight into one small spot of that great zone of volcanic disturbance, the district around Naples; a tract by no means remarkable for the violence of the earthquakes which have convulsed it.

If, in this part of Campania, we are enabled to establish, that considerable changes in the relative level of land and sea have taken place since the Christian era, it is all that we could have expected; and it is to recent antiquarian and geological research, not to history, that we are principally indebted for the information. I shall now proceed to lay before the reader some of the results of modern investigations in the Bay of Baiæ and the adjoining coast.

PROOFS OF ELEVATION AND SUBSIDENCE IN THE BAY OF BAIÆ.

Temple of Jupiter Serapis.—This celebrated monument of antiquity, a representation of which is given in the frontispiece*, affords in itself alone, unequivocal evidence that the relative level of land and sea has changed twice at Puzzuoli since the Christian era; and each movement, both of elevation and subsidence, has exceeded twenty feet. Before examining these proofs, I may observe, that a geological examination of the coast of the Bay of Baiæ, both on the

Fig. 86.



Ground plan of the coast of the Bay of Baiæ, in the environs of Puzzuoli.

---

* This view of the temple (substituted for one by A. de Jorio, given in the earlier editions) has been reduced from part of a beautiful coloured drawing taken in *1836, with the aid of the* camera lucida, by Mr. I'Anson, to illustrate a paper by Mr. Babbage on the temple, read March, 1834, and published in the Quart. Journ. of the Geol. Soc. of London, vol. iii. 1847.

north and south of Puzzuoli, establishes, in the most satisfactory manner, an elevation, at no remote period, of more than twenty feet, and, at one point, of more than thirty feet; and the evidence of this change would have been complete, if even the temple had, to this day, remain undiscovered.

Coast south of Puzzuoli.—If we coast along the shore from Naples to Puzzuoli, we find, on approaching the latter place, that the lofty and precipitous cliffs of indurated tuff, resembling that of which Naples is built, retire slightly from the sea; and that a low level tract of fertile land, of a very different aspect, intervenes between the present sea-beach and what was evidently the ancient line of coast.

The inland cliff may be seen opposite the small island of Nisida, about two miles and a half south-east of Puzzuoli (see Map, fig. 40. p. 361.), where, at the height of thirty-two feet above the level of the sea, Mr. Babbage observed an ancient mark, such as might have been worn by the waves; and, upon farther examination, discovered that, along that line, the face of the perpendicular rock, consisting of very hard tuff, was covered with barnacles (*Balanus sulcatus*, Lamk.), and drilled by boring testacea. Some of the hollows of the lithodomi contained the shells; while others were filled with the valves of a species of Arca.* Nearer to Puzzuoli, the inland cliff is eighty feet high, and as perpendicular as if it was still undermined by the waves. At its base, a new deposit, constituting the fertile tract above alluded to, attains a height of about twenty feet above the sea; and, since it is composed of regular sedimentary deposits, containing marine shells, its position proves that, subsequently to its formation, there has been a change of more than twenty feet in the relative level of land and sea.

Fig. 87.



a, Antiquities on hill S. E. of Puzzuoli (see ground plan, fig. 86.).
b, Ancient cliff now inland.
c, Terrace composed of recent submarine deposit.

The sea encroaches on these new incoherent strata; and as the soil is valuable, a wall has been built for its protection; but when I visited the spot in 1828, the waves had swept away part of this rampart, and exposed to view a regular series of strata of tuff, more or less argillaceous, alternating with beds of pumice and lapilli, and containing great abundance of marine shells, of species now common on this coast, and amongst them *Cardium rusticum, Ostrea edulis, Donax trunculus*, Lamk., and others. The strata vary from about a foot to a foot and a half in thickness, and one of them contains abundantly remains of works of art, tiles, squares of mosaic pavement of different colours, and small sculptured ornaments, perfectly uninjured. Intermixed with these I collected some teeth of the pig and

---

* Mr. Babbage examined this spot in company with Sir Edmund Head in June, 1828, and has shown me numerous specimens of the shells collected there, and in the Temple of Serapis.



1. Puzzuoli. 2. Temple of Serapis. 3. Caligula's Bridge. 4. Monte Barbaro. 5. Monte Nuovo. 6. Baths of Nero. 7. Baiæ. 8. Castle of Baiæ. 9. Bauli. 10. Cape Misenum. 11. Mount Epomeo in Ischia. 12. South part of Ischia.

ox. These fragments of building occur below as well as above strata containing marine shells. Puzzuoli itself stands chiefly on a promontory of the older tufaceous formation, which cuts off the new deposit, although I detected a small patch of the latter in a garden under the town.

From the town the ruins of a mole, called Caligula's Bridge, run out into the sea (see fig. 88. p. 509.).* This mole, which is believed to be eighteen centuries old, consists of a number of piers and arches, thirteen of which are now standing, and two others appear to have been overthrown. Mr. Babbage found, on the sixth pier, perforations of lithodomi four feet above the level of the sea; and, near the termination of the mole on the last pier but one, marks of the same, ten feet above the level of the sea, together with great numbers of balani and flustra. The depth of the sea, at a very small distance from most of the piers, is from thirty to fifty feet.

Coast north of Puzzuoli.—If we then pass to the north of Puzzuoli, and examine the coast between that town and Monte Nuovo, we find a repetition of analogous phenomena. The sloping sides of Monte Barbaro slant down within a short distance of the coast, and terminate in an inland cliff of moderate elevation, to which the geologist perceives at once that the sea must, at some former period, have extended. Between this cliff and the sea is a low plain or terrace, called La Starza (*c*, fig. 89.), corresponding to that before described on the south-east of the town; and as the sea encroaches rapidly, fresh sections of the strata may readily be obtained, of which the annexed is an example.

Fig. 89.



a, Remains of Cicero's villa, N. side of Puzzuoli.† *b*, Ancient cliff now inland.
c, Terrace (called La Starza) composed of recent submarine deposits.
d, Temple of Serapis.

Section on the shore north of the town of Puzzuoli:—

	Ft.	In.
1. Vegetable soil - - - - - - -	1	0
2. Horizontal beds of pumice and scoriæ, with broken fragments of unrolled bricks, bones of animals, and marine shells - - -	1	6
3. Beds of lapilli, containing abundance of marine shells, principally *Cardium rusticum*, *Donax trunculus*, Lam., *Ostrea edulis*, *Triton cutaceum*, Lam., and *Buccinum serratum*, Brocchi, the beds varying in thickness from one to eighteen inches - - - -	10	0
4. Argillaceous tuff, containing bricks and fragments of buildings not rounded by attrition - - - - - -	1	6

---

* This view is taken from Sir W. Hamilton, Campi Phlegræi, plate 26.

† This spot here indicated on the summit of the cliff is that from which

The thickness of many of these beds varies greatly as we trace them along the shore, and sometimes the whole group rises to a greater height than at the point above described. The surface of the tract which they compose appears to slope gently upwards towards the base of the old cliffs.

Now, if such appearances presented themselves on the coast of England, a geologist might endeavour to seek an explanation in some local change in the set of the tides and currents: but there are scarce any tides in the Mediterranean; and, to suppose the sea to have sunk generally from twenty to twenty-five feet since the shores of Campania were covered with sumptuous buildings, is an hypothesis obviously untenable. The observations, indeed, made during modern surveys on the moles and cothons (docks) constructed by the ancients in various ports of the Mediterranean, have proved that there has been no sensible variation of level in that sea during the last two thousand years.*

Thus we arrive, without the aid of the celebrated temple, at the conclusion, that the recent marine deposit at Puzzuoli was upraised in modern times above the level of the sea, and that not only this change of position, but the accumulation of the modern strata, was posterior to the destruction of many edifices, of which they contain the imbedded remains. If we next examine the evidence afforded by the temple itself, it appears, from the most authentic accounts, that the three pillars now standing erect continued, down to the middle of the last century, almost buried in the new marine strata (*c*, fig. 89.) The upper part of each protruding several feet above the surface was concealed by bushes, and had not attracted, until the year 1749, the notice of antiquaries; but, when the soil was removed in 1750, they were seen to form part of the remains of a splendid edifice, the pavement of which was still preserved, and upon it lay a number of columns of African breccia and of granite. The original plan of the building could be traced distinctly: it was of a quadrangular form, seventy feet in diameter, and the roof had been supported by forty-six noble columns, twenty-four of granite, and the rest of marble. The large court was surrounded by apartments, supposed to have been used as bathing-rooms; for a thermal spring, still used for medicinal purposes, issues just behind the building, and the water of this spring appears to have been originally conveyed by a marble duct, still extant, into the chambers, and then across the pavement by a groove an inch or two deep, to a conduit made of Roman brickwork, by which it gained the sea.

Many antiquaries have entered into elaborate discussions as to the deity to which this edifice was consecrated. It is admitted that, among other images found in excavating the ruins, there was one of the god Serapis; and at Puzzuoli a marble column was dug up, on

---

Hamilton's view, plate 26., Campi Phlegræi (reduced in fig. 88. p. 509.) is taken, and on which, he says, Cicero's villa, called the Academia, anciently stood.

† On the authority of Captain W. H. Smyth, R. N.

which was carved an ancient inscription, of the date of the building of Rome 648 (or B. C. 105), entitled "Lex parieti faciundo." This inscription, written in very obscure Latin, sets forth a contract, between the municipality of the town, and a company of builders who undertook to keep in repair certain public edifices, the Temple of Serapis being mentioned amongst the rest, and described as being near or towards the sea, "mare vorsum." Sir Edmund Head, after studying, in 1828, the topography and antiquities of this district, and the Greek, Roman, and Italian writers on the subject, informed me, that at Alexandria, on the Nile, the chief seat of the worship of Serapis, there was a Serapeum of the same form as this temple at Puzzuoli, and surrounded in like manner by chambers, in which the devotees were accustomed to pass the night, in the hope of receiving during sleep a revelation from the god, as to the nature and cure of their diseases. Hence it was very natural that the priests of Serapis, a pantheistic divinity, who, among other usurpations, had appropriated to himself the attributes of Esculapius, should regard the hot spring as a suitable appendage to the temple, although the original Serapeum of Alexandria could boast no such medicinal waters. Signor Carelli* and others, in objecting to these views, have insisted on the fact, that the worship of Serapis, which we know prevailed at Rome in the days of Catullus (in the first century before Christ), was prohibited by the Roman Senate, during the reign of the Emperor Tiberius. But there is little doubt that, during the reigns of that Emperor's successors, the shrines of the Egyptian god were again thronged by zealous votaries; and in no place more so than at Puteŏli (now Puzzuoli), one of the principal marts for the produce of Alexandria.

Without entering farther into an inquiry which is not strictly geological, I shall designate this valuable relic of antiquity by its generally received name, and proceed to consider the memorials of physical changes inscribed on the three standing columns in most legible characters by the hand of Nature. (See Frontispiece.) These pillars, which have been carved each out of a single block of marble, are forty feet three inches and a half in height. An horizontal fissure nearly intersects one of the columns; the other two are entire. They are all slightly out of the perpendicular, inclining somewhat to the south-west, that is, towards the sea.† Their surface is smooth and uninjured to the height of about twelve feet above their pedestals. Above this is a zone, about nine feet in height, where the marble has been pierced by a species of marine perforating bivalve—*Lithodomus*, Cuv.‡ The holes of these animals are pear-shaped, the external opening being minute, and gradually increasing downwards. At the bottom of the cavities, many shells are still found, notwithstanding the great numbers that have been taken out by visitors; in many the valves of a species of arca, an animal which conceals itself in small hollows, occur. The perforations are so considerable in depth and size, that they manifest a long-continued abode of the lithodomi in the columns; for, as the inhabitant grows older and increases in size, it bores a larger cavity, to correspond with the increased magnitude of its shell. We must, consequently, infer a long-continued immersion of the pillars in sea-water, at a time when the lower part was covered up and protected by marine, fresh-water, and volcanic strata, afterwards to be described, and by the rubbish of buildings; the highest part, at the same time, projecting above the waters, and being consequently weathered, but not materially injured. See fig. 90. p. 514.

---

* Dissertazione sulla Sagra Architettura degli Antichi.

† This appears from the measurement of Captain Basil Hall, R. N., Proceedings of Geol. Soc., No. 38. p. 114.; see also Patchwork, by the same author, vol. iii. p. 168. The fact of the three standing columns having been each formed out of a single stone was first pointed out to me by Mr. James Hall, and is important, as helping to explain why they were not shaken down.

‡ Modiola lithophaga, Lam. *Mytilus lithophagus*, Linn.

On the pavement of the temple lie some columns of marble, which are also perforated in certain parts; one, for example, to the length of eight feet, while, for the length of four feet, it is uninjured. Several of these broken columns are eaten into, not only on the exterior, but on the cross fracture, and, on some of them, other marine animals (serpulæ, &c.) have fixed themselves.* All the granite pillars are untouched by lithodomi. The platform of the temple, which is not perfectly even, was, when I visited it in 1828, about one foot below high-water mark (for there are small tides in the bay of Naples); and the sea, which was only one hundred feet distant, soaked through the intervening soil. The upper part of the perforations, therefore, were at least twenty-three feet above high-water mark; and it is clear that the columns must have continued for a long time in an erect position, immersed in salt water, and then the submerged portion must have been upraised to the height of about twenty-three feet above the level of the sea.

By excavations carried on in 1828, below the marble pavement on which the columns stand, another costly pavement of mosaic was found, at the depth of about five feet below the upper one (*a*, *b*, fig. 90.). The existence of these two pavements, at different levels, clearly implies some subsidence previously to the building of the more modern temple which had rendered it necessary to construct the new floor at a higher level.

We have already seen (p. 512.) that a temple of Serapis existed long before the Christian era. The change of level just mentioned must have taken place some time before the end of the second century, for inscriptions have been found in the temple, from which we learn that Septimius Severus adorned its walls with precious marbles, between the years 194 and 211 of our era, and the emperor Alexander Severus displayed the like munificence between the years 222 and 235.† From that era there is an entire dearth of historical information for a period of more than twelve centuries, except the significant fact that Alaric and his Goths sacked Puzzuoli in 456, and that Genseric did the like in 545, A.D. Yet we have fortunately a series of natural archives self-registered during the dark ages, by which many events which occurred in and about the temple are revealed to us. These natural records consist partly of deposits, which envelop the pillars below the zone of lithodomous perforations, and partly of those which surround the outer walls of the temple. Mr. Babbage after a minute examination of these has shown (see p. 507. note,) that incrustations on the walls of the exterior chambers and on the floor of the building demonstrate that the pavement did not sink down suddenly, but was depressed by a gradual movement. The sea first entered the court or atrium and mingled its waters partially with those of the hot spring. From this brackish medium a dark calcareous precipitate (*c*, *c*, fig. 90.) was thrown down, which became, in the course of time, more than two feet thick, including some serpulæ in it. The presence of these annelids teaches us that the water was salt or brackish. After this period the temple was filled up with an irregular mass of volcanic tuff (*d d*, fig. 90.), probably derived from an eruption of the neighbouring crater of the Solfatara, to the height of from five to nine feet above the pavement. Over this again a purely freshwater deposit of carbonate of lime (*e e*, fig. 90.) accumulated with an uneven bottom since it necessarily accommodated itself to the irregular outline of the upper surface of the volcanic shower before thrown down. The top of the same deposit (a freshwater limestone) was perfectly even and flat, bespeaking an ancient water level. It is suggested by Mr. Babbage that this freshwater lake may have been caused by the fall of ashes which choked up the channel previously communicating with the sea, so that the hot spring threw down calcareous matter in the atrium, without any marine intermixture. To the freshwater limestone succeeded another irregular mass of volcanic ashes and rubbish (*ff*, fig. 90.), some of it perhaps washed in by the waves of the sea during a storm, its surface rising to ten or eleven feet above the pavement. And thus we arrive at the period of greatest depression expressed in the accompanying diagram, when the lower half of the pillars were enveloped in the deposits above enumerated, and the

---

* *Serpula contortuplicata*, Linn., and *Vermilia triquetra*, Lam. These species, as well as *the Lithodomus*, are now inhabitants of the neighbouring sea.

† Brieslak, Voy. dans la Campanie, tom. ii. p. 167.

Fig. 90.



Temple of Serapis at its period of greatest depression.

a, *b*, Ancient mosaic pavement.
c c, Dark marine incrustation.
d d, First filling up, shower of ashes.
e e, Freshwater calcareous deposit.
f f, Second filling up.
A, Stadium.

uppermost twenty feet were exposed in the atmosphere, the remaining or middle portion, about nine feet long, being for years immersed in salt water and drilled by perforating bivalves. After this period other strata, consisting of showers of volcanic ashes and materials washed in during storms, covered up the pillars to the height in some places of thirty-five feet above the pavement. The exact time when these enveloping masses were heaped up, and how much of them were formed during submergence, and how much after the re-elevation of the temple, cannot be made out with certainty.

The period of deep submergence was certainly antecedent to the close of the fifteenth century. Professor James Forbes* has reminded us of a passage in an old Italian writer Loffredo, who says that in 1530, or fifty years before he wrote, which was in 1580, the sea washed the base of the hills which rise from the flat land called La Starza, as represented in fig. 90.; so that, to quote his words, "a person might then have fished from the site of those ruins which are now called the stadium" (A, fig. 90.).

But we know from other evidence that the upward movement had begun before 1530, for the Canonico Andrea di Jorio cites two authentic documents in illustration of this point. The first, dated Oct. 1503, is a deed written in Italian, by which Ferdinand and Isabella grant to the University of Puzzuoli a portion of land, "where the sea is drying up" (che va seccando el mare); the second, a document in Latin, dated May 23. 1511, or nearly eight years after, by which Ferdinand grants to the city a certain territory around Puzzuoli, where the ground *is dried up* from the sea (desiccatum).†

The principal elevation, however, of the low tract unquestionably took place at the time of the great eruption of Monte Nuovo in 1538. That event and the earthquakes which preceded it have been already described (p. 368.); and we have seen that two of the eye-witnesses of the convulsion, Falconi and Giacomo di Toledo, agree in declaring that the sea abandoned a considerable tract of the shore, so that fish were taken by the inhabitants; and, among other things, Falconi mentions that he saw two springs *in the newly discovered ruins.*

The flat land, when first upraised, must have been more extensive than now, for the sea encroaches somewhat rapidly, both to the north and south-east of Puzzuoli. The coast had, when I examined it in 1828, given way more than a foot in a twelvemonth; and I was assured, by fishermen in the bay, that it has lost ground near Puzzuoli, to the extent of thirty feet, within their memory.

It is, moreover, very probable that the land rose to a greater height at first before it ceased to move upwards, than the level at which it was observed to stand when the temple was re-discovered in 1749, for we learn from a memoir of Niccolini, published in 1838, that since the beginning of the nineteenth century, the temple of Serapis has subsided more than two feet. That learned architect visited the ruins frequently, for the sake of making drawings, in the beginning of the year 1807, and was in the habit of remaining there throughout the day, yet never saw the pavement overflowed by the sea, except occasionally when the south wind blew violently. On his return, sixteen years after, to superintend some excavations ordered by the king of Naples, he found the pavement covered by sea-water twice every day at high tide, so that he was obliged to place there a line of stones to stand upon. This induced him to make a series of observations from Oct. 1822 to July 1838, by which means he ascertained that the ground had been and was sinking, at the average rate of about seven millimetres a year, or about one inch in four years; so that, in 1838, fish were caught every day on that part of the pavement where, in 1807, there was never a drop of water in calm weather.*

---

* Ed. Journ. of Science, new series, No. II. p. 281.

† Sul Tempio di Serap. ch. viii.

On inquiring still more recently as to the condition of the temple and the continuance of the sinking of the ground, I learn from Signor Scacchi in a letter, dated June 1852, that the downward movement has ceased for several years, or has at least become almost inappreciable. During an examination undertaken by him at my request in the summer of that year (1852), he observed that the rising tide spread first over the seaward side of the flat surface of the pedestals of each column (confirming the fact previously noticed by others, that they are out of the perpendicular); and he also remarked that the water gained unequally on the base of each pillar, in such a manner as to prove that they have neither the same amount of inclination, nor lean precisely in the same direction.

From what was said before (p. 510.), we saw that the marine shells in the strata forming the plain called La Starza, considered separately, establish the fact of an upheaval of the ground to the height of twenty-three feet and upwards. The temple proves much more, because it could not have been built originally under water, and must therefore first have sunk down twenty feet at least below the waves, to be afterwards restored to its original position. Yet if such was the order of events we ought to meet with other independent signs of a like subsidence round the margin of a bay once so studded with buildings as the bay of Baiæ. Accordingly memorials of such submergence are not wanting. About a mile north-west of the temple of Serapis, and about 500 feet from the shore, are the ruins of a temple of Neptune and others of a temple of the Nymphs, now under water. The columns of the former edifice stand erect in five feet water, their upper portions just rising to the surface of the sea. The pedestals are doubtless buried in the sand or mud; so that, if this part of the bottom of the bay should hereafter be elevated, the exhumation of these temples might take place after the manner of that of Serapis. Both these buildings probably participated in the movement which raised the Starza; but either they were deeper under water than the temple of Serapis, or they were not raised up again to so great a height.

---

* Tavola Metrica Chronologica, &c. Napoli, 1838. Mr. Smith, of Jordan Hill, writing in 1847, estimated the rate of subsidence, at that period, at one inch annually. Quart. Journ. Geol. Soc. vol. iii. p. 237.

There are also two Roman roads under water in the bay, one reaching from Puzzuoli to the Lucrine Lake, which may still be seen, and the other near the castle of Baiæ (No. 8., fig. 88. p. 509.). The ancient mole, too, of Puzzuoli (No. 4. ibid.) before alluded to, has the water up to a considerable height of the arches; whereas Brieslak justly observes, it is next to certain that the piers must formerly have reached the surface before the springing of the arches*; so that, although the phenomena before described prove that this mole has been uplifted ten feet above the level at which it once stood, it is still evident that it has not yet been restored to its original position.

A modern writer also reminds us, that these effects are not so local as some would have us to believe; for on the opposite side of the Bay of Naples, on the Sorrentine coast, which, as well as Puzzuoli, is subject to earthquakes, a road, with some fragments of Roman buildings, is covered to some depth by the sea. In the island of Capri, also, which is situated some way out at sea, in the opening of the Bay of Naples, one of the palaces of Tiberius is now covered with water.†

That buildings should have been submerged, and afterwards upheaved, without being entirely reduced to a heap of ruins, will appear no anomaly, when we recollect that, in the year 1819, when the delta of the Indus sank down, the houses within the fort of Sindree subsided beneath the waves without being overthrown. In like manner, in the year 1692, the buildings around the harbour of Port Royal, in Jamaica, descended suddenly to the depth of between thirty and fifty feet under the sea without falling. Even on small portions of land transported to a distance of a mile down a declivity, tenements, like those near Mileto, in Calabria, were carried entire. At Valparaiso buildings were left standing in 1822, when their foundations, together with a long tract of the Chilian coast, were permanently upraised to the height of several feet. It is still more easy to conceive that an edifice may escape falling during the upheaval or subsidence of land, if the walls are supported on the exterior and interior with a deposit like that which surrounded and filled to the height of ten or eleven feet the temple of Serapis all the time it was sinking, and which enveloped it to more than twice that height when it was rising again to its original level.

We can scarcely avoid the conclusion, as Mr. Babbage has hinted, "that the action of heat is in some way or other the cause of the phenomena of the change of level of the temple. Its own hot spring, its immediate contiguity to the Solfatara, its nearness to the Monte Nuovo, the hot spring at the baths of Nero (No. 6. fig. 88.), on the opposite side of the Bay of Baiæ; the boiling springs and ancient volcanos of Ischia on one side and Vesuvius on the other, are the most prominent of a multitude of facts which point to that conclusion."* And when we reflect on the dates of the principal oscillations of level, and the volcanic history of the country before described (chap. 23.), we seem to discover a connection between each era of upheaval and a local development of volcanic heat, and again between each era of depression and the local quiescence or dormant condition of the subterranean igneous causes. Thus for example, before the Christian era, when so many vents were in frequent eruption in Ischia, and when Avernus and other points in the Phlegræan Fields were celebrated for their volcanic aspect and character, the ground on which the temple stood was several feet above water. Vesuvius was then regarded as a spent volcano; but when, after the Christian era, the fires of that mountain were rekindled, scarcely a single outburst was ever witnessed in Ischia, or around the Bay of Baiæ. Then the temple was sinking. Vesuvius, at a subsequent period, became nearly dormant for five centuries preceding the great outbreak of 1631 (see p. 374.), and in that interval the Solfatara was in eruption A. D. 1198, Ischia in 1302, and Monte Nuovo was formed in 1538. Then the foundations on which the temple stood were rising again. Lastly, Vesuvius once more became a most active vent, and has been so ever since, and during the same lapse of time the area of the temple, so far as we know anything of its history, has been subsiding.

---

* Voy. dans la Campanie, tome ii. p. 162.

† Mr. Forbes, Physical Notices of the Bay of Naples. Ed. Journ. of Sci., No. II., new *series*, *p. 280. October*, 1829. When I visited Puzzuoli, and arrived at the above conclusions, I knew nothing of Mr. Forbes's observations, which I first saw on my return to England the year following.

These phenomena would agree well with the hypothesis, that when the subterranean heat is on the increase, and when lava is forming without obtaining an easy vent, like that afforded by a great habitual chimney, such as Vesuvius, the incumbent surface is uplifted, but when the heated rocks below are cooling and contracting, and sheets of lava are slowly consolidating and diminishing in volume, then the incumbent land subsides.

Signor Niccolini, when he ascertained in 1838 that the relative levels of the floor of the temple and of the sea were slowly changing from year to year, embraced the opinion that it was the sea which was rising. But Signor Capocci successfully controverted this view, appealing to many appearances which attest the local character of the movements of the adjoining country, besides the historical fact that in 1538, when the sea retired permanently 200 yards from the ancient shore at Puzzuoli, there was no simultaneous retreat of the waters from Naples, Castelamare, and Ischia.†

Permanence of the ocean's level.— In concluding this subject I may observe, that the interminable controversies to which the phenomena of the Bay of Baiæ gave rise, have sprung from an extreme reluctance to admit that the land, rather than the sea, is subject alternately to rise and fall. Had it been assumed that the level of the ocean was invariable, on the ground that no fluctuations have as yet been clearly established, and that, on the other hand, the continents are inconstant in their level, as has been demonstrated by the most unequivocal proofs again and again, from the time of Strabo to our own times, the appearances of the temple at Puzzuoli could never have been regarded as enigmatical. Even if contemporary accounts had not distinctly attested the upraising of the coast, this explanation should have been proposed in the first instance as the most natural, instead of being now adopted unwillingly when all others have failed.

---

* Quart. Journ. Geol. Soc. 1847., vol. iii. p. 203.

† Nuove Ricerche sul Temp. di Serap.

To the strong prejudices still existing in regard to the mobility of the land, we may attribute the rarity of such discoveries as have been recently brought to light in the Bay of Baiæ and the Bay of Conception. A false theory, it is well known, may render us blind to facts which are opposed to our prepossessions, or may conceal from us their true import when we behold them. But it is time that the geologist should, in some degree, overcome those first and natural impressions which induced the poets of old to select the rock as the emblem of firmness—the sea as the image of inconstancy. Our modern poet, in a more philosophical spirit, saw in the sea "The image of eternity," and has finely contrasted the fleeting existence of the successive empires which have flourished and fallen on the borders of the ocean with its own unchanged stability.

> ——— Their decay
> Has dried up realms to deserts:—not so thou,
> Unchangeable, save to thy wild waves' play:
> Time writes no wrinkle on thine azure brow;
> Such as creation's dawn beheld, thou rollest now.
>
> Childe Harold, Canto iv.

CHAPTER XXX.

ELEVATION AND SUBSIDENCE OF LAND WITHOUT EARTHQUAKES.

Changes in the relative level of land and sea in regions not volcanic—Opinion of Celsius that the waters of the Baltic Sea and Northern Ocean were sinking—Objections raised to his opinion—Proofs of the stability of the sea level in the Baltic—Playfair's hypothesis that the land was rising in Sweden—Opinion of Von Buch—Marks cut on the rocks—Survey of these in 1820—Facility of detecting slight alterations of level on coast of Sweden—Shores of the ocean also rising—Area upheaved—Shelly deposits of Uddevalla—Of Stockholm, containing fossils shells characteristic of the Baltic—Subsidence in south of Sweden—Fishing-hut buried under marine strata—Upheaval in Sweden not always in horizontal planes—Sinking of land in Greenland—Bearing of these facts on geology.

We have now considered the phenomena of volcanos and earthquakes according to the division of the subject before proposed (p. 345.), and have next *to turn our attention to those slow and insensible changes in the relative level* of land and sea which take place in countries remote from volcanos, and where no violent earthquakes have occurred within the period of human observation. Early in the last century the Swedish naturalist, Celsius, expressed his opinion that the waters, both of the Baltic and Northern Ocean, were gradually subsiding. From numerous observations he inferred, that the rate of depression was about forty Swedish inches in a century.* In support of this position, he alleged that there were many rocks both on the shores of the Baltic and the ocean known to have been once sunken reefs, and dangerous to navigators, but which were in his time above water—that the waters of the Gulf of Bothnia had been gradually converted into land, several ancient ports having been changed into inland cities, small islands joined to the continent, and old fishing grounds deserted as being too shallow, or entirely dried up. Celsius also maintained, that the evidence of the change rested not only on modern observations, but on the authority of the ancient geographers, who had stated that Scandinavia was formerly an island. This island, he argued, must in the course of centuries, by the gradual retreat of the sea, have become connected with the continent; an event which he supposed to have happened after the time of Pliny, and before the ninth century of our era.

To this argument it was objected that the ancients were so ignorant of the geography of the most northern parts of Europe, that their authority was entitled to no weight; and that their representation of Scandinavia as an island, might with more propriety be adduced to prove the scantiness of their information, than to confirm so bold an hypothesis. It was also remarked, that if the land which connected Scandinavia with the main continent was laid dry between the time of Pliny and the ninth century, to the extent to which it is known to have risen above the sea at the latter period, the rate of depression could not have been uniform, as was pretended; for it ought to have fallen much more rapidly between the ninth and eighteenth centuries.

Many of the proofs relied on by Celsius and his followers were immediately controverted by several philosophers, who saw clearly that a fall of the sea in any one region could not take place without a general sinking of the waters over the whole globe; they denied that this was the fact, or that the depression was universal, even in the Baltic. In proof of the stability of the level of that sea, they appealed to the position of the island of Saltholm, not far from Copenhagen. This island is so low, that in autumn and winter it is permanently overflowed; and it is only dry in summer, when it serves for pasturing cattle. It appears, from the documents of the year 1280, that Saltholm was then also in the same state, and exactly on a level with the mean height of the sea, instead of having been about twenty feet under water, as it ought to have been, according to the computation of Celsius. Several towns, also, on the shores of the Baltic, as Lubeck, Wismar, Rostock, Stralsund, and others, after six and even eight hundred years, are as little elevated above the sea as at the era of their foundation, being now close to the water's edge. The lowest part of Dantzic was no higher than the mean level of the sea in the year 1000; and after eight centuries its relative position remains exactly the same.*

---

* The Swedish measure scarcely differs from ours; the foot being divided into twelve inches, and being less than ours by three eighths of an inch only.

Several of the examples of the gain of land and shallowing of the sea pointed out by Celsius, and afterwards by Linnæus, who embraced the same opinions, were ascribed by others to the deposition of sediment at points where rivers entered; and, undoubtedly, Celsius had not sufficiently distinguished between changes due to these causes and such as would arise if the waters of the ocean itself were diminishing. Many large rivers descending from a mountainous country, at the head of the Gulf of Bothnia, enter the sea charged with sand, mud, and pebbles; and it was said that in these places the low land had advanced rapidly, especially near Torneo. At Piteo also, half a mile had been gained in forty-five years; at Luleo†, no less than a mile in twenty-eight years; facts which might all be admitted consistently with the assumption that the level of the Baltic has remained unchanged, like that of the Adriatic, during a period when the plains of the Po and the Adige have greatly extended their area.

It was also alleged that certain insular rocks, once entirely covered with water, had at length protruded themselves above the waves, and grown, in the course of a century and a half, to be eight feet high. The following attempt was made to explain away this phenomenon: — In the Baltic, large erratic blocks, as well as sand and smaller stones which lie on shoals, are liable every year to be frozen into the ice, where the sea freezes to the depth of five or six feet. On the melting of the snow in spring, when the sea rises about half a fathom, numerous ice-islands float away, bearing up these rocky fragments so as to convey them to a distance; and if they are driven by the waves upon shoals, they may convert them into islands by depositing the blocks; if stranded upon low islands, they may considerably augment their height.

Browallius, also, and some other Swedish naturalists, affirmed that some islands were lower than formerly; and that, by reference to this kind of evidence, there was equally good reason for contending that the level of the Baltic was gradually rising. They also added another curious proof of the permanency of the water level, at some points at least, for many centuries. On the Finland coast were some large pines, growing close to the water's edge; these were cut down, and, by counting the concentric rings of annual growth, as seen in a transverse section of the trunk, it was demonstrated that they had stood there for four hundred years. Now, according to the Celsian hypothesis, the sea had sunk about fifteen feet during that period, in which case the germination and early growth of these pines must

---

* For a full account of the Celsian controversy, we may refer our readers to Von Hoff, Geschichte, &c. *vol.* i. p. 432.

† Pitio, Luleo, and Obo are spelt, in many English maps, Pitea, Lulea, Abo; the *a* is not sounded in the Swedish diphthong *ao* or å.

Fig. 91.



have been, for many seasons, below the level of the water. In lik manner it was asserted, that the lower walls of many ancient castle such as those of Sonderburg and Åbo, reached then to the water edge, and must, therefore, according to the theory of Celsius, hav been originally constructed below the level of the sea.

In reply to this last argument, Colonel Hällstrom, a Swedis engineer, well acquainted with the Finland coast, assured me, th ıse of the walls of the castle of Åbo is now ten feet above the , so that there may have been a considerable rise of the land at oint since the building was erected.

yfair, in his "Illustrations of the Huttonian Theory," in 1802, ted the sufficiency of the proofs adduced by Celsius, but attri- the change of level to the movement of the land, rather than liminution of the waters. He observed, "that in order to ıs or elevate the absolute level of the sea, by a given quantity, one place, we must depress or elevate it by the same quantity :he whole surface of the earth; whereas no such necessity with respect to the elevation or depression of the land."* The hesis of the rising of the land he adds, "agrees well with the nian theory, which holds, that our continents are subject to be upon by the expansive forces of the mineral regions; that by forces they have been actually raised up, and are sustained by in their present situation."†

:he year 1807, Von Buch, after returning from a tour in Scan- a, announced his conviction, "that the whole country, from rickshall in Norway to Åbo in Finland, and perhaps as far as tersburgh, was slowly and insensibly rising." He also sug- "that Sweden may rise more than Norway, and the northern than the southern part."‡ He was led to these conclusions pally by information obtained from the inhabitants, and pilots, ı part by the occurrence of marine shells of recent species, he had found at several points on the coast of Norway above rel of the sea. He also mentions the marks set on the rocks. Buch, therefore, has the merit of being the first geologist who, personal examination of the evidence, declared in favour of ıe of land in Scandinavia.

attention excited by this subject in the early part of the last y, induced many philosophers in Sweden to endeavour to ıine, by accurate observations, whether the standard level of altic was really subject to periodical variations; and under direction, lines or grooves, indicating the ordinary level of the on a calm day, together with the date of the year, were ed out upon the rocks. In 1820–21, all the marks made before years were examined by the officers of the pilotage establish- of Sweden; and in their report to the Royal Academy of ıolm they declared, that on comparing the level of the sea at ne of their observations with that indicated by the ancient , they found that the Baltic was lower relatively to the land in ı places, but the amount of change during equal periods of ıad not been every where the same. During their survey, ut new marks for the guidance of future observers, several of I had an opportunity of examining fourteen years after (in mmer of 1834), and in that interval the land appeared to me to isen at certain places north of Stockholm four or five inches.

---

393. † Sect. 398. ‡ Transl. of his Travels, p. 387.

I also convinced myself, during my visit to Sweden, after conversing with many civil engineers, pilots, and fishermen, and after examining some of the ancient marks, that the evidence formerly adduced in favour of the change of level, both on the coasts of Sweden and Finland, was full and satisfactory.* The alteration of level evidently diminishes as we proceed from the northern parts of the Gulf of Bothnia towards the south, being very slight around Stockholm. Some writers have indeed represented the rate of depression of the waters at Stockholm as very considerable, because certain houses in that city which are built on piles have sunk down within the memory of persons still living, so as to be out of the perpendicular; and this in consequence of the tops of the piles giving way and decaying, owing to a fall of the waters which has exposed them to be alternately wet and dry. The houses alluded to are situated on the borders of Lake Maeler, a large lake, the outlet of which joins the Baltic, in the middle of Stockholm. This lake is certainly lower than formerly; but the principal cause of the change is not the elevation of the land, but the removal of two old bridges built on piles, which formerly obstructed the discharge of the fresh water into the sea. Another cause is the opening, in the year 1819, of a new canal at Södertelje, a place south of Stockholm, by means of which a new line of communication was formed between Lake Maeler and the Baltic.†

It will naturally be asked, whether the mean level of a sea like the Baltic can ever be determined so exactly as to permit us to appreciate a variation of level, amounting only to one or two feet. In reply, I may observe, that, except near the Cattegat, there are no tides in the Baltic; and it is only when particular winds have prevailed for several days in succession, or at certain seasons when there has been an unusually abundant influx of river water, or when these causes have combined, that this sea is made to rise two or three feet above its standard level. The fluctuations due to these causes are nearly the same from year to year; so that the pilots and fishermen believe and apparently with reason, that they can mark a deviation, even of a few inches, from the ordinary or mean height of the waters.

There are, moreover, peculiarities in the configuration of the shores of Norway and Sweden, which facilitate, in a remarkable degree, the appreciation of slight changes in the relative level of land and water. It has often been said, that there are two coasts, an inner and an outer one; the inner being the shore of the main land; the outer one, a fringe of countless rocky islands of all dimensions, called the skär (*shair*). Boats and small vessels make their coasting voyages within this skär: for here they may sail in smooth water, even when the sea without is strongly agitated. But the navigation is very intricate, and the pilot must possess a perfect acquaintance with the breadth and depth of every narrow channel, and the position of innumerable sunken rocks. If on such a coast the land rises one or two feet in the course of half a century, the minute topography of the skär is entirely altered. To a stranger, indeed, who revisits it after an interval of many years, its general aspect remains the same; but the inhabitant finds that he can no longer penetrate with his boat through channels where he formerly passed, and he can tell of countless other changes in the height and breadth of isolated rocks, now exposed, but once only seen through the clear water.

---

* In the earlier editions I expressed many doubts as to the validity of the proofs of a gradual rise of land in Sweden. A detailed statement of the observations which I made in 1834, and which led me to change my opinion, will be found in the Philosophical Transactions for 1835, part i.

† See Professor Johnston's Paper, Ed. New Phil. Journ., No. 29., July 1833; and my remarks, Phil. Trans. 1835, p. 12.

The rocks of gneiss, mica-schist, and quartz are usually very hard on this coast, slow to decompose, and, when protected from the breakers, remaining for ages unaltered in their form. Hence it is easy to mark the stages of their progressive emergence by the aid of natural and artificial marks imprinted on them. Besides the summits of *fixed* rocks, there are numerous erratic blocks of vast size strewed over the shoals and islands in the skär, which have been probably drifted by ice in the manner before suggested.* All these are observed to have increased in height and dimensions within the last half century. Some, which were formerly known as dangerous sunken rocks, are now only hidden when the water is highest. On their first appearance, they usually present a smooth, bare, rounded protuberance, a few feet or yards in diameter; and a single sea-gull often appropriates to itself this resting-place, resorting there to devour its prey. Similar points, in the mean time, have grown to long reefs, and are constantly whitened by a multitude of sea-fowl; while others have been changed from a reef, annually submerged, to a small islet, on which a few lichens, a fir-seedling, and a few blades of grass, attest that the shoal has at length been fairly changed into dry land. Thousands of wooded islands around show the greater alterations which time can work. In the course of centuries also, the spaces intervening between the existing islands may be laid dry, and become grassy plains encircled by heights well clothed with lofty firs. This last step of the process, by which long fiords and narrow channels, once separating wooded islands, are deserted by the sea, has been exemplified within the memory of living witnesses on several parts of the coast.

Had the apparent fall of the waters been observed in the Baltic only, we might have endeavoured to explain the phenomenon by local causes affecting that sea alone. For instance, the channel by which the Baltic discharges its surplus waters into the Atlantic, might be supposed to have been gradually widened and deepened by the waves and currents, in which case a fall of the water like that before alluded to in Lake Maeler, might have occurred. But the lowering of level would in that case have been uniform and universal, and the waters could not have sunk at Torneo, while they retained their former level at Copenhagen. Such an explanation is also untenable on other grounds; for it is a fact, as Celsius long ago affirmed, that the alteration of level extends to the western shores of Sweden, bordering the ocean. The signs of elevation observed between Uddevalla and Gothenburg are as well established as those on the shores of the Bothnian Gulf. Among the places where they may be studied, are the islands of Marstrand and Gulholmen, the last-mentioned locality being one of those particularly pointed out by Celsius.

---

* *See p. 522.; also chap. 15. supra.*

The inhabitants there and elsewhere affirm, that the rate of the sinking of the sea (or elevation of land) varies in different and adjoining districts, being greatest at points where the coast is low. But in this they are deceived; for they measure the amount of rise by the area gained, which is most considerable where the land descends with a gentle slope into the sea. In the same manner, some advocates of the Celsian theory formerly appealed to the increase of lands near the mouths of rivers, not sufficiently adverting to the fact, that if the bed of the sea is rising, the change will always be most sensible where the bottom has been previously rendered shallow; whereas, at a distance from these points where the scarped granitic cliffs plunge at once into deep water, a much greater amount of elevation is necessary to produce an equally conspicuous change.

As to the area in northern Europe which is subject to this slow upheaving movement, we have not as yet sufficient data for estimating it correctly. It seems probable, however, that it reaches from Gothenburg to Torneo, and from thence to the North Cape, the rate of elevation increasing always as we proceed farther northwards. The two extremities of this line are more than a thousand geographical miles distant from each other; and as both terminate in the ocean, we know not how much farther the motion may be prolonged under water. As to the breadth of the tract, its limits are equally uncertain, though it evidently extends across the widest parts of the Gulf of Bothnia, and may probably stretch far into the interior, both of Sweden and Finland. Now if the elevation continue, a larger part of the Gulf of Bothnia will be turned into land, as also more of the ocean off the west coast of Sweden between Gothenburg and Uddevalla; and on the other hand, if the change has been going on for thousands of years at the rate of several feet in a century, large tracts of what is now land must have been submarine at periods comparatively modern. It is natural therefore to inquire whether there are any signs of the recent sojourn of the sea on districts now inland? The answer is most satisfactory.—Near Uddevalla and the neighbouring coastland, we find upraised deposits of shells belonging to species such as now live in the ocean; while on the opposite or eastern side of Sweden, near Stockholm, Gefle, and other places bordering the Bothnian Gulf, there are analogous beds containing shells of species characteristic of the Baltic.

Von Buch announced in 1807, that he had discovered in Norway and at Uddevalla in Sweden, beds of shells of existing species, at considerable heights above the sea. Since that time, other naturalists have confirmed his observation; and, according to Ström, deposits occur at an elevation of more than 400 feet above the sea in the northern part of Norway. M. Alex. Brongniart, when he visited Uddevalla, ascertained that one of the principal masses of shells, that of Capellbacken, is raised more than 200 feet above the sea, resting on rocks of gneiss, all the species being identical with those now inhabiting the contiguous ocean. The same naturalist also stated, that on examining with care the surface of the gneiss, immediately above the ancient shelly deposit, he found barnacles (*balani*) adhering to the rocks, showing that the sea had remained there for a long time. I was fortunate enough to be able to verify this observation by finding in the summer of 1834, at Kured, about two miles north of Uddevalla, and at the height of more than 100 feet above the sea, a surface of gneiss newly laid open by the partial removal of a mass of shells used largely in the district for making lime and repairing the roads. So firmly did these barnacles adhere to the gneiss that I broke off portions of the rock with the shells attached. The face of the gneiss was also encrusted with small zoophytes (*Cellepora?* Lam.); but had these or the barnacles been exposed in the atmosphere ever since the elevation of the rocks above the sea, they would doubtless have decomposed and been obliterated.

The town of Uddevalla (see Map, p. 523.) stands at the head of a narrow creek overhung by steep and barren rocks of gneiss, of which all the adjacent country is composed, except in the low grounds and bottoms of valleys, where strata of sand, clay, and marl frequently hide the fundamental rocks. To these newer and horizontal deposits the fossil shells above mentioned belong, and similar marine remains are found at various heights above the sea on the opposite island of Orust. The extreme distance from the sea to which such fossils extend is as yet unknown; but they have been already found at Trollhättan in digging the canal there, and still farther inland on the northern borders of Lake Wener, fifty miles from the sea, at an elevation of 200 feet near Lake Rogvarpen.

To pass to the Baltic: I observed near its shores at Södertelje, sixteen miles S. W. of Stockholm, strata of sand, clay, and marl, more than 100 feet high, and containing shells of species now inhabiting the Bothnian Gulf. These consist partly of marine and partly of freshwater species; but they are few in number, the brackishness of the water appearing to be very unfavourable to the development of testacea. The most abundant species are the common cockle and the common mussel and periwinkle of our shores (*Cardium edule*, *Mytilus edulis*, and *Littorina littorea*), together with a small tellina (*T. Baltica*) and a few minute univalves allied to *Paludina ulva*. These live in the same water as a *Lymneus*, a *Neritina* (*N. fluviatilis*), and some other freshwater shells.

But the marine mollusks of the Baltic above mentioned, although very numerous in individuals, are dwarfish in size, scarcely ever attaining a third of the average dimensions which they acquire in the salter waters of the ocean. By this character alone a geologist would generally be able to recognize an assemblage of Baltic fossils as distinguished from those derived from a deposit in the ocean. The absence also of oysters, barnacles, whelks, scallops, limpets (*ostrea, balanus, buccinum, pecten, patella*), and many other forms abounding alike in the sea near Uddevalla, and in the fossiliferous deposits of modern date on that coast, supplies an additional negative character of the greatest value, distinguishing assemblages of Baltic from those of oceanic shells. Now the strata containing Baltic shells are found in many localities near Stockholm, Upsala, and Gefle, and will probably be discovered every where around the borders of the Bothnian Gulf; for I have seen similar remains brought from Finland, in marl resembling that found near Stockholm. The utmost distance to which these deposits have yet been traced inland, is on the southern shores of Lake Maeler, at a place seventy miles from the sea.* Hence it appears from the distinct assemblage of fossil shells found on the eastern and western coasts of Sweden, that the Baltic has been for a long period separated as now from the ocean, although the intervening tract of land was once much narrower, even after both seas had become inhabited by all the existing species of testacea.

As no accurate observations on the rise of the Swedish coast refer to periods more remote than a century and a half from the present time, and as traditional information, and that derived from ancient buildings on the coast, do not enable the antiquary to trace back any monuments of change for more than five or six centuries, we cannot declare whether the rate of the upheaving force is uniform during very long periods. In those districts where the fossil shells are found at the height of more than 200 feet above the ocean, as at Uddevalla, Orust, and Lake Rogvarpen, the present rate of rise seems less than four feet in a century. Even at that rate it would have required five thousand years to lift up those deposits. But as the movement is now very different in different places, it may also have varied much in intensity at different eras.

We have, moreover, yet to learn not only whether the motion proceeds always at the same rate, but also whether it has been uniformly *in one direction*. The level of the land may oscillate; and for centuries there may be a depression, and afterwards a re-elevation, of the same district. Some phenomena in the neighbourhood of Stockholm appear to me only explicable on the supposition of the alternate rising and sinking of the ground since the country was inhabited by man. In digging a canal, in 1819, at Södertelje, about sixteen miles to the south of Stockholm, to unite Lake Maeler with the Baltic, marine strata, containing fossil shells of Baltic species, were passed through. At a depth of about sixty feet, they came down upon what seems to have been a buried fishing-hut, constructed of wood in a state of decomposition, which soon crumbled away on exposure to the air. The lowest part, however, which had stood on a level with the sea, was in a more perfect state of preservation. On the floor of this hut was a rude fireplace, consisting of a ring of stones, and within this were cinders and charred wood. On the outside lay boughs of the fir, cut as with an axe, with the leaves or needles still attached. It seems very difficult to explain the position of this buried hut, without imagining, as in the case of the temple of Serapis (see p. 486.), first, a subsidence to the depth of more than sixty feet, then a re-elevation. During the period of submergence, the hut must have become covered over with gravel and shelly marl, under which not only the hut, but several vessels also were found, of a very antique form, and having their timbers fastened together by wooden pegs instead of nails.*

---

* See a paper by the Author, Phil. Trans. 1835, part i.

Whether any of the land in Norway is now rising, must be determined by future investigations. Marine fossil shells, of recent species, have been collected from inland places near Drontheim; but Mr. Everest, in his "Travels through Norway," informs us that the small island of Munkholm, which is an insulated rock in the harbour of Drontheim, affords conclusive evidence of the land having in that region remained stationary for the last eight centuries. The area of this isle does not exceed that of a small village, and by an official survey, its highest point has been determined to be twenty-three feet above the mean high-water mark, that is, the mean between neap and spring tides. Now, a monastery was founded there by Canute the Great, A. D. 1028, and thirty-three years before that time it was in use as a common place of execution. According to the assumed average rate of rise in Sweden (about forty inches in a century), we should be obliged to suppose that this island had been three feet eight inches below high-water mark when it was originally chosen as the site of the monastery.

Professor Keilhau of Christiania, after collecting the observations of his predecessors respecting former changes of level in Norway, and combining them with his own, has made the fact of a general change of level at a modern period, that is to say, within the period of the actual testaceous fauna, very evident. He infers that the whole country from Cape Lindesnæs to Cape North, and beyond that as far as the fortress of Vardhuus, has been gradually upraised, and on the south-east coast the elevation has amounted to more than 600 feet. The marks which denote the ancient coast-line are so nearly horizontal that the deviation from horizontality, although the measurements have been made at a great number of points, is too small to be appreciated.

More recently (1844), however, it appears from the researches of

---

* See my paper before referred to, Phil. Trans. 1835, part i. p. 8, 9. Attempts have been since made to explain away the position of this hut, by conjecturing that a more ancient trench had been previously dug here, which had become filled up in time by sand drifted by the wind. The engineers who superintended the works in 1819, and with whom I conversed, had considered every hypothesis of the kind, but could not so explain the facts.

M. Bravais, member of the French scientific commission of the North, that in the Gulf of Alten in Finmark, the most northerly part of Norway, there are two distinct lines of upraised ancient sea-coast, one above the other, which are not parallel, and both of them imply that within a distance of fifty miles a considerable slope can be detected in such a direction as to show that the ancient shores have undergone a greater amount of upheaval in proportion as we advance inland.*

It has been already stated, that, in proceeding from the North Cape to Stockholm, the rate of upheaval diminishes from several feet to a few inches in a century. To the south of Stockholm the upward movement ceases, and at length in Scania, or the southernmost part of Sweden, it appears to give place to a movement in an opposite direction. In proof of this fact, Professor Nilsson observes, in the first place, that there are no elevated beds of recent marine shells in Scania like those farther to the north. Secondly, Linnæus, with a view of ascertaining whether the waters of the Baltic were retiring from the Scanian shore, measured, in 1749, the distance between the sea and a large stone near Trelleborg. This same stone was, in 1836, a hundred feet nearer the water's edge than in Linnæus's time, or eighty-seven years before. Thirdly, there is also a submerged peat moss, consisting of land and freshwater plants, beneath the sea at a point to which no peat could have been drifted down by any river. Fourthly, and what is still more conclusive, it is found that in seaport towns, all along the coast of Scania, there are streets below the high-water level of the Baltic, and in some cases below the level of the lowest tide. Thus, when the wind is high at Malmö, the water overflows one of the present streets, and some years ago some excavations showed an ancient street in the same place eight feet lower, and it was then seen that there had been an artificial raising of the ground, doubtless in consequence of that subsidence. There is also a street at Trelleborg, and another at Skanör, a few inches below high-water mark, and a street at Ystad is exactly on a level with the sea, at which it could not have been originally built.

The inferences deduced from the foregoing facts are in perfect harmony with the proofs brought to light by two Danish investigators, Dr. Pingel and Captain Graah, of the sinking down of part of the west coast of Greenland, for a space of more than 600 miles from north to south. The observations of Captain Graah were made during a survey of Greenland in 1823–24; and afterwards in 1828–29; those by Dr. Pingel were made in 1830–32. It appears from various signs and traditions, that the coast has been subsiding for the last four centuries from the firth called Igaliko, in lat. 60° 43′ N., to Disco Bay, extending to nearly the 69th degree of north latitude. Ancient buildings on low rocky islands and on the shore of the main land have been gradually submerged, and experience has taught the abo-original Greenlander never to build his hut near the water's edge. In one case the Moravian settlers have been obliged more than once to move inland the poles upon which their large boats were set, and the old poles still remain beneath the water as silent witnesses of the change.*

---

* Quarterly Journ. of Geol. Soc. No. 4. p. 534. M. Bravais' observations were verified in 1849 by Mr. R. Chambers in his "Tracings of N. of Europe," p. 208.

The probable cause of the movements above alluded to, whether of elevation or depression, will be more appropriately discussed in the following chapters, when the origin of subterranean heat is considered. But I may remark here, that the rise of Scandinavia has naturally been regarded as a very singular and scarcely credible phenomenon, because no region on the globe has been more free within the times of authentic history from violent earthquakes. In common, indeed, with our own island and with almost every spot on the globe, some movements have been, at different periods, experienced, both in Norway and Sweden. But some of these, as for example during the Lisbon earthquake in 1755, may have been mere vibrations or undulatory movements of the earth's crust prolonged from a great distance. Others, however, have been sufficiently local to indicate a source of disturbance immediately under the country itself. Notwithstanding these shocks, Scandinavia has, upon the whole, been as tranquil in modern times, and as free from subterranean convulsions, as any region of equal extent on the globe. There is also another circumstance which has made the change of level in Sweden appear anomalous, and has for a long time caused the proofs of the fact to be received with reluctance. Volcanic action, as we have seen, is usually intermittent: and the variations of level to which it has given rise have taken place by starts, not by a prolonged and insensible movement similar to that experienced in Sweden. Yet, as we enlarge our experience of modern changes, we discover instances in which the volcanic eruption, the earthquake, and the permanent rise or fall of land, whether slow or sudden, are all connected. The union of these various circumstances was exemplified in the case of the temple of Serapis, described in the last chapter, and we might derive other illustrations from the events of the present century in South America.

Some writers, indeed, have imagined that there is geological evidence in Norway of the sudden upheaval of land to a considerable height at successive periods, since the era when the sea was inhabited by the living species of testacea. They point in proof to certain horizontal lines of inland cliffs and sea-beaches containing recent shells at various heights above the level of the sea.† But these appearances, when truly interpreted, simply prove that there have been long pauses in the process of upheaval or subsidence. They mark eras at which the level of the sea has remained stationary for ages, and during which new strata were deposited near the shore in some places, while in others the waves and currents had time to hollow out rocks, undermine cliffs, and throw up long ranges of shingle. They undoubtedly show that the movement has not been always uniform or continuous, but they do not establish the fact of any sudden alterations of level.

---

* See Proceedings of Geol. Soc. No. 42. p. 208. I also conversed with Dr. Pingel on the subject at Copenhagen in 1834.

† Keilhau, Bulletin de la Soc. Géol. de France, tom. vii. p. 18.

When we are once assured of the reality of the gradual rise of a large region, it enables us to account for many geological appearances otherwise of very difficult explanation. There are large continental tracts and high table lands where the strata are nearly horizontal, bearing no marks of having been thrown up by violent convulsions, nor by a series of movements, such as those which occur in the Andes, and cause the earth to be rent open, and raised or depressed from time to time, while large masses are engulphed in subterranean cavities. The result of a series of such earthquakes might be to produce in a great lapse of ages a country of shattered, inclined, and perhaps vertical strata. But a movement like that of Scandinavia would cause the bed of the sea, and all the strata recently formed in it, to be upheaved so gradually, that it would merely seem as if the ocean had formerly stood at a higher level, and had slowly and tranquilly sunk down into its present bed.

The fact also of a very gradual and insensible elevation of land may explain many geological monuments of denudation, on a grand scale. If, for example, instead of the hard granitic rocks of Norway and Sweden, a large part of the bed of the Atlantic, consisting chiefly of soft strata, should rise up century after century, at the rate of about half an inch, or an inch, in a year, how easily might oceanic currents sweep away the thin film of matter thus brought up annually within the sphere of aqueous denudation! The tract, when it finally emerged, might present table lands and ridges of horizontal strata, with intervening valleys and vast plains, where originally, and during its period of submergence, the surface was level and nearly uniform.

These speculations relate to superficial changes; but others must be continually in progress in the subterranean regions. The foundations of the country, thus gradually uplifted in Sweden, must be undergoing important modifications. Whether we ascribe these to the expansion of solid matter by continually increasing heat, or to the liquefaction of rock, or to the crystallization of a dense fluid, or the accumulation of pent-up gases, in whatever conjectures we indulge, we can never doubt for a moment, that at some unknown depth beneath Sweden and the Baltic, the structure of the globe is in our own times becoming changed from day to day, throughout a space probably more than a thousand miles in length, and several hundred in breadth.

CHAPTER XXXI.

CAUSES OF EARTHQUAKES AND VOLCANOS.

Intimate connexion between the causes of volcanos and earthquakes—Supposed original state of fusion of the planet—Universal fluidity not proved by spheroidal figure of the earth—Attempt to calculate the thickness of the solid crust of the earth by precessional motion—Heat in mines increasing with the depth—Objections to the supposed intense heat of a central fluid—Whether chemical changes may produce volcanic heat—Currents of electricity circulating in the earth's crust.

It will hardly be questioned, after the description before given of the phenomena of earthquakes and volcanos, that both of these agents have, to a certain extent, a common origin; and I may now, therefore, proceed to inquire into their probable causes. But first, it may be well to recapitulate some of those points of relation and analogy which lead naturally to the conclusion that they spring from a common source.

The regions convulsed by violent earthquakes include within them the site of all the active volcanos. Earthquakes, sometimes local, sometimes extending over vast areas, often precede volcanic eruptions. The subterranean movement and the eruption return again and again, at irregular intervals of time, and with unequal degrees of force, to the same spots. The action of either may continue for a few hours, or for several consecutive years. Paroxysmal convulsions are usually followed, in both cases, by long periods of tranquillity. Thermal and mineral springs are abundant in countries of earthquakes and active volcanos. Lastly, hot springs situated in districts considerably distant from volcanic vents have been observed to have their temperature suddenly raised, and the volume of their water augmented, by subterranean movements.

All these appearances are evidently more or less connected with the passage of heat from the interior of the earth to the surface; and where there are active volcanos, there must exist, at some unknown depth below, enormous masses of matter intensely heated, and, in many instances, in a constant state of fusion. We have first, then, to inquire, whence is this heat derived?

It has long been a favourite conjecture, that the whole of our planet was originally in a state of igneous fusion, and that the central parts still retain a great portion of their primitive heat. Some have imagined, with the late Sir W. Herschel, that the elementary matter of the earth may have been first in a gaseous state, resembling those nebulæ which we behold in the heavens, and which are of dimensions so vast, that some of them would fill the orbits of the remotest planets of our system. The increased power of the telescope has of late years resolved the greater number of these nebulous appearances into clusters of stars, but so long as they were confidently supposed to consist of aëriform matter it was a favourite conjecture that they might, if concentrated, form solid spheres; and it was also imagined that the evolution of heat, attendant on condensation, might retain the materials of the new globes in a state of igneous fusion.

Without dwelling on such speculations, which can only have a distant bearing on geology, we may consider how far the spheroidal form of the earth affords sufficient ground for presuming that its primitive condition was one of universal fluidity. The discussion of this question would be superfluous, were the doctrine of original fluidity less popular; for it may well be asked, why the globe should be supposed to have had a pristine shape different from the present one? — why the terrestrial materials, when first called into existence, or assembled together in one place, should not have been subject to rotation, so as to assume at once that form which alone could retain their several parts in a state of equilibrium?

Let us, however, concede that the statical figure may be a modification of some other pre-existing form, and suppose the globe to have been at first a perfect and quiescent sphere, covered with an uniform ocean — what would happen when it was made to turn round on its axis with its present velocity? This problem has been considered by Playfair in his Illustrations, and he has decided, that if the surface of the earth, as laid down in Hutton's theory, has been repeatedly changed by the transportation of the detritus of the land to the bottom of the sea, the figure of the planet must in that case, whatever it may have been originally, be brought at length to coincide with the spheroid of equilibrium.* Sir John Herschel also, in reference to the same hypothesis, observes, "a centrifugal force would in that case be generated, whose general tendency would be to urge the water at every point of the surface to *recede* from the *axis*. A rotation might indeed be conceived so swift as to flirt the whole ocean from the surface, like water from a mop. But this would require a far greater velocity than what we now speak of. In the case supposed, the *weight* of the water would still keep it *on* the earth; and the tendency to recede from the axis *could* only be satisfied therefore by the water leaving the poles, and flowing towards the equator; there heaping itself up in a ridge, and being retained in opposition to its weight or natural tendency towards the centre by the pressure thus caused. This, however, could not take place without laying dry the polar regions, so that protuberant land would appear at the poles, and a zone of ocean be disposed around the equator. This would be the first or immediate effect. Let us now see what would afterwards happen if things were allowed to take their natural course.

"The sea is constantly beating on the land, grinding it down, and scattering its worn-off particles and fragments, in the state of sand and pebbles, over its bed. Geological facts afford abundant proof that the existing continents have all of them undergone this process even more than once, and been entirely torn in fragments, or reduced to powder, and submerged and re-constructed. Land, in this view of the subject, loses its attribute of fixity. As a mass it might hold together in opposition to forces which the water freely obeys; but in its state of successive or simultaneous degradation, when disseminated through the water, in the state of sand or mud, it is subject to all the impulses of that fluid. In the lapse of time, then, the protuberant land would be destroyed, and spread over the bottom of the ocean, filling up the lower parts, and tending continually to re-model the surface of the solid nucleus, in correspondence with the *form of equilibrium*. Thus after a sufficient lapse of time, in the case of an earth in rotation, the polar protuberances would gradually be cut down and disappear, being transferred to the equator (as being *then* the *deepest sea*), till the earth would assume by degrees the form we observe it to have—that of a flattened or *oblate* ellipsoid.

---

* Illust. of Hutt. Theory, § 435—443.

"We are far from meaning here to trace the process *by which* the earth really assumed its actual form; all we intend is to show that this is the form to which, under a condition of a rotation on its axis, it must *tend*, and which it would attain even if originally and (so to speak) perversely constituted otherwise."*

In this passage, the author has contemplated the superficial effects of aqueous causes only; but neither he nor Playfair seem to have followed out the same inquiry with reference to another part of Hutton's system; namely, that which assumes the successive fusion by heat of different parts of the solid earth. Yet the progress of geology has continually strengthened the evidence in favour of the doctrine that local variations of temperature have melted one part after another of the earth's crust, and this influence has perhaps extended downwards to the very centre. If, therefore, before the globe had assumed its present form, it was made to revolve on its axis, all matter to which freedom of motion was given by fusion, must before consolidating have been impelled towards the equatorial regions in obedience to the centrifugal force. Thus lava flowing out in superficial streams would have its motion retarded when its direction was towards the pole, accelerated when towards the equator, or if lakes and seas of lava existed beneath the earth's crust in equatorial regions, as probably now beneath the Peruvian Andes, the imprisoned fluid would force outwards and permanently upheave the overlying rocks. The statical figure, therefore, of the terrestrial spheroid (of which the longest diameter exceeds the shortest by about twenty-five miles), may have been the result of gradual and even of existing causes, and not of a primitive, universal, and simultaneous fluidity.†

Experiments made with the pendulum, and observations on the manner in which the earth attracts the moon, have shown that our planet is not an empty sphere, but, on the contrary, that its interior, whether solid or fluid, has a higher specific gravity than the exterior. It has also been inferred, that there is a regular increase in density from the surface towards the centre, and that the equatorial protuberance is continued inwards; that is to say, that layers of equal density are arranged elliptically, and symmetrically, from the exterior to the centre. These conclusions, however, have been deduced rather as a consequence of the hypothesis of primitive and simultaneous fluidity than proved by experiment. The inequalities in the moon's motion, by which some have endeavoured to confirm them, are so extremely slight, that the opinion can be regarded as little more than a probable conjecture.

---

* Herschel's Astronomy, chap. iii.

† See Hennessy, On Changes in Earth's Figure, &c. Journ. Geol. Soc. Dublin, 1849; and Proc. Roy. Irish Acad. vol. iv. p. 337.

The mean density of the earth has been computed by Laplace to be about 5½, or more than five times that of water. Now the specific gravity of many of our rocks is from 2½ to 3, and the greater part of the metals range between that density and 21. Hence some have imagined that the terrestrial nucleus may be metallic — that it may correspond, for example, with the specific gravity of iron, which is about 7. But here a curious question arises in regard to the form which materials, whether fluid or solid, might assume, if subjected to the enormous pressure which must obtain at the earth's centre. Water, if it continued to decrease in volume according to the rate of compressibility deduced from experiment, would have its density doubled at the depth of ninety-three miles, and be as heavy as mercury at the depth of 362 miles. Dr. Young computed that, at the earth's centre, steel would be compressed into one-fourth, and stone into one-eighth of its bulk.* It is more than probable, however, that after a certain degree of condensation, the compressibility of bodies may be governed by laws altogether different from those which we can put to the test of experiment; but the limit is still undetermined, and the subject is involved in such obscurity, that we cannot wonder at the variety of notions which have been entertained respecting the nature and conditions of the central nucleus. Some have conceived it to be fluid, others solid; some have imagined it to have a cavernous structure, and have even endeavoured to confirm this opinion by appealing to observed irregularities in the vibrations of the pendulum in certain countries.

An attempt has recently been made by Mr. Hopkins to determine the least thickness which can be assigned to the solid crust of the globe, if we assume the whole to have been once perfectly fluid, and a certain portion of the exterior to have acquired solidity by gradual refrigeration. This result he has endeavoured to obtain by a new solution of the delicate problem of the precessional motion of the pole of the earth. It is well known that while the earth revolves round the sun the direction of its axis remains very nearly the same, *i. e.* its different positions in space are all nearly parallel to each other. This parallelism, however, is not accurately preserved, so that the axis, instead of coming exactly into the position which it occupied a year before, becomes inclined to it at a very small angle, but always retaining very nearly the same inclination to the plane of the earth's orbit. This motion of the pole changes the position of the equinoxes by about fifty seconds annually, and always in the same direction. Thus the pole-star, after a certain time, will entirely lose its claim to that appellation, until in the course of somewhat more than 25,000 years the earth's axis shall again occupy its present angular position, and again point very nearly as now to the pole-star. This motion of the axis is called *precession.* It is caused by the attraction of the sun and moon, and principally the moon, on the protuberant parts at the earth's equator; and if these parts were solid to a great depth, the motion thus produced would differ considerably from that which would exist if they were perfectly fluid, and incrusted over with a thin shell only a few miles thick. In other words, the disturbing action of the moon will not be the same upon a globe all solid and upon one nearly all fluid, or it will not be the same upon a globe in which the solid shell forms one half of the mass, and another in which it forms only one tenth.

---

* Young's Lectures, and Mrs. Somerville's Connexion of the Physical Sciences p. 90.

Mr. Hopkins has, therefore, calculated the amount of precessional motion which would result if we assume the earth to be constituted as above stated; *i. e.* fluid internally, and enveloped by a solid shell; and he finds that the amount will not agree with the observed motion, unless the crust of the earth be of a certain thickness. In calculating the exact amount some ambiguity arises in consequence of our ignorance of the effect of pressure in promoting the solidification of matter at high temperatures. The hypothesis least favourable for a great thickness is found to be that which assumes the pressure to produce no effect on the process of solidification. Even on this extreme assumption the thickness of the solid crust must be nearly *four hundred miles*, and this would lead to the remarkable result that the proportion of the solid to the fluid part would be as 49 to 51, or, to speak in round numbers, there would be nearly as much solid as fluid matter in the globe. The conclusion, however, which Mr. Hopkins announces as that to which his researches have finally conducted him, is thus expressed: "Upon the whole, then, we may venture to assert that the minimum thickness of the crust of the globe, which can be deemed consistent with the observed amount of precession, cannot be less than one-fourth or one-fifth of the earth's radius." That is from 800 to 1000 miles.*

It will be remarked, that this is a *minimum*, and any still *greater* amount would be quite consistent with the actual phenomena; the calculations not being opposed to the supposition of the general solidity of the entire globe. Nor do they preclude us from imagining that great lakes or seas of melted matter may be distributed through a shell 400 or 800 miles thick, provided they be so inclosed as to move with it, whatever motion of rotation may be communicated by the disturbing forces of the sun and moon.

---

* Phil. Trans. 1839, and Researches in Physical Geology, 1st, 2nd, and 3rd series, London, 1839—1842; also on Phenomena and Theory of Volcanos, Report Brit. Assoc. 1847.

Central heat. — The hypothesis of internal fluidity calls for the more attentive consideration, as it has been found that the heat in mines augments in proportion as we descend. Observations have been made, not only on the temperature of the air in mines, but on that of the rocks, and on the water issuing from them. The mean rate of increase, calculated from results obtained in six of the deepest coal mines in Durham and Northumberland, is 1° Fahr. for a descent of forty-four English feet.* A series of observations, made in several of the principal lead and silver mines in Saxony, gave 1° Fahr. for every sixty-five feet. In this case, the bulb of the thermometer was introduced into cavities purposely cut in the solid rock at depths varying from 200 to above 900 feet. But in other mines of the same country, it was necessary to descend thrice as far for each degree of temperature.†

A thermometer was fixed in the rock of the Dolcoath mine, in Cornwall, by Mr. Fox, at the great depth of 1380 feet, and frequently observed during eighteen months; the mean temperature was 68° Fahr., that of the surface being 50°, which gives 1° for every seventy-five feet.

Kupffer, after an extensive comparison of the results in different countries, makes the increase 1° F. for about every thirty-seven English feet.‡ M. Cordier announces, as the result of his experiments and observations on the temperature of the interior of the earth, that the heat increases rapidly with the depth; but the increase does not follow the same law over the whole earth, being twice or three times as much in one country as in another, and these differences are not in constant relation either with the latitudes or longitudes of places.§ He is of opinion, however, that the increase would not be overstated at 1° Cent. for every twenty-five metres, or about 1° F. for every forty-five feet.‖ The experimental well bored at Grenelle, near Paris, gave about 1° F. for every sixty English feet, when they had reached a depth of 1312 feet.

Some writers have endeavoured to refer these phenomena (which, however discordant as to the ratio of increasing heat, appear all to point one way) to the condensation of air constantly descending from the surface into the mines. For the air under pressure would give out latent heat, on the same principle as it becomes colder when rarified in the higher regions of the atmosphere. But, besides that the quantity of heat is greater than could be supposed to flow from this source, the argument has been answered in a satisfactory manner by Mr. Fox, who has shown, that, in the mines of Cornwall the ascending have generally a higher temperature than the descending aërial currents. The difference between them was found to vary from 9° to 17° F.: a proof that, instead of imparting heat, these currents actually carry off a large quantity from the mines.*

---

* Ed. Journ. of Sci., April, 1832.

† Cordier, Mém. de l'Instit. tom. vii.

‡ Pog. Ann. tom. xv. p. 159.

§ See M. Cordier's Memoir on the Temperature of the Interior of the Earth, read to the Academy of Sciences, 4th June, 1827.—Edin. New Phil. Journal, No. viii. p. 273.

‖ Cordier, Mém. de l'Instit. tom. vii.

If we adopt M. Cordier's estimate of 1° F. for every 45 feet of depth as the mean result, and assume, with the advocates of central fluidity, that the increasing temperature is continued downwards, we should reach the ordinary boiling point of water at about two miles below the surface, and at the depth of about twenty-four miles should arrive at the melting point of iron, a heat sufficient to fuse almost every known substance. The temperature of melted iron was estimated at 21,000° F., by Wedgwood; but his pyrometer gives, as is now demonstrated, very erroneous results. Professor Daniell ascertained that the point of fusion is 2786° F.†

According to Mr. Daniell's scale, we ought to encounter the internal melted matter before penetrating through a thickness represented by that of the outer circular line in the annexed diagram (fig. 92.); whereas, if the other or less correct scale be adopted, we should meet with it at some point between the two circles; the space

Fig. 92.



Section of the earth in which the breadth of the outer boundary line represents a thickness of 25 miles; the space between the circles, including the breadth of the lines, 200 miles.

---

* Phil. Mag. and Ann. Feb. 1830.

† The heat was measured in Wedgwood's pyrometer by the contraction of pure clay, which is reduced in volume when heated, first by the loss of its water of combination, and afterwards, on the application of more intense heat, by incipient vitrification. The expansion of platina is the test employed by Mr. Daniell, in his pyrometer, and this has been found to yield uniform and constant results, such as are in perfect harmony with conclusions drawn from various other independent sources. The instrument for which the author received the Rumford Medal from the Royal Society, in 1833, is described in the Phil. Trans. 1830, part ii., and 1831, part ii.

between them, together with the lines themselves, representing a crust of 200 miles in depth. In either case, we must be prepared to maintain that a temperature many times greater than that sufficient to melt the most refractory substances known to us, is sustained at the centre of the globe; while a comparatively thin crust, resting upon the fluid, remains unmelted; or is even, according to M. Cordier, increasing in thickness, by the continual addition of new internal layers solidified during the process of refrigeration.

The mathematical calculations of Fourier, on the passage of heat through conducting bodies, have been since appealed to in support of these views; for he has shown that it is compatible with theory that the present temperature of the surface might co-exist with an intense heat, at a certain depth below. But his reasoning seems to be confined to the conduction of heat through solid bodies; and the conditions of the problem are wholly altered when we reason about a fluid nucleus, as we must do if it be assumed that the heat augments from the surface to the interior, according to the rate observed in mines. For when the heat of the lower portion of a fluid is increased, a circulation begins throughout the mass, by the ascent of hotter, and the descent of colder currents. And this circulation, which is quite distinct from the mode in which heat is propagated through solid bodies, must evidently occur in the supposed central ocean, if the laws of fluids and of heat are the same there as upon the surface.

In Mr. Daniell's experiments for obtaining a measure of the heat of bodies, at their point of fusion, he invariably found that it was impossible to raise the heat of a large crucible of melted iron, gold, or silver, a single degree beyond the melting point, so long as a bar of the respective metals was kept immersed in the fluid portions. So in regard to other substances, however great the quantities fused, their temperature could not be raised while any solid pieces immersed in them remained unmelted; every accession of heat being instantly absorbed during their liquefaction. These results are, in fact, no more than the extension of a principle previously established, that so long as a fragment of ice remains in water, we cannot raise the temperature of the water above 32° F.

If, then, the heat of the earth's centre amount to 450,000° F., as M. Cordier deems highly probable, that is to say, about twenty times the heat of melted iron, even according to Wedgwood's scale, and upwards of 160 times according to the improved pyrometer, it is clear that the upper parts of the fluid mass could not long have a temperature only just sufficient to melt rocks. There must be a continual tendency towards a uniform heat; and until this were accomplished, by the interchange of portions of fluid of different densities, the surface could not begin to consolidate. Nor, on the hypothesis of primitive fluidity, can we conceive any crust to have been formed until *the whole* planet had cooled down to about the temperature of incipient fusion.

It cannot be objected that hydrostatic pressure would prevent a tendency to equalization of temperature; for, as far as observations have yet been made, it is found that the waters of deep lakes and seas are governed by the same laws as a shallow pool; and no experiments indicate that solids resist fusion under high pressure. The arguments, indeed, now controverted, always proceed on the admission that the internal nucleus is in a state of fusion.

It may be said that we may stand upon the hardened surface of a lava current while it is still in motion,—nay, may descend into the crater of Vesuvius after an eruption, and stand on the scoriæ while every crevice shows that the rock is red-hot two or three feet below us; and at a somewhat greater depth, all is, perhaps, in a state of fusion. May not, then, a much more intense heat be expected at the depth of several hundred yards, or miles? The answer is,—that, until a great quantity of heat has been given off, either by the emission of lava, or in a latent form by the evolution of steam and gas, the melted matter continues to boil in the crater of a volcano. But ebullition ceases when there is no longer a sufficient supply of heat from below, and then a crust of lava may form on the top, and showers of scoriæ may then descend upon the surface, and remain unmelted. If the internal heat be raised again, ebullition will recommence, and soon fuse the superficial crust. So in the case of the moving current, we may safely assume that no part of the liquid beneath the hardened surface is much above the temperature sufficient to retain it in a state of fluidity.

It may assist us in forming a clearer view of the doctrine now controverted, if we consider what would happen were a globe of homogeneous composition placed under circumstances analogous, in regard to the distribution of heat, to those above stated. If the whole planet, for example, were composed of water covered with a spheroidal crust of ice fifty miles thick, and with an interior ocean having a central heat about two hundred times that of the melting point of ice, or 6400° F.; and if, between the surface and the centre, there was every intermediate degree of temperature between that of melting ice and that of the central nucleus;—could such a state of things last for a moment? If it must be conceded, in this case, that the whole spheroid would be instantly in a state of violent ebullition, that the ice (instead of being strengthened annually by new internal layers) would soon melt, and form part of an atmosphere of steam—on what principle can it be maintained that analogous effects would not follow, in regard to the earth, under the conditions assumed in the theory of central heat?*

M. Cordier admits that there must be tides in the internal melted ocean; but their effect, he says, has become feeble, although originally, when the fluidity of the globe was perfect, "the rise and fall of these ancient land tides could not have been less than from thirteen to sixteen feet." Now, granting for a moment, that these tides have become so feeble as to be incapable of causing the fissured shell of the earth to be first uplifted and then depressed every six hours, still may we not ask whether, during eruptions, the lava, which is supposed to communicate with a great central ocean, would not rise and fall sensibly in a crater such as Stromboli, where there is always melted matter in a state of ebullition?

---

* The above remarks are reprinted verbatim from my third edition, May, 1834. A memoir was afterwards communicated by M. Poisson to the Academy of Sciences, January, 1837, on the solid parts of the globe, containing an epitome of a work entitled "Théorie Mathématique de la Chaleur," published in 1835. In this memoir he controverts the doctrine of the high temperature of a central fluid on similar grounds to those above stated. He imagines, that if the globe ever passed from a liquid to a solid state by radiation of heat, the central nucleus must have begun to cool and consolidate first.

Whether chemical changes may produce volcanic heat.—Having now explained the reasons which have induced me to question the hypothesis of central heat as the primary source of volcanic action, it remains to consider what has been termed the chemical theory of volcanos. It is well known that many, perhaps all, of the substances of which the earth is composed are continually undergoing chemical changes. To what depth these processes may be continued downwards must, in a great degree, be matter of conjecture; but there is no reason to suspect that, if we could descend to a great distance from the surface, we should find elementary substances differing essentially from those with which we are acquainted.

All the solid, fluid, and gaseous bodies known to us consist of a very small number of these elementary substances variously combined: the total number of elements at present known is less than sixty; and not half of these enter into the composition of the more abundant inorganic productions. Some portions of such compounds are daily undergoing decomposition, and their constituent parts being set free are passing into new combinations. These processes are by no means confined to minerals at the earth's surface, and are very often accompanied by the evolution of heat, which is intense in proportion to the rapidity of the combinations. At the same time there is a development of electricity.

The spontaneous combustion of beds of bituminous shale, and of refuse coal thrown out of mines, is generally due to the decomposition of pyrites; and it is the contact of air and water which brings about the change. Heat results from the oxidation of the sulphur and iron, though on what principle heat is generated, when two or more bodies having a strong affinity for each other unite suddenly, is wholly unexplained.

Electricity a source of volcanic heat.—It has already been stated, that chemical changes develope electricity; which, in its turn, becomes a powerful disturbing cause. As a chemical agent, says Davy, its silent and slow operation in the economy of nature is much more important than its grand and impressive operation in lightning and thunder. It may be considered, not only as directly producing an infinite variety of changes, but as influencing almost all which take place; it would seem, indeed, that chemical attraction itself is only a peculiar form of the exhibition of electrical attraction.[*]

---

[*] Consolations in Travel, p. 271.

Now that it has been demonstrated that magnetism and electricity are always associated, and are perhaps only different conditions of the same power, the phenomena of terrestrial magnetism have become of no ordinary interest to the geologist. Soon after the first great discoveries of Oersted in electro-magnetism, Ampère suggested that all the phenomena of the magnetic needle might be explained by supposing currents of electricity to circulate constantly in the shell of the globe in directions parallel to the magnetic equator. This theory has acquired additional consistency the farther we have advanced in science; and according to the experiments of Mr. Fox, on the electro-magnetic properties of metalliferous veins, some trace of electric currents seems to have been detected in the interior of the earth.[*]

Some philosophers ascribe these currents to the chemical action going on in the superficial parts of the globe to which air and water have the readiest access; while others refer them, in part at least, to thermo-electricity excited by the solar rays on the surface of the earth during its rotation; successive parts of the atmosphere, land, and sea being exposed to the influence of the sun, and then cooled again in the night. That this idea is not a mere speculation, is proved by the correspondence of the diurnal variations of the magnet with the apparent motion of the sun; and by the greater amount of variation in summer than in winter, and during the day than in the night. M. de la Rive, although conceding that such minor variations of the needle may be due to thermo-electricity, contends that the general phenomena of terrestrial magnetism must be attributed to currents far more intense; which, though liable to secular fluctuations, act with much greater constancy and regularity than the causes which produce the diurnal variations.[†] The remark seems just; yet it is difficult to assign limits to the accumulated influence even of a very feeble force constantly acting on the whole surface of the earth. This subject, however, must evidently remain obscure, until we become acquainted with the causes which give a determinate direction to the supposed electric currents. Already the experiments of Faraday on the rotation of magnets have led him to speculate on the manner in which the earth, when once it had become magnetic, might produce electric currents within itself, in consequence of its diurnal rotation.[‡] We have seen also in a former chapter (p. 129.), that the recent observations of Schwabe, 1852, have led Col. Sabine to the discovery of a connexion between certain periodical changes, which take place in the spots on the sun, and a certain cycle of variations in terrestrial magnetism. These seem to point to the existence of a solar magnetic period, and suggest the idea of the sun's magnetism exerting an influence on the mass of our planet.

In regard to thermo-electricity, I may remark, that it may be generated by great inequalities of temperature, arising from a partial distribution of volcanic heat. Wherever, for example, masses of rock occur of great horizontal extent, and of considerable depth, which are at one point in a state of fusion (as beneath some active volcano); at another, red-hot; and at a third, comparatively cold — strong thermo-electric action may be excited.

---

[*] Phil. Trans. 1830, p. 399.

[†] Biblioth. Univers., 1833, Electricité. pp. 172, 173, &c.

[‡] Phil. Trans., 1832, p. 176. ; also

Some, perhaps, may object, that this is reasoning in a circle; first to introduce electricity as one of the primary causes of volcanic heat, and then to derive the same heat from thermo-electric currents. But there must, in truth, be much reciprocal action between the agents now under consideration; and it is very difficult to decide which should be regarded as the prime mover, or to see where the train of changes, once begun, would terminate. Whether subterranean electric currents if once excited might sometimes possess the decomposing power of the voltaic pile, is a question not perhaps easily answered in the present state of science; but such a power, if developed, would at once supply us with a never-failing source of chemical action from which volcanic heat might be derived.

Recapitulation. — Before entering, in the next chapter, still farther into the inquiry, how far the phenomena of volcanos and earthquakes accord with the hypothesis of a continued generation of heat by chemical action, it may be desirable to recapitulate, in a few words, the conclusions already obtained.

1st. The primary causes of the volcano and the earthquake are, to a great extent, the same, and must be connected with the passage of heat from the interior to the surface.

2dly. This heat has been referred, by many, to a supposed state of igneous fusion of the central parts of the planet when it was first created, of which a part still remains in the interior, but is always diminishing in intensity.

3dly. The spheroidal figure of the earth, adduced in support of this theory, does not of necessity imply an universal and simultaneous fluidity, in the beginning; for supposing the original figure of our planet had been strictly spherical — which, however, is a gratuitous assumption, resting on no established analogy — still the statical figure must have been assumed, if sufficient time be allowed, by the gradual operation of the centrifugal force, acting on the materials brought successively within its action by aqueous and igneous causes.

4thly. It appears, from experiment, that the heat in mines increases progressively with their depth; and if the ratio of increase be continued uniformly from the surface to the interior, the whole globe, with the exception of a small external shell, must be fluid, and the central parts must have a temperature many times higher than that of melted iron.

5thly. But the theory adopted by M. Cordier and others, which maintains the actual existence of such a state of things, seems wholly inconsistent with the laws which regulate the circulation of heat through fluid bodies. For, if the central heat were as intense as is represented, there must be a circulation of currents, tending to equalize the temperature of the resulting fluids, and the solid crust itself would be melted.

6thly. Instead of an original central heat, we may, perhaps, refer the heat of the interior to chemical changes constantly going on in the earth's crust; for the general effect of chemical combination is the evolution of heat and electricity, which in their turn become sources of new chemical changes.

CHAPTER XXXII.

CAUSES OF EARTHQUAKES AND VOLCANOS — *continued.*

Review of the proofs of internal heat — Theory of an unoxidated metallic nucleus — Whether the decomposition of water may be a source of volcanic heat — Geysers of Iceland — Causes of earthquakes — Wavelike motion — Expansive power of liquid gases — Connection between the state of the atmosphere and earthquakes — Permanent upheaval and subsidence of land — Expansion of rocks by heat — The balance of dry land how preserved — Subsidence in excess — Conclusion.

WHEN we reflect that the largest mountains are but insignificant protuberances upon the surface of the earth, and that these mountains are nevertheless composed of different parts which have been formed in succession, we may well feel surprise that the central fluidity of the planet should have been called in to account for volcanic phenomena. To suppose the entire globe to be in a state of igneous fusion, with the exception of a solid shell, not more than from thirty to one hundred miles thick, and to imagine that the central heat of this fluid spheroid exceeds by more than two hundred times that of liquid lava, is to introduce a force altogether disproportionate to the effects which it is required to explain.

The ordinary repose of the surface implies, on the contrary, an inertness in the internal mass which is truly wonderful. When we consider the combustible nature of the elements of the earth, so far as they are known to us, — the facility with which their compounds may be decomposed and made to enter into new combinations, — the quantity of heat which they evolve during these processes; when we recollect the expansive power of steam, and that water itself is composed of two gases which, by their union, produce intense heat; when we call to mind the number of explosive and detonating compounds which have been already discovered, we may be allowed to share the astonishment of Pliny, that a single day should pass without a general conflagration: — "Excedit profectò omnia miracula, ullum diem fuisse quo non cuncta conflagrarent."[*]

The signs of internal heat observable on the surface of the earth do not necessarily indicate the permanent existence of subterranean heated masses, whether fluid or solid, by any means so vast as our continents and seas; yet how insignificant would these appear if distributed through an external shell of the globe one or two hundred miles in depth! The principal facts in proof of the accumulation of heat below the surface may be summed up in a few words. Several volcanos are constantly in eruption, as Stromboli and Nicaragua; others are known to have been active for periods of 60, or even 150 years, as those of Sangay in Quito, Popocatepetl in Mexico, and the volcano of the Isle of Bourbon. Many craters emit hot vapours in the intervals between eruptions, and solfataras evolve incessantly the same gases as volcanos. Steam of high temperature has continued for more than twenty centuries to issue from the "stufas," as the Italians call them; thermal springs abound not only in regions of earthquakes, but are found in almost all countries, however distant from active vents; and, lastly, the temperature in the mines of various parts of the world is found to increase in proportion as we descend.

---

[*] Hist. Mundi, lib. ii. c. 107.

The diagram (fig. 93.) in the next page, may convey some idea of the proportion which our continents and the ocean bear to the radius of the earth.* If all the land were about as high as the Himalaya mountains, and the ocean every where as deep as the Pacific, the whole of both might be contained within a space expressed by the thickness of the line *a b*; and masses of nearly equal volume might be placed in the space marked by the line *c d*, in the interior. Seas of lava, therefore, of the size of the Mediterranean, or even of the Atlantic, would be as nothing if distributed through such an outer shell of the globe as is represented by the shaded portion of the figure *a b c d*. If throughout that space we imagine electro-chemical causes to be continually in operation, even of very feeble power, they might give rise to heat which, if accumulated at certain points, might melt or render red-hot entire mountains, or sustain the temperature of stufas and hot springs for ages.

Theory of an unoxidated metallic nucleus. — When Sir H. Davy first discovered the metallic bases of the earths and alkalies, he threw out the idea that those metals might abound in an unoxidized state in the subterranean regions to which water must occasionally penetrate. Whenever this happened, gaseous matter would be set free, the metals would combine with the oxygen of the water, and sufficient heat might be evolved to melt the surrounding rocks. This hypothesis, although afterwards abandoned by its author, was at first very favourably received both by the chemist and the geologist: for silica, alumina, lime, soda, and oxide of iron, — substances of which lavas are principally composed, — would all result from the contact of the inflammable metals alluded to with water. But whence this abundant store of unsaturated metals in the interior? It was assumed

---

* Reduced, by permission, from a figure in plate 40. of Sir H. De la Beche's Geological Sections and Views.



Fig. 93.

that, in the beginning of things, the nucleus of the earth was mainly composed of inflammable metals, and that oxidation went on with intense energy at first; till at length, when a superficial crust of oxides had been formed, the chemical action became more and more languid.

This speculation, like all others respecting the primitive state of the earth's nucleus, rests unavoidably on arbitrary assumptions. But we may fairly inquire whether any existing causes may have the power of deoxidating the earthy and alkaline compounds formed from time to time by the action of water upon the metallic bases. If so, and if the original crust or nucleus of the planet contained distributed through it here and there some partial stores of potassium, sodium, and other metallic bases, these might be oxidated and again deoxidated, so as to sustain for ages a permanent chemical action. Yet even then we should be unable to explain why such a continuous circle of operations, after having been kept up for thousands of years in one district, should entirely cease, and why another region, which had enjoyed a respite from volcanic action for one or many geological periods, should become a theatre for the development of subterranean heat.

It is well known to chemists, that the metallization of oxides, the most difficult to reduce, may be effected by hydrogen brought into contact with them at a red heat; and it is more than probable that the production of potassium itself, in the common gun-barrel process, is due to the power of nascent hydrogen derived from the water which the hydrated oxide contains. According to the recent experiments, also, of Faraday, it would appear that every case of metallic reduction by voltaic agency, from saline solutions, in which water is present, is due to the secondary action of hydrogen upon the oxide; both of these being determined to the negative pole and then reacting upon one another.

It is admitted that intense heat would be produced by the occasional contact of water with the metallic bases; and it is certain that, during the process of saturation, vast volumes of hydrogen must be evolved. The hydrogen, thus generated, might permeate the crust of the earth in different directions, and become stored up for ages in fissures and caverns, sometimes in a liquid form, under the necessary pressure. Whenever, at any subsequent period, in consequence of the changes effected by earthquakes in the shell of the earth, this gas happened to come in contact with metallic oxides at a high temperature, the reduction of these oxides might be the result.

No theory seems at first more startling than that which represents water as affording an inexhaustible supply of fuel to the volcanic fires; yet is it by no means visionary. It is a fact that must not be overlooked, that while a great number of volcanos are entirely submarine, the remainder occur for the most part in islands or maritime tracts. There are a few exceptions; but some of these, observes Dr. Daubeny, are near inland salt lakes, as in Central Tartary; while others form part of a train of volcanos, the extremities of which are near the sea.

Sir H. Davy suggested that, when the sea is distant, as in the case of some of the South American volcanos, they may still be supplied with water from subterranean lakes; since, according to Humboldt, large quantities of fish are often thrown out during eruptions.* Mr. Dana also, in his valuable and original observations on the volcanos of the Sandwich Islands, reminds us of the prodigious volume of atmospheric water which must be absorbed into the interior of such large and lofty domes, composed as they are entirely of porous lava. To this source alone he refers the production of the steam by which the melted matter is propelled upwards, even to the summit of cones three miles in height.*

---

* Phil. Trans. 1828, p. 250.

When treating of springs and overflowing wells, I have stated that porous rocks are percolated by fresh water to great depths, and that sea water probably penetrates in the same manner through the rocks which form the bed of the ocean. But, besides this universal circulation in regions not far from the surface, it must be supposed that, wherever earthquakes prevail, much larger bodies of water will be forced by the pressure of the ocean into fissures at greater depths, or swallowed up in chasms; in the same manner as on the land, towns, houses, cattle, and trees are sometimes engulphed. It will be remembered, that these chasms often close again after houses have fallen into them; and for the same reason, when water has penetrated to a mass of melted lava, the steam into which it is converted may often rush out at a different aperture from that by which the water entered.

The gases, it is said, exhaled from volcanos, together with steam, are such as would result from the decomposition of salt water, and the fumes which escape from the Vesuvian lava have been observed to deposit common salt.† The emission of free muriatic acid gas in great quantities is also thought by many to favour the theory of the decomposition of the salt contained in sea water. It has been objected, however, that M. Boussingault did not meet with this gas in his examination of the elastic fluids evolved from the volcanos of equatorial America; which only give out aqueous vapour (in very large quantity), carbonic acid gas, sulphurous acid gas, and sometimes fumes of sulphur.† In reply, Dr. Daubeny has remarked, that muriatic acid may have ceased to be disengaged, because the volcanic action has become languid in equatorial America, and sea water may no longer obtain admission.

M. Gay Lussac, while he avows his opinion that the decomposition of water contributes largely to volcanic action, called attention, nevertheless, to the supposed fact, that hydrogen had not been detected in a separate form among the gaseous products of volcanos; nor can it, he says, be present; for, in that case, it would be inflamed in the air by the red-hot stones thrown out during an eruption. Dr. Davy, in his account of Graham Island, says, "I watched when the lightning was most vivid, and the eruption of the greatest degree of violence, to see if there was any inflammation occasioned by this natural electric spark — any indication of the presence of inflammable gas; but in vain.§

May not the hydrogen, Gay Lussac inquires, be combined with chlorine, and produce muriatic acid? for this gas has been observed to be evolved from Vesuvius — and the chlorine may have been derived from sea salt; which was, in fact, extracted by simple washing from the Vesuvian lava of 1822, in the proportion of nine per cent.[*] But it was answered, that Sir H. Davy's experiments had shown, that hydrogen is not combustible when mixed with muriatic acid gas; so that if muriatic gas was evolved in large quantities, the hydrogen might be present without inflammation.[†] M. Abich, on the other hand, assures us, "that although it be true that vapour illuminated by incandescent lava has often been mistaken for flame," yet he clearly detected in the eruption of Vesuvius in 1834 the flame of hydrogen.[‡]

---

* Geology of American Exploring Expedition, p. 369.

† Davy, Phil. Trans. 1828, p. 244.

‡ Ann. de Chim. et de Phys. tom. iii. p. 181.

§ Phil. Trans. 1832, p. 240.

M. Gay Lussac, in the memoir just alluded to, expressed doubt as to the presence of sulphurous acid; but the abundant disengagement of this gas during eruptions has been since ascertained: and thus all difficulty in regard to the general absence of hydrogen in an inflammable state is removed; for, as Dr. Daubeny suggests, the hydrogen of decomposed water may unite with sulphur to form sulphuretted hydrogen gas, and this gas will then be mingled with the sulphurous acid as it rises to the crater. It is shown by experiment, that these gases mutually decompose each other when mixed where steam is present; the hydrogen of the one immediately uniting with the oxygen of the other to form water, while the excess of sulphurous acid alone escapes into the atmosphere. Sulphur is at the same time precipitated.

This explanation is sufficient; but it may also be observed that the flame of hydrogen would rarely be visible during an eruption; as that gas, when inflamed in a pure state, burns with a very faint blue flame, which even in the night could hardly be perceptible by the side of red-hot and incandescent cinders. Its immediate conversion into water when inflamed in the atmosphere, might also account for its not appearing in a separate form.

Dr. Daubeny is of opinion that water containing atmospheric air may descend from the surface of the earth to the volcanic foci, and that the same process of combustion by which water is decomposed may deprive such subterranean air of its oxygen. In this manner he explains the great quantities of nitrogen evolved from volcanic vents and thermal waters, and the fact that air disengaged from the earth in volcanic regions is either wholly or in part deprived of its oxygen.

Sir H. Davy, in his memoir on the "Phenomena of Volcanos," remarks, that there was every reason to suppose in Vesuvius the existence of a descending current of air; and he imagined that subterranean cavities which threw out large volumes of steam during the eruption, might afterwards, in the quiet state of the volcano, become filled with atmospheric air.[§] The presence of ammoniacal salts in volcanic emanations, and of ammonia (which is in part composed of nitrogen) in lava, favours greatly the notion of air as well as water being deoxidated in the interior of the earth.*

---

[*] Ann. de Chim. et de Phys., tom. xxii.

[†] Quart. Journ. of Science, 1823, p. 132. note by editor.

[‡] Phénom. Géol. &c. p. 3.

[§] Phil. Trans. 1828.

It has been alleged by Professor Bischoff that the slight specific gravity of the metals of the alkalies is fatal to Davy's hypothesis, for if the mean density of the earth, as determined by astronomers, surpass that of all kinds of rocks, these metals cannot exist, at least not in great quantities in the interior of the earth.† But Dr. Daubeny has shown, that if we take the united specific gravity of potassium, sodium, silicon, iron, and all the materials which, when united with oxygen, constitute ordinary lava, and then compare their weight with lava of equal bulk, the difference is not very material, the specific gravity of the lava only exceeding by about one fourth that of the unoxidized metals. Besides, at great depths, the metallic bases of the earths and alkalies may very probably be rendered heavier by pressure.‡ Nor is it fair to embarrass the chemical theory of volcanos, with a doctrine so purely gratuitous, as that which supposes the entire nucleus of the planet to have been at first composed of unoxidated metals.

Professor Bunsen of Marburg, after analysing the gases which escape from the volcanic fumeroles and solfataras of Iceland, and after calculating the quantity of hydrogen evolved between two eruptions, affirms in contradiction of opinions previously entertained, that the hydrogen bears a perfect relation in quantity to the magnitude of the streams of lava, assuming the fusion of these last to have been the result of the heat evolved during the oxidation of alkaline and earthy metals, and this to have been brought about by the decomposition of water. Yet after having thus succeeded in removing the principal objection once so triumphantly urged against Davy's hypothesis, Bunsen concludes by declaring that the hydrogen evolved in volcanic regions cannot have been generated by the decomposition of water coming in contact with alkaline and earthy metallic bases. For, says the professor, this process presupposes the prevalence of a temperature in which carbonic acid cannot exist in contact with hydrogen without suffering a partial reduction to carbonic oxide; "and not a trace of carbonic oxide is ever found in volcanic exhalations."§ At the same time it will be seen, by consulting the able memoirs of the Marburg chemist, that he supposes many energetic kinds of chemical action to be continually going on in the interior of the earth, capable of causing the disengagement of hydrogen; and there can be no doubt that this gas may be a source of innumerable new changes, capable of producing the local development of internal heat.

Cause of volcanic eruptions.—The most probable causes of a volcanic outburst at the surface have been in a great degree anticipated in the preceding speculations on the liquefaction of rocks and the generation of gases. When a minute hole is bored in a tube filled with gas condensed into a liquid, the whole becomes instantly aëriform, or, as some writers have expressed it, "flashes into vapour," and often bursts the tube. Such an experiment may represent the mode in which gaseous matter may rush through a rent in the rocks, and continue to escape for days or weeks through a small orifice, with an explosive power sufficient to reduce every substance which opposes its passage into small fragments or even dust. Lava may be propelled upwards at the same time, and ejected in the form of scoriæ. In some places, where the fluid lava lies at the bottom of a deep fissure, communicating on the one hand with the surface, and on the other with a cavern in which a considerable body of vapour has been formed, there may be an efflux of lava, followed by the escape of gas. Eruptions often commence and close with the discharge of vapour; and, when this is the case, the next outburst may be expected to take place by the same vent, for the concluding evolution of elastic fluids will keep open the duct, and leave it unobstructed.

---

* See Daubeny, Encyc. Metrop. Part 40.

† Jam. Ed. New Phil. Journ. No. li. p. 31.

‡ See Daubeny's Reply to Bischoff, Jam. Ed. New Phil. Journ. No. lii. p. 291.; and note in No. liii. p. 158.

§ Poggend. Ann. 1851, translated, Sci. Mem. 1852.

The breaking out of lava from the side or base of a lofty cone, rather than from the summit, may be attributed to the hydrostatic pressure to which the flanks of the mountain are exposed, when the column of lava has risen to a great height. Or if, before it has reached the top, there should happen to be any stoppage in the main duct, the upward pressure of the ascending column of gas and lava may burst a lateral opening.

In the case however of Mount Loa, in the Sandwich Islands, there appears to be a singular want of connexion or sympathy between the eruptions of the central and the great lateral vent. The great volcanic cone alluded to rises to the height of 13,760 feet above the level of the sea, having a crater at its summit, from which powerful streams of lava have flowed in recent times, and having another still larger crater, called Kilauea, on its south-eastern slope, about 4000 feet above the sea. This lateral cavity resembles a huge quarry cut in the mountain's side, being about 1000 feet deep when in its ordinary state. It is seven miles and a half in circuit, and scattered over its bottom, at different levels, are lakes and pools of lava, always in a state of ebullition. The liquid in one of these will sometimes sink 100 or 150 feet, while it is overflowing in another at a higher elevation, there being, it should seem, no communication between them. In like manner, lava overflows in the summit crater of Mount Loa, nearly 14,000 feet high, while the great lateral cauldron just alluded to (of Kilauea) continues as tranquil as usual, affording no relief to any part of the gases or melted matter which are forcing their way upwards in the centre of the mountain. "How," asks Mr. Dana, "if there were any subterranean channel connecting the two great vents, could this want of sympathy exist? How, according to the laws of hydrostatic pressure, can a column of fluid stand 10,000 feet higher in one leg of the syphon than in the other?" The eruptions, he observes, are not paroxysmal; on the contrary, the lava rises slowly and gradually to the summit of the lofty cone, and then escapes there without any commotion manifesting itself in Kilauea, a gulf always open on the flanks of the same mountain. One conclusion, he says, is certain, namely, *that volcanos are no safety valves* as they have been called; for here two independent and apparently isolated centres of volcanic activity, only sixteen miles distant from each other, are sustained in one and the same cone.*

Without pretending to solve this enigma, I cannot refrain from remarking, that the supposed independence of several orifices of eruption in one crater like Kilauea, when adduced in confirmation of the doctrine of two distinct sources of volcanic action underneath one mountain, proves too much. No one can doubt, that the pools of lava in Kilauea have been derived from some common reservoir, and have resulted from a combination of causes commonly called volcanic, which are at work in the interior at some unknown distance below. These causes have given rise in Mount Loa to eruptions from many points, but principally from one centre, so that a vast dome of ejected matter has been piled up. The subsidiary crater has evidently never given much relief to the imprisoned, heated, and liquefied matter, for Kilauea does not form a lateral protuberance interfering with the general shape or uniform outline of Mount Loa.

Geysers of Iceland. — As aqueous vapour constitutes the most abundant of the aëriform products of volcanos in eruption, it may be well to consider attentively a case in which steam is exclusively the moving power — that of the Geysers of Iceland. These intermittent hot springs occur in a district situated in the south-western division of Iceland, where nearly one hundred of them are said to break out within a circle of two miles. That the water is of atmospheric origin derived from rain and melted snow is proved, says Professor Bunsen, by the nitrogen which rises from them either pure or mixed with other gases. The springs rise through a thick current of lava, which may perhaps have flowed from Mount Hecla, the summit of that volcano being seen from the spot at the distance of more than thirty miles. In this district the rushing of water is sometimes heard in chasms beneath the surface; for here, as on Etna, rivers flow in subterranean channels through the porous and cavernous lavas. It has more than once happened, after earthquakes, that some of the boiling fountains have increased or diminished in violence and volume, or entirely ceased, or that new ones have made their appearance — changes which may be explained by the opening of new rents and the closing of pre-existing fissures.

Few of the Geysers play longer than five or six minutes at a time, although sometimes half an hour. The intervals between their eruptions are for the most part very irregular. The Great Geyser rises out of a spacious basin at the summit of a circular mound composed of siliceous incrustations deposited from the spray of its waters. The diameter of this basin, in one direction, is fifty-six feet, and forty-six in another. (See fig. 94.) In the centre is a pipe seventy-eight feet in perpendicular depth, and from eight to ten feet in diameter, but gradually widening, as it rises into the basin. The inside of the basin is whitish, consisting of a siliceous crust, and perfectly smooth, as are likewise two small channels on the sides of the mound, down which the water escapes when the bowl is filled to the margin. The circular basin is sometimes empty, as represented in the following sketch; but is usually filled with beautifully transparent water in a state of ebullition. During the rise of the boiling water in the pipe, especially when the ebullition is most violent, and when the water is thrown up in jets, subterranean noises are heard, like the distant firing of cannon, and the earth is slightly shaken. The sound then increases and the motion becomes more violent, till at length a column of water is thrown up, with loud explosions, to the height of one or two hundred feet. After playing for a time like an artificial fountain, and giving off great clouds of vapour, the pipe or tube is emptied; and a column of steam, rushing up with amazing force and a thundering noise, terminates the eruption.

---

* Proceed. Americ. Assoc. 1849.

Fig. 94.



View of the Crater of the Great Geyser in Iceland.*

If stones are thrown into the crater, they are instantly ejected; and such is the explosive force, that very hard rocks are sometimes shivered by it into small pieces. Henderson found that by throwing a great quantity of large stones into the pipe of Strockr, one of the Geysers, he could bring on an eruption in a few minutes.† The fragments of stone, as well as the boiling water, were thrown in that case to a much greater height than usual. After the water had been ejected, a column of steam continued to rush up with a deafening roar for nearly an hour; but the Geyser, as if exhausted by this

---

[*] Reduced from a sketch given by Sir W. J. Hooker, in his Tour in Iceland, vol. i. p. 149.

[†] Journal of a Residence in Iceland, p. 74.

effort, did not send out a fresh eruption when its usual interval of rest had elapsed. The account given by Sir George Mackenzie of a Geyser which he saw in eruption in 1810 (see fig. 95.), agrees perfectly with the above description by Henderson. The steam and water rose for half an hour to the height of 70 feet, and the white column remained perpendicular notwithstanding a brisk gale of wind which was blowing against it. Stones thrown into the pipe were projected to a greater height than the water. To leeward of the vapour a heavy shower of rain was seen to fall.*

Fig. 95.



Eruption of the New Geyser in 1810. (Mackenzie.)

Among the different theories proposed to account for these phenomena, I shall first mention one suggested by Sir J. Herschel. An imitation of these jets, he says, may be produced on a small scale, by heating red hot the stem of a tobacco pipe, filling the bowl with water, and so inclining the pipe as to let the water run through the stem. Its escape, instead of taking place in a continued stream, is then performed by a succession of violent explosions, at first of steam alone, then of water mixed with steam; and, as the pipe cools, almost wholly of water. At every such paroxysmal escape of the water, a portion is driven back, accompanied with steam, into the bowl. The intervals between the explosions depend on the heat, length, and inclination of the pipe; their continuance, on its thickness and conducting power.† The application of this experiment to the

---

* Mackenzie's Iceland. † MS. read to Geol. Soc. of London, Feb. 29. 1832.

Geysers merely requires that a subterranean stream, flowing through the pores and crevices of lava, should suddenly reach a fissure, in which the rock is red hot or nearly so. Steam would immediately be formed, which, rushing up the fissure, might force up water along with it to the surface, while, at the same time, part of the steam might drive back the water of the supply for a certain distance towards its source. And when, after the space of some minutes, the steam was all condensed, the water would return, and a repetition of the phenomena take place.

There is, however, another mode of explaining the action of the Geyser, perhaps more probable than that above described. Suppose water percolating from the surface of the earth to penetrate into the subterranean cavity A D (fig. 96.) by the fissures F F, while, at the same time, steam at an extremely high temperature, such as is commonly given out from the rents of lava currents during congelation, emanates from the fissures C. A portion of the steam is at first condensed into water, while the temperature of the water is raised by the latent heat thus evolved, till, at last, the lower part of the cavity is filled with boiling water and the upper with steam under high pressure. The expansive force of the steam becomes, at length, so great, that the water is forced up the fissure or pipe E B, and runs over the rim of the basin. When the pressure is thus diminished, the steam in the upper part of the cavity A expands, until all the water D is driven into the pipe; and when this happens, the steam, being the lighter of the two fluids, rushes up through the water with

Fig. 96.



Supposed reservoir and pipe of a Geyser in Iceland.*

---

* From Sir George Mackenzie's Iceland.

great velocity. If the pipe be choked up artificially, even for a few minutes, a great increase of heat must take place; for it is prevented from escaping in a latent form in steam; so that the water is made to boil more violently, and this brings on an eruption.

Professor Bunsen, before cited, adopts this theory to account for the play of the "Little Geyser," but says it will not explain the phenomena of the Great one. He considers this, like the others, to be a thermal spring, having a narrow funnel-shaped tube in the upper part of its course, where the walls of the channel have become coated over with siliceous incrustations. At the mouth of this tube the water has a temperature, corresponding to the pressure of the atmosphere, of about 212° Fahr., but at a certain depth below it is much hotter. This the professor succeeded in proving by experiment; a thermometer suspended by a string in the pipe rising to 266° Fahr., or no less than 48 degrees above the boiling point. After the column of water has been expelled, what remains in the basin and pipe is found to be much cooled.

Previously to these experiments of Bunsen and Descloizeaux made in Iceland in 1846, it would scarcely have been supposed possible that the lower part of a free and open column of water could be raised so much in temperature without causing a circulation of ascending and descending currents, followed by an almost immediate equalization of heat. Such circulation is no doubt impeded greatly by the sides of the well not being vertical, and by numerous contractions of its diameter, but the phenomenon may be chiefly due to another cause. According to recent experiments on the cohesion of liquids by Mr. Donny of Ghent, it appears that when water is freed from all admixture of air, its temperature can be raised, even under ordinary atmospheric pressure, to 275° Fahr., so much does the cohesion of its molecules increase* when they are not separated by particles of air. As water long boiled becomes more and more deprived of air, it is probably very free from such intermixture at the bottom of the Geysers.

Among other results of the experiments of Bunsen and his companion, they convinced themselves that the column of fluid filling the tube is constantly receiving accessions of hot water from below, while it becomes cooler above by evaporation on the broad surface of the basin. They also came to a conclusion of no small interest, as bearing on the probable mechanism of ordinary volcanic eruptions, namely that the tube itself is the main seat or focus of mechanical force. This was proved by letting down stones suspended by strings to various depths. Those which were sunk to considerable distances from the surface were not cast up again, whereas those nearer the mouth of the tube were ejected to great heights. Other experiments also were made tending to demonstrate the singular fact, that there is often scarce any motion below, when a violent rush of steam and water is taking place above. It seems that when a lofty column of water possesses a temperature increasing with the depth, any slight ebullition or disturbance of equilibrium in the upper portion may first force up water into the basin, and then cause it to flow over the edge. A lower portion, thus suddenly relieved of part of its pressure, expands and is converted into vapour more rapidly than the first, owing to its greater heat. This allows the next subjacent stratum, which is much hotter, to rise and flash into a gaseous form; and this process goes on till the ebullition has descended from the middle to near the bottom of the funnel.*

---

* See Mr. Horner's Anniversary Address, Quart. Journ. Geol. Soc. 1847, liii.

In speculating, therefore, on the mechanism of an ordinary volcanic eruption, we may suppose that large subterranean cavities exist at the depth of some miles below the surface of the earth, in which melted lava accumulates; and when water containing the usual mixture of air penetrates into these, the steam thus generated may press upon the lava and force it up the duct of a volcano, in the same manner as a column of water is driven up the pipe of a Geyser. In other cases we may suppose a continuous column of liquid lava mixed with *red hot water*, (for water may exist in that state, as Professor Bunsen reminds us, under pressure,) and this column may have a temperature regularly increasing downwards. A disturbance of equilibrium may first bring on an eruption near the surface, by the expansion and conversion into gas of entangled water and other constituents of what we call lava, so as to occasion a diminution of pressure. More steam would then be liberated, carrying up with it jets of melted rock, which being hurled up into the air may fall in showers of ashes on the surrounding country, and at length, by the arrival of lava and water more and more heated at the orifice of the duct or the crater of the volcano, expansive power may be acquired sufficient to expel a massive current of lava. After the eruption has ceased, a period of tranquillity succeeds, during which fresh accessions of heat are communicated from below, and additional masses of rock fused by degrees, while at the same time atmospheric or sea water is descending from the surface. At length the conditions required for a new outburst are obtained, and another cycle of similar changes is renewed.

Causes of earthquakes — wave-like motion. — I shall now proceed to examine the manner in which the heat of the interior may give rise to earthquakes. One of the most common phenomena attending subterranean movements, is the undulatory motion of the ground. And this, says Michell, will seem less extraordinary, if we call to mind the extreme elasticity of the earth and the compressibility of even the most solid materials. Large districts, he suggests, may rest on fluid lava; and, when this is disturbed, its motions may be propagated through the incumbent rocks. He also adds the following ingenious speculation: — "As a small quantity of vapour almost instantly generated at some considerable depth below the surface of the earth will produce a vibratory motion, so a very large quantity (whether it be generated almost instantly, or in any small portion of time) will produce a wave-like motion. The manner in which this wave-like motion will be propagated may, in some measure, be represented by the following experiment:—Suppose a large cloth, or carpet (spread upon a floor), to be raised at one edge, and then suddenly brought down again to the floor; the air under it, being by this means propelled, will pass along till it escapes at the opposite side, raising the cloth in a wave all the way as it goes. In like manner, a large quantity of vapour may be conceived to raise the earth in a wave, as it passes along between the strata, which it may easily separate in a horizontal direction, there being little or no cohesion between one stratum and another. The part of the earth that is first raised being bent from its natural form, will endeavour to restore itself by its elasticity; and the parts next to it being to have their weight supported by the vapour, which will insinuate itself under them, will be raised in their turn, till it either finds some vent, or is again condensed by the cold into water, and by that means prevented from proceeding any farther."* In a memoir published in 1843, on the structure of the Appalachian chain, by the Professors Rogers†, the following hypothesis is proposed as "simpler and more in accordance with dynamical considerations, and the recorded observations on earthquakes."—"In place," say they, "of supposing it possible for a body of vapour or gaseous matter to pass horizontally between the strata, or even between the crust and the fluid lava upon which it floats, and with which it must be closely entangled, we are inclined to attribute the movement to an *actual pulsation*, engendered in the *molten matter itself*, by a linear disruption under enormous tension, giving vent explosively to elastic vapours, escaping either to the surface, or into cavernous spaces beneath. According to this supposition, the movement of the subterranean vapours would be *towards*, and not from, the disrupted belt, and the oscillation of the crust would originate in the tremendous and sudden disturbance of the previous pressure on the surface of the lava mass below, brought about by the instantaneous and violent rending of the overlying strata."

---

* Liebig's Annalen der Chimie und Pharmacie, translated in "Reports and Memoirs" of Cavendish Soc. London, 1848.

This theory requires us to admit that the crust of the earth is so flexible, that it can assume the form and follow the motion of an undulation in the fluid below. Even if we grant this, says Mr. Mallet, another more serious objection presents itself, viz. the great velocity attributed to the transit of the wave in the subterranean sea of lava. We are called upon to admit that the speed of the wave below equals that of the true earthquake shock at the surface, which is so immense, that it is not inferior to the velocity of sound in the same solids. But the undulation in the fluid below must follow the laws of a tidal wave, or of the great sea-wave already spoken of. "Its velocity, like that of the tidal wave of our seas, will be a function of its length and of the depth of the fluid, diminished in this case by certain considerations as to the density and degree of viscidity of the liquid; and, although it would be at present impossible, for want of data, to calculate the exact velocity with which this subterranean lava-wave could move, it may be certainly affirmed that its velocity would be immeasurably short of the observed or theoretic velocity of the great earth-wave, or true shock, in earthquakes."*

---

* On the Cause and Phenomena of Earthquakes, Phil. Trans. vol. li. sect. 58. 1760.

† Trans. of Assoc. of American Geol. 1840—1842, p. 520.

Liquid gases.—The rending and upheaving of continental masses are operations which are not difficult to explain, when we are once convinced that heat, of sufficient power, not only to melt but to reduce to a gaseous form a great variety of substances, is accumulated in certain parts of the interior. We see that elastic fluids are capable of projecting solid masses to immense heights in the air; and the volcano of Cotopaxi has been known to throw out, to the distance of eight or nine miles, a mass of rock about one hundred cubic yards in volume. When we observe these aëriform fluids rushing out from particular vents for months, or even years, continuously, what power may we not expect them to exert in other places, where they happen to be confined under an enormous weight of rock?

The experiments of Faraday and others have shown, within the last twelve years, that many of the gases, including all those which are most copiously disengaged from volcanic vents, as the carbonic, sulphurous, and muriatic acids, may be condensed into liquids by pressure. At temperatures of from 30° to 50° F., the pressure required for this purpose varies from fifteen to fifty atmospheres; and this amount of pressure we may regard as very insignificant in the operations of nature. A column of Vesuvian lava that would reach from the lip of the crater to the level of the sea, must be equal to about three hundred atmospheres; so that, at depths which may be termed moderate in the interior of the crust of the earth, the gases may be condensed into liquids, even at very high temperatures. The method employed to reduce some of these gases to a liquid state is, to confine the materials, from the mutual action of which they are evolved, in tubes hermetically sealed, so that the accumulated pressure of the vapour, as it rises and expands, may force some part of it to assume the liquid state. A similar process may, and indeed must, frequently take place in subterranean caverns and fissures, or even in the pores and cells of many rocks; by which means, a much greater store of expansive power may be *packed* into a small space than could happen if these vapours had not the property of becoming liquid. For, although the gas occupies much less room in a liquid state, yet it exerts exactly the same pressure upon the sides of the containing cavity as if it remained in the form of vapour.

If a tube, whether of glass or other materials, filled with condensed gas, have its temperature slightly raised, it will often burst; for a slight increment of heat causes the elasticity of the gas to increase in a very high ratio. We have only to suppose certain rocks, permeated by these liquid gases (as porous strata are sometimes filled with water), to have their temperature raised some hundred degrees, and we obtain a power capable of lifting superincumbent masses of almost any conceivable thickness; while, if the depth at which the gas is confined be great, there is no reason to suppose that any other appearances would be witnessed by the inhabitants of the surface than vibratory movements and rents, from which no vapour might escape. In making their way through fissures a very few miles only in length, or in forcing a passage through soft yielding strata, the vapours may be cooled and absorbed by water. For water has a strong affinity to several of the gases, and will absorb large quantities, with a very slight increase of volume. In this manner, the heat or the volume of springs may be augmented, and their mineral properties made to vary.

---

* Mallet, p. 39.

Connexion between the state of the atmosphere and earthquakes.— The inhabitants of Stromboli, who are mostly fishermen, are said to make use of that volcano as a weather-glass, the eruptions being comparatively feeble when the sky is serene, but increasing in turbulence during tempestuous weather, so that in winter the island often seems to shake from its foundations. Mr. P. Scrope, after calling attention to these and other analogous facts, first started the idea (as long ago as the year 1825) that the diminished pressure of the atmosphere, the concomitant of stormy weather, may modify the intensity of the volcanic action. He suggests that where liquid lava communicates with the surface, as in the crater of Stromboli, it may rise or fall in the vent on the same principle as mercury in a barometer; because the ebullition or expansive power of the steam contained in the lava would be checked by every increase, and augmented by every diminution of weight. In like manner, if a bed of liquid lava be confined at an immense depth below the surface, its expansive force may be counteracted partly by the weight of the incumbent rocks, and also in part by atmospheric pressure acting contemporaneously on a vast superficial area. In that case, if the upheaving force increase gradually in energy, it will at length be restrained by only the slightest degree of superiority in the antagonist or repressive power, and then the equilibrium may be suddenly destroyed by any cause, such as an ascending draught of air, which is capable of depressing the barometer. In this manner we may account for the remarkable coincidence so frequently observed between the state of the weather and subterranean commotions, although it must be admitted that earthquakes and volcanic eruptions re-act in their turn upon the atmosphere, so that disturbances of the latter are generally the consequences rather than the forerunners of volcanic disturbances.*

From an elaborate catalogue of the earthquakes experienced in Europe and Syria during the last fifteen centuries, M. Alexis Perrey has deduced the conclusion that the number which happen in the winter season preponderates over those which occur in any one of the other seasons of the year, there being, however, some exceptions to this rule, as in the Pyrenees. Curious and valuable as are these data, M. d'Archiac justly remarks, in commenting upon them, that they are not as yet sufficiently extensive or accordant in different regions, to entitle us to deduce any general conclusions from them respecting the laws of subterranean movements throughout the globe.*

---

* Scrope on Volcanos, pp. 58—60.

Permanent elevation and subsidence. — It is easy to conceive that the shattered rocks may assume an arched form during a convulsion, so that the country above may remain permanently upheaved. In other cases gas may drive before it masses of liquid lava, which may thus be injected into newly opened fissures. The gas having then obtained more room, by the forcing up of the incumbent rocks, may remain at rest; while the lava congealing in the rents, may afford a solid foundation for the newly raised district.

Experiments have recently been made in America, by Colonel Totten, to ascertain the ratio according to which some of the stones commonly used in architecture expand with given increments of heat.† It was found impossible, in a country where the annual variation of temperature was more than 90° F., to make a coping of stones, five feet in length, in which the joints should fit so tightly as not to admit water between the stone and the cement; the annual contraction and expansion of the stones causing, at the junctions, small crevices, the width of which varied with the nature of the rock. It was ascertained that fine-grained granite expanded with 1° F. at the rate of ·000004825; while crystalline marble ·000005668; and red sandstone ·000009532, or about twice as much as granite.

Now, according to this law of expansion, a mass of sandstone, a mile in thickness, which should have its temperature raised 200° F., would lift a super-imposed layer of rock to the height of ten feet above its former level. But, suppose a part of the earth's crust, one hundred miles in thickness and equally expansive, to have its temperature raised 600° or 800°, this might produce an elevation of between two and three thousand feet. The cooling of the same mass might afterwards cause the overlying rocks to sink down again and resume their original position. By such agency we might explain the gradual rise of Scandinavia or the subsidence of Greenland, if this last phenomenon should also be established as a fact on farther inquiry.

It is also possible that as the clay in Wedgwood's pyrometer contracts, by giving off its water, and then, by incipient vitrification; so, large masses of argillaceous strata in the earth's interior may shrink, when subjected to heat and chemical changes, and allow the incumbent rocks to subside gradually.

Moreover, if we suppose that lava cooling slowly at great depths may be converted into various granitic rocks, we obtain another source of depression; for, according to the experiments of Deville and the calculations of Bischoff, the contraction of granite when passing from a melted or plastic to a solid and crystalline state must be more than ten per cent.* The sudden subsidence of land may also be occasioned by subterranean caverns giving way, when gases are condensed, or when they escape through newly-formed crevices. The subtraction, moreover, of matter from certain parts of the interior, by the flowing of lava and of mineral springs, must, in the course of ages, cause vacuities below, so that the undermined surface may at length fall in.

---

* Archiac, Hist. des Progrés de la Géol. 1847, vol. i. pp. 605—610.

† Silliman's American Journ. vol. xxii. p. 136. The application of these results to the theory of earthquakes was first suggested to me by Mr. Babbage.

The balance of dry land, how preserved.—In the present state of our knowledge, we cannot pretend to estimate the average number of earthquakes which may happen in the course of a single year. As the area of the ocean is nearly three times that of the land, it is probable that about three submarine earthquakes may occur for one exclusively continental; and when we consider the great frequency of slight movements in certain districts, we can hardly suppose that a day, if, indeed, an hour, ever passes without one or more shocks being experienced in some part of the globe. We have also seen that in Sweden, and other countries, changes in the relative level of sea and land may take place without commotion, and these perhaps produce the most important geographical and geological changes; for the position of land may be altered to a greater amount by an elevation or depression of one inch over a vast area, than by the sinking of a more limited tract, such as the forest of Aripao, to the depth of many fathoms at once.†

It must be evident, from the historical details above given, that the force of subterranean movement, whether intermittent or continuous, whether with or without disturbance, does not operate at random, but is developed in certain regions only; and although the alterations produced during the time required for the occurrence of a few volcanic eruptions may be inconsiderable, we can hardly doubt that, during the ages necessary for the formation of large volcanic cones, composed of thousands of lava currents, shoals might be converted into lofty mountains, and low lands into deep seas.

In a former chapter (p. 198), I have stated that aqueous and igneous agents may be regarded as antagonist forces; the aqueous labouring incessantly to reduce the inequalities of the earth's surface to a level, while the igneous are equally active in renewing the unevenness of the surface. By some geologists it has been thought that the levelling power of running water was opposed rather to the *elevating* force of earthquakes than to their action generally. This opinion is, however, untenable; for the sinking down of the bed of the ocean is one of the means by which the gradual submersion of land is prevented. The depth of the sea cannot be increased at any one point without a universal fall of the waters, nor can any partial deposition of sediment occur without the displacement of a quantity of water of equal volume, which will raise the sea, though in an imperceptible degree, even to the antipodes. The preservation, therefore, of the dry land may sometimes be effected by the subsidence of part of the earth's crust (that part, namely, which is covered by the ocean), and in like manner an upheaving movement must often tend to destroy land; for if it render the bed of the sea more shallow, it will displace a certain quantity of water, and thus tend to submerge low tracts.

---

* Bulletin de la Soc. Géol. 2nd series, vol. iv. p. 1312.

† See p. 468.

Astronomers having proved (see above, p. 129.), that there has been no change in the diameter of the earth during the last two thousand years, we may assume it as probable, that the dimensions of the planet remain uniform. If, then, we inquire in what manner the force of earthquakes must be regulated, in order to restore perpetually the inequalities of the surface which the levelling power of water tends to efface, it will be found, that the amount of depression must exceed that of elevation. It would be otherwise if the action of volcanos and mineral springs were suspended; for then the forcing outwards of the earth's envelope ought to be no more than equal to its sinking in.

To understand this proposition more clearly, it must be borne in mind, that the deposits of rivers and currents probably add as much to the height of lands which are rising, as they take from those which have risen. Suppose a large river to bring down sediment to a part of the ocean two thousand feet deep, and that the depth of this part is gradually reduced by the accumulation of sediment till only a shoal remains, covered by water at high tides; if now an upheaving force should uplift this shoal to the height of 2000 feet, the result would be a mountain 2000 feet high. But had the movement raised the same part of the bottom of the sea before the sediment of the river had filled it up; then, instead of changing a shoal into a mountain 2000 feet high, it would only have converted a deep sea into a shoal.

It appears, then, that the operations of the earthquake are often such as to cause the levelling power of water to counteract itself; and, although the idea may appear paradoxical, we may be sure, wherever we find hills and mountains composed of stratified deposits, that such inequalities of the surface would have had no existence if water, at some former period, had not been labouring to reduce the earth's surface to one level.

But, besides the transfer of matter by running water from the continents to the ocean, there is a constant transportation from below upwards, by mineral springs and volcanic vents. As mountain masses are, in the course of ages, created by the pouring forth of successive streams of lava, so stratified rocks, of great extent, originate from the deposition of carbonate of lime, and other mineral ingredients, with which springs are impregnated. The surface of the land, and portions of the bottom of the sea, being thus raised, the external accessions due to these operations would cause the dimensions of the planet to enlarge continually, if the amount of depression of the earth's crust were no more than equal to the elevation. In order, therefore, that the mean diameter of the earth should remain uniform, and the unevenness of the surface be preserved, it is necessary that the amount of subsidence should be in excess. And such a predominance of depression is far from improbable, on mechanical principles, since every upheaving movement must be expected either to produce caverns in the mass below, or to cause some diminution of its density. Vacuities must, also, arise from the subtraction of the matter poured out from volcanos and mineral springs, or from the contraction of argillaceous masses by subterranean heat; and the foundations having been thus weakened, the earth's crust, shaken and rent by reiterated convulsions must, in the course of time, fall in.

If we embrace these views, important geological consequences will follow ; since, if there be, upon the whole, more subsidence than elevation, the average depth to which former surfaces have sunk beneath their original level must exceed the height which ancient marine strata have attained above the sea. If, for example, marine strata, about the age of our chalk and greensand, have been lifted up in Europe to an extreme height of more than eleven thousand feet, and a mean elevation of some hundreds, we may conclude that certain parts of the surface, which existed when those strata were deposited, have sunk to an extreme depth of *more than* eleven thousand feet below their original level, and to a mean depth of *more than* a few hundreds.

In regard to faults, also, we must infer, according to the hypothesis now proposed, that a greater number have arisen from the sinking down than from the elevation of rocks.

To conclude: it seems to be rendered probable, by the views above explained, that the constant repair of the land, and the subserviency of our planet to the support of terrestrial as well as aquatic species, are secured by the elevating and depressing power of causes acting in the interior of the earth ; which, although so often the source of death and terror to the inhabitants of the globe—visiting in succession every zone, and filling the earth with monuments of ruin and disorder — are nevertheless the agents of a conservative principle above all others essential to the stability of the system.

BOOK III.

CHAPTER XXXIII.

CHANGES OF THE ORGANIC WORLD NOW IN PROGRESS.

Division of the subject—Examination of the question, Whether species have a real existence in nature?—Importance of this question in geology—Sketch of Lamarck's arguments in favour of the transmutation of species, and his conjectures respecting the origin of existing animals and plants—His theory of the transformation of the orang-outang into the human species.

The last book, from chapters fourteen to thirty-three inclusive, was occupied with the consideration of the changes brought about on the earth's surface, within the period of human observation, by inorganic agents; such, for example, as rivers, marine currents, volcanos, and earthquakes. But there is another class of phenomena relating to the organic world, which have an equal claim on our attention, if we desire to obtain possession of all the preparatory knowledge respecting the existing course of nature, which may be available in the interpretation of geological monuments. It appeared from our preliminary sketch of the progress of the science, that the most lively interest was excited among its earlier cultivators, by the discovery of the remains of animals and plants in the interior of mountains frequently remote from the sea. Much controversy arose respecting the nature of these remains, the causes which may have brought them into so singular a position, and the want of a specific agreement between them and known animals and plants. To qualify ourselves to form just views on these curious questions, we must first study the present condition of the animate creation on the globe.

This branch of our inquiry naturally divides itself into two parts: first, we may examine the vicissitudes to which species are subject; secondly, the processes by which certain individuals of these species occasionally become fossil. The first of these divisions will lead us, among other topics, to inquire, first, whether species have a real and permanent existence in nature? or whether they are capable, as some naturalists pretend, of being indefinitely modified in the course of a long series of generations? Secondly, whether, if species have a real existence, the individuals composing them have been derived originally from many similar stocks, or each from one only, the descendants of which have spread themselves gradually from a particular point over the habitable lands and waters? Thirdly, how far the duration of each species of animal and plant is limited by its dependence on certain fluctuating and temporary conditions in the state of the animate and inanimate world? Fourthly, whether there be proofs of the successive extermination of species in the ordinary course of nature, and whether there be any reason for conjecturing that new animals and plants are created from time to time, to supply their place?

Whether species have a real existence in nature.—Before we can advance a step in our proposed inquiry, we must be able to define precisely the meaning which we attach to the term species. This is even more necessary in geology than in the ordinary studies of the naturalist; for they who deny that such a thing as a species exists, concede nevertheless that a botanist or zoologist may reason as if the specific character were constant, because they confine their observations to a brief period of time. Just as the geographer, in constructing his maps from century to century, may proceed as if the apparent places of the fixed stars remained absolutely the same, and as if no alteration were brought about by the precession of the equinoxes; so, it is said, in the organic world, the stability of a species may be taken as absolute, if we do not extend our views beyond the narrow period of human history; but let a sufficient number of centuries elapse, to allow of important revolutions in climate, physical geography, and other circumstances, and the characters, say they, of the descendants of common parents may deviate indefinitely from their original type. (1).

Now, if these doctrines be tenable, we are at once presented with a principle of incessant change in the organic world; and no degree of dissimilarity in the plants and animals which may formerly have existed, and are found fossil, would entitle us to conclude that they may not have been the prototypes and progenitors of the species now living. Accordingly M. Geoffroy St. Hilaire has declared his opinion, that there has been an uninterrupted succession in the animal kingdom, effected by means of generation, from the earliest ages of the world up to the present day, and that the ancient animals whose remains have been preserved in the strata, however different, may nevertheless have been the ancestors of those now in being. This notion is not very generally received, but we are not warranted in assuming the contrary, without fully explaining the data and reasoning by which it may be refuted.

I shall begin by stating as concisely as possible all the facts and ingenious arguments by which the theory has been supported; and for this purpose I cannot do better than offer the reader a rapid sketch of Lamarck's statement of the proofs which he regards as confirmatory of the doctrine, and which he has derived partly from the works of his predecessors and in part from original investigations.

His proofs and inferences will be best considered in the order in which they appear to have influenced his mind, and I shall then point out some of the results to which he was led while boldly following out his principles to their legitimate consequences.

Lamarck's arguments in favour of the transmutation of species.—The name of species, observes Lamarck, has been usually applied to "every collection of similar individuals produced by other individuals like themselves."* This definition, he admits, is correct; because every living individual bears a very close resemblance to those from which it springs. But this is not all which is usually implied by the term species; for the majority of naturalists agree with Linnæus in supposing that all the individuals propagated from one stock have certain distinguishing characters in common, which will never vary, and which have remained the same since the creation of each species.

In order to shake this opinion, Lamarck enters upon the following line of argument:—The more we advance in the knowledge of the different organized bodies which cover the surface of the globe, the more our embarrassment increases, to determine what ought to be regarded as a species, and still more how to limit and distinguish genera. In proportion as our collections are enriched, we see almost every void filled up, and all our lines of separation effaced! we are reduced to arbitrary determinations, and are sometimes fain to seize upon the slight differences of mere varieties, in order to form characters for what we choose to call a species; and sometimes we are induced to pronounce individuals but slightly differing, and which others regard as true species, to be varieties.

The greater the abundance of natural objects assembled together, the more do we discover proofs that every thing passes by insensible shades into something else; that even the more remarkable differences are evanescent, and that nature has, for the most part, left us nothing at our disposal for establishing distinctions, save trifling, and, in some respects, puerile particularities.

We find that many genera amongst animals and plants are of such an extent, in consequence of the number of species referred to them, that the study and determination of these last has become almost impracticable. When the species are arranged in a series, and placed near to each other, with due regard to their natural affinities, they each differ in so minute a degree from those next adjoining, that they almost melt into each other, and are in a manner confounded together. If we see isolated species, we may presume the absence of some more closely connected, and which have not yet been discovered. Already are there genera, and even entire orders—nay, whole classes, which present an approximation to the state of things here indicated.

If, when species have been thus placed in a regular series, we select one, and then, making a leap over several intermediate ones, we take a second, at some distance from the first, these two will, on comparison, be seen to be very dissimilar; and it is in this manner that every naturalist begins to study the objects which are at his own door. He then finds it an easy task to establish generic and specific distinctions; and it is only when his experience is enlarged, and when he has made himself master of the intermediate links, that his difficulties and ambiguities begin. But while we are thus compelled to resort to trifling and minute characters in our attempt to separate species, we find a striking disparity between individuals which we know to have descended from a common stock; and these newly acquired peculiarities are regularly transmitted from one generation to another, constituting what are called *races*.

---

* Phil. Zool. tom. i. p. 54.

From a great number of facts, continues the author, we learn that in proportion as the individuals of one of our species change their situation, climate, and manner of living, they change also, by little and little, the consistence and proportions of their parts, their form, their faculties, and even their organisation, in such a manner that every thing in them comes at last to participate in the mutations to which they have been exposed. Even in the same climate, a great difference of situation and exposure causes individuals to vary; but if these individuals continue to live and to be reproduced under the same difference of circumstances, distinctions are brought about in them which become in some degree essential to their existence. In a word, at the end of many successive generations, these individuals, which originally belonged to another species, are transformed into a new and distinct species.*

Thus, for example, if the seeds of a grass, or any other plant which grows naturally in a moist meadow, be accidentally transported, first to the slope of some neighbouring hill, where the soil, although at a greater elevation, is damp enough to allow the plant to live; and if, after having lived there, and having been several times regenerated, it reaches by degrees the drier and almost arid soil of a mountain declivity, it will then, if it succeeds in growing, and perpetuates itself for a series of generations, be so changed that botanists who meet with it will regard it as a particular species.† The unfavourable climate in this case, deficiency of nourishment, exposure to the winds, and other causes, give rise to a stunted and dwarfish race, with some organ more developed than others, and having proportions often quite peculiar.

What nature brings about in a great lapse of time, we occasion suddenly by changing the circumstances in which a species has been accustomed to live. All are aware that vegetables taken from their birth-place, and cultivated in gardens, undergo changes which render them no longer recognizable as the same plants. Many which were naturally hairy become smooth, or nearly so; a great number of such as were creepers and trailed along the ground, rear their stalks and grow erect. Others lose their thorns or asperities; others, again, from the ligneous state which their stem possessed in hot climates, where they were indigenous, pass to the herbaceous; and, among them, some which were perennials become mere annuals. So well do botanists know the effects of such changes of circumstances, that they are averse to describe species from garden specimens, unless they are sure that they have been cultivated for a very short period.

"Is not the cultivated wheat" (*Triticum sativum*), asks Lamarck.

---

* Phil. Zool. tom. i. p. 62.

† Ibid.

"a vegetable brought by man into the state in which we now see it? Let any one tell me in what country a similar plant grows wild, unless where it has escaped from cultivated fields? Where do we find in nature our cabbages, lettuces, and other culinary vegetables, in the state in which they appear in our gardens? Is it not the same in regard to a great quantity of animals which domesticity has changed or considerably modified?"* Our domestic fowls and pigeons are unlike any wild birds. Our domestic ducks and geese have lost the faculty of raising themselves into the higher regions of the air, and crossing extensive countries in their flight, like the wild ducks and wild geese from which they were originally derived. A bird which we breed in a cage cannot, when restored to liberty, fly like others of the same species which have been always free. This small alteration of circumstances, however, has only diminished the power of flight, without modifying the form of any part of the wings. But when individuals of the same race are retained in captivity during a considerable length of time, the form even of their parts is gradually made to differ, especially if climate, nourishment, and other circumstances be also altered.

The numerous races of dogs which we have produced by domesticity are nowhere to be found in a wild state. In nature we should seek in vain for mastiffs, harriers, spaniels, greyhounds, and other races, between which the differences are sometimes so great that they would be readily admitted as specific between wild animals; "yet all these have sprung originally from a single race, at first approaching very near to a wolf, if, indeed, the wolf be not the true type which at some period or other was domesticated by man."

Although important changes in the nature of the places which they inhabit modify the organization of animals as well as vegetables; yet the former, says Lamarck, require more time to complete a considerable degree of transmutation; and, consequently, we are less sensible of such occurrences. Next to a diversity of the medium in which animals or plants may live, the circumstances which have most influence in modifying their organs are differences in exposure, climate, the nature of the soil, and other local particulars. These circumstances are as varied as are the characters of the species, and, like them, pass by insensible shades into each other, there being every intermediate gradation between the opposite extremes. But each locality remains for a very long time the same, and is altered so slowly that we can only become conscious of the reality of the change by consulting geological monuments, by which we learn that the order of things which now reigns in each place has not always prevailed, and by inference anticipate that it will not always continue the same.†

Every considerable alteration in the local circumstances in which each race of animals exists causes a change in their wants, and these new wants excite them to new actions and habits. These actions require the more frequent employment of some parts before but slightly exercised, and then greater development follows as a consequence of their more frequent use. Other organs no longer in use are impoverished and diminished in size, nay, are sometimes entirely annihilated, while in their place new parts are insensibly produced for the discharge of new functions.*

---

* Phil. Zool. tom. i. p. 227.

† Ibid. p. 232.

I must here interrupt the author's argument, by observing, that no positive fact is cited to exemplify the substitution of some *entirely new* sense, faculty, or organ, in the room of some other suppressed as useless. All the instances adduced go only to prove that the dimensions and strength of members and the perfection of certain attributes may, in a long succession of generations, be lessened and enfeebled by disuse; or, on the contrary, be matured and augmented by active exertion; just as we know that the power of scent is feeble in the greyhound, while its swiftness of pace and its acuteness of sight are remarkable—that the harrier and stag-hound, on the contrary, are comparatively slow in their movements, but excel in the sense of smelling.

It was necessary to point out to the reader this important chasm in the chain of evidence, because he might otherwise imagine that I had merely omitted the illustrations for the sake of brevity; but the plain truth is, that there were no examples to be found; and when Lamarck talks "of the efforts of internal sentiment," "the influence of subtle fluids," and "acts of organization," as causes whereby animals and plants may acquire *new organs*, he substitutes names for things; and, with a disregard to the strict rules of induction, resorts to fictions, as ideal as the "plastic virtue," and other phantoms of the geologists of the middle ages.

It is evident that, if some well-authenticated facts could have been adduced to establish one complete step in the process of transformation, such as the appearance, in individuals descending from a common stock, of a sense or organ entirely new, and a complete disappearance of some other enjoyed by their progenitors, time alone might then be supposed sufficient to bring about any amount of metamorphosis. The gratuitous assumption, therefore, of a point so vital to the theory of transmutation, was unpardonable on the part of its advocate.

But to proceed with the system: it being assumed as an undoubted fact, that a change of external circumstances may cause one organ to become entirely obsolete, and a new one to be developed, such as never before belonged to the species, the following proposition is announced, which, however staggering and absurd it may seem, is logically deduced from the assumed premises. It is not the organs, or, in other words, the nature and form of the parts of the body of an animal, which have given rise to its habits, and its particular faculties; but, on the contrary, its habits, its manner of living, and those of its progenitors, have in the course of time determined the form of its body, the number and condition of its organs—in short, the faculties which it enjoys. Thus otters, beavers, waterfowl, turtles, and frogs, were not made web-footed in order that they might swim; but their wants having attracted them to the water in search of prey, they stretched out the toes of their feet to strike the water and move rapidly along its surface. By the repeated stretching of their toes, the skin which united them at the base acquired a habit of extension, until, in the course of time, the broad membranes which now connect their extremities were formed.

---

* Phil. Zool. tom. i. p. 234.

In like manner, the antelope and the gazelle were not endowed with light agile forms, in order that they might escape by flight from carnivorous animals; but, having been exposed to the danger of being devoured by lions, tigers, and other beasts of prey, they were compelled to exert themselves in running with great celerity; a habit which, in the course of many generations, gave rise to the peculiar slenderness of their legs, and the agility and elegance of their forms.

The camelopard was not gifted with a long flexible neck because it was destined to live in the interior of Africa, where the soil was arid and devoid of herbage; but, being reduced by the nature of that country to support itself on the foliage of lofty trees, it contracted a habit of stretching itself up to reach the high boughs, until its neck became so elongated that it could raise its head to the height of twenty feet above the ground.

Another line of argument is then entered upon, in farther corroboration of the instability of species. In order, it is said, that individuals should perpetuate themselves unaltered by generation, those belonging to one species ought never to ally themselves to those of another; but such sexual unions do take place, both among plants and animals; and although the offspring of such irregular connections are usually sterile, yet such is not always the case. Hybrids have sometimes proved prolific, where the disparity between the species was not too great; and by this means alone, says Lamarck, varieties may gradually be created by near alliances, which would become races, and in the course of time would constitute what we term species.*

But if the soundness of all these arguments and inferences be admitted, we are next to inquire, what were the original types of form, organization, and instinct, from which the diversities of character, as now exhibited by animals and plants, have been derived? We know that individuals which are mere varieties of the same species would, if their pedigree could be traced back far enough, terminate in a single stock; so, according to the train of reasoning before described, the species of a genus, and even the genera of a great family, must have had a common point of departure. What, then, was the single stem from which so many varieties of form have ramified? Were there many of these, or are we to refer the origin of the whole animate creation, as the Egyptian priests did that of the universe, to a single egg?

---

* Phil. Zool. p. 64.

In the absence of any positive data for framing a theory on so obscure a subject, the following considerations were deemed of importance to guide conjecture.

In the first place, if we examine the whole series of known animals, from one extremity to the other, when they are arranged in the order of their natural relations, we find that we may pass progressively, or, at least, with very few interruptions, from beings of more simple to those of a more compound structure; and, in proportion as the complexity of their organization increases, the number and dignity of their faculties increase also. Among plants, a similar approximation to a graduated scale of being is apparent. Secondly, it appears, from geological observations, that plants and animals of more simple organization existed on the globe before the appearance of those of more compound structure, and the latter were successively formed at more modern periods; each new race being more fully developed than the most perfect of the preceding era.

Of the truth of the last-mentioned geological theory, Lamarck seems to have been fully persuaded; and he also shows that he was deeply impressed with a belief prevalent amongst the older naturalists, that the primeval ocean invested the whole planet long after it became the habitation of living beings; and thus he was inclined to assert the priority of the types of marine animals to those of the terrestrial, so as to fancy, for example, that the testacea of the ocean existed first, until some of them, by gradual evolution, were *improved* into those inhabiting the land.

These speculative views had already been, in a great degree, anticipated by Demaillet in his Telliamed, and by several modern writers; so that the tables were completely turned on the philosophers of antiquity, with whom it was a received maxim, that created things were always most perfect when they came first from the hands of their Maker; and that there was a tendency to progressive deterioration in sublunary things when left to themselves—

> ——— omnia fatis
> In pejus ruere, ac retrò sublapsa referri.

So deeply was the faith of the ancient schools of philosophy imbued with this doctrine, that, to check this universal proneness to degeneracy, nothing less than the re-intervention of the Deity was thought adequate; and it was held, that thereby the order, excellence, and pristine energy of the moral and physical world had been repeatedly restored.

But when the possibility of the indefinite modification of individuals descending from common parents was once assumed, as also the geological inference respecting the progressive development of organic life, it was natural that the ancient dogma should be rejected, or rather reversed, and that the most simple and imperfect forms and faculties should be conceived to have been the originals whence all others were developed. Accordingly, in conformity to these views, inert matter was supposed to have been first endowed with life; until, in the course of ages, sensation was superadded to mere vitality: sight, hearing, and the other senses were afterwards acquired; then instinct and the mental faculties; until, finally, by virtue of the tendency of things to *progressive improvement*, the irrational was developed into the rational.

The reader, however, will immediately perceive that when all the higher orders of plants and animals were thus supposed to be comparatively modern, and to have been derived in a long series of generations from those of more simple conformation, some farther hypothesis became indispensable, in order to explain why, after an indefinite lapse of ages, there were still so many beings of the simplest structure. Why have the majority of existing creatures remained stationary throughout this long succession of epochs, while others have made such prodigious advances? Why are there such multitudes of infusoria and polyps, or of confervæ and other cryptogamic plants? Why, moreover, has the process of development acted with such unequal and irregular force on those classes of beings which have been greatly perfected, so that there are wide chasms in the series; gaps so enormous, that Lamarck fairly admits we can never expect to fill them up by future discoveries?

The following hypothesis was provided to meet these objections. Nature, we are told, is not an intelligence, nor the Deity; but a delegated power—a mere instrument—a piece of mechanism acting by necessity—an order of things constituted by the Supreme Being, and subject to laws which are the expressions of his will. This Nature is *obliged* to proceed gradually in all her operations; she cannot produce animals and plants of all classes at once, but must always begin by the formation of the most simple kinds, and out of them elaborate the more compound, adding to them, successively, different systems of organs, and multiplying more and more their number and energy.

This Nature is daily engaged in the formation of the elementary rudiments of animal and vegetable existence, which correspond to what the ancients termed *spontaneous generation*. She is always beginning anew, day by day, the work of creation, by forming monads, or "rough draughts" (ébauches), which are the only living things she gives birth to *directly*.

There are distinct primary rudiments of plants and animals, and *probably* of each of the great divisions of the animal and vegetable kingdoms.[*] These are gradually developed into the higher and more perfect classes by the slow but unceasing agency of two influential principles: first, *the tendency to progressive advancement* in organization, accompanied by greater dignity in instinct, intelligence, &c.; secondly, *the force of external circumstances*, or of variations in the physical condition of the earth, or the mutual relations of plants and animals. For, as species spread themselves gradually over the globe, they are exposed from time to time to variations in climate, and to changes in the quantity and quality of their food; they meet with new plants and animals which assist or retard their development, by supplying them with nutriment, or destroying their foes. The nature, also, of each locality, is in itself fluctuating; so that, even if the relation of other animals and plants were invariable, the habits and organization of species would be modified by the influence of local revolutions.

---

[*] Animaux sans Vert. tom. i. p. 56. Introduction.

Now, if the first of these principles, *the tendency to progressive development*, were left to exert itself with perfect freedom, it would give rise, says Lamarck, in the course of ages, to a graduated scale of being, where the most insensible transition might be traced from the simplest to the most compound structure, from the humblest to the most exalted degree of intelligence. But, in consequence of the perpetual interference of the *external causes* before mentioned, this regular order is greatly interfered with, and an approximation only to such a state of things is exhibited by the animate creation, the progress of some races being retarded by unfavourable, and that of others accelerated by favourable, combinations of circumstances. Hence, all kinds of anomalies interrupt the continuity of the plan; and chasms, into which whole genera or families might be inserted, are seen to separate the nearest existing portions of the series.

Lamarck's theory of the transformation of the orang-outang into the human species. — Such is the machinery of the Lamarckian system; but the reader will hardly, perhaps, be able to form a perfect conception of so complicated a piece of mechanism, unless it is exhibited in motion, so that we may see in what manner it can work out, under the author's guidance, all the extraordinary effects which we behold in the present state of the animate creation. I have only space for exhibiting a small part of the entire process by which a complete metamorphosis is achieved, and shall therefore omit the mode by which, after a countless succession of generations, a small gelatinous body is transformed into an oak or an ape; passing on at once to the last grand step in the progressive scheme, by which the orang-outang, having been already evolved out of a monad, is made slowly to attain the attributes and dignity of man.

[illegible]

One of the races of quadrumanous animals which had reached the highest state of perfection, lost, by constraint of circumstances (concerning the exact nature of which tradition is unfortunately silent), the habit of climbing trees, and of hanging on by grasping the boughs with their feet as with hands. The individuals of this race being obliged, for a long series of generations, to use their feet exclusively for walking, and ceasing to employ their hands as feet, were transformed into bimanous animals, and what before were thumbs became mere toes, no separation being required when their feet were used solely for walking. Having acquired a habit of holding themselves upright, their legs and feet assumed, insensibly, a conformation fitted to support them in an erect attitude, till at last these animals could no longer go on all-fours without much inconvenience.

The Angola orang (*Simia troglodytes*, Linn.) is the most perfect of animals; much more so than the Indian orang (*Simia Satyrus*), which has been called the orang-outang, although *both* are *very inferior* to man in corporeal powers and intelligence. These animals frequently hold themselves upright; but their organization has *not yet* been sufficiently modified to sustain them habitually in this attitude, so that the standing posture is very uneasy to them. When the Indian orang is compelled to take flight from pressing danger, he immediately falls down upon all-fours, showing clearly that this was the original position of the animal. Even in man, whose organization, in the course of a long series of generations, has advanced so much farther, the upright posture is fatiguing, and can be supported only for a limited time, and by aid of the contraction of many muscles. If the vertebral column formed the axis of the human body, and supported the head and all the other parts in equilibrium, then might the upright position be a state of repose: but, as the human head does not articulate in the centre of gravity, as the chest, belly, and other parts press almost entirely forward with their whole weight, and as the vertebral column reposes upon an oblique base, a watchful activity is required to prevent the body from falling. Children who have large heads and prominent bellies can hardly walk at the end even of two years; and their frequent tumbles indicate the natural tendency in man to resume the quadrupedal state.

Now, when so much progress had been made by the quadrumanous animals before mentioned, that they could hold themselves habitually in an erect attitude, and were accustomed to a wide range of vision, and ceased to use their jaws for fighting and tearing, or for clipping herbs for food, their snout became gradually shorter, their incisor teeth became vertical, and the facial angle grew more open.

Among other ideas which the natural *tendency to perfection* engendered, the desire of ruling suggested itself, and this race succeeded at length in getting the better of the other animals, and made themselves masters of all those spots on the surface of the globe which best suited them. They drove out the animals which approached nearest them in organization and intelligence, and which were in a condition to dispute with them the good things of this world, forcing them to take refuge in deserts, woods, and wildernesses, where their multiplication was checked, and the progressive development of their faculties retarded; while, in the meantime, the dominant race spread itself in every direction, and lived in large companies, where new wants were successively created, exciting them to industry, and gradually perfecting their means and faculties.

In the supremacy and increased intelligence acquired by the ruling race, we see an illustration of the natural tendency of the organic world to grow more perfect; and, in their influence in repressing the advance of others, an example of one of those disturbing causes before enumerated, that *force of external circumstances* which causes such wide chasms in the regular series of animated being.

When the individuals of the dominant race became very numerous, their ideas greatly increased in number, and they felt the necessity of communicating them to each other, and of augmenting and varying the signs proper for the communication of ideas. Meanwhile the inferior quadrumanous animals, although most of them were gregarious, acquired no new ideas, being persecuted and restless in the deserts, and obliged to fly and conceal themselves, so that they conceived no new wants. Such ideas as they already had remained unaltered, and they could dispense with the communication of the greater part of these. To make themselves, therefore, understood by their fellows, required merely a few movements of the body or limbs — whistling, and the uttering of certain cries varied by the inflexions of the voice.

On the contrary, the individuals of the ascendant race, animated with a desire of interchanging their ideas, which became more and more numerous, were prompted to multiply the means of communication, and were no longer satisfied with mere pantomimic signs, nor even with all the possible inflexions of the voice, but made continual efforts to acquire the power of uttering articulate sounds, employing a few at first, but afterwards varying and perfecting them according to the increase of their wants. The habitual exercise of their throat, tongue, and lips, insensibly modified the conformation of these organs, until they became fitted for the faculty of speech.*

In effecting this mighty change, "the exigencies of the individuals were the sole agents; they gave rise to efforts, and the organs proper for articulating sounds were developed by their habitual employment." Hence, in this peculiar race, the origin of the admirable faculty of speech; hence also the diversity of languages, since the distance of places where the individuals composing the race established themselves soon favoured the corruption of conventional signs.†

In conclusion, it may be proper to observe that the above sketch of the Lamarckian theory is no exaggerated picture, and those passages which have probably excited the greatest surprise in the mind of the reader are literal translations from the original.

---

* Lamarck's Phil. Zool. tom. i. p. 356.

† Ibid. p. 357.

CHAPTER XXXIV.

TRANSMUTATION OF SPECIES—*continued.*

Recapitulation of the arguments in favour of the theory of transmutation of species—Their insufficiency—Causes of difficulty in discriminating species—Some varieties possibly more distinct than certain individuals of distinct species—Variability in a species consistent with a belief that the limits of deviation are fixed—No facts of transmutation authenticated—Varieties of the Dog—the Dog and Wolf distinct species—Mummies of various animals from Egypt identical in character with living individuals—Seeds and plants from the Egyptian tombs—Modifications produced in plants by agriculture and gardening.

The theory of the transmutation of species, considered in the last chapter, has met with some degree of favour from many naturalists, from their desire to dispense, as far as possible, with the repeated intervention of a First Cause, as often as geological monuments attest the successive appearance of new races of animals and plants, and the extinction of those pre-existing. But, independently of a predisposition to account, if possible, for a series of changes in the organic world by the regular action of secondary causes, we have seen that in truth many perplexing difficulties present themselves to one who attempts to establish the nature and reality of the specific character. And if once there appears ground of reasonable doubt, in regard to the constancy of species, the amount of transformation which they are capable of undergoing may seem to resolve itself into a mere question of the quantity of time assigned to the past duration of animate existence.

Before entering upon the reasons which may be adduced for rejecting Lamarck's hypothesis, I shall recapitulate, in a few words, the phenomena, and the whole train of thought, by which I conceive it to have been suggested, and which have gained for this and analogous theories, both in ancient and modern times, a considerable number of votaries.

In the first place, the various groups into which plants and animals may be thrown seem almost invariably, to a beginner, to be so natural, that he is usually convinced at first, as was Linnæus to the last, "that genera are as much founded in nature as the species which compose them."* When by examining the numerous intermediate gradations the student finds all lines of demarcation to be in most instances obliterated, even where they at first appeared most distinct, he grows more and more sceptical as to the real existence of genera, and finally regards them as mere arbitrary and artificial signs, invented, like those which serve to distinguish the heavenly constellations, for the convenience of classification, and having as little pretensions to reality.

---

* Genus omne est naturale, in primordio tale creatum. &c. Phil. Bot. § 159. See also ibid. § 162.

Doubts are then engendered in his mind as to whether species may not also be equally unreal. The student is probably first struck with the phenomenon, that some individuals are made to deviate widely from the ordinary type by the force of peculiar circumstances, and with the still more extraordinary fact, that the newly acquired peculiarities are faithfully transmitted to the offspring. How far, he asks, may such variations extend in the course of indefinite periods of time, and during great vicissitudes in the physical condition of the globe? His growing incertitude is at first checked by the reflection that nature has forbidden the intermixture of the descendants of distinct original stocks, or has, at least, entailed sterility on their offspring, thereby preventing their being confounded together, and pointing out that a multitude of distinct types must have been created in the beginning, and must have remained pure and uncorrupted to this day.

Relying on this general law, he endeavours to solve each difficult problem by direct experiment, until he is again astounded by the phenomenon of a prolific hybrid, and still more by an example of a hybrid perpetuating itself throughout several generations in the vegetable world. He then feels himself reduced to the dilemma of choosing between two alternatives; either to reject the test, or to declare that the two species, from the union of which the fruitful progeny has sprung, were mere varieties. If he prefer the latter, he is compelled to question the reality of the distinctness of all other supposed species which differ no more than the parents of such prolific hybrids; for although he may not be enabled immediately to procure, in all such instances, a fruitful offspring; yet experiments show, that after repeated failures, the union of two recognized species may at last, under very favourable circumstances, give birth to a fertile progeny. Such circumstances, therefore, the naturalist may conceive to have occurred again and again, in the course of a great lapse of ages.

His first opinions are now fairly unsettled, and every stay at which he has caught has given way one after another; he is in danger of falling into any new and visionary doctrine which may be presented to him; for he now regards every part of the animate creation as void of stability, and in a state of continual flux. In this mood he encounters the Geologist, who relates to him how there have been endless vicissitudes in the shape and structure of organic beings in former ages — how the approach to the present system of things has been gradual — that there has been a progressive development of organization subservient to the purposes of life, from the most simple to the most complex state — that the appearance of man is the last phenomenon in a long succession of events — and, finally, that a series of physical revolutions can be traced in the inorganic world, coeval and co-extensive with those of organic nature.

These views seem immediately to confirm all his preconceived doubts as to the stability of the specific character, and he begins to think there may exist an inseparable connection between a series of changes in the inanimate world, and the capability of the species to be indefinitely modified by the influence of external circumstances. Henceforth his speculations know no definite bounds; he gives the rein to conjecture, and fancies that the outward form, internal structure, instinctive faculties, nay, that reason itself may have been gradually developed from some of the simplest states of existence—that all animals, that man himself, and the irrational beings, may have had one common origin; that all may be parts of one continuous and progressive scheme of development, from the most imperfect to the more complex; in fine, he renounces his belief in the high genealogy of his species, and looks forward, as if in compensation, to the future perfectibility of man in his physical, intellectual, and moral attributes.

Let us now proceed to consider what is defective in evidence, and what fallacious in reasoning, in the grounds of these strange conclusions. Blumenbach judiciously observes, that "no general rule can be laid down for determining the distinctness of species, as there is no particular class of characters which can serve as a criterion. In each case we must be guided by *analogy* and *probability*." The multitude, in fact, and complexity of the proofs to be weighed is so great, that we can only hope to obtain presumptive evidence, and we must, therefore, be the more careful to derive our general views as much as possible from those observations where the chances of deception are least. We must be on our guard not to tread in the footsteps of the naturalists of the middle ages, who believed the doctrine of spontaneous generation to be applicable to all those parts of the animal and vegetable kingdoms which they least understood, in direct contradiction to the analogy of all the parts best known to them; and who, when at length they found that insects and cryptogamous plants were also propagated from eggs or seeds, still persisted in retaining their old prejudices respecting the infusory animalcules and other minute beings, the generation of which had not then been demonstrated by the microscope to be governed by the same laws.

Lamarck has, indeed, attempted to raise an argument in favour of his system, out of the very confusion which has arisen in the study of some orders of animals and plants, in consequence of the slight shades of difference which separate the new species discovered within the last half century. That the embarrassment of those who attempt to classify and distinguish the new acquisitions, poured in such multitudes into our museums, should increase with the augmentation of their number, is quite natural; since to obviate this, it is not enough that our powers of discrimination should keep pace with the increase of the objects, but we ought to possess greater opportunities of studying each animal and plant in all stages of its growth, and to know profoundly their history, their habits, and physiological characters, throughout several generations; for, in proportion as the series of known animals grows more complete, none can doubt there is a nearer approximation to a graduated scale of being; and thus the most closely allied species will be found to possess a greater number of characters in common.

Causes of the difficulty of discriminating species.—But, in point of fact, our new acquisitions consist, more and more as we advance, of specimens brought from foreign and often very distant and barbarous countries. A large proportion have never even been seen alive by scientific inquirers. Instead of having specimens of the young, the adult, and the aged individuals of each sex, and possessing means of investigating the anatomical structure, the peculiar habits, and instincts of each, what is usually the state of our information? A single specimen, perhaps, of a dried plant, or a stuffed bird or quadruped; a shell, without the soft parts of the animal; an insect in one stage of its numerous transformations;—these are the scanty and imperfect data which the naturalist possesses. Such information may enable us to separate species which stand at a considerable distance from each other; but we have no right to expect any thing but difficulty and ambiguity, if we attempt, from such imperfect opportunities, to obtain distinctive marks for defining the characters of species which are closely related.

sketchy data

If Lamarck could introduce so much certainty and precision into the classification of several thousand species of recent and fossil shells, notwithstanding the extreme remoteness of the organization of these animals from the type of those vertebrated species which are best known, and in the absence of so many of the living inhabitants of shells, we are led to form an exalted conception of the degree of exactness to which specific distinctions are capable of being carried, rather than to call in question their reality.

When our data are so defective, the most acute naturalist must expect to be sometimes at fault, and, like the novice, to overlook essential points of difference, passing unconsciously from one species to another, until, like one who is borne along in a current, he is astonished on looking back, at observing that he has reached a point so remote from that whence he set out.

It is by no means improbable, that, when the series of species of certain genera is very full, they may be found to differ less widely from each other than do the mere varieties or races of certain species. If such a fact could be established, it would, undoubtedly, diminish the chance of our obtaining certainty in our results; but it would by no means overthrow our confidence in the reality of species.

Some mere varieties possibly more distinct than certain individuals of distinct species.—It is almost necessary, indeed, to suppose that varieties will differ in some cases more decidedly than some species, if we admit that there is a graduated scale of being, and assume that the following laws prevail in the economy of the animate creation:—first, that the organization of individuals is capable of being modified to a limited extent, by the force of external causes; secondly, that these modifications are, to a certain extent, transmissible to their offspring; thirdly, that there are fixed limits, beyond which the descendants from common parents can never deviate from a certain type; fourthly, that each species springs from one original stock, and can never be permanently confounded by intermixing with the progeny of any other stock; fifthly, that each species shall endure for a considerable period of time. Now, let us assume, for the present, these rules hypothetically, and see what consequences may naturally be expected to result from them.

We must suppose that when the Author of Nature creates an animal or plant, all the possible circumstances in which its descendants are destined to live are foreseen, and that an organization is conferred upon it which will enable the species to perpetuate itself and survive under all the varying circumstances to which it must be inevitably exposed. Now, the range of variation of circumstances will differ essentially in almost every case. Let us take, for example, any one of the most influential conditions of existence, such as temperature. In some extensive districts near the equator, the thermometer might never vary, throughout several thousand centuries, for more than 20° Fahrenheit; so that if a plant or animal be provided with an organization fitting it to endure such a range, it may continue on the globe for that immense period, although every individual might be liable at once to be cut off by the least possible excess of heat or cold beyond the determinate degree. But if a species be placed in one of the temperate zones, and have a constitution conferred on it capable of supporting a similar range of temperature only, it will inevitably perish before a single year has passed away.

Humboldt has shown that, at Cumana, within the tropics, there is a difference of only 4° Fahr. between the temperature of the warmest and coldest months; whereas, in the temperate zones, the annual variation amounts to about 60°, and the extreme range of the thermometer in Canada is not less than 90°.

The same remark might be applied to any other condition, as food, for example; it may be foreseen that the supply will be regular throughout indefinite periods in one part of the world, and in another very precarious and fluctuating both in kind and quantity. Different qualifications may be required for enabling species to live for a considerable time under circumstances so changeable. If, then, temperature and food be among those external causes which, according to certain laws of animal and vegetable physiology, modify the organization, form, or faculties, of individuals, we instantly perceive that the degrees of variability from a common standard must differ widely in the two cases above supposed; since there is a necessity of accommodating a species in one case to a much greater latitude of circumstances than in the other.

If it be a law, for instance, that scanty sustenance should check those individuals in their growth which are enabled to accommodate themselves to privations of this kind, and that a parent, prevented in this manner from attaining the size proper to its species, should produce a dwarfish offspring, a stunted race will arise, as is remarkably exemplified in some varieties of the horse and dog. The difference of stature in some races of dogs, when compared to others, is as one to five in linear dimensions, making a difference of a hundred-fold in volume.[*] Now, there is a good reason to believe that species in general are by no means susceptible of existing under a diversity of circumstances, which may give rise to such a disparity in size, and, consequently, there will be a multitude of distinct species, of which no two adult individuals can ever depart so widely from a certain standard of dimensions as the mere varieties of certain other species—the dog, for instance. Now, we have only to suppose that what is true of size, may also hold in regard to colour and many other attributes; and it will at once follow, that the degree of possible discordance between varieties of the same species may, in certain cases, exceed the utmost disparity which can arise between two individuals of many distinct species.

The same remarks may hold true in regard to instincts; for, if it be foreseen that one species will have to encounter a great variety of foes, it may be necessary to arm it with great cunning and circumspection, or with courage or other qualities capable of developing themselves on certain occasions; such, for example, as those migratory instincts which are so remarkably exhibited at particular periods, after they have remained dormant for many generations. The history and habits of one variety of such a species may often differ more considerably from some other than those of many distinct species which have no such latitude of accommodation to circumstances.

Extent of known variability in species.—Lamarck has somewhat mis-stated the idea commonly entertained of a species; for it is not true that naturalists in general assume that the organisation of an animal or plant remains absolutely constant, and that it can never vary in any of its parts.[†] All must be aware that circumstances influence the habits, and that the habits may alter the state of the parts and organs; but the difference of opinion relates to the extent to which these modifications of the habits and organs of a particular species may be carried.

Now, let us first inquire what positive facts can be adduced in the history of known species, to establish a great and permanent amount of change in the form, structure, or instinct of individuals descending from some common stock. The best authenticated examples of the extent to which species can be made to vary may be looked for in the history of domesticated animals and cultivated plants. It usually happens, that those species, both of the animal and vegetable kingdom, which have the greatest pliability of organization, those which are most capable of accommodating themselves to a great variety of new circumstances, are most serviceable to man. These only can be carried by him into different climates, and can have their properties or instincts variously diversified by differences of nourishment and habits. If the resources of a species be so limited, and its habits and faculties be of such a confined and local character, that it can only flourish in a few particular spots, it can rarely be of great utility.

---

[*] Cuvier, Discours Prélimin. p. 128.

[†] Phil. Zool. tom. i. p. 266.

We may consider, therefore, that in the domestication of animals and the cultivation of plants, mankind have first selected those species which have the most flexible frames and constitutions, and have then been engaged for ages in conducting a series of experiments, with much patience and at great cost, to ascertain what may be the greatest possible deviation from a common type which can be elicited in these extreme cases.

Varieties of the dog — no transmutation. — The modifications produced in the different races of dogs exhibit the influence of man in the most striking point of view. These animals have been transported into every climate, and placed in every variety of circumstances; they have been made, as a modern naturalist observes, the servant, the companion, the guardian, and the intimate friend of man, and the power of a superior genius has had a wonderful influence not only on their forms, but on their manners and intelligence.* Different races have undergone remarkable changes in the quantity and colour of their clothing; the dogs of Guinea are almost naked, while those of the arctic circle are covered with a warm coat both of hair and wool, which enables them to bear the most intense cold without inconvenience. There are differences also of another kind no less remarkable, as in size, the length of their muzzles, and the convexity of their foreheads.

But, if we look for some of those essential changes which would be required to lend even the semblance of a foundation for the theory of Lamarck, respecting the growth of new organs and the gradual obliteration of others, we find nothing of the kind. For, in all these varieties of the dog, says Cuvier, the relation of the bones with each other remains essentially the same; the form of the teeth never changes in any perceptible degree, except that, in some individuals, one additional false grinder occasionally appears, sometimes on the one side, and sometimes on the other.† The greatest departure from a common type — and it constitutes the maximum of variation as yet known in the animal kingdom — is exemplified in those races of dogs which have a supernumerary toe on the hind foot with the corresponding tarsal bones; a variety analogous to one presented by six-fingered families of the human race.‡

Lamarck has thrown out as a conjecture, that the wolf may have been the original of the dog; and eminent naturalists are still divided in opinion on this subject. It seems now admitted that both species agree in the period of gestation, and Mr. Owen has been unable to confirm the alleged difference in the structure of a part of the intestinal canal.§ Mr. Bell inclines to the opinion that all the various races of dogs have descended from one common stock, of which the wolf is the original source.*

---

* Dureau de la Malle, An. des Sci. Nat. tom. xxi. p. 53. Sept. 1830.

† Disc. Prél. p. 129. sixth edition.

‡ Ibid.

§ Güldenstädt, cited by Pritchard Phys. Hist. of Mankind, vol. i. p. 96.

It is well known that the horse, the ox, the boar, and other domestic animals which have been introduced into South America, and have run wild in many parts, have entirely lost all marks of domesticity, and have reverted to the original characters of their species. But dogs have also become wild in Cuba, Hayti, and in all the Caribbean islands. In the course of the seventeenth century, they hunted in packs from twelve to fifty, or more, in number, and fearlessly attacked herds of wild boars and other animals. It is natural, therefore, to inquire to what form they reverted? Now, they are said by many travellers to have resembled very nearly the shepherd's dog; but it is certain that they were never turned into wolves They were extremely savage, and their ravages appear to have been as much dreaded as those of wolves; but when any of their whelps were caught, and brought from the woods to the towns, they grew up in the most perfect submission to man.

Many examples might be adduced to prove that the extent to which the alteration of species can be pushed in the domestic state depends on the original capacity of the species to admit of variation. The horse has been as long domesticated as the dog, yet its different races depart much less widely from a common type; the ass has been still less changed, the camel scarcely at all; yet these species have probably been subjected to the influence of domestication as long as the horse.

Mummies of animals in Egyptian tombs identical with species still living.—As the advocates of the theory of transmutation trust much to the slow and insensible changes which time may work, they are accustomed to lament the absence of accurate descriptions, and figures of particular animals and plants, handed down from the earliest periods of history, such as might have afforded data for comparing the condition of species, at two periods considerably remote. But, fortunately, we are in some measure independent of such evidence: for, by a singular accident, the priests of Egypt have bequeathed to us, in their cemeteries, that information which the museums and works of the Greek philosophers have failed to transmit.

For the careful investigation of these documents, we are greatly indebted to the skill and diligence of those naturalists who accompanied the French armies during their brief occupation of Egypt: that conquest of four years, from which we may date the improvement of the modern Egyptians in the arts and sciences, and the rapid progress which has been made of late in our knowledge of the arts and sciences of their remote predecessors. Instead of wasting their whole time, as so many preceding travellers had done, in exclusively collecting human mummies, M. Geoffroy and his associates examined diligently, and sent home great numbers of embalmed bodies of consecrated animals, such as the bull, the dog, the cat, the ape, the ichneumon, the crocodile, and the ibis.

---

* History of British Quadrupeds, p. 200. 1837.

To those who have never been accustomed to connect the facts of Natural History with philosophical speculations, who have never raised their conceptions of the end and import of such studies beyond the mere admiration of isolated and beautiful objects, or the exertion of skill in detecting specific differences, it will seem incredible that amidst the din of arms, and the stirring excitement of political movements, so much enthusiasm could have been felt in regard to these precious remains.

In the official report, drawn up by the Professors of the Museum at Paris, on the value of these objects, there are some eloquent passages, which may appear extravagant, unless we reflect how fully these naturalists could appreciate the bearing of the facts thus brought to light on the past history of the globe.

"It seems," say they, "as if the superstition of the ancient Egyptians had been inspired by Nature, with a view of transmitting to after ages a monument of her history. That extraordinary and eccentric people, by embalming with so much care the brutes which were the objects of their stupid adoration, have left us, in their sacred grottos, cabinets of zoology almost complete. The climate has conspired with the art of embalming to preserve the bodies from corruption, and we can now assure ourselves by our own eyes what was the state of a great number of species three thousand years ago. We can scarcely restrain the transports of our imagination, on beholding thus preserved, with their minutest bones, with the smallest portions of their skin, and in every particular most perfectly recognizable, many an animal, which at Thebes or Memphis, two or three thousand years ago, had its own priests and altars."*

Among the Egyptian mummies thus procured were not only those of numerous wild quadrupeds, birds, and reptiles; but, what was perhaps of still higher importance in deciding the great question under discussion, there were the mummies of domestic animals, among which those above mentioned, the bull, the dog, and the cat, were frequent. Now, such was the conformity of the whole of these species to those now living, that there was no more difference, says Cuvier, between them than between the human mummies and the embalmed bodies of men of the present day. Yet some of these animals have since that period been transported by man to almost every climate, and forced to accommodate their habits to the greatest variety of circumstances. The cat, for example, has been carried over the whole earth, and, within the last three centuries, has been naturalized in every part of the new world, — from the cold regions of Canada to the tropical plains of Guiana; yet it has scarcely undergone any perceptible mutation, and is still the same animal which was held sacred by the Egyptians.

Of the ox, undoubtedly, there are many very distinct races; but the bull Apis, which was led in solemn processions by the Egyptian priests, did not differ from some of those now living. The black cattle that have run wild in America, where there were many peculiarities in the climate not to be found, perhaps, in any part of the old world, and where scarcely a single plant on which they fed was of precisely the same species, instead of altering their form and habits, have actually reverted to the exact likeness of the aboriginal wild cattle of Europe.

---

* Ann. du Muséum d'Hist. Nat. tom. i. p. 234. 1802. The reporters were MM. Cuvier, Lacépède, and Lamarck.

In answer to the arguments drawn from the Egyptian mummies, Lamarck said they were identical with their living descendants in the same country, because the climate and physical geography of the banks of the Nile have remained unaltered for the last thirty centuries. But why, it may be asked, have other individuals of these species retained the same characters in many different quarters of the globe, where the climate and many other conditions are so varied?

Seeds and plants from the Egyptian tombs.—The evidence derived from the Egyptian monuments was not confined to the animal kingdom; the fruits, seeds, and other portions of twenty different plants, were faithfully preserved in the same manner; and among these the common wheat was procured by Delille, from closed vessels in the sepulchres of the kings, the grains of which retained not only their form, but even their colour; so effectual has proved the process of embalming with bitumen in a dry and equable climate. No difference could be detected between this wheat and that which now grows in the East and elsewhere; and in regard to the barley, I am informed by Mr. Brown, the celebrated botanist, that its identity with the grain of our own times can be tested by the closest comparison. On examining, for example, one of the seeds from Mr. Sam's Egyptian collection in the British Museum, it is found that "the structure of the husks or that part of the flower which is persistent, agrees precisely with the barley of the present day, in having one perfect flower and the filiform rudiments of a second." Some naturalists believe that the perfect identification of the ancient Egyptian cerealia with the varieties now cultivated has been carried still farther, by sowing the seeds taken out of the catacombs, and raising plants from them; but we want more evidence of this fact. Certain it is, that when the experiment was recently made in the botanic garden at Kew, with 100 seeds of wheat, barley, and lentils, from the Egyptian collection before mentioned of the British Museum, not one of them would germinate.*

Native country of the common wheat.—And here I may observe that there is an obvious answer to Lamarck's objection, that the botanist cannot point out a country where the common wheat grows wild, unless in places where it may have been derived from neighbouring cultivation.* All naturalists are well aware that the geographical distribution of a great number of species is extremely limited; that it was to be expected that every useful plant should first be cultivated successfully in the country where it was indigenous; and that, probably, every station which it partially occupied, when growing wild, would be selected by the agriculturist as best suited to it when artificially increased. Palestine has been conjectured, by a late writer on the cerealia, to have been the original habitation of wheat and barley; a supposition which is rendered the more plausible by Hebrew and Egyptian traditions, and by tracing the migrations of the worship of Ceres, as indicative of the migrations of the plant.†

---

* I by no means wish to express an opinion that seeds cannot retain their vitality after an entombment of 3000 years; but one of my botanical friends who entertained a philosophical doubt on this subject, being desirous of ascertaining the truth of three or four alleged instances of the germination of "mummy wheat," discovered, on communicating with several Egyptian travellers, that they had procured the grains in question, not directly from the catacombs, but from the Arabs, who are always ready to supply strangers with an article now very frequently in demand. The presence of an occasional grain of Indian corn or maize in several of the parcels of grain shown to my friend as coming from the catacombs confirmed his scepticism.

If we are to infer that some one of the wild grasses has been transformed into the common wheat, and that some animal of the genus *Canis*, still unreclaimed, has been metamorphosed into the dog, merely because we cannot find the domestic dog, or the cultivated wheat, in a state of nature, we may be next called upon to make similar admissions in regard to the camel; for it seems very doubtful whether any race of this species of quadruped is now wild.

Changes in plants produced by cultivation.—But if agriculture, it will be said, does not supply examples of extraordinary changes of form and organization, the horticulturist can, at least, appeal to facts which may confound the preceding train of reasoning. The crab has been transformed into the apple; the sloe into the plum; flowers have changed their colour, and become double; and these new characters can be perpetuated by seed; a bitter plant, with wavy sea-green leaves, has been taken from the sea-side, where it grew like wild charlock; has been transplanted into the garden, lost its saltness, and has been metamorphosed into two distinct vegetables, as unlike each other as is each to the parent plant—the red cabbage and the cauliflower. These, and a multitude of analogous facts, are undoubtedly among the wonders of nature, and attest more strongly, perhaps, the extent to which species may be modified, than any examples derived from the animal kingdom. But in these cases we find that we soon reach certain limits, beyond which we are unable to cause the individuals descending from the same stock to vary; while, on the other hand, it is easy to show that these extraordinary varieties could seldom arise, and could never be perpetuated in a wild state for many generations, under any imaginable combination of accidents. They may be regarded as extreme cases, brought about by human interference, and not as phenomena which indicate a capability of indefinite modification in the natural world.

The propagation of a plant by buds or grafts, and by cuttings, is obviously a mode which nature does not employ; and this multiplication, as well as that produced by roots and layers, seems merely to operate as an extension of the life of an individual, and not as a reproduction of the species such as happens by seed. All plants increased by grafts or layers retain precisely the peculiar qualities of the individual to which they owe their origin, and, like an individual, they have only a determinate existence; in some cases longer, and in others shorter.[*] It seems now admitted by horticulturists, that none of our garden varieties of fruit are entitled to be considered strictly permanent, but that they wear out after a time[†]; and we are thus compelled to resort again to seeds: in which case there is so decided a tendency in the seedlings to revert to the original type, that our utmost skill is sometimes baffled in attempting to recover the desired variety.

---

* Phil. Zool., tom. i. p. 227.

† L'Origine et la Patrie des Céréales, &c., Annales des Sciences Natur., tom. ix. p. 61.

Varieties of the cabbage.—The different races of cabbages afford, as was admitted, an astonishing example of deviation from a common type; but we can scarcely conceive them to have originated, much less to have lasted for several generations, without the intervention of man. It is only by strong manures that these varieties have been obtained, and in poorer soils they instantly degenerate. If, therefore, we suppose in a state of nature the seed of the wild *Brassica oleracea* to have been wafted from the sea-side to some spot enriched by the dung of animals, and to have there become a cauliflower, it would soon diffuse its seed to some comparatively sterile soils around, and the offspring would relapse to the likeness of the parent stock.

But if we go so far as to imagine the soil, in the spot first occupied, to be constantly manured by herds of wild animals, so as to continue as rich as that of a garden, still the variety could not be maintained; because we know that each of these races is prone to fecundate others, and gardeners are compelled to exert the utmost diligence to prevent cross-breeds. The intermixture of the pollen of varieties growing in the poorer soil around would soon destroy the peculiar characters of the race which occupied the highly manured tract; for, if these accidents so continually happen, in spite of our care, among the culinary varieties, it is easy to see how soon this cause might obliterate every marked singularity in a wild state.

Besides, it is well known that, although the pampered races which we rear in our gardens for use or ornament may often be perpetuated by seed, yet they rarely produce seed in such abundance, or so prolific in quality, as wild individuals; so that if the care of man were withdrawn, the most fertile variety would always, in the end, prevail over the more sterile.

Similar remarks may be applied to the double flowers, which present such strange anomalies to the botanist. The ovarium, in such cases, is frequently abortive; and the seeds, when prolific, are generally much fewer than where the flowers are single.

Changes caused by soil. — Some curious experiments, recently made on the production of blue instead of red flowers in the

---

[*] Smith's Introduction to Botany, p. 138. edit. 1807.

[†] See Mr. Knight's Observations, Hort. Trans., vol. ii. p. 160.

Hydrangea hortensis, illustrate the immediate effect of certain soils on the colours of the calyx and petals. In garden-mould or compost, the flowers are invariably red; in some kinds of bog-earth they are blue; and the same change is always produced by a particular sort of yellow loam.

Varieties of the primrose.—Linnæus was of opinion that the primrose, oxlip, cowslip, and polyanthus, were only varieties of the same species. The majority of the modern botanists, on the contrary, consider them to be distinct, although some conceived that the oxlip might be a cross between the cowslip and the primrose. Mr. Herbert has lately recorded the following experiment: — "I raised from the natural seed of one umbel of a highly manured red cowslip a primrose, a cowslip, oxlips of the usual and other colours, a black polyanthus, a hose-in-hose cowslip, and a natural primrose bearing its flower on a polyanthus stalk. From the seed of that very hose-in-hose cowslip I have since raised a hose-in-hose primrose. I therefore consider all these to be only local varieties, depending upon soil and situation."* Professor Henslow, of Cambridge, has since confirmed this experiment of Mr. Herbert; so that we have an example, not only of the remarkable varieties which the florist can obtain from a common stock, but of the distinctness of analogous races found in a wild state.†

On what particular ingredient, or quality in the earth, these changes depend, has not yet been ascertained.‡ But gardeners are well aware that particular plants, when placed under the influence of certain circumstances, are changed in various ways, according to the species; and as often as the experiments are repeated, similar results are obtained. The nature of these results, however, depends upon the species, and they are, therefore, part of the specific character; they exhibit the same phenomena, again and again, and indicate certain fixed and invariable relations between the physiological peculiarities of the plant, and the influence of certain external agents. They afford no ground for questioning the instability of species, but rather the contrary; they present us with a class of phenomena which, when they are more thoroughly understood, may afford some of the best tests for identifying species, and proving that the attributes originally conferred endure so long as any issue of the original stock remains upon the earth.

---

* Hort. Trans. vol. iv. p. 19.

† Loudon's Mag. of Nat. Hist., Sept. 1830, vol. iii. p. 408.

‡ Hort. Trans. vol. iii. p. 173.

CHAPTER XXXV.

WHETHER SPECIES HAVE A REAL EXISTENCE IN NATURE—*continued.*

Limits of the variability of species—Species susceptible of modification may be altered greatly in a short time, and in a few generations; after which they remain stationary—The animals now subject to man had originally an aptitude to domesticity—Acquired peculiarities which become hereditary have a close connexion with the habits or instincts of the species in a wild state—Some qualities in certain animals have been conferred with a view of their relation to man—Wild elephant domesticated in a few years, but its faculties incapable of farther development.

Variability of a species compared to that of an individual.—I endeavoured, in the last chapter, to show, that a belief in the reality of species is not inconsistent with the idea of a considerable degree of variability in the specific character. This opinion, indeed, is little more than an extension of the idea which we must entertain of the identity of an individual, throughout the changes which it is capable of undergoing.

If a quadruped, inhabiting a cold northern latitude, and covered with a warm coat of hair or wool, be transported to a southern climate, it will often, in the course of a few years, shed a considerable portion of its coat, which it gradually recovers on being again restored to its native country. Even there the same changes are, perhaps, superinduced to a certain extent by the return of winter and summer. We know that the Alpine hare (*Lepus variabilis*, Pal.) and the ermine, or stoat (*Mustela erminea*, Linn.) become white during winter, and again obtain their full colour during the warmer season; that the plumage of the ptarmigan undergoes a like metamorphosis in colour and quantity, and that the change is equally temporary. We are aware that, if we reclaim some wild animal, and modify its habits and instincts by domestication, it may, if it escapes, become in a few years nearly as wild and untractable as ever; and if the same individual be again retaken, it may be reduced to its former tame state. A plant is sown in a prepared soil, in order that the petals of its flowers may multiply, and their colour be heightened or changed: if we then withhold our care, the flowers of this same species become again single. In these, and innumerable other instances, we must suppose that the species was produced with a certain number of qualities; and, in the case of animals, with a variety of instincts, some of which may or may not be developed according to circumstances, or which, after having been called forth, may again become latent when the exciting causes are removed.

Now, the formation of races seems the necessary consequence of such a capability in species to vary, if it be a general law that the offspring should very closely resemble the parent. But, before we can infer that there are no limits to the deviation from an original type which may be brought about in the course of an indefinite number of generations, we ought to have some proof that, in each successive generation, individuals may go on acquiring an equal amount of new peculiarities, under the influence of equal changes of circumstances. The balance of evidence, however, inclines most decidedly on the opposite side; for in all cases we find that the quantity of divergence diminishes after a few generations in a very rapid ratio.

Species susceptible of modification may be greatly altered in a few generations.—It cannot be objected, that it is out of our power to go on varying the circumstances in the same manner as might happen in the natural course of events during some great geological cycle. For in the first place, where a capacity is given to individuals to adapt themselves to new circumstances, it does not generally require a very long period for its development: if, indeed, such were the case, it is not easy to see how the modification would answer the ends proposed, for all the individuals would die before new qualities, habits, or instincts were conferred.

When we have succeeded in naturalizing some tropical plant in a temperate climate, nothing prevents us from attempting gradually to extend its distribution to higher latitudes, or to greater elevations above the level of the sea, allowing equal quantities of time, or an equal number of generations, for habituating the species to successive increments of cold. But every husbandman and gardener is aware that such experiments will fail; and we are more likely to succeed in making some plants, in the course of the first two generations, support a considerable degree of difference of temperature than a very small difference afterwards, though we persevere for many centuries.

It is the same if we take any other cause instead of temperature; such as the quality of the food, or the kind of dangers to which an animal is exposed, or the soil in which a plant lives. The alteration in habits, form, or organization, is often rapid during a short period; but when the circumstances are made to vary farther, though in ever so slight a degree, all modification ceases, and the individual perishes. Thus some herbivorous quadrupeds may be made to feed partially on fish or flesh; but even these can never be taught to live on some herbs which they reject, and which would even poison them, although the same may be very nutritious to other species of the same natural order. So when man uses force or stratagem against wild animals, the persecuted race soon becomes more cautious, watchful, and cunning; new instincts seem often to be developed, and to become hereditary in the first two or three generations: but let the skill and address of man increase, however gradually, no farther variation can take place, no new qualities are elicited by the increasing dangers. The alteration of the habits of the species has reached a point beyond which no ulterior modification is possible, however indefinite the lapse of ages during which the new circumstances operate. Extirpation then follows, rather than such a transformation as could alone enable the species to perpetuate itself under the new state of things.

Animals now subject to man had originally an aptitude to domesticity.—It has been well observed by M. F. Cuvier and M. Dureau de la Malle, that unless some animals had manifested in a wild state an aptitude to second the efforts of man, their domestication would never have been attempted. If they had all resembled the wolf, the fox, and the hyæna, the patience of the experimentalist would have been exhausted by innumerable failures before he at last succeeded in obtaining some imperfect results; so, if the first advantages derived from the cultivation of plants had been elicited by as tedious and costly a process as that by which we now make some slight additional improvement in certain races, we should have remained to this day in ignorance of the greater number of their useful qualities.

Acquired instincts of some animals become hereditary.—It is undoubtedly true, that many new habits and qualities have not only been acquired in recent times by certain races of dogs, but have been transmitted to their offspring. But in these cases it will be observed, that the new peculiarities have an intimate relation to the habits of the animal in a wild state, and therefore do not attest any tendency to departure to an indefinite extent from the original type of the species. A race of dogs employed for hunting deer in the platform of Santa Fé, in Mexico, affords a beautiful illustration of a new hereditary instinct. The mode of attack, observes M. Roulin, which they employ consists in seizing the animal by the belly and overturning it by a sudden effort, taking advantage of the moment when the body of the deer rests only upon the fore-legs. The weight of the animal thus thrown over is often six times that of its antagonist. The dog of pure breed inherits a disposition to this kind of chase, and never attacks a deer from before while running. Even should the deer, not perceiving him, come directly upon him, the dog steps aside and makes his assault on the flank; whereas other hunting dogs, though of superior strength, and general sagacity, which are brought from Europe, are destitute of this instinct. For want of similar precautions, they are often killed by the deer on the spot, the vertebræ of their neck being dislocated by the violence of the shock.*

A new instinct has also become hereditary in a mongrel race of dogs employed by the inhabitants of the banks of the Magdalena almost exclusively in hunting the white-lipped pecari. The address of these dogs consists in restraining their ardour, and attaching themselves to no animal in particular, but keeping the whole herd in check. Now, among these dogs some are found, which the very first time they are taken to the woods, are acquainted with this mode of attack; whereas, a dog of another breed starts forward at once, is surrounded by the pecari, and, whatever may be his strength, is destroyed in a moment.

* M. Roulin, Ann. des Sci. Nat.

Some of our countrymen, engaged of late in conducting one of the principal mining associations in Mexico, that of Real del Monte, carried out with them some English greyhounds of the best breed, to hunt the hares which abound in that country. The great platform which is the scene of sport is at an elevation of about nine thousand feet above the level of the sea, and the mercury in the barometer stands habitually at the height of about nineteen inches. It was found that the greyhounds could not support the fatigues of a long chase in this attenuated atmosphere, and before they could come up with their prey, they lay down gasping for breath; but these same animals have produced whelps which have grown up, and are not in the least degree incommoded by the want of density in the air, but run down the hares with as much ease as the fleetest of their race in this country.

The fixed and deliberate stand of the pointer has with propriety been regarded as a mere modification of a habit, which may have been useful to a wild race accustomed to wind game, and steal upon it by surprise, first pausing for an instant, in order to spring with unerring aim. The faculty of the retriever, however, may justly be regarded as more inexplicable and less easily referable to the instinctive passions of the species. M. Majendie, says a French writer in a recently published memoir, having learnt that there was a race of dogs in England which stopped and brought back game of their own accord, procured a pair, and, having obtained a whelp from them, kept it constantly under his eyes, until he had an opportunity of assuring himself that, without having received any instruction, and on the very first day that it was carried to the chase, it brought back game with as much steadiness as dogs which had been schooled into the same manœuvre by means of the whip and collar.

Attributes of animals in their relation to man.—Such attainments, as well as the habits and dispositions which the shepherd's dog and many others inherit, seem to be of a nature and extent which we can hardly explain by supposing them to be modifications of instincts necessary for the preservation of the species in a wild state. When such remarkable habits appear in races of this species, we may reasonably conjecture that they were given with no other view than for the use of man and the preservation of the dog, which thus obtains protection.

As a general rule, I fully agree with M. F. Cuvier, that, in studying the habits of animals, we must attempt, as far as possible, to refer their domestic qualities to modifications of instincts which are implanted in them in a state of nature; and that writer has successfully pointed out, in an admirable essay on the domestication of the mammalia, the true origin of many dispositions which are vulgarly attributed to the influence of education alone.* But we should go too far if we did not admit that some of the qualities of particular animals and plants may have been given solely with a view to the connexion which it was foreseen would exist between them and man — especially when we see that connexion to be in many cases so intimate, that the greater number, and sometimes, as in the case of the camel, all the individuals of the species which exist on the earth are in subjection to the human race.

---

* Mém. du Mus. d'Hist. Nat.—Jameson, Ed. New Phil. Journ., Nos. 6, 7, 8.

We can perceive in a multitude of animals, especially in some of the parasitic tribes, that certain instincts and organs are conferred for the purpose of defence or attack against some other species. Now, if we are reluctant to suppose the existence of similar relations between man and the instincts of many of the inferior animals, we adopt an hypothesis no less violent, though in the opposite extreme to that which has led some to imagine the whole animate and inanimate creation to have been made solely for the support, gratification, and instruction of mankind.

Many species, most hostile to our persons or property, multiply, in spite of our efforts to repress them; others, on the contrary, are intentionally augmented many hundred fold in number by our exertions. In such instances, we must imagine the relative resources of man and of species, friendly or inimical to him, to have been prospectively calculated and adjusted. To withold assent to this supposition, would be to refuse what we must grant in respect to the economy of nature in every other part of the organic creation; for the various species of contemporary plants and animals have obviously their relative forces nicely balanced, and their respective tastes, passions, and instincts so contrived, that they are all in perfect harmony with each other. In no other manner could it happen that each species, surrounded, as it is, by countless dangers, should be enabled to maintain its ground for periods of considerable duration.

The docility of the individuals of some of our domestic species, extending, as it does, to attainments foreign to their natural habits and faculties, may, perhaps, have been conferred with a view to their association with man. But, lest species should be thereby made to vary indefinitely, we find that such habits are never transmissible by generation.

A pig has been trained to hunt and point game with great activity and steadiness*; and other learned individuals, of the same species, have been taught to spell; but such fortuitous acquirements never become hereditary, for they have no relation whatever to the exigencies of the animal in a wild state, and cannot, therefore, be developments of any instinctive propensities.

Influence of domestication.—An animal in domesticity, says M. F. Cuvier, is not essentially in a different situation, in regard to the feeling of restraint, from one left to itself. It lives in society without constraint, because, without doubt, it was a social animal; and it conforms itself to the will of man, because it had a chief, to which, in a wild state, it would have yielded obedience. There is nothing in its new situation that is not conformable to its propensities; it is satisfying its wants by submission to a master, and makes no sacrifice of its natural inclinations. All the social animals, when left to themselves, form herds more or less numerous; and all the individuals of the same herd know each other, are mutually attached, and will not allow a strange individual to join them. In a wild state, moreover, they obey some individual, which, by its superiority, has become the chief of the herd. Our domestic species had, originally, this sociability of disposition; and no solitary species, however easy it may be *to tame it*, has yet afforded true domestic races. We merely, therefore, develope, to our own advantage, propensities which propel the individuals of certain species to draw near to their fellows.

---

* In the New Forest, near Ringwood, Hants, by Mr. Toomer, keeper of Broomy Lodge. I have conversed with witnesses of the fact.

The sheep which we have reared is induced to follow us, as it would be led to follow the flock among which it was brought up; and, when individuals of gregarious species have been accustomed to one master, it is he alone whom they acknowledge as their chief — he only whom they obey. "The elephant allows himself to be directed only by the carnac whom he has adopted; the dog itself, reared in solitude with its master, manifests a hostile disposition towards all others; and every body knows how dangerous it is to be in the midst of a herd of cows, in pasturages that are little frequented, when they have not at their head the keeper who takes care of them.

"Every thing, therefore, tends to convince us, that formerly men were only, with regard to the domestic animals, what those who are particularly charged with the care of them still are — namely, members of the society which these animals form among themselves; and that they are only distinguished, in the general mass, by the authority which they have been enabled to assume from their superiority of intellect. Thus, every social animal which recognizes man as a member, and as the chief of its herd, is a domestic animal. It might even be said, that, from the moment when such an animal admits man as a member of its society, it is domesticated, as man could not enter into such a society without becoming the chief of it." *

But the ingenious author whose observations I have here cited, admits that the obedience which the individuals of many domestic species yield indifferently to every person, is without analogy in any state of things which could exist previously to their subjugation by man. Each troop of wild horses, it is true, has some stallion for its chief, who draws after him all the individuals of which the herd is composed; but, when a domesticated horse has passed from hand to hand, and has served several masters, he becomes equally docile towards *any person*, and is subjected to the whole human race. It seems fair to presume that the capability in the instinct of the horse to be thus modified, was given to enable the species to render greater services to man; and, perhaps, the facility with which many other acquired characters become hereditary in various races of the horse, may be explicable only on a like supposition. The amble, for example, a pace to which the domestic races in some parts of Spanish America are exclusively trained, has in the course of several generations, become hereditary, and is assumed by all the young colts before they are broken in.[*]

---

* Mém. du Mus. d'Hist. Nat.

It seems, also, reasonable to conclude, that the power bestowed on the horse, the dog, the ox, the sheep, the cat, and many species of domestic fowls, of supporting almost every climate, was given expressly to enable them to follow man throughout all parts of the globe, in order that we might obtain their services, and they our protection. If it be objected that the elephant which, by the union of strength, intelligence, and docility, can render the greatest services to mankind, is incapable of living in any but the warmest latitudes, we may observe that the quantity of vegetable food required by this quadruped would render its maintenance in the temperate zones too costly, and in the arctic impossible.

Among the changes superinduced by man, none appear, at first sight, more remarkable than the perfect tameness of certain domestic races. It is well known that, at however early an age we obtain possession of the young of many unreclaimed races, they will retain, throughout life, a considerable timidity and apprehensiveness of danger; whereas, after one or two generations, the descendants of the same stock will habitually place the most implicit confidence in man. There is good reason, however, to suspect that such changes are not without analogy in a state of nature; or, to speak more correctly, in situations where man has not interfered.

We learn from Mr. Darwin, that in the Galapagos archipelago, placed directly under the equator, and nearly 600 miles west of the American continent, all the terrestrial birds, as the finches, doves, hawks, and others, are so tame, that they may be killed with a switch. One day, says this author, "a mocking-bird alighted on the edge of a pitcher which I held in my hand, and began quietly to sip the water, and allowed me to lift it with the vessel from the ground." Yet formerly, when the first Europeans landed, and found no inhabitants in these islands, the birds were even tamer than now: already they are beginning to acquire that salutary dread of man which in countries long settled is natural even to young birds, which have never received any injury. So in the Falkland Islands, both the birds and foxes are entirely without fear of man; whereas, in the adjoining mainland of South America, many of the same species of birds are extremely wild; for there they have for ages been persecuted by the natives.[†]

Dr. Richardson informs us, in his able history of the habits of the North American animals, that, "in the retired parts of the mountains where the hunters had seldom penetrated, there is no difficulty in approaching the Rocky Mountain sheep, which there exhibit *the simplicity of character so remarkable in the domestic species;* but where they have been often fired at, they are exceedingly wild, alarm their companions, on the approach of danger, by a hissing noise, and scale the rocks with a speed and agility that baffle pursuit." *

---

[*] Dureau de la Malle. Ann. des Sci. Nat., tom. xxi. p. 58.

[†] Darwin's Journ. in Voyage of H.M.S. Beagle, p. 475.

It is probable, therefore, that as man, in diffusing himself over the globe, has tamed many wild races, so, also, he has made many tame races wild. Had some of the larger carnivorous beasts, capable of scaling the rocks, made their way into the North American mountains before our hunters, a similar alteration in the instincts of the sheep would doubtless have been brought about.

Wild elephants domesticated in a few years. — No animal affords a more striking illustration of the principal points which I have been endeavouring to establish than the elephant; for, in the first place, the wonderful sagacity with which he accommodates himself to the society of man, and the new habits which he contracts, are not the result of time, nor of modifications produced in the course of many generations. These animals will breed in captivity, as is now ascertained, in opposition to the vulgar opinion of many modern naturalists, and in conformity to that of the ancients Ælian and Columella †: yet it has always been the custom, as the least expensive mode of obtaining them, to capture wild individuals in the forests, usually when full grown; and, in a few years after they are taken — sometimes, it is said, in the space of a few months — their education is completed.

Had the whole species been domesticated from an early period in the history of man, like the camel, their superior intelligence would, doubtless, have been attributed to their long and familiar intercourse with the lord of the creation; but we know that a few years is sufficient to bring about this wonderful change of habits; and although the same individual may continue to receive tuition for a century afterwards, yet it makes no farther progress in the general development of its faculties. Were it otherwise, indeed, the animal would soon deserve more than the poet's epithet of "half-reasoning."

From the authority of our countrymen employed in the late Burmese war, it appears, in corroboration of older accounts, that when elephants are required to execute extraordinary tasks, they may be made to understand that they will receive unusual rewards. Some favourite dainty is shown to them, in the hope of acquiring which the work is done; and so perfectly does the nature of the contract appear to be understood, that the breach of it, on the part of the master, is often attended with danger. In this case, a power has been given to the species to adapt their social instincts to new circumstances with surprising rapidity; but the extent of this change is defined by strict and arbitrary limits. There is no indication of a tendency to continued divergence from certain attributes with which the elephant was originally endued—no ground whatever for anticipating that, in thousands of centuries, any material alteration could ever be effected. All that we can infer from analogy is, that some more useful and peculiar races might probably be formed, if the experiment were fairly tried; and that some individual characteristic, now only casual and temporary, might be perpetuated by generation.

---

* Fauna Boreali-Americana, p. 273.

† Mr. Corse on the Habits, &c. of the Elephant, Phil. Trans., 1799.

In all cases, therefore, where the domestic qualities exist in animals, they seem to require no lengthened process for their development; and they appear to have been wholly denied to some classes, which, from their strength and social disposition, might have rendered great services to man; as, for example, the greater part of the quadrumana. The orang-outang, indeed, which, for its resemblance in form to man, and apparently for no other good reason, has been assumed by Lamarck to be the most perfect of the inferior animals, has been tamed by the savages of Borneo, and made to climb lofty trees, and to bring down the fruit. But he is said to yield to his masters an unwilling obedience, and to be held in subjection only by severe discipline. We know nothing of the faculties of this animal which can suggest the idea that it rivals the elephant in intelligence; much less anything which can countenance the dreams of those who have fancied that it might have been transmuted into the "dominant race." One of the baboons of Sumatra (*Simia carpolegus*) appears to be more docile, and is frequently trained by the inhabitants to ascend trees, for the purpose of gathering cocoa-nuts; a service in which the animal is very expert. He selects, says Sir Stamford Raffles, the ripe nuts, with great judgment, and pulls no more than he is ordered.[*] The capuchin and cacajao monkeys are, according to Humboldt, taught to ascend trees in the same manner, and to throw down fruit on the banks of the lower Orinoco.[†]

It is for the Lamarckians to explain how it happens that those same savages of Borneo have not themselves acquired, by dint of longing, for many generations, for the power of climbing trees, the elongated arms of the orang, or even the prehensile tails of some American monkeys. Instead of being reduced to the necessity of subjugating stubborn and untractable brutes, we should naturally have anticipated "that their wants would have excited them to efforts, and that continued efforts would have given rise to new organs;" or rather to the re-acquisition of organs which, in a manner irreconcileable with the principle of the *progressive* system, have grown obsolete in tribes of men which have such constant need of them.

Recapitulation.—It follows, then, from the different facts which have been considered in this chapter, that a short period of time is generally sufficient to effect nearly the whole change which an alteration of external circumstances can bring about in the habits of a species, and that such capacity of accommodation to new circumstances is enjoyed, in very different degrees, by different species.

Certain qualities appear to be bestowed exclusively with a view to the relations which are destined to exist between different species, and, among others, between certain species and man; but these latter are always so nearly connected with the original habits and propensities of each species in a wild state, that they imply no indefinite capacity of varying from the original type. The acquired habits derived from human tuition are rarely transmitted to the offspring; and when this happens, it is almost universally the case with those merely which have some obvious connexion with the attributes of the species when in a state of independence.

---

[*] Linn. Trans. vol. xiii. p. 244.

[†] Pers. Narr. of Travels to the Equinoctial Regions of the New Continent, in the years 1779—1804.

CHAPTER XXXVI.

WHETHER SPECIES HAVE A REAL EXISTENCE IN NATURE—*continued.*

Phenomena of hybrids—Hunter's opinions—Mules not strictly intermediate between parent species—Hybrid plants—Experiments of Kölreuter and Wiegmann—Vegetable hybrids prolific throughout several generations—Why rare in a wild state—De Candolle on hybrid plants—The phenomena of hybrids confirm the distinctness of species—Theory of the gradation in the intelligence of animals as indicated by the facial angle—Doctrine that certain organs of the fœtus in mammalia assume successively the forms of fish, reptile, and bird—Recapitulation.

Phenomena of hybrids.—We have yet to consider another class of phenomena, those relating to the production of hybrids, which have been regarded in a very different light with reference to their bearing on the question of the permanent distinctness of species; some naturalists considering them as affording the strongest of all proofs in favour of the reality of species; others, on the contrary, appealing to them as countenancing the opposite doctrine, that all the varieties of organization and instinct now exhibited in the animal and vegetable kingdoms may have been propagated from a small number of original types.

In regard to the mammifers and birds it is found that no sexual union will take place between races which are remote from each other in their habits and organization; and it is only in species that are very nearly allied that such unions produce offspring. It may be laid down as a general rule, admitting of very few exceptions among quadrupeds, that the hybrid progeny is sterile; and there seem to be no well authenticated examples of the continuance of the mule race beyond one generation. The principal number of observations and experiments relate to the mixed offspring of the horse and the ass; and in this case it is well established that the he-mule can generate, and the she-mule produce. Such cases occur in Spain and Italy, and much more frequently in the West Indies and New Holland; but these mules have never bred in cold climates, seldom in warm regions, and still more rarely in temperate countries.

The hybrid offspring of the she-ass and the stallion, the γιννος of Aristotle, and the hinnus of Pliny, differs from the mule, or the offspring of the ass and mare. In both cases, says Buffon, these animals retain more of the dam than of the sire, not only in the magnitude, but in the figure of the body: whereas, in the form of the head, limbs, and tail, they bear a greater resemblance to the sire. The same naturalist infers, from various experiments respecting cross-breeds between the he-goat and ewe, the dog and she-wolf, the goldfinch and canary-bird, that the male transmits his sex to the greatest number, and that the preponderance of males over females exceeds that which prevails where the parents are of the same species.

Hunter's opinion. — The celebrated John Hunter has observed, that the true distinction of species must ultimately be gathered from their incapacity of propagating with each other, and producing offspring capable of again continuing itself. He was unwilling, however, to admit that the horse and the ass were of the same species, because some rare instances had been adduced of the breeding of mules, although he maintained that the wolf, the dog, and the jackal were all of one species; because he had found, by two experiments, that the dog would breed both with the wolf and the jackal; and that the mule, in each case, would breed again with the dog. In these cases, however, it may be observed, that there was always one parent at least of pure breed, and no proof was obtained that a true hybrid race could be perpetuated; a fact of which I believe no examples are yet recorded, either in regard to mixtures of the horse and ass, or any other of the mammalia.

Should the fact be hereafter ascertained, that two mules can propagate their kind, we must still inquire whether the offspring may not be regarded in the light of a monstrous birth, proceeding from some accidental cause, or, rather, to speak more philosophically, from some general law not yet understood, but which may not be permitted permanently to interfere with those laws of generation by which species may, in general, be prevented from becoming blended. If, for example, we discovered that the progeny of a mule race degenerated greatly, in the first generation, in force, sagacity, or any attribute necessary for its preservation in a state of nature, we might infer that, like a monster, it is a mere temporary and fortuitous variety. Nor does it seem probable that the greater number of such monsters could ever occur unless obtained by art; for, in Hunter's experiments, stratagem or force was, in most instances, employed to bring about the irregular connexion.*

Mules not strictly intermediate between the parent species. — It seems rarely to happen that the mule offspring is truly intermediate in character between the two parents. Thus Hunter mentions that, in his experiments, one of the hybrid pups resembled the wolf much more than the rest of the litter; and we are informed by Wiegmann, that, in a litter lately obtained in the Royal Menagerie at Berlin, from a white pointer and a she-wolf, two of the cubs resembled the common wolf-dog, but the third was like a pointer with hanging ears.

---

* Phil. Trans. 1787 Additional Remarks, Phil. Trans., 1789. See also Essays by the late Dr. Samuel G. Morton, On Prolific Hybrids, &c.; and on Hybridity as a Test of Species.—American Journ. of Science, vol. iii. 1847.

There is undoubtedly a very close analogy between these phenomena and those presented by the intermixture of distinct races of the same species, both in the inferior animals and in man. Dr. Prichard, in his "Physical History of Mankind," cites examples where the peculiarities of the parents have been transmitted very unequally to the offspring; as where children, entirely white, or perfectly black, have sprung from the union of the European and the negro. Sometimes the colour or other peculiarities of one parent, after having failed to show themselves in the immediate progeny, reappear in a subsequent generation; as where a white child is born of two black parents, the grandfather having been a white.*

The same author judiciously observes that, if different species mixed their breed, and hybrid races were often propagated, the animal world would soon present a scene of confusion; its tribes would be every where blended together, and we should perhaps find more hybrid creatures than genuine and uncorrupted races.†

Hybrid plants.—Kölreuter's experiments.—The history of the vegetable kingdom has been thought to afford more decisive evidence in favour of the theory of the formation of new and permanent species from hybrid stocks. The first accurate experiments in illustration of this curious subject appear to have been made by Kölreuter, who obtained a hybrid from two species of tobacco, *Nicotiana rustica* and *N. paniculata*, which differ greatly in the shape of their leaves, the colour of the corolla, and the height of the stem. The stigma of a plant of *N. rustica* was impregnated with the pollen of a plant of *N. paniculata.* The seed ripened, and produced a hybrid which was intermediate between the two parents, and which, like all the hybrids which this botanist brought up, had imperfect stamens. He afterwards impregnated this hybrid with the pollen of *N. paniculata*, and obtained plants which much more resembled the last. This he continued through several generations, until, by due perseverance, he actually changed the *Nicotiana rustica* into the *Nicotiana paniculata.*

The plan of impregnation adopted, was the cutting off of the anthers of the plant intended for fructification before they had shed pollen, and then laying on foreign pollen upon the stigma.

Weigmann's experiments.—The same experiment has since been repeated with success by Weigmann, who found that he could bring back the hybrids to the exact likeness of either parent, by crossing them a sufficient number of times.

The blending of the characters of the parent stocks, in many other of Weigmann's experiments, was complete; the colour and shape of the leaves and flowers, and even the scent, being intermediate, as in the offspring of the two species of verbascum. An intermarriage, also, between the common onion and the leek (*Allium cepa* and *A.*

---

* Prichard, vol. i. p. 217.

† Ibid. p. 97.

porrum) gave a mule plant, which, in the character of its leaves and flowers, approached most nearly to the garden onion, but had the elongated bulbous root and smell of the leek.

The same botanist remarks, that vegetable hybrids, when not strictly intermediate, more frequently approach the female than the male parent species; *but they never exhibit characters foreign to both.* A re-cross with one of the original stocks generally causes the mule plant to revert towards that stock; but this is not always the case, the offspring sometimes continuing to exhibit the character of a full hybrid.

In general, the success attending the production and perpetuity of hybrids among plants depends, as in the animal kingdom, on the degree of proximity between the species intermarried. If their organization be very remote, impregnation never takes place; if somewhat less distant, seeds are formed, but always imperfect and sterile. The next degree of relationship yields hybrid seedlings, but these are barren; and it is only when the parent species are very nearly allied that the hybrid race may be perpetuated for several generations. Even in this case, the best authenticated examples seem confined to the crossing of hybrids with individuals of pure breed. In none of the experiment most accurately detailed does it appear that both the parents were mules.

Wiegmann diversified as much as possible his mode of bringing about these irregular unions among plants. He often sowed parallel rows, near to each other, of the species from which he desired to breed; and, instead of mutilating, after Kölreuter's fashion, the plants of one of the parent stocks, he merely washed the pollen off their anthers. The branches of the plants in each row were then gently bent towards each other and intertwined; so that the wind, and numerous insects, as they passed from the flowers of one to those of the other species, carried the pollen and produced fecundation.

Vegetable hybrids why rare in a wild state.—The same observer saw a good exemplification of the manner in which hybrids may be formed in a state of nature. Some wallflowers and pinks had been growing in a garden, in a dry sunny situation, and their stigmas had been ripened so as to be moist, and to absorb pollen with avidity, although their anthers were not yet developed. These stigmas became impregnated by pollen blown from some other adjacent plants of the same species; but had they been of different species, and not too remote in their organization, mule races must have resulted.

When, indeed, we consider how busily some insects have been shown to be engaged in conveying anther-dust from flower to flower, especially bees, flower-eating beetles, and the like, it seems a most enigmatical problem how it can happen that promiscuous alliances between distinct species are not perpetually occurring.

How continually do we observe the bees diligently employed in collecting the red and yellow powder by which the stamens of flowers are covered, loading it on their hind legs, and carrying it to their hive for the purpose of feeding their young! In thus providing for their own progeny, these insects assist materially the process for fructification.* Few persons need be reminded that the stamens in certain plants grow on different blossoms from the pistils; and, unless the summit of the pistil be touched with the fertilizing dust, the fruit does not swell, nor the seed arrive at maturity. It is by the help of bees chiefly, that the development of the fruit of many such species is secured, the powder which they have collected from the stamens being unconsciously left by them in visiting the pistils.

How often, during the heat of a summer's day, do we see the males of diœcious plants, such as the yew-tree, standing separate from the females, and sending off into the air, upon the slightest breath of wind, clouds of buoyant pollen! That the zephyr should so rarely intervene to fecundate the plants of one species with the anther-dust of others, seems almost to realize the converse of the miracle believed by the credulous herdsmen of the Lusitanian mares —

> Ore omnes versæ in Zephyrum, stant rupibus altis
> Exceptantque leves auras: et sæpe sine ullis
> Conjugiis, vento gravidæ, mirabile dictu.†

But, in the first place, it appears that there is a natural aversion in plants, as well as in animals, to irregular sexual unions; and in most of the successful experiments in the animal and vegetable world, some violence has been used in order to procure impregnation. The stigma imbibes, slowly and reluctantly, the granules of the pollen of another species, even when it is abundantly covered with it; and if it happen that, during this period, ever so slight a quantity of the anther-dust of its own species alight upon it, this is instantly absorbed, and the effect of the foreign pollen destroyed. Besides, it does not often happen that the male and female organs of fructification, in different species, arrive at a state of maturity at precisely the same time. Even where such synchronism does prevail, so that a cross impregnation is effected, the chances are very numerous against the establishment of a hybrid race.

If we consider the vegetable kingdom generally, it must be recollected that even of the seeds which are well ripened, a great part are either eaten by insects, birds, and other animals, or decay for want of room and opportunity to germinate. Unhealthy plants are the first which are cut off by causes prejudicial to the species, being usually stifled by more vigorous individuals of their own kind. If, therefore, the relative fecundity or hardiness of hybrids be in the least degree inferior, they cannot maintain their footing for many generations, even if they were ever produced beyond one generation in a wild state. In the universal struggle for existence, the right of the strongest eventually prevails; and the strength and durability of a race depends mainly on its prolificness, in which hybrids are acknowledged to be deficient.

---

* See Barton on the Geography of Plants, p. 67. † Georg. lib. iii. 273.

Centaurea hybrida, a plant which never bears seed, and is supposed to be produced by the frequent intermixture of two well-known species of Centaurea, grows wild upon a hill near Turin. *Ranunculus lacerus*, also sterile, has been produced accidentally at Grenoble, and near Paris, by the union of two Ranunculi; but this occurred in gardens.*

Mr. Herbert's experiments.—Mr. Herbert, in one of his ingenious papers on mule plants, endeavours to account for their non-occurrence in a state of nature, from the circumstance that all the combinations that were likely to occur have already been made many centuries ago, and have formed the various species of botanists; but in our gardens, he says, whenever species, having a certain degree of affinity to each other, are transported from different countries, and brought for the first time into contact, they give rise to hybrid species.† But we have no data, as yet, to warrant the conclusion, that a single permanent hybrid race has ever been formed, even in gardens, by the intermarriage of two allied species brought from distant habitations. Until some fact of this kind is fairly established, and a new species, capable of perpetuating itself in a state of perfect independence of man, can be pointed out, it seems reasonable to call in question entirely this hypothetical source of new species. That varieties do sometimes spring up from cross-breeds, in a natural way, can hardly be doubted; but they probably die out even more rapidly than races propagated by grafts or layers.

Opinion of De Candolle.—De Candolle, whose opinion on a philosophical question of this kind deserves the greatest attention, has observed, in his Essay on Botanical Geography, that the *varieties* of plants range themselves under two general heads: those produced by external circumstances, and those formed by hybridity. After adducing various arguments to show that neither of these causes can explain the permanent diversity of plants indigenous in different regions, he says, in regard to the crossing of races, "I can perfectly comprehend without altogether sharing the opinion, that, where many species of the same genera occur near together, hybrid species may be formed, and I am aware that the great number of species of certain genera which are found in particular regions may be explained in this manner; but I am unable to conceive how any one can regard the same explanation as applicable to species which live naturally at great distances. If the three larches, for example, now known in the world, lived in the same localities, I might then believe that one of them was the produce of the crossing of the two others; but I never could admit that the Siberian species has been produced by the crossing of those of Europe and America. I see, then, that there exist, in organized beings, permanent differences which cannot be referred to any one of the actual causes of variation, and these differences are what constitute *species*." *

---

* Hon. and Rev. W. Herbert, Hort. Trans., vol. iv. p. 41.

Reality of species confirmed by the phenomena of hybrids.—The most decisive arguments, perhaps, amongst many others, against the probability of the derivation of permanent species from cross-breeds, are to be drawn from the fact alluded to by De Candolle, of species having a close affinity to each other occurring in distinct botanical provinces, or countries inhabited by groups of distinct species of indigenous plants; for in this case naturalists, who are not prepared to go the whole length of the transmutationists, are under the necessity of admitting that, in some cases, species which approach very near to each other in their characters, were so created from their origin; an admission fatal to the idea of its being a general law of nature that a few original types only should be formed, and that all intermediate races should spring from the intermixture of those stocks.

This notion, indeed, is wholly at variance with all that we know of hybrid generation; for the phenomena entitle us to affirm, that had the types been at first somewhat distant, *no cross-breeds would ever have been produced*, much less those prolific races which we now recognise as distinct species.

In regard, moreover, to the permanent propagation of hybrid races among animals, insuperable difficulties present themselves, when we endeavour to conceive the blending together of the different instincts and propensities of two species, so as to insure the preservation of the intermediate race. The common mule, when obtained by human art, may be protected by the power of man; but, in a wild state, it would not have precisely the same wants either as the horse or the ass; and if, in consequence of some difference of this kind, it strayed from the herd, it would soon be hunted down by beasts of prey, and destroyed.

If we take some genus of insects, such as the bee, we find that each of the numerous species has some difference in its habits, its mode of collecting honey, or constructing its dwelling, or providing for its young, and other particulars. In the case of the common hive bee, the workers are described, by Kirby and Spence, as being endowed with no less than thirty distinct instincts.† So also we find that, amongst a most numerous class of spiders, there are nearly as many different modes of spinning their webs as there are species. When we recollect how complicated are the relations of these instincts with co-existing species, both of the animal and vegetable kingdoms, it is scarcely possible to imagine that a bastard race could spring from the union of two of these species, and retain just so much of the qualities of each parent stock as to preserve its ground in spite of the dangers which surround it.

We might also ask, if a few generic types alone have been *created* among insects, and the intermediate species have proceeded from hybridity, where are those original types, combining, as they ought to do, the elements of all the instincts which have made their appearance in the numerous derivative races? So also in regard to animals of all classes, and of plants; if species are in general of hybrid origin, where are the stocks which combine in themselves the habits, properties, and organs, of which all the intervening species ought to afford us mere modifications?

---

* Essai Elémentaire, &c., 3me partie. † Intr. to Entom. vol. ii. p. 504. ed. 1817.

Recapitulation of the arguments from hybrids. — I shall now conclude this subject by summing up, in a few words, the results to which I have been led by the consideration of the phenomena of hybrids. It appears that the aversion of individuals of distinct species to the sexual union is common to animals and plants; and that it is only when the species approach near to each other in their organization and habits, that any offspring are produced from their connexion. Mules are of extremely rare occurrence in a state of nature, and no examples are yet known of their having procreated in a wild state. But it has been proved, that hybrids are not universally sterile, provided the parent stocks have a near affinity to each other, although the continuation of the mixed race, for several generations, appears hitherto to have been obtained only by crossing the hybrids with individuals of pure species; an experiment which by no means bears out the hypothesis that a true hybrid race could ever be permanently established.

Hence we may infer, that aversion to sexual intercourse is, in general, a good test of the distinctness of original stocks, or of *species;* and the procreation of hybrids is a proof of the very near affinity of species. Perhaps, hereafter, the number of generations for which hybrids may be continued, before the race dies out (for it seems usually to degenerate rapidly), may afford the zoologist and botanist an experimental test of the difference in the degree of affinity of allied species.

I may also remark, that if it could have been shown that a single permanent species had ever been produced by hybridity (of which there is no satisfactory proof), it might certainly have lent some countenance to the notions of the ancients respecting the gradual deterioration of created things, but none whatever to Lamarck's theory of their progressive perfectibility; for observations have hitherto shown that there is a tendency in mule animals and plants to degenerate in organization.

It was before remarked, that the theory of progressive development arose partly from an attempt to ingraft the doctrines of the transmutationists upon one of the most popular generalizations in geology. But we have seen in the ninth chapter, that the modern researches of geologists have broken at many points the chain of evidence once supposed to exist in favour of the doctrine, that, at each successive period in the earth's history, animals and plants of a higher grade, or more complex organisation, have been created. The recent origin of man, and the absence of all signs of any rational being holding an analogous relation to former states of the animate world, affords one, and perhaps in the present state of science the only argument of much weight in support of the hypothesis of a progressive scheme; but none whatever in favour of the fancied evolution of one species out of another.

Theory of the gradation in intellect as shown by the facial angle.—When the celebrated anatomist, Camper, first attempted to estimate the degrees of sagacity of different animals, and of the races of man, by the measurement of the facial angle, some speculators were bold enough to affirm, that certain Simiæ, or apes, differed as little from the more savage races of men, as those do from the human race in general; and that a scale might be traced from "apes with foreheads villanous low" to the African variety of the human species, and from that to the European. The facial angle was measured by drawing a line from the prominent centre of the forehead to the most advanced part of the lower jaw-bone, and observing the angle which it made with the horizontal line; and it was affirmed, that there was a regular series of such angles from birds to the mammalia.

The gradation from the dog to the monkey was said to be perfect, and from that again to man. One of the ape tribe has a facial angle of 42°; and another, which approximated nearest to man in figure, an angle of 50°. To this succeeds (longo sed proximus intervallo) the head of the African negro, which, as well as that of the Kalmuc, forms an angle of 70°; while that of the European contains 80°. The Roman painters preferred the angle of 95°; and the character of beauty and sublimity, so striking in some works of Grecian sculpture, as in the head of the Apollo, and in the Medusa of Sisocles, is given by an angle which amounts to 100°. *

A great number of valuable facts and curious analogies in comparative anatomy were brought to light during the investigations which were made by Camper, John Hunter, and others, to illustrate this scale of organization; and their facts and generalizations must not be confounded with the fanciful systems which White and others deduced from them. ‡

That there is some connexion between an elevated and capacious forehead, in certain races of men, and a large development of the intellectual faculties, seems highly probable; and that a low facial angle is frequently accompanied with inferiority of mental powers, is certain; but the attempt to trace a graduated scale of intelligence through the different species of animals accompanying the modifications of the form of the skull, is a mere visionary speculation. It has been found necessary to exaggerate the sagacity of the ape tribe at the expense of the dog; and strange contradictions have arisen in the conclusions deduced from the structure of the elephant; some anatomists being disposed to deny the quadruped the intelligence which he really possesses, because they found that the volume of his brain was small in comparison to that of the other mammalia; while others were inclined to magnify extravagantly the superiority of his intellect, because the vertical height of his skull is so great when compared to its horizontal length.

---

* Prichard's Phys. Hist. of Mankind, vol. i. p. 159.

† Ch. White on the Regular Gradation in Man, &c. 1799.

Different races of men are all of one species.—It would be irrelevant to our subject if we were to enter into a farther discussion on these topics; because, even if a graduated scale of organization and intelligence could have been established, it would prove nothing in favour of a tendency, in each species, to attain a higher state of perfection. I may refer the reader to the writings of Blumenbach, Prichard, Lawrence, and more recently Latham*, for convincing proofs that the varieties of form, colour, and organization of different races of men, are perfectly consistent with the generally received opinion, that all the individuals of the species have originated from a single pair; and, while they exhibit in man as many diversities of a physiological nature as appear in any other species, they confirm also the opinion of the slight deviation from a common standard of which species are capable.

The power of existing and multiplying in every latitude, and in every variety of situation and climate, which has enabled the great human family to extend itself over the habitable globe, is partly, says Lawrence, the result of physical constitution, and partly of the mental prerogative of man. If he did not possess the most enduring and flexible corporeal frame, his arts would not enable him to be the inhabitant of all climates, and to brave the extremes of heat and cold, and the other destructive influences of local situation.† Yet, notwithstanding this flexibility of bodily frame, we find no signs of indefinite departure from a common standard, and the intermarriages of individuals of the most remote varieties are not less fruitful than between those of the same tribe.

Tiedemann on the brain of the fœtus in vertebrated animals.—There is yet another department of anatomical discovery to which I must allude, because it has appeared to some persons to afford a distant analogy, at least, to that progressive development by which some of the inferior species may have been gradually perfected into those of more complex organization. Tiedemann found, and his discoveries have been most fully confirmed and elucidated by M. Serres, that the brain of the fœtus, in the highest class of vertebrated animals, assumes, in succession, forms, bearing a certain degree of resemblance to those which belong to fishes, reptiles, and birds, before it acquires the additions and modifications which are peculiar to the mammiferous tribe; so that, in the passage from the embryo to the perfect mammifer, there is a typical representation, it is said, of all those transformations which the primitive species are supposed to have undergone, during a long series of generations, between the present period and the remotest geological era.

---

* R. G. Latham, The Nat. Hist. of the Varieties of Man, 8vo. London, 1850.

† Lawrence, Lectures on Phys. Zool. and Nat. Hist. of Man, p. 192. Ed. 1823.

"If you examine the brain of the mammalia," says M. Serres, "in an early stage of uterine life, you perceive the cerebral hemispheres consolidated, as in fish, in two vesicles, isolated one from the other; at a later period, you see them affect the configuration of the cerebral hemispheres of reptiles; still later again, they present you with the forms of those of birds; finally they acquire, at the era of birth, and sometimes later, the permanent forms which the adult mammalia present.

"The cerebral hemispheres, then, arrive at the state which we observe in the higher animals only by a series of successive metamorphoses. If we reduce the whole of these evolutions to four periods, we shall see, that in the first are born the cerebral lobes of fishes; and this takes place homogeneously in all classes. The second period will give us the organization of reptiles; the third, the brain of birds; and the fourth, the complex hemispheres of mammalia.

"If we could develop the different parts of the brain of the inferior classes, we should make, in succession, a reptile out of a fish, a bird out of a reptile, and a mammiferous quadruped out of a bird. If, on the contrary, we could starve this organ in the mammalia, we might reduce it successively to the condition of the brain of the three inferior classes.

"Nature often presents us with this last phenomenon in monsters, but never exhibits the first. Among the various deformities which organized beings may experience, they never pass the limits of their own classes to put on the forms of the class above them. Never does a fish elevate itself so as to assume the form of the brain of a reptile; nor does the latter ever attain that of birds; nor the bird that of the mammifer. It may happen that a monster may have two heads; but the conformation of the brain always remains circumscribed narrowly within the limits of its class."*

Dr. Clark of Cambridge, in a memoir on "Fœtal Development" (1845), has shown that the concurrent labours of Valentin, Ratke, and Bischoff disprove the reality of the supposed anatomical analogy between the embryo condition of certain organs in the higher orders, and the perfect structure of the same organs in animals of an inferior class. The hearts and brains, for example, of birds and mammals do not pass through forms which are permanent in fishes and reptiles; there is only just so much resemblance as may point to a unity of plan running through the organization of the whole series of vertebrated animals; but which lends no support whatever to the notion of a gradual transmutation of one species into another; least of all of the passage, in the course of many generations, from an animal of a more simple to one of a more complex structure.

Recapitulation.—For the reasons, therefore, detailed in this and the two preceding chapters, we may draw the following inferences in regard to the reality of *species* in nature:—

---

* E. R. A. Serres, Anatomie comparée du Cerveau, illustrated by numerous plates, tome i. 1824.

1st. That there is a capacity in all species to accommodate themselves, to a certain extent, to a change of external circumstances, this extent varying greatly, according to the species.

2ndly. When the change of situation which they can endure is great, it is usually attended by some modifications of the form, colour, size, structure, or other particulars; but the mutations thus superinduced are governed by constant laws, and the capability of so varying, forms part of the permanent specific character.

3dly. Some acquired peculiarities, of form, structure, and instinct, are transmissible to the offspring; but these consist of such qualities and attributes only as are intimately related to the natural wants and propensities of the species.

4thly. The entire variation from the original type, which any given kind of change can produce, may usually be effected in a brief period of time, after which no farther deviation can be obtained by continuing to alter the circumstances, though ever so gradually; indefinite divergence, either in the way of improvement or deterioration, being prevented, and the least possible excess beyond the defined limits being fatal to the existence of the individual.

5thly. The intermixture of distinct species is guarded against by the aversion of the individuals composing them to sexual union, or by the sterility of the mule offspring. It does not appear that true hybrid races have ever been perpetuated for several generations, even by the assistance of man; for the cases usually cited relate to the crossing of mules with individuals of pure species, and not to the intermixture of hybrid with hybrid.

6thly. From the above considerations, it appears that species have a real existence in nature; and that each was endowed, at the time of its creation, with the attributes and organization by which it is now distinguished.

CHAPTER XXXVII.

LAWS WHICH REGULATE THE GEOGRAPHICAL DISTRIBUTION OF SPECIES.

Analogy of climate not attended with identity of species — Botanical geography — Stations — Habitations — Distinct provinces of indigenous plants — Vegetation of islands — Marine vegetation — In what manner plants become diffused — Effects of wind, rivers, marine currents — Agency of animals — Many seeds pass through the stomachs of animals and birds undigested — Agency of man in the dispersion of plants, both voluntary and involuntary — Its analogy to that of the inferior animals.

Next to determining the question whether species have a real existence, the consideration of the laws which regulate their geographical distribution is a subject of primary importance to the geologist. It is only by studying these laws with attention, by observing the positions which groups of species occupy at present, and inquiring how these may be varied in the course of time by migrations, by changes in physical geography, and other causes, that we can hope to learn whether the duration of species be limited, or in what manner the state of the animate world is affected by the endless vicissitudes of the inanimate.

Different regions inhabited by distinct species. — That different regions of the globe are inhabited by entirely distinct animals and plants, is a fact which has been familiar to all naturalists since Buffon first pointed out the want of *specific* indentity between the land quadrupeds of America and those of the Old World. The same phenomenon has, in later times, been forced in a striking manner upon our attention, by the examination of New Holland, where the indigenous species of animals and plants were found to be, almost without exception, distinct from those known in other parts of the world.

But the extent of this parcelling out of the globe amongst different *nations*, as they have been termed, of plants and animals — the universality of a phenomenon so extraordinary and unexpected, may be considered as one of the most interesting facts clearly established by the advance of modern science.

Scarcely fourteen hundred species of plants appear to have been known and described by the Greeks, Romans, and Arabians. At present, more than three thousand species are enumerated, as natives of our own island.* In other parts of the world there have been now collected (1846) upwards of 100,000 species, specimens of which are preserved in European herbariums. It was not to be supposed, therefore, that the ancients should have acquired any correct notions respecting what may be called the geography of plants, although the influence of climate on the character of the vegetation could hardly have escaped their observation.

---

* Barton's Lectures on the Geography of Plants, p. 2. 1827.

Antecedently to investigation, there was no reason for presuming that the vegetable productions, growing wild in the eastern hemisphere, should be unlike those of the western, in the same latitude; nor that the plants of the Cape of Good Hope should be unlike those of the south of Europe; situations where the climate is little dissimilar. The contrary supposition would have seemed more probable, and we might have anticipated an almost perfect identity in the animals and plants which inhabit corresponding parallels of latitude. The discovery, therefore, that each separate region of the globe, both of the land and water, is occupied by distinct groups of species, and that most of the exceptions to this general rule may be referred to disseminating causes now in operation, is eminently calculated to excite curiosity, and to stimulate us to seek some hypothesis respecting the first introduction of species which may be reconcileable with such phenomena.

Botanical geography.—A comparison of the *plants* of different regions of the globe affords results more to be depended upon in the present state of our knowledge than those relating to the animal kingdom, because the science of botany is more advanced, and probably comprehends a great proportion of the total number of the vegetable productions of the whole earth. Humboldt, in several eloquent passages of his Personal Narrative, was among the first to promulgate philosophical views on this subject. Every hemisphere, says this traveller, produces plants of different species; and it is not by the diversity of climates that we can attempt to explain why equinoctial Africa has no Laurineæ, and the New World no Heaths; why the Calceolariæ are found only in the southern hemisphere; why the birds of the continent of India glow with colours less splendid than the birds of the hot parts of America: finally, why the tiger is peculiar to Asia, and the ornithorhynchus to New Holland.*

"We can conceive," he adds, "that a small number of the families of plants, for instance, the Musaceæ and the Palms, cannot belong to very cold regions, on account of their internal structure and the importance of certain organs; but we cannot explain why no one of the family of Melastomas vegetates north of the parallel of thirty degrees; or why no rose-tree belongs to the southern hemisphere. Analogy of climates is often found in the two continents without identity of productions."†

The luminous essay of De Candolle on "Botanical Geography" presents us with the fruits of his own researches and those of Humboldt, Brown, and other eminent botanists, so arranged, that the principal phenomena of the distribution of plants are exhibited in connexion with the causes to which they are chiefly referrible.‡ "It might not, perhaps, be difficult," observes this writer, "to find two points, in the United States and in Europe, or in equinoctial America and Africa, which present all the same circumstances: as, for example, the same temperature, the same height above the sea, a similar soil, an equal dose of humidity; yet nearly all, *perhaps all*, the plants in these two similar localities shall be distinct. A certain degree of analogy, indeed, of aspect, and even of structure, might very possibly be discoverable between the plants of the two localities in question; but the *species* would in general be different. Circumstances, therefore, different from those which now determine the *stations*, have had an influence on the *habitations* of plants."

---

* Pers. Nar., vol. v. p. 180.

† Ibid.

‡ Essai Elémentaire de Géographie Botanique. Extrait du 18me vol. du Dict. des Sci. Nat.

Stations and habitations of plants.—As I shall frequently have occasion to speak of the *stations* and *habitations* of plants in the technical sense in which the terms are used in the above passage, I may remind the geologist that station indicates the peculiar nature of the locality where each species is accustomed to grow, and has reference to climate, soil, humidity, light, elevation above the sea, and other analogous circumstances; whereas, by habitation is meant a general indication of the country where a plant grows wild. Thus the *station* of a plant may be a salt-marsh, a hill-side, the bed of the sea, or a stagnant pool. Its *habitation* may be Europe, North America, or New Holland, between the tropics. The study of stations has been styled the topography, that of habitations the geography, of botany. The terms thus defined, express each a distinct class of ideas, which have been often confounded together, and which are equally applicable in zoology.

In farther illustration of the principle above alluded to, that difference of longitude, independently of any influence of temperature, is accompanied by a great, and sometimes a complete, diversity in the species of plants, De Candolle observes, that, out of 2891 species of phænogamous plants described by Pursh, in the United States, there are only 385 which are found in northern or temperate Europe. MM. Humboldt and Bonpland, in all their travels through equinoctial America, found only twenty-four species (these being all Cyperaceæ and Gramineæ) common to America and any part of the Old World. They collected, it is true, chiefly on the mountains, or the proportion would have been larger; for Dr. J. Hooker informs me that many tropical plants of the New World are identical with African species. Nevertheless, the general discordance of these Floras is very striking. On comparing New Holland with Europe, Mr. Brown ascertained that, out of 4100 species, discovered in Australia, there were only 166 common to Europe, and of this small number there were some few which may have been transported thither by man. Almost all of the 166 species were cryptogamic, and the rest consist, in nearly every case, of phænogamous plants which also inhabit intervening regions.

But what is still more remarkable, in the more widely separated parts of the ancient continent, notwithstanding the existence of an uninterrupted land-communication, the diversity in the specific character of the respective vegetations is almost as striking. Thus there is found one assemblage of species in China, another in the countries bordering the Black Sea and the Caspian, a third in those surrounding the Mediterranean, a fourth in the great platforms of Siberia and Tartary, and so forth.

The distinctness of the groups of indigenous plants, in the same parallel of latitude, is greatest where continents are disjoined by a wide expanse of ocean. In the northern hemisphere, near the pole, where the extremities of Europe, Asia, and America unite or approach near to one another, a considerable number of the same species of plants are found, common to the three continents. But it has been remarked, that these plants, which are thus so widely diffused in the arctic regions, are also found in the chain of the Aleutian islands, which stretch almost across from America to Asia, and which may probably have served as the channel of communication for the partial blending of the Floras of the adjoining regions. It has, indeed, been observed to be a general rule, that plants found at two points very remote from each other occur also in places intermediate.

Dr. J. Hooker informs me that in high latitudes in the southern ocean, in spite of the great extent of the sea, Floras of widely disconnected islands contain many species in common. Perhaps icebergs, transporting to vast distances not only stones, but soil with the seeds of plants, may explain this unusually wide diffusion of insular plants.

In islands very distant from continents the total number of plants is comparatively small; but a large proportion of the species are such as occur nowhere else. In so far as the Flora of such islands is not peculiar to them, it contains, in general, species common to the nearest main lands.* The islands of the great southern ocean exemplify these rules; the easternmost containing more American, and the western more Indian plants.† Madeira and Teneriffe contain many species, and even entire genera, peculiar to them; but they have also plants in common with Portugal, Spain, the Azores, and the north-west coast of Africa.‡

In the Canaries, out of 533 species of phænogamous plants, it is said that 310 are peculiar to these islands, and the rest identical with those of the African continent; but in the Flora of St. Helena, which is so far distant even from the western shores of Africa, there have been found, out of thirty native species of the phænogamous class, only *one or two* which are to be found in any other part of the globe. On the other hand, of sixty cryptogamic plants, collected by Dr. J. Hooker in the same island, twelve only were peculiar.

The natural history of the Galapagos archipelago, described by Mr. Darwin, affords another very instructive illustration of the laws governing the geographical distribution of plants and animals in islands. This group consists of ten principal islands, situated in the

---

* Prichard, vol. i. p. 36. Brown, Appendix to Flinders.

† Forster, Observations, &c.

‡ Humboldt, Pers. Nar., vol. i. p. 270. of the translation. Prichard, Phys. Hist. of Mankind, vol. i. p. 37.

Pacific Ocean, under the equator, about 600 miles westward of the coast of South America. As they are all formed of volcanic rocks, many of the craters, of which there are about 2000 in number, having a very fresh aspect, we may regard the whole as much more modern in origin than the mass of the adjoining continent; yet neither has the Flora or Fauna been derived from South America, but consists of species, for the most part, indigenous, yet stamped with a character decidedly South American.

What is still more singular, there is a difference between the species inhabiting the different islands. Of flowering plants, for example, there are 185 species at present known, and forty cryptogamic, making together 225. One hundred of the former class are new species, probably confined to this archipelago; and of the rest, ten at least have been introduced by man. Of twenty-one species of *Compositæ*, all but one are peculiar, and they belong to twelve genera, no less than ten of which genera are confined to the Galapagos. Dr. Hooker observes, that the type of this Flora has an undoubted relation to that of the western side of South America, and he detects in it no affinity with that of the numerous islands scattered over other parts of the Pacific. So in regard to the birds, reptiles, land-shells, and insects, this archipelago, standing as it does in the Pacific Ocean, is zoologically part of America. Although each small island is not more than fifty or sixty miles apart, and most of them are in sight of each other, formed of precisely the same rocks, rising nearly to an equal height, and placed under a similar climate, they are tenanted each by a different set of beings, the tortoises, mocking-thrushes, finches, beetles, scarcely any of them ever ranging over the whole, and often not even common to any two of the islands.

"The archipelago," says Mr. Darwin, "is a little world within itself, or rather a satellite attached to America; whence it has derived a few stray colonists, and has received the general character of its indigenous productions. One is astonished," he adds, "at the amount of creative force displayed on so many small, barren, and rocky islands, and still more so, at its diverse, yet analogous action on points so near each other. I have said that the Galapagos archipelago might be called a satellite attached to America, but it should rather be called a group of satellites physically similar, organically distinct, yet intimately related to each other, and all related in a marked, though much lesser degree, to the great American continent."*

Number of botanical provinces.—De Candolle has enumerated twenty great botanical provinces inhabited by indigenous or aboriginal plants; and although many of these contain a variety of species which are common to several others, and sometimes to places very remote, yet the lines of demarcation are, upon the whole, astonishingly well defined.† Nor is it likely that the bearing of the evidence on which these general views are founded will ever be materially affected, since they are already confirmed by the examination of nearly one hundred thousand species of plants.

---

* Voyage of the Beagle, 2d edition, 1845, p. 377.

† See a farther subdivision, by which twenty-seven provinces are made, by M. Alph. De Candolle, son of De Candolle. Monogr. des Campanulées. Paris, 1830.

The entire change of opinion which the contemplation of these phenomena has brought about is worthy of remark. The first travellers were persuaded that they should find, in distant regions, the plants of their own country, and they took a pleasure in giving them the same names. It was some time before this illusion was dissipated; but so fully sensible did botanists at last become of the extreme smallness of the number of phænogamous plants common to different continents, that the ancient Floras fell into disrepute. All grew diffident of the pretended identifications; and we now find that every naturalist is inclined to examine each supposed exception with scrupulous severity.* If they admit the fact, they begin to speculate on the mode whereby the seeds may have been transported from one country into the other, or inquire on which of two continents the plant was indigenous, assuming that a species, like an individual, cannot have two birthplaces.

Marine vegetation.—The marine vegetation is divisible into different systems, like those prevailing on the land; but they are much fewer, as we might have expected, the temperature of the ocean being more uniform than that of the atmosphere, and consequently the dispersion of species from one zone to another being less frequently checked by the intervention of uncongenial climates. The proportion also of land to sea throughout the globe being small, the migration of marine plants is not so often stopped by barriers of land, as is that of the terrestrial species by the ocean. The number of hydrophytes, as they are termed, is very considerable, and their stations are found to be infinitely more varied than could have been anticipated; for while some plants are covered and uncovered daily by the tide, others live at the depth of several hundred feet. Among the known provinces of Algæ, we may mention, 1st, The north circumpolar, from lat 60° N. to the pole; 2dly, The North Atlantic or the region of Fucus proper and Delesseriæ, extending from lat. 40° N. to lat. 60° N.; 3dly, That of the Mediterranean, which may be regarded as a sub-region of the *fourth* or warmer temperate zone of the Atlantic, between lat. 23° N. and lat. 40° N.; 5thly, The Tropical Atlantic, in which Sargassum, Rhodomelia, Corallinea, and Siphonia abound; 6thly, The South Atlantic, where the Fucus reappears; 7thly, The Antartic American, comprehending from Chili to Cape Horn, the Falkland Islands, and thence round the world south of latitude 50° S.; 8thly, The Australian and New Zealand, which is very peculiar, being characterized, among other generic forms, by Cystoseiriæ and Fuceæ; 9thly, The Indian Ocean and Red Sea; and, 10thly, The Chinese and Japanese seas.† In addition to the above provinces, there are several others not yet well determined in the Pacific Ocean and elsewhere. There are, however, many species which range through several of these geographical regions of subaqueous vegetation, being common to very remote countries; as, for example, to the coasts of Europe and the United States, and others, to Cape Horn and Van Diemen's Land, the same plants extending also for the most part to the New Zealand sea. Of the *species* strictly antarctic (excluding the New Zealand and Tasmanian groups) Dr. Hooker has identified not less than a fifth part of the whole with British Algæ! Yet is there a much smaller proportion of cosmopolite species among the Algæ than among the terrestrial cellular plants, such as lichens, mosses, and Hepaticæ.

---

* De Candolle. Essai Elémen. de Géog. Botan., p. 45.

† I am indebted for the above sketch of distinct regions of algæ to my friend Dr. Joseph Hooker, who refers the botanical student to the labours of Dr. Harvey, of Trinity College, Dublin.

It must always be borne in mind, that the distinctness alluded to between the provinces, whether of subaqueous or terrestrial plants, relates strictly to *species*, and not to forms. In regard to the numerical preponderance of certain forms, and many peculiarities of internal structure, there is usually a marked agreement in the vegetable productions of districts placed in corresponding latitudes, and under similar physical circumstances, however remote their position. Thus there are innumerable points of analogy between the vegetation of the Brazils, equinoctial Africa, and India; and there are also points of difference wherein the plants of these regions are distinguishable from all extra-tropical groups. But there is a very small proportion of the entire number of species common to the three continents. The same may be said, if we compare the plants of the United States with that of the middle of Europe: the species are distinct, but the forms are often so analogous, as to have been styled "geographical representatives." There are very few *species* of phænogamous plants, says Dr. J. Hooker, common to Van Diemen's Land, New Zealand, and Fuegia, but a great many *genera*, and some of them are confined to these three distant regions of the southern hemisphere, being in many instances each severally represented by a single species. The same naturalist also observe that the southern temperate as well as the antarctic regions, possess each of them representatives of some of the genera of the analogous climates of the opposite hemisphere; but very few of the species are identical unless they be such as are equally diffused over other countries, or which inhabit the Andes, by the aid of which they have evidently effected their passage southwards.

Manner in which plants become diffused.— Winds.—Let us now consider what means of diffusion, independently of the agency of man, are possessed by plants, whereby, in the course of ages, they may be enabled to stray from one of the botanical provinces above mentioned to another, and to establish new colonies at a great distance from their birthplace.

The principal of the inanimate agents provided by nature for scattering the seeds of plants over the globe, are the movements of the atmosphere and of the ocean, and the constant flow of water from the mountains to the sea. To begin with the winds: a great number of seeds are furnished with downy and feathery appendages, enabling them, when ripe, to float in the air, and to be wafted easily to great distances by the most gentle breeze. Other plants are fitted for dispersion by means of an attached wing, as in the case of the fir tree, so that they are caught up by the wind as they fall from the cone, and are carried to a distance. Amongst the comparatively small number of plants known to Linnæus, no less than 138 genera are enumerated as having winged seeds.

As winds often prevail for days, weeks, or even months together, in the same direction, these means of transportation may sometimes be without limits; and even the heavier grains may be borne through considerable spaces, in a very short time, during ordinary tempests; for strong gales, which can sweep along grains of sand, often move at the rate of about forty miles an hour, and if the storm be very violent, at the rate of fifty-six miles.* The hurricanes of tropical regions, which root up trees and throw down buildings, sweep along at the rate of ninety miles an hour†; so that, for however short a time they prevail, they may carry even the heavier fruits and seeds over friths and seas of considerable width, and doubtless are often the means of introducing into islands the vegetation of adjoining continents. Whirlwinds are also instrumental in bearing along heavy vegetable substances to considerable distances. Slight ones may frequently be observed in our fields, in summer, carrying up haycocks into the air, and then letting fall small tufts of hay far and wide over the country; but they are sometimes so powerful as to dry up lakes and ponds, and to break off the boughs of trees, and carry them up in a whirling column of air.

Franklin tells us, in one of his letters, that he saw, in Maryland, a whirlwind which began by taking up the dust which lay in the road, in the form of a sugar-loaf with the pointed end downwards, and soon after grew to the height of forty or fifty feet, being twenty or thirty in diameter. It advanced in a direction contrary to the wind; and although the rotatory motion of the column was surprisingly rapid, its onward progress was sufficiently slow to allow a man to keep pace with it on foot. Franklin followed it on horseback, accompanied by his son, for three quarters of a mile, and saw it enter a wood, where it twisted and turned round large trees with surprising force. These were carried up in a spiral line, and were seen flying in the air, together with boughs and innumerable leaves, which, from their height, appeared reduced to the apparent size of flies. As this cause operates at different intervals of time throughout a great portion of the earth's surface, it may be the means of bearing not only plants but insects, land testacea and their eggs, with many other species of animals, to points which they could never otherwise have reached, and from which they may then begin to propagate themselves again as from a new centre.

Distribution of crypto[illegible] [illegible]nts. — It has been found that a great numerical proporti[illegible] the [illegible] to the limitation of species to certain [illegible] various tribes of cryptogamic plants. Linnæus observed that, as the germs of plants of this class, such as mosses, fungi, and lichens, consist of an impalpable powder, the particles of which are scarcely visible to the naked eye, there is no difficulty to account for their being dispersed throughout the atmosphere, and carried to every point of the globe, where there is a station fitted for them. Lichens in particular ascend to great elevations, sometimes growing two thousand feet above the line of perpetual snow, at the utmost limits of vegetation, and where the mean temperature is nearly at the freezing point. This elevated position must contribute greatly to facilitate the dispersion of those buoyant particles of which their fructification consists.*

---

* [illegible] ea.

Some have inferred, from the springing up of mushrooms whenever particular soils and decomposed organic matter are mixed together, that the production of fungi is accidental, and not analogous to that of perfect plants. But Fries, whose authority on these questions is entitled to the highest respect, has shown the fallacy of this argument in favour of the old doctrine of equivocal generation. "The sporules of fungi," says this naturalist, "are so infinite, that in a single individual of *Reticularia maxima*, I have counted above ten millions, and so subtile as to be scarcely visible, often resembling thin smoke; so light that they may be raised perhaps by evaporation into the atmosphere, and dispersed in so many ways by the attraction of the sun, by insects, wind, elasticity, adhesion, &c., that it is difficult to conceive a place from which they may be excluded."†

The club-moss called *Lycopodium cernuum* affords a striking example of a cryptogamous plant universally distributed over all equinoctial countries. It scarcely ever passes beyond the northern tropic, except in one instance, where it appears around the hot-springs in the Azores, although it is neither an inhabitant of the Canaries or of Madeira. Doubtless its microscopic sporules are every where present, ready to germinate on any spot where they can enjoy throughout the year the proper quantity of warmth, moisture, light, and other conditions essential to the species.

Almost every lichen brought home from the southern hemisphere by the antarctic expedition under Sir James Ross, amounting to no less than 200 species, was ascertained to be also an inhabitant of the northern hemisphere, and almost all of them European.

Agency of rivers and currents.—In considering, in the next place, the instrumentality of the aqueous agents of dispersion, I cannot do better than cite the words of one of our ablest botanical writers. "The mountain stream or torrent," observes Keith, "washes down to the valley the seeds which may accidentally fall into it, or which it may happen to sweep from its banks when it suddenly overflows them. The broad and majestic river, winding along the extensive plain, and traversing the continents of the world, conveys to the distance of many hundreds of miles the seeds that may have vegetated at its source. Thus the southern shores of the Baltic are visited by seeds which grew in the interior of Germany, and the western shores of the Atlantic by seeds that have been generated in the interior of America."* Fruits, moreover, indigenous to America and the West Indies, such as that of the *Mimosa scandens*, the cashew-nut, and others, have been known to be drifted across the Atlantic by the Gulf stream, on the western coasts of Europe, in such a state that they might have vegetated had the climate and soil been favourable. Among these the *Guilandina Bonduc*, a leguminous plant, is particularly mentioned, as having been raised from a seed found on the west coast of Ireland.†

---

* Linn., Tour in Lapland, vol. ii. p. 282.

† Fries, cited by Lindley, Introd. to Nat. Syst. of Botany.

Sir Hans Sloane states, that several kinds of beans cast ashore on the Orkney Isles, and Ireland, but none of which appear to have naturalized themselves, are derived from trees which grow in the West Indies, and many of them in Jamaica. He conjectures that they might have been conveyed by rivers into the sea, and then by the Gulf stream to greater distances, in the same manner as the sea-weed called *Lenticula marina*, or Sargasso, which grows on the rocks about Jamaica, is known to be "carried by the winds and current towards the coast of Florida, and thence into the North American ocean, where it lies very thick on the surface of the sea."‡

The absence of liquid matter in the composition of seeds renders them comparatively insensible to heat and cold, so that they may be carried without detriment through climates where the plants themselves would instantly perish. Such is their power of resisting the effects of heat, that Spallanzani mentions some seeds that germinated after having been boiled in water.§ Sir John Herschel informs me that he has sown at the Cape of Good Hope the seeds of the *Acacia lophanta* after they had remained for twelve hours in water of 140° Fahrenheit, and they germinated far more rapidly than unboiled seeds. He also states that an eminent botanist, Baron Ludwig, could not get the seeds of a species of cedar to grow at the Cape till they were thoroughly boiled.

When therefore, a strong gale, after blowing violently off the land for a time, dies away, and the seeds alight upon the surface of the waters, or wherever the ocean, by eating away the sea-cliffs, throws down into its waves plants which would never otherwise reach the shores, the tides and currents become active instruments in assisting the dissemination of almost all classes of the vegetable kingdom. The pandanus and many other plants have been distributed in this way over the islands of the Pacific. I have before called attention (p. 618.) to the interesting fact that one-fifth of all the algæ found in the antarctic regions in 1841–3, by Dr. J. Hooker, were of species common to the British seas. He has suggested that cold currents which prevail from Cape Horn to the equator, and are there met by other cold waters, may by their direct influence, as well as by their temperature, facilitate the passage of antarctic species to the Arctic Ocean. In like manner the migration of certain marine animals from the southern to the northern hemisphere may have been brought about by the same cause.

---

* System of Physiological Botany, vol. ii. p. 405.

† Brown, Append. to Tuckey, No. v. p. 481.

‡ Phil. Trans. 1696.

§ System of Physiological Botany, vol. ii. p. 403.

In a collection of six hundred plants from the neighbourhood of the river Zaire, in Africa, Mr. Brown found that thirteen species were also met with on the opposite shores of Guiana and Brazil. He remarked that most of these plants were found only on the lower parts of the river Zaire, and were chiefly such as produced seeds capable of retaining their vitality a long time in the currents of the ocean. Dr. J. Hooker informs me that after an examination of a great many insular floras, he has found that no one of the large natural orders is so rich in species common to other countries, as the Leguminosæ. The seeds in this order, which comprises the largest proportion of widely diffused littoral species, are better adapted than those of any other plants for water-carriage.

The migration of plants aided by islands.—Islands, moreover, and even the smallest rocks, play an important part in aiding such migrations; for when seeds alight upon them from the atmosphere, or are thrown up by the surf, they often vegetate, and supply the winds and waves with a repetition of new and uninjured crops of fruit and seeds. These may afterwards pursue their course through the atmosphere, or along the surface of the sea, in the same direction. The number of plants found at any given time on an islet affords us no test whatever of the extent to which it may have co-operated towards this end, since a variety of species may first thrive there and then perish, and be followed by other chance-comers like themselves. If neither St. Helena nor Ascension have promoted the botanical intercourse between the Old and New Worlds, we may easily account for the fact by remembering that they are not only extremely minute and isolated spots, but are also bounded by lofty and precipitous shores without beaches, where the seeds of foreign species could readily establish themselves.

Currents and winds in the arctic regions drift along icebergs covered with an alluvial soil, on which herbs and pine-saplings are seen growing, which may often continue to vegetate on some distant shore where the ice-island is stranded.

Dispersion of marine plants.—With respect to marine vegetation, the seeds, being in their native element, may remain immersed in water without injury for indefinite periods, so that there is no difficulty in conceiving the diffusion of species wherever uncongenial climates, contrary currents, and other causes do not interfere. All are familiar with the sight of the floating sea-weed.

> "Flung from the rock on ocean's foam to sail,
> Where'er the surge may sweep, the tempest's breath prevail."

Remarkable accumulations of that species of sea-weed generally known as gulf-weed, or sargasso, occur on each side of the equator in the Atlantic, Pacific, and Indian Oceans. Columbus and other navigators, who first encountered these banks of algæ in the Northern Atlantic, compared them to vast inundated meadows, and state that they retarded the progress of their vessels. The most extensive bank is a little west of the meridian of Fayal, one of the Azores, between latitudes 35° and 36°: violent north-winds sometimes prevail in this space, and drive the sea-weed to low latitudes, as far as the 24th or even the 20th degree.* Along the northern edge of the Gulf stream Dr. Hooker found *Fucus nodosus*, and *F. serratus*, which he traced all the way from lat. 36° N. to England.

The hollow pod-like receptacles in which the seeds of many algæ are lodged, and the filaments attached to the seed-vessels of others, seem intended to give buoyancy; and I may observe that these hydrophytes are in general *proliferous*, so that the smallest fragment of a branch can be developed into a perfect plant. The seeds, moreover, of the greater number of species are enveloped with a mucous matter like that which surrounds the eggs of some fish, and which not only protects them from injury, but serves to attach them to floating bodies or to rocks.

Agency of animals in the distribution of plants.—But we have as yet considered part only of the fertile resources of nature for conveying seeds to a distance from their place of growth. The various tribes of animals are busily engaged in furthering an object whence they derive such important advantages. Sometimes an express provision is found in the structure of seeds to enable them to adhere firmly by prickles, hooks, and hairs, to the coats of animals, or feathers of the winged tribe, to which they remain attached for weeks, or even months, and are borne along into every region whither birds or quadrupeds may migrate. Linnæus enumerates fifty genera of plants, and the number now known to botanists is much greater, which are armed with hooks, by which, when ripe, they adhere to the coats of animals. Most of these vegetables, he remarks, require a soil enriched with dung. Few have failed to mark the locks of wool hanging on the thorn-bushes, wherever the sheep pass, and it is probable that the wolf or lion never give chase to herbivorous animals without being unconsciously subservient to this part of the vegetable economy.

A deer has strayed from the herd when browsing on some rich pasture, when he is suddenly alarmed by the approach of his foe. He instantly takes to flight, dashing through many a thicket, and swimming across many a river and lake. The seeds of the herbs and shrubs which have adhered to his smoking flanks are washed off again by the waters. The thorny spray is torn off, and fixes itself in its hairy coat, until brushed off again in other thickets and copses. Even on the spot where the victim is devoured many of the seeds which he had swallowed immediately before the chase may be left on the ground uninjured, and ready to spring up in a new soil.

The passage, indeed, of undigested seeds through the stomachs of animals is one of the most efficient causes of the dissemination of plants, and is of all others, perhaps, the most likely to be overlooked. Few are ignorant that a portion of the oats eaten by a horse preserve their germinating faculty in the dung. The fact of their being still nutritious is not lost on the sagacious rook. To many, says Linnæus, it seems extraordinary, and something of a prodigy, that when a field is well tilled and sown with the best wheat, it frequently produces darnel or the wild oat, especially if it be manured with new dung; they do not consider that the fertility of the smaller seeds is not destroyed in the stomachs of animals.*

---

* Greville, Introduction to Algæ Britannicæ, p. 12.

Agency of birds. — Some birds of the order Passeres devour the seeds of plants in great quantities, which they eject again in very distant places, without destroying its faculty of vegetation: thus a flight of larks will fill the cleanest field with a great quantity of various kinds of plants, as the melilot trefoil (*Medicago lupulina*), and others whose seeds are so heavy that the wind is not able to scatter them to any distance.† In like manner, the blackbird and misselthrush, when they devour berries in too great quantities, are known to consign them to the earth undigested in their excrement.‡

Pulpy fruits serve quadrupeds and birds as food, while their seeds, often hard and indigestible, pass uninjured through the intestines, and are deposited far from their original place of growth in a condition peculiarly fit for vegetation.§ So well are the farmers, in some parts of England, aware of this fact, that when they desire to raise a quickset hedge in the shortest possible time, they feed turkeys with the haws of the common white-thorn (*Cratægus Oxyacantha*), and then sow the stones which are ejected in their excrement, whereby they gain an entire year in the growth of the plant.‖ Birds when they pluck cherries, sloes, and haws, fly away with them to some convenient place; and when they have devoured the fruit, drop the stone into the ground. Captain Cook, in his account of the volcanic island of Tanna, one of the New Hebrides, which he visited in his second voyage, makes the following interesting observation: — "Mr. Forster, in his botanical excursion this day, shot a pigeon, in the craw of which was a wild nutmeg."¶ It is easy, therefore, to perceive, that birds in their migrations to great distances, and even across seas, may transport seeds to new isles and continents.

The sudden deaths to which great numbers of frugivorous birds are annually exposed must not be omitted as auxiliary to the transportation of seeds to new habitations. When the sea retires from the shore, and leaves fruits and seeds on the beach, or in the mud of estuaries, it might, by the returning tide, wash them away again, or destroy them by long immersion; but when they are gathered by land birds which frequent the sea side, or by waders and water-fowl, they are often borne inland; and if the bird to whose crop they have been consigned is killed, they may be left to grow up far from the sea. Let such an accident happen but once in a century, or a thousand years, it will be sufficient to spread many of the plants from one continent to another; for in estimating the activity of these causes, we must not consider whether they act slowly in relation to the period of our observation, but in reference to the duration of species in general.

---

* Linnæus, Amœn. Acad., vol. ii. p. 409.

† Amœn. Acad., vol. iv. Essay 75. § 8.

‡ Ibid., vol. vi. § 22.

§ Smith's Introd. to Phys. and Syst. Botany, p. 304. 1807.

‖ This information was communicated to me by Professor Henslow, of Cambridge.

¶ Book iii. ch. iv.

Let us trace the operation of this cause in connection with others. A tempestuous wind bears the seeds of a plant many miles through the air, and then delivers them to the ocean; the oceanic current drifts them to a distant continent; by the fall of the tide they become the food of numerous birds, and one of these is seized by a hawk or eagle, which, soaring across hill and dale to a place of retreat, leaves, after devouring its prey, the unpalatable seeds to spring up and flourish in a new soil.

The machinery before adverted to, is so capable of disseminating seeds over almost unbounded spaces, that were we more intimately acquainted with the economy of nature, we might probably explain all the instances which occur of the aberration of plants to great distances from their native countries. The real difficulty which must present itself to every one who contemplates the present geographical distribution of species, is the small number of exceptions to the rule of the non-intermixture of different groups of plants. Why have they not, supposing them to have been ever so distinct originally, become more blended and confounded together in the lapse of ages?

Agency of man in the dispersion of plants.—But in addition to all the agents already enumerated as instrumental in diffusing plants over the globe, we have still to consider man—one of the most important of all. He transports with him, into every region, the vegetables which he cultivates for his wants, and is the involuntary means of spreading a still greater number which are useless to him, or even noxious. "When the introduction of cultivated plants," says De Candolle, "is of recent date, there is no difficulty in tracing their origin; but when it is of high antiquity, we are often ignorant of the true country of the plants on which we feed. No one contests the American origin of the maize or the potato; nor the origin, in the Old World, of the coffee-tree, and of wheat. But there are certain objects of culture, of very ancient date, between the tropics, such for example as the banana, of which the origin cannot be verified. Armies, in modern times, have been known to carry, in all directions, grain and cultivated vegetables from one extremity of Europe to the other; and thus have shown us how, in more ancient times, the conquests of Alexander, the distant expeditions of the Romans, and afterwards the crusades, may have transported many plants from one part of the world to the other."*

---

* De Candolle, Essai Elémen. &c., p. 50.

But, besides the plants used in agriculture, the number which have been naturalized by accident, or which man has spread unintentionally, is considerable. One of our old authors, Josselyn, gives a catalogue of such plants as had, in his time, sprung up in the colony since the English planted and kept cattle in New England. They were two-and-twenty in number. The common nettle was the first which the settlers noticed; and the plantain was called by the Indians "Englishman's foot," as if it sprung from their footsteps.*

"We have introduced every where," observes De Candolle, "some weeds which grow among our various kinds of wheat, and which have been received, perhaps, originally from Asia along with them. Thus, together with the Barbary wheat, the inhabitants of the south of Europe have sown, for many ages, the plants of Algiers and Tunis. With the wools and cottons of the East, or of Barbary, there are often brought into France the grains of exotic plants, some of which naturalize themselves. Of this I will cite a striking example. There is, at the gate of Montpellier, a meadow set apart for drying foreign wool, *after it has been washed.* There hardly passes a year without foreign plants being found naturalized in this drying-ground. I have gathered there *Centaurea parviflora*, *Psoralea palæstina*, and *Hypericum crispum*." This fact is not only illustrative of the aid which man lends inadvertently to the propagation of plants, but it also demonstrates the multiplicity of seeds which are borne about in the woolly and hairy coats of wild animals.

The same botanist mentions instances of plants naturalized in seaports by the ballast of ships; and several examples of others which have spread through Europe from botanical gardens, so as to have become more common than many indigenous species.

It is scarcely a century, says Linnæus, since the Canadian erigeron, or flea-bane, was brought from America to the botanical garden at Paris; and already the seeds have been carried by the winds so that it is diffused over France, the British islands, Italy, Sicily, Holland, and Germany.‡ Several others are mentioned by the Swedish naturalist, as having been dispersed by similar means. The common thorn-apple (*Datura Stramonium*), observes Willdenow, now grows as a noxious weed throughout all Europe, with the exception of Sweden, Lapland, and Russia. It came from the East Indies and Abyssinia to us, and was thus universally spread by certain quacks, who used its seeds as an emetic.‡ The same plant is now abundant throughout the greater part of the United States, along road-sides and about farm-yards. The yellow monkey-flower, *Mimulus luteus*, a plant from the north-west region of America, has now established itself in various parts of England, and is spreading rapidly.

In hot and ill-cultivated countries, such naturalizations take place more easily. Thus the *Chenopodium ambrosioides*, sown by Mr. Burchell on a point of St. Helena, multiplied so fast in four years as to become one of the commonest weeds in the island, and it has maintained its ground ever since 1845.*

---

* Quarterly Review. vol. xxx. p. 8.

† Essay on the Habitable Earth, Amœn Acad., vol. ii. p. 409.

‡ Principles of Botany, p. 389.

The most remarkable proof, says De Candolle, of the extent to which man is unconsciously the instrument of dispersing and naturalizing species, is found in the fact, that in New Holland, America, and the Cape of Good Hope, the aboriginal European species exceed in number all the others which have come from any distant regions; so that, in this instance, the influence of man has surpassed that of all the other causes which tend to disseminate plants to remote districts. Of nearly 1600 British flowering plants, it is supposed that about 300 species are naturalized; but a large proportion of these would perish with the discontinuance of agriculture.

Although we are but slightly acquainted, as yet, with the extent of our instrumentality in naturalizing species, yet the facts ascertained afford no small reason to suspect that the number which we introduce unintentionally exceeds all those transported by design. Nor is it unnatural to suppose that the functions, which the inferior beings, extirpated by man, once discharged in the economy of nature, should devolve upon the human race. If we drive many birds of passage from different countries, we are probably required to fulfil their office of carrying seeds, eggs of fish, insects, mollusks, and other creatures, to distant regions: if we extirpate quadrupeds, we must replace them not merely as consumers of the animal and vegetable substances which they devoured, but as disseminators of plants, and of the inferior classes of the animal kingdom. I do not mean to insinuate that the very same changes which man brings about, would have taken place by means of the agency of other species, but merely that he supersedes a certain number of agents; and so far as he disperses plants unintentionally, or against his will, his intervention is strictly analogous to that of the species so extirpated.

I may observe, moreover, that if, at former periods, the animals inhabiting any given district have been partially altered by the extinction of some species, and the introduction of others, whether by new creations or by immigration, a change must have taken place in regard to the particular plants conveyed about with them to foreign countries. As, for example, when one set of migratory birds is substituted for another, the countries from and to which seeds are transported are immediately changed. Vicissitudes, therefore, analogous to those which man has occasioned, may have previously attended the springing up of new relations between species in the vegetable and animal worlds.

It may also be remarked, that if man is the most active agent in enlarging, so also is he in circumscribing the geographical boundaries of particular plants. He promotes the migration of some, he retards that of other species; so that, while in many respects he appears to be exerting his power to blend and confound the various provinces of indigenous species, he is, in other ways, instrumental in obstructing the fusion into one group of the inhabitants of contiguous provinces.

---

* Principles of Botany, p. 389.

Thus, for example, when two botanical regions exist in the same great continent, such as *the European region*, comprehending the central parts of Europe, and those surrounding the Mediterranean, and *the Oriental region*, as it has been termed, embracing the countries adjoining the Black Sea and the Caspian, the interposition between these of thousands of square miles of cultivated lands opposes a new and powerful barrier against the mutual interchange of indigenous plants. Botanists are well aware that garden plants naturalize and diffuse themselves with great facility in comparatively unreclaimed countries, but spread themselves slowly and with difficulty in districts highly cultivated. There are many obvious causes for this difference; by drainage and culture the natural variety of stations is diminished, and those stray individuals by which the passage of a species from one fit station to another is effected, are no sooner detected by the agriculturist, than they are uprooted as weeds. The larger shrubs and trees, in particular, can scarcely ever escape observation, when they have attained a certain size, and will rarely fail to be cut down if unprofitable.

The same observations are applicable to the interchange of the insects, birds, and quadrupeds of two regions situated like those above alluded to. No beasts of prey are permitted to make their way across the intervening arable tracts. Many birds, and hundreds of insects, which would have found some palatable food amongst the various herbs and trees of the primeval wilderness, are unable to subsist on the olive, the vine, the wheat, and a few trees and grasses favoured by man. In addition, therefore, to his direct intervention, man, in this case, operates indirectly to impede the dissemination of plants, by intercepting the migration of animals, many of which would otherwise have been active in transporting seeds from one province to another.

Whether, in the vegetable kingdom, the influence of man will tend, after a considerable lapse of ages, to render the geographical range of *species in general* more extended, as De Candolle seems to anticipate, or whether the compensating agency above alluded to will not counterbalance the exceptions caused by our naturalizations, admits at least of some doubt. In the attempt to form an estimate on this subject, we must be careful not to underrate, or almost overlook, as some appear to have done, the influence of man in checking the diffusion of plants, and restricting their distribution to narrower limits.

CHAPTER XXXVIII.

LAWS WHICH REGULATE THE GEOGRAPHICAL DISTRIBUTION OF SPECIES—*continued.*

Geographical distribution of animals—Buffon on specific distinctness of quadrupeds of Old and New World—Doctrine of "natural barriers"—Different regions of indigenous mammalia—Europe—Africa—India, and Indian Archipelago—Australia—North and South America—Quadrupeds in islands—Range of the Cetacea—Dispersion of quadrupeds—their powers of swimming—Migratory instincts—Drifting of animals on ice-floes—On floating islands of drift-timber—Migrations of Cetacea—Habitations of birds—Their migrations and facilities of diffusion—Distribution of reptiles, and their power of dissemination.

Geographical distribution of animals.—ALTHOUGH in speculating on "philosophical possibilities," said Buffon, "the same temperature might have been expected, all other circumstances being equal, to produce the same beings in different parts of the globe, both in the animal and vegetable kingdoms, yet is is an undoubted fact, that when America was discovered, its indigenous quadrupeds were all dissimilar to those previously known in the Old World. The elephant, the rhinoceros, the hippopotamus, the camelopard, the camel, the dromedary, the buffalo, the horse, the ass, the lion, the tiger, the apes, the baboons, and a number of other mammalia, were nowhere to be met with on the new continent; while in the old, the American species, of the same great class, were nowhere to be seen—the tapir, the lama, the pecari, the jaguar, the couguar, the agouti, the paca, the coati, and the sloth."

These phenomena, although few in number relatively to the whole animate creation, were so striking and so positive in their nature, that the great French naturalist caught sight at once of a general law in the geographical distribution of organic beings, namely, the limitation of groups of distinct species to regions separated from the rest of the globe by certain natural barriers. It was, therefore, in a truly philosophical spirit that, relying on the clearness of the evidence obtained respecting the larger quadrupeds, he ventured to call in question the identifications announced by some contemporary naturalists of species of animals said to be common to the southern extremities of America and Africa.*

The migration of quadrupeds from one part of the globe to another, observes Dr. Prichard, is prevented by uncongenial climates and the branches of the ocean which intersect continents. "Hence, by a reference to the geographical site of countries, we may divide the earth into a certain number of regions fitted to become the abodes of particular groups of animals, and we shall find, on inquiry, that each of these provinces, thus conjecturally marked out, is actually inhabited by a distinct nation of quadrupeds."* It will be observed that the language of Buffon respecting "natural barriers," which has since been so popular, would be wholly without meaning if the geographical distribution of organic beings had not led naturalists to adopt very generally *the doctrine of specific centres*, or, in other words, to believe that each species, whether of plant or animal, originated in a single birth-place. Reject this view, and the fact that not a single native quadruped is common to Australia, the Cape of Good Hope, and South America, can in no ways be explained by adverting to the wide extent of intervening ocean, or to the sterile deserts, or the great heat or cold of the climates, through which each species must have passed, before it could migrate from one of those distant regions to another. It might fairly be asked of one who talked of impassable barriers, why the same kangaroos, rhinoceroses, or lamas, should not have been created simultaneously in Australia, Africa, and South America! The horse, the ox, and the dog, although foreign to these countries until introduced by man, are now able to support themselves there in a wild state, and we can scarcely doubt that many of the quadrupeds at present peculiar to Australia, Africa, and South America, might have continued in like manner to inhabit each of the three continents had they been indigenous or could they once have got a footing there as new colonists.

---

* Buffon, vol. v.—On the Virginian Opossum.

At the same time every zoologist will be willing to concede, that even if the departure of each species from a single centre had not appeared to be part of the plan of Nature, the range of species in general must have become limited, under the influence of a variety of causes, especially in the class of terrestrial mammalia. Scarcely any one of these could be expected to retain as fair a claim to the title of cosmopolite as man, although even the human race, fitted as it is by its bodily constitution and intellectual resources to spread very widely over the earth, is far from being strictly cosmopolite. It is excluded both from the arctic and antarctic circles, from many a wide desert and the summits of many mountain-chains; and lastly, from three-fourths of the globe covered by water, where there are large areas very prolific in animal life, even in the highest order of the vertebrate class. But the *habitations* of species are, as before stated, in reference to plants (see above, p. 614.), circumscribed by causes different from those which determine their *stations*, and these causes are clearly connected with the time and place of the original creation of each species.

As the names and characters of land quadrupeds are much better known to the general reader than those of other great families of the animal kingdom, I shall select this class to exemplify the zoological provinces into which species are divisible, confining myself, however, to those facts which may help to elucidate some principle, or rule apparently followed by the Author of Nature, in regard to that "mystery of mysteries," the first peopling of the earth with living beings.* First, then, the *European region* comprehends, besides Europe, the borders of the Mediterranean, and even the north of Africa, and extends into Asia, beyond the Oural mountains and the Caspian. Although the species are almost all peculiar, the number of characteristic *genera* is remarkably small. The bear, the fox, the hare, the rabbit, the deer, and almost every European form is found equally in several of the other large provinces of mammalia, where the species are distinct. Even the mole (*Talpa*), although confined to the northern parts of the old world, ranges eastwards, as far as the Himalaya mountains.

---

* Prichard's Phys. Hist. of Mankind, vol. i. p. 54.

2dly. The *African* Fauna, on the other hand, is singlarly rich in generic forms, not met with in a living state in any other region. The hippopotamus, for example, of which two very distinct species are known, the giraffe, the Chimpanzee, the blue-faced baboon, the four-fingered monkeys (*Colobus*), many carnivora, such as *Proteles*, allied to the hyæna, and a multitude of other forms, are exclusively African. A few of the species inhabiting the northern confines of this continent, such as the dromedary, lion, and jackall, are also common to Asia; and a much larger number of *forms* belong equally to the great Asiatic province, the species being distinct. The elephant, for example, of Africa is smaller, has a rounder head, and larger ears than the Indian one, and has only three instead of four nails on each hind foot. In like manner, not one of three African species of rhinoceros agrees with one of the three Indian kinds.

3dly. The *Southern* region of *Africa*, where that continent extends into the temperate zone, constitutes another separate zoological province, surrounded as it is on three sides by the ocean, and cut off from the countries of milder climate in the northern hemisphere, by the intervening torrid zone. In many instances, this region contains the same genera which are found in temperate climates to the northward of the line: but then the southern are different from the northern species. Thus, in the south we find the quagga and the zebra; in the north, the horse, the ass, and the jiggetai of Asia.

The south of Africa is spread out into fine level plains from the tropic to the Cape. In this region, says Pennant, besides the horse genus, of which five species have been found, there are also peculiar species of rhinoceros, the hog, and the hyrax, among pachydermatous races; and amongst the ruminating, the Cape buffalo, and a variety of remarkable antelopes, as the springbok, the oryx, the gnou, the leucophoë, the pygarga, and several others.†

4thly. The assemblage of quadrupeds in *Madagascar* affords a striking illustration of the laws before alluded to, as governing the distribution of species in islands. Separated from Africa by the Mozambique channel, which is 300 miles wide, Madagascar forms, with two or three small islands in its immediate vicinity, a zoological province by itself, all the species except one, and nearly all the genera, being peculiar. The only exception consists of a small insectivorous quadruped (*Centetes*), found also in the Mauritius, to which place it is supposed to have been taken in ships. The most characteristic feature of this remarkable fauna consists in the number of quadrumana of the Lemur family, no less than six genera of those monkeys being exclusively met with in this island, and a seventh genus of the same, called *Galago*, which alone has any foreign representative, being found, as we might from analogy have anticipated, in the nearest main land. Had the species of quadrupeds in Madagascar agreed with those of the contiguous parts of Africa, as do those of England with the rest of Europe, the naturalist would have inferred that there had been a land communication since the period of the coming in of the existing quadrupeds, whereas we may now conclude that the Mozambique channel has constituted an insuperable barrier to the fusion of the continental fauna with that of the great island during the whole period that has elapsed since the living species were created.

---

* In the above enumeration of the leading zoological provinces of land quadrupeds I have been most kindly assisted by Mr. Waterhouse of the British Museum, author of a most able and comprehensive work on the "Natural History of the Mammalia," now in the course of publication. London, Bailliere, 1846.

† Pennant's Hist. of Quadrupeds, cited by Prichard, Phys. Hist. of Mankind, vol. i. p. 66.

5thly. Another of the great nations of terrestrial mammalia is that of *India*, containing a great variety of peculiar forms, such as the sloth-bear (*Prochilus*), the musk-deer (*Moscus*), the nylghau, the gibbon or long-armed ape, and many others. 6thly. A portion of the islands of the *Indian archipelago* might, perhaps, be considered by some geologists as an appendage of the same province. In fact, we find in the large islands of Java, Sumatra, and Borneo the same genera, for the most part, as on the continent of India, and some of the same species, *e.g.* the tapir (*Tapirus Malayanus*), the rhinoceros of Sumatra, and some others. Most of the species, however, are distinct, and each island has many, and even a few genera, peculiar to itself. Between eighty and ninety species are known to inhabit Java, and nearly the same number occur in Sumatra. Of these, more than half are common to the two islands. Borneo, which is much less explored, has yielded already upwards of sixty species, more than half of which are met with either in Java, or Sumatra. Of the species inhabiting Sumatra and not found in Java, Borneo contains the greater portion. Upon the whole, if these three large islands were united and a fusion of their respective indigenous mammalia should take place, they would present a fauna related to that of continental India, and comprising about as many species as we might expect from analogy to discover in an area of equal extent. The Philippine Islands are peopled with another assemblage of species generically related to the great Indian type.

7thly. But the islands of Celebes, Amboina, Timor, and New *Guinea*, constitute a different region of mammalia more allied to the Australian type, as having an intermixture of marsupial quadrupeds, yet showing an affinity also to the Indian in such forms as the deer (*Cervus*), the weasel (*Viverra*), the pig (*Sus*), the Macaque monkey (*Circopithecus*), and others. As we proceed in a south-westerly direction, from Celebes to Amboina and thence to New Guinea, we find the Indian types diminishing in number, and the Australian (*i. e.* marsupial forms) increasing. Thus in New Guinea seven species of pouched quadrupeds have been detected, and among them two singular tree-kangaroos; yet only one species of the whole seven, viz. the flying opossum (*Petaurus ariel*), is common to the Indian archipelago and the main land of Australia. The greater zoological affinity, therefore, between the latter and the New Guinea fauna, although it seems in some way connected with geographical proximity, is not to be explained simply by the mutual migration of species from the one to the other.

8thly. When *Australia* was discovered, its land quadrupeds, belonging almost exclusively to the marsupial or pouched tribe, such as the kangaroos, wombats, flying opossums, kangaroo-rats, and others, some feeding on herbs and fruits, others carnivorous, were so novel in their structure and aspect, that they appeared to the naturalist almost as strange as if they were the inhabitants of some other planet. We learn from the recent investigations of Mr. Waterhouse*, that no less than 170 species of marsupial quadrupeds have now been determined, and of the whole number all but thirty-two are exclusively restricted to Australia. Of these thirty-two, nine belong to the islands in the Indian archipelago before mentioned, and the other twenty-three are all species of opossum inhabiting the tropical parts of South America, or a few of them extending into Mexico and California, and one, the Virginian opossum, into the United States.

9thly. It only remains for me to say something of the mammiferous fauna of *North* and *South America*. It has often been said that, where the three continents of Asia, Europe, and North America, approach very near to each other towards the pole, the whole arctic region forms one zoological and botanical province. The narrow straits which separate the old and new world are frozen over in winter, and the distance is farther lessened by intervening islands. Many plants and animals of various classes have accordingly spread over all the arctic lands, being sometimes carried in the same manner as the polar bear, when it is drifted on floating ice from Greenland to Iceland. But on a close inspection of the arctic mammalia, it has been found of late years that a very small number of the American species are identical with those of Europe or Asia. The genera are, in great part, the same or nearly allied; but the species are rarely identical, and are often very unlike, as in the case of the American badger and that of Europe. Some of the *genera* of arctic America, such as the musk ox (*Ovibos*), are quite peculiar, and the distinctness of the fauna of the great continents goes on increasing in proportion as we trace them southwards, or as they recede farther from each other, and become more and more separated by the ocean. At length we find that the three groups of tropical mammalia, belonging severally to America, Africa, and India, have not a single species in common.

---

* Natural History of the Mammalia, vol. i., on the Marsupials. London, Bailliere. 1846.

The predominant influence of climate over all the other causes which limit the range of species in the mammalia is perhaps nowhere so conspicuously displayed as in North America. The arctic fauna, so admirably described by Sir John Richardson, has scarcely any species in common with the fauna of the state of New York, which is 600 miles farther south, and comprises about forty distinct mammifers. If again we travel farther south about 600 miles, and enter another zone, running east and west, in South Carolina, Georgia, Alabama, and the contiguous states, we again meet with a new assemblage of land quadrupeds, and this again differs from the fauna of Texas, where frosts are unknown. It will be observed that on this continent there are no great geographical barriers running east and west, such as high snow-clad mountains, barren deserts, or wide arms of the sea, capable of checking the free migration of species from north to south. But notwithstanding the distinctness of those zones of indigenous mammalia, there are some species, such as the buffalo (*Bison Americanus*), the racoon (*Procyon lotor*), and the Virginian opossum (*Didelphis Virginiana*), which have a wider habitation, ranging almost from Canada to the Gulf of Mexico; but they form exceptions to the general rule. The opossum of Texas (*Didelphis canerivora*) is different from that of Virginia, and other species of the same genus inhabit westward of the Rocky Mountains, in California, for example, where almost all the mammalia differ from those in the United States.

10thly. The *West Indian* land quadrupeds are not numerous, but several of them are peculiar; and 11thly, *South America* is the most distinct, with the exception of Australia, of all the provinces into which the mammalia can be classed geographically. The various genera of monkeys, for example, belong to the family Platyrrhini, a large natural division of the quadrumana, so named from their widely separated nostrils. They have a peculiar dentition, and many of them prehensile tails, and are entirely unknown in other quarters of the globe. The sloths and armadillos, the true blood-sucking bats or vampyres (*Phyllostomidæ*), the capybara, the largest of the rodents, the carnivorous coati-mondi (*Nasua*), and a great many other forms, are also exclusively characteristic of South America.

"In Peru and Chili," says Humboldt, "the region of the grasses, which is at an elevation of from 12,300 to 15,400 feet, is inhabited by crowds of lama, guanaco, and alpaca. These quadrupeds, which here represent the genus camel of the ancient continent, have not extended themselves either to Brazil or Mexico; because, during their journey, they must necessarily have descended into regions that were too hot for them."* In this passage it will be seen that the doctrine of "specific centres" is tacitly assumed.

---

* Description of the Equatorial Regions.

Quadrupeds in Islands.—Islands remote from continents, especially those of small size, are either destitute of quadrupeds, except such as have been conveyed to them by man, or contain species peculiar to them. In the Galapagos archipelago no indigenous quadrupeds were found except one mouse, which is supposed to be distinct from any hitherto found elsewhere. A peculiar species of fox is indigenous in the Falkland Islands, and a rat in New Zealand, which last country, notwithstanding its magnitude, is destitute of other mammalia, except bats, and these, says Dr. Prichard, may have made their way along the chain of islands which extend from the shores of New Guinea far into the Southern Pacific. The same author remarks, that among the various groups of fertile islands in the Pacific, no quadrupeds have been met with except the rat and a few bats as above mentioned, and the dog and hog, which appear to have been conveyed thither by the natives from New Guinea. "Rats are to be found even on some desert islands, whither they may have been conveyed by canoes which have occasionally approached the shore. It is known, also, that rats occasionally swim in large numbers to considerable distances."*

Geographical range of the Cetacea.—It is natural to suppose that the geographical range of the different species of Cetacea should be less correctly ascertained than that of the terrestrial mammifers. It is, however, well known that the whales which are obtained by our fishers in the South Seas are distinct from those of the North; and the same dissimilarity has been found in all the other marine animals, of the same class, so far as they have yet been studied by naturalists.

Dispersion of quadrupeds. — Let us now inquire what facilities the various land quadrupeds enjoy of spreading themselves over the surface of the earth. In the first place, as their numbers multiply, all of them, whether they feed on plants, or prey on other animals, are disposed to scatter themselves gradually over as wide an area as is accessible to them. But before they have extended their migrations over a large space, they are usually arrested either by the sea, or a zone of uncongenial climate, or some lofty and unbroken chain of mountains, or a tract already occupied by a hostile and more powerful species.

Their powers of swimming.—Rivers and narrow friths can seldom interfere with their progress; for the greater part of them swim well, and few are without this power when urged by danger and pressing want. Thus, amongst beasts of prey, the tiger is seen swimming about among the islands and creeks in the delta of the Ganges, and the jaguar traverses with ease the largest streams in South America.† The bear, also, and the bison, cross the current of the Mississippi. The popular error, that the common swine cannot escape by swimming when thrown into the water, has been contradicted by several curious and well-authenticated instances during the floods in Scotland of 1829. One pig, only six months old, after having been carried down from

---

* Prichard, Phys. Hist. of Mankind, vol. i. p. 75.

† Buffon, vol. v. p. 204.

Garmouth to the bar at the mouth of the Spey, a distance of a quarter of a mile, swam four miles eastward to Port Gordon, and landed safe. Three others, of the same age and litter, swam, at the same time, five miles to the west, and landed at Blackhill.*

In an adult and wild state, these animals would doubtless have been more strong and active, and might, when hard pressed, have performed a much longer voyage. Hence islands remote from the continent may obtain inhabitants by casualties which, like the late storms in Morayshire, may only occur once in many centuries, or thousands of years, under all the same circumstances. It is obvious that powerful tides, winds, and currents may sometimes carry along quadrupeds capable, in like manner, of preserving themselves for hours in the sea, to very considerable distances; and in this way, perhaps, the tapir (*Tapir Indicus*) may have become common to Sumatra and the Malayan peninsula.

To the elephant, in particular, the power of crossing rivers is essential in a wild state, for the quantity of food which a herd of these animals consumes renders it necessary that they should be constantly moving from place to place. The elephant crosses the stream in two ways. If the bed of the river be hard, and the water not of too great a depth, he fords it. But when he crosses great rivers, such as the Ganges and the Niger, the elephant swims deep, so deep, that the end of his trunk only is out of the water; for it is a matter of indifference to him whether his body be completely immersed, provided he can bring the tip of his trunk to the surface, so as to breathe the external air.

Animals of the deer kind frequently take to the water, especially in the rutting season, when the stags are seen, swimming for several leagues at a time, from island to island, in search of the does, especially in the Canadian lakes; and in some countries where there are islands near the sea-shore, they fearlessly enter the sea and swim to them. In hunting excursions, in North America, the elk of that country is frequently pursued for great distances through the water.

The large herbivorous animals, which are gregarious, can never remain long in a confined region, as they consume so much vegetable food. The immense herds of bisons (*Bos Americanus*) which often, in the great valleys of the Mississippi and its tributaries, blacken the surface of the prairie lands, are continually shifting their quarters, followed by wolves, which prowl about in their rear. "It is no exaggeration," says Mr. James, "to assert, that in one place, on the banks of the Platte, at least ten thousand bisons burst on our sight in an instant. In the morning, we again sought the living picture; but upon all the plain, which last evening was so teeming with noble animals, not one remained."†

Migratory instincts.—Besides the disposition common to the individuals of every species slowly to extend their range in search of food, in proportion as their numbers augment, a migratory instinct often developes itself in an extraordinary manner, when, after an unusually prolific season, or upon a sudden scarcity of provisions, great multitudes are threatened by famine. It may be useful to enumerate some examples of these migrations, because they may put us upon our guard against attributing a high antiquity to a particular species merely because it is diffused over a great space: they show clearly how soon, in a state of nature, a newly created species might spread itself, in every direction, from a single point.

---

* [illegible] T. D. Lauder, Bart., on the [illegible] Morayshire, Aug. 1829, p. 302, [illegible]dition.

† Expedition from Pittsburg to the Rocky Mountains, vol. ii. p. 153.

In very severe winters, great numbers of the black bears of America migrate from Canada into the United States; but in milder seasons, when they have been well fed, they remain and hybernate in the north.* The rein-deer, which, in Scandinavia, can scarcely exist to the south of the sixty-fifth parallel, descends, in consequence of the greater coldness of the climate, to the fiftieth degree in Chinese Tartary, and often roves into a country of more southern latitude than any part of England.

In Lapland, and other high latitudes, the common squirrels, whenever they are compelled, by want of provisions, to quit their usual abodes, migrate in amazing numbers, and travel directly forwards, allowing neither rocks nor forests, nor the broadest waters to turn them from their course. Great numbers are often drowned in attempting to pass friths and rivers. In like manner the small Norway rat sometimes pursues its migrations in a straight line across rivers and lakes; and Pennant informs us, that when the rats, in Kamtschatka, become too numerous, they gather together in the spring, and proceed in great bodies westward, swimming over rivers, lakes, and arms of the sea. Many are drowned or destroyed by water-fowl or fish. As soon as they have crossed the river Penginsk, at the head of the gulf of the same name, they turn southward, and reach the rivers Judoma and Okotsk by the middle of July; a district more than 800 miles distant from their point of departure.

The lemings, also, a small kind of rat, are described as natives of the mountains of Kolen, in Lapland; and once or twice in a quarter of a century they appear in vast numbers, advancing along the ground, and "devouring every green thing." Innumerable bands

Fig. 97.



The Leming, or Lapland Marmot (Mus Lemmus, Linn.).

---

* Richardson's Fauna Boreali-Americana, p. 16.

march from the Kolen, through Nordland and Finmark, to the Western Ocean, which they immediately enter; and after swimming about for some time, perish. Other bands take their route through Swedish Lapland, to the Bothnian Gulf, where they are drowned in the same manner. They are followed in their journeys by bears, wolves, and foxes, which prey upon them incessantly. They generally move in lines, which are about three feet from each other, and exactly parallel, going directly forward through rivers and lakes; and when they meet with stacks of hay or corn, gnawing their way through them instead of passing round.* These excursions usually precede a rigorous winter, of which the lemings seem in some way forewarned.

Vast troops of the wild ass, or *onager* of the ancients, which inhabit the mountainous deserts of Great Tartary, feed, during the summer, in the tracts east and north of Lake Aral. In the autumn they collect in herds of hundreds, and even thousands, and direct their course towards Persia, to enjoy a warm retreat during winter.† Bands of two or three hundred quaggas, a species of wild ass, are sometimes seen to migrate from the tropical plains of southern Africa to the vicinity of the Malaleveen River. During their migrations they are followed by lions, who slaughter them night by night.‡

The migratory swarms of the springbok, or Cape antelope, afford another illustration of the rapidity with which a species under certain circumstances may be diffused over a continent. When the stagnant pools of the immense deserts south of the Orange River dry up, which often happens after intervals of three or four years, myriads of these animals desert the parched soil, and pour down like a deluge on the cultivated regions near the Cape. The havoc committed by them resembles that of the African locusts; and so crowded are the herds, that "the lion has been seen to walk in the midst of the compressed phalanx with only as much room between him and his victims as the fears of those immediately around could procure by pressing outwards." §

Dr. Horsfield mentions a singular fact in regard to the geographical distribution of the *Mydaus meliceps*, an animal intermediate between the polecat and badger. It inhabits Java, and is "confined exclusively to those mountains which have an elevation of more than seven thousand feet above the level of the ocean; on these it occurs with the same regularity as many plants. The long-extended surface of Java, abounding with conical points which exceed this elevation, affords many places favourable for its resort. On ascending these mountains, the traveller scarcely fails to meet with this animal, which, from its peculiarities, is universally known to the inhabitants of these elevated tracts, while to those of the plains it is as strange as an

---

* Phil. Trans., vol. ii. p. 872.

† Wood's Zoography, vol. i. p. 11.

‡ On the authority of Mr. Campbell. Library of Entert. Know., Menageries, vol. i. p. 152.

§ Cuvier's Animal Kingdom by Griffiths, vol. ii. p. 109. Library of Entertaining Knowledge, Menageries, vol. i. p. 366.

Fig. 98.



Mydaus meliceps, or badger-headed Mydaus. Length, including the tail, 16 inches.

animal from a foreign county. In my visits to the mountainous districts, I uniformly met with it; and, as far as the information of the natives can be relied on, it is found on all the mountains."*

Now, if asked to conjecture how the Mydaus arrived at the elevated regions of each of these isolated mountains, we might say that, before the island was peopled by man, by whom their numbers are now thinned, they may occasionally have multiplied so as to be forced to collect together and migrate: in which case, notwithstanding the slowness of their motions, some few would succeed in reaching another mountain, some twenty, or even, perhaps, fifty miles distant; for although the climate of the hot intervening plains would be unfavourable to them, they might support it for a time, and would find there abundance of insects on which they feed. Volcanic eruptions, which, at different times have covered the summits of some of those lofty cones with sterile sand and ashes, may have occasionally contributed to force on these migrations.

Drifting of animals on ice-floes.—The power of the terrestrial mammalia to cross the sea is very limited, and it was before stated that the same species is scarcely ever common to districts widely separated by the ocean. If there be some exceptions to this rule, they generally admit of explanation; for there are natural means whereby some animals may be floated across the water, and the sea may in the course of ages wear a wide passage through a neck of land, leaving individuals of a species on each side of the new channel. Polar bears are known to have been frequently drifted on the ice from Greenland to Iceland: they can also swim to considerable distances, for Captain Parry, on the return of his ships through Barrow's Straits, met with a bear swimming in the water about midway between the shores, which were about forty miles apart, and where no ice was in sight.† "Near the east coast of Greenland," observes Scoresby, "they have been seen on the ice in such quantities, that they were compared to flocks of sheep on a common; and they are often found on field-ice, above two hundred miles from the shore."‡ Wolves, in the arctic regions, often venture upon the ice near the shore, for the purpose of preying upon young seals, which they surprise when asleep. When these ice-floes get detached, the wolves are often carried out to sea; and though some may be drifted to islands or continents, the greater part of them perish, and have been often heard in this situation howling dreadfully, as they die by famine.[*]

---

* Horsfield, Zoological Researches in Java, No. ii., from which the figure is taken.

† Append. to Parry's Second Voyage, years 1819–20.

‡ Account of the Arctic Regions, vol. i. p. 518.

During the short summer which visits Melville Island, various plants push forth their leaves and flowers the moment the snow is off the ground, and form a carpet spangled with the most lively colours. These secluded spots are reached annually by herds of musk-oxen and rein-deer, which travel immense distances over dreary and desolate regions, to graze undisturbed on these luxuriant pastures.[†] The rein-deer often pass along in the same manner, by the chain of the Aleutian Islands, from Behring's Straits to Kamtschatka, subsisting on the moss found in these islands during their passage.[‡] But the musk-ox, notwithstanding its migratory habits, and its long journeys over the ice, does not exist either in Asia or Greenland.[§]

On floating islands of drift-wood. — Within the tropics there are no ice-floes; but, as if to compensate for that mode of transportation, there are floating islets of matted trees, which are often borne along through considerable spaces. These are sometimes seen sailing at the distance of fifty or one hundred miles from the mouth of the Ganges, with living trees standing erect upon them. The Amazon, the Congo, and the Orinoco, also produce these verdant rafts, which are formed in the manner already described when speaking of the great raft of the Atchafalaya, an arm of the Mississippi, where a natural bridge of timber, ten miles long, and more than two hundred yards wide, existed for more than forty years, supporting a luxuriant vegetation, and rising and sinking with the water which flowed beneath it.

On these green islets of the Mississippi, observes Malte-Brun, young trees take root, and the pistia and nenuphar display their yellow flowers: serpents, birds, and the cayman alligator, come to repose there, and all are sometimes carried to the sea, and engulphed in its waters.[||]

Spix and Martius relate that, during their travels in Brazil, they were exposed to great danger while ascending the Amazon in a canoe, from the vast quantity of drift-wood constantly propelled against them by the current; so much so, that their safety depended on the crew being always on the alert to turn aside the trunks of trees with long poles. The tops alone of some trees appeared above water, others had their roots attached to them with so much soil that they might be compared to floating islets. On these, say the travellers, we saw some very singular assemblages of animals, pursuing peacefully their uncertain way in strange companionship. On one raft were several grave-looking storks, perched by the side of a party of monkeys, who made comical gestures, and burst into loud cries, on seeing the canoe. On another was seen a number of ducks and divers, sitting by a group of squirrels. Next came down, upon the stem of a large rotten cedar tree, an enormous crocodile, by the side of a tiger-cat, both animals regarding each other with hostility and mistrust, but the saurian being evidently most at his ease, as conscious of his superior strength.*

---

[*] Turton in a note to Goldsmith's Nat. Hist., vol. iii. p. 43.

[†] Supplement to Parry's First Voyage of Discovery, p. 189.

[‡] Godman's American Nat. Hist., vol. i. p. 22.

[§] Dr. Richardson, Brit. Assoc. Report, vol. v. p. 161.

[||] System of Geography, vol. v. p. 157.

Similar green rafts, principally composed of canes and brushwood, are called "camelotes" on the Parana in South America; and they are occasionally carried down by inundations, bearing on them the tiger, cayman, squirrels, and other quadrupeds, which are said to be always terror-stricken on their floating habitation. No less than four tigers (pumas) were landed in this manner in one night at Monte Video, lat. 35° S., to the great alarm of the inhabitants, who found them prowling about the streets in the morning.†

In a memoir lately published, a naval officer relates that, as he returned from China by the eastern passage, he fell in, among the Moluccas, with several small floating islands of this kind, covered with mangrove trees interwoven with underwood. The trees and shrubs retained their verdure, receiving nourishment from a stratum of soil which formed a white beach round the margin of each raft, where it was exposed to the washing of the waves and the rays of the sun.‡ The occurrence of soil in such situations may easily be explained; for all the natural bridges of timber which occasionally connect the islands of the Ganges, Mississippi, and other rivers, with their banks, are exposed to floods of water, densely charged with sediment.

Captain W. H. Smyth informs me, that, when cruizing in the Cornwallis amidst the Philippine Islands, he has more than once seen, after those dreadful hurricanes called typhoons, floating masses of wood, with trees growing upon them; and ships have sometimes been in imminent peril, as often as these islands were mistaken for terra firma, when, in fact, they were in rapid motion.

It is highly interesting to trace, in imagination, the effects of the passage of these rafts from the mouth of a large river to some archipelago, such as those in the South Pacific, raised from the deep, in comparatively modern times, by the operations of the volcano and the earthquake, and the joint labours of coral animals and testacea. If a storm arise, and the frail vessel be wrecked, still many a bird and insect may succeed in gaining, by flight, some island of the newly formed group, while the seeds and berries of herbs and shrubs, which fall into the waves, may be thrown upon the strand. But if the surface of the deep be calm, and the rafts are carried along by a current, or wafted by some slight breath of air fanning the foliage of the green trees, it may arrive, after a passage of several weeks, at the bay of an island, into which its plants and animals may be poured out as from an ark, and thus a colony of several hundred new species may at once be naturalized.

---

* Spix and Martius, Reise, &c., vol. iii. pp. 1011. 1013.

† Sir W. Parish's Buenos Ayres, p. 187., and Robertson's Letters on Paraguay, p. 220.

‡ United Service Journal, No. xxiv. p. 697.

The reader should be reminded, that I merely advert to the transportation of these rafts as of extremely rare and accidental occurrence; but it may account, in tropical countries, for some of the rare exceptions to the general law of the confined range of mammiferous species.

Migrations of the Cetacea. — Many of the Cetacea, the whales of the northern seas for example, are found to desert one tract of the sea, and to visit another very distant, when they are urged by want of food, or danger. The seals also retire from the coast of Greenland in July, return again in September, and depart again in March, to return in June. They proceed in great droves northwards, directing their course where the sea is most free from ice, and are observed to be extremely fat when they set out on this expedition, and very lean when they come home again.*

Species of the Mediterranean, Black Sea, and Caspian identical. — Some naturalists have wondered that the sea-calves, dolphins, and other marine mammalia of the Mediterranean and Black Sea, should be identical with those found in the Caspian: and among other fanciful theories, they have suggested that they may dive through subterranean conduits, and thus pass from one sea into the other. But as the occurrence of wolves and other noxious animals, on both sides of the British Channel, was adduced, by Verstegan and Desmarest, as one of many arguments to prove that England and France were once united; so the correspondence of the aquatic species of the inland seas of Asia with those of the Black Sea tends to confirm the hypothesis, for which there are abundance of independent geological data, that those seas were connected together by straits at no remote period of the earth's history.

Geographical Distribution and Migrations of Birds.

I shall now offer a few observations on some of the other divisions of the animal kingdom. Birds, notwithstanding their great locomotive powers, form no exception to the general rules already laid down; but, in this class, as in plants and terrestrial quadrupeds, different groups of species are circumscribed within definite limits. We find, for example, one assemblage in the Brazils, another in the same latitudes in Central Africa, another in India, and a fourth in New Holland. Of twenty-six different species of land birds found in the Galapagos archipelago, all, with the exception of one, are distinct from those inhabiting other parts of the globe †; and in other archipelagos a single island sometimes contains a species found in no other spot on the whole earth; as is exemplified in some of the parrot tribe. In this extensive family, which are, with few exceptions, inhabitants

---

* Krantz, vol. i. p. 129., cited by Goldsmith, Nat. Hist., vol. iii. p. 260.

† Darwin's Journal, &c., p. 461.

:opical regions, the American group has not one in common with African, nor either of these with the parrots of India.*

.nother illustration is afforded by that minute and beautiful tribe, humming-birds. The whole of them are, in the first place, ıliar to the new world; but some species are confined to Mexico, le others exist only in some of the West India Islands, and have been found elsewhere in the western hemisphere. Yet there are :ies of this family which have a vast range, as the *Trochilus ımifrons* (or *Mellisuga Kingii*), which is found over a space of 0 miles on the west coast of South America, from the hot dry ntry of Lima to the humid forests of Tierra del Fuego. Captain g, during his survey in the years 1826–30, found this bird at Straits of Magellan, in the month of May — the depth of winter ucking the flowers of a large species of fuchsia, then in bloom, in midst of a shower of snow.

:he ornithology of our own country affords one well-known and king exemplification of the law of a limited specific range; for the ımon grouse (*Tetrao scoticus*) occurs nowhere in the known world ept in the British isles.

ome species of the vulture tribe are said to be cosmopolites; and common wild goose (*Anas anser*, Linn.), if we may believe some ithologists, is a general inhabitant of the globe, being met with n Lapland to the Cape of Good Hope, frequent in Arabia, Persia, na, and Japan, and in the American continent from Hudson's Bay South Carolina.† An extraordinary range has also been attributed he nightingale, which extends from western Europe to Persia, and l farther. In a work entitled Specchio Comparativo ‡, by Charles ıaparte, many species of birds are enumerated as common to Rome l Philadelphia: the greater part of these are migratory, but some them, such as the long-eared owl (*Strix otus*) are permanent in h countries. The correspondence of the ornithological fauna of eastern and western hemispheres increases considerably, as might ve been anticipated, in high northern latitudes.§

Their facilities of diffusion.—In parallel zones of the northern l southern hemispheres, a great general correspondence of form is ervable, both in the aquatic and terrestrial birds; but there is ely any specific identity: and this phenomenon is truly remarke, when we recollect the readiness with which some birds, not ed with great powers of flight, shift their quarters to different ions, and the facility with which others, possessing great strength wing, perform their aërial voyage. Some migrate periodically m high latitudes, to avoid the cold of winter, and the accompanints of cold, — scarcity of insects and vegetable food; others, it is d, for some particular kinds of nutriment required for rearing ir young: for this purpose, they often traverse the ocean for

---

Prichard, vol. i. p. 47.

Bewick's Birds, vol. ii. p. 294., who s Latham.

‡ Pisa, 1827 (not sold).

§ Bachman, Silliman's Amer. Journ., No. 61. p. 92.

thousands of miles, and recross it at other periods, with equal security.

Periodical migrations, no less regular, are mentioned by Humboldt, of many American water-fowl, from one part of the tropics to another, in a zone where there is the same temperature throughout the year. Immense flights of ducks leave the valley of the Orinoco, when the increasing depth of its waters and the flooding of its shores prevent them from catching fish, insects, and aquatic worms. They then betake themselves to the Rio Negro and Amazon, having passed from the eighth and third degrees of north latitude to the first and fourth of south latitude, directing their course south-south-east. In September, when the Orinoco decreases and re-enters its channel, these birds return northwards.*

The insectivorous swallows which visit our island would perish during winter, if they did not annually repair to warmer climes. It is supposed that in these aërial excursions the average rapidity of their flight is not less than fifty miles an hour; so that, when aided by the wind, they soon reach warmer latitudes. Spallanzani calculated that the swallow can fly at the rate of ninety-two miles an hour, and conceived that the rapidity of the swift might be three times greater.† The rate of flight of the eider duck (*Anas mollissima*) is said to be ninety miles an hour; and Bachman says that the hawk, wild pigeon (*Columba migratoria*), and several species of wild ducks in North America, fly at the rate of forty miles an hour, or nearly a thousand miles in twenty-four hours.‡

When we reflect how easily different species, in a great lapse of ages, may be each overtaken by gales and hurricanes, and, abandoning themselves to the tempest, be scattered at random through various regions of the earth's surface, where the temperature of the atmosphere, the vegetation, and the animal productions, might be suited to their wants, we shall be prepared to find some species capriciously distributed, and to be sometimes unable to determine the native countries of each. Captain Smyth informs me, that, when engaged in his survey of the Mediterranean, he encountered a gale in the Gulf of Lyons, at the distance of between twenty and thirty leagues from the coast of France, which bore along many land birds of various species, some of which alighted on the ship, while others were thrown with violence against the sails. In this manner islands become tenanted by species of birds inhabiting the nearest mainland.

Geographical Distribution and Dissemination of Reptiles.

A few facts respecting the third great class of vertebrated animals will suffice to show that the plan of nature in regard to their location on the globe is perfectly analogous to that already exemplified in other parts of the organic creation, and has probably been determined by similar causes.

---

* Voyage aux Régions Equinoxiales, tome vii. p. 429.

† Fleming, Phil. Zool., vol. ii. p. 43.

‡ Silliman's Amer. Journ. No. [illegible] p. 83.

Habitations of reptiles.—Of the great saurians, the gavials which inhabit the Ganges differ from the cayman of America, or the crocodile of the Nile. The monitor of New Holland is specifically distinct from the Indian species; these latter, again, from the African, and all from their congeners in the new world. So in regard to snakes; we find the boa of America represented by the python, a different though nearly allied genus in India. America is the country of the rattlesnake; Africa, of the cerastes; and Asia, of the hooded snake, or cobra di capello. The amphibious genera Siren and Menopoma belong to North America, possessing both lungs and gills, and respiring at pleasure either air or water. The only analogous animal of the old world is the *Proteus anguinus* of the lakes of Lower Carniola, and the grotto of Adelsberg between Trieste and Vienna.*

There is a legend that St. Patrick expelled all reptiles from Ireland; and certain it is that none of the three species of snakes common in England, nor the toad, have been observed there by naturalists. They have our common frog, and our water-newt, and according to Ray (Quad. 264.), the green lizard (*Lacerta viridis*).

Migrations of the larger reptiles.—The range of the large reptiles is, in general, quite as limited as that of some orders of the terrestrial mammalia. The great saurians sometimes cross a considerable tract in order to pass from one river to another; but their motions by land are generally slower than those of quadrupeds. By water, however, they may transport themselves to distant situations more easily. The larger alligator of the Ganges sometimes descends beyond the brackish water of the delta into the sea; and in such cases it might chance to be drifted away by a current, and survive till it reached a shore at some distance; but such casualties are probably very rare.

Turtles migrate in large droves from one part of the ocean to another during the ovipositing season; and they find their way annually to the island of Ascension, from which the nearest land is about 800 miles distant. Dr. Fleming mentions, that an individual of the hawk's bill turtle (*Chelonia imbricata*), so common in the American seas, has been taken at Papa Stour, one of the West Zetland Islands†; and, according to Sibbald, "the same animal came into Orkney." Another was taken, in 1774, in the Severn, according to Turton. Two instances, also, of the occurrence of the leathern tortoise (*C. coriacea*), on the coast of Cornwall, in 1756, are mentioned by Borlase. These animals of more southern seas can be considered only as stragglers attracted to our shores during uncommonly warm seasons by an abundant supply of food, or carried by the Gulf stream, or driven by storms to high latitudes.

Some of the smaller reptiles lay their eggs on aquatic plants; and these must often be borne rapidly by rivers, and conveyed to distant regions in a manner similar to the dispersion of seeds before adverted to. But that the larger ophidians may be themselves transported across the seas, is evident from the following most interesting account of the arrival of one at the island of St. Vincent. It is worthy of being recorded, says Mr. Guilding, "that a noble specimen of the *Boa constrictor* was lately conveyed to us by the currents, twisted round the trunk of a large sound cedar tree, which had probably been washed out of the bank by the floods of some great South American river, while its huge folds hung on the branches, as it waited for its prey. The monster was fortunately destroyed after killing a few sheep, and his skeleton now hangs before me in my study, putting me in mind how much reason I might have had to fear in my future rambles through the forests of St. Vincent, had this formidable reptile been a pregnant female, and escaped to a safe retreat."*

---

* Richardson, Brit. Assoc. Rep., vol. v. p. 202.

† Brit. Animals, p. 149., who cites Sibbald.

CHAPTER XXXIX.

LAWS WHICH REGULATE THE GEOGRAPHICAL DISTRIBUTION OF SPECIES—*continued.*

Geographical distribution and migrations of Fish—of Testacea—of Zoophytes—Distribution of Insects—Migratory instincts of some species—Certain types characterize particular countries—Their means of dissemination—Geographical distribution and diffusion of man—Speculations as to the birth-place of the human species—Progress of human population—Drifting of canoes to vast distances—On the involuntary influence of man in extending the range of many other species.

Geographical Distribution and Migrations of Fish.

Although we are less acquainted with the habitations of marine animals than with the grouping of the terrestrial species before described, yet it is well ascertained that their distribution is governed by the same general laws. The testimony borne by MM. Péron and Lesueur to this important fact is remarkably strong. These eminent naturalists, after collecting and describing many thousand species of marine animals which they brought to Europe from the southern hemisphere, insist most emphatically on their distinctness from those north of the equator; and this remark they extend to animals of all classes, from those of a more simple to those of a more complex organization—from the Sponges and Medusæ to the Cetacea. "Among all those which we have been able to examine," say they, "with our own eyes, or with regard to which it has appeared to us possible to pronounce with certainty, there is not a single animal of the southern regions which is not distinguished by essential characters from the analogous species in the northern seas."†

On comparing the freshwater fish of Europe and North America

---

[*] Zool. Journ. vol. iii. p. 406. Dec. 1827.

[†] Sur les Habitations des Animaux Marins.—Ann. du Mus., tom. xv., and by Prichard, Phys. Hist. of Mankind, vol. i. p. 51.

Sir John Richardson remarks, that the only species which is unequivocally common to the two continents is the pike (*Esox lucius*); and it is curious that this fish is unknown to the westward of the Rocky Mountains, the very coast which approaches nearest to the old continent.* According to the same author the genera of freshwater fish in China agree closely with those of the peninsula of India, but the species are not the same. "As in the distribution," he adds, "of marine fish, the interposition of a continent stretching from the tropics far into the temperate or colder parts of the ocean, separate different icthyological groups; so with respect to the freshwater species, the intrusion of arms of the sea running far to the northwards, or the interposition of a lofty mountain-chain, effects the same thing. The freshwater fish of the Cape of Good Hope and the South American ones, are different from those of India and China, &c."†

Cuvier and Valenciennes, in their "Histoire des Poissons," observe, that very few species of fish cross the Atlantic. Although their statement is correct, it is found that a great many species are common to the opposite sides of the Indian Ocean, inhabiting alike the Red Sea, the eastern coast of Africa, Madagascar, the Mauritius, the Indian Ocean, the southern seas of China, the Malay archipelago, the northern coasts of Australia, and the whole of Polynesia!‡ This very wide diffusion, says Sir J. Richardson, may have been promoted by chains of islands running east and west, which are wanting in the deep Atlantic. An archipelago extending far in longitude, favours the migration of fish by multiplying the places of deposit for spawn along the shores of islands, and on intervening coral banks; and in such places, also, fish find their appropriate food.

The flying fish are found (some stragglers excepted) only between the tropics: in receding from the line, they never approach a higher latitude than the fortieth parallel. The course of the Gulf stream, however, and the warmth of its water, enable some tropical fish to extend their habitations far into the temperate zone; thus the chætodons which abound in the seas of hot climates, are found among the Bermudas on the thirty-second parallel, where they are preserved in basins inclosed from the sea, as an important article of food for the garrison and inhabitants. Other fish, following the direction of the same great current, range from the coast of Brazil to the banks of Newfoundland.§

All are aware that there are certain fish of passage which have their periodical migrations, like some tribes of birds. The salmon, towards the season of spawning, ascends the rivers for hundreds of miles, leaping up the cataracts which it meets in its course, and then retreats again into the depths of the ocean. The herring and the haddock, after frequenting certain shores, in vast shoals, for a series of years, desert them again, and resort to other stations, followed by the species which prey on them. Eels are said to descend into the sea for the purpose of producing their young, which are seen returning into the fresh water by myriads, extremely small in size, but possessing the power of surmounting every obstacle which occurs in the course of a river, by applying their slimy and glutinous bodies to the surface of rocks, or the gates of a lock, even when dry, and so climbing over it.* Before the year 1800 there were no eels in Lake Wener, the largest inland lake in Sweden, which discharges its waters by the celebrated cataracts of Trolhättan. But I am informed by Professor Nilsson, that since the canal was opened uniting the river Gotha with the lake by a series of nine locks, each of great height, eels have been observed in abundance in the lake. It appears, therefore, that though they were unable to ascend the falls, they have made their way by the locks, by which in a very short space a difference of level of 114 feet is overcome.

---

* Brit. Assoc. Reports, vol. v. p. 203.

† Report to the Brit. Assoc., 1845, p. 192.

‡ Richardson, ibid. p. 190.

§ Sir J. Richardson, ibid. p. 190.

Gmelin says, that the Anseres (wild geese, ducks, and others) subsist, in their migrations, on the spawn of fish; and that oftentimes, when they void the spawn, two or three days afterwards, the eggs retain their vitality unimpaired.† When there are many disconnected freshwater lakes in a mountainous region, at various elevations, each remote from the other, it has often been deemed inconceivable how they could all become stocked with fish from one common source; but it has been suggested, that the minute eggs of these animals may sometimes be entangled in the feathers of water-fowl. These, when they alight to wash and plume themselves in the water, may often unconsciously contribute to propagate swarms of fish, which, in due season, will supply them with food. Some of the water-beetles, also, as the Dyticidæ, are amphibious, and in the evening quit their lakes and pools; and, flying in the air, transport the minute ova of fishes to distant waters. In this manner some naturalists account for the fry of fish appearing occasionally in small pools caused by heavy rains; but the showers of small fish, stated in so many accounts to have fallen from the atmosphere, require farther investigation.

Geographical Distribution and Migrations of Testacea.

The Testacea, of which so great a variety of species occurs in the sea, are a class of animals of peculiar importance to the geologist; because their remains are found in strata of all ages, and generally in a higher state of preservation than those of other organic beings. Climate has a decided influence on the geographical distribution of species in this class; but as there is much greater uniformity of temperature in the waters of the ocean, than in the atmosphere which invests the land, the diffusion of marine mollusks is on the whole more extensive.

Some forms attain their fullest development in warm latitudes; and are often exclusively confined to the torrid zone, as *Nautilus*,

---

* Phil. Trans. 1747, p. 395.

† Amœn. Acad., Essay 75.

Harpa, *Terebellum*, *Pyramidella*, *Delphinula*, *Aspergillum*, *Tridacna*, *Cucullæa*, *Crassatella*, *Corbis*, *Perna*, and *Plicatula*. Other forms are limited to one region of the sea, as the *Trigonia* to parts of Australia, and the *Concholepas* to the western coast of South America. The marine species inhabiting the ocean on the opposite sides of the narrow isthmus of Panama, are found to differ almost entirely, as we might have anticipated, since a West Indian mollusk cannot enter the Pacific without coasting round South America, and passing through the inclement climate of Cape Horn. The continuity of the existing lines of continent from north to south, prevents any one species from belting the globe, or from following the direction of the isothermal lines.

Currents also flowing permanently in certain directions, and the influx at certain points of great bodies of fresh water, limit the extension of many species. Those which love deep water are arrested by shoals; others, fitted for shallow seas, cannot migrate across unfathomable abysses. The nature also of the ground has an important influence on the testaceous fauna, both on the land and beneath the waters. Certain species prefer a sandy, others a gravelly, and some a muddy sea-bottom. On the land, limestone is of all rocks the most favourable to the number and propagation of species of the genera Helix, Clausilia, Bulimus, and others. Professor E. Forbes has shown as the result of his labours in dredging in the Ægean Sea, that there are eight well-marked regions of depth, each characterized by its peculiar testaceous fauna. The first of these, called the littoral zone, extends to a depth of two fathoms only; but this narrow belt is inhabited by more than one hundred species. The second region, of which ten fathoms is the inferior limit, is almost equally populous; and a copious list of species is given as characteristic of each region down to the seventh, which lies between the depths of 80 and 105 fathoms, all the inhabited space below this being included in the eighth province, where no less than 65 species of Testacea have been taken. The majority of the shells in this lowest zone are white or transparent. Only two species of Mollusca are common to all the eight regions, namely, *Arca lactea* and *Cerithium lima*.*

Great range of some provinces and species.—In Europe conchologists distinguish between the arctic fauna, the southern boundary of which corresponds with the isothermal line of 32° F., and the Celtic, which, commencing with that limit as its northern frontier, extends southwards to the mouth of the English Channel and Cape Finisterre, in France. From that point begins the Lusitanian fauna, which according to the recent observations of Mr. M'Andrew (1852), ranges to the Canary Islands. The Mediterranean province is distinct from all those above enumerated, although it has some species in common with each.

The Indo-Pacific region is by far the most extensive of all. It reaches from the Red Sea and the eastern coast of Africa, to the Indian Archipelago, and adjoining parts of the Pacific Ocean. To the geologist it furnishes a fact of no small interest, by teaching us that one group of living species of mollusca may prevail throughout an area exceeding in magnitude the utmost limits we can as yet assign to any assemblage of contemporaneous fossil species. Mr. Cuming obtained more than a hundred species of shells from the eastern coast of Africa identical with those collected by himself in the Philippines and in the eastern coral islands of the Pacific Ocean, a distance equal to that from pole to pole.*

---

* Report to the Brit. Assoc. 1843, p. 130.

Certain species of the genus *Ianthina* have a very wide range, being common to seas north and south of the equator. They are all provided with a beautifully contrived float, which renders them buoyant, facilitating their dispersion, and enabling them to become active agents in disseminating other species. Captain King took a specimen of *Ianthina fragilis*, alive, a little north of the equator, so loaded with barnacles (*Pentelasmis*) and their ova that the upper part of its shell was invisible. The "Rock Whelk" (*Purpura lapillus*), a well-known British univalve, inhabits both the North Atlantic and North Pacific.

Helix putris (*Succinea putris*, Lam.), so common in Europe, where it reaches from Norway to Italy, is also said to occur in the United States, and in Newfoundland. As this animal inhabits constantly the borders of pools and streams where there is much moisture, it is not impossible that different water-fowl have been the agents of spreading some of its minute eggs, which may have been entangled in their feathers. The freshwater snail, *Lymneus palustris*, so abundant in English ponds, ranges uninterruptedly from Europe to Cashmere, and thence to the eastern parts of Asia. *Helix aspersa*, one of the commonest of our larger land-shells, is found in St. Helena and other distant countries. Some conchologists have conjectured that it was accidentally imported into St. Helena in some ship; for it is an eatable species, and these animals are capable of retaining life during long voyages, without air or nourishment.†

Perhaps no species has a better claim to be called cosmopolite than one of our British bivalves, *Saxicava rugosa*. It is spread over all the north-polar seas, and ranges in one direction through Europe to Senegal, occurring on both sides of the Atlantic; while in another it finds its way into the North Pacific, and thence to the Indian Ocean. Nor do its migrations cease till it reaches the Australian seas.

A British brachiopod, named *Terebratula caput-serpentis*, is com-

---

[*] Quart. Journ. Geol. Soc., 1846, vol. ii. p. 268.

[†] Four individuals of a large species of land-shell (*Bulimus*), from Valparaiso, were brought to England by Lieutenant Graves, who accompanied Captain King in his expedition to the Straits of Magellan. They had been packed up in a box, and enveloped in cotton: two for a space of thirteen, one for seventeen, and a fourth for upwards of twenty months: but, on being exposed by Mr. Broderip to the warmth of a fire in London, and provided with tepid water and leaves, they revived, and lived for several months in Mr. Loddiges' palm-house, till accidentally drowned.

mon, according to Professor E. Forbes, to both sides of the North Atlantic, and to the South African and Chinese seas.

Confined range of other species. — Mr. Lowe, in a memoir published in the Cambridge Transactions in 1834, enumerates seventy-one species of land Mollusca, collected by him in the islands of Madeira and Porto Santo, sixty of which belonged to the genus Helix alone, including as sub-genera Bulimus and Achatina, and excluding Vitrina and Clausilia; — forty-four of these are new. It is remarkable, that very few of the above-mentioned species are common to the neighbouring archipelago of the Canaries; but it is a still more striking fact, that, of the sixty species of the three genera above mentioned, thirty-one are natives of Porto Santo; whereas, in Madeira, which contains ten times the superficies, were found but twenty-nine. Of these only four were common to the two islands, which are separated by a distance of only twelve leagues; and two even of these four (namely, *Helix rhodostoma* and *H. ventrosa*) are species of general diffusion, common to Madeira, the Canaries, and the south of Europe.*

The confined range of these mollusks may easily be explained, if we admit that species have only one birth-place; and the only problem to be solved would relate to the exceptions — to account for the dissemination of some species throughout several islands, and the European continent. May not the eggs, when washed into the sea by the undermining of cliffs, or blown by a storm from the land, float uninjured to a distant shore?

Their mode of diffusion— Notwithstanding the proverbially slow motion of snails and mollusks in general, and although many aquatic species adhere constantly to the same rock for their whole lives, they are by no means destitute of provision for disseminating themselves rapidly over a wide area. "Some Mollusca," says Professor E. Forbes, "migrate in their larva state, for all of them undergo a metamorphosis either in the egg or out of the egg. The Gasteropoda commence life under the form of a small spiral shell, and an animal furnished with ciliated wings, or lobes, like a pteropod, by means of which it can swim freely, and in this form can migrate with ease through the sea."†

We are accustomed to associate in our minds the idea of the greatest locomotive powers with the most mature and perfect state of each species of invertebrate animal, especially when they undergo a series of transformations; but in all the Mollusca the reverse is true. The young fry of the cockle, for example (*Cardium*), possess, when young or in the larva state, an apparatus which enables them both to swim and to be carried along easily by a marine current. (See fig. 99.)

These small bodies here represented, which bear a considerable resemblance to the fry of the univalve, or gasteropodous shells above mentioned, are so minute at first as to be just visible to the naked eye. They begin to move about from the moment they are hatched, by

---

* Camb. Phil. Trans., vol. iv. 1831.

† Edin. New Phil. Journ. April 1844.

Fig. 99.



The young fry of a cockle (Cardium pygmæum), from Loven's Kongl. Vetenskaps. Akadem. Handling, 1848.

A, The young just hatched, magnified 100 diameters. B, The same farther advanced.
a, The ciliated organ of locomotion with its filamentous appendage *b*.
c, The rudimentary intestine.
d, The rudimentary shell.

means of the long cilia, *a*, *a*, placed on the edges of the locomotive disk or velum. This disk shrinks up as they increase in size, and gradually disappears, no trace of it being visible in the perfect animal.

Some species of shell-bearing Mollusca lay their eggs in a sponge-like nidus, wherein the young remain enveloped for a time after their birth; and this buoyant substance floats far and wide as readily as sea-weed. The young of other viviparous tribes are often borne along entangled in sea-weed. Sometimes they are so light, that, like grains of sand, they can be easily moved by currents. Balani and Serpulæ are sometimes found adhering to floating cocoa-nuts, and even to fragments of pumice. In rivers and lakes, on the other hand, aquatic univalves usually attach their eggs to leaves and sticks which have fallen into the water, and which are liable to be swept away during floods, from tributaries to the main streams, and from thence to all parts of the same basins. Particular species may thus migrate during one season from the head waters of the Mississippi, or any other great river, to countries bordering the sea, at the distance of many thousand miles.

An illustration of the mode of attachment of these eggs will be seen in the annexed cut. (Fig. 100.)

The habit of some Testacea to adhere to floating wood is proved by their fixing themselves to the bottoms of ships. By this mode of conveyance *Mytilus polymorphus*, previously known only in the Danube and Wolga, may have been brought to the Commercial Docks in the Thames, and to Hamburgh, where the species is now domiciled. But Mr. Gray suggests that as the animal is known to have the faculty of living for a very long time out of water, it is more probable that it was brought in Russian timber, than borne uninjured through the salt water at the bottom of a vessel.*

A lobster (*Astacus marinus*) was lately taken alive covered with living mussels (*Mytilus edulis*)†; and a large female crab (*Cancer pagurus*), covered with oysters, and bearing also *Anomia ephippium*, and Actiniæ, was taken in April, 1832, off the English coast. The

---

* Phil. Trans. 1835, p. 303.

† The specimen is preserved in the Museum of the Zool. Soc. of London.

Fig. 100.



Eggs of freshwater mollusks.

Fig. 1. Eggs of *Ampullaria ovata* (a fluviatile species) fixed to a small sprig which had fallen into the water.
Fig. 2. Eggs of *Planorbis albus*, attached to a dead leaf lying under water.
Fig. 3. Eggs of the common Limneus (*L. vulgaris*), adhering to a dead stick under water.

oysters, seven in number, include individuals of six years' growth and the two largest are four inches long and three inches and a half broad. Both the crab and the oysters were seen alive by Mr. Robert Brown.*

From this example we learn the manner in which oysters may be diffused over every part of the sea where the crab wanders; and if they are at length carried to a spot where there is nothing but fine mud, the foundation of a new oyster-bank may be laid on the death of the crab. In this instance the oysters survived the crab many days, and were killed at last only by long exposure to the air.

Geographical Distribution and Migrations of Zoophytes.

Zoophytes are very imperfectly known; but there can be little doubt that each maritime region possesses species peculiar to itself. The Madrepores, or lamelliferous Polyparia, are found in their fullest development only in the tropical seas of Polynesia and the East and West Indies; and this family is represented only by a few species in our seas. The zoophytes of the Mediterranean, according to Ehrenberg, differ almost entirely from those of the Red Sea, although only seventy miles distant. Out of 120 species of Anthozoa, only two are common to both seas.† Péron and Lesueur, after studying the Holothuriæ, Medusæ, and other congeners of delicate and changeable forms, came to the conclusion that each kind has its place of residence determined by the temperature necessary to support its existence. Thus, for example, they found the abode of *Pyrosoma Atlantica* to be confined to one particular region of the Atlantic Ocean.*

---

* This specimen is in the collection of my friend Mr. Broderip, who observes, that this crab, which was apparently in perfect health, could not have cast her shell for six years, whereas some naturalists have stated that the species moults annually, without limiting the moulting period to the early stages of the growth of the animal.

† Quart. Journ. Geol. Soc., vol. iv. p. 336.

Let us now inquire how the transportation of Zoophytes from one part of the globe to another is effected. Many of them, as in the families Flustra and Sertularia, attach themselves to sea-weed, and are occasionally drifted along with it. Many fix themselves to the shells of Mollusca, and are thus borne along by them to short distances. Others, like some species of sea-pens, float about in the ocean, and are usually believed to possess powers of spontaneous motion. But the most frequent mode of transportation consists in the buoyancy of their eggs, or certain small vesicles, which are detached, and are capable of becoming the foundation of a new colony. These gems, as they are called, have, in many instances, a locomotive power of their own, by which they proceed in a determinate direction for several days after separation from the parent. They are propelled by means of numerous short threads or *ciliæ*, which are in constant and rapid vibration; and, when thus supported in the water, they may be borne along by currents to a great distance.

That some zoophytes adhere to floating bodies, is proved by their being found attached to the bottoms of ships, like certain Testacea before alluded to.

Geographical Distribution and Migrations of Insects.

Before I conclude this sketch of the manner in which the habitable parts of the earth are shared out among particular assemblages of organic beings, I must offer a few remarks on insects, which, by their numbers and the variety of their powers and instincts, exert a prodigious influence in the economy of animate nature. As a large portion of these minute creatures are strictly dependent for their subsistence on certain species of vegetables, the entomological provinces must coincide in a considerable degree with the botanical.

All the insects, says Latreille, brought from the eastern parts of Asia and China, whatever be their latitude and temperature, are distinct from those of Europe and of Africa. The insects of the United States, although often approaching very close to our own, are, with very few exceptions, specifically distinguishable by some characters. In South America, the equinoctial lands of New Granada and Peru on the one side, and of Guiana on the other, contain for the most part distinct groups; the Andes forming the division, and interposing a narrow line of severe cold between climates otherwise very similar.†

Migratory instincts. — Nearly all the insects of the United States and Canada, differ specifically from the European; while those of Greenland appear to be in a great measure identical with our own. Some insects are very local; while a few, on the contrary, are common to remote countries, between which the torrid zone and the ocean intervene. Thus our painted lady butterfly (*Vanessa cardui*) re-appears at the Cape of Good Hope and in New Holland and Japan with scarcely a varying streak.* The same species is said to be one of the few insects which are universally dispersed over the earth, being found in Europe, Asia, Africa, and America; and its wide range is the more interesting, because it seems explained by its migratory instinct, seconded, no doubt, by a capacity, enjoyed by few species, of enduring a great diversity of temperature.

---

* Voy. aux Terres Australes, tom. i. p. 492.

† Géographie Générale des Insectes et des Arachnides. Mém. du Mus. d'Hist. Nat., tom. iii.

A vast swarm of this species, forming a column from ten to fifteen feet broad, was, a few years since, observed in the Canton de Vaud; they traversed the country with great rapidity from north to south, all flying onwards in regular order, close together, and not turning from their course on the approach of other objects. Professor Bonelli, of Turin, observed, in March of the same year, a similar swarm of the same species, also directing their flight from north to south, in Piedmont, in such immense numbers that at night the flowers were literally covered with them. They had been traced from Coni, Raconi, Susa, &c. A similar flight at the end of the last century is recorded by M. Louch, in the Memoirs of the Academy of Turin. The fact is the more worthy of notice, because the caterpillars of this butterfly are not gregarious, but solitary from the moment that they are hatched; and this instinct remains dormant, while generation after generation passes away, till it suddenly displays itself in full energy when their numbers happen to be in excess.

Not only peculiar species, but certain types, distinguish particular countries; and there are groups, observes Kirby, which represent each other in distant regions, whether in their form, their functions, or in both. Thus the honey and wax of Europe, Asia, and Africa, are in each case prepared by bees congenerous with our common hive-bee (*Apis*, Latr.); while, in America, this genus is nowhere indigenous, but is replaced by Melipona, Trigona, and Euglossa; and in New Holland by a still different but undescribed type.† The European bee (*Apis mellifica*), although not a native of the new world, is now established both in North and South America. It was introduced into the United States by some of the early settlers, and has since overspread the vast forests of the interior, building hives in the decayed trunks of trees. "The Indians," says Irving, "consider them as the harbinger of the white man, as the buffalo is of the red man, and say that in proportion as the bee advances the Indian and the buffalo retire. It is said," continues the same writer, "that the wild bee is seldom to be met with at any great distance from the frontier, and that they have always been the heralds of civilization, preceding it as it advanced from the Atlantic borders. Some of the ancient settlers of the west even pretend to give the very year when the honey-bee first crossed the Mississippi.[*] The same species is now also naturalized in Van Diemen's Land and New Zealand.

---

* Kirby and Spence, vol. iv. p. 487.; and other authors.

† Kirby and Spence, vol. iv. p. 497.

As almost all insects are winged, they can readily spread themselves wherever their progress is not opposed by uncongenial climates, or by seas, mountains, and other physical impediments; and these barriers they can sometimes surmount by abandoning themselves to violent winds, which, as I before stated, when speaking of the dispersion of seeds (p. 618.), may in a few hours carry them to very considerable distances. On the Andes some sphinxes and flies have been observed by Humboldt, at the height of 19,180 feet above the sea, and which appeared to him to have been involuntarily carried into these regions by ascending currents of air.[†]

White mentions a remarkable shower of aphides which seem to have emigrated, with an east wind, from the great hop plantations of Kent and Sussex, and blackened the shrubs and vegetables where they alighted at Selborne, spreading at the same time in great clouds all along the vale from Farnham to Alton. These aphides are sometimes accompanied by vast numbers of the common lady-bird (*Coccinella septempunctata*), which feed upon them.[‡]

It is remarkable, says Kirby, that many of the insects which are ocasionally observed to emigrate, as, for instance, the Libellulæ, Coccinellæ, Carabi, Cicadæ, &c. are not usually social insects; but seem to congregate, like swallows, merely for the purpose of emigration.[§] Here, therefore, we have an example of an instinct developing itself on certain rare emergencies, causing unsocial species to become gregarious and to venture sometimes even to cross the ocean.

The armies of locusts which darken the air in Africa and traverse the globe from Turkey to our southern counties in England, are well known to all. When the western gales sweep over the Pampas they bear along with them myriads of insects of various kinds. As a proof of the manner in which species may be thus diffused, I may mention that when the Creole frigate was lying in the outer roads off Buenos Ayres, in 1819, at the distance of six miles from the land, her decks and rigging were suddenly covered with thousands of flies and grains of sand. The sides of the vessel had just received a fresh coat of paint, to which the insects adhered in such numbers as to spot and disfigure the vessel, and to render it necessary partially to renew the paint.[‖] Captain W. H. Smyth was obliged to repaint his vessel, the Adventure, in the Mediterranean, from the same cause. He was on his way from Malta to Tripoli, when a southern wind blowing from the coast of Africa, then one hundred miles distant, drove such myriads of flies upon the fresh paint, that not the smallest point was left unoccupied by insects.

---

[*] Washington Irving's Tour in the Prairies, ch. ix.

[†] Malte-Brun, vol. v. p. 379.

[‡] Kirby and Spence, vol. ii. p. 9. 1817.

[§] Kirby and Spence, vol. ii. p. 12. 1817.

[‖] I am indebted to Lieutenant Graves, R. N., for this information.

To the southward of the river Plate, off Cape St. Antonio, and at the distance of fifty miles from land, several large dragon-flies alighted on the Adventure frigate, during Captain King's late expedition to the Straits of Magellan. If the wind abates when insects are thus crossing the sea, the most delicate species are not necessarily drowned; for many can repose without sinking on the water. The slender long-legged tipulæ have been seen standing on the surface of the sea, when driven out far from our coast, and took wing immediately on being approached.* Exotic beetles are sometimes thrown on our shore, which revive after having been long drenched in salt water; and the periodical appearance of some conspicuous butterflies amongst us, after being unseen some for five others for fifty years, has been ascribed, not without probability, to the agency of the winds.

'Inundations of rivers, observes Kirby, if they happen at any season except in the depth of winter, always carry down a number of insects, floating on the surface of bits of stick, weeds, &c.; so that when the waters subside, the entomologist may generally reap a plentiful harvest. In the dissemination, moreover, of these minute beings, as in that of plants, the larger animals play their part. Insects are, in numberless instances, borne along in the coats of animals, or the feathers of birds; and the eggs of some species are capable, like seeds, of resisting the digestive powers of the stomach, and after they are swallowed with herbage, may be ejected again unharmed in the dung.

Geographical Distribution and Diffusion of Man.

I have reserved for the last some observations on the range and diffusion of the human species over the earth, and the influence of man in spreading other animals and plants, especially the terrestrial.

Many naturalists have amused themselves in speculating on the probable birth-place of mankind, the point from which, if we assume the whole human race to have descended from a single pair, the tide of emigration must originally have proceeded. It has been always a favourite conjecture, that this birth-place was situated within or near the tropics, where perpetual summer reigns, and where fruits, herbs, and roots are plentifully supplied throughout the year. The climate of these regions, it has been said, is suited to a being born without any covering, and who had not yet acquired the arts of building habitations or providing clothes.

Progress of human population.—"The hunter state," it has been argued, "which Montesquieu placed the first, was probably only the second stage to which mankind arrived; since so many arts must have been invented to catch a salmon, or a deer, that society could no longer have been in its infancy when they came into use."[*] When regions where the spontaneous fruits of the earth abound became overpeopled, men would naturally diffuse themselves over the neighbouring parts of the temperate zone; but a considerable time would probably elapse before this event took place; and it is possible, as a writer before cited observes, that in the interval before the multiplication of their numbers and their increasing wants had compelled them to emigrate, some arts to take animals were invented, but far inferior to what we see practised at this day among savages. As their habitations gradually advanced into the temperate zone, the new difficulties they had to encounter would call forth by degrees the spirit of invention, and the probability of such inventions always rises with the number of people involved in the same necessity.[†]

---

* I state this fact on the authority of my friend, Mr. John Curtis.

A distinguished modern writer, who coincides for the most part in the views above mentioned, has introduced one of the persons in his second dialogue, as objecting to the theory of the human race having gradually advanced from a savage to a civilized state, on the ground that "the first man must have inevitably been destroyed by the elements or devoured by savage beasts, so infinitely his superiors in physical force."[‡] He then contends against the difficulty here started by various arguments, all of which were, perhaps, superfluous; for if a philosopher is pleased to indulge in conjectures on this subject, why should he not assign, as the original seat of man, some one of those large islands within the tropics, which are as free from large beasts of prey as Van Diemen's Land or Australia? Here man may have remained for a period, peculiar to a single island, just as some of the large anthropomorphous species are now limited to one island within the tropics. In such a situation, the new-born race might have lived in security, though far more helpless than the New Holland savages, and might have found abundance of vegetable food. Colonies may afterwards have been sent forth from this mother country, and then the peopling of the earth may have proceeded according to the hypothesis before alluded to.

To form a probable conjecture respecting the country from whence the early civilization of India was derived, has been found almost as difficult as to determine the original birth-place of the human race. That the dawn of oriental civilization did not arise within the limits of the tropics, is the conclusion to which Baron William von Humboldt has come after much patient research into "the diversities of the structure of language and their influence on the mental development of the human race." According to him the ancient Zend country from whence the spread of knowledge and the arts has been traced in a south-easterly direction, lay to the north-west of the upper Indus.[§]

---

[*] Brand's Select Dissert. from the Amœn. Acad., vol. i. p. 118.

[†] Ibid.

[‡] Sir H. Davy, Consolations in Travel, p. 74.

[§] W. von Humboldt, "On the Kawi

As to the time of the first appearance of man upon the earth, if we are to judge from the discordance of opinion amongst celebrated chronologers, not even a rude approximation has yet been made owards determining a point of so much interest. The problem eems hitherto to have baffled the curiosity of the antiquary, if pos-ible, more completely than the fixing on a geographical site for the original habitation of the ancestors of the human race. The Chevalier Bunsen, in his elaborate and philosophical work on Ancient Egypt *, has satisfied not a few of the learned, by an appeal to monumental inscriptions still extant, that the successive dynasties of kings may be traced back without a break, to Menes, and that the date of his reign would correspond with the year 3640, B. C. He supposes at the same time, what is most reasonable, that the Egyptian people must have existed for a long period (probably at least for five centuries), in their earlier and less settled state, before they reached the point of civilization at which Menes consolidated them into a great and united empire. This would carry us back to upwards of 4000 years B. C., or to an epoch coincident with that commonly set down for the creation of the world in accordance with computations founded on the combined ages of the successive antediluvian patriarchs. It follows that the same epoch of Menes is anterior by a great many centuries to the most ancient of the dates usually fixed upon for the Mosaic deluge. The fact that no record or tradition of any great and overwhelming flood has been detected in the mythology, or monumental annals of the Egyptians, will suggest many reflections to a geologist who has weighed well the evidence we possess of a variety of partial deluges which have happened in districts not free like Egypt, for the last 3000 years, from earthquakes and other causes of great aqueous catastrophes. The tales and legends of calamitous floods preserved in Greece, Asia Minor, the southern shores of the Baltic, China, Peru, and Chili have, as we have seen, been all of them handed down to us by the inhabitants of regions in which the operation of natural causes in modern times, and the recurrence of a succession of disastrous floods, afford us data for interpreting the meaning of the obscure traditions of an illiterate age.†

In his learned treatise on ancient chronology, Dr. Hales has selected, from a much greater number, a list of no less than 120 authors, all of whom give a different period for the epoch of the creation of the world, the extreme range of difference between them amounting to no less than 3268 years. It appears that even amongst authorities, who in England are generally regarded as orthodox, there is a variance, not of years or of one or two centuries, but of upwards of a millennium, according as they have preferred to follow the Hebrew, or the Samaritan, or the Greek versions of the Mosaic writings. Can

---

Language," &c. cited in Cosmos. Introduction.

* Egypten's Stelle, &c. Egypt restored to her Place in Universal History, by C. C. J. Bunsen. 1845.

† For Grecian and Asiatic deluges, see above, p. 356.; Cimbrian, p. 331.; Chinese, p. 7.; Peruvian, p. 502.; Chilian or Araucanian deluge, p. 500.

we then wonder that they who decipher the monuments of Egypt, or the geologist who interprets the earth's autobiography, should arrive at views respecting the date of an ancient empire, or the age of our planet, irreconcileable with every one of these numerous and conflicting chronologies? The want of agreement amongst the learned in regard to the probable date of the deluge of Noah is a source of far greater perplexity and confusion than our extreme uncertainty as to the epoch of the creation, — the deluge being a comparatively modern event, from which the repeopling of the earth and the history of the present races of mankind is made to begin.

Naturalists have long felt that to render probable the received opinion that all the leading varieties of the human family have originally sprung from a single pair, (a doctrine against which there appears to me to be no sound objection,) a much greater lapse of time is required for the slow and gradual formation of races, (such as the Caucasian, Mongolian, and Negro,) than is embraced in any of the popular systems of chronology. The existence of two of these marked varieties above mentioned can be traced back 3000 years before the present time, or to the painting of pictures, preserved in the tombs or on the walls of buried temples in Egypt. In these we behold the Negro and Caucasian physiognomies portrayed as faithfully and in as strong contrast as if the likenesses of those races has been taken yesterday. When we consider therefore the extreme slowness of the changes, which climate and other modifying causes have produced in modern times, we must allow for a vast series of antecedent ages, in the course of which the long-continued influence of similar external circumstances gave rise to peculiarities, probably increased in many successive generations, until they were fixed by hereditary transmission. The characteristic forms and features thus acquired by certain tribes, may have been afterwards diffused by migration from a few centres over wide continental spaces. The theory, therefore, that all the races of man have come from one common stock receives support from every investigation which forces us to expand our ideas of the duration of past time, or which multiplies the number of years that have passed away since the origin of man. Hitherto, geology has neither enlarged nor circumscribed the "human period;" but simply proved that in the history of animated nature it is comparatively modern, or the last of a long series of antecedent epochs, in each of which the earth has been successively peopled by distinct species of animals and plants.

In an early stage of society the necessity of hunting acts as a principle of repulsion, causing men to spread with the greatest rapidity over a country, until the whole is covered with scattered settlements. It has been calculated that eight hundred acres of hunting-ground produce only as much food as half an acre of arable land. When the game has been in a great measure exhausted, and a state of pasturage succeeds, the several hunter tribes, being already scattered, may multiply in a short time into the greatest number which the pastoral state is capable of sustaining. The necessity says Brand, thus imposed upon the two savage states, of dispersing themselves far and wide over the country, affords a reason why, at a very early period, the worst parts of the earth may have become inhabited.

But this reason, it may be said, is only applicable in as far as regards the peopling of a continuous continent; whereas the smallest islands, however remote from continents, have almost always been found inhabited by man. St. Helena, it is true, afforded an exception; for when that island was discovered in 1501, it was only inhabited by sea-fowl, and occasionally by seals and turtles, and was covered with a forest of trees and shrubs, all of species peculiar to it, with one or two exceptions, and which seem to have been expressly created for this remote and insulated spot.*

The islands also of Mauritius, Bourbon, Pitcairns, and Juan Fernandez, and those of the Galapagos archipelago, one of which is seventy miles long, were uninhabited when first discovered, and, what is more remarkable than all, the Falkland Islands, which together are 120 miles in length by 60 in breadth, and abounding in food fit for the support of man.

Drifting of canoes to vast distances. — But very few of the numerous coral islets and volcanos of the vast Pacific, capable of sustaining a few families of men, have been found untenanted; and we have, therefore, to inquire whence and by what means, if all the members of the great human family have had one common source, could those savages have migrated. Cook, Forster, and others, have remarked that parties of savages in their canoes must have often lost their way, and must have been driven on distant shores, where they were forced to remain, deprived both of the means and of the requisite intelligence for returning to their own country. Thus Captain Cook found on the island of Wateoo three inhabitants of Otaheite, who had been drifted thither in a canoe, although the distance between the two isles is 550 miles. In 1696, two canoes, containing thirty persons, who had left Ancorso, were thrown by contrary winds and storms on the island of Samar, one of the Philippines, at a distance of 800 miles. In 1721, two canoes, one of which contained twenty-four, and the other six persons, men, women, and children, were drifted from an island called Farroilep to the island of Guaham, one of the Marians, a distance of 200 miles.†

Kotzebue, when investigating the Coral Isles of Radack, at the eastern extremity of the Caroline Isles, became acquainted with a person of the name of Kadu, who was a native of Ulea, an isle 1500 miles distant, from which he had been drifted with a party. Kadu and three of his countrymen one day left Ulea in a sailing boat, when a violent storm arose, and drove them out of their course: they drifted about the open sea for eight months, according to their reckoning by the moon, making a knot on a cord at every new moon. Being expert fishermen, they subsisted entirely on the produce of the sea; and when the rain fell, laid in as much fresh water as they had vessels to contain it. "Kadu," says Kotzebue, "who was the best diver, frequently went down to the bottom of the sea, where it is well known that the water is not so salt, with a cocoa-nut shell, with only a small opening."* When these unfortunate men reached the isles of Radack, every hope and almost every feeling had died within them; their sail had long been destroyed, their canoe had long been the sport of winds and waves, and they were picked up by the inhabitants of Aur in a state of insensibility; but by the hospitable care of those islanders they soon recovered, and were restored to perfect health.†

---

* See p. 615.

† Malte-Brun's Geography, vol. iii. p. 419.

Captain Beechey, in his voyage to the Pacific, fell in with some natives of the Coral Islands, who had in a similar manner been carried to a great distance from their native country. They had embarked, to the number of 150 souls, in three double canoes, from Anaa, or Chain Island, situated about three hundred miles to the eastward of Otaheite. They were overtaken by the monsoon, which dispersed the canoes; and after driving them about the ocean, left them becalmed, so that a great number of persons perished. Two of the canoes were never heard of; but the other was drifted from one uninhabited island to another, at each of which the voyagers obtained a few provisions; and at length, after having wandered for a distance of 600 miles, they were found and carried to their home in the Blossom.‡

Mr. Crawfurd informs me that there are several well authenticated accounts of canoes having been drifted from Sumatra to Madagascar, and by such causes a portion of the Malayan language, with some useful plants, have been transferred to that island, which is principally peopled by negroes.

The space traversed in some of these instances was so great, that similar accidents might suffice to transport canoes from various parts of Africa to the shores of South America, or from Spain to the Azores, and thence to North America; so that man, even in a rude state of society, is liable to be scattered involuntarily by the winds and waves over the globe, in a manner singularly analogous to that in which many plants and animals are diffused. We ought not, then, to wonder, that during the ages required for some tribes of the human race to attain that advanced stage of civilization which empowers the navigator to cross the ocean in all directions with security, the whole earth should have become the abode of rude tribes of hunters and fishers. Were the whole of mankind now cut off, with the exception of one family, inhabiting the old or new continent, or Australia, or even some coral islet of the Pacific, we might expect their descendants, though they should never become more enlightened than the South Sea Islanders or the Esquimaux, to spread in the course of ages over the whole earth, diffused partly by the tendency of population to increase, in a limited district, beyond the means of subsistence, and partly by the accidental drifting of canoes by tides and currents to distant shores.

---

* Chamisso states that the water which they brought up was cooler, and *in their opinion*, less salt. It is difficult to conceive its being fresher near the bottom, except where submarine springs may happen to rise.

† Kotzebue's Voyage, 1815—1818. Quarterly Review, vol. xxvi. p. 361.

‡ Narrative of a Voyage to the Pacific, &c., in the years 1825, 1826, 1827, 1828, p. 170.

Involuntary Influence of Man in diffusing Animals and Plants.

Many of the general remarks which have been made respecting the influence of man in spreading or in checking the diffusion of plants apply equally to his relations with the animal kingdom. On a future occasion I shall be led to speak of the instrumentality of our species in naturalizing useful animals and plants in new regions, when explaining my views of the effects which the spreading and increase of certain species exert in the extirpation of others. At present I shall confine myself to a few remarks on the involuntary aid which man lends to the dissemination of species.

In the mammiferous class our influence is chiefly displayed in increasing the number of quadrupeds which are serviceable to us, and in exterminating or reducing the number of those which are noxious.

Sometimes, however, we unintentionally promote the multiplication of inimical species, as when we introduced the rat, which was not indigenous in the new world, into all parts of America. They have been conveyed over in ships, and now infest a great multitude of islands and parts of that continent. In like manner the Norway rat (*Mus decumanus*) has been imported into England, where it plunders our property in ships and houses.

Among birds, the house sparrow may be cited as a species known to have extended its range with the tillage of the soil. During the last century it has spread gradually over Asiatic Russia towards the north and east, always following the progress of cultivation. It made its first appearance on the Irtisch in Tobolsk, soon after the Russians had ploughed the land. It came in 1735 up the Obi to Beresow, and four years after to Naryn, about fifteen degrees of longitude farther east. In 1710, it had been seen in the higher parts of the coast of the Lena, in the government of Irkutzk. In all these places it is now common, but is not yet found in the uncultivated regions of Kamtschatka.*

The great viper (*Fer de lance*), a species no less venomous than the rattlesnake, which now ravages Martinique and St. Lucia, was accidentally introduced by man, and exists in no other part of the West Indies.

Many parasitic insects which attack our persons, and some of which are supposed to be peculiar to our species, have been carried into all parts of the earth, and have as high a claim as man to a *universal* geographical distribution.

---

* Gloger, Abänd. der Vögel, p. 103.; Pallas, Zoog. Rosso-Asiat., tom. ii. p. 197.

A great variety of insects have been transported in ships from one country to another, especially in warmer latitudes. The European house-fly has been introduced in this way into all the South Sea Islands. Notwithstanding the coldness of our climate in England we have been unable to prevent the cockroach (*Blatta orientalis*) from entering and diffusing itself in our ovens and kneading troughs, and availing itself of the artificial warmth which we afford. It is well known also that beetles, and many other kinds of ligniperdous insects, have been introduced into Great Britain in timber; especially several North American species. "The commercial relations," says Malte-Brun[*], "between France and India, have transported from the latter country the aphis, which destroys the apple-tree, and two sorts of Neuroptera, the *Lucifuga* and *Flavicola*, mostly confined to Provence and the neighbourhood of Bourdeaux, where they devour the timber in the houses and naval arsenals."

Among mollusks we may mention the *Teredo navalis*, which is a native of equatorial seas, but which, by adhering to the bottom of ships, was transported to Holland, where it has been most destructive to vessels and piles. The same species has also become naturalized in England, and other countries enjoying an extensive commerce. *Bulimus undatus*, a land species of considerable size, native of Jamaica and other West Indian islands, has been imported, adhering to tropical timber, into Liverpool; and, as I learn from Mr. Broderip, is now naturalized in the woods near that town.

In all these and innumerable other instances we may regard the involuntary agency of man as strictly analogous to that of the inferior animals. Like them, we unconsciously contribute to extend or limit the geographical range and numbers of certain species, in obedience to general rules in the economy of nature, which are for the most part beyond our control.

---

[*] Syst. of Geog., vol. viii. p. 169.

CHAPTER XL.

THEORIES RESPECTING THE ORIGINAL INTRODUCTION OF SPECIES.

Proposal of an hypothesis on this subject — Supposed centres or foci of creation — Why distinct provinces of animals and plants have not become more blended together — Brocchi's speculations on the loss of species — Stations of plants and animals — Causes on which they depend — Stations of plants how affected by animals — Equilibrium in the number of species how preserved — Peculiar efficacy of insects in this task — Rapidity with which certain insects multiply or decrease in numbers — Effect of omnivorous animals in preserving the equilibrium of species — Reciprocal influence of aquatic and terrestrial species on each other.

Theory of Linnæus. — It would be superfluous to examine the various attempts which were made to explain the phenomena of the distribution of species alluded to in the preceding chapters, in the infancy of the sciences of botany, zoology, and physical geography. The theories or rather conjectures then indulged now stand refuted by a simple statement of facts; and if Linnæus were living he would be the first to renounce the notions which he promulgated. For he imagined the habitable world to have been for a certain time limited to one small tract, the only portion of the earth's surface that was as yet laid bare by the subsidence of the primæval ocean. In this fertile spot he supposed the originals of all the species of plants which exist on this globe to have been congregated together with the first ancestors of all animals and of the human race. "In quâ commodè habitaverint animalia omnia, et vegetabilia lætè germinaverint." In order to accommodate the various habitudes of so many creatures, and to provide a diversity of climate suited to their several natures, the tract in which the creation took place was supposed to have been situated in some warm region of the earth, but to have contained a lofty mountain range, on the heights and in the declivities of which were to be found all temperatures and every climate, from that of the torrid to that of the frozen zone.*

That there never was a universal ocean since the planet was inhabited, or, rather, since the oldest groups of strata yet known to contain organic remains were formed, is proved by the presence of terrestrial plants or by indications of shores in all the older formations; and if this conclusion was not established, yet no geologist could deny that, since the first small portion of the earth was laid dry, there have been many entire changes in the species of plants and animals inhabiting the land.

But, without dwelling on the above and other refuted theories, let us inquire whether some hypothesis cannot be substituted as simple as that of Linnæus, to which the phenomena now ascertained in regard to the distribution both of aquatic and terrestrial species may be referred. The following may, perhaps, be reconcileable with known facts:—Each species may have had its origin in a single pair, or individual, where an individual was sufficient, and species may have been created in succession at such times and in such places as to enable them to multiply and endure for an appointed period, and occupy an appointed space on the globe.

---

* De terrâ habitabili incremento; also Prichard, Phys. Hist. of Mankind, vol. i. p. 17., where the hypotheses of different naturalists are enumerated.

In order to explain this theory, let us suppose every living thing to be destroyed in the western hemisphere, both on the land and in the ocean, and permission to be given to man to people this great desert, by transporting into it animals and plants from the eastern hemisphere, a strict prohibition being enforced against introducing two original stocks of the same species.

Now it is easy to show that the result of such a mode of colonizing would correspond exactly, so far as regards the grouping of animals and plants, with that now observed throughout the globe. In the first place, it would be necessary for naturalists, before they imported species into particular localities, to study attentively the climate and other physical conditions of each spot. It would be no less requisite to introduce the different species in succession, so that each plant and animal might have time and opportunity to multiply before the species destined to prey upon it was admitted. Many herbs and shrubs, for example, must spread far and wide before the sheep, the deer, and the goat could be allowed to enter, lest they should devour and annihilate the original stocks of many plants, and then perish themselves for want of food. The above-mentioned herbivorous animals in their turn must be permitted to make considerable progress before the entrance of the first pair of wolves or lions. Insects must be allowed to swarm before the swallow could be permitted to skim through the air, and feast on thousands at one repast.

It is evident that, however equally in this case our original stocks were distributed over the whole surface of land and water, there would nevertheless arise distinct botanical and zoological provinces, for there are a great many natural barriers which oppose common obstacles to the advance of a variety of species. Thus, for example, almost all the animals and plants naturalized by us, towards the extremity of South America, would be unable to spread beyond a certain limit, towards the east, west, and south; because they would be stopped by the ocean, and a few of them only would succeed in reaching the cooler latitudes of the northern hemisphere, because they would be incapable of bearing the heat of the tropics, through which they must pass. In the course of ages, undoubtedly, exceptions would arise, and some species might become common to the temperate and polar regions, or both sides of the equator; for I have before shown that the powers of diffusion conferred on some classes are very great. But we might confidently predict that these exceptions would never become so numerous as to invalidate the general rule.

Some of the plants and animals transplanted by us to the coast of Chili and Peru would never be able to cross the Andes, so as to reach the eastern plains; nor, for a similar reason, would those first car-blished in the Pampas, or the valleys of the Amazon and the Orinoco, ever arrive at the shores of the Pacific.

In the ocean an analogous state of things would prevail; for there, also, climate would exert a great influence in limiting the range of species, and the land would stop the migrations of aquatic tribes as effectually as the sea arrests the dispersion of the terrestrial. As certain birds, insects, and the seeds of plants can never cross the direction of prevailing winds, so currents form natural barriers to the dissemination of many oceanic races. A line of shoals may be as impassable to deep-water species, as are the Alps and the Andes to plants and animals peculiar to plains; while deep abysses may prove insuperable obstacles to the migrations of the inhabitants of shallow waters.

Supposed centres, or foci, of creation.—It is worthy of observation, that one effect of the introduction of single pairs of each species must be the confined range of certain groups in spots, which, like small islands, or solitary inland lakes, have few means of interchanging their inhabitants with adjoining regions. Now this congregating in a small space, of many peculiar species, would give an appearance of *centres* or *foci* of creation, as they have been termed, as if they were favourite points where the creative energy has been in greater action than in others, and where the numbers of peculiar organic beings have consequently become more considerable.

I do not mean to call in question the soundness of the inferences of some botanists, as to the former existence of certain limited spots whence species of plants have been propagated, radiating, as it were, in all directions from a common centre. On the contrary, I conceive these phenomena to be the necessary consequences of the plan of nature before suggested, operating during the successive mutations of the surface, some of which the geologist can prove to have taken place subsequently to the period when many species now existing were created. In order to exemplify how this arrangement of plants may have been produced, let us imagine that, about three centuries before the discovery of St. Helena (itself of submarine volcanic origin), a multitude of new islands had been thrown up in the surrounding sea, and that these had each become clothed with plants emigrating from St. Helena, in the same manner as the wild plants of Campania have diffused themselves over Monte Nuovo. Whenever the first botanist investigated the new archipelago, he would, in all probability, find a different assemblage of plants in each of the islands of recent formation; but in St. Helena itself, he would meet with individuals of every species, belonging to all parts of the archipelago, and some, in addition, peculiar to itself, viz., those which had not been able to obtain a passage into any one of the surrounding new-formed lands. In this case it might be truly said that the original island was the primitive focus, or centre, of a certain type of vegetation; whereas, in the surrounding islands, there would be a smaller number of species, yet all belonging to the same group.

But this peculiar distribution of plants would not warrant the conclusion that, in the space occupied by St. Helena, there had been a greater exertion of creative power than in the spaces of equal area occupied by the new adjacent lands; because, within the period in which St. Helena had acquired its peculiar vegetation, each of the spots supposed to be subsequently converted into land may have been the birth-places of a great number of *marine* animals and plants, which may have had time to scatter themselves far and wide over the southern Atlantic.

Why distinct provinces not more blended.—Perhaps it may be objected to some parts of the foregoing train of reasoning, that during the lapse of past ages, especially during many partial revolutions of the globe of comparatively modern date, different zoological and botanical provinces ought to have become more confounded and blended together—that the distribution of species approaches too nearly to what might have been expected, if animals and plants had been introduced into the globe when its physical geography had already assumed the features which it now wears; whereas we know that, in certain districts, considerable geographical changes have taken place since species identical with those now in being were created.

Brocchi's speculations on loss of species.—These and many kindred topics cannot be fully discussed until we have considered, not merely the general laws which may regulate the first introduction of species, but those which may limit their *duration* on the earth. Brocchi remarked, when hazarding some interesting conjectures respecting "the loss of species," that a modern naturalist had no small assurance, who declared "that individuals alone were capable of destruction, and that species were so perpetuated that nature could not annihilate them, so long as the planet lasted, or at least that nothing less than the shock of a comet, or some similar disaster, could put an end to their existence."* The Italian geologist, on the contrary, had satisfied himself, that many species of Testacea, which formerly inhabited the Mediterranean, had become extinct, although a great number of others, which had been the contemporaries of those lost races, still survived. He came to the opinion that about half the species which peopled the waters when the Subapennine strata were deposited had gone out of existence; and in this inference he does not appear to have been far wrong.

But, instead of seeking a solution of this problem, like some other geologists of his time, in a violent and general catastrophe, Brocchi endeavoured to imagine some regular and constant law by which species might be made to disappear from the earth gradually and in succession. The death, he suggested, of a species might depend, like that of individuals, on certain peculiarities of constitution conferred upon them at their birth; and as the longevity of the one depends on a certain force of vitality, which, after a period, grows weaker and weaker, so the duration of the other may be governed by the quantity of prolific power bestowed upon the species which, after a season, may decline in energy, so that the fecundity and multiplication of individuals may be gradually lessened from century to century, "until that fatal term arrives when the embryo, incapable of extending and developing itself, abandons, almost at the instant of its formation, the slender principle of life by which it was scarcely animated,—and so all dies with it."

---

* Necker, Phytozool. Philosoph. p. 21.; Brocchi, Conch. Foss. Subap., tome i. p. 229.

Now we may coincide in opinion with the Italian naturalist, as to the gradual extinction of species one after another, by the operation of regular and constant causes, without admitting an inherent principle of deterioration in their physiological attributes. We might concede, "that many species are on the decline, and that the day is not far distant when they will cease to exist;" yet deem it consistent with what we know of the nature of organic beings, to believe that the last individuals of each species retain their prolific powers in their full intensity.

Brocchi has himself speculated on the share which a change of climate may have had in rendering the Mediterranean unfit for the habitation of certain Testacea, which still continued to thrive in the Indian Ocean, and of others which were now only represented by analogous forms within the tropics. He must also have been aware that other extrinsic causes, such as the progress of human population, or the increase of some one of the inferior animals, might gradually lead to the extirpation of a particular species, although its fecundity might remain to the last unimpaired. If, therefore, amid the vicissitudes of the animate and inanimate world, there are known causes capable of bringing about the decline and extirpation of species, it became him thoroughly to investigate the full extent to which these might operate, before he speculated on any cause of so purely hypothetical a kind as "the diminution of the prolific virtue."

If it could have been shown that some wild plant had insensibly dwindled away and died out, as sometimes happens to cultivated varieties propagated by cuttings, even though climate, soil, and every other circumstance should continue identically the same—if any animal had perished while the physical condition of the earth, and the number and force of its foes, with every other extrinsic cause, remain unaltered, then might we have some ground for suspecting that the infirmities of age creep on as naturally on species as upon individuals. But, in the absence of such observations, let us turn to another class of facts, and examine attentively the circumstances which determine the *stations* of particular animals and plants, and perhaps we shall discover, in the vicissitudes to which these stations are exposed, a cause fully adequate to explain the phenomena under consideration.

Stations of plants and animals.—Stations comprehend all the circumstances, whether relating to the animate or inanimate world, which determine whether a given plant or animal can exist in a given place; so that if it be shown that stations can become essentially

modified by the influence of known causes,
as well as individuals, are mortal.

Every naturalist is familiar with the fact,
cular country, such as Great Britain, there
thousand species of plants, ten thousand i
in each of the other classes; yet there wil
dred, perhaps not half that number, inhal
There may be no want of space in the s
a large mountain, or an extensive moor, o
taining room enough for individuals of ev
yet the spot will be occupied by a few to th
these few are enabled, throughout long p
ground successfully against every intruder,
lities which species enjoy, by virtue of th
invading adjacent territories.

The principal causes which enable a cer
thus to maintain their ground against all
known, on the relations between the phy
species, and the climate, exposure, soil, and
of the locality. Some plants live only on
a third class in marshes. Of the latter,
water morass,—others in salt marshes,
copiously absorb saline particles. Some p
warm latitude, where, during the heat of su
irrigated by the cool waters of melting snow
so fatal to the generality of species, affords
The *Carex arenaria* and the *Elymus ar*
vigour on a sandy dune, obtaining an ascen
which in a stiff clay would immediately stif

Where the soil of a district is of so p
extremely favourable to certain species,
other, the former get exclusive possession
the case of heaths, live in societies. In
(*Sphagnum*) is fully developed in peaty s
the heath, in the language of botanists, a
polies, however, are not common, for the
causes. Not only are many species endow
obtain and keep possession of similar sta
reasons not fully explained by the physiol
rendering the soil where it has grown l
of other individuals of its own species, or
same family. Yet the same spot, so far fr
improved, for plants of *another* family.
the soil more fertile for the fir tribe, an
oaks. Every agriculturist feels the force o
world, and regulates accordingly the rotati

Equilibrium in the number of species, h
plants of a given country," says De Can
style, "are at war one with another.

themselves by chance in a particular spot tend, by the mere occupancy of space, to exclude other species—the greater choke the smaller; the longest livers replace those which last for a shorter period; the more prolific gradually make themselves masters of the ground, which species multiplying more slowly would otherwise fill."

In this continual strife it is not always the resources of the plant itself which enable it to maintain or extend its ground. Its success depends, in a great measure, on the number of its foes or allies, among the animals and plants inhabiting the same region. Thus, for example, a herb which loves the shade may multiply, if some tree with spreading boughs and dense foliage flourish in the neighbourhood. Another, which, if unassisted, would be overpowered by the rank growth of some hardy competitor, is secure because its leaves are unpalatable to cattle; which, on the other hand, annually crop down its antagonist, and rarely suffer it to ripen its seed.

Oftentimes we see some herb which has flowered in the midst of a thorny shrub, when all the other individuals of the same species, in the open fields around, are eaten down, and cannot bring their seed to maturity. In this case, the shrub has lent his armour of spines and prickles to protect the defenceless herb against the mouths of the cattle; and thus a few individuals which occupied, perhaps, the most unfavourable station in regard to exposure, soil, and other circumstances, may, nevertheless, by the aid of an ally, become the principal source whereby the winds are supplied with seeds which perpetuate the species throughout the surrounding tract. Thus, in the New Forest in Hampshire, the young oaks which are not consumed by the deer, or uprooted by the swine, are indebted to the holly for their escape.

In the above examples we see one plant shielding another from the attacks of animals; but instances are, perhaps, still more numerous, where some animal defends a plant against the enmity of some other subject of the vegetable kingdom.

Scarcely any beast, observes a Swedish naturalist, will touch the nettle, but fifty different kinds of insects are fed by it.* Some of these seize upon the root, others upon the stem; some eat the leaves; others devour the seeds and flowers: but for this multitude of enemies, the nettle (*Urtica dioica*), which is now found in all the four quarters of the globe, would annihilate a great number of plants. Linnæus tells us, in his "Tour in Scania," that goats were turned into an island which abounded with the *Agrostis arundinacea*, where they perished by famine; but horses which followed them grew fat on the same plant. The goat, also, he says, thrives on the meadow-sweet and water-hemlock, plants which are injurious to cattle.†

Agency of insects.—Every plant, observes Wilcke, has its proper insect allotted to it to curb its luxuriancy, and to prevent it from multiplying to the exclusion of others. "Thus grass in meadows sometimes flourishes so as to exclude all other plants: here the Phalæna graminis (*Bombyx gram.*), with her numerous progeny, finds a well-spread table; they multiply in immense numbers, and the farmer, for some years, laments the failure of his crop; but, the grass being consumed, the moths die with hunger, or remove to another place. Now the quantity of grass being greatly diminished, the other plants, which were before choked by it, spring up, and the ground becomes variegated with a multitude of different species of flowers. Had not Nature given a commission to this minister for that purpose the grass would destroy a great number of species of vegetables, of which the equilibrium is now kept up."[*]

---

* Amœn. Acad. vol. vi. p. 17. § 12.

† Ibid. vol. vii. p. 409.

In the above passage allusion is made to the ravages committed in 1740, and the two following years, in many provinces of Sweden, by a most destructive insect. The same moth is said never to touch the foxtail grass, so that it may be classed as a most active ally and benefactor of that species, and as peculiarly instrumental in preserving it in its present abundance.[†] A discovery of Rolander, cited in the treatise of Wilcke above mentioned, affords a good illustration of the checks and counter-checks which Nature has appointed to preserve the balance of power among species. "The *Phalæna strobilella* has the fir cone assigned to it to deposit its eggs upon; the young caterpillars coming out of the shell consume the cone and superfluous seed; but, lest the destruction should be too general, the *Ichneumon strobilellæ* lays its eggs in the caterpillar, inserting its long tail in the openings of the cone till it touches the included insect, for its body is too large to enter. Thus it fixes its minute egg upon the caterpillar, which being hatched, destroys it."[‡]

Entomologists enumerate many parallel cases where insects, appropriated to certain plants, are kept down by other insects, and these again by parasites expressly appointed to prey on them.[§] Few, perhaps, are in the habit of duly appreciating the extent to which insects are active in preserving the balance of species among plants, and thus regulating indirectly the relative numbers of many of the higher orders of terrestrial animals.

The peculiarity of their agency consists in their power of suddenly multiplying their numbers to a degree which could only be accomplished in a considerable lapse of time in any of the larger animals, and then as instantaneously relapsing, without the intervention of any violent disturbing cause, into their former insignificance.

If, for the sake of employing, on different but rare occasions, a power of many hundred horses, we were under the necessity of feeding all these animals at great cost in the intervals when their services were not required, we should greatly admire the invention of a machine, such as the steam-engine, which was capable at any moment of exerting the same degree of strength without any consumption of food during periods of inaction. The same kind of admiration is strongly excited when we contemplate the powers of insect life, in the creation of which the Author of Nature has been so prodigal. A scanty number of minute individuals, to be detected only by careful research, are ready in a few days, weeks, or months, to give birth to myriads, which may repress any degree of monopoly in another species, or remove nuisances, such as dead carcases, which might taint the air. But no sooner has the destroying commission been executed than the gigantic power becomes dormant—each of the mighty host soon reaches the term of its transient existence, and the season arrives when the whole species passes naturally into the egg, and thence into the larva and pupa state. In this defenceless condition it may be destroyed either by the elements, or by the augmentation of some of its numerous foes which may prey upon it in the early stages of its transformation; or it often happens that in the following year the season proves unfavourable to the hatching of the eggs or the development of the pupæ.

---

[*] Amœn. Acad., vol. vi. p. 17. § 11, 12.

[†] Kirby and Spence, vol. i. p. 178.

[‡] Amœn. Acad., vol. vi. p. 26. § 14.

[§] Kirby and Spence, vol. iv. p. 218.

Thus the swarming myriads depart which may have covered the vegetation like the aphides, or darkened the air like locusts. In almost every season there are some species which in this manner put forth their strength, and then, like Milton's spirits, which thronged the spacious hall, "reduce to smallest forms their shapes immense"—

> ——— So thick the aëry crowd
> Swarm'd and were straiten'd; till, the signal given,
> Behold a wonder! they but now who seem'd
> In bigness to surpass earth's giant sons,
> Now less than smallest dwarfs.

A few examples will illustrate the mode in which this force operates. It is well known that, among the countless species of the insect creation, some feed on animal, others on vegetable matter; and, upon considering a catalogue of eight thousand British Insects and Arachnidæ, Mr. Kirby found that these two divisions were nearly a counterpoise to each other, the carnivorous being somewhat preponderant. There are also distinct species, some appointed to consume living, others dead or putrid animal and vegetable substances. One female, of *Musca carnaria*, will give birth to twenty thousand young; and the larvæ of many flesh-flies devour so much food in twenty-four hours, and grow so quickly, as to increase their weight two hundred-fold! In five days after being hatched they arrive at their full growth and size, so that there was ground, says Kirby, for the assertion of Linnæus, that three flies of *M. vomitoria* could devour a dead horse as quickly as a lion *; and another Swedish naturalist remarks, that so great are the powers of propagation of a single species even of the smallest insects, that each can commit, when required, more ravages than the elephant. †

Next to locusts, the aphides, perhaps, exert the greatest power over the vegetable world, and, like them, are sometimes so numerous

---

* Kirby and Spence, vol. i. p. 250. † Wilcke, Amœn. Acad. c. ii.

as to darken the air. The multiplicatio
without parallel, and almost every pla
Reaumur has proved that in five gener
progenitor of 5,904,900,000 descendant
one year there may be twenty generat
that, as among caterpillars we find so
unalterably attached to one or more par
others that feed indiscriminately on m
precisely with the aphides: some are pa
feeders; and as they resemble other ins
do also in being more abundant in some
1793 they were the chief, and in 1798
of the hops. In 1794, a season almost
hop was perfectly free from them; whil
the former, suffered very much from the

The ravages of the caterpillars of som
a good illustration of the temporary inc
trees of a considerable wood have been
bare as in winter, by the caterpillars of
viridana), which has been observed the y
The silver Y moth (*Plusia gamma*), a
species, is not dreaded by us for its d
their caterpillars have at times created
Reaumur observes that the female mo
eggs; so that if twenty caterpillars were
all lived through the winter and beca
May, the eggs laid by these, if half o
fertile, would in the next generation pr
A modern writer, therefore, justly obser
put causes in operation to keep them in
of this moth alone, leaving out of cons
other British species, might soon destroy
tation.‖

In the latter part of the last century
the sugar-cane (*Formica saccharivora*),
hosts in the island of Granada, as to pu
that vegetable. Their numbers were i
and roads were filled with them; many d
with rats, mice, and reptiles, and even bi
of this plague. It was not till 1780 th
hilated by torrents of rain, which accom

Devastations caused by locusts.—We
some instances of the devastations of
Among other parts of Africa, Cyrenaica
infested by myriads of these creatures

---

* Kirby and Spence, vol. i. p. 174.
† Trans. Linn. Soc., vol. vi.
‡ Lib. Ent. Know., Insect Trans.,
p 203. See Haworth, Lep.
§ Reaumur, ii. 337.

‖ L
p. 212
¶ F
Castle

every green thing. The effect of the havoc committed by them may be estimated by the famine they occasioned. St. Augustin mentions a plague of this kind in Africa which destroyed no less than 800,000 men in the kingdom of Massinissa alone, and many more upon the territories bordering upon the sea. It is also related, that in the year 591, an infinite army of locusts migrated from Africa into Italy; and, after grievously ravaging the country, were cast into the sea, when there arose a pestilence from their stench which carried off nearly a million of men and beasts.

In the Venetian territory, also, in 1478, more than thirty thousand persons are said to have perished in a famine occasioned by this scourge; and other instances are recorded of their devastations in France, Spain, Italy, Germany, &c. In different parts of Russia also, Hungary, and Poland,—in Arabia and India, and other countries, their visitations have been periodically experienced. Although they have a preference for certain plants, yet, when these are consumed, they will attack almost all the remainder. In the accounts of the invasions of locusts, the statements which appear most marvellous relate to the prodigious mass of matter which encumbers the sea wherever they are blown into it, and the pestilence arising from its putrefaction. Their dead bodies are said to have been, in some places, heaped one upon another, to the depth of four feet, in Russia, Poland, and Lithuania; and when, in Southern Africa, they were driven into the sea, by a north-west wind, they formed, says Barrow, along the shore, for fifty miles, a bank three or four feet high.* But when we consider that forests are stripped of their foliage, and the earth of its green garment, for thousands of square miles, it may well be supposed that the volume of animal matter produced may equal that of great herds of quadrupeds and flights of large birds suddenly precipitated into the sea.

The occurrence of such events at certain intervals, in hot countries, like the severe winters and damp summers returning after a series of years in the temperate zone, may affect the proportional numbers of almost all classes of animals and plants, and probably prove fatal to the existence of many which would otherwise thrive there; while, on the contrary, the same occurrences can scarcely fail to be favourable to certain species which, if deprived of such aid, might not maintain their ground.

Although it may usually be remarked that the extraordinary increase of some one species is immediately followed and checked by the multiplication of another, yet this does not always happen; partly because many species feed in common on the same kinds of food, and partly because many kinds of food are often consumed indifferently by one and the same species. In the former case, where a variety of different animals have precisely the same taste, as, for example, when many insectivorous birds and reptiles devour alike some particular fly or beetle, the unusual numbers of these insects may cause only a slight and almost imperceptible augmentation of each of these species of bird and reptile. In the other instance, where one animal preys on others of almost every class, as, for example, where our English buzzards devour not only small quadrupeds, as rabbits and field-mice, but also birds, frogs, lizards, and insects, the profusion of any one of these last may cause all such general feeders to subsist more exclusively upon the species thus in excess, by which means the balance may be restored.

---

* Travels in Africa, p. 257. Kirby and Spence, vol. i. p. 215.

Agency of omnivorous animals.—The number of species which are nearly omnivorous is considerable; and although every animal has, perhaps, a predilection for some one description of food rather than another, yet some are not even confined to one of the great kingdoms of the organic world. Thus, when the racoon of the West Indies can procure neither fowls, fish, snails, nor insects, it will attack the sugar-canes, and devour various kinds of grain. The civets, when animal food is scarce, maintain themselves on fruits and roots.

Numerous birds, which feed indiscriminately on insects and plants, are perhaps more instrumental than any other of the terrestrial tribes in preserving a constant equilibrium between the relative numbers of different classes of animals and vegetables. If the insects become very numerous and devour the plants, these birds will immediately derive a larger portion of their subsistence from insects, just as the Arabians, Syrians, and Hottentots feed on locusts, when the locusts devour their crops.

Reciprocal influence of aquatic and terrestrial species.—The intimate relation of the inhabitants of the water to those of the land, and the influence exerted by each on the relative number of species, must not be overlooked amongst the complicated causes which determine the existence of animals and plants in certain regions. A large portion of the amphibious quadrupeds and reptiles prey partly on aquatic plants and animals, and in part on terrestrial; and a deficiency of one kind of prey causes them to have immediate recourse to the other. The voracity of certain insects, as the dragon-fly, for example, is confined to the water during one stage of their transformations, and in their perfect state to the air. Innumerable water-birds, both of rivers and seas, derive in like manner their food indifferently from either element; so that the abundance or scarcity of prey in one induces them either to forsake or more constantly to haunt the other. Thus an intimate connection between the state of the animate creation in a lake or river, and in the adjoining dry land, is maintained; or between a continent, with its lakes and rivers, and the ocean. It is well known that many birds migrate, during stormy seasons, from the sea-shore into the interior, in search of food; while others, on the contrary, urged by like wants, forsake their inland haunts, and live on substances rejected by the tide.

The migration of fish into rivers during the spawning season supplies another link of the same kind. Suppose the salmon to be reduced in numbers by some marine foes, as by seals and grampuses the consequence must often be, that in the course of a few years the otters at the distance of several hundred miles inland, will be lessened in number from the scarcity of fish. On the other hand, if there be a dearth of food for the young fry of the salmon in rivers and estuaries, so that few return to the sea, the sand-eels and other marine species, which are usually kept down by the salmon, will swarm in greater profusion.

It is unnecessary to accumulate a greater number of illustrations in order to prove that the stations of different plants and animals depend on a great complication of circumstances,—on an immense variety of relations in the state of the animate and inanimate worlds. Every plant requires a certain climate, soil, and other conditions, and often the aid of many animals, in order to maintain its ground. Many animals feed on certain plants, being often restricted to a small number, and sometimes to one only; other members of the animal kingdom feed on plant-eating species, and thus become dependent on the conditions of the *stations* not only of their prey, but of the plants consumed by them.

Having duly reflected on the nature and extent of these mutual relations in the different parts of the organic and inorganic worlds, we may next proceed to examine the results which may be anticipated from the fluctuations now continually in progress in the state of the earth's surface, and in the geographical distribution of its living productions.

CHAPTER XLI.

EXTINCTION OF SPECIES.—CHANGES IN THE STATIONS OF ANIMALS.

Extension of the range of one species alters the condition of many others—The first appearance of a new species causes the chief disturbance—Changes known to have resulted from the advance of human population—Whether man increases the productive powers of the earth—Indigenous quadrupeds and birds extirpated in Great Britain—Extinction of the dodo—Rapid propagation of domestic quadrupeds in America—Power of exterminating species no prerogative of man—Concluding remarks.

WE have seen that the stations of animals and plants depend not merely on the influence of external agents in the inanimate world, and the relations of that influence to the structure and habits of each species, but also on the state of the contemporary living beings which inhabit the same part of the globe. In other words, the possibility of the existence of a certain species in a given place, or of its thriving more or less therein, is determined not merely by temperature, humidity, soil, elevation, and other circumstances of the like kind; but also by the existence or non-existence, the abundance or scarcity, of a particular assemblage of other plants and animals in the same region.

If it be shown that both these classes of circumstances, whether relating to the animate or inanimate creation, are perpetually changing, it will follow that species are subject to incessant vicissitudes; and if the result of these mutations, in the course of ages, be so great as materially to affect the general condition of *stations*, it will follow that the successive destruction of species must now be part of the regular and constant order of nature.

Extension of the range of one species alters the condition of others. — It will be desirable, first, to consider the effects which every extension of the numbers or geographical range of one species must produce on the condition of others inhabiting the same regions. When the necessary consequences of such extensions have been fully explained, the reader will be prepared to appreciate the important influence which slight modifications in the physical geography of the globe may exert on the condition of organic beings.

In the first place, it is clear that when any region is stocked with as great a variety of animals and plants as the productive powers of that region will enable it to support, the addition of any new species, or the *permanent* numerical increase of one previously established, must always be attended either by the local extermination or the numerical decrease of some other species.

There may undoubtedly be considerable fluctuations from year to year, and the equilibrium may be again restored without any permanent alteration; for, in particular seasons, a greater supply of heat, humidity, or other causes, may augment the total quantity of vegetable produce, in which case all the animals subsisting on vegetable food, and others which prey on them, may multiply without any one species giving way: but whilst the aggregate quantity of vegetable produce remains unaltered, the progressive increase of one animal or plant implies the decline of another.

All agriculturists and gardeners are familiar with the fact that when weeds intrude themselves into the space appropriated to cultivated species, the latter are starved in their growth or stifled. If we abandon for a short time a field or garden, a host of indigenous plants,

> The darnel, hemlock, and rank fumitory,

pour in and obtain the mastery, extirpating the exotics, or putting an end to the monopoly of some native plants.

If we inclose a park, and stock it with as many deer as the herbage will support, we cannot add sheep without lessening the number of the deer; nor can other herbivorous species be subsequently introduced, unless the individuals of each species in the park become fewer in proportion.

So, if there be an island where leopards are the only beasts of prey, and the lion, tiger, and hyæna afterwards enter, the leopards, if they stand their ground, will be reduced in number. If the locusts then arrive and swarm greatly, they may deprive a large number of plant-eating animals of their food, and thereby cause a famine, and only among them, but among the beasts of prey: certain species perhaps, which had the weakest footing in the island may thus be annihilated.

We have seen how many distinct geographical provinces there are of aquatic and terrestrial species, and how great are the powers of migration conferred on different classes, whereby the inhabitants of one region may be enabled from time to time to invade another, and do actually so migrate and diffuse themselves over new countries. Now, although our knowledge of the history of the animate creation dates from so recent a period, that we can scarcely trace the advance or decline of any animal or plant, except in those cases where the influence of man has intervened; yet we can easily conceive what must happen when some new colony of wild animals or plants enters a region for the first time, and succeeds in establishing itself.

Supposed effects of the first entrance of the polar bear into Iceland.—Let us consider how great are the devastations committed at certain periods by the Greenland bears, when they are drifted to the shores of Iceland in considerable numbers on the ice. These periodical invasions are formidable even to man; so that when the bears arrive, the inhabitants collect together, and go in pursuit of them with fire-arms—each native who slays one being rewarded by the king of Denmark. The Danes of old, when they landed in their marauding expeditions upon our coast, hardly excited more alarm, nor did our islanders muster more promptly for the defence of their lives and property against the common enemy, than the modern Icelanders against these formidable brutes. It often happens, says Henderson, that the natives are pursued by the bear when he has been long at sea, and when his natural ferocity has been heightened by the keenness of hunger; if unarmed, it is frequently by stratagem only that they make their escape.*

Let us cast our thoughts back to the period when the first polar bears reached Iceland, before it was colonized by the Norwegians in 874; we may imagine the breaking up of an immense barrier of ice like that which, in 1816 and the following year, disappeared from the east coast of Greenland, which it had surrounded for four centuries. By the aid of such means of transportation a great number of these quadrupeds might effect a landing at the same time, and the havoc which they would make among the species previously settled in the island would be terrific. The deer, foxes, seals, and even birds, on which these animals sometimes prey, would be soon thinned down.

But this would be a part only, and probably an insignificant portion, of the aggregate amount of change brought about by the new invader. The plants on which the deer fed, being less consumed in consequence of the lessened numbers of that herbivorous species, would soon supply more food to several insects, and probably to some terrestrial testacea, so that the latter would gain ground. The increase of these would furnish other insects and birds with food, so that the numbers of these last would be augmented. The diminution of the seals would afford a respite to some fish which they had persecuted; and these fish, in their turn, would then multiply and press upon their peculiar prey. Many water-fowls, the eggs and young of which are devoured by foxes, would increase when the foxes were thinned down by the bears; and the fish on which the water-fowls subsisted would then, in their turn, be less numerous. Thus the numerical proportions of a great number of the inhabitants, both of the land and sea, might be permanently altered by the settling of one new species in the region; and the changes caused indirectly would ramify through all classes of the living creation, and be almost endless.

---

* Journal of a Residence in Iceland, p. 276.

An actual illustration of what we have here only proposed hypothetically, is in some degree afforded by the selection of small islands by the eider duck for its residence during the season of incubation, its nest being seldom if ever found on the shores of the main land, or even of a large island. The Icelanders are so well aware of this, that they have expended a great deal of labour in forming artificial islands, by separating from the main land certain promontories, joined to it by narrow isthmuses. This insular position is necessary to guard against the destruction of the eggs and young birds, by foxes, dogs, and other animals. One year, says Hooker, it happened that, in the small island of Vidoe, adjoining the coast of Iceland, a fox got over *upon the ice*, and caused great alarm, as an immense number of ducks were then sitting on their eggs or young ones. It was long before he was taken, which was at last, however, effected by bringing another fox to the island, and fastening it by a string near the haunt of the former, by which he was allured within shot of the hunter.*

The first appearance of a new species causes the chief disturbance. — It is usually the first appearance of an animal or plant, in a region to which it was previously a stranger, that gives rise to the chief alteration; since, after a time, an equilibrium is again established. But it must require ages before such a new adjustment of the relative forces of so many conflicting agents can be definitely settled. The causes in simultaneous action are so numerous, that they admit of an almost infinite number of combinations; and it is necessary that all these should have occurred once before the total amount of change, capable of flowing from any new disturbing force, can be estimated.

Thus, for example, suppose that once in two centuries a frost of unusual intensity, or a volcanic eruption of great violence accompnied by floods from the melting of glaciers, should occur in Iceland; or an epidemic disease, fatal to the larger number of individuals of some one species, and not affecting others, — these, and a variety of other contingencies, all of which may occur at once, or at periods separated by different intervals of time, ought to happen before it would be possible for us to declare what ultimate alteration the presence of any new comer, such as the bear before mentioned, might occasion in the animal population of the isle.

---

* Tour in Iceland, vol. i. p. 64, 2nd edit.

Every new condition in the state of the organic or inorganic creation, a new animal or plant, an additional snow-clad mountain, any permanent change, however slight in comparison to the whole, gives rise to a new order of things, and may make a material change in regard to some one or more species. Yet a swarm of locusts, or a frost of extreme intensity, or an epidemic disease, may pass away without any great apparent derangement; no species may be lost, and all may soon recover their former relative numbers, because the same scourges may have visited the region again and again, at preceding periods. Every plant that was incapable of resisting such a degree of cold, every animal which was exposed to be entirely cut off by an epidemic or by famine caused by the consumption of vegetation by the locusts, may have perished already, so that the subsequent recurrence of similar catastrophes is attended only by a temporary change.

Changes caused by Man.

We are best acquainted with the mutations brought about by the progress of human population, and the growth of plants and animals favoured by man. To these, therefore, we should in the first instance turn our attention. If we conclude, from the concurrent testimony of history and of the evidence yielded by geological data, that man is, comparatively speaking, of very modern origin, we must at once perceive how great a revolution in the state of the animate world the increase of the human race, considered merely as consumers of a certain quantity of organic matter, must necessarily cause.

Whether man increases the productive powers of the earth.—It may perhaps, be said, that man has, in some degree, compensated for the appropriation to himself of so much food, by artificially improving the natural productiveness of soils, by irrigation, manure, and a judicious intermixture of mineral ingredients conveyed from different localities. But it admits of reasonable doubt whether, upon the whole, we fertilize or impoverish the lands which we occupy. This assertion may seem startling to many; because they are so much in the habit of regarding the sterility or productiveness of land in relation to the wants of man, and not as regards the organic world generally. It is difficult, at first, to conceive, if a morass is converted into arable land, and made to yield a crop of grain, even of moderate abundance, that we have not improved the capabilities of the habitable surface—that we have not empowered it to support a larger quantity of organic life. In such cases, however, a tract, before of no utility to man, may be reclaimed, and become of high agricultural importance, though it may, nevertheless, yield a scantier vegetation. If a lake be drained, and turned into a meadow, the space will provide sustenance to man, and many terrestrial animals serviceable to him, but not, perhaps, so much food as it previously yielded to the aquatic races.

If the pestiferous Pontine marshes were drained, and covered with corn, like the plains of the Po, they might, perhaps, feed a smaller number of animals than they do now; for these morasses are filled with herds of buffaloes and swine, and they swarm with birds, reptiles, and insects.

The felling of dense and lofty forests, which covered, even within the records of history, a considerable space on the globe, now tenanted by civilized man, must generally have lessened the amount of vegetable food throughout the space where these woods grew. We must also take into our account the area covered by towns, and a still larger surface occupied by roads.

If we force the soil to bear extraordinary crops one year, we are, perhaps, compelled to let it lie fallow the next. But nothing so much counterbalances the fertilizing effects of human art as the extensive cultivation of foreign herbs and shrubs, which, although they are often more nutritious to man, seldom thrive with the same rank luxuriance as the native plants of a district. Man is, in truth, continually striving to diminish the natural diversity of the stations of animals and plants in every country, and to reduce them all to a small number fitted for species of economical use. He may succeed perfectly in attaining his object, even though the vegetation be comparatively meagre, and the total amount of animal life be greatly lessened.

Spix and Martius have given a lively description of the incredible number of insects which lay waste the crops in Brazil, besides swarms of monkeys, flocks of parrots, and other birds, as well as the paca, agouti, and wild swine. They describe the torment which the planter and the naturalist suffer from the musquitoes, and the devastation of the ants and blattæ; they speak of the dangers to which they were exposed from the jaguar, the poisonous serpents, crocodiles, scorpions, centipedes, and spiders. But with the increasing population and cultivation of the country, say these naturalists, these evils will gradually diminish; when the inhabitants have cut down the woods, drained the marshes, made roads in all directions, and founded villages and towns, man will, by degrees, triumph over the rank vegetation and the noxious animals, and all the elements will second and amply recompense his activity.*

The number of human beings now peopling the earth is supposed to amount to eight hundred millions, so that we may easily understand how great a number of beasts of prey, birds, and animals of every class, this prodigious population must have displaced, independently of the still more important consequences which have followed from the derangement brought about by man in the relative numerical strength of particular species.

---

* Travels in Brazil, vol. i. p. 260.

Indigenous quadrupeds and birds extirpated in Great Britain.— Let us make some inquiries into the extent of the influence which the progress of society has exerted during the last seven or eight centuries, in altering the distribution of indigenous British animals. Dr. Fleming has prosecuted this inquiry with his usual zeal and ability; and in a memoir on the subject has enumerated the best-authenticated examples of the decrease or extirpation of certain species during a period when our population has made the most rapid advances. I shall offer a brief outline of his results.*

The stag, as well as the fallow deer and the roe, were formerly so abundant in our island, that, according to Lesley, from five hundred to a thousand were sometimes slain at a hunting-match; but the native races would already have been extinguished, had they not been carefully preserved in certain forests. The otter, the marten, and the polecat, were also in sufficient numbers to be pursued for the sake of their fur; but they have now been reduced within very narrow bounds. The wild cat and fox have also been sacrificed throughout the greater part of the country, for the security of the poultry-yard or the fold. Badgers have been expelled from nearly every district, which at former periods they inhabited.

Besides these, which have been driven out from their favourite haunts, and every where reduced in number, there are some which have been wholly extirpated; such as the ancient breed of indigenous horses, and the wild boar; of the wild oxen a few remains are still preserved in some of the old English parks. The beaver, which is eagerly sought after for its fur, had become scarce at the close of the ninth century; and, by the twelfth century, was only to be met with, according to Giraldus de Barri, in one river in Wales, and another in Scotland. The wolf, once so much dreaded by our ancestors, is said to have maintained its ground in Ireland so late as the beginning of the eighteenth century (1710), though it had been extirpated in Scotland thirty years before, and in England at a much earlier period. The bear, which, in Wales, was regarded as a beast of the chase equal to the hare or the boar†, only perished, as a native of Scotland, in the year 1057.‡

Many native birds of prey have also been the subjects of unremitting persecution. The eagles, larger hawks, and ravens, have disappeared from the more cultivated districts. The haunts of the mallard, the snipe, the redshank, and the bittern, have been drained equally with the summer dwellings of the lapwing and the curlew. But these species still linger in some portion of the British isles; whereas the larger capercailzies or wood grouse, formerly natives of the pine-forests of Ireland and Scotland, have been destroyed within the last sixty years. The egret and the crane, which appear to have been formerly very common in Scotland, are now only occasional visitants.§

The bustard (*Otis tarda*), observes Graves, in his British Ornithology*, "was formerly seen in the downs and heaths of various parts of our island, in flocks of forty or fifty birds; whereas it is now a circumstance of rare occurrence to meet with a single individual." Bewick also remarks, "that they were formerly more common in this island than at present; they are now found only in the open counties of the south and east—in the plains of Wiltshire, Dorsetshire, and some parts of Yorkshire."† In the few years that have elapsed since Bewick wrote, this bird has entirely disappeared from Wiltshire and Dorsetshire.

---

* Ed. Phil. Journ., No. xxii. p. 287. Oct. 1824.

† Ray. Syn. Quad., p. 214.

‡ Fleming, Ed. Phil. Journ., No. xxii. p. 295.

§ Fleming, ibid., p. 292.

These changes, it may be observed, are derived from very imperfect memorials, and relate only to the larger and more conspicuous animals inhabiting a small spot on the globe; but they cannot fail to exalt our conception of the enormous revolutions which, in the course of several thousand years, the whole human species must have effected.

Extinction of the dodo.—The kangaroo and the emu are retreating rapidly before the progress of colonization in Australia; and it scarcely admits of doubt, that the general cultivation of that country must lead to the extirpation of both. The most striking example of the loss, even within the last two centuries, of a remarkable species, is that of the dodo—a bird first seen by the Dutch, when they landed on the Isle of France, at that time uninhabited, immediately after the discovery of the passage to the East Indies by the Cape of Good Hope. It was of a large size, and singular form; its wings short, like those of an ostrich, and wholly incapable of sustaining its heavy body, even for a short flight. In its general appearance it differed from the ostrich, cassowary, or any known bird.‡

Many naturalists gave figures of the dodo after the commencement of the seventeenth century; and there is a painting of it in the British Museum, which is said to have been taken from a living individual. Beneath the painting is a leg, in a fine state of preservation, which ornithologists are agreed cannot belong to any other known bird. In the museum at Oxford, also, there is a foot and a head in an imperfect state.

In spite of the most active search, during the last century, no information respecting the dodo was obtained, and some authors have gone so far as to pretend that it never existed; but a great mass of satisfactory evidence in favour of its recent existence has now been collected by Mr. Broderip§, and by Mr. Strickland and Dr. Melville. Mr. Strickland, agreeing with Professor Reinhardt, of Copen-

---

[*] Vol. iii. London, 1821.

[†] Land Birds, vol. i. p. 316. ed. 1821.

Some have complained that inscriptions on tomb-stones convey no general information, except that individuals were born and died, accidents which must happen alike to all men. But the death of a *species* is so remarkable an event in natural history that it deserves commemoration, and it is with no small interest that we learn, from the archives of the University of Oxford, the exact day and year when the remains of the last specimen of the dodo, which had been permitted to rot in the Ashmolean Museum, were cast away. The relics, we are told, were "a musæo subducta, annuente vice-cancellario aliisque curatoribus, ad ea lustranda convocatis, die Januarii 8vo, A.D. 1755." Zool. Journ. No. 12. p. 559. 1828.

[§] Penny Cyclopædia, "Dodo." 1837.

hagen, in referring the dodo to the Columbidæ, calls it a "vulture-like frugiverous pigeon." It appears, also, that another short-winged bird of the same order, called "The Solitaire," inhabited the small island of Rodrigues, 300 miles east of the Mauritius, and has been exterminated by man, as have one or two different but allied birds of the Isle of Bourbon.*

Rapid propagation of domestic quadrupeds over the American continent.—Next to the direct agency of man, his indirect influence in multiplying the numbers of large herbivorous quadrupeds of domesticated races may be regarded as one of the most obvious causes of the extermination of species. On this, and on several other grounds, the introduction of the horse, ox, and other mammalia, into America, and their rapid propagation over that continent within the last three centuries, is a fact of great importance in natural history. The extraordinary herds of wild cattle and horses which overran the plains of South America sprung from a very few pairs first carried over by the Spaniards; and they prove that the wide geographical range of large species in great continents does not necessarily imply that they have existed there from remote periods.

Humboldt observes, in his Travels, on the authority of Azzara, that it is believed there exist, in the Pampas of Buenos Ayres, twelve million cows and three million horses, without comprising, in this enumeration, the cattle that have no acknowledged proprietor. In the Llanos of Caraccas, the rich hateros, or proprietors of pastoral farms, are entirely ignorant of the number of cattle they possess. The young are branded with a mark peculiar to each herd, and some of the most wealthy owners mark as many as fourteen thousand a year.† In the northern plains, from the Orinoco to the lake of Maraycabo, M. Depons reckoned that 1,200,000 oxen, 180,000 horses, and 90,000 mules, wandered at large.‡ In some parts of the valley of the Mississippi, especially in the country of the Osage Indians, wild horses are immensely numerous.

The establishment of black cattle in America dates from Columbus's second voyage to St. Domingo. They there multiplied rapidly; and that island presently became a kind of nursery from which these animals were successively transported to various parts of the continental coast, and from thence into the interior. Notwithstanding these numerous exportations, in twenty-seven years after the discovery of the island, herds of four thousand head, as we learn from Oviedo, were not uncommon, and there were even some that amounted to eight thousand. In 1587, the number of hides exported from St. Domingo alone, according to Acosta's report, was 35,444; and in the same year there were exported 64,350 from the ports of New Spain. This was in the sixty-fifth year after the taking of Mexico, previous to which event the Spaniards, who came into that country, had not been able to engage in any thing else than war.§ Every one is aware that these animals are now established throughout the American continent from Canada to the Straits of Magellan.

---

* Messrs. Strickland and Melville on "the Dodo and its Kindred." London, 1848.

† Pers. Nar. vol. iv.

‡ Quarterly Review, vol. xxi. p. 335.

§ Ibid.

The ass has thriven very generally in the New World; and we learn from Ulloa, that in Quito they ran wild, and multiplied in amazing numbers, so as to become a nuisance. They grazed together in herds, and when attacked defended themselves with their mouths. If a horse happened to stray into the places where they fed, they all fell upon him, and did not cease biting and kicking till they left him dead.*

The first hogs were carried to America by Columbus, and established in the island of St. Domingo the year following its discovery, in November, 1493. In succeeding years they were introduced into other places where the Spaniards settled; and, in the space of half a century, they were found established in the New World, from the latitude of 25° north, to the 40th degree of south latitude. Sheep, also, and goats have multiplied enormously in the New World, as have also the cat and the rat; which last, as before stated, has been imported unintentionally in ships. The dogs introduced by man which have at different periods become wild in America, hunted in packs, like the wolf and the jackall, destroying not only hogs, but the calves and foals of the wild cattle and horses.

Ulloa in his voyage, and Buffon on the authority of old writers, relate a fact which illustrates very clearly the principle before explained, of the check which the increase of one animal necessarily offers to that of another. The Spaniards had introduced goats into the island of Juan Fernandez, where they became so prolific as to furnish the pirates who infested those seas with provisions. In order to cut off this resource from the buccaneers, a number of dogs were turned loose into the island; and so numerous did they become in their turn, that they destroyed the goats in every accessible part, after which the number of the wild dogs again decreased.†

Increase of rein-deer imported into Iceland.—As an example of the rapidity with which a large tract may become peopled by the offspring of a single pair of quadrupeds, it may be mentioned that in the year 1773 thirteen rein-deer were exported from Norway, only three of which reached Iceland. These were turned loose into the mountains of Guldbringè Syssel, where they multiplied so greatly, in the course of forty years, that it was not uncommon to meet with herds, consisting of from forty to one hundred, in various districts.

The rein-deer, observes a modern writer, is in Lapland a loser by his connexion with man, but Iceland will be this creature's paradise. There is, in the interior, a tract which Sir G. Mackenzie computes at not less than forty thousand square miles, without a single human habitation, and almost entirely unknown to the natives themselves. There are no wolves; the Icelanders will keep out the bears; and the rein-deer, being almost unmolested by man, will have no enemy whatever, unless it has brought with it its own tormenting gad-fly.*

---

* Ulloa's Voyage. Wood's Zoog. vol. i. p. 9.

† Buffon, vol. v. p. 100. Ulloa's Voyage, vol. ii. p. 220.

Besides the quadrupeds before enumerated, our domestic fowls have also succeeded in the West Indies and America, where they have the common fowl, the goose, the duck, the peacock, the pigeon, and the guinea-fowl. As these were often taken suddenly from the temperate to very hot regions, they were not reared at first without much difficulty; but after a few generations, they became familiarized to the climate, which, in many cases, approached much nearer than that of Europe to the temperature of their original native countries.

The fact of so many millions of wild and tame individuals of our domestic species, almost all of them the largest quadrupeds and birds, having been propagated throughout the new continent within the short period that has elapsed since the discovery of America, while no appreciable improvement can have been made in the productive powers of that vast continent, affords abundant evidence of the extraordinary changes which accompany the diffusion and progressive advancement of the human race over the globe. That it should have remained for us to witness such mighty revolutions is a proof, even if there was no other evidence, that the entrance of man into the planet is, comparatively speaking, of extremely modern date, and that the effects of his agency are only beginning to be felt.

Population which the globe is capable of supporting.—A modern writer has estimated, that there are in America upwards of four million square miles of useful soil, each capable of supporting 200 persons; and nearly six million, each mile capable of supporting 490 persons.† If this conjecture be true, it will follow, as that author observes, that if the natural resources of America were fully developed, it would afford sustenance to five times as great a number of inhabitants as the entire mass of human beings existing at present upon the globe. The new continent, he thinks, though less than half the size of the old, contains an equal quantity of useful soil, and much more than an equal amount of productive power. Be this as it may, we may safely conclude that the amount of human population now existing constitutes but a small proportion of that which the globe is capable of supporting, or which it is destined to sustain at no distant period, by the rapid progress of society, especially in America, Australia, and certain parts of the old continent.

Power of exterminating species no prerogative of man.—But if we reflect that many millions of square miles of the most fertile land, occupied originally by a boundless variety of animal and vegetable forms, have been already brought under the dominion of man, and compelled, in a great measure, to yield nourishment to him, and to a limited number of plants and animals which he has caused to increase, we must at once be convinced, that the annihilation of a multitude of species has already been effected, and will continue to go on hereafter, in certain regions, in a still more rapid ratio, as the colonies of highly civilized nations spread themselves over unoccupied lands.

---

* Travels in Iceland in 1810, p. 342.

† Maclaren, art. America, Encyc. Brit.

Yet, if we wield the sword of extermination as we advance, we have no reason to repine at the havoc committed, nor to fancy, with the Scottish poet, that "we violate the social union of nature;" or complain, with the melancholy Jacques, that we

> Are mere usurpers, tyrants, and what's worse,
> To fright the animals and to kill them up
> In their assign'd and native dwelling-place.

We have only to reflect, that in thus obtaining possession of the earth by conquest, and defending our acquisitions by force, we exercise no exclusive prerogative. Every species which has spread itself from a small point over a wide area must, in like manner, have marked its progress by the diminution or the entire extirpation of some other, and must maintain its ground by a successful struggle against the encroachments of other plants and animals. That minute parasitic plant, called "the rust" in wheat, has, like the Hessian fly, the locust, and the aphis, caused famines ere now amongst the "lords of the creation." The most insignificant and diminutive species, whether in the animal or vegetable kingdom, have each slaughtered their thousands, as they disseminated themselves over the globe, as well as the lion, when first it spread itself over the tropical regions of Africa.

Concluding remarks.—Although we have as yet considered one class only of the causes (the organic) by which species may become exterminated, yet it cannot but appear evident that the continued action of these alone, throughout myriads of future ages, must work an entire change in the state of the organic creation, not merely on the continents and islands, where the power of man is chiefly exerted, but in the great ocean, where his control is almost unknown. The mind is prepared by the contemplation of such future revolutions to look for the signs of others, of an analogous nature, in the monuments of the past. Instead of being astonished at the proofs there manifested of endless mutations in the animate world, they will appear to one who has thought profoundly on the fluctuations now in progress, to afford evidence in favour of the uniformity of the system, unless, indeed, we are precluded from speaking of *uniformity* when we characterize a principle of endless variation.

CHAPTER XLII.

EXTINCTION OF SPECIES.—INFLUENCE OF INORGANIC CAUSES.

Powers of diffusion indispensable, that each species may maintain its ground—How changes in physical geography affect the distribution of species—Rate of the change of species due to this cause cannot be uniform—Every change in the physical geography of large regions tends to the extinction of species—Effects of a general alteration of climate on the migration of species—Gradual refrigeration would cause species in the northern and southern hemispheres to become distinct—Elevation of temperature the reverse—Effects on the condition of species which must result from inorganic changes inconsistent with the theory of transmutation.

Powers of diffusion indispensable, that each species may maintain its ground.—Having shown in the last chapter, how considerably the numerical increase or the extension of the geographical range of any one species must derange the numbers and distribution of others, let us now direct our attention to the influence which the inorganic causes described in the second book are continually exerting on the habitations of species.

So great is the instability of the earth's surface, that if nature were not continually engaged in the task of sowing seeds and colonizing animals, the depopulation of a certain portion of the habitable sea and land would in a few years be considerable. Whenever a river transports sediment into a lake or sea, so as materially to diminish its depth, the aquatic animals and plants which delight in deep water are expelled: the tract, however, is not allowed to remain useless; but is soon peopled by species which require more light and heat, and thrive where the water is shallow. Every addition made to the land by the encroachment of the delta of a river banishes many subaqueous species from their native abodes; but the new-formed plain is not permitted to lie unoccupied, being instantly covered with terrestrial vegetation. The ocean devours continuous lines of sea-coasts, and precipitates forests or rich pasture land into the waves: but this space is not lost to the animate creation; for shells and sea-weeds soon adhere to the new-made cliffs, and numerous fish people the channel which the current has scooped out for itself. No sooner has a volcanic island been thrown up than some lichens begin to grow upon it, and it is sometimes clothed with verdure while smoke and ashes are still occasionally thrown from the crater. The cocoa, pandanus, and mangrove take root upon the coral reef before it has fairly risen above the waves. The burning stream of lava that descends from Etna rolls through the stately forest, and converts to ashes every tree and herb which stands in its way; but the black strip of land thus desolated is covered again in the course of time, with oaks, pines, and chestnuts, as luxuriant as those which the fiery torrent swept away.

Every flood and landslip, every wave which a hurricane or earthquake throws upon the shore, every shower of volcanic dust and ashes which buries a country far and wide to the depth of many feet, every advance of the sand-flood, every conversion of salt water into fresh, when rivers alter their main channel of discharge, every permanent variation in the rise or fall of tides in an estuary — these and countless other causes displace, in the course of a few centuries, certain plants and animals from stations which they previously occupied. If, therefore, the Author of nature had not been prodigal of those numerous contrivances, before alluded to, for spreading all classes of organic beings over the earth — if He had not ordained that the fluctuations of the animate and inanimate creation should be in perfect harmony with each other, it is evident that considerable spaces, now the most habitable on the globe, would soon be as devoid of life, as are the Alpine snows, or the dark abysses of the ocean, or the moving sands of the Sahara.

The powers, then, of migration and diffusion conferred on animals and plants are indispensable to enable them to maintain their ground, and would be necessary, even though it were never intended that a species should gradually extend its geographical range. But a facility of shifting their quarters being once given, it cannot fail to happen that the inhabitants of one province should occasionally penetrate into some other; since the strongest of those barriers which I before described as separating distinct regions are all liable to be thrown down, one after the other, during the vicissitudes of the earth's surface.

How changes in physical Geography affect the distribution of species. — The numbers and distribution of particular species are affected in two ways, by changes in the physical geography of the earth: — First, these changes promote or retard the migrations of species; secondly, they alter the physical conditions of the localities which species inhabit. If the ocean should gradually wear its way through an isthmus, like that of Suez, it would open a passage for the intermixture of the aquatic tribes of two seas previously disjoined, and would, at the same time, close a free communication which the terrestrial plants and animals of two continents had before enjoyed. These would be, perhaps, the most important consequences, in regard to the distribution of species, which would result from the breach made by the sea in such a spot; but there would be others of a distinct nature, such as the conversion of a certain tract of land, which formed the isthmus, into sea. This space, previously occupied by terrestrial plants and animals, would be immediately delivered over to the aquatic; a local revolution which might have happened in innumerable other parts of the globe, without being attended by any alteration in the blending together of species of two distinct provinces.

Rate of change of species cannot be uniform. — This observation leads me to point out one of the most interesting conclusions to which we are led by the contemplation of the vicissitudes of the inanimate world in relation to those of the animate. It is clear that, if the agency of inorganic causes be uniform, as I have supposed, they must operate very irregularly on the state of organic beings, so that the rate according to which these will change in particular regions will not be equal in equal periods of time.

I am not about to advocate the doctrine of general catastrophes recurring at certain intervals, as in the ancient Oriental cosmogonies, nor do I doubt that, if very considerable periods of equal duration could be compared one with another, the rate of change in the living, as well as in the inorganic world, might be nearly uniform; but if we regard each of the causes separately, which we know to be at present the most instrumental in remodelling the state of the surface, we shall find that we must expect each to be in action for thousands of years, without producing any extensive alterations in the habitable surface, and then to give rise, during a very brief period, to important revolutions.

Illustration derived from subsidences.—I shall illustrate this principle by a few of the most remarkable examples which present themselves. In the course of the last century, as we have seen, a considerable number of instances are recorded of the solid surface, whether covered by water or not, having been permanently sunk or upraised by subterranean movements. Most of these convulsions are only accompanied by temporary fluctuations in the state of limited districts, and a continued repetition of these events for thousands of years might not produce any decided change in the state of many of those great zoological or botanical provinces of which I have sketched the boundaries.

When, for example, large parts of the ocean and even of inland seas are a thousand fathoms or upwards in depth, it is a matter of no moment to the animate creation that vast tracts should be heaved up many fathoms at certain intervals, or should subside to the same amount. Neither can any material revolution be produced in South America either in the terrestrial or the marine plants or animals by a series of shocks on the coast of Chili, each of which, like that of Penco, in 1751, should uplift the coast about twenty-five feet. Nor if the ground sinks fifty feet at a time, as in the harbour of Port Royal, in Jamaica, in 1692, will such alterations of level work any general fluctuations in the state of organic beings inhabiting the West Indian Islands, or the Caribbean Sea.

It is only when the subterranean powers, by shifting gradually the points where their principal force is developed, happen to strike upon some particular region where a slight change of level immediately affects the distribution of land and water, or the state of the climate, or the barriers between distinct groups of species over extensive areas, that the rate of fluctuation becomes accelerated, and may, in the course of a few years or centuries, work mightier changes than had been experienced in myriads of antecedent years.

Thus for example, a repetition of subsidences causing the narrow isthmus of Panama to sink down a few hundred feet, would, in a few centuries, bring about a great revolution in the state of the animate creation in the western hemisphere. Thousands of aquatic speci would pass, for the first time, from the Caribbean Sea into the Pacif and thousands of others, before peculiar to the Pacific Ocean, woul make their way into the Caribbean Sea, the Gulf of Mexico, and th Atlantic. A considerable modification would probably be occasione by the same event in the direction or volume of the Gulf stream, an thereby the temperature of the sea and the contiguous lands migh be altered as far as the influence of that current extends. A chang of climate might thus be produced in the ocean from Florida t Spitzbergen, and in many countries of North America, Europe, an Greenland. Not merely the heat, but the quantity of rain whic falls, would be altered in certain districts, so that many species woul be excluded from tracts where they before flourished: others woul be reduced in number; and some would thrive more and multiply The seeds also and the fruits of plants would no longer be drifted in precisely the same directions, nor the eggs of aquatic animals; neither would species be any longer impeded in their migrations toward particular stations before shut out from them by their inability to cross the mighty current.

Let us take another example from a part of the globe which is at present liable to suffer by earthquakes, namely, the low sandy tract which intervenes between the Sea of Azof and the Caspian. If there should occur a sinking down to a trifling amount, and such ravines should be formed as might be produced by a few earthquakes, not more considerable than have fallen within our limited observation during the last 150 years, the waters of the Sea of Azof would pour rapidly into the Caspian, which, according to the measurements lately made by the Academy of St. Petersburg, is 84 feet below the level of the Black Sea.* The Sea of Azof would immediately borrow from the Black Sea, that sea again from the Mediterranean, and the Mediterranean from the Atlantic, so that an inexhaustible current would pour down into the low tracts of Asia bordering the Caspian, by which all the sandy salt steppes adjacent to that sea would be inundated. An area of several thousand square leagues, now below the level of the Mediterranean, would be converted from land into sea.

Illustration derived from the elevation of land.—Let us next imagine a few cases of the elevation of land of small extent at certain critical points, as, for example, in the shallowest part of the Straits of Gibraltar, where the deepest soundings from the African to the European side give only 220 fathoms. In proportion as this submarine barrier of rock was upheaved, the whole channel would be contracted in width and depth, and the volume of water which the current constantly flowing from the Atlantic pours into the Mediterranean would be lessened. But the loss of the inland sea by evaporation would remain the same; so that being no longer able to draw on the ocean for a supply sufficient to restore its equilibrium, it must sink, and leave dry a certain portion of land around its borders. The current which now flows constantly out of the Black Sea into the Mediterranean would then rush in more rapidly, and the level of the Mediterranean would be thereby prevented from falling so low; but the level of the Black Sea would, for the same reason, sink; so that when, by a continued series of elevatory movements, the Straits of Gibraltar had become completely closed up, we might expect large and level sandy steppes to surround both the Black Sea and Mediterranean, like those occurring at present on the skirts of the Caspian, and the Lake of Aral. The geographical range of hundreds of aquatic species would be thereby circumscribed, and that of hundreds of terrestrial plants and animals extended.

---

* See a note on this subject, chap. x. p. 157.

A line of submarine volcanos crossing the channel of some strait, and gradually choking it up with ashes and lava, might produce a new barrier as effectually as a series of earthquakes; especially if thermal springs, charged with carbonate of lime, silica, and other mineral ingredients, should promote the rapid multiplication of corals and shells, and cement them together with solid matter precipitated during the intervals between eruptions. Suppose in this manner a stoppage to be caused of the Bahama channel between the bank of that name and the coast of Florida. This insignificant revolution, confined to a mere spot in the bottom of the ocean, would, by diverting the main current of the Gulf stream, give rise to extensive changes in the climate and distribution of animals and plants inhabiting the northern hemisphere.

Illustration from the formation of new islands.—A repetition of elevatory movements of earthquakes might continue over an area as extensive as Europe, for thousands of ages, at the bottom of the ocean, in certain regions, and produce no visible effects; whereas, if they should operate in some shallow parts of the Pacific, amid the coral archipelagos, they would soon give birth to a new continent. Hundreds of volcanic islands may be thrown up, and become covered with vegetation, without causing more than local fluctuations in the animate world; but if a chain like the Aleutian archipelago, or the Kurile Isles, run for a distance of many hundred miles, so as to form an almost uninterrupted communication between two continents, or two distant islands, the migrations of plants, birds, insects, and even of some quadrupeds, may cause, in a short time, an extraordinary series of revolutions tending to augment the range of some animals and plants, and to limit that of others. A new archipelago might be formed in the Mediterranean, the Bay of Biscay, and a thousand other places, and might produce less important events than one rock which should rise up between Australia and Java, so placed that winds and currents might cause an interchange of the plants, insects, and birds.

From the wearing through of an isthmus.—If we turn from the igneous to the aqueous agents, we find the same tendency to an irregular rate of change, naturally connected with the strictest uniformity in the energy of those causes. When the sea, for example, gradually encroaches upon both sides of a narrow isthmus, as that o Sleswick, separating the North Sea from the Baltic, where, as befor stated, the cliffs on both the opposite coasts are wasting away*, n material alteration results for thousands of years, save only that ther is a progressive conversion of a small strip of land into water. A fe feet only, or a few yards, are annually removed; but if, at last, th partition should be broken down, and the tides of the ocean shoul enter by a direct passage into the inland sea, instead of going by circuitous route through the Cattegat, a body of salt water woul sweep up as far as the Gulfs of Bothnia and Finland, the waters o which are now brackish, or almost fresh; and this revolution woul be attended by the local annihilation of many species.

Similar consequences must have resulted on a small scale, whe the sea opened its way through the isthmus of Staveren in th thirteenth century, forming a union between an inland lake and th ocean, and opening, in the course of one century, a shallow strait, more than half as wide as the narrowest part of that which divide England from France.

Changes in physical geography which must occasion extinction o species. — It will almost seem superfluous, after I have thus traced the important modifications in the condition of living beings which flow from changes of trifling extent, to argue that entire revolutions might be brought about, if the climate and physical geography of the whole globe were greatly altered. It has been stated, that species are in general local, some being confined to extremely small spots, and depending for their existence on a combination of causes, which, if they are to be met with elsewhere, occur only in some very remote region. Hence it must happen that, when the nature of these localities is changed, the species will perish; for it will rarely happen that the cause which alters the character of the district will afford new facilities to the species to establish itself elsewhere.

African deserts. — If we attribute the origin of a great part of the desert of Africa to the gradual progress of moving sands, driven eastward by the westerly winds, we may safely infer that a variety of species must have been annihilated by this cause alone. The sand-flood has been inundating, from time immemorial, some of the rich lands on the west of the Nile; and we have only to multiply this effect a sufficient number of times in order to understand how, in the lapse of ages, a whole group of terrestrial animals and plants may become extinct.

The African desert, without including Bornou and Darfour, extends, according to the calculation of Humboldt, over 194,000 square leagues; an area nearly three times as great as that of France. In a small portion of so vast a space, we may infer from analogy that there were many peculiar species of plants and animals which must have been banished by the sand, and their habitations invaded by the camel, and by birds and insects formed for the arid sands.

---

* See above, p. 317.

There is evidently nothing in the nature of the catastrophe to favour the escape of the former inhabitants to some adjoining province; nothing to weaken, in the bordering lands, that powerful barrier against emigration—pre-occupancy. Nor, even if the exclusion of a certain group of species from a given tract were compensated by an extension of their range over a new country, would that circumstance tend to the conservation of species in general; for the extirpation would merely then be transferred to the region so invaded. If it be imagined, for example, that the aboriginal quadrupeds, birds, and other animals of Africa, emigrated in consequence of the advance of drift-sand, and colonized Arabia, the indigenous Arabian species must have given way before them, and have been reduced in number or destroyed.

Let us next suppose that, in some central and more elevated parts of the great African desert, the upheaving power of subterranean movements should be exerted throughout an immense series of ages, accompanied at certain intervals, by volcanic eruptions, such as gave rise at once, in 1755, to a mountain 1600 feet high, on the Mexican plateau. When the continued repetition of these events had caused a mountain-chain, it is obvious that a complete transformation in the state of the climate would be brought about throughout a vast area.

We may imagine the summits of the new chain to rise so high as to be covered, like Mount Atlas, for several thousand feet, with snow, during a great part of the year. The melting of these snows, during the greatest heat, would cause the rivers to swell in the season when the greatest drought now prevails; the waters, moreover, derived from this source, would always be of lower temperature than the surrounding atmosphere, and would thus contribute to cool the climate. During the numerous earthquakes and volcanic eruptions supposed to accompany the gradual formation of the chain, there would be many floods caused by the bursting of temporary lakes, and by the melting of snows by lava. These inundations might deposit alluvial matter far and wide over the original sands, as the country assumed varied shapes, and was modified again and again by the moving power from below, and the aqueous erosion of the surface above. At length the Sahara might be fertilized, irrigated by rivers and streamlets intersecting it in every direction, and covered by jungle and morasses; so that the animals and plants which now people Northern Africa would disappear, and the region would gradually become fitted for the reception of a population of species perfectly dissimilar in their forms, habits, and organization.

There are always some peculiar and characteristic features in the physical geography of each large division of the globe; and on these peculiarities the state of animal and vegetable life is dependent. If therefore, we admit incessant fluctuations in the physical geography, we must, at the same time, concede the successive extinction of terrestrial and aquatic species to be part of the economy of our

Effects of a general Alteration in Climate on the Distribution of Species.

Some of the effects which must attend every general alteration of *climate* are sufficiently peculiar to claim a separate consideration before concluding the present chapter.

I have before stated that, during seasons of extraordinary severity, many northern birds, and in some countries many quadrupeds, migrate southwards. If these cold seasons were to become frequent, in consequence of a gradual and general refrigeration of the atmosphere, such migrations would be more and more regular, until, at length, many animals, now confined to the arctic regions, would become the tenants of the temperate zone; while the inhabitants of the temperate zone would approach nearer to the equator. At the same time, many species previously established on high mountains would begin to descend, in every latitude, towards the middle regions; and those which were confined to the flanks of mountains would make their way into the plains. Analogous changes would also take place in the vegetable kingdom.

If, on the contrary, the heat of the atmosphere be on the increase, the plants and animals of low grounds would ascend to higher levels, the equatorial species would migrate into the temperate zone, and those of the temperate into the arctic circle.

But although some species might thus be preserved, every great change of climate must be fatal to many which can find no place of retreat when their original habitations become unfit for them. For if the general temperature be on the rise, then there is no cooler region whither the polar species can take refuge; if it be on the decline, then the animals and plants previously established between the tropics have no resource. Suppose the general heat of the atmosphere to increase, so that even the arctic region became too warm for the musk-ox and rein-deer, it is clear that they must perish; so if the torrid zone should lose so much of its heat by the progressive refrigeration of the earth's surface as to be an unfit habitation for apes, boas, bamboos, and palms, these tribes of animals and plants, or, at least, most of the species now belonging to them, would become extinct, for there would be no warmer latitudes for their reception.

It will follow, therefore, that as often as the climates of the globe are passing from the extreme of heat to that of cold — from the summer to the winter of the great year before alluded to * — the migratory movement will be directed constantly from the poles towards the equator; and for this reason the species inhabiting parallel latitudes, in the northern and southern hemispheres, must become widely different. For I assume, on grounds before explained, that the original stock of each species is introduced into one spot of the earth only, and, consequently, no species can be at once indig in the arctic and antarctic circles.

---

* See above, chap. vii. p. 112.

But when, on the contrary, a series of changes in the phys geography of the globe, or any other supposed cause, occasion elevation of the general temperature,—when there is a passage fr the winter to one of the vernal or summer seasons of the great cy of climate,—then the order of the migratory movement is inver The different species of animals and plants direct their course fr the equator towards the poles; and the northern and south hemispheres may become peopled to a certain limited extent identical species.

I say limited because we cannot speculate on the entire tra position of a group of animals and plants from tropical to polar la tudes, or the reverse, as a probable or even possible event. We m believe the mean annual temperature of one zone to be transfera to another, but we know that the same climate cannot be so transferr Whatever be the general temperature of the earth's surface, co parative equability of heat will characterize the tropical region while great periodical variations will belong to the temperate, a still more to the polar latitudes. These, and many other peculiariti connected with heat and light, depend on fixed astronomical caus such as the motion of the earth and its position in relation to t sun, and not on those fluctuations of its surface, which may influe the general temperature.

Among many obstacles to such extensive transference of habitatio we must not forget the immense lapse of time required, according the hypothesis before suggested, to bring about a considerable chan in climate. During a period so vast, the other causes of extirpati before enumerated, would exert so powerful an influence as to prev all, save a very few hardy species, from passing from equatorial polar regions, or from the tropics to the pole.*

But the power of accommodation to new circumstances is great certain species, and might enable many to pass from one zone another, if the mean annual heat of the atmosphere and the oc were greatly altered. To the marine tribes, especially, such passage would be possible; for they are less impeded in their mig tions by barriers of land, than are the terrestrial by the ocean. A to this, that the temperature of the ocean is much more uniform th that of the atmosphere investing the land; so that we may eas suppose that most of the testacea, fish, and other classes, might p from the equatorial into the temperate regions, if the mean temp rature of those regions were transposed, although a second expatr tion of these species of tropical origin into the arctic and antarc circles would probably be impossible.

Let us now consider more particularly the effect of vicissitudes climate in causing one species to give way before the increas numbers of some other.

---

* See above chaps. vi. vii. and viii.

When temperature forms the barrier which arrests the progress of an animal or plant in a particular direction, the individuals are fewer and less vigorous as they approach the extreme confines of the geographical range of the species. But these stragglers are ready to multiply rapidly on the slightest increase or diminution of heat that may be favourable to them, just as particular insects increase during a hot summer, and certain plants and animals gain ground after a series of congenial seasons.

In almost every district, especially if it be mountainous, there are a variety of species the limits of whose habitations are conterminous, some being unable to proceed farther without encountering too much heat, others too much cold. Individuals, which are thus on the borders of the regions proper to their respective species, are like the outposts of hostile armies, ready to profit by every slight change of circumstances in their favour, and to advance upon the ground occupied by their neighbours and opponents.

The proximity of distinct climates produced by the inequalities of the earth's surface, bring species possessing very different constitutions into such immediate contact, that their naturalizations are very speedy whenever opportunities of advancing present themselves. Many insects and plants, for example, are common to low plains within the arctic circle, and to lofty mountains in Scotland and other parts of Europe. If the climate, therefore, of the polar regions were transferred to our own latitudes, the species in question would immediately descend from these elevated stations to overrun the low grounds. Invasions of this kind, attended by the expulsion of the pre-occupants, are almost instantaneous, because the change of temperature not only places the one species in a more favourable position, but renders the others sickly and almost incapable of defence.

These changes inconsistent with the theory of transmutation.— Lamarck, when speculating on the transmutation of species, supposed every modification in organization and instinct to be brought about slowly and insensibly in an indefinite lapse of ages. But he does not appear to have sufficiently considered how much every alteration in the physical condition of the habitable surface changes the relations of a great number of co-existing species, and that some of these would be ready instantly to avail themselves of the slightest change in their favour, and to multiply to the injury of others. Even if we thought it possible that the palm or the elephant, which now flourish in equatorial regions, could ever learn to bear the variable seasons of our temperate zone, or the rigours of an arctic winter, we might with no less confidence affirm, that they must perish before they had time to become habituated to such new circumstances. That they would be displaced by other species as often as the climate varied, may be inferred from the data before explained respecting the local extermination of species produced by the multiplication of others.

Suppose the climate of the highest part of the woody zone of Etna to be transferred to the sea-shore at the base of the mountain, no botanist would anticipate that the olive, lemon-tree, and prickly pe (*Cactus Opuntia*) would be able to contend with the oak and che nut, which would begin forthwith to descend to a lower level; o that these last would be able to stand their ground against the pi which would also, in the space of a few years, begin to occupy lower position. We might form some kind of estimate of the tim which might be required for the migrations of these plants; where we have no data for concluding that any number of thousands o years would be sufficient for one step in the pretended metam- phosis of one species into another, possessing distinct attributes and qualities.

This argument is applicable not merely to *climate*, but to any othe cause of mutation. However slowly a lake may be converted into a marsh, or a marsh into a meadow, it is evident that before the lac- trine plants can acquire the power of living in marshes, or the marsh plants of living in a less humid soil, other species, already existing in the region, and fitted for these several stations, will intrude and keep possession of the ground. So, if a tract of salt water becomes fresh by passing through every intermediate degree of brackishness still the marine mollusks will never be permitted to be gradually metamorphosed into fluviatile species; because long before any such transformation can take place by slow and insensible degrees, other tribes, already formed to delight in brackish or fresh water, will avail themselves of the change in the fluid, and will, each in their turn monopolize the space.

It is idle, therefore, to dispute about the abstract possibility of th conversion of one species into another, when there are known cause so much more active in their nature, which must always interven and prevent the actual accomplishment of such conversions. A faint image of the certain doom of a species less fitted to strugg with some new condition in a region which it previously inhabite and where it has to contend with a more vigorous species, is present by the extirpation of savage tribes of men by the advancing colon of some civilized nation. In this case the contest is merely betwe two different *races* — two varieties, moreover, of a species whi exceeds all others in its aptitude to accommodate its habits to t most extraordinary variations of circumstances. Yet few futu events are more certain than the speedy extermination of the India of North America and the savages of New Holland in the course a few centuries, when these tribes will be remembered only in poet or history.

Concluding remarks. — We often hear astonishment expressed the disappearance from the earth in times comparatively modern many small as well as large animals, the remains of which have be found in a fossil state, under circumstances implying that neither a great geographical revolution, nor the exterminating influence of m has intervened to account for their extinction. But in all such ca we should inquire whether we are sufficiently acquainted with the numerous and complicated conditions on which the perpetuation of each species depends, to entitle us to wonder if it should be suddenly cut off.

Mr. Darwin, when calling attention to the fact that the horse, megatherium, megalonyx, and many contemporary Mammalia, had perished in South America after that continent had acquired its present configuration, and when, if we may judge by the Testacea, the climate very nearly resembled the present, observes, "that in the living creation one species is often extremely rare in a given region, while another of the same genus and with closely allied habits is exceedingly common. A zoologist familar with such phenomena, if asked to explain them, usually replies, that some slight difference in climate, food, or the number of its enemies, must determine the relative strength of the two species in question, although we may be unable to point out the precise manner of the action of the check. We are, therefore, driven to the conclusion, that causes generally quite inappreciable by us, determine whether a given species shall be abundant or scanty in numbers. Why, then, should we feel astonishment if the rarity is occasionally carried a step farther, — to extinction?"*

CHAPTER XLIII.

EXTINCTION AND CREATION OF SPECIES.

Theory of the successive extinction of species consistent with a limited geographical distribution — Opinions of botanists respecting the centres from which plants have been diffused — Whether there are grounds for inferring that the loss, from time to time, of certain animals and plants, is compensated by the introduction of new species? — Whether any evidence of such new creations could be expected within the historical era? — The question whether the existing species have been created in succession must be decided by geological monuments.

Successive Extinction of Species consistent with their limited Geographical Distribution.

IN the preceding chapters I have pointed out the strict dependence of each species of animal and plant on certain physical conditions in the state of the earth's surface, and on the number and attributes of other organic beings inhabiting the same region. I have also endeavoured to show that all these conditions are in a state of continual fluctuation, the igneous and aqueous agents remodelling, from time to time, the physical geography of the globe, a migrations of species causing new relations to spring up succes between different organic beings. I have deduced as a corollary, the species existing at any particular period, must, in the cour ages, become extinct one after the other. "They must die o borrow an emphatical expression from Buffon, "because Time f against them."

---

* Journ. of Nat. Hist. &c. 2d edit., 1845, p. 175.; also Lyell's 2d Visit to the United States, vol. i. p. 351.

If the views which I have taken are just, there will b difficulty in explaining why the habitations of so many sp are now restrained within exceedingly narrow limits. Every revolution, such as those contemplated in the preceding chapter, t to circumscribe the range of some species, while it enlarges th others; and if we are led to infer that new species originate in spot only, each must require time to diffuse itself over a wide It will follow, therefore, from the adoption of this hypothesis, that recent origin of some species, and the high antiquity of others equally consistent with the general fact of their limited distributi some being local, because they have not existed long enough to a of their wide dissemination; others, because circumstances in animate or inanimate world have occurred to restrict the range wh they may once have obtained. As a general rule, however, spe common to many distant provinces, or those now found to inha very distant parts of the globe, are to be regarded as the most ancie Numerically speaking, they may not perhaps be largely represent but their wide diffusion shows that they have had a long time spread themselves, and have been able to survive many importa revolutions in physical geography.

After so much evidence has been brought to light by the geolog of land and sea having changed places in various regions since existing species were in being, we can feel no surprise that zoologist and botanist have hitherto found it difficult to refer geographical distribution of species to any clear and determin principles, since they have usually speculated on the phenome upon the assumption that the physical geography of the globe undergone no material alteration since the introduction of the spe now living. So long as this assumption was made, the facts rela to the geography of plants and animals appeared capricious in extreme, and by many the subject was pronounced to be so fu mystery and anomalies, that the establishment of a satisfactory th was hopeless.*

---

* This and the preceding chapter, on the causes of extinction of species and their present geographical distribution, are reprinted almost verbatim from the original edition of the second volume of "The Principles," published in January, 1832. It was I believe the first attempt to point out how former changes in the geography and local climate of many parts of the globe must be taken account when we endeavour to exp the actual provinces of plants animals, the changes alluded to ha been proved by geological eviden be subsequent to the creation of a proportion of the species now living, these having been, according to the which I advocated, introduced in su

·es from which plants have been diffused.—Some botanists ɜd, in accordance with the hypothesis of Willdenow, that ns were the centres of creation from which the plants now ng large continents have radiated; to which De Candolle and with much reason, objected, that mountains, on the contrary, n the barriers between two provinces of distinct vegetation. ɔlogist who is acquainted with the extensive modifications he surface of the earth has undergone in very recent geo- ɜpochs, may be able, perhaps, to reconcile both these theories application to different regions.

ty range of mountains, which is so ancient as to date from a when the species of animals and plants differed from those ing, will naturally form a barrier between contiguous pro- but a chain which has been raised, in great part, within ch of existing species, and around which new lands have rom the sea within that period, will be a centre of peculiar on.

France," observes De Candolle, "the Alps and Cevennes a great number of the plants of the south from spreading ves to the northward; but it has been remarked that some have made their way through the gorges of these chains, and ıd on their northern sides, principally in those places where ; lower and more interrupted."* Now the chains here alluded probably been of considerable height ever since the era when ıting vegetation began to appear, and were it not for the ıures which divide them, they might have caused much more terminations to the extension of distinct assemblages of

of the Italian peninsula, on the other hand, have gained a ·able portion of their present height since a majority of the species now inhabiting the Mediterranean, and probably, also, e terrestrial plants of the same region were in being. Large f land have been added, both on the Adriatic and Mediterra- le, to what originally constituted a much narrower range of ıns, if not a chain of islands running nearly north and south, ·sica and Sardinia. It may therefore be presumed that the nes have been a centre whence species have diffused them- ›ver the contiguous *lower* and *newer* regions. In this and ogous situations, the doctrine of Willdenow, that species ıdiated from the mountains as from centres, may be well

---

not all at one geological epoch. ird volume, published in May, ınnounced my conviction that er part of the existing Fauna ı of Sicily were older than the ı, plains, and rivers, which the :ies of animals and plants now (Prin. of Geol. vol. iii. ch. ix.; repeated in Elements of Geol., 2d edit., vol. i. p. 297.) This line of reasoning has since been ably followed up and elucidated by Professor E. Forbes in an excellent paper (published in 1846) already alluded to. (See page 86.)

* Essai Elémentaire, &c. p. 46.

Introduction of New Species.

If the reader should infer, from the facts laid before him i preceding chapters, that the successive extinction of animal plants may be part of the constant and regular course of natu will naturally inquire whether there are any means provided f repair of these losses? Is it part of the economy of our system the habitable globe should, to a certain extent, become depop both in the ocean and on the land; or that the variety of sp should diminish until some new era arrives when a new and ext dinary effort of creative energy is to be displayed? Or is it po that new species can be called into being from time to time, and that so astonishing a phenomenon can escape the observation of ralists?

Humboldt has characterized these subjects as among the myst which natural science cannot reach; and he observes that the inve gation of the origin of beings does not belong to zoological botanical geography. To geology, however, these topics do stri appertain; and this science is chiefly interested in inquiries into state of the animate creation as it now exists, with a view of point out its relations to antecedent periods when its condition was d ferent.

Before offering any hypothesis towards the solution of so difficul problem, let us consider what kind of evidence we ought to expe in the present state of science, of the first appearance of new anima or plants, if we could imagine the successive creation of species constitute, like their gradual extinction, a regular part of the econo of nature.

In the first place, it is obviously more easy to prove that a specie once numerously represented in a given district, has ceased to b than that some other which did not pre-exist has made its appe ance—assuming always, for reasons before stated, that single stock only of each animal and plant are originally created, and th individuals of new species do not suddenly start up in many differe places at once.

So imperfect has the science of natural history remained down t our own times, that, within the memory of persons now living, th numbers of known animals and plants have been doubled, or even quadrupled, in many classes. New and often conspicuous species are annually discovered in parts of the old continent, long inhabited by the most civilized nations. Conscious, therefore, of the limited extent of our information, we always infer, when such discoveries are made, that the beings in question had previously eluded ou research; or had at least existed elsewhere, and only migrated at a recent period into the territories where we now find them. It is difficult, even in contemplation, to anticipate the time when we shal be entitled to make any other hypothesis in regard to all the marine tribes, and to by far the greater number of the terrestrial;—such as birds, which possess such unlimited powers of migration; insects which, besides the variability of each species in number, are also so capable of being diffused to vast distances; and cryptogamous plants, to which, as to many other classes, both of the animal and vegetable kingdom, similar observations are applicable.

What kind of evidence of new creations could be expected?— What kind of proofs, therefore, could we reasonably expect to find of the origin at a particular period of a new species?

Perhaps it may be said in reply that, within the last two or three centuries, some forest tree or new quadruped might have been observed to appear suddenly in those parts of England or France which had been most thoroughly investigated;—that naturalists might have been able to show that no such living being inhabited any other region of the globe, and that there was no tradition of any thing similar having before been observed in the district where it had made its appearance.

Now, although this objection may seem plausible, yet its force will be found to depend entirely on the rate of fluctuation which we suppose to prevail in the animate world, and on the proportion which such conspicuous subjects of the animal and vegetable kingdoms bear to those which are less known and escape our observation. There are perhaps more than a million species of plants and animals, exclusive of the microscopic and infusory animalcules, now inhabiting the terraqueous globe. The terrestrial plants may amount, says De Candolle, to somewhere between 110,000 and 120,000 *; but the data on which this conjecture is founded are considered by many botanists to be vague and unsatisfactory. Sprengel only enumerated, in 1827, about 31,000 known phænogamous, and 6000 cryptogamous plants; but that naturalist omitted many, perhaps 7000 phænogamous, and 1000 cryptogamous species. Mr. Lindley, in a letter to the author in 1836, expressed his opinion that it would be rash to speculate on the existence of more than 80,000 phænogamous, and 10,000 cryptogamous plants. "If we take," he says, in a letter to the author on this subject, "37,000 as the number of published phænogamous species, and then add, for the undiscovered species in Asia and New Holland 15,000, in Africa 10,000, and in America, 18,000, we have 80,000 species; and if 7000 be the number of published cryptogamous plants, and we allow 3000 for the undiscovered species (making 10,000), there would then be, on the whole, 90,000 species." But since that period one catalogue, as I learn from Dr. J. Hooker, contains a list of the names of 78,000 phænogamous plants which had been published before 1841.

It was supposed by Linnæus that there were four or five species of insects in the world for each phænogamous plant: but if we may judge from the relative proportion of the two classes in Great Britain, the number of insects must be still greater; for the total number of British insects, "according to the last census," is about 12,500 †;

---

* Géog. des Plantes. Dict. des Sci.

† See Catalogue of Brit. Insects, by John Curtis, Esq.

in the animate creation. If we divide the surface of the earth into twenty regions of equal area, one of these might comprehend a space of land and water about equal in dimensions to Europe, and might contain a twentieth part of the million of species which may be assumed to exist in the animal kingdom. In this region one species only would, according to the rate of mortality before assumed, perish in twenty years, or only five out of fifty thousand in the course of a century. But as a considerable proportion of the whole would belong to the aquatic classes, with which we have a very imperfect acquaintance, we must exclude them from our consideration; and if they constitute half of the entire number, then one species only might be lost in forty years among the terrestrial tribes. Now the Mammalia, whether terrestrial or aquatic, bear so small a proportion to other classes of animals, forming less, perhaps, than one thousandth part of the whole, that if the longevity of species in the different orders were equal, a vast period must elapse before it would come to the turn of this conspicuous class to lose one of their number. If one species only of the whole animal kingdom died out in forty years, no more than one mammifer might disappear in 40,000 years in a region of the dimensions of Europe.

It is easy, therefore, to see, that in a small portion of such an area, in countries, for example, of the size of England and France, periods of much greater duration must elapse before it would be possible to authenticate the first appearance of one of the larger plants and animals, assuming the annual birth and death of one species to be the rate of vicissitude in the animate creation throughout the world.

The observations of naturalists, upon living species may, in the course of future centuries, accumulate positive data, from which an insight into the laws which govern this part of our terrestrial system may be derived; but, in the present deficiency of historical records, we have traced up the subject to that point where geological monuments alone are capable of leading us on to discovery of ulterior truths. To these, therefore, we must appeal, carefully examining the strata of recent formation wherein the remains of *living* species, both animal and vegetable, are known to occur. We must study these strata in strict reference to their chronological order, as deduced from their superposition, and other relations. From these sources we may learn which of the species, now our contemporaries, have survived the greatest revolutions of the earth's surface; which of them have co-existed with the greatest number of animals and plants now extinct; and which have made their appearance only when the animate world had nearly attained its present condition.

From such data we may be enabled to infer, whether species have been called into existence in succession, or all at one period; whether singly, or by groups simultaneously; whether the antiquity of man be as high as that of any of the inferior beings which now share the planet with him, or whether the human species is one of the most recent of the whole.

or lignite, be thus formed in the subaqueous regions, a change in the submarine geography may be said to have resulted from the action of organic powers. So in regard to the growth of coral reefs; it is probable that a large portion of the matter of which they are composed is supplied by mineral springs, which often rise up at the bottom of the sea, and which, on land, abound throughout volcanic regions hundreds of leagues in extent. The matter thus constantly given out could not go on accumulating for ever in the waters, but would be precipitated in the abysses of the sea, even if there were no polyps and testacea; but these animals arrest and secrete the carbonate of lime on the summits of submarine mountains, and form reefs many hundred feet in thickness, and hundreds of miles in length, where, but for them, none might ever have existed.

Why the vegetable soil does not augment in thickness.—If no such voluminous masses are formed on the land, it is not from the want of solid matter in the structure of terrestrial animals and plants; but merely because, as I have so often stated, the continents are those parts of the globe where accessions of matter can scarcely ever take place—where, on the contrary, the most solid parts already formed are, each in their turn, exposed to gradual degradation. The quantity of timber and vegetable matter which grows in a tropical forest in the course of a century is enormous, and multitudes of animal skeletons are scattered there during the same period, besides innumerable land shells and other organic substances. The aggregate of these materials, therefore, might constitute a mass greater in volume than that which is produced in any coral-reef during the same lapse of years; but, although this process should continue on the land for ever, no mountains of wood or bone would be seen stretching far and wide over the country, or pushing out bold promontories into the sea. The whole solid mass is either devoured by animals, or decomposes, as does a portion of the rock and soil on which the animals and plants are supported.

The waste of the strata themselves, accompanied by the decomposition of their organic remains, and the setting free of their alkaline ingredients, is one source from whence running water and the atmosphere may derive the materials which are absorbed by the roots and leaves of plants. Another source is the passage into a gaseous form of even the hardest parts of animals and plants which die and putrefy in the air, where they are soon resolved into the elements of which they are composed: and while a portion of these constituents is volatilized, the rest is taken up by rain-water, and sinks into the earth, or flows towards the sea; so that they enter again and again into the composition of different organic beings.

The principal elements found in plants are hydrogen, carbon, and oxygen; so that water and the atmosphere contain all of them, either in their own composition or in solution.* The constant supply of these elements is maintained not only by the putrefaction of animal and vegetable substances, and the decay of rocks, but also by the copious evolution of carbonic acid and other gases from volcanos and mineral springs, and by the effects of ordinary evaporation, whereby aqueous vapours are made to rise from the ocean, and to circulate round the globe.

---

* See some good remarks on the Formation of Soils, Bakewell's Geology, chap. xviii.

It is well known that, when two gases of different specific gravity are brought into contact, even though the heavier be the lowermost, they soon become uniformly diffused by mutual absorption through the whole space which they occupy. By virtue of this law, the heavy carbonic acid finds its way upwards through the lighter air of the atmosphere, and conveys nourishment to the lichen which covers the mountain top.

If the quantity of food consumed by terrestrial animals, and the elements imbibed by the roots and leaves of plants, were derived entirely from that supply of hydrogen, carbon, oxygen, nitrogen, and other elements, given out into the atmosphere and the waters by the putrescence of organic substances, then we might imagine that the vegetable mould would, after a series of years, neither gain nor lose a single particle by the action of organic beings; and this conclusion is not far from the truth; but the operation which renovates the vegetable and animal mould is by no means so simple as that here supposed. Thousands of carcases of terrestrial animals are floated down, every century, into the sea; and, together with forests of drift-timber, are imbedded in subaqueous deposits, where their elements are imprisoned in solid strata, and may there remain locked up throughout whole geological epochs before they again become subservient to the purposes of life.

On the other hand, fresh supplies are derived by the atmosphere and by running water, as before stated, from the disintegration of rocks and their organic contents, and through the agency of mineral springs from the interior of the earth, from whence all the elements before mentioned, which enter principally into the composition of animals and vegetables, are continually evolved. Even nitrogen is found, by chemists, to be contained very generally in the waters of mineral springs.

Vegetation not an antagonist power counterbalancing the action of running water.—If we suppose that the copious supply from the nether regions, by springs and volcanic vents, of carbonic acid and other gases, together with the decomposition of rocks, may be just sufficient to counterbalance that loss of matter which, having already served for the nourishment of animals and plants, is annually carried down in organized forms, and buried in subaqueous strata, we concede the utmost that is consistent with probability. An opinion, however, has been expressed, that the processes of vegetable life, by absorbing various gases from the atmosphere, cause so large a mass of solid matter to accumulate on the surface of the land, that this mass alone may constitute a great counterpoise to all the matter transported to lower levels by the aqueous agents of decay. "Torrents and rivers," it is said—"the waves of the sea and marine currents—act upon lines only; but the power of vegetation to absorb the elastic and non-elastic fluids circulating round the earth, extends over the whole surface of the continents. By the silent but universal action of this great antagonist power, the spoliation and waste caused by running water on the land, and by the movements of the ocean, are neutralized, and even counterbalanced." *

In opposition to these views, I conceive that we shall form a juster estimate of the influence of vegetation, if we consider it as being in a slight degree conservative, and capable of retarding the waste of land, but not of acting as an antagonist power. The vegetable mould is seldom more than a few feet in thickness, and frequently does not exceed a few inches; and we by no means find that its volume is more considerable on those parts of our continents which we can prove, by geological data, to have been elevated at more ancient periods, and where, consequently, there has been the greatest time for the accumulation of vegetable matter, produced throughout successive zoological epochs. On the contrary, these higher and older regions are more frequently denuded, so as to expose the bare rock to the action of the sun and air.

We find in the torrid zone, where the growth of plants is most rank and luxurious, that accessions of matter due to their agency are by no means the most conspicuous. Indeed it is in these latitudes, where the vegetation is most active, that, for reasons to be explained in the next chapter, even those superficial peat mosses are unknown which cover a large area in some parts of our temperate zone. If the operation of animal and vegetable life could restore to the general surface of the continents a portion of the elements of those disintegrated rocks, of which such enormous masses are swept down annually into the sea, the effects would long ere this have constituted one of the most striking features in the structure and composition of our continents. All the great steppes and table-lands of the world, where the action of running water is feeble, would have become the grand repositories of organic matter, accumulated without that intermixture of earthy sediment which so generally characterizes the subaqueous strata.

I have already stated that, in the known operation of the *igneous* causes, a real antagonist power is found, which may counterbalance the levelling action of running water (p. 563.); and there seems no good reason for presuming that the upheaving and depressing force of earthquakes, together with the ejection of matter by volcanos, may not be fully adequate to restore that inequality of the surface which rivers and the waves and currents of the ocean annually tend to lessen. If a counterpoise be derived from this source, the quantity and elevation of land above the sea may for ever remain the same, in spite of the action of the aqueous causes, which, if thus counteracted, may never be able to reduce the surface of the earth more nearly to a state of equilibrium than that which it has now attained; and, on the other hand, the force of the aqueous agents themselves might thus continue for ever unimpaired.

---

* See Professor Sedgwick's Anniversary Address to the Geological Society Feb. 1831, p. 24.

Conservative influence of vegetation.—If, then, vegetation cannot act as an antagonist power amid the mighty agents of change which are always modyfying the surface of the globe, let us next inquire how far its influence is conservative,—how far it may retard the levelling effects of running water, which it cannot oppose, much less counterbalance.

It is well known that a covering of herbage and shrubs may protect a loose soil from being carried away by rain, or even by the ordinary action of a river, and may prevent hills of loose sand from being blown away by the wind; for the roots bind together the separate particles into a firm mass, and the leaves intercept the rain-water, so that it dries up gradually, instead of flowing off in a mass and with great velocity. The old Italian hydrographers make frequent mention of the increased degradation which has followed the clearing away of natural woods in several parts of Italy. A remarkable example was afforded in the Upper Val d' Arno, in Tuscany, on the removal of the woods clothing the steep declivities of the hills by which that valley is bounded. When the ancient forest laws were abolished by the Grand Duke Joseph, during the last century, a considerable tract of surface in the Cassentina (the Clausentinium of the Romans) was denuded, and immediately the quantity of sand and soil washed down into the Arno increased enormously. Frisi, alluding to such occurrences, observes, that as soon as the bushes and plants were removed, the waters flowed off more rapidly, and, in the manner of floods, swept away the vegetable soil.*

This effect of vegetation is of high interest to the geologist, when he is considering the formation of those valleys which have been principally due to the action of rivers. The spaces intervening between valleys, whether they be flat or ridgy, when covered with vegetation, may scarcely undergo the slightest waste, as the surface may be protected by the green sward of grass; and this may be renewed, in the manner before described, from elements derived from rain-water and the atmosphere. Hence, while the river is continually bearing down matter in the alluvial plain, and undermining the cliffs on each side of every valley, the height of the intervening rising grounds may remain stationary.

In this manner, a cone of loose scoriæ, sand, and ashes, such as Monte Nuovo, may, when it has once become densely clothed with herbage and shrubs, suffer scarcely any farther dilapidation; and the perfect state of the cones of hundreds of extinct volcanos in France, the Neapolitan territory, Sicily, and elsewhere, may prove nothing whatever, either as to their relative or absolute antiquity. We may be enabled to infer, from the integrity of such conical hills of incoherent materials, that no flood can have passed over the countries where they are situated, since their formation; but the atmospheric action alone, in spots where there happen to be no torrents, and where the surface was clothed with vegetation, could scarcely in any lapse of ages have destroyed them.

---

* Treatise on Rivers and Torrents, p. 5. Garston's translation.

During a tour in Spain, in 1830, I was surprised to see a district of gently undulating ground in Catalonia, consisting of red and grey sandstone, and in some parts of red marl, almost entirely denuded of herbage; while the roots of the pines, holm oaks, and some other trees, were half exposed, as if the soil had been washed away by a flood. Such is the state of the forests, for example, between Oristo and Vich, and near San Lorenzo. But, being overtaken by a violent thunder-storm, in the month of August, I saw the whole surface, even the highest levels of some flat-topped hills, streaming with mud, while on every declivity the devastation of torrents was terrific. The peculiarities in the physiognomy of the district were at once explained; and I was taught that, in speculating on the greater effects which the direct action of rain may once have produced on the surface of certain parts of England, we need not revert to periods when the heat of the climate was *tropical*.

In the torrid zone the degradation of land is generally more rapid; but the waste is by no means proportioned to the superior quantity of rain or the suddenness of its fall, the transporting power of water being counteracted by a greater luxuriance of vegetation. A geologist who is no stranger to tropical countries observes, that the softer rocks would speedily be washed away in such regions, if the numerous roots of plants were not matted together in such a manner as to produce considerable resistance to the destructive power of the rains. The parasitical and creeping plants also entwine in every possible direction, so as to render the forests nearly impervious, and the trees possess forms and leaves best calculated to shoot off the heavy rains; which, when they have thus been broken in their fall, are quickly absorbed by the ground beneath, or, when thrown into the drainage depressions, give rise to furious torrents.*

Influence of Man in modifying the Physical Geography of the Globe.

Before concluding this chapter, I shall offer a few observations on the influence of man in modifying the physical geography of the globe; for we must class his agency among the powers of organic nature.

Felling of forests.—The felling of forests has been attended, in many countries, by a diminution of rain, as in Barbadoes and Jamaica.† For in tropical countries, where the quantity of aqueous on their summits. The aërial current, now deprived of all the humidity with which it can part, arrives in a state of complete exsiccation at Peru, where consequently no rain falls. But in the region of America, beyond the thirtieth parallel, the Andes serve as a screen to intercept the moisture brought by the prevailing winds from the Pacific Ocean: rains are copious on their summits, and in Chili on their *western* declivities; but none falls on the plains to the *eastward*, except occasionally when the wind blows from the Atlantic."*

---

* De la Beche, Geol. Man., p. 184., 1st ed.

† Phil. Trans. vol. ii. p. 294.

I have been more particular in explaining these views, because they appear to place in a true light the dependence of vegetation on climate, the humidity being increased, and more uniformly diffused throughout the year, by the gradual spreading of wood.

It has been affirmed, that formerly, when France and England were covered with wood, Europe was much colder than at present; that the winters in Italy were longer, and that the Seine, and many other rivers, froze more regularly every winter than now. M. Arago, in an essay on this subject, has endeavoured to show, by tables of observations on the congelation of the Rhine, Danube, Rhone, Po, Seine, and other rivers, at different periods, that there is no reason to believe the cold to have been in general more intense in ancient times.† He admits, however, that the climate of Tuscany has been so far modified, by the removal of wood, as that the winters are less cold; but the summers also, he contends, are less hot than of old; and the summers, according to him, were formerly hotter in France than in our own times. His evidence is derived chiefly from documents showing that wine was made three centuries ago in the Vivarais and several other provinces, at an earlier season, at greater elevations, and in higher latitudes, than are now found suitable to the vine.

There seems little doubt that in the United States of North America the rapid *clearing* of the country has rendered the winters less severe and the summers less hot; in other words, the extreme temperatures of January and July have been observed from year to year to approach somewhat nearer to each other. Whether in this case, or in France, the *mean* temperature has been raised, seems by no means as yet decided; but there is no doubt that the climate has become, as Buffon would have said, "less excessive."

I have before shown, when treating of the excavation of new estuaries in Holland by inroads of the ocean, as also of the changes on our own coasts, that although the conversion of sea into land by artificial labours may be great, yet it must always be in subordination to the power of the tides and currents, or to the great movements which alter the relative level of the land and sea (Chap. XX.). If, in addition to the assistance obtained by parliamentary grants for defending

---

* Maclaren, art. America, Encyc. Britannica, where the position of the American forests, in accordance with this theory, is laid down in a map.

† Annuaire du Bureau des Long. 1834.

Dunwich from the waves, all the resources of Europe h
directed to the same end, the existence of that port might
have been prolonged for several centuries (p. 310.). But in t
time, the current would have continued to sweep away portio
the adjoining cliffs on each side, giving to the whole line of
present form, until at length the town, projecting as a narr
montory, must have become exposed to the irresistible fur
waves.

It is scarcely necessary to observe, that the control which
obtain over the igneous agents is less even than that which
exert over the aqueous. He cannot modify the upheaving
pressing force of earthquakes, or the periods or degree of vi
volcanic eruptions; and on these causes the inequalities of th
surface, and, consequently, the shape of the sea and land
mainly to depend. The utmost that man can hope to effe
respect is occasionally to divert the course of a lava-stream
prevent the burning matter, for a season, from overwhelmin
or some other of the proudest works of human industry.

If all the nations of the earth should attempt to quarry
lava which flowed during one eruption from the Icelandic
in 1783, and the two following years, and should attempt t
it to the deepest abysses of the ocean, they might toil for t
of years and not accomplish their task. Yet the matter bo
to the sea by two great rivers, the Ganges and Burrampooter
quarter of a century, probably equals in weight and volume
of Icelandic lava produced by that great eruption (p. 2
significant is the aggregate force exerted by man, when
with the ordinary operations of aqueous or igneous agen
natural world.

No application, perhaps, of human skill and labour tends
to vary the state of the habitable surface, as that employe
drainage of lakes and marshes, since not only the station
animals and plants, but the general climate of a district, ma
modified. It is also a kind of alteration to which it is diffi
anything analogous in the agency of inferior beings; for
always, before we decide that any part of the influence
novel and anomalous, carefully to consider the powers o
animated agents which may be limited or superseded by him
who have reasoned on these subjects seem to have forgotte
human race often succeeds to the discharge of functions
fulfilled by other species. Suppose the growth of some of
terrestrial plants, or, in other words, the extent of fore
diminished by man, and the climate to be thereby modifie

---

* Since this was written I have seen
in New Brunswick (1852) a lake formed
by beavers who had thrown a dam,
consisting of sticks, stones, and mud,
across the course of a small streamlet,
between Fredericton and the Portage
south of the Peninsula
beavers have since been
man, but the lake remains,
rats have taken possession
parts of the lake to build
in them.

not follow that this kind of innovation is unprecedented. It is a change in the state of vegetation, and such may often have been the result of the appearance of new species upon the earth. The multiplication, for example, of certain insects in parts of Germany, during the last century, destroyed more trees than man, perhaps, could have felled during an equal period.

It would be rash, however, to affirm that the power of man to modify the surface may not differ in kind or degree from that of other living beings; although the problem is certainly more complex than many who have speculated on such topics have imagined. If land be raised from the sea, the greatest alteration in its physical condition, which could ever arise from the influence of organic beings, would probably be produced by the first immigration of terrestrial plants, whereby the new tract would become covered with vegetation. The change next in importance would seem to be when animals first enter, and modify the proportionate numbers of certain species of plants. If there be any anomaly in the intervention of man, in farther varying the relative numbers in the vegetable kingdom, it may not so much consist in the kind or absolute quantity of alteration, as in the circumstance that a *single species*, in this case, would exert, by its superior power and universal distribution, an influence equal to that of hundreds of other terrestrial animals.

If we inquire whether man, by his direct power, or by the changes which he may give rise to indirectly, tends, upon the whole, to lessen or increase the inequalities of the earth's surface, we shall incline, perhaps, to the opinion that he is a levelling agent. In mining operations he conveys upwards a certain quantity of materials from the bowels of the earth; but, on the other hand, much rock is taken annually from the land, in the shape of ballast, and afterwards thrown into the sea, and by this means, in spite of prohibitory laws, many harbours, in various parts of the world, have been blocked up. We rarely transport heavy materials to higher levels, and our pyramids and cities are chiefly constructed of stone brought down from more elevated situations. By ploughing up thousands of square miles, and exposing a surface for part of the year to the action of the elements, we assist the abrading force of rain, and diminish the conservative effects of vegetation.

CHAPTER XLV.

INCLOSING OF FOSSILS IN PEAT, BLOWN SAND, AND VOLCANIC EJECTIONS.

Division of the subject—Imbedding of organic remains in deposits on emerged land—Growth of peat—Site of ancient forests in Europe now occupied by peat—Bog iron-ore—Preservation of animal substances in peat—Miring of quadrupeds—Bursting of the Solway moss—Great Dismal Swamp—Imbedding of organic bodies and human remains in blown sand—Moving sands of African deserts—De Luc on their recent origin—Buried temple of Ipsambul—Dried carcasses in the sands—Towns overwhelmed by sand-floods—Imbedding of organic and other remains in volcanic formations on the land.

Division of the subject.—The next subject of inquiry is the mode in which the remains of animals and plants become fossil, or are buried in the earth by natural causes. M. Constant Prevost has observed, that the effects of geological causes are divisible into two great classes; those produced during the submersion of land beneath the waters, and those which take place after its emersion. Agreeably to this classification, I shall consider, first, in what manner animal and vegetable remains become included and preserved in deposits on emerged land, or that part of the surface which is not *permanently* covered by water, whether of seas or lakes; secondly, the manner in which organic remains become imbedded in subaqueous deposits.

Under the first division, I shall treat of the following topics:—1st, the growth of peat, and the preservation of vegetable and animal remains therein;—2dly, the burying of organic remains in blown sand;—3dly, of the same in the ejections and alluviums of volcanos;—4thly, in alluviums generally, and in the ruins of landslips;—5thly, in the mud and stalagmite of caves and fissures.

Growth of Peat, and Preservation of Vegetable and Animal Remains therein.

The generation of peat, when not completely under water, is confined to moist situations, where the temperature is low, and where vegetables may decompose without putrefying. It may consist of any of the numerous plants which are capable of growing in such *stations;* but a species of moss (*Sphagnum*) constitutes a considerable part of the peat found in marshes of the north of Europe; this plant having the property of throwing up new shoots in its upper part, while its lower extremities are decaying.* Reeds, rushes, and other aquatic plants may usually be traced in peat; and their organization is often so entire that there is no difficulty in discriminating the distinct species.

Analysis of peat.—In general, says Sir H. Davy, one hundred parts of dry peat contain from sixty to ninety-nine parts of matter destructible by fire; and the residuum consists of earths usually of the same kind as the substratum of clay, marl, gravel, or rock, on which they are found, together with oxide of iron. "The peat of the chalk counties of England," observes the same writer, "contains much gypsum: but I have found very little in any specimens from Ireland or Scotland, and in general these peats contain very little saline matter."* From the researches of Dr. MacCulloch, it appears that peat is intermediate between simple vegetable matter and lignite, the conversion of peat to lignite being gradual, and being brought about by a prolonged action of water.†

---

* For a catalogue of plants which form peat, see Rev. Dr. Rennie's Essays on Peat, p. 171.; and Dr. MacCulloch's Western Isles, vol. i. p. 129.

Peat abundant in cold and humid climates.—Peat is sometimes formed on a declivity in mountainous regions, where there is much moisture; but in such situations it rarely, if ever, exceeds four feet in thickness. In bogs, and in low grounds into which alluvial peat is drifted, it is found forty feet thick, and upwards; but in such cases it generally owes one half of its volume to the water which it contains. It has seldom, if ever, been discovered within the tropics; and it rarely occurs in the valleys, even in the south of France and Spain. It abounds more and more, in proportion as we advance farther from the equator, and becomes not only more frequent but more inflammable in northern latitudes.‡

The same phenomenon is repeated in the southern hemisphere. No peat is found in Brazil, nor even in the swampy parts of the country drained by the La Plata on the east side of South America, or in the island of Chiloe on the west; yet when we reach the 45th degree of latitude and examine the Chonos Archipelago or the Falkland Islands, and Tierra del Fuego, we meet with an abundant growth of this substance. Almost all plants contribute here by their decay to the production of peat, even the grasses; but it is a singular fact, says Mr. Darwin, as contrasted with what occurs in Europe, that no kind of moss enters into the composition of the South American peat, which is formed by many plants, but chiefly by that called by Brown *Astelia pumila.*§

I learn from Dr. Forchhammer (1849) that water charged with vegetable matter in solution does not throw down a deposit of peat in countries where the mean temperature of the year is above 43° or 44° Fahrenheit. Frost causes the precipitation of such peaty matter, but in warm climates the attraction of the carbon for the oxygen of the air mechanically mixed with the water increases with the increasing temperature, and the dissolved vegetable matter or humic acid (which is organic matter in a progressive state of decomposition) being converted into carbonic acid, rises and is absorbed into the atmosphere, and thus disappears.

Extent of surface covered by peat.—There is a vast extent of surface in Europe covered with peat, which, in Ireland, is said to extend over a tenth of the whole island. One of the mosses on the Shannon

---

* Irish Bog Reports, p. 209.

† System of Geology, vol. ii p. 353.

‡ Rev. Dr. Rennie on Peat, p. 260.

§ Darwin's Journal, p. 349.; 2d ed. p. 287.

is described as being fifty miles long, by two or three broad;
the great marsh of Montoire, near the mouth of the Loire, is m
tioned, by Blavier, as being more than fifty leagues in circumferen
It is a curious and well ascertained fact, that many of these mos
of the north of Europe occupy the place of forests of pine and o
which have, many of them, disappeared within the historical e
Such changes are brought about by the fall of trees and the stag
tion of water, caused by their trunks and branches obstructing t
free drainage of the atmospheric waters, and giving rise to a mar
In a warm climate, such decayed timber would immediately be
moved by insects, or by putrefaction; but, in the cold temperat
now prevailing in our latitudes, many examples are recorded
marshes originating in this source. Thus, in Mar forest, in Ab
deenshire, large trunks of Scotch fir, which had fallen from age a
decay, were soon immured in peat, formed partly out of their peri
ing leaves and branches, and in part from the growth of other plan
We also learn, that the overthrow of a forest by a storm, about t
middle of the seventeenth century, gave rise to a peat-moss n
Lochbroom, in Ross-shire, where, in less than half a century aft
the fall of the trees, the inhabitants dug peat.[*] Dr. Walker mentio
a similar change, when, in the year 1756, the whole wood of Drum
lanrig in Dumfries-shire was overset by the wind. Such even
explain the occurrence, both in Britain and on the Continent,
mosses where the trees are all broken within two or three feet
the original surface, and where their trunks all lie in the sam
direction.[†]

It may however be suggested in these cases, that the soil h
become exhausted for trees, and that, on the principle of that natur
rotation which prevails in the vegetable world, one set of plants di
out and another succeeded. It is certainly a remarkable fact that
the Danish islands, and in Jutland and Holstein, fir wood of vario
species, especially Scotch fir, is found at the bottom of the pea
mosses, although it is well ascertained that for the last five centuri
no Coniferæ have grown wild in these countries; the coniferous tre
which now flourish there having been all planted towards the close
the last century.

Nothing is more common than the occurrence of buried trees
the bottom of the Irish peat-mosses, as also in most of those
England, France, and Holland; and they have been so often observ
with parts of their trunks standing erect, and with their roots fix
to the subsoil, that no doubt can be entertained of their havin
generally grown on the spot. They consist, for the most part, of th
fir, the oak, and the birch: where the subsoil is clay, the remains
oak are the most abundant; where sand is the substratum, fir pr
vails. In the marsh of Curragh, in the Isle of Man, vast trees a
discovered standing firm on their roots, though at the depth of eig
teen or twenty feet below the surface. Some naturalists have desir
to refer the imbedding of timber in peat-mosses to aqueous transpo

---

[*] Rennie's Essays on Peat, p. 65.

[†] Ibid p. 30.

ation, since rivers are well known to float wood into lakes; but the facts above mentioned show that, in numerous instances, such an hypothesis is inadmissible. It has, moreover, been observed, that in Scotland, as also in many parts of the Continent, the largest trees are found in those peat-mosses which lie in the least elevated regions, and that the trees are proportionally smaller in those which lie at higher levels; from which fact De Luc and Walker have both inferred that the trees grew on the spot, for they would naturally attain a greater size in lower and warmer levels. The leaves, also, and fruits of each species, are continually found immersed in the moss along with the parent trees; as, for example, the leaves and acorns of the oak, the cones and leaves of the fir, and the nuts of the hazel.

Recent origin of some peat-mosses. — In Hatfield moss, in Yorkshire, which appears clearly to have been a forest eighteen hundred years ago, fir-trees have been found ninety feet long, and sold for masts and keels of ships; oaks have also been discovered there above one hundred feet long. The dimensions of an oak from this moss are given in the Philosophical Transactions, No. 275., which must have been larger than any tree now existing in the British dominions.

In the same moss of Hatfield, as well as in that of Kincardine, in Scotland, and several others, Roman roads have been found covered to the depth of eight feet by peat. All the coins, axes, arms, and other utensils found in British and French mosses, are also Roman; so that a considerable portion of the peat in European peat-bogs is evidently not more ancient than the age of Julius Cæsar. Nor can any vestiges of the ancient forests described by that general, along the line of the great Roman way in Britain, be discovered, except in the ruined trunks of trees in peat.

De Luc ascertained that the very site of the aboriginal forests of Hercinia, Semana, Ardennes, and several others, are now occupied by mosses and fens; and a great part of these changes have with much probability, been attributed to the strict orders given by Severus, and other emperors, to destroy all the wood in the conquered provinces. Several of the British forests, however, which are now mosses, were cut at different periods, by order of the English parliament, because they harboured wolves or outlaws. Thus the Welsh woods were cut and burnt, in the reign of Edward I.; as were many of those in Ireland, by Henry II., to prevent the natives from harbouring in them, and harassing his troops.

It is curious to reflect that considerable tracts have, by these accidents, been permanently sterilized, and that, during a period when civilization has been making great progress, large areas in Europe have, by human agency, been rendered less capable of administering to the wants of man. Rennie observes*, with truth, that in those regions alone which the Roman eagle never reached — in the remote circles of the German empire, in Poland and Prussia, and still more in Norway, Sweden, and the vast empire of Russia — can we see what Europe was before it yielded to the power of Rome. Desolation now reigns where stately forests of pine and oak once flo such as might now have supplied all the navies of Europe with

---

* Essays on Peat, &c., p. 74.

Sources of bog iron-ore.—At the bottom of peat-mosses sometimes found a cake, or "pan," as it is termed, of oxide and the frequency of bog iron-ore is familiar to the mine The oak, which is so often dyed black in peat, owes its colou same metal. From what source the iron is derived has often subject of discussion, until the discoveries of Ehrenberg length to have removed the difficulty. He had observe marshes about Berlin, a substance of a deep ochre yellow into red, which covered the bottom of the ditches, and which it had become dry after the evaporation of the water, a exactly like oxide of iron. But under croscope it was found to consist of articulated threads or plates, partly silice partly ferruginous, of what he consid animalcule, *Gaillonella ferruginea*, but most naturalists now regard as a plant.* can be little doubt, therefore, that bog i consists of an aggregate of millions of these organic bodies invi the naked eye.†

Fig. 101.



Gaillonella ferruginea.
a. 2000 times magnified.

Preservation of animal substances in peat.—One inte circumstance attending the history of peat-mosses is the hig of preservation of animal substances buried in them for per many years. In June, 1747, the body of a woman was fou feet deep, in a peat-moor in the Isle of Axholm, in Lincol The antique sandals on her feet afforded evidence of her havin buried there for many ages: yet her nails, hair, and ski described as having shown hardly any marks of decay. C estate of the Earl of Moira, in Ireland, a human body was d a foot deep in gravel, covered with eleven feet of moss; the bod completely clothed and the garments seemed all to be made of Before the use of wool was known in that country the clothing inhabitants was made of hair, so that it would appear that this had been buried at that early period; yet it was fresh and unimpa In the Philosophical Transactions we find an example recorded bodies of two persons having been buried in moist peat, in Derby in 1674, about a yard deep, which were examined twenty-eight and nine months afterwards; "the colour of their skin was fa natural, their flesh soft as that of persons newly dead."§

Among other analogous facts we may mention, that in digg pit for a well near Dulverton, in Somersetshire, many pigs found in various postures, still entire. Their shape was well served, the skin, which retained the hair, having assumed a dry, branous appearance. Their whole substance was converted i white, friable, laminated, inodorous, and tasteless substance

---

[*] See above, p. 388. note.

[†] Ehrenberg, Taylor's Scientific Mem. vol. i. part iii. p. 402.

[‡] Dr. Rennie, on Peat, p. 521. several other instances are referre

[§] Phil. Trans., vol. xxxviii. 17

which, when exposed to heat, emitted an odour precisely similar to broiled bacon.*

Cause of the antiseptic property of peat.—We naturally ask whence peat derives this antiseptic property? It has been attributed by some to the carbonic and gallic acids which issue from decayed wood, as also to the presence of charred wood in the lowest strata of many peat-mosses, for charcoal is a powerful antiseptic, and capable of purifying water already putrid. Vegetable gums and resins also may operate in the same way.†

The tannin occasionally present in peat is the produce, says Dr. MacCulloch, of tormentilla, and some other plants; but the quantity he thinks too small, and its occurrence too casual, to give rise to effects of any importance. He hints that the soft parts of animal bodies, preserved in peat-bogs, may have been converted into adipocire by the action of water merely; an explanation which appears clearly applicable to some of the cases above enumerated.‡

Miring of quadrupeds.—The manner, however, in which peat contributes to preserve, for indefinite periods, the harder parts of terrestrial animals, is a subject of more immediate interest to the geologist. There are two ways in which animals become occasionally buried in the peat of marshy grounds; they either sink down into the semifluid mud, underlying a turfy surface upon which they have rashly ventured, or, at other times, as we shall see in the sequel, a bog "bursts," and animals may be involved in the peaty alluvium.

In the extensive bogs of Newfoundland, cattle are sometimes found buried with only their heads and necks above ground; and after having remained for days in this situation, they have been drawn out by ropes and saved. In Scotland, also, cattle venturing on the "quaking moss" are often mired, or "laired," as it is termed; and in Ireland, Mr. King asserts that the number of cattle which are lost in sloughs is quite incredible.§

Solway moss.—The description given of the Solway moss will serve to illustrate the general character of these boggy grounds. That moss, observes Gilpin, is a flat area, about seven miles in circumference, situated on the western confines of England and Scotland. Its surface is covered with grass and rushes, presenting a dry crust and a fair appearance; but it shakes under the least pressure, the bottom being unsound and semifluid. The adventurous passenger, therefore, who sometimes in dry seasons traverses this perilous waste, to save a few miles, picks his cautious way over the rushy tussocks as they appear before him, for here the soil is firmest. If his foot slip, or if he venture to desert this mark of security, it is possible he may never more be heard of.

"At the battle of Solway, in the time of Henry VIII. (1542), when the Scotch army, commanded by Oliver Sinclair, was routed, an unfortunate troop of horse, driven by their fears, plunged into this morass, which instantly closed upon them. The tale was tradi-

---

* Dr. Rennie, on Peat, &c., p. 521.

† Ibid. p. 531.

‡ Syst. of Geol. vol. ii. pp. 340—346.

§ Phil. Trans. vol. xv. p. 949.

tional, but it is now authenticated; a ma
armour, having been found by peat-digger
always supposed the affair had happened.
well preserved, and the different parts of
guished."[*]

The same moss, on the 16th of Dec
filled like a great sponge with water durin
an unusual height above the surrounding
The turfy covering seemed for a time t
bladder retaining the fluid within, till it
when a stream of black half-consolidate
creep over the plain, resembling in th
ordinary lava-current. No lives were lo
overwhelmed some cottages, and covered
parts of the original moss subsided to the
feet; and the height of the moss, on the l
which it invaded, was at least fifteen feet.

Bursting of a peat-moss in Ireland.—
Sligo (January, 1831), affords another exa
After a sudden thaw of snow, the bog betw
gave way; and a black deluge, carrying
hundred acres of bog, took the directio
rolled on with the violence of a torren
timber, mud, and stones, and overwheln
arable land. On passing through some b
out a wide and deep ravine, and part
Bloomfield to St. James's Well was comp
below the foundation for the breadth of 20

Great Dismal Swamp.—I have describ
America[†], an extensive swamp or mora
north to south, and twenty-five wide, betw
in Virginia, and Weldon in North Carolin
Dismal," and has somewhat the appearance
covered with aquatic trees and shrubs, the
of a peat bog. It is higher on all sides exc
ing country, towards which it sends fort
north, east, and south, receiving a suppl
its centre it rises 12 feet above the flat reg
soil, to the depth of 15 feet, is formed of ve
admixture of earthy particles, and offers
rule before alluded to, namely, that such p
ever occur so far south as lat. 36°, or in an
heat is so great as in Virginia. In di
morass for the purpose of obtaining timb
has been thrown out from time to time, a
air, in which case it soon rots away so th

---

[*] Gilpin, Observ. on Picturesque Beauty, &c., 1772.

[†] Tr
p. 143.

showing clearly that it owes its preservation to the shade afforded by a luxuriant vegetation and to the constant evaporation of the spongy soil by which the air is cooled during the hot months. The surface of the bog is carpeted with mosses, and densely covered with ferns and reeds, above which many evergreen shrubs and trees flourish, especially the White Cedar (*Cupressus thyoides*), which stands firmly supported by its long tap roots in the softest parts of the quagmire. Over the whole the deciduous Cypress (*Taxodium distichum*) is seen to tower with its spreading top, in full leaf in the season when the sun's rays are hottest, and when, if not intercepted by a skreen of foliage, they might soon cause the fallen leaves and dead plants of the preceding autumn to decompose, instead of adding their contributions to the peaty mass. On the surface of the wide morass lie innumerable trunks of large and tall trees, while thousands of others, blown down by the winds, are buried at various depths in the black mire below. They remind the geologist of the prostrate position of large stems of Sigillaria and Lepidodendron, converted into coal in ancient carboniferous rocks.

Bones of herbivorous quadrupeds in peat. — The antlers of large and full-grown stags are amongst the most common and conspicuous remains of animals in peat. They are not horns which have been shed; for portions of the skull are found attached, proving that the whole animal perished. Bones of the ox, hog, horse, sheep, and other herbivorous animals, also occur. M. Morren has discovered in the peat of Flanders the bones of otters and beavers *; but no remains have been met with belonging to those extinct quadrupeds, of which the living congeners inhabit warmer latitudes, such as the elephant, rhinoceros, hippopotamus, hyæna, and tiger, though these are so common in superficial deposits of silt, mud, sand, or stalactite, in various districts throughout Great Britain. Their absence seems to imply that they had ceased to live before the atmosphere of this part of the world acquired that cold and humid character which favours the growth of peat.

Remains of ships, &c. in peat mosses. — From the facts before mentioned, that mosses occasionally burst, and descend in a fluid state to lower levels, it will readily be seen that lakes and arms of the sea may occasionally become the receptacles of drift peat. Of this, accordingly, there are numerous examples; and hence the alternations of clay and sand with different deposits of peat so frequent on some coasts, as on those of the Baltic and German Ocean. We are informed by Deguer, that remains of ships, nautical instruments, and oars, have been found in many of the Dutch mosses; and Gerard, in his History of the Valley of the Somme, mentions that in the lowest tier of that moss was found a boat loaded with bricks, proving that these mosses were at one period navigable lakes and arms of the sea, as were also many mosses on the coast of Picardy, Zealand, and Friesland, from which soda and

---

* Bulletin de la Soc. Géol. de France, tom. ii. p. 26.

and Beechey, was so fine as to resemble a fluid when put in motion. Neither the features of the colossal figures, nor the colour of the stucco with which some were covered, nor the paintings on the walls, had received any injury from being enveloped for ages in this dry impalpable dust.*

At some future period, perhaps when the pyramids shall have perished, the action of the sea, or an earthquake, may lay open to the day some of these buried temples. Or we may suppose the desert to remain undisturbed, and changes in the surrounding sea and land to modify the climate and the direction of the prevailing winds, so that these may then waft away the Libyan sands as gradually as they once brought them to those regions. Thus, many a town and temple of higher antiquity than Thebes or Memphis may reappear in their original antiquity, and a part of the gloom which overhangs the history of the earlier nations be dispelled.

Whole caravans are said to have been overwhelmed by the Libyan sands; and Burckhardt informs us that "after passing the Akaba near the head of the Red Sea, the bones of dead camels are the only guides of the pilgrim through the wastes of sand."—"We did not see," says Captain Lyon, speaking of a plain near the Soudah mountains, in Northern Africa, "the least appearance of vegetation; but observed many skeletons of animals, which had died of fatigue on the desert, and occasionally the grave of some human being. All these bodies were so dried by the heat of the sun, that putrefaction appears not to have taken place after death. In recently expired animals I could not perceive the slightest offensive smell; and in those long dead, the skin with the hair on it remained unbroken and perfect, although so brittle as to break with a slight blow. The sand-winds never cause these carcasses to change their places; for, in a short time, a slight mound is formed round them, and they become stationary."†

Towns overwhelmed by sand floods.—The burying of several towns and villages in England, France, and Jutland, by blown sand is on record; thus, for example, near St. Pol de Leon, in Brittany, a whole village was completely buried beneath drift sand, so that nothing was seen but the spire of the church.‡ In Jutland marine shells adhering to sea-weed are sometimes blown by the violence of the wind to the height of 100 feet and buried in similar hills of sand.

In Suffolk, in the year 1688, part of Downham was overwhelmed by sands which had broken loose about 100 years before, from a warren five miles to the south-west. This sand had, in the course of a century, travelled five miles, and covered more than 1000 acres of land.§ A considerable tract of cultivated land on the north coast of Cornwall has been inundated by drift sand, forming hills several

---

* Stratton, Ed. Phil. Journ., No. v. p. 62.

† Travels in North Africa in the Years 1818, 1819, and 1820, p. 83.

‡ Mém. de l'Acad. des Sci. de Paris, 1772. See also the case of the buried church of Eccles, above, p. 306.

§ Phil. Trans., vol. ii. p. 722.

We read of several buried cities in Central India, and among others of Oujein (or Oojain) which about fifty years before the Christian era was the seat of empire, of art, and of learning; but which in the time of the Rajah Vicramaditya, was overwhelmed, according to tradition, together with more than eighty other large towns in the provinces of Malwa and Bagur, "by a shower of earth." The city which now bears the name is situated a mile to the southward of the ancient town. On digging on the spot where the latter is supposed to have stood, to the depth of fifteen or eighteen feet, there are frequently discovered, says Mr. Hunter, entire brick walls, pillars of stone, and pieces of wood of an extraordinary hardness, besides utensils of various kinds, ancient coins, and occasionally buried wheat in a state resembling charcoal.*

The soil which covers Oujein is described as "being of an ash-grey colour, with minute specks of black sand."† And the "shower of earth," said to have "fallen from heaven," has been attributed by some travellers to volcanic agency. There are however no active volcanos in central India, the nearest to Oujein being Denodur hill near Bhooj, the capital of Cutch, 300 geographical miles distant, if indeed that hill has ever poured out lava in historical times, which is doubted by many.‡ The latest writers on Oujein avow their suspicion that the supposed "catastrophe" was nothing more than the political decline and final abandonment of a great city which, like Nineveh or Babylon, and many an ancient seat of empire in the East, after losing its importance as a metropolis became a heap of ruins. The rapidity with which the sun-dried bricks, of which even the most splendid oriental palaces are often constructed, crumble down when exposed to rain and sun, and are converted into mounds of ordinary earth and clay, is well known. According to Captain Dangerfield, trap tuff and columnar basalt constitute the rocks in the environs of Oujein§, and the volcanic nature of these formations, from which the materials of the bricks were originally derived, may have led to the idea of the city having been overwhelmed by a volcanic eruption.

---

* Narrative of Journey from Agra to Oujein, Asiatic Researches, vol. vi. p. 36.

† Asiatic Journal, vol. ix. p. 35.

‡ See above, p. 460.

§ Sir J. Malcolm's Central India. Appendix, No. 2. p. 324.

CHAPTER XI

BURYING OF FOSSILS IN ALLUVIAL D

Fossils in alluvium — Effects of sudden inund
abundantly preserved in alluvium where earth
— Buried town — Effects of landslips — Orga
— Form and dimensions of caverns — their pr
subterranean rivers of the Morea — Katavothra
cement — Human remains imbedded in Morea
of France and elsewhere, of human remains an
proof of former co-existence of man with those

Fossils in alluvium. — THE next sub
according to the division before proposed
bodies in alluvium.

The gravel, sand, and mud in the be
contain any animal or vegetable remain
continually shifting its place, and the att
so great, that even the hardest rocks c
ground down to powder. But when san
swept by a flood, and then let fall upon
may envelop trees or the remains of anin
are often permanently preserved. In t
by the floods in Scotland, in 1829, the d
hares, rabbits, moles, mice, partridges, a
were found partially buried.* But in
flood usually effaces the memorials left b
a sufficient depth of undisturbed transpo
to preserve the organic remains for ages

Where earthquakes prevail, and the lev
from time to time, the remains of anin
humed and protected from disintegration
with alluvial accumulations by transien
upraised; and, if any organic remains
transported materials, they may, after
beyond the reach of the erosive power of
the drainage is repeatedly deranged b
every fissure, every hollow caused by the
a depository of organic and inorganic s
transient floods.

Marine alluvium. — In May, 1787, a
sea was caused at Coringa, Ingeram, and
Coromandel, in the East Indies, by a

Sir T. D. Lauder, Bart., on Floods in Mo

N.E., which raised the waters so that they rolled inland to the distance of about twenty miles from the shore, swept away many villages, drowned more than 10,000 people, and left the country covered with marine mud, on which the carcasses of about 100,000 head of cattle were strewed. An old tradition of the natives of a similar flood, said to have happened about a century before, was, till this event, regarded as fabulous by the European settlers.* The same coast of Coromandel was, so late as May, 1832, the scene of another catastrophe of the same kind; and when the inundation subsided, several vessels were seen grounded in the fields of the low country about Coringa.

Many of the storms termed hurricanes have evidently been connected with submarine earthquakes, as is shown by the atmospheric phenomena attendant on them, and by the sounds heard in the ground and the odours emitted. Such were the circumstances which accompanied the swell of the sea in Jamaica, in 1780, when a great wave desolated the western coast, and, bursting upon Savanna la Mar, swept away the whole town in an instant, so that not a vestige of man, beast, or habitation, was seen upon the surface.†

Houses and works of art in alluvial deposits.—A very ancient subterranean town, apparently of Hindoo origin, was discovered in India in 1833, in digging the Doab canal. Its site is north of Saharunpore, near the town of Behat, and seventeen feet below the present surface of the country. More than 170 coins of silver and copper have already been found, and many articles in metal and earthenware. The overlying deposit consisted of about five feet of river sand, with a substratum, about twelve feet thick, of red alluvial clay. In the neighbourhood are several rivers and torrents, which descend from the mountains charged with vast quantities of mud, sand, and shingle; and within the memory of persons now living the modern Behat has been threatened by an inundation, which, after retreating, left the neighbouring country strewed over with a superficial covering of sand several feet thick. In sinking wells in the environs, masses of shingle and boulders have been reached resembling those now in the river-channels of the same district, under a deposit of thirty feet of reddish loam. Captain Cautley, therefore, who directed the excavations, supposes that the matter discharged by torrents has gradually raised the whole country skirting the base of the lower hills; and that the ancient town, having been originally built in a hollow, was submerged by floods, and covered over with sediment seventeen feet in thickness.‡

We are informed, by M. Boblaye, that in the Morea, the formation termed céramique, consisting of pottery, tiles, and bricks, intermixed with various works of art, enters so largely into the alluvium and vegetable soil upon the plains of Greece, and into hard and crystalline breccias which have been formed at the foot of declivities, conceive that they can owe their origin to the mere fracturing and displacement of solid masses.

---

* Dodsley's Ann. Regist., 1788.

† Edwards, Hist. of West Indies, vol. i. p. 235. ed. 1801.

‡ Journ. of Asiat. Soc., Nos. xxv. and xxix., 1834.

In the limestone of Kentucky, in the basin of Green River, one of the tributaries of the Ohio, a line of underground cavities has been traced in one direction for a distance of ten miles, without any termination; and one of the chambers, of which there are many, all connected by narrow tunnels, is no less than ten acres in area, and 150 feet in its greatest height. Besides the principal series of "antres vast," there are a great many lateral embranchments not yet explored.*

The cavernous structure here alluded to, is not altogether confined to calcareous rocks; for it has lately been observed in micaceous and argillaceous schist in the Grecian island of Thermia (Cythnos of the ancients), one of the Cyclades. Here also spacious halls, with rounded and irregular walls, are connected together by narrow passages or tunnels, and there are many lateral branches which have no outlet. A current of water has evidently at some period flowed through the whole, and left a muddy deposit of bluish clay upon the floor; but the erosive action of the stream cannot be supposed to have given rise to the excavations in the first instance. M. Virlet suggests that fissures were first caused by earthquakes, and that these fissures became the chimneys or vents for the disengagement of gas, generated below by volcanic heat. Gases, he observes, such as the muriatic, sulphuric, fluoric, and others, might, if raised to a high temperature, alter and decompose the rocks which they traverse. There are signs of the former action of such vapours in rents of the micaceous schist of Thermia, and thermal springs now issue from the grottos of that island. We may suppose that afterwards the elements of the decomposed rocks were gradually removed in a state of solution by mineral waters; a theory which, according to M. Virlet, is confirmed by the effect of heated gases which escape from rents in the isthmus of Corinth, and which have greatly altered and corroded the hard siliceous and jaspideous rocks.†

When we reflect on the quantity of carbonate of lime annually poured out by mineral waters, we are prepared to admit that large cavities must, in the course of ages, be formed at considerable depths below the surface in calcareous rocks.‡ These rocks, it will be remembered, are at once more soluble, more permeable, and more fragile, than any others, at least all the compact varieties are very easily broken by the movements of earthquakes, which would produce only flexures in argillaceous strata. Fissures once formed in limestone are not liable, as in many other formations, to become closed up by impervious clayey mattor, and hence a stream of acidulous water might for ages obtain a free and unobstructed passage.§

Morea.—Nothing is more common in limestone districts than the

---

* Nahum Ward, Trans. of Antiq. Soc. of Massachusetts. Holmes's United States, p. 438.

† Bull. de la Soc. Géol. de France, tom. ii. p. 329.

‡ See above, p. 240.

§ See remarks by M. Boblaye, Ann. des Mines, 3me série, tom. iv.

engulfment of rivers, which after holding a subterranea
many miles escape again by some new outlet. As they
charged with fine sediment, and often with sand and pe
they enter, whereas they are usually pure and limpid whe
out again, they must deposit much matter in empty sp
interior of the earth. In addition to the materials thu
stalagmite, or carbonate of lime, drops from the roofs of
in this mixture the bones of animals washed in by riv
entombed. In this manner we may account for those b
which we often find in caves, some of which are of hi
while others are very recent and in daily progress. I
are engulfed streams more conspicuous than in the M
the phenomena attending them have been lately studied a
in great detail by M. Boblaye and his fellow-labourers of
expedition to Greece.* Their account is peculiarly in
geologists, because it throws light on the red osseous b
taining the bones of extinct quadrupeds which are so
almost all the countries bordering the Mediterranean. It
the numerous caverns of the Morea occur in a compact
the age of the English chalk, immediately below which ar
strata referred to the period of our greensand. In the m
districts of that peninsula there are many deep land-locke
basins, closed round on all sides by mountains of fissure
nous limestone. The year is divided almost as distinctly
the tropics into a rainy season, which lasts upwards of
and a season of drought of nearly eight months' durat
the torrents are swollen by the rains, they rush from
heights into the inclosed basins; but, instead of giving
as would be the case in most other countries, they are
gulfs or chasms, called by the Greeks "Katavothra,"
correspond to what are termed "swallow-holes" in th
England. The water of these torrents is charged with
red ochreous earth, resembling precisely the well-know
the osseous breccias of the Mediterranean. It dissolves i
effervescence, and leaves a residue of hydrated oxide of ir
iron, impalpable grains of silex, and small crystals of q
of the same description abounds every where on the su
decomposing limestone in Greece, that rock containing
siliceous and ferruginous matter.

Many of the Katavothra being insufficient to give pa
the water in the rainy season, a temporary lake is formed
mouth of the chasm, which then becomes still farther ob
pebbles, sand, and red mud, thrown down from the tur
The lake being thus raised, its waters generally escape th
openings, at higher levels, around the borders of the pl
tuting the bottom of the closed basin.

In some places, as at Kavaros and Tripolitza, where th discharge is by a gulf in the middle of the plain, nothing can be seen over the opening in summer, when the lake dries up, but a deposit of red mud, cracked in all directions. But the Katavothron is more commonly situated at the foot of the surrounding escarpment of limestone; and in that case there is sometimes room enough to allow a person to enter, in summer, and even to penetrate far into the interior. Within is seen a suite of chambers, communicating with each other by narrow passages; and M. Virlet relates, that in one instance he observed, near the entrance, human bones imbedded in recent red mud, mingled with the remains of plants and animals of species now inhabiting the Morea. It is not wonderful, he says, that the bones of man should be met with in such receptacles; for so murderous have been the late wars in Greece, that skeletons are often seen lying exposed on the surface of the country.*

---

* Ann. des Mines, 3me série, tom. iv., 1833.

In summer, when no water is flowing into the Katavothron, its mouth, half closed up with red mud, is masked by a vigorous vegetation, which is cherished by the moisture of the place. It is then the favourite hiding-place and den of foxes and jackals; so that the same cavity serves at one season of the year for the habitation of carnivorous beasts, and at another as the channel of an engulfed river. Near the mouth of one chasm, M. Boblaye and his companions saw the carcass of a horse, in part devoured, the size of which seemed to have prevented the jackals from dragging it in: the marks of their teeth were observed on the bones, and it was evident that the floods of the ensuing winter would wash in whatsoever might remain of the skeleton.

It has been stated that the waters of all these torrents of the Morea are turbid where they are engulfed; but when they come out again, often at the distance of many leagues, they are perfectly clear and limpid, being only charged occasionally with a slight quantity of calcareous sand. The points of efflux are usually near the sea-shores of the Morea, but sometimes they are submarine; and when this is the case, the sands are seen to boil up for a considerable space, and the surface of the sea, in calm weather, swells in large convex waves. It is curious to reflect, that when this discharge fails in seasons of drought, the pressure of the sea may force its salt waters into subterraneous caverns, and carry in marine sand and shells, to be mingled with ossiferous mud, and the remains of terrestrial animals.

In general, however, the efflux of water at these inferior openings is surprisingly uniform. It seems, therefore, that the large caverns in the interior must serve as reservoirs, and that the water escapes gradually from them, in consequence of the smallness of the rents and passages by which they communicate with the surface.

The phenomena above described are not confined to the Morea, but occur in Greece generally, and in those parts of Italy, Spain, Asia Minor, and Syria, where the formations of the Morea extend. The Copaic lake in Bœotia has no outlet, except by underground

---

* Bull. de la Soc. Géol. de France, tom. iii. p. 223.

Dr. Schmerling has discovered in a cavern at Chockier, about two leagues from Liège, three distinct beds of stalagmite, and between each of them a mass of breccia, and mud mixed with quartz pebbles, and in the three deposits the bones of extinct quadrupeds.*

This exception does not invalidate the generality of the phenomenon pointed out by Dr. Buckland, one cause of which may perhaps be this, that if several floods pass at different intervals of time through a subterranean passage, the last, if it has power to drift along fragments of rock, will also tear up any alternating stalagmitic and alluvial beds that may have been previously formed. Another cause may be, that a particular line of caverns will rarely be so situated, in relation to the lowest levels of a country, as to become, at two distinct epochs, the receptacle of engulfed rivers; and if this should happen, some of the caves, or at least the tunnels of communication, may at the first period be entirely choked up with transported matter, so as not to allow the subsequent passage of water in the same direction.

As the same chasms may remain open throughout periods of indefinite duration, the species inhabiting a country may in the meantime be greatly changed, and thus the remains of animals belonging to very different epochs may become mingled together in a common tomb. For this reason it is often difficult to separate the monuments of the human epoch from those relating to periods long antecedent, and it was not without great care and skill that Dr. Buckland was enabled to guard against such anachronisms in his investigation of several of the English caves. He mentions that human skeletons were found in the cave of Wokey Hole, near Wells, in the Mendips, dispersed through reddish mud and clay, and some of them united by stalagmite into a firm osseous breccia. "The spot on which they lie is within reach of the highest floods of the adjacent river, and the mud in which they are buried is evidently fluviatile."†

In speaking of the cave of Paviland on the coast of Glamorganshire, the same author states that the entire mass through which bones were dispersed appeared to have been disturbed by ancient diggings, so that the remains of extinct animals had become mixed with recent bones and shells. In the same cave was a human skeleton, and the remains of recent testacea of eatable species, which may have been carried in by man.

In several caverns on the banks of the Meuse, near Liège, Dr. Schmerling has found human bones in the same mud and breccia with those of the elephant, rhinoceros, bear, and other quadrupeds of extinct species. He has observed none of the dung of any of these animals: and from this circumstance, and the appearance of the mud and pebbles, he concludes that these caverns were never inhabited by wild beasts, but washed in by a current of water. As the human skulls and bones were in fragments, and no entire skeleton had been found, he does not believe that these caves were places of sepul but that the human remains were washed in at the same time a bones of extinct quadrupeds, and that these lost species of mam co-existed on the earth with man.

---

* Journ. de Géol., tom. i. p. 286. July, 1830.

† Reliquiæ Diluvianæ, p. 165.

Caverns in the South of France. — Similar associations in south of France, of human bones and works of art, with remai extinct quadrupeds, have induced other geologists to maintain man was an inhabitant of that part of Europe before the rhinoc hyæna, tiger, and many fossil species disappeared. I may first tion the cavern of Bize, in the department of Aude, where M. M de Serres met with a small number of human bones mixed those of extinct animals and with land shells. They occur in a careous stony mass, bound together by a cement of stalagmite. examining the same caverns, M. Tournal found not only in these careous beds, but also in a black mud which overlies a red c mud, several human teeth, together with broken angular fragm of a rude kind of pottery, and also recent marine and terre shells. The teeth preserve their enamel; but the fangs are so altered as to adhere strongly when applied to the tongue. Of terrestrial shells thus associated with the bones and pottery, most common are *Cyclostoma elegans*, *Bulimus decollatus*, *nemoralis*, and *H. nitida*. Among the marine are found *P jacobæus*, *Mytilus edulis*, and *Natica mille-punctata*, all of them able kinds, and which may have been brought there for food. B were found in the same mass belonging to three new species of an extinct bear (*Ursus arctoïdeus*), and the wild bull (*Bos* formerly a native of Germany.*

In the same parts of France, M. de Christol has found in cav in a tertiary limestone at Pondres and Souvignargues, two lea north of Lunel-viel, in the department of Herault, human bones pottery confusedly mixed with remains of the rhinoceros, hyæna, and other terrestrial mammifers. They were imbedde alluvial mud, of the solidity of calcareous tufa, and containing flint pebbles and fragments of the limestone of the country. Ben this mixed accumulation, which sometimes attained a thickne thirteen feet, is the original floor of the cavern, about a foot t covered with bones and the dung of animals (*album græcum*), sandy and tufaceous cement.

The human bones in these caverns of Pondres and Souvignar were found, upon a careful analysis, to have parted with their an matter to as great a degree, as those of the hyæna which acc pany them, and are equally brittle, and adhere as strongly to tongue.

In order to compare the degree of alteration of these bones those known to be of high antiquity, M. Marcel de Serres and Ballard, chemists of Montpellier, procured some from a Ga sarcophagus, in the plain of Lunel, supposed to have been bu for fourteen or fifteen centuries at least. In these the cellular tissue was empty, but they were more solid than fresh bones. They did not adhere to the tongue in the same manner as those of the caverns of Bize and Pondres, yet they had lost at least three fourths of their original animal matter.

---

* M. Marcel de Serres, Géognosie des Terrains Tertiaries, p. 64. Introduct

The superior solidity of the Gaulish bones to those in a fresh skeleton is a fact in perfect accordance with the observations made by Dr. Mantell on bones taken from a Saxon tumulus near Lewes.

M. Tessier has also described a cavern near Mialet, in the department of Gard, where the remains of the bear and other animals were mingled confusedly with human bones, coarse pottery, teeth pierced for amulets, pointed fragments of bone, bracelets of bronze, and a Roman urn. Part of this deposit reached to the roof of the cavity, and adhered firmly to it. The author suggests that the exterior portion of the grotto may at one period have been a den of bears, and that afterwards the aboriginal inhabitants of the country took possession of it either for a dwelling or a burial place, and left there the coarse pottery, amulets, and pointed pieces of bone. At a third period the Romans may have used the cavern as a place of sepulture or concealment, and to them may have belonged the urn and bracelets of metal. If we then suppose the course of the neighbouring river to be impeded by some temporary cause, a flood would be occasioned which, rushing into the open grotto, may have washed all the remains into the interior caves and tunnels, heaping the whole confusedly together.*

In the controversy which has arisen on this subject MM. Marcel de Serres, De Christol, Tournal, and others, have contended, that the phenomena of this and other caverns in the south of France prove that the fossil rhinoceros, hyæna, bear, and several other lost species were once contemporaneous inhabitants of the country, together with man; while M. Desnoyers has supported the opposite opinion. The flint hatchets and arrow-heads, he says, and the pointed bones and coarse pottery of many French and English caves, agree precisely in character with those found in the tumuli, and under the dolmens (rude altars of unhewn stone) of the primitive inhabitants of Gaul, Britain, and Germany. The human bones, therefore, in the caves which are associated with such fabricated objects, must belong not to antediluvian periods, but to a people in the same stage of civilization as those who constructed the tumuli and altars.

In the Gaulish monuments we find, together with the objects of industry above mentioned, the bones of wild and domestic animals of species now inhabiting Europe, particularly of deer, sheep, wild-boars, dogs, horses, and oxen. This fact has been ascertained in Quercy, and other provinces; and it is supposed by antiquaries that the animals in question were placed beneath the Celtic altars in memory of sacrifices offered to the Gaulish divinity Hesus, and in the tombs to commemorate funeral repasts, and also from a supposition prevalent among savage nations, which induces them to lay up provisions for the manes of the dead in a future life. But in n these ancient monuments have any bones been found of the elep rhinoceros, hyæna, tiger, and other quadrupeds, such as are in caves, as might certainly have been expected, had these sp continued to flourish at the time that this part of Gaul was inha by man.*

---

* Bull. de la Soc. Géol. de France, tom. ii. pp. [illegible]

We are also reminded by M. Desnoyers of a passage in Flor which it is related that Cæsar ordered the caves into which the A tanian Gauls had retreated to be closed up.† It is also on re that so late as the eighth century, the Aquitanians defended thems in caverns against King Pepin. As many of these caverns ther may have served in succession as temples and habitations, as pla sepulture, concealment, or defence, it is easy to conceive that h bones, and those of animals, in osseous breccias of much older may have been swept away together, by inundations, and then b in one promiscuous heap.

It is not on the evidence of such intermixtures that we ought re to admit either the high antiquity of the human race, or the r date of certain lost species of quadrupeds.

Among the various modes in which the bones of animals be preserved independently of the agency of land floods and eng rivers, I may mention that open fissures often serve as natural falls in which herbivorous animals perish. This may happen the readily when they are chased by beasts of prey, or when surp while carelessly browsing on the shrubs which so often overgrow conceal the edges of fissures.‡

During the excavations recently made near Behat in India bones of two deer were found at the bottom of an ancient well w had been filled up with alluvial loam. Their horns were brok pieces, but the jaw bones and other parts of the skeleton rema tolerably perfect. "Their presence," says Captain Cautley, "is e accounted for, as a great number of these and other animals are stantly lost in galloping over the jungles and among the high by falling into deserted wells."§

Above the village of Selside, near Ingleborough in Yorkshi chasm of enormous but unknown depth occurs in the scar-limes a member of the carboniferous series. "The chasm," says Prof Sedgwick, "is surrounded by grassy shelving banks, and m animals, tempted towards its brink, have fallen down and perishe it. The approach of cattle is now prevented by a strong lofty w but there can be no doubt that, during the last two or three thou years, great masses of bony breccia must have accumulated in lower parts of the great fissure, which probably descends thr the whole thickness of the scar-limestone, to the depth of per five or six hundred feet."‖

---

* Desnoyers, Bull. de la Soc. Géol. de France, tom. ii. p. 252.

† Hist. Rom. Epit., lib. iii. c. 10.

‡ Buckland, Reliquiæ Diluvianæ, p. 25.

§ See above, pp. 730, 731.

‖ On the Lake Mountains of of England, Geol. Soc. Jan. 5. 183

When any of these natural pit-falls happen to communicate with lines of subterranean caverns, the bones, earth, and breccia, may sink by their own weight, or be washed into the vaults below.

At the north extremity of the rock of Gibraltar are perpendicular fissures, on the ledges of which a number of hawks nestle and rear their young in the breeding season. They throw down from their nests the bones of small birds, mice, and other animals on which they feed, and these are gradually united into a breccia of angular fragments of the decomposing limestone with a cement of red earth.

At the pass of Escrinet in France, on the northern escarpment of the Coiron hills, near Aubenas, I have seen a breccia in the act of forming. Small pieces of disintegrating limestone are transported, during heavy rains, by a streamlet, to the foot of the declivity, where land shells are very abundant. The shells and pieces of stone soon become cemented together by stalagmite into a compact mass, and the talus thus formed is in one place fifty feet deep, and five hundred yards wide. So firmly is the lowest portion consolidated, that it is quarried for mill-stones.

Recent stalagmitic limestone of Cuba. — One of the most singular examples of the recent growth of stalagmitic limestone in caves and fissures, is that described by Mr. R. C. Taylor, as observable on the north-east part of the island of Cuba.* The country there is composed of a white marble, in which are numerous cavities, partially filled with a calcareous deposit of a brick-red colour. In this red deposit are shells, or often the hollow casts of shells, chiefly referable to eight or nine species of land snails, a few scattered bones of quadrupeds, and, what is still more singular, marine univalve shells, often at the height of many hundred, or even one thousand feet above the sea. The following explanation is given of the gradual increase of this deposit. Land snails of the genera Helix, Cyclostoma, Pupa, and Clausilia, retire into the caves, the floors of which are strewed with myriads of their dead and unoccupied shells, at the same time that water infiltered through the mountain throws down carbonate of lime, enveloping the shells, together with fragments of the white limestone which occasionally falls from the roof. Multitudes of bats resort to the caves; and their dung, which is of a bright red colour, (probably derived from the berries on which they feed,) imparts its red hue to the mass. Sometimes also the Hutia, or great Indian rat of the island, dies and leaves its bones in the caves. "At certain seasons the soldier-crabs resort to the sea-shore, and then return from their pilgrimage, each carrying with them, or rather dragging, the shell of some marine univalve for many a weary mile. They may be traced even at the distance of eight or ten miles from the shore, on the summit of mountains 1200 feet high, like the pilgrims of the olden times, each bearing his shell to denote the character and extent of his wanderings." By this means several species of marine testacea of the

---

* Notes on Geol. of Cuba, 1836, Phil. Mag., July, 1837.

genera Trochus, Turbo, Littorina, and Monodonta, are conveye
into inland caverns, and enter into the composition of the new
formed rock.

CHAPTER XLVII.

IMBEDDING OF ORGANIC REMAINS IN SUBAQUEOUS DEPOSITS.

Division of the subject—Imbedding of terrestrial animals and plants—Incr
specific gravity of wood sunk to great depths in the sea—Drift-timber of
Mackenzie in Slave Lake and Polar Sea—Floating trees in the Mississippi—
the Gulf Stream—on the coast of Iceland, Spitzbergen, and Labrador—S
marine forests—Example on coast of Hampshire—Mineralization of plan
Imbedding of marine plants—of insects—of reptiles—Bones of birds why
—Imbedding of terrestrial quadrupeds by river floods—Skeletons in m
shell marl—Imbedding of mammiferous remains in marine strata.

Division of the subject.—Hᴀᴠɪɴɢ treated of the imbedding of orga
remains in deposits formed upon the land, I shall next consider
including of the same in deposits formed under water.

It will be convenient to divide this branch of our subject i
three parts ; considering, first, the various modes whereby the re
of *terrestrial* species may be buried in subaqueous formations ;
condly, the modes whereby animals and plants inhabiting *fresh wa*
may be so entombed ; thirdly, how *marine* species may become p
served in new strata.

The phenomena above enumerated demand a fuller share
attention than those previously examined, since the deposits wh
originate upon dry land are insignificant in thickness, superfic
extent, and durability, when contrasted with those of subaque
origin. At the same time, the study of the latter is beset w
greater difficulties ; for we are here concerned with the results
processes much farther removed from the sphere of ordinary
servation. There is, indeed, no circumstance which so seriou
impedes the acquisition of just views in our science as an habit
disregard of the important fact, that the reproductive effects of t
principal agents of change are confined to another element—to th
larger portion of the globe, from which by our very organisation,
are almost entirely excluded.*

Imbedding of Terrestrial Plants.

When a tree falls into a river from the undermining of the ba
or from being washed in by a torrent or flood, it floats on the surf

---

* See above, p. 67.

not because the woody portion is specifically lighter than water, but because it is full of pores containing air. When soaked for a considerable time, the water makes its way into these pores, and the wood becomes *water-logged* and sinks. The time required for this process varies in different woods; but several kinds may be drifted to great distances, sometimes across the ocean, before they lose their buoyancy.

Wood sunk to a great depth in the sea.—If wood be sunk to vast depths in the sea, it may be impregnated with water suddenly. Captain Scoresby informs us, in his Account of the Arctic Regions, that on one occasion a whale, on being harpooned, ran out all the lines in the boat, which it then dragged under water, to the depth of several thousand feet, the men having just time to escape to a piece of ice. When the fish returned to the surface "to blow," it was struck a second time, and soon afterwards killed. The moment it expired it began to sink,—an unusual circumstance, which was found to be caused by the weight of the sunken boat, which still remained attached to it. By means of harpoons and ropes the fish was prevented from sinking, until it was released from the weight by connecting a rope to the lines of the attached boat, which was no sooner done than the fish rose again to the surface. The sunken boat was then hauled up with great labour; for so heavy was it, that although before the accident it would have been buoyant when full of water, yet it now required a boat at each end to keep it from sinking. "When it was hoisted into the ship, the paint came off the wood in large sheets; and the planks, which were of wainscot, were as completely soaked in every pore as if they had lain at the bottom of the sea since the flood! A wooden apparatus that accompanied the boat in its progress through the deep, consisting chiefly of a piece of thick deal, about fifteen inches square, happened to fall overboard, and though it originally consisted of the lightest fir, sank in the water like a stone. The boat was rendered useless: even the wood of which it was built, on being offered to the cook for fuel, was tried and rejected as incombustible."[*]

Captain Scoresby found that, by sinking pieces of fir, elm, ash, &c., to the depth of four thousand and sometimes six thousand feet, they became impregnated with sea-water, and when drawn up again, after immersion, for an hour, would no longer float. The effect of this impregnation was to increase the dimensions as well as the specific gravity of the wood, every solid inch having increased one-twentieth in size and twenty-one twenty-fifths in weight.[†]

Drift-wood of the Mackenzie River.—When timber is drifted down by a river, it is often arrested by lakes; and, becoming waterlogged, it may sink and be imbedded in lacustrine strata, if any be there forming; sometimes a portion floats on till it reaches the sea. In the course of the Mackenzie River we have an example of vast accumulations of vegetable matter now in progress under both th circumstances.

---

[*] Account of the Arctic Regions, vol. ii. p. 193.

[†] Ibid. p. 202.

In Slave Lake in particular, which vies in dimensions with s of the great freshwater seas of Canada, the quantity of drift-tim brought down annually is enormous. "As the trees," says Richardson, "retain their roots, which are often loaded with e and stones, they readily sink, especially when water-soaked; accumulating in the eddies, form shoals, which ultimately augm into islands. A thicket of small willows covers the new-form island as soon as it appears above water, and their fibrous ro serve to bind the whole firmly together. Sections of these isla are annually made by the river, assisted by the frost; and it interesting to study the diversity of appearances they present, cording to their different ages. The trunks of the trees gradu decay until they are converted into a blackish brown substa resembling peat, but which still retains more or less of the fibr structure of the wood; and layers of this often alternate with lay of clay and sand, the whole being penetrated, to the depth of four five yards or more, by the long fibrous roots of the willows. deposition of this kind, with the aid of a little infiltration of bi minous matter, would produce an excellent imitation of coal, w vegetable impressions of the willow-roots. What appeared m remarkable was the horizontal slaty structure that the old alluv banks presented, or the *regular curve* that the strata assumed fr unequal subsidence.

"It was in the rivers only that we could observe sections of th deposits; but the same operation goes on, on a much more magnific scale, in the lakes. A shoal of many miles in extent is formed on t south side of Athabasca Lake, by the drift timber and vegetal debris brought down by the Elk River; and the Slave Lake its must in process of time be filled up by the matters daily convey into it from Slave River. Vast quantities of drift-timber are buri under the sand at the mouth of the river, and enormous piles of are accumulated on the shores of every part of the lake." *

The banks of the Mackenzie display almost every where horizon beds of wood coal, alternating with bituminous clay, gravel, sa and friable sandstone; sections, in short, of such deposits as are n evidently forming at the bottom of the lakes which it traverses.

Notwithstanding the vast forests intercepted by the lakes, a st greater mass of drift-wood is found where the Mackenzie reaches t sea, in a latitude where no wood grows at present except a fe stunted willows. At the mouths of the river the alluvial matter h formed a barrier of islands and shoals, where we may expect a gre formation of coal at some distant period.

The abundance of floating timber on the Mackenzie is owing, Dr. Richardson informs me, to the direction and to the length of t course of this river, which runs from south to north, so that t sources of the stream lie in much warmer latitudes than its mouths. In the country, therefore, where the sources are situated, the frost breaks up at an earlier season, while yet the waters in the lower part of its course are ice-bound. Hence the current of water, rushing down northward, reaches a point where the thaw has not begun, and, finding the channel of the river blocked up with ice, it overflows the banks, sweeping through forests of pines, and carrying away thousands of uprooted trees.

---

* Dr. Richardson's Geognost. Obs. on Capt. Franklin's Polar Expedition.

Drift-timber on coasts of Iceland, Spitzbergen, &c.—The ancient forests of Iceland, observes Malte-Brun, have been improvidently exhausted; but, although the Icelander can obtain no timber from the land, he is supplied with it abundantly by the ocean. An immense quantity of thick trunks of pines, firs, and other trees, are thrown upon the northern coast of the island, especially upon North Cape and Cape Langaness, and are then carried by the waves along these two promontories to other parts of the coast, so as to afford sufficiency of wood for fuel and for constructing boats. Timber is also carried to the shores of Labrador and Greenland; and Crantz assures us that the masses of floating wood thrown by the waves upon the island of John de Mayen often equal the whole of that island in extent.*

In a similar manner the bays of Spitzbergen are filled with drift-wood, which accumulates also upon those parts of the coast of Siberia that are exposed to the east, consisting of larch trees, pines, Siberian cedars, firs, and Pernambuco and Campeachy woods. These trunks appear to have been swept away by the great rivers of Asia and America. Some of them are brought from the Gulf of Mexico, by the Bahama stream; while others are hurried forward by the current which, to the north of Siberia, constantly sets in from east to west. Some of these trees have been deprived of their bark by friction, but are in such a state of preservation as to form excellent building timber.† Parts of the branches and almost all the roots remain fixed to the pines which have been drifted into the North Sea, into latitudes too cold for the growth of such timber, but the trunks are usually barked.

The leaves and lighter parts of plants are seldom carried out to sea, in any part of the globe, except during tropical hurricanes among islands, and during the agitations of the atmosphere which sometimes accompany earthquakes and volcanic eruptions.

Comparative number of living and fossilized species of plants.—It will appear from these observations that, although the remains of terrestrial vegetation, borne down by aqueous causes from the land, are chiefly deposited at the bottom of lakes or at the mouths of rivers; yet a considerable quantity is drifted about in all directions by currents, and may become imbedded in any *marine* formation, or

---

* Malte-Brun, Geog., vol. v. part i. p. 112.—Brantz, Hist. of Greenland, tom. i. pp. 53—54.

† Olafsen, Voyage to Iceland, tom. i. Malte-Brun's Geog., vol. v. part i. p. 112.

may sink down, when water-logged, to th
abysses, and there accumulate without in
stances.

It may be asked whether we have any d
remains of a considerable proportion of th
will be permanently preserved, so as to
supposing the strata now in progress to
upraised? To this inquiry it may be an
reasons for expecting that more than a sm
now flourishing in the globe will become f
habitations of a great number of them
seas, and even where they grow near to
circumstances are quite accidental and par
bedding and conservation of vegetable
example, that the species of plants inh
basin of the Rhine, or that region, exte
sea, which is watered by the Rhine and it
be about 2500 in number, exclusive of th
estimate is by no means exaggerated; yet
the deposits which have resulted from the
the Lake of Constance, and off the coast o
expect to obtain from the recent strata
of *fifty* species in such a state of preserva
to determine their specific characters with

Those naturalists, therefore, who infe
the globe was, at certain periods, less
because they have as yet discovered only
of a particular epoch, while they can
hundred thousand living ones, are reasoni
standard of comparison is not the same in

Submarine forests on coast of Hants.—
the submarine position of several forest
standing in a vertical position on the B
in some instances, to the subsidence of la
which require a different explanation.
Harris, discovered, in 1831, evident trace
mean level of the sea, at Bournmouth, i
having been laid open during a low sprin
peat and wood, and is situated between th
about 200 yards off, and extends fifty yar
lies in the direct line of the Bournmouth
of which it is separated by 200 yards
Down the valley flows a large brook, tr
considerable tract of rough, boggy, and
duces a few birch trees, and a great abu
Seventy-six rings of annual growth we
section of one of the buried fir-trees, w
diameter. Besides the stumps and root

---

* See above, pp. 303, a

birch are found in the peat; and it is a curious fact, that a part of many of the trees have been converted into iron pyrites. The peat rests on pebbly strata, precisely similar to the sand and pebbles occurring on the adjoining heaths.

As the sea is encroaching on this shore, we may suppose that at some former period the Bourne Valley extended farther, and that its extremity consisted, as at present, of boggy ground, partly clothed with fir-trees. The bog rested on that bed of pebbles which we now see below the peat; and the sea, in its progressive encroachments, eventually laid bare, at low water, the sandy foundations; upon which a stream of fresh water, rushing through the sand at the fall of the tides, carried out loose sand with it. The super-stratum of vegetable matter, being matted and bound together by the roots of trees, remained; but being undermined, sank down below the level of the sea, and then the waves washed sand and shingle over it. In support of this hypothesis, it may be observed, that small streams of fresh water often pass under the sands of the sea-beach, so that they may be crossed dry-shod; and the water is seen, at the point where it issues, to carry out sand and even pebbles.

Mineralization of plants.—Although the botanist and chemist have as yet been unable to explain fully the manner in which wood becomes petrified, it is nevertheless ascertained that, under favourable circumstances, the lapidifying process is now continually going on. A piece of wood was lately procured by Mr. Stokes, from an ancient Roman aqueduct in Westphalia, in which some portions were converted into spindle-shaped bodies, consisting of carbonate of lime, while the rest of the wood remained in a comparatively unchanged state.* It appears that in some cases the most perishable, in others the most durable, portions of plants are preserved, variations which doubtless depend on the time when the mineral matter was supplied. If introduced immediately, on the first commencement of decomposition, then the most destructible parts are lapidified, while the more durable do not waste away till afterwards, when the supply has failed, and so never become petrified. The converse of these circumstances gives rise to exactly opposite results.

Professor Göppert, of Breslau, has instituted a series of curious experiments, in which he has succeeded in producing some very remarkable imitations of fossil petrifactions. He placed recent ferns between soft layers of clay, dried these in the shade, and then slowly and gradually heated them, till they were red-hot. The result was the production of so perfect a counterpart of fossil plants as might have deceived an experienced geologist. According to the different degrees of heat applied, the plants were obtained in a brown or perfectly carbonized condition; and sometimes, but more rarely, they were in a black shining state, adhering closely to the layer of clay. If the red heat was sustained until all the organic matter was burnt up, only an impression of the plant remained.

---

* Geol. Trans., second series, vol. v. p. 212.

The same chemist steeped plants in a moderately strong solution of sulphate of iron, and left them immersed in it for several days, until they were thoroughly soaked in the liquid. They were then dried, and kept heated until they would no longer shrink in volume, and until every trace of organic matter had disappeared. On cooling them he found that the oxide formed by this process had taken the form of the plants. A variety of other experiments were made by steeping animal and vegetable substances in siliceous, calcareous, and metallic solutions, and all tended to prove that the mineralization of organic bodies can be carried much farther in a short time than had been previously supposed.[*]

Imbedding of the Remains of Insects.

I have observed the elytra and other parts of beetles in a band of fissile clay, separating two beds of recent shell-marl, in the Loch of Kinnordy in Forfarshire. Amongst these, Mr. Curtis recognized *Elator lineatus* and *Atopa cervina*, species still living in Scotland. These, as well as other remains which accompanied them, appear to belong to terrestrial, not aquatic, species, and must have been carried down in muddy water during an inundation. In the lacustrine peat of the same locality, the elytra of beetles are not uncommon; but in the deposits of drained lakes generally, and in the silt of our estuaries, the relics of this class of the animal kingdom are rare. In the blue clay of very modern origin of Lewes levels, Dr. Mantell has found the Indusia, or cases of the larvæ of Phryganea, in abundance, with minute shells belonging to the genera Planorbis, Limnea, &c., adhering to them.[†]

When speaking of the migrations of insects, I pointed out that an immense number are floated into lakes and seas by rivers, or blown by winds far from the land; but they are so buoyant that we can only suppose them, under very peculiar circumstances, to sink to the bottom before they are either devoured by insectivorous animals or decomposed.

Remains of Reptiles.

As the bodies of several crocodiles were found in the mud brought down to the sea by the river inundation which attended an earthquake in Java, in the year 1699, we may imagine that extraordinary floods of mud may stifle many individuals of the shoals of alligators and other reptiles which frequent lakes and the deltas of rivers in tropical climates. Thousands of frogs were found leaping about among the wreck, carried into the sea by the inundations in Morayshire, in 1829[‡]; and it is evident that whenever a sea-cliff is undermined, or land is swept by other violent causes into the sea, land reptiles may be carried in.

---

[*] Göppert, Poggendorff's Annalen der Physik und Chemie, vol. xxxviii. part iv., Leipsic, 1836. See also Lyell's Manual of Geol., p. 40.

[†] Trans. Geol. Soc., vol. iii. part i. p. 201., second series.

[‡] Sir T. D. Lauder's Account, 2d ed. p. 312.

Remains of Birds.

We might have anticipated that the imbedding of the remains of birds in new strata would be of very rare occurrence, for their powers of flight insure them against perishing by numerous casualties to which quadrupeds are exposed during floods; and if they chance to be drowned, or to die when swimming on the water, it will scarcely ever happen that they will be submerged so as to become preserved in sedimentary deposits. In consequence of the hollow tubular structure of their bones and the quantity of their feathers they are extremely light in proportion to their volume; so that when first killed they do not sink to the bottom like quadrupeds, but float on the surface until the carcass either rots away or is devoured by predaceous animals. To these causes we may ascribe the absence of any vestige of the bones of birds in the recent marl formations of Scotland; although these lakes, until the moment when they were artificially drained, were frequented by a great abundance of water-fowl.

Imbedding of Terrestrial Quadrupeds.

River inundations recur in most climates at very irregular intervals, and expend their fury on those rich alluvial plains, where herds of herbivorous quadrupeds congregate together. These animals are often surprised; and, being unable to stem the current, are hurried along until they are drowned, when they sink at first immediately to the bottom. Here their bodies are drifted along, together with sediment, into lakes or seas, and may then be covered by a mass of mud, sand, and pebbles, thrown down upon them. If there be no sediment superimposed, the gases generated by putrefaction usually cause the bodies to rise again to the surface about the ninth, or at latest the fourteenth day. The pressure of a thin covering of mud would not be sufficient to retain them at the bottom; for we see the putrid carcasses of dogs and cats, even in rivers, floating with considerable weights attached to them, and in sea-water they would be still more buoyant.

Where the body is so buried in drift-sand, or mud accumulated upon it, as never to rise again, the skeleton may be preserved entire; but if it comes again to the surface while in the process of putrefaction, the bones commonly fall piecemeal from the floating carcass, and may in that case be scattered at random over the bottom of the lake, estuary, or sea; so that a jaw may afterwards be found in one place, a rib in another, a humerus in a third—all included, perhaps, in a matrix of fine materials, where there may be evidence of very slight transporting power in the current, or even of none, but simply of some chemical precipitate.

A large number of the bodies of drowned animals, if they fl into the sea or a lake, especially in hot climates, are instan devoured by sharks, alligators, and other carnivorous beasts, whi may have power to digest even the bones; but during extraordin floods, when the greatest number of land animals are destroyed, waters are commonly so turbid, especially at the bottom of channel, that even aquatic species are compelled to escape into so retreat where there is clearer water lest they should be stifled. I this reason, as well as the rapidity of sedimentary deposition at s seasons, the probability of carcasses becoming permanently imbed is considerable.

Flood in the Solway Firth, 1794.—One of the most memora floods of modern date, in our island, is that which visited part of southern borders of Scotland, on the 24th of January, 1794, which spread particular devastation over the country adjoining Solway Firth.

We learn from the account of Captain Napier, that the hea rains had swollen every stream which entered the Firth of Solwa so that the inundation not only carried away a great number of cat and sheep, but many of the herdsmen and shepherds, washing do their bodies into the estuary. After the storm, when the fl subsided, an extraordinary spectacle was seen on a large sand-ba called "the beds of Esk," where there is a meeting of the tidal wate and where heavy bodies are usually left stranded after great floo On this single bank were found collected together the bodies of black cattle, 3 horses, 1840 sheep, 45 dogs, 180 hares, besides great number of smaller animals, and, mingled with the rest, t corpses of two men and one woman.*

Floods in Scotland, 1829.—In those more recent floods Scotland, in August, 1829, whereby a fertile district on the east co became a scene of dreadful desolation, a vast number of animals a plants were washed from the land, and found scattered about after t storm, around the mouths of the principal rivers. An eye-witn thus describes the scene which presented itself at the mouth of t Spey, in Morayshire:—"For several miles along the beach crow were employed in endeavouring to save the wood and other wre with which the heavy-rolling tide was loaded; whilst the margin the sea was strewed with the carcasses of domestic animals, and wi millions of dead hares and rabbits."†

Savannahs of South America.—We are informed by Humbold that during the periodical swellings of the large rivers in Sou America great numbers of quadrupeds are annually drowned. (the wild horses, for example, which graze in immense troops in t savannahs, thousands are said to perish when the river Apure, tributary of the Orinoco, is swollen, before they have time to rea the rising ground of the Llanos. The mares, during the season high water, may be seen, followed by their colts, swimming about and feeding on the grass, of which the top alone waves above the waters. In this state they are pursued by crocodiles; and their thighs frequently bear the prints of the teeth of these carnivorous reptiles. "Such is the pliability," observes the celebrated traveller, "of the organization of the animals which man has subjected to his sway, that horses, cows, and other species of European origin, lead, for a time, an amphibious life, surrounded by crocodiles, water-serpents, and manatees. When the rivers return again into their beds, they roam in the savannah, which is then spread over with a fine odoriferous grass, and enjoy, as in their native climate, the renewed vegetation of spring."*

---

* Treatise on Practical Store Farming, p. 25.

† Sir T. D. Lauder's Floods in Mor shire, 1829; and above, p. 196.

Floods of the Parana.—The great number of animals which are drowned in seasons of drought in the tributaries of the Plata, was before mentioned. Sir W. Parish states, that the Parana flowing from the mountains of Brazil to the estuary of the Plata, is liable to great floods, and during one of these, in the year 1812, vast quantities of cattle were carried away, "and when the waters began to subside, and the islands which they had covered became again visible, the whole atmosphere for a time was poisoned by the effluvia from the innumerable carcasses of skunks, capybaras, tigers, and other wild beasts which had been drowned."†

Floods of the Ganges.—We find it continually stated, by those who describe the Ganges and Burrampooter, that these rivers carry before them, during the flood season, not only floats of reeds and timber, but dead bodies of men, deer, and oxen.‡

In Java, 1699.—I have already referred to the effects of a flood which attended an earthquake in Java in 1699, when the turbid waters of the Batavian river destroyed all the fish except the carp; and when drowned buffaloes, tigers, rhinoceroses, deer, apes, and other wild beasts, were brought down to the sea-coast by the current, with several crocodiles which had been stifled in the mud. (See above, p. 503.)

On the western side of the same island, in the territory of Galongoon, in the Regencies, a more recent volcanic eruption (that of 1822, before described) (see above, p. 431), was attended by a flood, during which the river Tandoi bore down hundreds of carcasses of rhinoceroses and buffaloes, and swept away more than one hundred men and women from a multitude assembled on its banks to celebrate a festival. Whether the bodies reached the sea, or were deposited, with drift matter, in some of the large intervening alluvial plains, we are not informed.§

Sumatra.—"On the coast of Orissa," says Heynes, "I have seen tigers and whole herds of black cattle carried along by what are called freshes, and trees of immense size."‖

---

* Humboldt's Pers. Nar., vol. iv. p. 394.

† Buenos Ayres and La Plata, p. 187.

‡ Malte-Brun, Geog., vol. iii. p. 22.

§ This account I had from Mr. Baumhauer, Director-General of Finances in Java.

‖ Tracts on India, p. 397.

Mammiferous remains in marine strata.—As the bones of mammalia are often so abundantly preserved in peat, and such lakes as have just been described, the encroachments of a sea upon a coast may sometimes throw down the imbedded skeletons, so that they may be carried away by tides and currents, and entombed in submarine formations. Some of the smaller quadrupeds, also, which burrow in the ground, as well as reptiles and every species of plant, are liable to be cast down into the waves by this cause, which must not be overlooked, although probably of comparatively small importance amongst the numerous agents whereby terrestrial organic remains are included in submarine strata.

During the great earthquake of Conception in 1835, some cattle, which were standing on the steep sides of the island of Quiriquina, were rolled by the shock into the sea, while on a low island at the head of the Bay of Conception seventy animals were washed off by a great wave and drowned.*

CHAPTER XLVIII.

IMBEDDING OF THE REMAINS OF MAN AND HIS WORKS IN SUBAQUEOUS STRATA.

Drifting of human bodies to the sea by river inundations—Destruction of bridges and houses—Loss of lives by shipwreck—How human corpses may be preserved in recent deposits—Number of wrecked vessels—Fossil skeletons of men—Fossil canoes, ships, and works of art—Chemical changes which metallic articles have undergone after long submergence—Imbedding of cities and forests in subaqueous strata by subsidence—Earthquake of Cutch in 1819—Buried Temples of Cashmere—Berkeley's arguments for the recent date of the creation of man—Concluding remarks.

I shall now proceed to inquire in what manner the mortal remains of man and the works of his hands may be permanently preserved in subaqueous strata. Of the many hundred million human beings which perish in the course of every century on the land, every vestige is usually destroyed in the course of a few thousand years; but of the smaller number that perish in the waters, a certain proportion must be entombed under circumstances that may enable parts of them to endure throughout entire geological epochs.

The bodies of men, together with those of the inferior animals, are occasionally washed down during river inundations into seas and lakes. (See pp. 726—728.) Belzoni witnessed a flood on the Nile in September, 1818, where, although the river rose only three feet and a half above its ordinary level, several villages, with some hundreds of men, women, and children, were swept away.† It was before mentioned that a rise of six feet of water in the Ganges, in was attended with a much greater loss of lives. (See above, p.

---

* Darwin's Journal, p. 372. 2d ed. 1845, p. 304.

† Narrative of Discovery in Egypt, &c., London, 1820,

In the year 1771, when the inundations in the north of E appear to have equalled the floods of Morayshire in 1829, a number of houses and their inhabitants were swept away rivers Tyne, Can, Wear, Tees, and Greta; and no less than t one bridges were destroyed in the courses of these rivers. village of Bywell the flood tore the dead bodies and coffins out churchyard, and bore them away, together with many of the inhabitants. During the same tempest an immense number of horses, and sheep, were also transported to the sea, while the coast was covered with the wreck of ships. Four centuries (in 1338), the same district had been visited by a similar conti of heavy rains followed by disastrous floods, and it is not impr that these catastrophes may recur periodically, though after unc intervals. As the population increases, and buildings and bridg multiplied, we must expect the loss of lives and property to augr

Fossilization of human bodies in the bed of the sea.—If hundreds of human bodies committed to the deep in the w ordinary burial we add those of individuals lost by shipwrec shall find that, in the course of a single year, a great num human remains are consigned to the subaqueous regions. I hereafter advert to a calculation by which it appears that more five hundred *British* vessels alone, averaging each a burthen of 120 tons, are wrecked, and sink to the bottom, *annually*. Of the crews for the most part escape, although it sometimes ha that all perish. In one great naval action several thousand viduals sometimes share a watery grave.

Many of these corpses are instantly devoured by predaceou sometimes before they reach the bottom; still more frequently they rise again to the surface, and float in a state of putrefa Many decompose on the floor of the ocean, where no sedim thrown down upon them; but if they fall upon a reef where and shells are becoming agglutinated into a solid rock, or su where the delta of a river is advancing, they may be preserv an incalculable series of ages.

Often at the distance of a few hundred feet from a coral where wrecks are not unfrequent, there are no soundings a depth of many hundred fathoms. Canoes, merchant vessels ships of war may have sunk and have been enveloped, in situations, in calcareous sand and breccia, detached by the bre from the summit of a submarine mountain. Should a vol eruption happen to cover such remains with ashes and sand, current of lava be afterwards poured over them, the ships and h skeletons might remain uninjured beneath the superincumbent like the houses and works of art in the subterranean cities of pania. Already many human remains may have been thus pres

---

[*] Scots Mag., vol. xxxiii., 1771.

beneath formations more than a thousand feet in thickness; for, in some volcanic archipelagos, a period of thirty or forty centuries might well be supposed sufficient for such an accumulation. It was stated, that at the distance of about forty miles from the base of the delta of the Ganges, there is an elliptical space about fifteen miles in diameter where soundings of from 100 to 300 fathoms sometimes fail to reach the bottom. (See above, p. 279.) As during the flood season the quantity of mud and sand poured by the great rivers into the Bay of Bengal is so great that the sea only recovers its transparency at the distance of sixty miles from the coast, this depression must be gradually shoaling, especially as during the monsoons, the sea loaded with mud and sand, is beaten back in that direction towards the delta. Now, if a ship or human body sink down to the bottom in such a spot, it is by no means improbable that it may become buried under a depth of a thousand feet of sediment in the same number of years.

Even on that part of the floor of the ocean to which no accession of drift matter is carried (a part which probably constitutes, at any given period, by far the larger proportion of the whole submarine area), there are circumstances accompanying a wreck which favour the conservation of skeletons. For when the vessel fills suddenly with water, especially in the night, many persons are drowned between decks and in their cabins, so that their bodies are prevented from rising again to the surface. The vessel often strikes upon an uneven bottom, and is overturned; in which case the ballast, consisting of sand, shingle, and rock, or the cargo, frequently composed of heavy and durable materials, may be thrown down upon the carcasses. In the case of ships of war, cannon, shot, and other warlike stores, may press down with their weight the timbers of the vessel as they decay, and beneath these and the metallic substances the bones of man may be preserved.

Number of wrecked vessels.—When we reflect on the number of curious monuments consigned to the bed of the ocean in the course of every naval war from the earliest times, our conceptions are greatly raised respecting the multiplicity of lasting memorials which man is leaving of his labours. During our last great struggle with France, thirty-two of our ships of the line went to the bottom in the space of twenty-two years, besides seven 50-gun ships, eighty-six frigates, and a multitude of smaller vessels. The navies of the other European powers, France, Holland, Spain, and Denmark, were almost annihilated during the same period, so that the aggregate of their losses must have many times exceeded that of Great Britain. In every one of these ships were batteries of cannon constructed of iron or brass, whereof a great number had the dates and places of their manufacture inscribed upon them in letters cast in metal. In each there were coins of copper, silver, and often many of gold, capable of serving as valuable historical monuments; in each were an infinite variety of instruments of the arts of war and peace; many formed of materials, such as glass and earthenware, capable

of lasting for indefinite ages when once
action of the waves, and buried under
exclude the corroding action of sea-
over, of timber which is conveyed fron
sea by the sinking of ships of a larg
computed that 2000 tons of wood are
one 74-gun ship; and reckoning fifty
the acre, it would require forty acres
these vessels.*

It would be an error to imagine t
conducive than the peaceful spirit of
accumulation of wrecked vessels in th
examination of Lloyd's lists, from the
ment of 1829, Capt. W. H. Smyth asc
British vessels alone lost during that pe
to no less than one and a half *daily;* a
hardly have been anticipated, although
that the number of merchant vessels e
navigation of England and Scotland,
thousand, having one with another a
My friend, Mr. J. L. Prevost, also in
Lloyd's list for the years 1829, 1830,
less than 1953 vessels were lost in thos
tonnage being about 150 tons, or in all
the enormous rate of 100,000 tons annu
of one nation only. This increased
increasing activity in commerce.

Out of 551 ships of the royal navy lo
period above mentioned, only 160 wer
enemy, the rest having either stranded
burnt by accident; a striking proof th
warfare, however great, may be far exce
the lee-shore, and all the other perils of

Durable nature of many of their
dollars and other coins have been som
ship, and on these, when they happen
capable of protecting them from chemic
of historical interest will remain inscrib
indefinite as have the delicate marking
plants in some of the ancient secondary
ship, moreover, there are some precious
articles of use and ornament composed
nature, on which letters and various ima
which they may retain when included in
a crystal preserves its natural form.

---

* Quart. Journ. of Agricult., No. ix. p. 433.

† Cæsar Moreau's Tables of the Na- vigati

‡ I
of Ca

It was, therefore, a splendid boast, that the deeds of the English chivalry at Agincourt made Henry's chronicle

> —— as rich with praise
> As is the ooze and bottom of the deep
> With sunken wreck and sumless treasuries;

for it is probable that a greater number of monuments of the skill and industry of man will, in the course of ages, be collected together in the bed of the ocean, than will exist at any one time on the surface of the continents.

If our species be of as recent a date as is generally supposed, it will be vain to seek for the remains of man and the works of his hands imbedded in submarine strata, except in those regions where violent earthquakes are frequent, and the alterations of relative level so great, that the bed of the sea may have been converted into land within the historical era. We need not despair, however, of the discovery of such monuments, when those regions which have been peopled by man from the earliest ages, and which are at the same time the principal theatres of volcanic action, shall be examined by the joint skill of the antiquary and geologist.

Power of human remains to resist decay.—There can be no doubt that human remains are as capable of resisting decay as are the harder parts of the inferior animals; and I have already cited the remark of Cuvier, that "in ancient fields of battle the bones of men have suffered as little decomposition as those of horses which were buried in the same grave." (See above p. 147.) In the delta of the Ganges bones of men have been found in digging a well at the depth of ninety feet*; but as that river frequently shifts its course and fills up its ancient channels, we are not called upon to suppose that these bodies are of extremely high antiquity, or that they were buried when that part of the surrounding delta where they occur was first gained from the sea.

Fossil skeletons of men.—Several skeletons of men, more or less mutilated, have been found in the West Indies, on the north-west coast of the main land of Guadaloupe, in a kind of rock which is known to be forming daily, and which consists of minute fragments of shells and corals, incrusted with a calcareous cement resembling travertin, by which also the different grains are bound together. The lens shows that some of the fragments of coral composing this stone still retain the same red colour which is seen in the reefs of living coral which surround the island. The shells belong to species of the neighbouring sea intermixed with some terrestrial kinds which now live on the island, and among them is the *Bulimus Guadaloupensis* of Férussac. The human skeletons still retain some of their animal matter, and all their phosphate of lime. One of them, of which the head is wanting, may now be seen in the British Museum, and another in the Royal Cabinet at Paris. According to M. König,

---

* Von Hoff, vol. i. p. 379.

At the mouth of a river in Nova Scotia, a schooner of thirty-two tons, laden with live stock, was lying with her side to the tide, when the bore, or tidal wave, which rises there about ten feet in perpendicular height, rushed into the estuary, and overturned the vessel, so that it instantly disappeared. After the tide had ebbed, the schooner was so totally buried in the sand, that the taffrel or upper rail over the stern was alone visible.* We are informed by Leigh that, on draining Martin Meer, a lake eighteen miles in circumference, in Lancashire, a bed of marl was laid dry, wherein no fewer than eight canoes were found imbedded. In figure and dimensions they were not unlike those now used in America. In a morass about nine miles distant from this Meer a whetstone and an axe of mixed metal were dug up.† In Ayrshire, also, three canoes were found in Loch Doon some few years ago; and during the year 1831 four others, each hewn out of separate oak trees. They were twenty-three feet in length, two and a half in depth, and nearly four feet in breadth at the stern. In the mud which filled one of them was found a war-club of oak and a stone battle-axe. A canoe of oak was also found in 1820, in peat overlying the shell-marl of the Loch of Kinnordy in Forfarshire.‡

Manner in which ships may be preserved in a deep sea. — It is extremely possible that the submerged woodwork of ships which have sunk where the sea is two or three miles deep has undergone greater chemical changes in an equal space of time, than in the cases above mentioned; for the experiments of Scoresby show that wood may at certain depths be impregnated in a single hour with salt water, so that its specific gravity is entirely altered. It may often happen that hot springs charged with carbonate of lime, silex, and other mineral ingredients, may issue at great depths, in which case every pore of the vegetable tissue may be injected with the lapidifying liquid, whether calcareous or siliceous, before the smallest decay commences. The conversion, also, of wood into lignite is probably more rapid under enormous pressure. But the change of the timber into lignite or coal would not prevent the original form of a ship from being distinguished; for as we find, in strata of the carboniferous era, the bark of the hollow reed-like trees converted into coal, and the central cavity filled with sandstone, so might we trace the outline of a ship in coal; while in the indurated mud, sandstone, or limestone, filling the interior, we might discover instruments of human art, ballast consisting of rocks foreign to the rest of the stratum, and other contents of the ship.

Submerged metallic substances. — Many of the metallic substances which fall into the waters probably lose, in the course of ages, the forms artificially imparted to them; but under certain circumstances these may be preserved for indefinite periods. The cannon inclosed in a calcareous rock, drawn up from the delta of the Rhone, which is carbonate of lime. The surface generally, both under the incrustation, and where freed from it, was of a variegated colour, mottled with spots of green, dirty white, and red. On minute inspection with a lens, the green and red patches proved to consist of crystals of the red oxide and carbonate of copper, and the dirty white chiefly of oxide of tin.

---

* Silliman's Geol. Lectures, p. 78., who cites Penn.

† Leigh's Lancashire, p. 17. A. D. 1700.

‡ Geol. Trans., second series, vol. ii. p. 87.

The mineralizing process, says Dr. Davy, which has produced these new combinations, has, in general, penetrated very little into the substance of the helmet. The incrustation and rust removed, the metal is found bright beneath; in some places considerably corroded, in others very slightly. It proves, on analysis, to be copper, alloyed with 18·5 per cent. of tin. Its colour is that of our common brass, and it possesses a considerable degree of flexibility.

"It is a curious question," he adds, "how the crystals were formed in the helmet, and on the adhering calcareous deposit. There being no reason to suppose deposition from solution, are we not under the necessity of inferring, that the mineralizing process depends on a small motion and separation of the particles of the original compound? This motion may have been due to the operation of electro-chemical powers which may have separated the different metals of the alloy.*

Effects of the Subsidence of Land, in imbedding Cities and Forests in subaqueous Strata.

We have hitherto considered the transportation of plants and animals from the land by *aqueous* agents, and their inhumation in lacustrine or submarine deposits, and we may now inquire what tendency the subsidence of tracts of land may have to produce analogous effects. Several examples of the sinking down of buildings, and portions of towns near the shore, to various depths beneath the level of the sea during subterranean movements, were before enumerated in treating of the changes brought about by *inorganic* causes. The events alluded to were comprised within a brief portion of the historical period, and confined to a small number of the regions of active volcanos. Yet these authentic facts, relating merely to the last century and a half, gave indications of considerable changes in the physical geography of the globe, and we are not to suppose that these were the only spots throughout the surrounding land and sea which suffered similar depressions.

If, during the short period since South America has been colonized by Europeans, we have proof of alterations of level at the three principal ports on the western shores, Callao, Valparaiso, and Conception †, we cannot for a moment suspect that these cities, so distant from each other, have been selected as the peculiar points where the desolating power of the earthquake has expended its chief fury. On considering how small is the area occupied by the seaports of to view. They contain freshwater shells, of the genera Lymneus, Paludina, and Cyrena, with land shells, all of recent species, and are precisely such deposits as would be formed if the whole valley were now converted into a great lake, and if the numerous rivers and torrents descending from the surrounding mountains were allowed sufficient time to fill up the lake-basin with fine sediment and gravel. Fragments of pottery met with at the depth of 40 and 50 feet in this lacustrine formation show that the upper part of it at least has accumulated within the human epoch.

---

* Phil. Trans., 1826, part. ii. p. 55.

† See above, pp. 453. 457. 499. 501.

Dr. Thomas Thomson, who visited Cashmere in 1848, observes that several of the lakes which still exist in the great valley, such as that near the town of Cashmere, five miles in diameter, and some others, are deeper than the adjoining river-channels, and may have been formed by subsidence during the numerous earthquakes which have convulsed that region in the course of the last 2000 years. It is also probable that the freshwater strata seen to extend far and wide over the whole of Cashmere originated not in one continuous sheet of water once occupying the entire valley, but in many lakes of limited area, formed and filled in succession. Among other proofs of such lake-basins of moderate dimensions having once existed and having been converted into land at different periods Dr. Thomson mentions that the ruins of Avantipura, not far from the modern village of that name, stand on an older freshwater deposit at the base of the mountains, and terminate abruptly towards the plain in a straight line, such as admits of no other explanation than by supposing that the advance of the town in that direction was arrested by a lake, now drained or represented only by a marsh. In that neighbourhood, as very generally throughout Cashmere, the rivers run in channels or alluvial flats, bounded by cliffs of lacustrine strata, horizontally stratified, and these strata form low table-lands from 20 to 50 feet high between the different watercourses. On a table-land of this kind near Avantipura, portions of two buried temples are seen, which have been partially explored by Major Cunningham, who, in 1847, discovered that in one of the buildings a magnificent colonnade of seventy-four pillars is preserved underground. He exposed to view three of the pillars in a cavity still open. All the architectural decorations below the level of the soil are as perfect and fresh-looking as when first executed. The spacious quadrangle must have been silted up gradually at first, for some unsightly alterations, not in accordance with the general plan and style of architecture, were detected, evidently of subsequent date, and such as could only have been required when the water and sediment had already gained a certain height in the interior of the temple.

This edifice is supposed to have been erected about the year 850 of our era, and was certainly submerged before the year 1416, when the Mahomedan king, Sikandar, called Butshikan or the idol-breaker, destroyed all the images of Hindoo temples in Cashmere. Ferishta the historian particularly alludes to Sikandar having demolished every Cashmerian temple save one, dedicated to Mahadéva, which escaped "in consequence of its foundations being below the neighbouring aqueous, to remodel more than once the entire crust of the earth. *One* complete revolution will be inadequate to efface every monument of our existence; for many works of art might enter again and again into the formations of successive eras, and escape obliteration even though the very rocks in which they had been for ages imbedded were destroyed, just as pebbles included in the conglomerates of one epoch often contain the organized remains of beings which flourished during a prior era.

Yet it is no less true, as a late distinguished philosopher has declared, "that none of the works of a mortal being can be eternal."* They are in the first place wrested from the hands of man, and lost as far as regards their subserviency to his use, by the instrumentality of those very causes which place them in situations where they are enabled to endure for indefinite periods. And even when they have been included in rocky strata, when they have been made to enter as it were into the solid framework of the globe itself, they must nevertheless eventually perish; for every year some portion of the earth's crust is shattered by earthquakes, or melted by volcanic fire, or ground to dust by the moving waters on the surface. "The river of Lethe," as Bacon eloquently remarks, runneth as well above ground as below."†

CHAPTER XLIX.

IMBEDDING OF AQUATIC SPECIES IN SUBAQUEOUS STRATA.

Inhumation of freshwater plants and animals—Shell marl—Fossilized seed-vessels and stems of chara—Recent deposits in American lakes—Freshwater species drifted into seas and estuaries—Lewes levels—Alternations of marine and freshwater strata, how caused—Imbedding of marine plants and animals—Cetacea stranded on our shores—Littoral and estuary Testacea swept into the deep sea—Burrowing shells—Living Testacea found at considerable depths—Blending of organic remains of different ages.

Having treated of the imbedding of terrestrial plants and animals, and of human remains, in deposits now forming beneath the waters, I come next to consider in what manner *aquatic* species may be entombed in strata formed in their own element.

Freshwater plants and animals.—The remains of species belonging to those genera of the animal and vegetable kingdoms which are more or less exclusively confined to fresh water are for the most part preserved in the beds of lakes or estuaries, but they are oftentimes swept down by rivers into the sea, and there intermingled with the exuviæ of marine races. The phenomena attending their composed of five spiral valves, of a quadrangular form (*g*). In *Chara hispida*, which abounds in the lakes of Forfarshire, and which has become fossil in the Bakie Loch, each of the spiral valves of the seed-vessel turns rather more than twice round the circumference, the whole together making between ten and eleven rings. The number of these rings differs greatly in different species, but in the same appears to be very constant.

---

* Davy, Consolations in Travel, p. 276.

† Essay on the Vicissitude of Things.

The stems of Charæ occur fossil in the Scotch marl in great abundance. In some species, as in *Chara hispida*, the plant when living contains so much carbonate of lime in its vegetable organization, independently of calcareous incrustation, that it effervesces strongly with acids when dry. The stems of *Chara hispida* are longitudinally striated, with a tendency to be spiral. These striæ, as appears to be the case with all Charæ, turn always like the worm of a screw from right to left, while those of the seed-vessel wind round in a contrary direction. A cross section of the stem exhibits a curious structure, for it is composed of a large tube surrounded by smaller tubes (fig. 103., *b*, *c*) as is seen in some extinct as well as recent species. In the stems of several species, however, there is only a single tube.*

Fig. 103.



Stem and branches of Chara hispida.

a, Stem and branches of the natural size.
b, Section of the stem magnified.
c, Showing the central tube surrounded by two rings of smaller tubes.

The valves of a small animal called cypris (*C. ornata?* Lam.) occur completely fossilized, like the stems of Charæ, in the Scotch travertin above mentioned. The same cypris inhabits the lakes and ponds of England, where, together with many other species, it is not uncommon. Although extremely minute, they are visible to the naked the vegetable soil, is a bed of peat about five feet thick, inclosing many trunks of trees. Next below is a stratum of blue clay containing freshwater shells of about nine species, such as now inhabit the district. Intermixed with these was observed the skeleton of a deer. Lower down, the layers of blue clay contain, with the above-mentioned freshwater shells, several marine species well known on our coast. In the lowest beds, often at the depth of thirty-six feet, these marine Testacea occur without the slightest intermixture of fluviatile species, and amongst them the skull of the narwal, or sea unicorn (*Monodon monoceros*), has been detected. Underneath all these deposits is a bed of pipe-clay, derived from the subjacent chalk.*

---

* On Freshwater Marl, &c. By C. Lyell. Geol. Trans., vol. ii., second series, p. 73.

If we had no historical information respecting the former existence of an inlet of the sea in this valley and of its gradual obliteration, the inspection of the section above described would show, as clearly as a written chronicle, the following sequence of events. First, there was a salt-water estuary peopled for many years by species of marine Testacea identical with those now living, and into which some of the larger Cetacea occasionally entered. Secondly, the inlet grew shallower, and the water became brackish, or alternately salt and fresh, so that the remains of freshwater and marine shells were mingled in the blue argillaceous sediment of its bottom. Thirdly the shoaling continued until the river-water prevailed, so that it was no longer habitable by marine Testacea, but fitted only for the abode of fluviatile species and aquatic insects. Fourthly, a peaty swamp or morass was formed, where some trees grew, or perhaps were drifted during floods, and where terrestrial quadrupeds were mired. Finally, the soil being flooded by the river only at distant intervals, became a verdant meadow.

In delta of Ganges and Indus. — It was before stated, that on the sea-coast, in the delta of the Ganges, there are eight great openings, each of which has evidently, at some ancient period, served in its turn as the principal channel of discharge.† As the base of the delta is 200 miles in length, it must happen that, as often as the great volume of river-water is thrown into the sea by a new mouth, the sea will at one point be converted from salt to fresh, and at another from fresh to salt; for, with the exception of those parts where the principal discharge takes place, the salt water not only washes the base of the delta, but enters far into every creek and lagoon. It is evident, then, that repeated alternations of beds containing freshwater shells, with others filled with marine exuviæ, may here be formed. It has also been shown by artesian borings at Calcutta (see above, p. 267.), that the delta once extended much farther than now into the gulf, and that the river is only recovering from the sea the ground which had been lost by subsidence at some former period. Analogous phenomena must sometimes be occasioned by such alternate elevation and depression as has occurred in modern narwal (*Monodon monoceros*) was found on the beach near Boston in Lincolnshire, in the year 1800, the whole of its body buried in the mud. A fisherman going to his boat saw the horn, and tried to pull it out, when the animal began to stir itself.[*] An individual of the common whale (*Balæna mysticetus*), which measured seventy feet, came ashore near Peterhead, in 1682. Many individuals of the genus Balænoptera have met the same fate. It will be sufficient to refer to those cast on shore near Burnt Island, and at Alloa, recorded by Sibbald and Neill. The other individual mentioned by Sibbald, as having come ashore at Boyne, in Banffshire, was probably a razor-back. Of the genus Catodon (*Cachalot*), Ray mentions a large one stranded on the west coast of Holland in 1598, and the fact is also commemorated in a Dutch engraving of the time of much merit. Sibbald, too, records that a herd of Cachalots, upwards of 100 in number, were found stranded at Cairston, in Orkney. The dead bodies of the larger Cetacea are sometimes found floating on the surface of the waters, as was the case with the immense whale exhibited in London in 1831. And the carcase of a sea-cow or Lamantine (*Halicora*) was, in 1785, cast ashore near Leith.

---

* Mantell, Geol. of Sussex, p. 285.; Trans., vol. iii. part i. p. 201., 2nd series. also Catalogue of Org. Rem., Geol.

† Page 276.

To some accident of this kind we may refer the position of the skeleton of a whale, seventy-three feet long, which was found at Airthrey, on the Forth, near Stirling, imbedded in clay twenty feet higher than the surface of the highest tide of the river Forth at the present day. From the situation of the Roman station and causeways at a small distance from the spot, it is concluded that the whale must have been stranded there at a period prior to the Christian era.[†]

Other fossil remains of this class have also been found in estuaries, known to have been silted up in recent times, one example of which has been already mentioned near Lewes, in Sussex.

Marine reptiles. — Some singular fossils have lately been discovered in the Island of Ascension in a stone said to be continually forming on the beach, where the waves throw up small rounded fragments of shells and corals, which, in the course of time, become firmly agglutinated together, and constitute a stone used largely for building and making lime. In a quarry on the N. W. side of the island, about 100 yards from the sea, some fossil eggs of turtles have been discovered in the hard rock thus formed. The eggs must have been nearly hatched at the time when they perished; for the bones of the young turtle are seen in the interior, with their shape fully developed, the interstices

Fig. 106.



Fossil eggs of turtles from the Island of Ascension.[‡]

---

[*] Fleming's Brit. Animals, p. 37.; in which work other cases are enumerated.

[†] Quart. Journ. of Lit. Sci., &c., No. xv. p. 172. Oct. 1819.

[‡] This specimen has been presented by Mr. Lonsdale to the Geological Society of London.

and sometimes brackish water, which may have been accumulating for centuries, until at length they are carried away and spread out along the bottom of the sea, at a depth at which they could not have lived and multiplied. Thus littoral and estuary shells are more frequently liable even than freshwater species, to be intermixed with the exuviæ of pelagic tribes.

After the storm of February 4. 1831, when several vessels were wrecked in the estuary of the Forth, the current was directed against a bed of oysters with such force, that great heaps of them were thrown *alive* upon the beach, and remained above high-water mark. I collected many of these oysters, as also the common eatable whelks (*Buccina*), thrown up with them, and observed that, although still living, their shells were worn by the long attrition of sand which had passed over them as they lay in their native bed, and which had evidently not resulted from the mere action of the tempest by which they were cast ashore.

From these facts we learn that the union of the two parts of a bivalve shell does not prove that it has not been transported to a distance; and when we find shells worn, and with all their prominent parts rubbed off, they may still have been imbedded where they grew.

Burrowing shells.—It sometimes appears extraordinary, when we bserve the violence of the breakers on our coast, and see the strength f the current in removing cliffs, and sweeping out new channels, hat many tender and fragile shells should inhabit the sea in the immediate vicinity of this turmoil. But a great number of the bivalve Testacea, and many also of the turbinated univalves, burrow in sand r mud. The Solen and the Cardium, for example, which are usually ound in shallow water near the shore, pierce through a soft bottom without injury to their shells; and the Pholas can drill a cavity hrough mud of considerable hardness. The species of these and many other tribes can sink, when alarmed, with considerable rapidity, ften to the depth of several feet, and can also penetrate upwards gain to the surface, if a mass of matter be heaped upon them. The urricane, therefore, may expend its fury in vain, and may sweep way even the upper part of banks of sand or mud, or may roll ebbles over them, and yet these Testacea may remain below secure nd uninjured.

Shells become fossil at considerable depths.—I have already stated hat, at the depth of 950 fathoms, between Gibraltar and Ceuta, Captain Smith found a gravelly bottom, with fragments of broken hells, carried thither probably from the comparatively shallow parts f the neighbouring straits, through which a powerful current flows. Beds of shelly sand might here, in the course of ages, be accumulated everal thousand feet thick. But, without the aid of the drifting ower of a current, shells may accumulate in the spot where they ive and die, at great depths from the surface, if sediment be thrown down upon them; for even in our own colder latitudes, the depths at which living marine animals abound is very considerable. Captain supplied by rivers draining a continent, or currents preying on a line of cliffs, in order that stratified formations, hundreds of feet in thickness, and replete with organic remains, should result in the course of ages.

But although some deposits may thus extend continuously for a thousand miles or more near certain coasts, the greater part of the bed of the ocean, remote from continents and islands, may very probably receive, at the same time, no new accessions of drift matter, all sediment being intercepted by intervening hollows, in which a marine current must clear its waters as thoroughly as a turbid river in a lake. Erroneous theories in geology may be formed not only from overlooking the great extent of simultaneous deposits now in progress, but also from the assumption that such formations may be universal or coextensive with the bed of the ocean.

We frequently observe, on the sea beach, very perfect specimens of fossil shells, quite detached from their matrix, which have been washed out of older formations, constituting the sea-cliffs. They may be all of extinct species, like the Eocene freshwater and marine shells strewed over the shores of Hampshire, yet when they become mingled with the shells of the present period, and buried in the same deposits of mud and sand, they would appear, if upraised and examined by future geologists, to have been all of the same age. That such intermixture and blending of organic remains of different ages have actually taken place in former times, is unquestionable, though the occurrence appears to be very local and exceptional. It is, however, a class of accidents more likely than almost any other to lead to serious anachronisms in geological chronology.

CHAPTER L.

FORMATION OF CORAL REEFS.

Growth of coral chiefly confined to tropical regions — Principal genera of coral-building zoophytes — Their rate of growth — Seldom flourish at greater depths than twenty fathoms — Atolls or annular reefs with lagoons — Maldive Isles — Origin of the circular form — Coral reefs not based on submerged volcanic craters — Mr. Darwin's theory of subsidence in explanation of atolls, encircling and barrier reefs — Why the windward side of atolls highest — Subsidence explains why all atolls are nearly on one level — Alternate areas of elevation and subsidence — Origin of openings into the lagoons — Size of atolls and barrier reefs — Objection to the theory of subsidence considered — Composition, structure, and stratified arrangement of rocks now forming in coral reefs — Lime whence derived — Supposed increase of calcareous matter in modern epochs controverted — Concluding remarks.

THE powers of the organic creation in modifying the form and structure of the earth's crust, are most conspicuously displayed in the labours of the coral animals. We may compare the operation of these zoophytes in the ocean, to the effects produced on a smaller

Genera of Zoophytes most common in coral reefs.

Fig. 109.



Astrea dipsacea, Lam.

Fig. 110.



Extremity of branch of *Madrepora muricata*, Lin.

Fig. 111.



Caryophyllia fastigiata, Lam.

Fig. 112.



Porites clavaria, Lam.

Fig. 113.



Oculina hirtella, Lam.

Ehrenberg also questions the fact of channels and harbours having been closed up in the Red Sea by the rapid increase of coral limestone. He supposes the notion to have arisen from the circumstance of havens having been occasionally filled up in some places with coral sand, in others with large quantities of ballast of coral rock thrown down from vessels.

reefs are exclusively the work of zoophytes: a great variety of shells, and, among them, some of the largest and heaviest of known species, contribute to augment the mass. In the South Pacific, great beds of oysters, mussels, *Pinnæ marinæ*, *Chamæ* (or *Tridacnæ*), and other shells, cover in profusion almost every reef; and on the beach of çoral islands are seen the shells of echini and broken fragments of crustaceous animals. Large shoals of fish are also discernible through the clear blue water, and their teeth and hard palates cannot fail to be often preserved although their soft cartilaginous bones may decay.

It was the opinion of the German naturalist Forster, in 1780, after his voyage round the world with Captain Cook, that coral animals had the power of building up steep and almost perpendicular walls from great depths in the sea, a notion afterwards adopted by Captain Flinders and others; but it is now very generally believed that these zoophytes cannot live in water of great depths.

Mr. Darwin has come to the conclusion, that those species which are most effective in the construction of reefs, rarely flourish at a greater depth than 20 fathoms, or 120 feet. In some lagoons, however, where the water is but little agitated, there are, according to Kotzebue, beds of living coral in 25 fathoms water, or 150 feet; but these may perhaps have begun to live in shallower water, and may have been carried downwards by the subsidence of the reef. There are also various species of zoophytes, and among them some which are provided with calcareous as well as horny stems, which live in much deeper water, even in some cases to a depth of 180 fathoms; but these do not appear to give origin to stony reefs.

There is every variety of form in coral reefs, but the most remarkable and numerous in the Pacific consist of circular or oval strips of dry land, enclosing a shallow lake or lagoon of still water, in which zoophytes and mollusca abound. These annular reefs just raise themselves above the level of the sea, and are surrounded by a deep and often unfathomable ocean.

In the annexed cut (fig. 114.), one of these circular islands is

Fig. 114.



View of Whitsunday Island. (Capt. Beechey.) *

---

* Voyage to the Pacific, &c. in 1825–28.

and unite them into a symmetrical structure; myriads of architects are at work night and day, month after month, and we see their soft and gelatinous bodies through the agency of the vital laws conquering the great mechanical power of the waves of an ocean, which neither the art of man, nor the inanimate works of nature could successfully resist."*

As the coral animals require to be continually immersed in salt water, they cannot raise themselves by their own efforts above the level of the lowest tides. The manner in which the reefs are converted into islands above the level of the sea is thus described by Chamisso, a naturalist who accompanied Kotzebue in his voyages:— "When the reef," says he, "is of such a height that it remains almost dry at low water the corals leave off building. Above this line a continuous mass of solid stone is seen composed of the shells of mollusks and echini, with their broken-off prickles and fragments of coral, united by calcareous sand, produced by the pulverization of shells. The heat of the sun often penetrates the mass of stone when it is dry, so that it splits in many places, and the force of the waves is thereby enabled to separate and lift blocks of coral, frequently six feet long and three or four in thickness, and throw them upon the reef, by which means the ridge becomes at length so high that it is covered only during some seasons of the year by the spring tides. After this the calcareous sand lies undisturbed, and offers to the seeds of trees and plants cast upon it by the waves a soil upon which they rapidly grow, to overshadow its dazzling white surface. Entire trunks of trees, which are carried by the rivers from other countries and islands, find here, at length, a resting-place after their long wanderings: with these come some small animals, such as insects and lizards, as the first inhabitants. Even before the trees form a wood, the sea-birds nestle here; stray land-birds take refuge in the bushes; and, at a much later period, when the work has been long since completed, man appears and builds his hut on the fruitful soil."†

In the above description the solid stone is stated to consist of shell and coral, united by sand; but masses of very compact limestone are also found even in the uppermost and newest parts of the reef, such as could only have been produced by chemical precipitation. Professor Agassiz also informs me that his observations on the Florida reefs (which confirm Darwin's theory of atolls to be mentioned in the sequel) have convinced him, that large blocks are loosened, not by shrinkage in the sun's heat, as Chamisso imagined, but by innumerable perforations of lithodomi and other boring testacea.

The carbonate of lime may have been principally derived from the decomposition of corals and testacea; for when the animal matter undergoes putrefaction, the calcareous residuum must be set free under circumstances very favourable to precipitation, especially when there are other calcareous substances, such as shells and corals, on which it times more than a hundred in number, each of which is a miniature atoll in itself; in other words, a ring-shaped strip of coral surrounding a lagoon of salt water. To account for the origin of these, Mr. Darwin supposes the larger annular reef to have been broken up into a number of fragments, each of which acquired its peculiar configurations under the influence of causes similar to those to which the structure of the parent atoll has been due. Many of the minor rings are no less than three, and even five miles in diameter, and some are situated in the midst of the principal lagoon; but this happens only in cases where the sea can enter freely through breaches in the outer or marginal reef.

---

* Darwin's Journal, &c., pp. 547, 548., and 2d edit., of 1845, p. 460.

† Kotzebue's Voy., 1815–18, vol. iii. pp. 331—333.

The rocks of the Maldives are composed of sandstone formed of broken shells and corals, such as may be obtained in a loose state from the beach, and which is seen when exposed for a few days to the air to become hardened. The sandstone is sometimes observed to be an aggregate of broken shells, corals, pieces of wood, and shells of the cocoa-nut.*

The Laccadive islands run in the same line with the Maldives, on the north, as do the isles of the Chagos Archipelago, on the south; so that these may be continuations of the same chain of submerged mountains, crested in a similar manner by coral limestones.

Origin of the circular form — not volcanic.— The circular and oval shape of so many reefs, each having a lagoon in the centre, and being surrounded on all sides by a deep ocean, naturally suggested the idea that they were nothing more than the crests of submarine volcanic craters overgrown by coral; and this theory I myself advocated in the earlier editions of this work. Although I am now about to show that it must be abandoned, it may still be instructive to point out the grounds on which it was formerly embraced. In the first place, it had been remarked that there were many active volcanos in the coral region of the Pacific, and that in some places, as in Gambier's group, rocks composed of porous lava rise up in a lagoon bordered by a circular reef, just as the two cones of eruption called the Kamenis have made their appearance in the times of history within the circular gulf of Santorin.† It was also observed that as in S. Shetland, Barren Island, and others of volcanic origin, there is one narrow breach in the walls of the outer cone by which ships may enter a circular gulf, so in like manner there is often a single deep passage leading into the lagoon of a coral island, the lagoon itself seeming to represent the hollow or gulf just as the ring of dry coral recals to our minds the rim of a volcanic crater. More lately, indeed, Mr. Darwin has shown that the numerous volcanic craters of the Galapagos Archipelago in the Pacific have all of them their southern sides the lowest, or in many cases quite broken down, so that if they were submerged and incrusted with coral, they would resemble true atolls in shape.‡

---

* Captain Moresby on the Maldives, Journ. Roy. Geograph. Soc., vol. v. part ii. p. 400.

† See above, p. 442.

‡ Darwin, Volcanic Islands, p. 113.

Another argument which I adduced when formerly defending this doctrine was derived from Ehrenberg's statement, that some banks of coral in the Red Sea were square, while many others were ribbon-like strips, with flat tops, and without lagoons. Since, therefore, all the genera and many of the species of zoophytes in the Red Sea agreed with those which elsewhere construct lagoon islands, it followed that the stone-making zoophytes are not guided by their own instinct in the formation of annular reefs, but that this peculiar shape and the position of such reefs in the midst of a deep ocean must depend on the outline of the submarine bottom, which resembles nothing else in nature but the crater of a lofty submerged volcanic cone. The enormous size, it is true, of some atolls made it necessary for me to ascribe to the craters of many submarine volcanos a magnitude which was startling, and which had often been appealed to as a serious objection to the volcanic theory. That so many of them were of the same height, or just level with the water, did not present a difficulty so long as we remained ignorant of the fact that the reef-building species do not grow at greater depths than twenty-five fathoms.

May be explained by subsidence. — Mr. Darwin, after examining a variety of coral formations in different parts of the globe, was induced to reject the opinion that their shape represented the form of the original bottom. Instead of admitting that the ring of dead coral rested on a circular or oval ridge of rock, or that the lagoon corresponded to a pre-existing cavity, he advanced a new opinion, which must, at first sight, seem paradoxical in the extreme; namely, that the lagoon is precisely in the place once occupied by the highest part of a mountainous island, or, in other cases, by the top of a shoal.

The following is a brief sketch of the facts and arguments in favour of this new view: — Besides those rings of dry coral which inclose lagoons, there are others having a similar form and structure which encircle lofty islands. Of the latter kind is Vanikoro, (see map, fig. 39., p. 351.), celebrated on account of the shipwreck of La Peyrouse, where the coral reef runs at the distance of two or three miles from the shore, the channel between it and the land having a general depth of between 200 and 300 feet. This channel, therefore, is analogous to a lagoon, but with an island standing in the middle like a picture in its frame. In like manner in Tahiti we see a mountainous land, with every where round its margin a lake or zone of smooth salt water, separated from the ocean by an encircling reef of coral, on which a line of breakers is always foaming. So also New Caledonia, a long narrow island east of New Holland, in which the rocks are granitic, is surrounded by a reef which runs for a length of 400 miles. This reef encompasses not only the island itself, but a ridge of rocks which are prolonged in the same direction beneath the sea. No one, therefore, will contend for a moment that in this case the corals are based upon the rim of a volcanic crater, in the middle of which stands a mountain or island of granite.

The great barrier reef, already mentioned as running parallel to the north-east coast of Australia for nearly 1000 miles, is another most remarkable example of a long strip of coral running parallel to a coast. Its distance from the mainland varies from twenty to seventy miles, and the depth of the great arm of the sea thus inclosed is usually between ten and twenty fathoms, but towards one end from forty to sixty. This great reef would extend much farther, according to Mr. Jukes, if the growth of coral were not prevented off the shores of New Guinea by a muddy bottom, caused by rivers charged with sediment which flow from the southern coast of that great island.*

Two classes of reefs, therefore, have now been considered; first, the atoll, and, secondly, the encircling and barrier reef, all agreeing perfectly in structure, and the sole difference lying in the absence in the case of the atoll of all land, and in the others the presence of land bounded either by an encircling or a barrier reef. But there is still a third class of reefs, called by Mr. Darwin "fringing reefs," which approach much nearer the land than those of the encircling and barrier class, and which indeed so nearly touched the coast as to leave nothing in the intervening space resembling a lagoon. "That these reefs are not attached quite close to the shore appears to be the result of two causes; first, that the water immediately adjoining the beach is rendered turbid by the surf, and therefore injurious to all zoophytes; and, secondly, that the larger and efficient kinds only flourish on the outer edge amidst the breakers of the open sea."†

It will at once be conceded that there is so much analogy between the form and position of the strip of coral in the atoll, and in the encircling and barrier reef, that no explanation can be satisfactory which does not include the whole. If we turn in the first place to the encircling and barrier reefs, and endeavour to explain how the zoophytes could have found a bottom on which to begin to build, we are met at once with a great difficulty. It is a general fact, long since remarked by Dampier, that high land and deep seas go together. In other words, steep mountains coming down abruptly to the sea-shore are generally continued with the same slope beneath the water. But where the reef, as at *b* and *c* (fig. 118.), is distant several miles from a steep coast, a line drawn perpendicularly downwards from its outer edges *b c* to the fundamental rock *d e*, must descend to a depth

Fig. 118.



Supposed section of an island with an encircling reef of coral.

A, The island.
b, *c*, Highest points of the encircling reef between which and the coast is seen a space occupied by still water.

---

[*] Quart. Journ. Geol. Soc. 4. xciii.

[†] Darwin's Journal, p. 557. 2d edit. chap. 20, and Coral Islands, chapters 1, 2, 3.

and the longer the subsidence continues the farther will the coast of the mainland recede.

When the first edition of this work appeared in 1831, several years before Mr. Darwin had investigated the facts on which his theory is founded, I had come to the opinion that the land was subsiding at the bottom of those parts of the Pacific where atolls are numerous, although I failed to perceive that such a subsidence, if conceded, would equally solve the enigma as to the form both of annular and barrier reefs.

I shall cite the passage referred to, as published by me in 1831: — "It is a remarkable circumstance that there should be so vast an area in Eastern Oceanica, studded with minute islands, without one single spot where there is a wider extent of land than belongs to such islands as Otaheite, Owhyhee, and a few others, which either have been or are still the seats of active volcanos. If an equilibrium only were maintained between the upheaving and depressing force of earthquakes, large islands would very soon be formed in the Pacific; for, in that case, the growth of limestone, the flowing of lava, and the ejection of volcanic ashes, would combine with the upheaving force to form new land.

"Suppose a shoal, 600 miles in length, to sink fifteen feet, and then to remain unmoved for a thousand years; during that interval the growing coral may again approach the surface. Then let the mass be re-elevated fifteen feet, so that the original reef is restored to its former position: in this case, the new coral formed since the first subsidence will constitute an island 600 miles long. An analogous result would have occurred if a lava-current fifteen feet thick had overflowed the submerged reef. The absence, therefore, of more extensive tracts of land in the Pacific, seems to show that the amount of subsidence by earthquakes exceeds, in that quarter of the globe, at present, the elevation due to the same cause."[*]

Another proof also of subsidence derived from the structure of atolls, was pointed out by me in the following passage in all former editions. "The low coral islands of the Pacific," says Captain Beechey, "follow one general rule in having their windward side higher and more perfect than the other. At Gambier and Matilda islands this inequality is very conspicuous, the weather side of both being wooded, and of the former inhabited, while the other sides are from twenty to thirty feet under water; where, however, they may be perceived to be equally *narrow* and well defined. It is on the leeward side also that the entrances into the lagoons occur; and although they may sometimes be situated on a side that runs in the direction of the wind, as at Bow Island, yet there are none to windward." These observations of Captain Beechey accord with those which Captain Horsburgh and other hydrographers have made in regard to the coral islands of other seas. From this fortunate circumstance ships can enter and sail out with ease; whereas if the narrow inlets were to windward, vessels which once entered and is five miles in length by one in breadth. It has a flat surface, and, on all sides, except the north, is bounded by perpendicular cliffs about fifty feet high, composed entirely of dead coral, more or less porous, honey-combed at the surface, and hardening into a compact calcareous mass, which possesses the fracture of secondary limestone, and has a species of millepore interspersed through it. These cliffs are considerably undermined by the action of the waves, and some of them appear on the eve of precipitating their superincumbent weight into the sea. Those which are less injured in this way present no alternate ridges or indication of the different levels which the sea might have occupied at different periods; but a smooth surface, as if the island, which has probably been raised by volcanic agency, had been forced up by one great subterraneous convulsion.* At the distance of a few hundred yards from this island, no bottom could be gained with 200 fathoms of line.

---

[*] See Principles of Geology, 1st edit., vol. ii. p. 296.

Fig. 120.



Elizabeth, or Henderson's Island.

It will be seen, from the annexed sketch, communicated to me by Lieutenant Smith, of the Blossom, that the trees came down to the beach towards the centre of the island; a break at first sight resembling the openings which usually lead into lagoons; but the trees stand on a steep slope, and no hollow of an ancient lagoon was perceived.

Beechey also remarks, that the surface of Henderson's Island is flat, and that in Queen Charlotte's Island, one of the same group, but under water, there was no lagoon, the coral having grown up every where to one level. The probable cause of this obliteration of the central basin or lagoon will be considered in the sequel.

That the bed of the Pacific and Indian oceans, where atolls are frequent, must have been sinking for ages, might be inferred, says Mr. Darwin, from simply reflecting on two facts; first, that the efficient coral-building zoophytes do not flourish in the ocean at a greater depth than 120 feet; and, secondly, that there are spaces occupying areas of many hundred thousand square miles, where all the islands consist of coral, and yet none of which rise to a greater height than may be accounted for by the action of the winds and waves on broken and triturated coral. Were we to take for granted that the floor of the ocean had remained stationary from the time when the coral began to grow, we should be compelled to assume that an incredible number of submarine mountains of vast height (for the ocean is always deep, and often unfathomable between the different atolls), had all come to within 120 feet of the surface, and yet no one mountain had risen above water. But no sooner do we admit the theory of subsidence, than this great difficulty vanishes. However atolls, it was stated that some of the smallest observed by Beechey in the Pacific were only a mile in diameter. If their external slope under water equals upon an average an angle of 45°, then would such an atoll at the depth of half a mile, or 2640 feet, have a diameter of two miles. Hence it would appear that there must be a tendency in every atoll to grow smaller, except in those cases where oscillations of level enlarge the base on which the coral grows by throwing down a talus of detrital matter all round the original cone of limestone.

---

* Beechey's Voyage to the Pacific, &c., p. 46.

Bow Island is described by Captain Beechey as seventy miles in circumference, and thirty in its greatest diameter, but we have seen that some of the Maldives are much larger.

As the shore of an island or continent which is subsiding will recede from a coral reef at a slow or rapid rate according as the surface of the land has a steep or gentle slope, we cannot measure the thickness of the coral by its distance from the coast; yet, as a general rule, those reefs which are farthest from the land imply the greatest amount of subsidence. We learn from Flinders, that the barrier reef of north-eastern Australia is in some places seventy miles from the mainland, and it should seem that a calcareous formation is there in progress 1000 miles long from north to south, with a breadth varying from twenty to seventy miles. It may not, indeed, be continuous over this vast area, for doubtless innumerable islands have been submerged one after another between the reef and mainland, like some which still remain, as, for example, Murray's Islands, lat. 9° 54′ S. We are also told that some parts of the gulf inclosed within the barrier are 400 feet deep, so that the efficient rock-building corals cannot be growing there, and in other parts of it islands appear encircled by reefs.

It will follow as one of the consequences of the theory already explained that, provided the bottom of the sea does not sink too fast to allow the zoophytes to build upwards at the same pace, the thickness of coral will be great in proportion to the rapidity of subsidence, so that if one area sinks two feet while another sinks one, the mass of coral in the first area will be double that in the second. But the downward movement must in general have been very slow and uniform, or where intermittent, must have consisted of a great number of depressions, each of slight amount, otherwise the bottom of the sea would have been carried down faster than the corals could build upwards, [illegible] the island or continent would be permanently submerged, having reached a depth of 120 or 150 feet, at which the effective reef-constructing zoophytes cease to live. If, then, the subsidence required to account for all the existing atolls must have amounted to three or four thousand feet, or even sometimes more, we are brought to the conclusion that there has been a *slow* and *gradual* sinking to this enormous extent. Such an inference is perfectly in harmony with views which the grand scale of denudation, everywhere observable in the older rocks, has led geologists to adopt in reference to upward movements. They must also have been gradual and continuous throughout indefinite ages to allow the waves and currents of the ocean to operate with adequate power.

The map constructed by Mr. Darwin to display at one view the geographical position of all the coral reefs throughout the globe is of the highest geological interest (see above, p. 351.), leading to splendid generalizations, when we have once embraced the theory that all atolls and barrier reefs indicate recent subsidence, while the presence of fringing reefs proves the land to be stationary or rising. These two classes of coral formations are depicted by different colours; and one of the striking facts brought to light by the same classification of coral formations is the absence of active volcanos in the areas of subsidence, and their frequent presence in the areas of elevation. The only supposed exception to this remarkable coincidence at the time when Mr. Darwin wrote, in 1842, was the volcano of Torres Strait, at the northern point of Australia, placed on the borders of an area of subsidence; but it has been since proved that this volcano has no existence.

We see, therefore, an evident connection, first, between the bursting forth every now and then of volcanic matter through rents and fissures, and the expansion or forcing outwards of the earth's crust, and, secondly, between a dormant and less energetic development of subterranean heat, and an amount of subsidence sufficiently great to cause mountains to disappear over the broad face of the ocean, leaving only small and scattered lagoon islands, or groups of atolls, to indicate the spots where those mountains once stood.

On a review of the differently-coloured reefs on the map alluded to, it will be seen that there are large spaces in which upheaval, and others in which depression prevails, and these are placed alternately, while there are a few smaller areas where movements of oscillation occur. Thus if we commence with the western shores of South America, between the summit of the Andes and the Pacific (a region of earthquakes and active volcanos), we find signs of recent elevation, not attested indeed by coral formations, which are wanting there, but by upraised banks of marine shells. Then proceeding westward, we traverse a deep ocean without islands, until we come to a band of *atolls* and encircled islands, including the Dangerous and Society archipelagos, and constituting an area of subsidence more than 4000 miles long and 600 broad. Still farther, in the same direction, we reach the chain of islands to which the New Hebrides, Salomon, and New Ireland belong, where fringing reefs and masses of elevated coral indicate another area of upheaval. Again, to the westward of the New Hebrides we meet with the encircling reef of New Caledonia and the great Australian barrier, implying a second area of subsidence.

The only objection deserving attention which has hitherto been advanced against the theory of atolls, as before explained (p. 759.), is that proposed by Mr. Maclaren.* "On the outside," he observes,

---

* Scotsman, Nov. 1842, and Jameson's Edin. Journ. of Science, 1843.

"of coral reefs very highly inclined, no bottom is sometimes found with a line of 2000 or 3000 feet, and this is by no means a rare case. It follows that the reef ought to have this thickness; and Mr. Darwin's diagrams show that he understood it so. Now, if such masses of coral exist under the sea, they ought somewhere to be found on *terra firma;* for there is evidence that all the lands yet visited by geologists, have been at one time submerged. But neither in the great volcanic chain, extending from Sumatra to Japan, nor in the West Indies, nor in any other region yet explored, has a bed or formation of coral even 500 feet thick been discovered, so far as we know."

When considering this objection, it is evident that the first question we have to deal with is, whether geologists have not already discovered calcareous masses of the required thickness and structure, or precisely such as the upheaval of atolls might be expected to expose to view? We are called upon, in short, to make up our minds both as to the internal composition of the rocks that must result from the growth of corals, whether in lagoon islands or barrier reefs, and the external shape which the reefs would retain when upraised gradually to a vast height,—a task by no means so easy as some may imagine. If the reader has pictured to himself large masses of entire corals, piled one upon the other, for a thickness of several thousand feet, he unquestionably mistakes altogether the nature of the accumulations now in progress. In the first place, the strata at present forming very extensively over the bottom of the ocean, within such barrier reefs as those of Australia and New Caledonia, are known to consist chiefly of horizontal layers of calcareous sediment, while here and there an intermixture must occur of the detritus of granitic and other rocks brought down by rivers from the adjoining lands, or washed from sea-cliffs by the waves and currents. Secondly, in regard to atolls, the stone-making polypifers grow most luxuriantly on the outer edge of the island, to a thickness of a few feet only. Beyond this margin broken pieces of coral and calcareous sand are strewed by the breakers over a steep seaward slope, and as the subsidence continues the next coating of live coral does not grow vertically over the first layer, but on a narrow annular space within it, the reef, as was before stated (p. 761.), constantly contracting its dimensions as it sinks. Thirdly, within the lagoon the accumulation of calcareous matter is chiefly sedimentary, a kind of chalky mud derived from the decay of the softer corallines, with a mixture of calcareous sand swept by the winds and waves from the surrounding circular reef. Here and there, but only in partial clumps, are found living corals, which grow in the middle of the lagoon, and mixed with these and with fine mud and sand, a great variety of shells, and fragments of testacea and echinoderms.

We owe to Lieutenant Nelson the discovery that in the Bermudas the calcareous mud resulting from the decomposition of the softer corallines is absolutely undistinguishable when dried from the but they ought, he says, to be of rare occurrence, for in the case of atolls or of barrier or fringing reefs, the characteristic outline must usually be destroyed by denudation as soon as a reef begins to rise; since it is immediately exposed to the action of the breakers, and the large and conspicuous corals on the outer rim of the atoll or barrier are the first to be destroyed and to fall to the bottom of vertical and undermined cliffs. After slow and continued upheaval a wreck alone can remain of the original reef. If, therefore, says Mr. Darwin, "at some period as far in futurity as the secondary rocks are in the past, the bed of the Pacific with its atolls and barrier reefs should be converted into a continent, we may conceive that scarcely any or none of the existing reefs would be preserved, but only widely spread strata of calcareous matter derived from their wear and tear."[*]

When it is urged in support of the objection before stated (p. 767.) that the theory of atolls by subsidence implies the accumulation of calcareous formations 2000 or 3000 feet thick, it must be conceded that this estimate of the minimum density of the deposits is by no means exaggerated. On the contrary, when we consider that the space over which atolls are scattered in Polynesia and the Indian oceans may be compared to the whole continent of Asia, we cannot but infer from analogy that the differences in level in so vast an area have amounted, antecedently to subsidence, to 5000 or even a greater number of feet. Whatever was the difference in height between the loftiest and lowest of the original mountains or mountainous islands on which the different atolls are based, that difference must represent the thickness of coral which has now reduced all of them to one level. Flinders, therefore, by no means exaggerated the volume of the limestone, which he conceived to have been the work of coral animals; he was merely mistaken as to the manner in which they were enabled to build reefs in an unfathomed ocean.

But is it reasonable to expect, after the waste caused by denudation, that calcareous masses, gradually upheaved in an open sea, should retain such vast thicknesses? Or may not the limestones of the cretaceous and oolitic epochs, which attain in the Alps and Pyrenees a density of 3000 or 4000 feet, and are in great part made up of coralline and shelly matter, present us with a true geological counterpart of the recent coral reefs of equatorial seas?

Before we attach serious importance to arguments founded on negative evidence, and opposed to a theory which so admirably explains a great variety of complicated phenomena, we ought to remember that the upheaval to the height of 4000 feet of atolls in which the coralline limestone would be 4000 feet thick, implies, first, a slow subsidence of 4000 feet, and, secondly, an elevation of the same amount. Even if the reverse or ascending movement began the instant the downward one ceased, we must allow a great lapse of ages for the accomplishment of the whole operation. We must also assume that at the commencement of the period in reous matter, or where the lake is fed by springs, that shells accumulate and form marl.

---

[*] Letter to Mr. Maclaren, Scotsman, 1843.

All the lakes in Forfarshire which have produced deposits of shell-marl have been the sites of springs, which still evolve much carbonic acid, and a small quantity of carbonate of lime. But there is no marl in Loch Fithie, near Forfar, where there are *no springs*, although that lake is surrounded by these calcareous deposits, and although, in every other respect, the site is favourable to the accumulation of aquatic testacea.

We find those Charæ which secrete the largest quantity of calcareous matter in their stems to abound near springs impregnated with carbonate of lime. We know that, if the common hen be deprived altogether of calcareous nutriment, the shells of her eggs will become of too slight a consistency to protect the contents; and some birds eat chalk greedily during the breeding season.

If, on the other hand, we turn to the phenomena of inorganic nature, we observe that, in volcanic countries, there is an enormous evolution of carbonic acid, either free, in a gaseous form, or mixed with water; and the springs of such districts are usually impregnated with carbonate of lime in great abundance. No one who has travelled in Tuscany, through the region of extinct volcanos and its confines, or who has seen the map constructed by Targioni (1827), to show the principal sites of mineral springs, can doubt, for a moment, that if this territory was submerged beneath the sea, it might supply materials for the most extensive coral reefs. The importance of these springs is not to be estimated by the magnitude of the rocks which they have thrown down on the slanting sides of hills, although of these alone large cities might be built, nor by a coating of travertin that covers the soil in some districts for miles in length. The greater part of the calcareous matter passes down in a state of solution to the sea, and in all countries the rivers which flow from chalk and other marly and calcareous rocks carry down vast quantities of lime into the ocean. Lime is also one of the component parts of augite and other volcanic and hypogene minerals, and when these decompose is set free, and may then find its way in a state of solution to the sea.

The lime, therefore, contained generally in sea water, and secreted so plentifully by the testacea and corals of the Pacific, may have been derived either from springs rising up in the bed of the ocean, or from rivers fed by calcareous springs, or impregnated with lime derived from disintegrated rocks, both volcanic and hypogene. If this be admitted, the greater proportion of limestone in the more modern formations as compared to the most ancient, will be explained, for springs in general hold no argillaceous, and but a small quantity of siliceous matter in solution, but they are continually subtracting calcareous matter from the inferior rocks. The constant transfer, therefore, of carbonate of lime from the lower or older portions of the earth's crust to the surface, must cause at all periods, and throughout an indefinite succession of geological epochs, a preponderance of calcareous matter in the newer as contrasted with the older formations.

fact of the first introduction of a moral and intellectual being — so also we may conceive the first creation of the planet itself.

I am far from denying the weight of this reasoning from analogy; but, although it may strengthen our conviction, that the present system of change has not gone on from eternity, it cannot warrant us in presuming that we shall be permitted to behold the signs of the earth's origin, or the evidences of the first introduction into it of organic beings. We aspire in vain to assign limits to the works of creation in *space*, whether we examine the starry heavens, or that world of minute animalcules which is revealed to us by the microscope. We are prepared, therefore, to find that in *time* also the confines of the universe lie beyond the reach of mortal ken. But in whatever direction we pursue our researches, whether in time or space, we discover every where the clear proofs of a Creative Intelligence, and of His foresight, wisdom, and power.

As geologists, we learn that it is not only the present condition of the globe which has been suited to the accommodation of myriads of living creatures, but that many former states also have been adapted to the organization and habits of prior races of beings. The disposition of the seas, continents, and islands, and the climates, have varied; the species likewise have been changed; and yet they have all been so modelled, on types analogous to those of existing plants and animals, as to indicate, throughout, a perfect harmony of design and unity of purpose. To assume that the evidence of the beginning or end of so vast a scheme lies within the reach of our philosophical inquiries, or even of our speculations, appears to be inconsistent with a just estimate of the relations which subsist between the finite powers of man and the attributes of an Infinite and Eternal Being.

and the absence of claws, hoofs, and horns. *Etym.*, *ανοπλος*, *anoplos*, unarmed, and *ϑηριον*, *therion*, a wild beast.

Antagonist Power. Two powers in nature, the action of the one counteracting that of the other, by which a kind of equilibrium or balance is maintained, and the destructive effect prevented that would be produced by one operating without a check.

Antennæ. The articulated horns with which the heads of insects are invariably furnished.

Anthracite. A shining substance like black-lead; a species of mineral charcoal. *Etym.*, *ανθραξ*, *anthrax*, coal.

Anthracotherium. A name given to an extinct quadruped, supposed to belong to the Pachydermata, the bones of which were first found in lignite and coal of the tertiary strata. *Etym.*, *ανθραξ*, *anthrax*, coal, and *ϑηριον*, *therion*, wild beast.

Anthropomorphous. Having a form resembling the human. *Etym.*, *ανθρωπος*, *anthropos*, a man, and *μορφε*, *morphe*, form.

Antiseptic. Substances which prevent corruption in animal and vegetable matter, as common salt does, are said to be antiseptic. *Etym.*, *αντι*, *anti*, against, and *σηπω*, *sepo*, to putrefy.

Arenaceous. Sandy. *Etym.*, *arena*, sand.

Argillaceous. Clayey, composed of clay. *Etym.*, *argilla*, clay.

Arragonite. A simple mineral, a variety of carbonate of lime, so called from having been first found in Arragon, in Spain.

Atolls. Coral islands of an annular form, or consisting of a circular strip or ring of coral surrounding a central lagoon.

Augite. A simple mineral of a dark green, or black colour, which forms a constituent part of many varieties of volcanic rocks. Name applied by Pliny to a particular mineral, from the Greek *αυγη*, *auge*, lustre.

Avalanches. Masses of snow which, being detached from great heights in the Alps, acquire enormous bulk by fresh accumulations as they descend; and when they fall into the valleys below often cause great destruction. They are also called *lavanges* and *lavanches* in the dialects of Switzerland.

Basalt. One of the most common varieties of the Trap-rocks. It is a dark green or black stone, composed of augite and felspar, very compact in texture, and of considerable hardness, often found in regular pillars of three or more sides called basaltic columns. Remarkable examples of this kind are seen at the Giant's Causeway, in Ireland, and at Fingal's Cave, in Staffa, one of the Hebrides. The term is used by Pliny, and is said to come from *basal*, an Æthiopian word signifying iron. The rock often contains much iron.

"**Basin**" of Paris, "**Basin**" of London. Deposits lying in a hollow or trough, formed of older rocks; sometimes used in geology almost synonymously with "formations," to express the deposits lying in a certain cavity or depression in older rocks.

Belemnite. An extinct genus of the order of molluscous animals called Cephalopoda, having a long, straight, and chambered conical shell. *Etym.*, *βελεμνον*, *belemnon*, a dart.

Bitumen. Mineral pitch, of which the tar-like substance which is often seen to ooze out of the Newcastle coal when on the fire, and which makes it cake, is a good example. *Etym.*, *bitumen*, pitch.

Bituminous Shale. An argillaceous shale, much impregnated with bitumen, which is very common in the Coal Measures.

Blende. A metallic ore, a compound of the metal zinc with sulphur. It is often found in brown shining crystals; hence its name among the German miners, from the word *blenden*, to dazzle.

Bluffs. High banks presenting a precipitous front to the sea or a river. A term used in the United States of North America.

Botryoidal. Resembling a bunch of Grapes. *Etym.*, *βοτρυς*, *botrys*, a bunch of grapes, and *ειδος*, *eidos*, form.

Boulders. A provincial term for large rounded blocks of stone lying on the surface of the ground, or sometimes imbedded in loose soil, different in composition from the rocks in their vicinity, and which have been therefore transported from a distance.

Breccia. A rock composed of angular fragments connected together by lime or other mineral substance. An Italian term.

Calc Sinter. A German name for the deposits from springs holding of lime in solution—petrifying springs. *Etym.*, *kalk*, lime, and *sintern*,

Calcaire Grossier. An extensive stratum, or rather series of strata, found the Paris Basin, belonging to the Eocene tertiary period. *Etym.*, *calcaire*, stone, and *grossier*, coarse.

Calcareous Rock. Limestone. *Etym.*, *calx*, lime.

Calcareous Spar. Crystallized carbonate of lime.

Calcedony. A siliceous simple mineral, uncrystallized. Agates are partly posed of calcedony.

Carbon. An undecomposed inflammable substance, one of the simple bodies. Charcoal is almost entirely composed of it. *Etym.*, *carbo*, coal.

Carbonate of Lime. Lime combines with great avidity with carbonic gaseous acid only obtained fluid when united with water,—and all tions of it with other substances are called *Carbonates*. All limestones carbonates of lime, and quicklime is obtained by driving off the carbonic by heat.

Carbonated Springs. Springs of water, containing carbonic acid gas. are very common, especially in volcanic countries; and sometimes so much gas, that if a little sugar be thrown into the water it effervesces soda-water.

Carbonic Acid Gas. A natural gas which often issues from the ground, cially in volcanic countries. *Etym.*, *carbo*, coal; because the gas is by the slow burning of charcoal.

Carboniferous. A term usually applied, in a technical sense, to an group of secondary strata; but any bed containing coal may be said to carboniferous. *Etym.*, *carbo*, coal, and *fero*, to bear.

Cataclysm. A deluge. *Etym.*, κατακλυζω, *cataclu̇zo*, to deluge.

Cephalopoda. A class of molluscous animals, having their organs of arranged round their head. *Etym.*, κεφαλη, *cephale*, head, and feet.

Cetacea. An order of vertebrated mammiferous animals inhabiting the The whale, dolphin, and narwal are examples. *Etym.*, *cete*, whale.

Chalk. A white earthy limestone, the uppermost of the secondary strata.

Chert. A siliceous mineral, nearly allied to calcedony and flint, but less geneous and simple in texture. A gradual passage from chert to is not uncommon.

Chloritic Sand. Sand coloured green by an admixture of the simple chlorite. *Etym.*, χλωρος, *chlorus*, green.

Cleavage. Certain rocks, usually called Slate-rocks, may be cleaved into indefinite number of thin laminæ which are parallel to each other, but are generally not parallel to the planes of the true strata or layers of tion. The planes of cleavage, therefore, are distinguishable from those stratification.

Clinkstone, called also phonolite, a felspathic rock of the trap family, fissile. It is sonorous when struck with a hammer, whence its name.

Coal Formation. This term is generally understood to mean the same as Coal Measures, or Carboniferous group.

Coleoptera. An order of insects (Beetles) which have four wings, the pair being crustaceous and forming a shield. *Etym.*, κολεος, *coleos*, a and πτερον, *pteron*, a wing.

Conformable. When the planes of one set of strata are generally those of another set which are in contact they are said to be

Fig. 98.



Thus the set *a*, *b*, Fig. 98. rest conformably on the inferior set *c*, *d*; but rest unconformably on E.

Congeners. Species which belong to the same genus.

Conglomerate, or **Puddingstone.** Rounded water-worn fragments of rock pebbles, cemented together by another mineral substance, which may be a siliceous, calcareous, or argillaceous nature. *Etym.*, *con*, together, to heap.

Coniferæ. An order of plants, all of which have discs in their wood fibres, by which they are recognised in a fossil state. Their ovules are naked (see Gymnogens). Most of the northern kinds bear the seeds in cones; but the yew does not, nor do a host of tropical and south temperate species. *Etym.*, *conus*, a cone, and *fero*, to bear.

Cosmogony, Cosmology. Words synonymous in meaning, applied to speculations respecting the first origin or mode of creation of the earth. *Etym.*, *κοσμος*, *kosmos*, the world, and *γονη*, *gonee*, generation, or *λογος*, *logos*, discourse.

Crag. A provincial name in Norfolk and Suffolk for certain tertiary deposits usually composed of sand with shells, belonging to the Older Pliocene period.

Crater. The circular cavity at the summit of a volcano, from which the volcanic matter is ejected. *Etym.*, *crater*, a great cup or bowl.

Cretaceous. Belonging to chalk. *Etym.*, *creta*, chalk.

Crop Out. A miner's or mineral surveyor's term, to express the rising up or exposure at the surface of a stratum or series of strata.

Crust of the Earth. See "Earth's crust."

Crustaceous. Animals having a shelly coating or crust which they cast periodically. Crabs, shrimps, and lobsters, are examples.

Cryptogamic. Asexual, flowerless, or Acotyledonous plants; a term applied to half the vegetable kingdom in contradistinction to Phænogamic, sexual, or flowering plants. It includes Fungi, Seaweeds, Lichens, Mosses, Ferns, &c., which have no obvious flowers, and no cotyledons (seed-lobes) to their spores or seeds. *Etym.*, *κρυπτος*, *cruptos*, concealed, and *γαμος*, *gamos*, marriage.

Crystals. Simple minerals are frequently found in regular forms, with facets like the drops of cut glass of chandeliers. Quartz being often met with in rocks in such forms, and beautifully transparent like ice, was called *rock-crystal*, *κρυσταλλος*, *crystallos*, being Greek for ice. Hence the regular *forms* of other minerals are called crystals, whether they be clear or opaque.

Crystallized. A mineral which is found in regular forms or crystals is said to be crystallized.

Crystalline. The internal texture which regular crystals exhibit when broken, or a confused assemblage of ill-defined crystals. Loaf-sugar and statuary-marble have a *crystalline* texture. Sugar-candy and calcareous spar are crystallized.

Cupriferous. Copper-bearing. *Etym.*, *cuprum*, copper, and *fero*, to bear.

Cycadeæ. A small and very anomalous order of flowering plants, chiefly found in Mexico, the East Indian Islands, South Africa, and Australia. They are Gymnogens as to ovules, and neither Exogens nor Endogens in the wood of their short, simple, or branched trunks, and they have dicotyledonous seeds. The leaves are pinnated (like those of cocoa-nut palms), and when young are rolled inwards as in Ferns. The wood fibres are curiously perforated, and marked, by which they are recognised in a fossil state as well as by the trunk and foliage, and the cones, which contain the male flowers. The term is derived from *κυκας*, *cycas*, a name applied by the ancient Greek naturalist Theophrastus to a palm.

Cyperaceæ. A tribe of plants answering to the English sedges; they are distinguished from grasses by their stems being solid, and generally triangular, instead of being hollow and round. Together with *Gramineæ* they constitute what writers on botanical geography often call *glumaceæ*.

Debacle. A great rush of waters, which, breaking down all opposing barriers, carries forward the broken fragments of rocks, and spreads them in its course. *Etym.*, *débacler*, French, to unbar, to break up as a river does at the cessation of a long-continued frost.

Delta. When a great river, before it enters the sea, divides into separate streams, they often diverge and form two sides of a triangle, the sea being the base. The land included by the three lines, and which is invariably alluvial, was first called, in the case of the Nile, a delta, from its resemblance to the letter of the Greek alphabet which goes by that name Δ. Geologists apply the term to alluvial land formed by a river at its mouth, without reference to its precise shape.

Denudation. The carrying away by the action of running water of a p[illegible]on of the solid materials of the land, by which inferior rocks are laid [illegible] *denudo*, to lay bare.

skins; but in geology it refers not only to the cast-off coverings of animals, but to fossil shells and other remains which animals have left in the strata of the earth. *Etym.*, *exuere*, to put off or divest.

Faluns. A French provincial name for some tertiary strata abounding in shells in Touraine, which resemble in lithological characters the "Crag" of Norfolk and Suffolk.

Fault, in the language of miners, is the sudden interruption of the continuity of strata in the same plane, accompanied by a crack or fissure, varying in width from a mere line to several feet, which is generally filled with broken stone, clay, &c.

The strata, *a*, *b*, *c*, &c. must at one time have been continuous; but a fracture having taken place at the fault F, either by the upheaving of the portion A, or the sinking of the portion B, the strata were so displaced that the bed *a* in B is many feet, lower than the same bed *a* in the portion A.

Fig. 99.



Fauna. The various kinds of animals peculiar to a country constitute its Fauna, as the various kinds of plants constitute its Flora. The term is derived from the Fauni, or rural deities, in Roman Mythology.

Felspar. A simple mineral, which, next to quartz, constitutes the chief material of rocks. The white angular portions in granite are felspar. This mineral always contains some alkali in its composition. In *common felspar* the alkali is potash; in another variety, called Albite or Cleavlandite, it is soda. Glassy felspar is a term applied when the crystals have a considerable degree of transparency. *Compact* felspar is a name of more vague signification. The substance so called appears to contain both potash and soda.

Felspathic. Of or belonging to felspar.

Ferruginous. Any thing containing iron. *Etym.*, *ferrum*, iron.

Fissile, easily cleft, dividing readily into an indefinite number of parallel laminæ, like slates.

Floetz Rocks. A German term applied to the secondary strata by the geologists of that country, because these rocks were supposed to occur most frequently in flat horizontal beds. *Etym.*, *flotz*, a layer or stratum.

Flora. The various kinds of trees and plants found in any country constitute the Flora of that country in the language of botanists.

Fluviatile. Belonging to a river. *Etym.*, *fluvius*, a river.

Foraminifera. A name given by D'Orbigny to a family of microscopic shells. Their different chambers are united by a small perforation or *foramen.* Recent observation has shown that some at least are not Cephalopoda, as D'Orbigny supposed.

Formation. A group, whether of alluvial deposits, sedimentary strata, or igneous rocks, referred to a common origin or period.

Fossil. All minerals were once called fossils, but geologists now use the word only to express the remains of animals and plants found buried in the earth. *Etym.*, *fossilis*, any thing that may be dug out of the earth.

Fossiliferous. Containing organic remains.

Galena. A metallic ore, a compound of lead and sulphur. It has often the appearance of highly polished lead. *Etym.*, γαλεω, *galeo*, to shine.

Garnet. A simple mineral, generally of a deep red colour, crystallized; most commonly met with in mica slate, but also in granite and other igneous rocks.

Gasteropods. A division of the Testacea, in which, as in the limpet, the foot is attached to the body. *Etym.*, γαστηρ, *gaster*, belly, and ποδα, *poda*, feet.

Gault. A provincial name in the east of England for a series of beds of clay and marl, the geological position of which is between the Upper and Lower Greensand.

Gavial. A kind of crocodile found in India.

Gem, or **Gemmule**, from the Latin *gemma*, a bud. The term, applied to zoophytes, means a young animal not confined within an envelope or egg.

Melastoma. A genus of Melastomaceæ, an order of exotic plants of the evergreen tree, and shrubby kinds. *Etym.*, *μελας*, *melas*, black, and *στομα*, *stoma*, mouth; because the fruit of one of these species stains the lips.

Mesotype. A simple mineral, white, and needle-shaped, one of the Zeolite family, frequently met with in the Trap-rocks.

Metamorphic Rocks. A stratified division of hypogene rocks, highly crystalline, such as gneiss and mica-schist, and so named because they have been *altered* by plutonic action. *Etym.*, *μετα*, *meta*, trans, and *μορφη*, *morphe*, form.

Mica. A simple mineral, having a shining silvery surface, and capable of being split into very thin elastic leaves or scales. It is often called *talc* in common life; but mineralogists apply the term talc to a different mineral. The brilliant scales in granite are mica. *Etym.*, *mico*, to shine.

Mica-slate, Mica-schist, Micaceous Schistus. One of the metamorphic or crystalline stratified rocks of the hypogene class, which is characterized by being composed of a large proportion of mica united with quartz.

Miocene. A division of tertiary strata intervening between the Eocene and Pliocene formations; so called, because a minority of its fossil shells are referable to living species. *Etym.*, *μειων*, *meion*, less, and *καινος*, *kainos*, recent.

Molasse. A provincial name for a soft green sandstone, associated with marl and conglomerates, belonging to the Miocene Tertiary Period, extensively developed in the lower country of Switzerland. *Etym.*, French, *molle*, soft.

Mollusca, Molluscous Animals. Animals, such as shell-fish, which, being devoid of bones, have soft bodies. *Etym.*, *mollis*, soft.

Monad. The smallest of visible animalcules, spoken of by Buffon and his followers as constituting the elementary molecules of organic beings.

Monitor. An animal of the saurian or lizard tribe, species of which are found in both the fossil and recent state.

Monocotyledonous. A grand division of the vegetable kingdom (including palms, grasses, Lilaceæ, &c.), founded on the plant having only one *cotyledon*, or seed-lobe. *Etym.*, *μονος*, *monos*, single.

Moraine, a Swiss term for the débris of rocks brought into valleys by glaciers. See p. 228.

Moschus. A quadruped resembling the chamois or mountain goat, from which the perfume musk is obtained.

Mountain Limestone, or Carboniferous Limestone. A series of limestone strata of marine origin, usually forming the lowest member of the Coal Measures.

Moya. A term applied in South America to mud poured out from volcanos during eruptions.

Multilocular. Many-chambered; a term applied to those shells which, like the nautilus, ammonite, and others, are divided into many compartments. *Etym.*, *multus*, many, and *loculus*, a partition.

Muriate of Soda. The scientific name for common culinary salt, because it is composed of muriatic acid and the alkali soda.

Musaceæ. A family of tropical monocotyledonous plants, including the banana and plantains.

Muschelkalk. A limestone, belonging to the Upper New Red Sandstone group. Its position is between the Magnesian Limestone and the Lias. This formation has not yet been found in England, and the German name is adopted by English geologists. The word means shell limestone. *Etym.*, *muschel*, shell, and *kalkstein*, limestone.

Naphtha. A very thin, volatile, inflammable, and fluid mineral substance, of which there are springs in many countries, particularly in volcanic districts.

Nenuphar. A yellow water-lily. P. 618.

New Red Sandstone. A formation so named, because it consists chiefly of sandy and argillaceous strata, the predominant colour of which is brick-red, but containing portions which are of a greenish-grey. These occur often in spots and stripes, so that the series has sometimes been called the variegated sandstone. This formation is divided into the Upper New Red in which the Muschelkalk is included, and the Lower New Red of which the Magnesian Limestone is a member.

Nodule. A rounded irregular-shaped lump or mass. *Etym.*, diminutive of *nodus*, knot.

PEPERINO. An Italian name for a particular kind of volcanic rock, formed like tuff, by the cementing together of volcanic sand, cinders, or scoriæ, &c.

PETROLEUM. A liquid mineral pitch, so called because it is seen to ooze like oil out of the rock. *Etym.*, *petra*, rock, and *oleum*, oil.

PHÆNOGAMOUS or PHANEROGAMIC PLANTS. A name given by Linnæus to those plants in which the reproductive organs are apparent. *Etym.*, φανερος, *phaneros*, evident, or φαινω, *phaino*, to show, and γαμος, *gamos*, marriage.

PHLEGRÆAN FIELDS. Campi Phlegræi, or "the Burnt Fields." The country around Naples, so named by the Greeks, from the traces of igneous action every where visible.

PHONOLITE. See "Clinkstone."

HRYGANEA. A genus of four-winged insects, the larvæ of which, called caddis-worms, are used by anglers as a bait.

HYSICS. The department of science which treats of the properties of natural bodies, laws of motion, &c.; sometimes called natural philosophy and mechanical philosophy. *Etym.*, φυσις, *physis*, nature.

HYTOLOGY, PHYTOLOGICAL. The department of science which relates to plants—synonymous with botany and botanical. *Etym.*, φυτον, *phyton*, plant, and λογος, *logos*, discourse.

HYTOPHAGOUS. Plant-eating. *Etym.*, φυτον, *phyton*, plant, and φαγειν, *phagein*, to eat.

ISOLITE. A stone possessing a structure like an agglutination of pease. *Etym.*, πισον, *pison*, pea, and λιθος, *lithos*, stone.

ISTIA. P. 618. The plant mentioned by Malte-Brun is probably the *Pistia Stratiotes*, a floating plant, related to English duckweed, but very much larger.

IT COAL. Ordinary coal; called so, because it is obtained by sinking pits in the ground.

ITCHSTONE. A rock of a uniform texture, belonging to the unstratified and volcanic classes, which has an unctuous appearance like indurated pitch.

LASTIC CLAY. One of the beds of the Eocene Tertiary Period; so called, because it is used for making pottery. The formation to which this name is applied is a series of beds chiefly sands, with which the clay is associated. *Etym.*, πλασσω, *plasso*, to form or fashion.

LESIOSAURUS. A fossil extinct amphibious animal, resembling the saurian, or lizard and crocodile tribe. *Etym.*, πλησιον, *plesion*, near to, and σαυρα, *saura*, a lizard.

LIOCENE, OLDER and NEWER. Two divisions of the Tertiary Period which are the most modern, and of which the largest part of the fossil shells are of recent species. *Etym.*, πλειων, *pleion*, more, and καινος, *kainos*, recent.

LUTONIC ACTION. The influence of volcanic heat and other subterranean causes under pressure.

LUTONIC ROCKS. Granite, porphyry, and other igneous rocks supposed to have consolidated from a melted state at a great depth from the surface.

OLYPARIA. CORALS. A numerous class of invertebrated animals, belonging to the great division called Radiata.

ORPHYRY. An unstratified or igneous rock. The term is as old as the time of Pliny, and was applied to a red rock with small, angular, white bodies diffused through it, which are crystallized felspar, brought from Egypt. The term is hence applied to every species of unstratified rock in which detached crystals of felspar or some other mineral are diffused through a base of other mineral composition. *Etym.*, πορφυρα, *porphyra*, purple.

ORTLAND LIMESTONE, PORTLAND BEDS. A series of limestone strata, belonging to the upper part of the Oolite Group, found chiefly in England in the Island of Portland on the coast of Dorsetshire. The great supply of the building stone used in London is from these quarries.

OZZUOLANA. Volcanic ashes, largely used as mortar for buildings, similar in nature to what is called in this country Roman cement. It gets its name from Puzzuoli, a town in the Bay of Naples, from which it is shipped in large quantities to all parts of the Mediterranean.

RECIPITATE. Substances which, having been dissolved in a fluid, are separated from it by combining chemically and forming a solid, which falls to the bottom of the fluid. This process is the opposite to that of chemical solution.

RODUCTA. An extinct genus of fossil bivalve shells occurring only in the older secondary rocks. It is closely allied to the living genus Terebratula.

gneiss are probably layers of deposition, which have assumed a crystalline texture. See "Cleavage." *Etym*, *schistus*, adj. Latin, that which may be split.

Schistose Rocks. See "Schist."

Scoriæ. Volcanic cinders. The word is Latin for cinders.

Seams. Thin layers which separate two strata of greater magnitude.

Secondary Strata. An extensive series of the stratified rocks which compose the crust of the globe, with certain characters in common, which distinguish them from another series below them called *primary*, and from a third series above them called *tertiary*.

Secular Refrigeration. The periodical cooling and consolidation of the globe from a supposed original state of fluidity from heat. *Sæculum*, age or period.

Sedimentary Rocks are those which have been formed by their materials having been thrown down from a state of suspension or solution in water.

Selenite. Crystallized gypsum, or sulphate of lime—a simple mineral.

Septaria. Flattened balls of stone, generally a kind of iron-stone, which, on being split, are seen to be separated in their interior into irregular masses. *Etym.*, *septa*, inclosures.

Serpentine. A rock usually containing much magnesian earth, for the most part unstratified, but sometimes appearing to be an altered or metamorphic stratified rock. Its name is derived from frequently presenting contrasts of colour, like the skin of some serpents.

Shale. A provincial term, adopted by geologists, to express an indurated slaty clay. *Etym.*, German *schalen*, to peel, to split.

Shell Marl. A deposit of clay, peat, and other substances mixed with shells, which collects at the bottom of lakes.

Shingle. The loose and completely water-worn gravel on the sea-shore.

Silex. The name of one of the pure earths, being the Latin word for *flint*, which is wholly composed of that earth. French geologists have applied it as a generic name for all minerals composed entirely of that earth, of which there are many of different external forms.

Silica. One of the pure earths. *Etym.*, *silex*, flint, because found in that mineral.

Silicate. A chemical compound of silica and another substance, such as silicate of iron. Consult elementary works on chemistry.

Siliceous. Of or belonging to the earth of flint. *Etym.*, *silex*, which see. A siliceous rock is one mainly composed of silex.

Silicified. Any substance that is petrified or mineralized by *siliceous* earth.

Silt. The more comminuted sand, clay, and earth, which is transported by running water. It is often accumulated by currents in banks. Thus the mouth of a river is silted up when its entrance into the sea is impeded by such accumulation of loose materials.

Simple Mineral. Individual mineral substances, as distinguished from rocks, which last are usually an aggregation of simple minerals. They are not simple in regard to their nature; for when subjected to chemical analysis, they are found to consist of a variety of different substances. Pyrites is a simple mineral in the sense we use the term, but it is a chemical compound of sulphur and iron.

Sinter, Calcareous or Siliceous. A German name for a rock precipitated from mineral waters. *Etym.*, *sintern*, to drop.

Slate. See "Cleavage" and "Schist."

Solfatara. A volcanic vent from which sulphur, sulphureous, watery, and acid vapours and gases are emitted.

Sporules. The reproductory corpuscula (minute bodies) of cryptogamic plants. *Etym.*, *σπορα*, *spora*, a seed.

Stalactite. When water holding lime in solution deposits it as it drops from the roof of a cavern, long rods of stone hang down like icicles, and these are called *stalactites*. *Etym.*, *σταλαζω*, *stalazo*, to drop.

Stalagmite. When water holding lime in solution drops on the floor of a cavern, the water evaporating leaves a crust composed of layers of limestone: such a crust is called *stalugmite*, from *σταλαγμα*, *stalagma*, a drop, in opposition to *staluctite*, which see.

Statical Figure. The figure which results from the equilibrium of forces. From *στατος*, *statos*, stable, or standing still.

Sternum. The breast-bone, or the flat bone occupying the front of the c

Stilbite. A crystallized simple mineral, usually white, one of the Z frequently included in the mass of the Trap-rocks.

Tufa, Calcareous. A porous rock deposited by calcareous waters on their exposure to the air, and usually containing portions of plants and other organic substances incrusted with carbonate of lime. The more solid form of the same deposit is called "travertin," into which it passes.

Tufa, Volcanic. See "Tuff."

Tufaceous. A rock with the texture of tuff, or tufa, which see.

Tuff, or Tufa Volcanic. An Italian name for a variety of volcanic rock of an earthy texture, seldom very compact, and composed of an agglutination of fragments of scoriæ and loose materials ejected from a volcano.

Turbinated. Shells which have a spiral or screw-form structure. *Etym.*, *turbinatus*, made like a top.

Turrilite. An extinct genus of chambered shells, allied to the Ammonites, having the siphuncle near the dorsal margin.

Unconformable. See "Conformable."

Unoxidized, Unoxidated. Not combined with oxygen.

Veins, Mineral. Cracks in rocks filled up by substances different from the rock, which may either be earthy or metallic. Veins are sometimes many yards wide; and they ramify or branch off into innumerable smaller parts, often as slender as threads, like the veins in an animal, hence their name.

Vertebrated Animals. A great division of the animal kingdom, including all those which are furnished with a back-bone, as the mammalia, birds, reptiles, and fishes. The separate joints of the back-bone are called *vertebræ*, from the Latin verb *verto*, to turn.

Vesicle. A small, circular, inclosed space, like a little bladder. *Etym.*, diminutive of *vesica*, Latin for a bladder.

Vitrification. The conversion of a body into glass by heat.

Volcanic Bombs. Volcanos throw out sometimes detached masses of melted lava, which, as they fall, assume rounded forms (like bomb-shells), and are often elongated into a pear shape.

Volcanic Foci. The subterranean centres of action in volcanos, where the heat is supposed to be in the highest degree of energy.

Wacke. A rock nearly allied to basalt, of which it may be regarded as a soft and earthy variety.

Warp. The deposit of muddy waters, artificially introduced into low lands. See p. 326.

Zeolite. A family of simple minerals, including stilbite, mesotype, analcime, and some others, usually found in the trap or volcanic rocks. Some of the most common varieties swell or boil up when exposed to the blow-pipe, and hence the name of *ζεω*, *zeo*, to boil, and *λιθος*, *lithos*, stone.

Zoophites. Corals, sponges, and other aquatic animals allied to them; so called because, while they are the habitation of animals, they are fixed to the ground, and have the forms of plants. *Etym.*, *ζωον*, *zoon*, animal, and *φυτον*, *phyton*, plant.

INDEX.

A.

M., on eruption of Vesuvius in 1834, 378.
50.
2, 523.
cited, 499. 502.
Mr., on fossil elephant, 80.
n on age of the baobab tree, 422.
on Burnet's theory, 32.
embankment of the, 255.
delta of the, 256.
R., new passage formed by, 338.
ormerly a seaport, 256.
, deposits in, 36. 38. 71. 257. 774.
Sea, Prof. E. Forbes dredging in, 649.
fossil shells of, mentioned by ancients, 15.
digenous quadrupeds of, 82.
at radiated by, 94.
rrents on coast of, 292. 342.
ift sands of deserts, 726.
vastations of locusts in, 674.
rata forming off tropical coast of, 774.
sert of its area, 694.
, M., on fish of coal formation, 136.
n abrupt transition from one fossil fauna to
er, 184.
motion, &c. of glaciers, 224. 226.
la on fossil remains, 21.
y, fossil whale found at, 771.
a, coal plants, 88.
, volcanos in, 352.
ough, incursions of sea at, 311.
ey, race of, 293.
Isles, eruptions, &c. in, 352. 468.
dria, temple of Serapis at, 512.
known provinces of, 617.
Dr., on coral in Madagascar, 778.
whale cast ashore at, 771.
, imbedding of organic remains in, 730.
olcanic, 386.
alagmite, alternating with, in caves, 736.
aussure on the, 45.
ertiary rocks of the, 119.
greatly raised during tertiary epoch, 124.
signs of lateral pressure in the, 171.
rocks, 177.
n, R., land formed by its deposits, 342.
nimals floated down on drift-wood by, 640.
a, its coast undermined, 331.
ecent strata in lakes of, 254. 768.
pecific distinctness of animals of, 612. 629.
omesticated animals run wild in, 585. 685.
., continuous beds of coal in, 115.
., deposit "New red" like English, 158.
. and S., mammiferous fauna of, 633.
ala in lavas, 550.
osuck, flood in valley of, 209.
re, M., on electric currents in the earth, 543.
therium, in oolite of Stonesfield, 138.
, changes of level in, 762.
eight of perpetual snow on, 112.
Andes, volcanos of, 346.
——, sudden upheaval of, 170.
——, signs of lateral pressure in, 171.
Andesite, rock described, 347.
Angiospermous plants wanting in older rocks, 133.
Animals, extinction of, 700.
——, quantity of food required by large, 82.
——, Lamarck on production of new organs in, 568.
——, imported into America have run wild, 585. 685.
——, aptitude of some kinds to domestication, 593. 598.
——, hereditary instincts of, 593.
——, domestic qualities of, 592. 595.
——, their acquired habits rarely transmissible, 595. 600.
——, changes in brain of fœtus in, 609.
——, plants diffused by, 623.
——, their geographical distribution, 76, 77.
——, migrations of, 635.
——, causes which determine the stations of, 669. 676.
——, influence of man on their distribution, 682.
——, fossil, in peat, caves, &c., 722. 725. 730. 732. 749. 752.
Anio, R., flood of the, 212.
——, travertin formed by, 244.
Anoplotherium, fossil of Isle of Wight, 142.
Antarctic circle, area still unexplored, 99.
Antwerp, sunk region near, 327.
Apennines, their relative age, 119. 124.
Aphides, account of a shower of, 656.
——, their multiplication, 673.
Aqueous causes, supposed former intensity of, 153.
——, their action described, 198.
Aqueous lavas, description of, 374. 385. 728.
Arabian Gulf filling with coral, 776.
Arabian writers, 17.
Arago, M., on influence of forests on climate, 715.
——, on solar radiation, 127.
——, on level of Mediterranean and Red Sea, 294.
——, on formation of ground ice, 221.
Araucanian tradition of a flood, 499.
Araucaria, fir, in coal, 88.
Arbroath, houses, &c. swept away by sea at, 302.
Archiac, M., 257.
Arctic fauna extended farther south than now, 125.
Arduino, memoirs of, 41.
——, on submarine volcanos, 41. 71.
Areas of elevation and subsidence proved by coral islands, 792.
Aristarchus, 212.
Aristotle, opinions of, 12.
——, on spontaneous generation, 22.
——, on deluge of Deucalion, 356.
Arkansas, R., 264.
——, floods of, 270.
Arso, volcanic eruption of, in Ischia
Artesian well at Paris, temperature [illegible]
—— well, at Fort William, near Calcutta
—— well in delta of Po, 257.
—— wells near London, 224.

t., discoveries in south Polar Seas, 99.
, in Yorkshire, 76.
fississippi valley, 636.
ke, 269.
zing from bottom of sea, near Trinidad,

springs, 250.
alt by evaporation in, 335.
uxine.
ains in Jamaica, 506.
ssissippi described, 264.
ctor, migration of, 646.
on inroads of sea in Cornwall, 323.
ft-sand in Cornwall, 728.
., on ceramique, in Morea, 731.
ulfed rivers and caves in Morea, 734.
thquakes in Greece, 736.
e, whence derived, 722.
thquake of, 456.
on plants common to Old and New
4.
l wave frequent in Bristol Channel and
32.
Vincent, M., on isle of Santorin, 445.
334.
ons of deluges on shores of the, 356.
vidence bearing on theory of progressive
ent, 133.
phy, 613.
ces, their number, 616. 666. 668.
alf, gradual elevation of coast of, 520.
land, volcanic, 546.
h, submarine forest at, 746.
lt, M., on volcanos in Andes, 348.
es evolved by volcanos, 549.
ut., on drifting of rocks by ice, 220. 230.
ottom of the sea, 26.
Vesuvius before 1631, 374.
tra, delta of, 275. 278.
their doctrines, 4.
fossils of Hampshire, 46.
ofessor, cited, 80.
llui rhinoceros, 80.
., on upraised sea-coast in Finmark, 530.
Val del Bove, 411.
es now forming in the Morea, 734.
ta of the, 256.
n temple of Serapis, 517.
suvius, 381. 384.
., his discovery of water in African desert,

vaste of cliffs of, 317.
gs, 247.
nnel, currents in, 293.
illage, buried under blown sand, 727.
e tertiary strata of, 122.
of coast of, 324.
fossil conchology, 20.
rnet's theory, 34.
lta of Po, 257.
tinction of species, 668.
e Subapennines, 119.
Mr., on opossum of Stonesfield, 139.
ells from Conception Bay, 500.
llmi revived, 650.
oulting of crabs, 653.
turalization of a foreign landshell, 664.
e Dodo, 684.
, M. Adolphe, 87.
ssil plants of coal, 88. 117. 133.
nts in islands, 112.
, M. Alex. on modern lava streams, 427.
vated beaches in Sweden, 527.
. R., on structure of vessels in myzoden-

lants common to Africa, Guiana, and
22.
Brown, on wheat in Egyptian tombs, 587.
Buch. *See* Von Buch.
Buckland, Rev. Dr., on landslip near Axmouth, 321.
——, on fossil elephants, &c., in India, 7.
——, on fossils from Eschscholtz's Bay, 82.
——, on fossils in caves and fissures, 739, 740.
——, on Val del Bove, 402.
Buffon, his theory of the earth, 39.
——, reproved by the Sorbonne, 39.
——, on geographical distribution of animals, 590. 612. 629.
——, on extinction of species, 702.
Buist, Mr., on submarine forests in estuary of Tay, 303.
——, on mud volcanos in India, 448.
Bunbury, Mr., on coal plants of Alabama, 88.
——, on ferns in carboniferous era, 87.
Bunsen, Chevalier, on Ancient Egypt, 659.
Bunsen, Professor, on Geysers of Iceland, 558.
——, on mineral springs in Iceland, 245.
——, on mud volcanos of Iceland, 447.
——, on solfataras of Iceland, 551.
Bunter Sandstein, fossils of, 193.
Bura, submerged Grecian town, 15. 762.
Buried cones on Etna, section of, 397.
—— temples of Cashmere, 762.
Burnes, Sir A., on Cutch, earthquake of, 461. 464.
Burnet, his theory of the earth, 31.
Burntisland, whale cast ashore near, 771.
Burrampooter, R., delta of the, 275. *See* Brahmapootra.
——, bodies of men, deer, &c. floated off by, 751.
Bustards recently extirpated in England, 683.

C.

Calabria, geological description of, 474.
——, earthquake of 1783 in, 471.
——, tertiary strata of, 74.
Calanna, lava of Etna turned from its course by hill of, 409, 410.
——, valley of, 402. 404.
Calcareous springs, 239.
Calcutta, artesian well at, 280.
Caldcleugh, Mr., on earthquake in Chili, 1835, 453.
——, on eruption of Coseguina, 349.
California, volcanos in, 349.
Callao town destroyed by sea, 502.
——, changes caused by earthquakes at, 501. 761.
Camels, carcasses of, imbedded in drift sand, 727.
Campagna di Roma, calcareous deposits of, 242.
Campania, aqueous lavas in, 728.
Camper, on facial angle, 608.
Canada, earthquakes frequent in, 470.
——, climate of, 582.
——, probably colder in newest tertiary period, 126.
Canary Islands, eruptions in, 436.
Cannon in calcareous rock, 759.
——, account of one taken up near the Downs, 726.
Canoes drifted to great distances, 661.
——, fossil, 759.
Cape May, encroachment of sea at, 332.
—— of Good Hope, icebergs seen off, 100.
Capocci, M., on temple of Serapis, 518.
Caraccas, earthquakes in, 465. 470.
Carang Assam volcano, 465.
Carbonated springs, 248.
Carbonic acid, supposed atmosphere of, 248.
—— gas, its effects on rocks, 249.
Carboniferous series, 115. 137.
—— era, predominance of ferns in, 87.
—— era, climate in, 87.
—— flora, knowledge of, recently acquired, 126.
—— period, vast duration of, 249.
——. *See* Coal.
Cardiganshire, tradition of loss of land in
Cardium, locomotive powers when you

Crag strata, fossils of the, 142.
Craters of elevation, theory of, 371. 380. 415.
Crawfurd, Mr., his discovery of fossils in Ava, 28.
——, on eruption in Sumbawa, 106. 464, 465.
——, on drifting of canoes, 662.
Creation, supposed centres or foci of, 667.
——, epoch of, difference of opinion on, 660.
Cremona, lakes filled up near, 255.
Crocodiles imbedded by a river inundation in Java, 503. 748.
Cromer, waste of cliffs of, 306.
Cropthorn, fossils found at, 76.
Cruickshanks, Mr. A., on Chilian earthquake, 457.
Cuba, fossils in caves of, 741.
Culver, cliff, 318.
Cumana, earthquake of, 470.
Cunningham, Major, on buried temples of Cashmere, 764.
Cupressus thyoides, 725.
Currents from equatorial regions, 96.
——, from the pole to the equator, 107.
——, causes and velocity of, 293.
——, polar and tropical, direction of, 295.
——, destroying and transporting power of, 297. 340.
——, in estuaries, their power, 337.
——, in the Straits of Gibraltar, 333.
——, reproductive effects of, 337.
——, on the British shores, 339.
——, convey species from Antarctic to Arctic Ocean, 622.
Curtis, Mr., on ravages caused by aphides, 674.
——, on power of the Tipulæ to cross the sea, 657.
——, on number of British insects, 705.
——, on fossil insects, 748.
Curves of the Mississippi, 265.
Cutch, changes caused by earthquake of 1819 in, 459. 762.
Cuvier on durability of bones of men, 147. 757.
—— on crocodiles of Ganges, 277.
—— on variability in species, 583, 584.
—— on fish not crossing the Atlantic, 647.
—— on identity of Egyptian mummies with living species, 586.
——, on number of fishes, 706.
Cuvier, M. F., on aptitude of some animals to domestication, 593.
——, on influence of domestication, 595.
Cypris, fossil and living, 768.

D.

Dana, Mr., on Sandwich Islands, 354. 372. 383. 548.
——, on fragments of recent coral thrown up by Polynesian volcanos, 372.
——, on Mount Loa, volcano, 552.
——, on "volcanos no safety valves," 552.
Dangerfield, Capt. F., on buried cities in India, 729.
—— on Oujein, 729.
Daniell, Professor, on the trade winds, 106.
——, on melting point of iron, 539.
Dante cited, 52. 256.
Dantzic, waste of land near, 331.
Darby, on lakes formed by Red River, 269.
——, on delta of Mississippi, 272.
Darwin, Mr. C., on distribution of animals and plants, 77. 98. 141.
——, on vegetation required for support of large quadrupeds, 82.
——, Mr. C., on drifting of rocks by ice, 228.
——, on earthquakes, 347. 453. 456. 476. 753.
——, on earthquake waves, 497.
——, on rise of land, 458. 502.
——, on oolitic travertin, 439.
——, on great droughts in S. America, 696.
——, on peat of S. America, 719.
Darwin, Mr. C., on coral islands, 779, 780. 783. 785. 789.
——, geology of S. America, 170.
——, on recent shells in Chili, 190.
——, on shingle on coast of S. America, 342.
——, map of coral reefs, 352. 792. 794.
——, on crateriform hills of Galapagos, 372.
——, infusoria brought home by, 388.
——, on new islands forming in Atlantic, 436.
——, on nat. hist. of Galapagos, 141. 597. 615, 616. 642.
——, on extinction of animals, 701.
Daubeny, Dr., on springs, 237.
——, on Mount Vultur, 356.
——, on Vesuvius, 380.
——, on decomposition of trachyte, 385.
——, on flowing of lava under water, 383.
——, on volcanos, 548, 549, 550, 551.
D'Aubuisson cited, 58. 411.
Davis, Mr., on Chinese deluge, 7.
Davy, Sir H., on lake of the Solfatara, 243.
——, on formation of travertin, 243.
——, on theory of progressive development, 131.
——, on eruption of Vesuvius, 378.
——, on chemical agency of electricity, 542.
——, his theory of unoxidated metallic nucleus, 546.
——, on agency of air and water in volcanos, 548. 550.
——, his analysis of peat. 718.
Davy, Dr., on Graham Island, 436. 549.
——, on helmet taken from sea near Corfu, 760.
De Beaumont. *See* Beaumont, De.
Debey, Dr., of Aix, on cretaceous dicotyledons, 133.
De Candolle, on hybrid plants, 605.
——, on distribution of plants, 613. 616.
——, on agency of man in dispersion of plants, 625.
——, on stations of plants, 670.
——, on barriers separating botanical provinces, 703.
——, on number of land plants, 705.
——, on longevity of trees, 422.
Dechen, Von, map of Germany. &c., 123.
Dee, R., bridge over, swept away by floods, 208.
Deer, their powers of swimming, 636.
——, diminished number in Great Britain, 683.
——, remains of, in marl lakes, 752.
De la Beche, Sir H., on rocks in S. Wales, 91.
——, on delta of Rhone in Lake of Geneva, 253.
——, on storm of Nov. 1824, 321.
——, on submarine forests, 323.
——, on earthquake of Jamaica, 1692, 504.
——, on action of rain in the tropics, 713.
De la Hire, on fossil wood from Ava, 1692, 28.
Delhi territory, elephants in, 81.
Delta of the Adige and Brenta, 256.
—— of the Brahmapootra or Burrampooter, 275.
—— of the Ganges, 275 to 284.
—— of the Mississippi, 263 to 275.
—— of the Mississippi, antiquity of, 271.
—— of the Nile, 261.
—— of the Po, 256.
—— of Rhone, in Lake of Geneva, 252.
—— of Rhone, in Mediterranean, 258.
Deltas, chronological computations of age of, 253. 285.
——, of Lake Superior, 253.
——, grouping of strata in, 286.
De Luc, his treatise on Geology, 56.
——, on conversion of forests into peat mosses, 721.
De Luc, M. G. A., his natural chronometers. 726.
Deluge, ancient theories on, 18. 23. 25. 31. 42. 155.
——, fossil shells referred to the, 20.
Deluges, local, how caused, 7. 269.
——, traditions of different, 7. 11. 42. 331. 356. 500, 501.
Demaillet, speculative views of, 572.
Denudation can only keep pace with deposition, 154.
——, effects of, 708.
Deposition of sediment, shifting of the area 188.
—— and denudation parts of the same process

Erratic blocks, submarine, laid dry by upheaval, 229.
Eruptions, volcanic, number of per year, 450.
——, cause of, 533.
Ergebirge, mica slate of the, 48.
Escher, M., on flood in valley of Bagnes, 211.
Eschscholtz Bay, fossils of, 82.
Essex, tertiary strata of, 76.
——, inroads of sea on coast of, 311.
Estuaries, how formed, 327. 337.
——, imbedding of freshwater species in, 768.
Etna, description of and its eruptions, 396. to 424.
——, towns overflowed by lava of, 400. 728.
——, subterranean caverns on, 401.
——, a glacier under lava on, 412.
——, marine formations at its base, 401.
——, antiquity of cone of, 422.
Euganean Hills, lavas of, 359.
Euphrates, delta of advancing rapidly, 284.
Euxine burst its barrier, according to Strabo, 14.
——, gradually filling up, 14.
——. *See* Black Sea.
Evaporation, water carried off by, 260. 294. 334.
——, currents caused by, 294.
Everest, Rev. R., on climate of fossil elephant, 81.
——, on sediment of Ganges, 281.
Excavation of valleys, 488.
Expansion of rocks by heat, 560.
Extinction of species, 697. 701.
—— of animals, 700 702.

F.

Fabio Colonna, 23.
Facial angle, 608.
Fair Island, action of the sea on, 301.
Falconer, Dr., on fossil quadrumana, 144.
——, on crocodiles of Ganges, 277.
——, on peat near Calcutta, 280.
Falconi on elevation of coast of Bay of Baiæ, 367.
Falkland Islands, quadrupeds of, 141. 635.
Falloppio on fossils, 21.
Falls of Niagara, 214.
—— of St. Mary, 254.
Faluns of Touraine, 142.
Faraday, Mr., on water of the Geysers, 246.
——, on slow deposition of sulphate of baryta, 343.
——, on electric currents in the earth, 543.
——, on metallic reduction by voltaic agency, 548.
——, on liquefaction of gases, 560.
Faroe Islands, deposits forming near the, 774.
Farquharson, Rev. J., on floods in Scotland, 208.
——, on formation of ground ice, 222.
Faujas, on Velay and Vivarais, 1779, 48.
Faults, 162.
Fauna formerly as diversified as now, 160.
——, arctic, described by Sir J. Richardson, 634.
Felspar, decomposition of, 247.
Ferrara on lavas of Etna, 283.
——, on floods on Etna, 412.
——, on earthquake in Sicily, 471.
Ferruginous springs, 247.
Fez, earthquakes in, 358.
Fife, trap rocks of, 161.
——, coast of, submarine forests on, 303.
——, encroachments of sea on, 303.
Findhorn town swept away by sea, 302.
Fish, their distribution, and migrations, 646.
——, fossil, 745.
——, fossil of coal formation, 136.
Fissures, sulphur, &c., ejected by, 470.
——, caused by Calabrian earthquake, 479. 480. 481.
——, caused by earthquake near New Madrid, 468.
——, preservation of organic remains in, 732.
Fitton, Dr., on history of English geology, 51.
FitzRoy, Capt., on earthquake in Chili, 1835, 453. 455.
Flamborough Head, waste of, 303.
Fleming, Dr., on uniformity in climate, 74.
——, on fossil elephant, 76.
——, on submarine forests, 303.
——, on rapid flight of birds, 644.
——, on turtles taken on coast of England, 645.
——, on changes in the animal kingdom caused by man, 683.
——, on stranding of cetacea, 771.
Flinders on coral reefs, 776. 791.
Flint on course of Mississippi, &c., 264. 265.
——, on earthquakes in Mississippi valley, 466.
Floods, by bursting of lakes, 269.
——, in North America, 209.
——, in valley of Bagnes, 210.
——, in Scotland, 207. 750.
——, traditions of, 499. 501.
——, causes which may give rise to, 156.
——, at Tivoli, 211.
——, caused by melting of snow by lava, 348. 411.
——. *See* Deluge.
Flysch, of the Alps, eocene, 124.
Folkstone, subsidence of land at, 316.
Fontenelle, his eulogy on Palissy, 23.
Foot-marks, fossil, in North America, 136.
Forbes, Prof. E. on glacial epoch, 86.
——, on fossils of tertiary, 184.
——, on new island in Gulf of Santorin, 443.
——, on regions of depth in Ægean Sea, 649.
——, on migration of mollusca, 651.
——, cited, 703.
Forbes, Prof. J. D., on glacier motion, 224.
——, on rate of flowing of lava, 378. 400.
——, on temple of Serapis, 515. 517.
Forchhammer, Dr., on boulders drifted by ice, 231.
——, on peat, 719.
Forests, influence of, 712, 713. 715.
——, sites of, now covered by peat, 720.
——, destroyed by insects, 717.
——, submarine, 303. 323. 746.
——, submerged, in Columbia R. by land-slides, 215.
Forfarshire, waste of coast of, 302.
——, marl lakes of, 766. 797.
Forshey, Mr., on Mississippi, 264. 271.
Forster, Mr., on coral reefs, 779.
Forsyth on climate of Italy, 395.
Fortis cited, 42.
——, views of Arduino confirmed by, 48.
—— and Testa on fossil fish, 44.
Fort William, near Calcutta, artesian well, 280.
Fossiliferous formations, breaks in the series, 180.
Fossilization of organic remains on emerged land 718. 775.
——, in peat mosses, 722.
——, in caves and fissures, 732.
——, in alluvium and landslips, 730.
——, in volcanic formations on land, 349. 728.
——, subaqueous deposits, 742. 753.
——, in marl lakes, 752.
Fossils, early speculations concerning their nature, 19, 24 to 27.
——, distinctness of secondary and tertiary, 119.
——, mammiferous of tertiary eras, 137. 140.
——, why distinct in successive groups, 190.
——, *See* Organic Remains.
Fossil trees, upright position of some, 91.
Fourier, Baron, on temperature of spaces surrounding our atmosphere, 108.
——, on central heat, 127.
——, on radiation of heat, 127.
Fox, Mr., on heat in mines, 538.
——, on electric currents in the earth, 543.
France, waste of coast of, 324.
——, caves of, 738.
Franconia, caves of, 736.
Franklin on a whirlwind in Maryland,

Heat, whether gradual decline of, in globe, 129.
——, expansion of rocks by, 561.
Heber, Bishop, on animals of Himalaya, 81.
Hecla, columnar basalt of, 48.
——, eruptions of, 424.
Helena, St., bounded by lofty shores, 622.
Heligoland, inroads of sea on, 329.
Helix, range of species of, 650.
Henderson on eruption of Skaptar Jokul, 1783, 425.
Henderson's Island described, 788.
Henslow, Rev. Prof., on the cowslip, 590.
——, on diffusion of plants, 624.
Herbert, Hon. Mr., on varieties and hybrids in plants, 590. 605.
Herculaneum, 385. 389.
Herne Bay, waste of cliffs in, 312.
Herodotus cited, 8. 261.
Herschel, Sir J. F. W., on varying heat received by the two hemispheres, 100.
——, on astronomical causes of changes in climate, 126.
——, on variable splendour of stars, 128.
——, on the trade winds, 297.
——, on height of Etna, 396.
——, on form of the earth, 534.
——, on Geysers of Iceland, 555.
——, on the effects of heat on seeds, 621.
——, on the author's theory of climate, 92.
Herschel, Sir W., on the elementary matter of the earth, 533.
Hewett, Capt., on rise of tides, 291.
——, on currents, 293.
——, on banks in North Sea, 308. 340.
Hibbert, Dr., on the Shetland Islands, 299, 300.
Hilaire, M. Geof. St., on animal kingdom, 567.
Himalaya mountains, animals inhabiting the, 81.
——, height of perpetual snow on, 112.
Hindoo cosmogony, 4.
—— town buried, 731.
Hindostan, earthquakes in, 494.
Hippopotamus indicates warmth of river, 76.
Hitchcock, Report on Geol. of Massachusetts, 137.
Hoff, Von, on level of Caspian, 18.
——, on encroachments of sea, 331, 332.
——, on earthquakes, 358.
——, on human remains in delta of Ganges, 757.
——, on a buried vessel, 758.
Hoffmann, M., on lavas of Vesuvius, 379.
——, on Etna, 415, 416.
Holland, gradual sinking of coast, 327.
——, inroads of sea in, 328.
——, submarine peat in, 770.
Hooke on duration of species, 27, 28.
—— on earthquakes, 27. 29. 508.
Hooker, Dr. J., on icebergs in antarctic seas, 229.
——, on tropical plants, 614.
——, floras of islands in Southern Ocean, 615.
——, on flora of Galapagos Islands, 616.
——, on wide range of certain plants, 618. 621. 623.
——, on delta of Ganges, 279.
——, on rain in India, 200.
Hocker, Sir W.. on eruption of Skaptar Jokul, 425.
——, his view of the crater of the great Geyser, 554.
——, on drifting of a fox on ice, 680.
Hopkins, Mr., on glacier motion, 224, 225.
——, on thickness of earth's crust, 536.
Hopkins, Mr., on astronomical causes of change of climate, 128.
——, on changes of climate, 93.
——, on earthquakes, 453.
——, on M. E. de Beaumont's theory of mountain chains, 170.
Hordwell, loss of land at, 318.
Horner, Mr., on brine springs, 247.
——, on submarine forest in Somersetshire, 323.
——, dissertation on coal, 91.
Horsburgh, Capt., on icebergs in low latitudes, 99.
Horsburgh on coral islands, 782. 787.
Horses drowned in rivers in South America, 750.
Horsfield, Dr., on earthquakes in Java, 471. 494.
——, on distribution of *Mydaus meliceps* in Java, 638.
Hubbard, Prof., cited, 210.
Huc, on Yaks frozen in ice in Thibet, 85.
Human race geologically modern, 660.
Human remains in peat mosses, 722.
——, in caves, 735, 736. 739.,
——, their durability, 147. 757.
—— in delta of Ganges, 757.
—— in calcareous rock at Guadaloupe, 757.
—— in breccias in the Morea, 735.
Humber, warp of the, 288.
——, encroachment of sea in its estuary, 304.
Humboldt on laws regulating diffusion of heat, 93.
—— on preservation of animals in frozen mud, 85.
—— on distribution of land and sea, 109.
—— on transportation of sediment by currents, 342.
——, his definition of volcanic action, 345.
—— on mud eruptions in the Andes, 348.
—— on volcanic eruptions in Tartary, 355.
—— on eruption of Jorullo, 428.
—— on earthquakes, 466. 470.
—— on distribution of species, 613, 614.
—— on migrations of animals, 644. 656. 685.
—— cited, 8. 77. 84.
—— on earthquake in New Madrid, 466.
—— on earthquake of Lisbon, 495.
—— on mud Volcanos, 448.
Humboldt, W. von, on dawn of oriental civilization, 658.
Humming-birds, distribution, &c., 97. 643.
Hunter, John, on mule animals, 601.
Huron, Lake, recent strata of, 768.
Hurricanes connected with earthquakes, 731.
——, plants drifted to sea by, 745.
Hurst Castle shingle bank, 318.
Hutchinson, John, his "Moses's Principia," 33.
Hutton, distinguished geology from cosmogony, 3.
—— on igneous rocks and granite, 51.
—— represented oldest rocks as derivatives, 52.
Huttonian theory, 50. 57.
Hybrid races, Lamarck on, 572.
—— animals, 600.
—— plants, 602.
Hydrogen, deoxidating power of, 547.
——, flame of, seen in eruption of Vesuvius, 378.
——, why not found in a separate form among volcanic gases, 548.
Hydrophytes, distribution of, 617. 623.
Hydrostatic pressure of ascending lava, 416. 553.
Hypogene rocks, 178.
Hyracotherium, Eocene mammifer, 142.
Hythe, encroachments of sea at, 816.

I.

Ianthina fragilis, its range, &c., 650.
Ice, animals imbedded in, 83.
Ice of rivers, transporting power of, 219.
——, drift, influence of, on temperature, 95.
——, predominance of, in antarctic circle, 98.
——, formation of field, 107.
——, transportation of rocks by, 155. 219. 521.
Icebergs, formation of, 96, 97.
——, distance to which they float, 100. 227.
——, limits of glaciers and, 228.
——, plants and animals transported by, 622. 639.
——, action of, when stranded, 228.
——, rocks transported by. *See* Ice.
——, floating in Northern hemisphere, 86.
——, not all formed by glaciers, 228.
Iceland, icebergs stranded on, 97.
——, geysers of, 246. 553, 555.

migrations of animals in, 637.
essure caused by landslips, 322.
ure in Andes and Alps, 171.
Dr. R. G., on Natural History of Man, 609.
Sir T. D., on floods in Scotland, 208. 636.

vated by rivers, 213.
ts of decomposition on, 384.
ng of, under water, 382.
ostatic pressure of ascending. 582.
land and Central France, 426, 427.
parative volume of ancient and modern,

nded distinction between ancient and mo-
3.
ral composition of, 449. 551.
of flowing, 378. 400.
loro. *See* Moro.
reatise of, 1759, 40.
heory of, 26.
., on Priscodelphinus, 145.
migrations of, 637.
fossil bones on banks of, 78. 80.
da Vinci, 19.
man bones in tumulus near, 739.
ry recently filled up near, 748. 768.
es near, 737.
ence of, on plants, 89.
effect of, in Shetland Islands, 299
nversion of wood into, 759.
royed by earthquake, 501.
ted recent marine strata at, 502.
nce derived, 796.
re, inroads of sea on coast of, 304.
r., on fossil plants of Melville Islands, 88.
mber of plants, 705.
spersion of plants, 620.
sil plants of coal, 88. 133.
133.
n filling up of Gulf of Bothnia, 521.
bsidence of Scania, 530.
stancy of species. 568.
l existence of genera, 578.
usion of plants, 624. 626.
roduction of species, 665.
671.
tradition in Cornwall, 324.
erculaneum and Pompeii, 387.

thquakes at, 358. 495.
: proposed geological maps, 26.
il shells, 26.
, on levels of Atlantic and Pacific, 295.
t, volcano of Sandwich Isles, 552.
vastations of, 674.
formed in sea by, 675.
e Rhine, 185.
Mississippi valley, 265.
ary strata of the, 142.
tesian wells near, 234.
sin, tertiary deposits of, 121.
s fossils, 142. 144.
Ness described, 309.
undermined near, 309.
Siberia, 78. 80. 83. 85.
on the Ganges, 276. 277.
slands formed near, 276.
ubsidence near, 460.
on fossil quadrumana, 144.
ls, caravans overwhelmed by, 727.
s, waste of cliffs at, 321.
breaches made by the sea in, 330.

M.

d, Dr., on earthquakes in Chittagong,
MacClelland, Dr., on volcanic line in bay of Bengal, 354.
MacCulloch, Dr., on gradation from peat to coal, 719.
—— on origin of limestones, 796.
Macacus pliocenus of Owen, fossil in valley of Thames, 144.
——, Suffolk Eocene species, 144.
Macaluba, in Sicily, mud volcanos, 448.
Mackenzie, Sir G., his section of geyser, 556.
——, on reindeer in Iceland, 686.
Mackenzie River, driftwood of, 90. 743.
——, floods of, 84.
Maclaren, Mr. C., on Graham Island, 435.
——, on quantity of useful soil in America, 687.
——, on position of American forests, 714.
—— remarks, theory of atolls, 792.
Macmurdo, Captain, on earthquake of Cutch, 460.
Madagascar, extent of coral near, 776.
——, assemblage of quadrupeds in, 631.
Madrid, New, great earthquake at, 466.
——, sunk country near it, 270.
Maeler, lake, 524. 528.
Magellan, Straits of, tides in, 291. 293.
Magnesia deposited by springs, 238.
Magnesian limestone and travertin compared, 240.
Magnetism, terrestrial, phenomena of, 543.
——, solar, 129.
Mahomet, his cosmogony, 18.
Malabar, coral near, 776.
Maldiva Islands, coral reefs of, 778. 782.
Mallet, Captain, on petroleum of Trinidad, 250.
Mallet, Mr., on the dynamics of earthquakes, 453. 475.
——, on whirling motion during earthquakes, 476.
——, cited, 560,
——, on transit of the earthwave, 483.
——, on theory of waves, 498.
Mammalia, different regions of indigenous, 629.
——, fossil, of successive tertiary periods, 138. 140.
——, imbedding of, in subaqueous strata, 749. 753.
Mammifer, fossil of trias, 137.
Mammoth, Siberian, 75.
——, bones of, in Yorkshire, 76.
Man, recent origin of, 147. 182. 687. 764.
——, why able to live in all climates, 609.
——, diffusion of, 657.
——, changes caused by, 151. 182. 630. 663. 681. 713.
——, durability of the bones of, 147. 757.
——, remains of, in osseous breccias of Morea, 735.
——, his remains and works fossil, 753.
Manetho, 63.
Mantell, Dr., on bones from Saxon tumulus, 739.
——, on Lewes Levels, 748. 768.
Map of Siberia, 79.
——, of World, showing present unequal distribution of land and sea, 110.
——, showing position of land and sea, which might produce extremes of heat and cold, 111.
——, of Europe, showing extent of land covered by sea since commencement of tertiary period (Pl.I.), 121.
——, of coast from Nieuport to mouth of Elbe, 326.
——, of volcanos from Philippine Islands to Bengal, 351.
—— of volcanic district of Naples, 361.
—— of Gulf of Santorin, 442.
—— of Chili, 454, 455.
—— of Cutch, 460.
—— of Calabria, 472.
—— of Sweden, 522.
Maracaybo, Lake, 466.
Marine deposits, imbedding of land quadrupeds in, 749. 753.
——, of human remains and works of art in, 756.
——, of freshwater species in, 768.
——, plants and animals, imbedded in, 770.

Marine vegetation, 617. 622.
Marl lakes of Scotland, animals and plants fossilized in, 752. 766.
Marsili, on arrangement of shells in Adriatic, 36. 38. 40.
——, on deposits of coasts of Languedoc, 260.
Marsupial animals, distribution of, 633.
—— fossil, 138.
Martigny destroyed by floods, 211.
Martius, on drifting of animals by the Amazon, 640.
——, on Brazil, 682.
Maryland, whirlwind in, 619.
Mattani on fossils of Volterra, 34.
Mattioli on organic remains, 21.
Mauritius, reef uplifted above level of sea, 794.
Mediterranean, microscopic testacea of, 44.
——, deposition of salt in the, 334.
——, new island in, 432.
——, its temperature, depth, level, &c., 45. 294. 334. 510.
——, same level as Red Sea, 294.
Megna R., arm of Brahmapootra, 279.
Melville Island, fossils of, 90.
——, migrations of animals into, 640.
Melville, Dr., on dodo, 684.
Memphis, in delta of Nile, 261.
Mendip Hills, caves of, 737.
Menu's Institutes, 4, 5.
Mercati on organic remains, 22.
Mersey, vessel in bed of, 758.
Messina, tide in Straits of, 290.
——, earthquakes at, 477. 488. 490.
Metallic nucleus, theory of an unoxidated, 545.
Metallic substances changed by submersion, 759.
Metamorphic rocks, how formed, 177.
——, of the Alps, 178.
——, why those visible to us must be very ancient, 178.
Mexico, Gulf of, tides in, 295.
——, currents in, 96. 292.
——, volcanos of, 349. 546.
Meyen, Dr., on earthquake in Chili, 1822, 458.
Michell on phenomena of earthquakes, 41.
—— on the geology of Yorkshire, 42.
—— on earthquake at Lisbon, 358. 497.
—— on retreat of the sea during earthquakes, 498.
—— on wave-like motion of earthquakes, 558.
—— on earthquakes cited, 499.
Microlestes, triassic mammifer, 137. 145.
Middendorf, Mr., on Siberian mammoth, 81.
Migrations of plants, 618.
—— of animals, 635, 636.
—— of cetacea, 642.
—— of birds, 642.
—— of fish, 646.
—— of zoophytes, 653.
—— of insects, 655.
Migratory powers indispensable to animals, 689.
Milford Haven, rise of tides at, 291.
Millennium, 20. 32.
Mineral waters, their connection with volcanos, 237.
——, ingredients most common in. *See* Springs, 237.
Mineralization of plants, 747.
Mines, heat in, augments with the depth, 558.
Miocene strata of Suffolk, fossils of, 142.
——, proportion of living species in fossil shells of the, 183.
Mississippi, its course, delta, &c., 263. 275.
——, drift-wood of the, 267.
——, earthquakes in valley of, 270. 350.
——, antiquity of delta of, 272.
——, earthquake region of, 467.
——, banks higher than swamps, 266.
Missouri, R., 264.
Mitchell, Dr., on waste of cliffs, 311.
Moel Tryfane, recent marine shells on, 122.
Mollusca. *See* Testacea.
——, provinces of, 649.
Molluscous animals, longevity of species of,
Moluccas, eruptions in the, 504.
Monkeys, fossil, 144.
Monte Barbaro, description of, 373.
—— Bolca, fossil fish of, 44.
—— Nuovo, formation of, 368. 518.
—— Somma, structure of, 382.
Monti Rossi on Etna described, 397. 399.
Montlosier, on Auvergne, 49.
Moraines of glaciers, 223. 226. 228.
Morayshire, town in, destroyed by sea, 305.
——, effect of floods in, 208. 735.
Morea, Céramique of, [illegible]1.
——, osseous breccias now forming in the,
——, human remains imbedded in, 733.
Morlot, on subsidence in Adriatic, 282.
Moro, Lazzaro, his geological views, 34.
——, on primary rocks, 52.
Morocco, earthquakes at, 356.
Morton, Dr. S. G., on hybrids and species,
Mountain chains, on the elevation of, 63.
——, theory of sudden rise of, 163.
Moya of the Andes described, 348. 679.
Mud eruptions in Quito, 1797, 348.
—— volcanos, 447.
Mules sometimes prolific, 601.
Murchison, Sir R., on the Hartz mountains,
——, on tertiary deposits of the Alps, 113.
——, on geography of Siberia, 78. 84. 12
——, map of Russia, 123.
——, on depression of Caspian, 137.
——, on travertin of Tivoli, 243.
——, on tertiary deposits of Alps, 124.
Muschelkalk, 125.
Mydaus meliceps, 638.
Myrmecobius fasciatus, 138.
Mytilus polymorphus, 652.

N.

Nantucket, banks of, 293.
Naples, volcanic district round, 361.
——, recent tertiary strata near, 74.
Narwal stranded near Boston, 771.
——, fossil near Lewes, 769.
Nasmyth, Mr., on nonconductibility of dry clay, 413.
Needles of Isle of Wight, 318.
Negro physiognomy traced back 3000 years
Neill on whales stranded, 771.
Nelson, Lieut., on coral reefs, 793.
Neptune, temple of, under water, 516.
Neptunists and Vulcanists, rival factions
Nerbuddah, river, 705.
Newbold, Lieut., on mud of Nile, 262.
Newfoundland, cattle mired in bogs of,
Newhaven, its cliffs undermined, 317.
New Holland, plants of, 112. 614.
——, animals of, 630.
——, coral reefs of, 776. 791.
New Kameni, formation of, 443.
New Madrid U. S., earthquakes at, 350.
New Zealand, animals in, 635.
——, tree ferns in, 89.
Niagara, Falls of, 214.
——, their recession, 217, 218.
——, height of, 216.
Niccolini, M., on Temple of Serapis, 518.
Nicolosi destroyed by earthquake, 399.
Nile, R., delta of the, 261.
——, cities buried under blown sand near
——, swept away by flood of, 733.
Nilson, M., on subsidence of Scania, 320.

migrations of eels, 648.
n springs. 710.
ure of geology, remarks on, 158.
'aste of cliffs of, 305.
of land on coast of, 308.
e, drift wood on, 745.
erland, land destroyed by sea in, 303.
ee from earthquakes, 531.
f land in, 192. 527. 529.
nce situated on an arm of the sea, 307.
Crag, fossils of, 143.
ia, rise of tides in, 332.
ic limestone, 124.
emple of, under water, 516.
w island formed in 1783, 425. 432.

O.

ssils on shores of, 81.
manency of its level, 518.
n tertiary strata of Italy, 42.
iscoveries of, 542.
eluge, 349. 356.
tion of, with Mississippi, 264.
Ir., on raised sea beaches in Ireland, 122.
ndstone formation, fossils of, 135. 193.
ndstone, reptile in, 135.
ssil remains, 22.
Arabian writer, 17.
ake, distance from Niagara, 216.
sils of the, 137.
ucture, recent, in Lancerote, &c. 439.
ang, change of, to man, 575.
M. A. de, on Pampean mud, 170.
emains, controversy as to real nature of,

dding of. *See* Fossilization.
rtance of the study of, 60.
pt transition from those of the secondary to
the tertiary rocks, 120.
also Fossils.
hilosophers, 10.
osmogony, 7.
lands, waste of, 301.
New, ground sinking, 268.
ks of trees in soil of delta, 268.
reccias, 735, 736. 741.
coral reefs of, 784. 786.
aried Indian city, 729.
has filled up an arm of the Sea, 744.
i, 10. 345.
of., on bones of turtles, 772.
he dog and wolf, 584.
ertiary mammalia, 142. 144.
ed, 184.
of mammoth, 78.
British fossil mammalia and birds, 137.
, 787.
&c., thrown ashore alive by storm, 773.
rations of, 652.

P.

cean, depth of, 104.
eight above the Atlantic, 294.
idence greater than elevation in, 787.
l and volcanic islands of, 354. 776. 780. 787.
rium of Isle of Wight, 142.
shaken by earthquakes, 355.
organic remains, 23.
mountains of Siberia, 45.
Caspian Sea, 45.
ssil bones of Siberia, 45. 78. 80.
, 333.
Mr., on shingle beaches, 318. 320.

Palms, rare in carboniferous group, 88.
Pampas, gradual rise of, 170.
Panama, tides in Bay of, 295.
Papandayang, eruption of, 493.
——, its cone truncated, 493.
Papyrus rolls in Herculaneum, 392.
Paradise, Burnet on seat of, 32.
Parana, R., animals drifted down on rafts by, 641.
——, animals drowned in, 696.
Paris basin, formations of the, 121.
——, fossils of the, 142.
Parish, Sir W., on inroads of sea during earthquakes, 499. 502.
——, on drifting of animals on floating rafts, 641.
——, on great droughts in S. America, 696.
——, on floods of Parana R., 751.
Parma, tertiary strata near, 74.
Paroxysmal energy of ancient causes controverted, 174.
Parrot, on Caspian sea, 157.
Parrots near Cape Horn, 97.
Parry, Captain, highest northern latitude reached by, 98.
——, on migration of polar bear, 639.
——, on animals of Melville Island, 640.
Patagonia, tides on coast of, 291.
Paviland cave, 737.
Peat in delta of Ganges, 280.
——, on preservation of fossils in, 711. 718. 722.
——, distribution of, 719.
——, bogs bursting of, 724.
——, submarine, 725.
Peat of Great Dismal Swamp, Virginia, 724.
Pembrokeshire, loss of land in, 324.
Penco destroyed by earthquake, 499.
——, elevation near, 500.
Pennant on waste of Yorkshire coast, 304.
——, on migration of animals, 77. 631. 637.
Pentagonal network of mountain chains, M. E. de Beaumont on, 170.
Penzance, loss of land near, 323.
Permian rocks, reptiles in, 136.
Péron on distribution of species, 646.
Perrey, M. Alexis, on frequency of earthquakes in winter, 561.
Persain Gulf, coral in, 776.
Peru, volcanos in, 347.
——, earthquakes in, 347. 501.
Peruvian tradition of a great flood, 8. 502.
Peterhead, whale stranded near, 771.
Phascolotherium Bucklandi, 139.
Philippi, Dr. A., on fossil tertiary shells of Sicily, 183.
Phillips, Mr. J., on waste of Yorkshire coast, 304.
Phlegræan fields, volcanos of, 372.
Physical Geography. *See* Geography.
Pietra Mala, inflammable gas of, 11.
Pigs, instincts of, 595.
—— swim to great distances, 635.
——, fossil, 722.
Pilla, M., on Monte Somma, 382.
Pindar cited, 398.
Pingel, Dr., on subsidence of Greenland, 580.
Pisolitic limestone of France, 120.
Pitch lake of Trinidad, 250.
Plants, carboniferous, wide geographical range, 160.
——, varieties in, produced by horticulture, 588.
——, extent of variation in, 589.
——, their geographical distribution, 97. 112. 613.
——, dispersion of, 618.
——, stations of, 614. 669.
——, equilibrium among, kept up by insects, 672.
——, number of terrestrial, 705.
——, imbedding of, in subaqueous deposits, 742. 765. 770.
——, on number which are now becoming fossil, 745.
——, mineralization of, 747.

es, fossil, in old red sandstone, 135.
n coal, 136.
, R., description of its course, 325.
s delta, 326.
aff made of siliceous cases of infusoria, 388.
ceros, fossil, food of, 80.
, delta of, in Mediterranean, 258.
elta of, in Lake of Geneva, 189. 252. 286.
eposits at its confluence with the Arve, 298.
cannon in calcareous rock in its delta, 759.
dson, Sir J., on rocks near Mackenzie River,

n sheep of Rocky Mountains, 597.
n distribution of animals, 640. 645.
n drift-timber, in Slave Lake, 744.
n arctic fauna. 634.
n diffusion of fish, 647.
n isothermal lines, 94.
dson, Mr. W., on Herne Bay, 312.
l, Dr., on sediment of Mississippi, 272.
M. de la, on terrestrial magnetism, 543.
ice, carrying power of, 219.
, difference in the sediment of, 189. 258,
inuosities of, 205.
ubmarine, in Thessaly, &c., 357.
hen confluent, do not occupy bed of propor-
lly larger surface, 207.
t, M., on geysers of Iceland, 246.
tson, Capt., on mud volcanos, 449.
ll bank, recent deposits on, 774.
, specific gravity of, 206.
lifference in texture of older and newer, 175.
ltered by subterranean gases, 243.
rigin of the primary, 176.
ersistency of mineral character in, 157.
lder, why most solid and disturbed, 162.
ction of frost on, 221. 231.
ransportation of, by ice, 155. 219.
rooved by glacial action, 155. 227. 229,
s, Prof., on Appalachain chain, 559.
n roads under water in Bay of Baiæ, 517.
ey Marsh, gained from sea, 316.
M. G., on hornblende and augite, 449.
Sir J., on cold of antarctic regions, 99.
btained soundings at depth of 27,600 feet, 104.
onfirms Cook as to antarctic ice, 125.
n icebergs, 98. 229.
erg, slide of the, 732.
on of the earth, currents caused by, 296.
f crops, 670. 720.
r, River, vessel found in its old bed, 316. 758.
, Mr., 81.
of Cutch described, 463.
rmerly destroyed by sea, 316.

S.

ruck, reptiles in coal strata at, 136.
, Capt., on well at Chiswick, 234.
n waters of Amazon discolouring the sea, 342.
, Col., on solar magnetic period, 129. 544.
a, island of, 432.
R., flood on, 209.
unpore, buried town near, 731.
drew's, loss of land at, 303.
un-barrel, fossil, near, 760.
mingo, hot springs caused by earthquake in

fossil human skeleton in, 758.
lena, tides at, 291.
go, earthquake at, 457.
therine's Docks, a fossil vessel found in, 758.
wrence, Gulf of, earthquakes in, 470.
rocks drifted by ice in the, 220.
aura, earthquakes in, 474.
chael, siliceous springs of, 246.

St. Michael's Mount, 323.
St. Paul, volcanic island, 446.
St. Vincent's, volcanos of, 466.
——, counter currents in the air proved by eruption in, 106.
——, boa constrictor conveyed on driftwood to, 646.
Salt, on its deposition in the Mediterranean, 334.
Salt springs, 18. 247.
Saltholm, island of, 520.
Samothracian deluge, 356.
Sand bars along western coast of Adriatic, 257.
——, drift, estuaries blocked up by, 307.
——, imbedding of towns, &c. in, 726.
——, cones of thrown up during earthquake, 483.
Sandown Bay, excavated by sea, 318.
Sandwich Islands volcanos, 354. 372. 383. 429. 548. 552.
Sandwich Land, perpetual snow to level of sea-beach in, 99.
San Fillippo, travertin of, 241.
San Lio, on Etna, fissures in plain of, 399.
Santa Maria, island of, raised 10 feet, 455.
Santorin, geological structure of, 445.
——, chart and section of, 442.
——, new islands in Gulf of, 441.
Saracens, learning of the, 17.
Saussure on the Alps and Jura, 45.
——, on glaciers in Alps, 223.
Savanna la Mar, swept away by sea, 731.
Saxicava rugosa, cosmopolite shell, 650.
Scandinavia called an island by the ancients, 520.
——, gradual rise of, 520. 563.
——. *See* Sweden.
Scania, gradual subsidence of, 530.
Scacchi, Sig., on temple of Serapis, 516.
——, on origin of Monte Nuovo, 371.
Scheuchzer, his theory, 1708, 33.
Schmerling, Dr., on fossils in caves, 737.
Schwabe, M., on spots in the sun, 129. 544.
Sciacca, island of. *See* Graham Island.
Scilla on organic remains, 1670, 24.
Scilla, rock of, 488.
Scoresby, Capt., on the gulf stream, 96.
——, on formation of field ice, 108.
——, on weight of rocks transported by icebergs, 227.
——, cited, 639. 743.
Scotland, floods in, 207. 750.
——, colder climate indicated by newest tertiary strata of, 126.
——, waste of islands and coast of, 298.
——, slight earthquakes felt in, 358.
——, peat-mosses of, 720. 723.
——, marl lakes of, 752. 766. 770.
Scrope, Mr. G. P., on eruption of Vesuvius in 1822, 375.
——, on columnar basalts of Vesuvius, 385.
——, on pisolitic globules at Pompeii, 387.
——, on eruptions of Etna, 408. 410.
——. on cause of convexity of plain of Malpais, 429.
——, on connection between state of atmosphere and earthquakes, 561.
Sea does not change its level, but land, 15.
——, its influence on climate, 97.
——, area covered by, 124.
——, its encroachment on coasts, 298. 302. 324.
——, its rise and retreat during earthquakes, 497.
Sea-beaches, raised, in Ireland, 122.
——, progressive motion of, 316.
Seals, migration of, 642.
Sea-weed, banks formed by drift, 622. 770.
Secondary rocks, fossils of the, 86.
——, origin of the, 117.
Sedgwick, Professor, on the Hartz mountains, 48.
——, on tertiary deposits of the Alps, 119.
——, on the antagonist power of vegetation, 711.
——, on organic remains in fissures, 740.
——, on diluvial waves, 423.

, buried city of, 393.
nite alternating with alluvium in caves, 737.
ariable splendour of, 128.
l figure of the earth, 534. 544.
s of plants, description of, 614.
animals, 677.
l on organic remains, 23.
opinions of, 23.
nson on eruption in Iceland, 425.
nson, Mr., R. on level of Red Sea and Mediterranean, 294.
son, Mr., on drift stones on Bell-rock, 302.
n the German Ocean, 315. 340.
n waste of cliffs, 324.
olm, rise of land near, 526, 527.
, Mr., on mineralization of plants, 747.
field, fossils of, 138. 145.
of November, 1824, effect of, 317, 318. 320.
cited, 14. 260. 355. 361,
eology of, 14.
y, Capt. R., on delta of Ganges, 283.
of Dover, formation of, 315.
heir depth, 315.
of Gibraltar, currents in, &c., 332. 335.
laws governing deposition of, 188.
ow deposition of, proved by fossils, 154.
n consolidation of, 175.
cations in deltas, causes of, 287.
débris deposited by currents, 288.
nconformable, inferences derived from, 187.
, hypothesis of, 14.
and, Mr., on tertiary strata, Cropthorn, 76.
n dodo, 684.
oli, its appearance during Calabrian earthes, 488.
onstancy in eruption, 546. 561.
jets of steam, in volcanic regions, 237. 546.
bury, Mr., on coral islands, 778. 782.
enine strata, 74.
arly Italian geologists on, 42. 70.
rine forests, 303. 323. 746.
eat, 724. 770.
ivers, 357.
olcanos, 431. 454.
ruptions in mid Atlantic, 436.
lence of land, 460. 465. 470. 477. 495. 503, 504. 691. 761, 762.
reat areas of, 170. 790.
reater than elevation, 563. 787.
imultaneous in Miocene epoch, 192.
f land, delta of Mississippi, 271.
f coral islands, slow and uniform, 791.
ranean movements, uniformity of, 186.
novements near New Madrid, 1811–12, 270.
, cliffs undermined, 309.
ertiary strata of, 142.
uric acid, lake of, in Java, 353.
ureous springs, 245.
a, volcanos in, 354.
nimals destroyed by river floods in, 751.
wa, subsidence in island of, 1815, 464. 762.
shes, transported to great distances by erups of, 106.
ariations in spots of, 129.
Isles of, volcanic region of, 350.
rbunds, part of delta of Ganges, 276.
country," west of New Madrid in U. S., 467.
ior, Lake, deltas of, 253.
recent deposits in, 254. 768.
ts depth, extent, &c., 254.
ursting of, would cause a flood, 156.
, waste of its coast, 317.
, R., fossils near, 6.
ge Bay, excavated by sea, 318.
, gradual rise of, 520. 563.
gradual subsidence of south of, 530.
earthquakes in, 531.

Sweden, land rising, 192.
——. *See* also Scandinavia.
Switzerland, towns destroyed by landslips in, 732.
Syria, earthquakes in, 355. 452.

T.

Tacitus cited, 364.
Tagliamento, R., delta of the, 257.
Targioni, on geology of Tuscany, 40.
Tartary, volcanos in, 355.
Taxodium distichum in Great Dismal Swamp, 725.
Tay, estuary of, encroachment of sea in, 302.
——, submarine forests in, 303.
Taylor, Mr. R. C., on waste of cliffs, 306.
——, on gain of land on coast of Norfolk, 308.
——, on caves in isle of Cuba, 741.
Tchihatchoff, M., map of Italy, 123.
Teissier, M., on human bones in caves, &c., 739.
Temperature, great changes in, 92.
——, difference of, in places in same latitudes, 95
——, warmer in tertiary periods, 75.
——, oscillation of, 125.
——. *See* Climate.
Temples, buried, in Egypt, 726.
—— under water in Bay of Baiæ, 518.
—— buried in Cashmere, 762.
Teneriffe, volcanic eruptions in, 439.
Terra del Fuego, fauna of, 141.
Terranuova, subsidence near, 470.
——, fault in the tower of, 478.
——, landslips near, 485.
Tertiary formations, general remarks on, 141. 182, 183.
——, geographical changes implied by, 118.
——, glacial in Scotland, 126.
——, origin of successive periods, 182.
——, circumstances under which these and the secondary formations may have originated, 117, 118.
——, fossils of the newest, 183.
——, fossil mammals of successive, 142.
—— formations of England, 76. 142.
——. of the Paris basin, 142.
——, deposits, climate of warmer, 86.
Testacea, their geographical distribution, 648.
——, fossil, importance of, 183.
——, marine, imbedding of, 768.
——, freshwater, 770.
——, burrowing, 773.
——, longevity of species of, 76.
——, number of recent, in different tertiary periods, 142. 183.
Texel, waste of islands near the, 328.
Thames, valley of, tertiary strata in, 76.
——, gain and loss of land in its estuary, 312.
——, tide in its estuary, 338.
——, buried vessels in alluvial plain of the, 758.
Thanet, Isle of, loss of land in, 313.
Thermo-electricity, 543.
Thibet, yak or wild ox of, in ice, 85.
Thomson, Dr. T., on Western Himalaya and Thibet, 764.
——, on buried temples in Cashmere, 763.
Thrace subject to earthquakes, 355.
Thury, M. Hericart de, on artesian wells, 234. 236.
Thylacotherium Prevostii, 138.
Tiber, growth of its delta, 243.
Tide wave of the Atlantic, 308.
Tides, height to which they rise, 279. 290.
——, effect of winds on the, 295.
——, effects of, on wells near London, 233.
——, their destroying and transporting power, 291.
——, their reproductive effects, 337.
—— and currents, drifting remains of animals by 753.

Tiedemann on changes in brain of fœtus, 609.
Tiger of Bengal found in Siberia, 77.
Tigris and Euphrates, their union a modern event, 284.
Tigris, river, delta of, advancing, 284.
Tilesius on Siberian mammoth, 81.
Time, prepossessions in regard to the duration of past, 62.
Tivoli, flood at, 211.
——, travertin of, 244.
Tomboro, volcano, eruption of, 465.
——, town of, submerged, 465.
Torre del Greco overflowed by lava, 394.
——, columnar lavas of, 384.
Torrents, action of, in widening valleys, 204.
Torres' Strait, volcano of, 792.
Totten, Col., on expansion of rocks by heat, 562.
Tournal, M., on French caves, 738, 739.
Towns destroyed by landslips, 732.
Trade winds, 106. 295.
Traditions of losses of land, 324. 327.
——, of floods, 500, 501.
Transition texture, 176.
——, formations, 177.
Trap rocks of many different ages, 160.
Travertin of the Elsa, 239.
—— of San Vignone, 240.
—— of San Filippo, 241.
——, spheroidal structure of, 242.
——, compared to English magnesian limestone, 243.
——, of Tivoli, 244.
Travertin oolitic, recent in Lancerote, 439.
Tree-ferns, distribution of, 88.
——, extend more south than north of equator, 86.
Trees, longevity of, 422.
Trias, fossil mammifer of, 157.
Trimmer, Mr., on recent marine shells in Wales, 122.
Trinidad, subsidence in, 250.
——, pitch lake of, 250.
Tripergola, 370, 371. 395.
Tripolitza, plain of, breccias in, 734.
Trollhattan, 527.
Truncation of volcanic cones, 352. 493.
Tufa. *See* Travertin.
Tuff, infusorial, 388.
Turner, Dr., on decomposition of felspar, 247.
Turtles, migrations of, 645.
——, eggs of, fossil, 771.
Turton cited, 645.
Tuscany, geology of, 23. 40.
——, calcareous springs of, 239.
Tyrol, Dolomieu on the, 49.

U.

Uddevalla, upraised deposits at, 184. 527.
Ullah Bund, formation of the, 461.
Ulloa cited, 501, 502. 686.
Unconformable strata, inferences derived from, 187.
Uniformity of laws of nature, 71. 149. 373.
——, of system of past changes in animate and inanimate world, 181.
Universal formations, theory of, 49. 154.
Universal ocean, theory of, 26. 34.
—— disproved by organic remains, 191.
Upsala, strata near, 528.

V.

Val d'Arno, Upper, effect of destruction of forests in 712.
Val del Bove on Etna described, 403.
——, form, composition, and origin of dikes in, 406.
——, lavas and breccias of the, 411.
Val del Bove, origin of the, 412.
——, floods in, 411.
Val di Calanna, 405. 407. 410.
Val di Noto, Dolomieu on the, 49.
Valdivia, earthquake at, 453.
Valenciennes, M., , on fish not crossing the
647.
Valley, newly formed in Georgia, U. S., 203.
Valleys, Targioni on origin of, 40.
——, excavation of, in Central France, 213.
—— of elevation, section of, 420.
—— on Etna, account of, 404.
——, the excavation of, assisted by earthquak
Vallisneri on the origin of springs, 23.
——, on marine deposits of Italy, 34.
—— cited, 34, 35. 52.
Valparaiso, changes caused by earthquakes
517. 761.
Van Dieman's Land, climate of, 97.
Vedas, sacred hymns of, 4.
Vegetable soil, why it does not increase, 709.
——, how formed, 710.
Vegetation, luxuriant, not required to support
animals, 82.
——, centres of, 703.
——, its conservative influence, 710. 712.
——, its influence on climate, 715.
Veins, mineral, on their formation, 494.
—— of lava. *See* Dikes.
Verneuil, M. de, on lowland of Siberia, 84.
Verona, fossils of, 20. 22. 34.
——, Arduino on mountains of, 41.
Verstegan, on separation of England from Fr
315. 642.
Vertebrated animals in oldest strata, 135.
Vessels, fossil. *See* Ships.
Vesta, temple of, 212.
Vesuvius, excavation of tuff on, 213.
——, history of, 363. 374.
——, eruptions of, 363. 374.
——, dikes of, 379.
——, lava of, 384.
——, structure and origin of the cone of, 385.
—— and Somma, probable section of, 386.
——, volcanic alluvium on, 728.
Vicentin, Dolomieu on the, 49.
——, submarine lavas of the, 71.
Victoria land skirted by ice, 99.
Vidal, Capt., on Rockall bank, 774.
Villages buried by landslips, 732.
Virlet, M., on Samothracian deluge, 296.
——, on volcanos of Greece, 355.
——, on Santorin, 443. 445, 446.
——, on corrosion of rocks by gases, 733.
—— on human bones imbedded in Morea, 730.
Vivarais, basalts of the, 48.
Volcanic action, defined, 345.
—— power adequate to effect lateral pressure.
—— lines, 169. 352.
—— craters in Galapagos with southern side lo
783.
——, action, uniformity of, 162. 711.
—— cones, truncation of, 352. 493.
——, their perfect state no proof of relative age
—— conglomerates, 438.
—— dikes. *See* Dikes.
—— eruptions, causes of, 542.
——, average number of, per annum, 430.
—— formations, fossils in, 379. 728.
—— products, mineral composition of, 443.
—— regions, their geographical boundaries, 34
—— map showing extent of, 351.
—— rocks, subterranean, 178. 450.
—— of all geological periods, 160.
Volcanos, safety valves according to Strabo, 15
——, remarks on their position, 345. 355.
—— and earthquakes, effects of same causes, 34

Volcanos, agency of water in, 545.
——, mode of computing the age of, 420.
——, sometimes inactive for centuries, 346. 421.
—— of Sandwich Islands, 354. 372. 548. 383. 429.
——, chemical theory of, 546.
——, mud, 447.
——, " no safety valves," Dana on, 553.
Voltaire on systems of geology, 54.
Volterra, Mattani, on fossils of, 34.
Von Baer, Prof., on frozen soil of Siberia, 84.
—— on ice-drifted rocks, 231.
Von Buch on rise of land in Sweden, 523. 526.
—— on volcanic lines, 352.
—— on volcanos of Greece, 355.
—— on formation of Monte Nuovo, 369.
—— on Vesuvius and Somma, 367. 380. 382, 383.
—— on eruption in Lancerote, 436.
—— on glaciers, 228.
—— on new islands, 468.
—— on volcanic regions, 346.
Von Hoff. *See* Hoff.
Vulcanists and Neptunists, factions of, 50. 55.
Vultur, Mount, 356.
Vultures, range of, 643.

W.

Wallerius, theory of, 45.
Wallich, Dr., on Ava fossils, 28.
——, on wood in peat near Calcutta, 280.
Warping, land gained by, 288. 339.
Water, action of running, 204.
——, its power on freezing, 204.
——, excavating power of, 204.
——, transporting power of, 204.
——, sorting power of, 286.
——, agency of, in volcanos, 548.
Waterhouse, Mr., of British Museum, on provinces of indigenous land quadrupeds, 631.
Wealden strata, fossils of, 117. 137. 140.
Webster, Dr., of Nova Scotia, on rain-prints, 202.
Wells, artesian, 233.
Wener, Lake, strata near, 527.
Werner, Professor of Mineralogy at Freyberg, 1775, 46.
——, his lecture, 47.
——, on granite of the Hartz, 47.
——, principal merit of his system, 48.
——, technical terms of, 58.
——, on transition rocks, 176.
West Indian land quadrupeds, 634.
West Indies, earthquakes in, 29. 350. 505.
——, active volcanos in, 350.
Whales stranded, 771.
Whewell, Rev. Dr., on modern progress of geology, 59.
——, on the tides, 332.
Whirlwinds, violent, during eruption in Sumbawa, 465.
Whirlwind, dispersion of seeds by, 619.
Whiston, his theory of the earth, 32.
White Mountains, landslips in the, 209.
Whitehurst, theory of, 1778, 45.
——, on subsidence at Lisbon, 495.
Wildenow on diffusion of plants by man, 626.
——, on centres of vegetable creation, 703.
Wilkinson, Sir J. G., on deposits of Nile, 262.
——, on sand drift in Egypt, 726.
Wilson, Prof., on cosmogony of Vedas, 4.
Winds, trade, 106. 295.
——, currents caused by the, 293.
——, sand drifted by the, 307. 726.
Wolf, and dog, distinct species, 585.
——, hybrids between the, 601.
——, drifted to sea on ice, 640.
—— extirpated in Great Britain, 683.
Wollaston, Dr., on water of Mediterranean, 334.
Wood, Mr. S., on fossil quadrumana, 144.
Wood impregnated with salt water when sunk to great depths, 743.
——, drift, 90. 268. 640. 743.
—— converted into lignite, 759.
Woodward, theory of, 31. 34. 54. 65.
Wrecks, number of, annually, 754, 755.

X.

Xanthus, the Lydian, his theory, 14.

Y.

Yak, wild ox of Thibet, frozen in ice, 85.
Yakutzt, frozen soil of, 84.
Yaou, flood of, 7.
Yarmouth, estuary silted up at, 307.
——, rise of the tide at, 291. 307.
Yenesei, R., fossils on banks of, 79.
Yorkshire, bones of mammoth in, 76.
——, waste of its coasts, 303.
Young, Dr., on effects of compression at earth's centre, 536.

Z.

Zante, earthquakes in island of, 474.
Zealand, New, number of ferns, 116.
——, resemblance of plants with ancient carboniferous flora, 116.
——, length and breadth of, 116.
Zeuglodon, eocene cetacea, 145.
Zoological provinces how formed, 666.
——, why not more blended together, 668.
Zoophytes, their geographical distribution, 653.
——, their powers of diffusion, 654.
——, abundance of, 706.
——, which form coral reefs, 776.
Zuyder Zee, formation, 328.
——, great mosses on the site of, 327.

THE END.

3 2044 011 908 696

The borrower must return this item on or before the last date stamped below. If another user places a recall for this item, the borrower will be notified of the need for an earlier return.

*Non-receipt of overdue notices does **not** exempt the borrower from overdue fines.*

Harvard College Widener Library
Cambridge, MA 02138 617-495-2413

WIDENER
FEB 1 0 2003
BOOK DUE

WIDENER
SEP 1 0 2005
CANCELLED

Please handle with care.
Thank you for helping to preserve
library collections at Harvard.